


PROJECT CONTROLS INSTITUTE GLOBAL

PFL-AI

Body of Knowledge

The reference for the PCI AI Project Finance Leader

Structuring · modelling · coverage · the governed use of AI



AI proposes; the professional verifies,
decides and remains accountable.

FIRST EDITION — DRAFT

For editorial and technical review · not for release or distribution

Finance intelligently. Control predictively. Deliver successfully.

PFL-AI Body of Knowledge

The reference for the PCI AI Project Finance Leader
Project economics · structuring · financial mathematics · the
governed use of AI

FIRST EDITION — DRAFT FOR EDITORIAL AND TECHNICAL REVIEW
NOT FOR RELEASE OR DISTRIBUTION
PROJECT CONTROLS INSTITUTE GLOBAL
Finance intelligently. Control predictively. Deliver successfully.
AI proposes; the professional verifies, decides and remains accountable.

— Status of this draft

This is a **complete first draft** of all 16 domains of this volume, produced under the Institute's phased authoring programme. It is **not a released PCI publication**: it carries no entitlement, syllabus or examination status, and the released edition will carry the full copyright, disclaimer and notices of the PCI book family.

What has been verified. Every number printed in this volume as a result — in worked examples, in-text calculations, multiple-choice options, exercise solutions and case studies — is recomputed independently with decimal arithmetic by the Institute's golden-answer verification suite, which must pass in full before any domain passes gate. All figures are PCI-original artwork generated from source specifications maintained by the Institute. No text, table, diagram, question or distinctive structure from any other publisher or certification body is reproduced; public standards are discussed and cited by name without reproducing their content. All organisations, projects and cases are fictitious.

What has not. This draft was **AI-drafted and requires human editorial and technical review before release**. It is not attributed to any named author or expert, and no claim of human authorship is made for it. Nothing in it should be presented as reviewed until that review is recorded. Where a professional judgement is stated rather than a measured effect, the text says so; readers should treat any unqualified generalisation as a drafting defect and report it.

Legal and jurisdictional note. Nothing here is legal, tax, accounting or investment advice. Treatments differ by jurisdiction and by reporting framework; specific matters must be referred to qualified professional advisers in the relevant jurisdiction.

— How to use this book

This is a reference, not a course. It is written to be read in order once and consulted out of order thereafter, and the apparatus below exists to make the second use as easy as the first.

How anything is addressed. Content is numbered Domain.KnowledgeArea.Topic — so 7.3.2 is the second topic of the third Knowledge Area of Domain 7, and a cross-reference of the form KA 10.2 is precise. Page numbers are never used for cross-references, because this volume is regenerated from source and its pagination is not stable across editions. Every reference in the text is therefore still valid in the next one.

The worked examples are the spine of the book. Each follows the same five steps — Setup, Formula, Substitution, Result, Interpretation — and the Interpretation is deliberately the longest and the most valuable. It is where the number is turned into a decision: what breaks the result, what the breakeven is, which assumption the conclusion is most sensitive to, and what a reviewer should check. If you read only one part of a worked example, read that one. The four steps before it exist so that you can reproduce the number and disagree with it.

Every number can be checked, and should be. Every figure printed as a result anywhere in this volume — in worked examples, in the text, in multiple-choice options, in exercise solutions, in case studies — is recomputed independently with decimal arithmetic by a verification suite that must pass in full before any chapter is accepted. Appendix C records how many checks stand behind each domain. If you find a number that does not reproduce from its stated method and inputs, that is a defect in this book and worth reporting.

The AI in this KA sections are not an appendix to the subject. Each states three things: where AI genuinely earns its place in that Knowledge Area, where it must not go, and how to verify its output concretely. They exist because the alternative — a single chapter about AI at the back — teaches that the question is separable from the work, and it is not. One principle governs all of them: AI proposes; the professional verifies, decides and remains accountable.

What the sections at the end of each domain are for. Advanced topics extend the domain past the level a candidate is assessed on, and each closes with a list of invariants a reviewer can test. Industry variations say what changes by sector, and are written so that a reader in one sector can see what a reader in another is dealing with. Case studies carry real arithmetic and are the place where several Knowledge Areas have to work together. Executive perspective is what a director cannot delegate. Calculation exercises each carry a full solution and a Common error note, and the common error is frequently the more useful half. The Practitioner's toolkit items are meant to be adopted and then left stable; adapt the headings to your organisation and stop changing them. Exam preparation lists what is assessed, the calculations to be able to do under time pressure, and the traps — each cross-referenced to where it is taught.

Two conventions worth knowing before you meet them. Where a result is established in one domain, the others cite it rather than re-derive it; if two domains appear to derive the same thing independently, that is a defect. And where one word carries two genuinely different concepts, the later use states the collision explicitly rather than leaving you to infer it. Appendix B lists both.

If you are studying for the examination, work the calculation exercises before reading their solutions, and treat the Common error notes as the syllabus they effectively are. If you are using this at work, start from the Practitioner's toolkit of the domain you need and follow its cross-references back into the treatment.

Contents

Domain 1 — Foundations of Project Finance Leadership	9
Knowledge Area 1.1 The project finance leader and the financing landscape	10
Knowledge Area 1.2 Value, cash and risk: the discipline's logic	19
Knowledge Area 1.3 Ethics, fiduciary awareness and responsible AI	30
Domain 2 — Accounting and Financial-Statement Foundations	47
Knowledge Area 2.1 The accrual model	48
Knowledge Area 2.2 The three statements and their articulation	53
Knowledge Area 2.3 Project-relevant treatments	63
Knowledge Area 2.4 Ratio interpretation and project interfaces	73
Domain 3 — Time Value of Money and Financial Mathematics	94
Knowledge Area 3.1 Interest and value	95
Knowledge Area 3.2 Annuities and loan schedules	104
Knowledge Area 3.3 Real-world adjustments: inflation, escalation and currency	122
Domain 4 — Investment Appraisal and Capital Budgeting	152
Knowledge Area 4.1 The discounted measures: NPV, IRR and MIRR	152
Knowledge Area 4.2 The complementary measures	162
Knowledge Area 4.3 Decision contexts: exclusivity, rationing and judgment	169
Domain 5 — Project Development and Bankability	191
Knowledge Area 5.1 Concept and feasibility	192
Knowledge Area 5.2 Sponsors and special-purpose vehicles	198
Knowledge Area 5.3 The bankability test	204
Knowledge Area 5.4 Construction and operational readiness	211
Domain 6 — Financial Modelling and Model Governance	227
Knowledge Area 6.1 Model architecture	228
Knowledge Area 6.2 Construction and operating models	233
Knowledge Area 6.3 Debt schedules, the cash waterfall and returns	241
Knowledge Area 6.4 Checks, sensitivity, model audit and AI controls	247
Domain 7 — Revenue, Demand and Commercial Models	266
Knowledge Area 7.1 Contracted and merchant revenue, tariffs and availability payments	267
Knowledge Area 7.2 Demand models, concessions and service revenue	274
Knowledge Area 7.3 Price escalation and volume risk	280
Knowledge Area 7.4 Counterparty credit quality and revenue stress testing	287
Domain 8 — Cost, Schedule and Contingency Integration	303
Knowledge Area 8.1 Development, capital, operating and lifecycle cost; estimate classes	304
Knowledge Area 8.2 Schedule-driven cash flow and escalation	311
Knowledge Area 8.3 Contingency and management reserve	318
Knowledge Area 8.4 Delay impact, cost-to-complete, and the interface with project controls	326

Domain 9 — Funding Structure and Sources of Capital	343
Knowledge Area 9.1 Equity and shareholder instruments	344
Knowledge Area 9.2 Senior, subordinated and mezzanine debt; bonds	353
Knowledge Area 9.3 Islamic finance concepts, export credit and development finance	360
Knowledge Area 9.4 Government support, grants, sustainable finance and refinancing	368
Domain 10 — Debt Sizing, Covenants and Credit Metrics	386
Knowledge Area 10.1 Debt capacity and sizing	387
Knowledge Area 10.2 The coverage ratios	397
Knowledge Area 10.3 Reserve accounts and the debt-service schedule	406
Knowledge Area 10.4 Covenants, default and cure	415
Domain 11 — Risk Identification and Allocation	433
Knowledge Area 11.1 Construction and completion risk	434
Knowledge Area 11.2 Market risks and operations	441
Knowledge Area 11.3 Counterparty, political, currency, interest-rate and force-majeure risk	448
Knowledge Area 11.4 Environmental and social, technology, cybersecurity and AI model risk	457
Domain 12 — Contracts and Transaction Structure	473
Knowledge Area 12.1 EPC and O&M	474
Knowledge Area 12.2 Offtake, concession, supply and interface agreements	483
Knowledge Area 12.3 Guarantees, direct agreements and the security package	490
Knowledge Area 12.4 Risk allocation, claims and change	496
Domain 13 — Due Diligence and Financial Close	514
Knowledge Area 13.1 The diligence streams	515
Knowledge Area 13.2 Model audit	523
Knowledge Area 13.3 Conditions precedent and documentation	529
Knowledge Area 13.4 Syndication and financial close	539
Domain 14 — Construction Monitoring and Drawdown	558
Knowledge Area 14.1 Sources and uses, draw requests and conditions	559
Knowledge Area 14.2 Cost-to-complete and contingency draw	568
Knowledge Area 14.3 Progress certification and change control	576
Knowledge Area 14.4 Schedule delay, lender reporting and completion tests	584
Domain 15 — Operations, Performance and Restructuring	603
Knowledge Area 15.1 Operational monitoring, financial reporting and covenant testing	604
Knowledge Area 15.2 The cash waterfall in operation, reserves and distributions	612
Knowledge Area 15.3 Refinancing, waivers and amendments	619
Knowledge Area 15.4 Distress, restructuring, exit and handback	627
Domain 16 — Data, Automation and Responsible AI in Finance	645
Knowledge Area 16.1 Financial-data architecture, forecast automation and anomaly detection	646
Knowledge Area 16.2 Scenario generation, document review and model assistance	658
Knowledge Area 16.3 Explainability, validation, bias and model risk	665
Knowledge Area 16.4 Privacy, cybersecurity, human approval and AI governance	674
Appendix A — Formula and symbol sheet	692

Appendix B — Notation, terminology and conventions	695
Appendix C — Verification record	697
Appendix D — Figure index	698
Appendix E — Practitioner's toolkit library	701
Appendix F — Standards and frameworks referenced	705
Appendix G — Integrated capstones	707
Capstone One — Kestrel Water: the master thread, assembled	708
Capstone Two — Aurora Ridge: the road that cannot be geared	713
Capstone Three — Helios Flats: the ratio that is not what it says	716
Capstone Four — Harbournate Point: lending past the lease	719
The eight capstones, and what they establish together	722
PCI Professional Laws	723
PCI Foundational Laws	724
How to read these laws	724
Part I — Accountability and the governed use of AI	724
Part II — Evidence, information and honest reporting	730
Part III — Professional conduct	734
Index of Foundational Laws	743
PFL-AI Professional Laws — PCI AI Project Finance Leader	744
How to read these laws	744
Domain 1 — Foundations of project finance leadership	745
Domain 4 — Investment appraisal and capital budgeting	748
Domain 5 — Project development and bankability	749
Domain 6 — Financial modelling	750
Domain 7 — Revenue, demand and commercial models	757
Domain 9 — Funding structure and sources of capital	758
Domain 10 — Debt sizing, covenants and credit metrics	760
Domain 11 — Risk identification and allocation	763
Domain 12 — Contracts and transaction structure	764
Domain 13 — Due diligence and financial close	766
Domain 14 — Construction monitoring and drawdown	770
Domain 15 — Operations, performance and restructuring	773
Domain 16 — Data, automation and responsible AI in finance	774
Index of PFL-AI Professional Laws	779
Glossary	782
Index	797

01

PART ONE

Foundations

Domains 1–4 — the profession, accounting foundations, financial mathematics and investment appraisal: the financial grammar of project finance leadership.



01

DOMAIN 1

Foundations of Project Finance Leadership

— Why this domain exists

Project finance is a distinctive answer to a distinctive problem: how to fund a large, long-lived, single-purpose asset whose only security is itself — its contracts and the cash they will produce. This domain establishes what makes that answer work, and what the leader at the centre of it actually does. It maps the role across the project lifecycle (KA 1.1), builds the discipline's three-cornered logic — value, cash and risk (KA 1.2) — and grounds the profession's obligations: fiduciary awareness, independence, and the governed use of AI (KA 1.3). Everything later in the book is a specialisation of this domain: the mathematics (Domains 3–4), the structures (Domains 5, 9, 12), the lender's machinery (Domains 10, 13–15) and the AI curriculum (Domain 16) all stand on the concepts fixed here. A reader who finishes only this domain should already reason like the profession: follow the cash, price the risk, know who bears it, and stay accountable.

Learning objectives. After this domain a candidate can: describe the project finance leader's role at each lifecycle stage; place a financing on the recourse spectrum and explain what limited recourse buys and costs; **price** the recourse decision — computing the incremental cost of the limited-recourse route and the breakeven probability of a parent-impairing failure at which it repays that cost — and explain why the breakeven falls with facility size and why it is nonetheless the wrong sole test; explain the SPV's purpose, the interests of each party around it, and the five ways a ring-fence leaks; describe the infrastructure-finance market's asset classes and investors, and compute the Macaulay duration of a project's cash stream to distinguish matching an asset's life from matching its duration; explain why cash, not profit, is the binding constraint, demonstrate the difference, and translate covenant headroom into days of receivables; derive the levered-return identity, locate the crossover at which leverage stops helping, and show how far the equity cliff moves when the same debt amortises rather than paying interest only; price a retained risk through the capital structure the lenders will impose; price sponsor support as a contingent claim; state the risk-return-bankability logic; and apply the profession's ethical and responsible-AI obligations to realistic situations — including in explicit expected-value terms, while explaining why the duty does not depend on the arithmetic.

The master thread. Kestrel Water SPC — whose loan, availability stream and investment case Domains 3 and 4 priced — began here: a sponsor group weighing how to finance a desalination plant at all. The figures this domain works with are the ones the rest of the book inherits: capital cost **USD 60,000,000**, funded 70/30 as **USD 42,000,000** of senior debt at **6.0 % over 12 years** — annual instalment **USD 5,009,635.23**, of which year-one interest is **2,520,000** and principal **2,489,635** (Domain 3) — plus **USD 18,000,000** of sponsor equity; a 25-year asset life; first-year documented **CFADS** of **USD 6,384,000** on revenue of **12,000,000** (Domain 2), giving **DSCR 1.2743** (Domain 10); and an appraisal at 8.0 % of **NPV +16,179,360** on a 15-year operating stream of 8,900,000 (Domain

4). This domain tells the part of the story that precedes all of it — the choice of financing route — and Domain 5 takes the project through development to bankability.

KNOWLEDGE AREA 1.1

The project finance leader and the financing landscape

Topics: 1.1.1 the role across the lifecycle · 1.1.2 corporate versus project finance — the recourse spectrum · 1.1.3 the SPV and its stakeholders · 1.1.4 the infrastructure-finance market.

1.1.1 The role across the lifecycle

The project finance leader is the person accountable for a project's **financial integrity end to end** — not the deal-closer alone, and not the accountant alone. The role changes costume by stage while keeping one spine:

Stage	What the finance leader owns
Development	Screening economics (Domain 4); funding development spend at risk; shaping a financeable concept (Domain 5)
Structuring	Capital structure and funding sources (Domain 9); risk allocation into contracts (Domains 11-12)
Execution (financial close)	Due diligence, model audit, documentation, conditions precedent (Domain 13)
Construction	Drawdowns, cost-to-complete, lender reporting (Domain 14)
Operations	Covenant compliance, waterfall management, distributions, refinancing (Domain 15)
Maturity/exit	Handback, sale, restructuring where needed (Domain 15)

The spine is a single question asked at every stage: **will the cash arrive, and who is exposed if it does not?** The leader's authority rests on being the person in the room who can answer it with evidence.

1.1.2 Corporate versus project finance — the recourse spectrum

Definitions. In **corporate (balance-sheet) finance**, lenders lend to a company and are repaid from its whole cash flow; every asset stands behind every debt. In **project finance**, lenders lend to a ring-fenced project and are repaid **only from that project's cash flows**, with security over its assets and contracts — **non-recourse** to the sponsors, or **limited recourse** where sponsors give bounded support (a completion guarantee, a cost-overflow facility). Real deals sit on a spectrum between the poles.

What limited recourse buys sponsors: risk containment (a failed project cannot sink the parent), balance-sheet capacity, the ability to share a mega-project among partners, and discipline — lenders' due diligence becomes a second pair of eyes on every assumption. What it costs: higher margins and fees (lenders carry risk they cannot chase a parent for), heavy transaction and diligence costs, long documentation timelines, and covenant control over the project's cash (Domain 10). The break-even is scale and risk-shape: single-asset, contract-backed, capital-intensive projects with long lives are where the machinery pays.

Fig 1.1.1 — The recourse spectrum

Pricing the choice. "Scale and risk-shape" is the right answer and an unusable one until it is arithmetic. The limited-recourse route costs more in two distinguishable ways — a **margin and fee differential** that scales with the facility, and a **close-cost premium** that is largely fixed — and it buys one thing that can be valued: the parent's exposure to a failure it did not cause and cannot survive. Setting the cost against the exposure gives a breakeven probability, and the shape of that breakeven against deal size is the whole of the scale argument.

Incremental cost of the limited-recourse route

$$= \text{PV}(\text{project-finance debt service} - \text{corporate debt service}) + (\text{close costs}_{\text{PF}} - \text{close costs}_{\text{corporate}})$$

Breakeven failure probability $p^* = \text{incremental cost} \div \text{exposure the ring-fence removes}$

WORKED EXAMPLE

Worked example 1.1.2 — Kestrel's recourse decision, priced.

- Setup.** Kestrel needs **USD 42,000,000** of debt inside a **60,000,000** envelope. Two routes. Project route: the SPV borrows at **6.0 % over 12 years** (the master facility) and the close-cost budget is Domain 13's itemised **USD 2,709,000** (KA 13.3.4). Corporate route: the international water operator borrows the same amount on its own balance sheet at **4.60 %** over the same 12 years — 140 basis points tighter, because the lender is looking at an established credit rather than at a plant that does not yet exist — with close costs of **350,000** (arrangement and legal only — none of the seven diligence streams, no model audit, no security perfection across a contract set). The downside being insured against is a post-completion performance failure in operating year three, at which point the sponsors' completion support has already fallen away: the offtake terminates and enforcement realises the single-purpose asset at **40 % of capital cost — USD 24,000,000**. Cash costs are compared at the appraisal rate of **8.0 %** (Domain 4).
- Formula.** As above. $AF(0.046, 12)$ and $AF(0.06, 12)$ size the two instalments; $AF(0.08, 12)$ prices the annual differential; the exposure is the loan's year-three closing balance less the enforcement recovery.
- Substitution.** $AF(0.06, 12) = 8.383844 \rightarrow 42,000,000/8.383844 = 5,009,635.23$. $AF(0.046, 12) = 9.066641 \rightarrow 42,000,000/9.066641 = 4,632,366.30$. Differential 377,268.94 a year; $AF(0.08, 12) = 7.536078 \rightarrow \text{PV } 2,843,128.16$. Close-cost premium $2,709,000 - 350,000 = 2,359,000$. Year-three closing balance from Domain 3's schedule: 34,073,997.27; exposure $34,073,997.27 - 24,000,000$.
- Result.**

	Project route	Corporate route	Differential
Annual debt service	5,009,635.23	4,632,366.30	377,268.94
PV of debt service at 8 %	37,753,001.96	34,909,873.80	2,843,128.16
Close costs at financial close	2,709,000	350,000	2,359,000
Incremental cost of limited recourse			USD 5,202,128.16
Exposure removed (year-three balance 34,073,997.27 less 24,000,000 recovery)			USD 10,073,997.27
Breakeven failure probability p^*			51.6392 %

The incremental cost is **12.3860 %** of the debt raised, of which the fixed close-cost premium is **45.3468 %**. 5. **Interpretation.** Read the headline first and then refuse to stop there. **On expected value alone, the limited-recourse route does not pay:** it requires the sponsors to believe there is better than a **one-in-two** chance of a failure severe enough to leave 10,073,997 of debt unrecovered, and no board that has just approved a 60,000,000 plant believes anything of the kind. That is not an argument against project finance; it is the discovery that **project finance is not bought with expected-value arithmetic**. Three reasons the 51.64 % is the wrong sole test. First, it prices a mean and the sponsor is insuring a tail. The loss that matters is not the 10,073,997 itself but its correlation with everything else — a failed project consolidates onto the parent's balance sheet in the same quarter that its own lenders are re-testing covenants and its own rating is under review, so the realised cost of the corporate route in the bad state is far above the enforcement shortfall. Expected value averages exactly that asymmetry away; Domain 13 (KA 13.1.3) makes the same caution about the right tail of a diligence loss. Second, it prices only one of the three things the structure buys. The regional infrastructure fund cannot guarantee anything beyond its equity, so without the ring-fence there is no partnership at all and the operator funds 18,000,000 of equity it does not have; that option has a value the table does not contain. Third, the corporate route's 4.60 % is not a fact but a facility — it consumes the operator's own borrowing capacity, and the next project priced at the margin is the one that pays for it. Now the **scale** result, which the breakeven does capture cleanly and which Fig 1.1.3 plots in full. Because the close-cost premium is essentially fixed while the exposure scales with the facility, p^* falls hyperbolically with size: **93.7893 % at 15,000,000** of debt, **51.6392 %** at Kestrel's 42,000,000, **34.7791 % at 150,000,000**, approaching **28.2224 %** — the margin differential alone — as the fixed premium becomes immaterial. Below about **USD 13,702,087** of debt, p^* exceeds 100 %: the route cannot pay at any failure probability, because the close-cost premium alone exceeds the whole exposure it removes. That is the same reading Domain 13 gives an impossible breakeven detection rate (KA 13.1.3) — an impossible configuration, not a worthless idea — and it is the arithmetic reason the machinery is not reached for on small facilities, whatever their risk shape. Two cautions for the reviewer. The 140 basis points and the 40 % recovery are the two parameters that move the answer most and both are estimates: raise the enforcement recovery from 40 % to **50 %** of capital cost and the exposure collapses to **4,073,997.27** while p^* rises to **127.6910 %** — impossible — so a route decision resting on this number alone is resting on the recovery assumption. And the fixed premium is only approximately fixed — diligence scope does grow with project complexity — which flattens the curve without changing its direction.

1.1.3 The SPV and its stakeholders

Definition. The **special-purpose vehicle (SPV)** is a company created to do exactly one thing — own, build, finance and operate the project — and legally incapable of doing anything else. Ring-

fencing is what makes non-recourse lending possible: the SPV's contracts are its assets, and every major relationship is written down (Domain 12 builds the contract matrix in full).

The parties and what each optimises:

Party	Wants	Watches
Sponsors (equity)	Return on equity; contained risk; distributions	Equity IRR, distribution tests
Lenders	Repayment with margin; downside protection	DSCR/LLCR, covenants, security (Domain 10)
Offtaker / grantor	Reliable service at agreed price	Availability, tariffs, handback condition
EPC contractor	Construction margin	Variations, delay LDs (Domain 12)
Operator (O&M)	Fee; performance regime it can meet	Availability/output guarantees
Government / regulator	Delivery of policy outcomes; compliance	Permits, obligations, public interest
Community & environment	Benefit without harm	E&S performance (Domain 11)

The finance leader's daily craft is reconciling these optimisations inside one cash flow — which is why the cash waterfall (Domain 15) reads like a peace treaty.

Fig 1.1.2 — The SPV at the centre of its contracts

1.1.4 The infrastructure-finance market

The asset classes and their financing habits, in one professional sweep: **transport** (toll roads, rail, airports — patronage or availability models); **power and renewables** (PPAs, capacity markets; the energy transition's build-out is the market's largest engine); **water** (desalination and treatment concessions — Kestrel's world); **digital infrastructure** (data centres, towers, fibre — shorter refresh cycles, credit-tenant leases); **social infrastructure** (hospitals, schools, housing under availability PPPs); and **natural resources** (commodity-linked, price-hedged). The capital comes from commercial banks (construction-phase specialists), institutional investors and infrastructure funds (long-dated operations-phase capital), export credit agencies and development banks (Domain 9), and bond markets (refinancing bankable operating assets). The leader's market literacy is matching **asset shape to capital shape**: construction risk to banks and ECAs, stabilised cash flows to institutions — mismatches are expensive at best and fatal at close.

Two axes, routinely conflated. "Asset shape" is doing two jobs in that sentence, and separating them is what makes the principle operational. The first axis is **risk-holding capability** — which investor can price, absorb and be paid for construction risk, demand risk or technology risk. That axis dominates, and it is the axis MCQ 1.1-C tests. The second is **timing**, and here the profession's own shorthand misleads: capital described as "long-dated" is being matched to the horizon over which cash arrives, not to the stream's **Macaulay duration** — the present-value-weighted average time to receipt, which is the measure of how far a value moves when a rate moves. The two are very different numbers on the same asset, and an investor who matches the wrong one will systematically buy the wrong asset.

$$\text{Macaulay duration } D = \frac{\sum [t \times CF_t / (1 + r)^t]}{\sum [CF_t / (1 + r)^t]} \quad (\text{years})$$

For a level stream of n payments: $D = (1 + r)/r - n \div [(1 + r)^n - 1]$

Limit as $n \rightarrow \infty$: $D \rightarrow (1 + r)/r$

WORKED EXAMPLE**Worked example 1.1.4 — a fifteen-year asset with a six-year duration.**

- Setup.** An institutional investor with liabilities of average duration **14 years** is offered three positions on the same desalination economics, all discounted at **8.0 %**: (a) Kestrel operating — the level availability stream of **8,900,000 a year for 15 years** (Domain 4's appraisal stream); (b) Kestrel greenfield — the identical stream, but only from year 4, after a three-year construction period; (c) Kestrel indexed — the same 15-year stream starting at 8,900,000 and escalating at **2.5 %** a year (Domain 3's Fisher discipline governs the world it is quoted in). Which matches the liabilities?
- Formula.** As above. For (c) the closed form does not apply, so the summation is used directly with $CF_t = 8,900,000 \times 1.025^{(t-1)}$.
- Substitution.** (a) $D = 1.08/0.08 - 15/(1.08^{15} - 1) = 13.5 - 15/2.172169$. (b) The same weights, every receipt three years later, so $D = 6.594460 + 3$. (c) $\sum t \times CF_t/1.08^t \div \sum CF_t/1.08^t$ over 15 terms.
- Result.**

Position	Present value	Macaulay duration	Gap to a 14-year liability
(a) Operating, 15 years level	76,179,360.32	6.5945 years	(7.4055)
(b) Greenfield, 3-year deferral	60,473,632.32	9.5945 years	(4.4055)
(c) Operating, 15 years indexed at 2.5 %	87,937,828.16	7.0342 years	(6.9658)
Level stream over the full 25-year asset life	—	9.2254 years	(4.7746)
Any level stream at 8 %, however long	—	capped at 13.5000 years	never closes

- Interpretation.** The first result is the one that reorders a reader's intuitions: **a 15-year asset has a duration of 6.59 years — 44 % of its life**. Level streams front-load present value: **54.01 %** of the operating stream's present value arrives in the first six of its fifteen years, and an investor who bought it to match a 14-year liability has bought something less than half as rate-sensitive as the liability it is hedging. The second result is stronger and it is an identity, not an estimate: because $D \rightarrow (1 + r)/r$, **no level stream discounted at 8 % can ever have a duration above 13.5 years, at any tenor**. Extending the concession from 15 years to 25 buys 2.63 years of duration; extending it to 63 years would be needed to reach 13.0. A 14-year duration is therefore unreachable by tenor alone, and the reviewer's cue is immediate: any liability-matching claim that rests on lengthening a level stream is arithmetically confused. What does add duration is deferral (+3.00 years, exactly the deferral, because deferring every weight shifts the weighted mean) and **escalation** (+0.44 years at 2.5 %, because escalation moves weight to the later periods). That is the investor-side reason indexed availability payments and inflation-linked tariffs are prized by liability-driven capital — a fact usually explained on the revenue side (Domain 7) and rarely on the buyer's. Now the honest complication, and it is the professional point of the example. By duration alone, the **greenfield** position at 9.59 years is the closest match to the 14-year liability — and that is emphatically not advice to a pension fund to buy construction risk. The two axes disagree, and the risk axis wins: a construction-phase position carries completion, cost-overrun and technology exposures the fund cannot price, cannot manage and is not paid for, and

duration is a first-order sensitivity measure that says nothing whatever about the probability that the cash arrives at all. The correct professional conclusion is the layered one: **match risk first, then close the residual timing gap with instruments rather than with asset selection** — indexation in the revenue contract, and interest-rate or inflation hedging at the fund level. One caution on the arithmetic itself: duration is computed at a stated rate and moves with it, so a duration quoted without its discount rate is not a number — at 6 % the same 15-year level stream has a duration of **6.9260 years** and the ceiling rises to **17.6667**.




Fig 1.1.3 — The recourse decision against facility size

AI in this KA

Market screening and precedent research are natural AI accelerants — summarising comparable transactions, extracting terms from public disclosures, drafting stakeholder maps. The governed habits start in Domain 1 because the failure modes do: a fluent but invented "precedent transaction" is this profession's textbook hallucination case. Sources are verified against the registry discipline (every claimed deal traced to a public record), and the stakeholder analysis an AI drafts is walked, party by party, by someone who has sat across from those parties. **AI proposes; the professional verifies, decides and remains accountable.** Worked example 1.3.3 prices exactly this failure on Kestrel's own facility, and the number is larger than most readers expect.

One verification habit specific to this KA. The two computations above are the ones a machine gets plausibly wrong rather than obviously wrong. A recourse comparison assembled by a tool will usually discount both routes correctly and still be worthless, because the exposure term — the one number that is not in any term sheet — has to be constructed from an enforcement assumption a human must own and state. And a duration figure is the classic silently-wrong output: the formula is standard, so the answer arrives with no warning that it was computed at a different rate, on a different stream, or on the asset's life rather than its cash flows. In both cases the discipline is the same and it is cheap: **make the tool state the parameter, then recompute one line by hand.**

■ KEY TERMS — KA 1.1

Term	Meaning
Recourse / non-recourse / limited recourse	Whom the lender can pursue: the sponsor's balance sheet; the project only; the project plus bounded sponsor support.
SPV	Ring-fenced single-purpose project company; the borrower and contract hub.
Sponsor	Equity investor promoting the project (this book's project-finance sense).
Offtaker	The buyer of the project's output or service under contract.
Ring-fencing	Legal isolation of the project's assets, contracts and cash.
Asset-capital matching	Pairing project risk phases with the capital suited to hold them — on two axes, risk-holding capability and timing.
Recourse sentence	The three-limbed statement of sponsor support: who stands behind what, until when, capped at what.
Close-cost premium	The largely fixed excess of project-finance transaction costs over a corporate facility's; the source of the scale effect.
Breakeven failure probability p^*	Incremental cost of the limited-recourse route ÷ the exposure the ring-fence removes.
Macaulay duration	Present-value-weighted average time to receipt; for a level stream capped at $(1 + r)/r$, whatever the tenor.

■ SAMPLE MCQS — KA 1.1

MCQ 1.1-A [1.1.2 · Application] A sponsor gives lenders a guarantee that covers cost overruns until the plant passes its completion test, after which lenders may look only to project cash flows. This financing is best described as:

- A. full recourse
- B. non-recourse
- C. limited recourse ✓ CORRECT
- D. unsecured corporate lending

Rationale: Bounded sponsor support (here, to completion) between the poles is the defining shape of limited recourse. A would expose the sponsor for the loan's life; B would mean no sponsor support at all; D abandons both the security package and the ring-fence.

MCQ 1.1-B [1.1.3 · Analysis] Which single feature of the SPV makes non-recourse lending possible?

- A. its tax registration
- B. legal ring-fencing: the SPV can conduct only the project, so its contracts and cash are isolated and chargeable ✓ CORRECT
- C. its sponsors' credit ratings
- D. the size of its share capital

Rationale: Lenders can accept project-only recourse because the ring-fence guarantees no other business can dilute, encumber or divert the cash they are lending against. C reverses the concept (sponsor credit is what non-recourse lending does without); A and D are administrative facts, not the mechanism.

MCQ 1.1-C [1.1.4 · Application] A fund holding long-dated pension liabilities wants infrastructure exposure. The asset-capital matching principle points it toward:

- A. construction-phase risk in a greenfield project
- B. stabilised operating assets with contracted cash flows ☒ **CORRECT**
- C. development-stage equity at risk
- D. short-term bridge lending

Rationale: Long-dated stable liabilities match long-dated stable cash flows on the axis that dominates — risk-holding capability. A and C sit where construction and development specialists (banks, ECAs, developers) hold the risk; D matches a treasury desk, not a pension profile. Note that on the timing axis alone a deferred greenfield stream is the closer duration match (WE 1.1.4) — which is why the risk axis must be settled first.

MCQ 1.1-D [1.1.2 · Application] The limited-recourse route costs 5,202,128 more in present value than the corporate route and removes an enforcement exposure of 10,073,997. The breakeven probability of a parent-impairing failure is:

- A. 12.39 %
- B. 23.42 %
- C. 51.64 % ☒ **CORRECT**
- D. 28.22 %

Rationale: $5,202,128 / 10,073,997 = 51.64\%$ (WE 1.1.2). A divides the incremental cost by the 42,000,000 of debt instead of by the exposure — a cost intensity, not a breakeven; B uses only the 2,359,000 close-cost premium and drops the 2,843,128 margin differential; D is the large-facility asymptote, which omits the fixed close-cost premium altogether and therefore applies to no actual facility.

MCQ 1.1-E [1.1.4 · Analysis] A level availability stream pays 8,900,000 a year for 15 years, discounted at 8.0 %. Its Macaulay duration is closest to:

- A. 6.59 years ☒ **CORRECT**
- B. 8.00 years
- C. 13.50 years
- D. 15.00 years

Rationale: $D = 1.08 / 0.08 - 15 / (1.08^{15} - 1) = 6.5945$ (WE 1.1.4). B is the unweighted mean of the payment dates 1 to 15 — the duration you get by forgetting to discount the weights; C is the $(1 + r) / r$ ceiling, which a level stream approaches only as the tenor approaches infinity; D confuses the asset's life with its duration, the error the example exists to disarm.

MCQ 1.1-F [1.1.2 · Evaluation] A sponsor's board is shown a breakeven failure probability of 51.64 % and concludes that limited recourse "fails its own test" and should be abandoned. The best professional response is:

- A. agree — the arithmetic is decisive
- B. the expected-value test prices a mean while the sponsor is insuring a correlated tail, and it values none of the partnership or balance-sheet capacity the structure delivers; the breakeven is one input, not the decision ☒ **CORRECT**
- C. recompute at a higher discount rate until the answer changes
- D. the calculation is invalid because probabilities of project failure cannot be estimated

Rationale: WE 1.1.2's own interpretation: the exposure term is an expected shortfall, not the correlated loss that would arise in the bad state, and the structure additionally buys an option (the fund's participation) the table does not contain. A treats one input as the decision; C is assumption-shopping, which is the misconduct 1.3.1 names; D overstates the objection — the parameter is uncertain, which is an argument for stating it and testing it, not for discarding the frame.

MCQ 1.1-G [1.1.4 · Analysis] An investment committee paper recommends a 25-year availability concession to an insurer whose liabilities have an average duration of 14 years, on the ground that "extending the tenor from 15 years to 25 brings the asset's duration into line with the liability". The stream is level and the discount rate is 8.0 %. The reviewer should:

- A. accept the recommendation — a 25-year asset is the closest available match to a 14-year liability
- B. reject the reasoning as arithmetically impossible: at 8 % a level stream's duration is capped at $(1 + r)/r = 13.5000$ years, and 25 years reaches only 9.2254, so no tenor closes the gap
✓ CORRECT
- C. correct the reasoning but keep the recommendation — 9.2254 years is the longest duration the concession can offer, so tenor is still the right lever and the residual gap belongs to the liability side
- D. reject the recommendation because duration is not a meaningful measure for infrastructure assets

Rationale: extending 15 years to 25 buys **2.6309** years of duration ($6.5945 \rightarrow 9.2254$) and the ceiling is never reached at any finite tenor, so the paper's stated mechanism cannot deliver what it claims (WE 1.1.4); duration is added by deferral (+3.0000 years), escalation (+0.4398 at 2.5 %) or a lower rate (the ceiling is 17.6667 at 6 %), and the residual gap is closed with instruments rather than asset selection. A confuses the asset's life with its duration, the error the example exists to disarm. C is the strongest of the wrong answers and gets halfway: it drops the paper's mechanism and then repeats its conclusion, when 9.2254 is not the longest duration available — deferring the same 15-year stream by three years reaches **9.5945**, which is why WE 1.1.4 ranks the greenfield position ahead of the long concession. D discards a first-order measure the profession uses correctly; the defect is the claim made with it, not the measure.

MCQ 1.1-H [1.1.2 · Comprehension] Kestrel's breakeven failure probability p^* falls from 93.7893 % on a 15,000,000 facility to 51.6392 % at 42,000,000 and approaches 28.2224 % on very large ones. Which statement restates the reason correctly?

- A. lenders charge a lower margin on larger facilities, so the incremental cost of the project route shrinks
- B. the close-cost premium is broadly fixed while the exposure the ring-fence removes scales with the facility, so a partly fixed cost divided by a proportional benefit falls toward the margin differential alone **✓ CORRECT**
- C. larger projects fail more often, so the probability required to justify the structure is lower
- D. enforcement recoveries improve with project size, which enlarges the exposure the structure removes

Rationale: the cost has a fixed element (the **2,359,000** close-cost premium) and a proportional one (140 basis points, worth **6.7694 %** of the debt in present value), while the exposure removed is proportional (**23.9857 %** of debt on these assumptions) — which is exactly why the curve is a hyperbola with 28.2224 % as its asymptote (1.1.2). A asserts a pricing pattern the example does not contain and the arithmetic does not need. C confuses the probability required with the probability

expected. D reverses the direction: a better recovery reduces the exposure removed and therefore raises p^* — at a 50 % recovery it reaches 127.6910 %.

■ SELF-CHECK — KA 1.1

1. State the finance leader's one recurring question. — Will the cash arrive, and who is exposed if it does not?
2. Name two things limited recourse buys a sponsor and two things it costs. — Buys: risk containment, balance-sheet capacity (also partnering, lender discipline). Costs: pricing and fees, transaction complexity (also covenant control, time).
3. Why does every party around the SPV get a contract? — Non-recourse credit is built from contracts: each relationship must be enforceable because the cash flow is the only security.
4. Why does the recourse breakeven fall as the facility grows? — The close-cost premium is largely fixed while the exposure removed scales with the facility, so p^* falls hyperbolically toward the margin differential alone (28.2224 %).
5. State the duration ceiling and what it rules out. — A level stream's duration cannot exceed $(1 + r)/r$ — 13.5 years at 8 % — so no amount of tenor can match a longer-duration liability; only deferral, escalation or a lower rate moves it.

KNOWLEDGE AREA 1.2

Value, cash and risk: the discipline's logic

Topics: 1.2.1 value creation in projects · 1.2.2 cash as the binding constraint · 1.2.3 leverage, risk and the bankability triangle.

1.2.1 Value creation in projects

A project creates value when the present value of what it will produce exceeds what it costs to build and run — Domain 4's NPV, stated in words. The foundation point is where value can be created or destroyed by financing: structure does not conjure value from a bad project, but it can (1) allocate each risk to the party who bears it cheapest — lowering the priced-in premiums; (2) match capital to risk phase — lowering the blended cost of funds; and (3) impose diligence and covenant discipline that keeps forecast value from leaking in execution. The corollary the profession lives by: **financing engineering amplifies project quality; it never substitutes for it.**

Channel one, made computable. "Allocate each risk to the party who bears it cheapest" is usually taught as a comparison of two parties' expected costs, and Domain 11 (KA 11.2.2) builds that register properly, item by item. What that comparison omits — and what makes the allocation question a financing question rather than a risk-register question — is that a risk the SPV retains is not paid for out of a contingency line. **It is paid for in the capital structure**, because lenders respond to retained construction risk by de-gearing rather than by pricing, and equity is the most expensive money in the structure. The consequence is that the sponsor's true reservation price for transferring a risk is usually several times the risk's own expected cost, and is invisible on any risk register.

WORKED EXAMPLE**Worked example 1.2.1 — what retaining a risk actually costs.**

1. **Setup.** Kestrel's EPC contractor will accept a defined construction risk — say a scope interface the sponsors would otherwise carry — for a fixed **1,350,000** addition to the contract price. The sponsors' own estimate of the risk's expected cost is **900,000**, so the quote carries a **50 %** loading and the risk register says refuse. The lenders' credit committee, told the risk is retained, does not reprice: it reduces senior gearing from **70 %** to **62 %** of the 60,000,000 envelope. Cost of equity is Domain 9's derived **15.42 %** (KA 9.1.3); the senior rate is **6.0 %**; the horizon is the 12-year debt term and the comparison rate is the appraisal's **8.0 %**.
2. **Formula.** Extra equity = capex × (new equity share – old equity share). Annual cost of the substitution = extra equity × ($k_e - k_d$). Cost of retention = that annuity discounted; the **breakeven transfer price** is that present value.
3. **Substitution.** Equity $60,000,000 \times 0.30 = 18,000,000$ becomes $60,000,000 \times 0.38 = 22,800,000$, so **4,800,000** of debt is replaced by equity — 8.0000 % of the envelope. Annual $4,800,000 \times (0.1542 - 0.0600) = 4,800,000 \times 0.0942 = 452,160$. PV $452,160 \times AF(0.08, 12) = 452,160 \times 7.536078$.
4. **Result.** Cost of retention **USD 3,407,513.04** in present value — **3.7861 times** the risk's own expected cost of 900,000. Against a transfer price of 1,350,000, transferring creates **USD 2,057,513.04** of value, and the sponsor should be willing to pay up to **3,407,513.04** — the breakeven — before retention becomes the cheaper answer.
5. **Interpretation.** The register said refuse and the register was wrong by **2,057,513**, because it compared the quote with the wrong number. This is the first channel of 1.2.1 in arithmetic: value was created not by reducing anyone's risk but by **moving it to where it is financed more cheaply**, and the gain is the spread between equity and debt — 942 basis points on 4,800,000 — not any difference in the parties' views of the hazard. Four things a reviewer should take from it. **The form of the lender's response matters more than the risk.** Had the committee priced the retention at, say, 35 basis points of margin on the full 42,000,000 instead of de-gearing, the cost would have been **147,000** a year and **1,107,803.47** in present value — under a third as much — and the same 1,350,000 quote would then have been rejected correctly. The professional discipline is therefore to ask the credit committee how it will respond before negotiating the contract price, which is a conversation most sponsors have in the wrong order. **The answer is robust to the discount convention.** At 10 % the retention cost is 3,080,878.89 and at 6 % it is 3,790,838.88, so the transfer pays across the plausible range; when a conclusion survives its own sensitivity band, say so, because that is what makes it usable in a negotiation. **Two costs, not one, and they add.** Domain 11's method prices the transferee's premium against the retainer's expected cost; this prices the financing consequence. Both are real, they are additive, and an allocation decision taken on either alone is taken on half the arithmetic. And **the transfer is only worth its price if the transferee can pay** — a fixed-price wrap from a contractor whose balance sheet cannot absorb the loss is a priced illusion, which is precisely why Domain 11 tests capability and Domain 12 writes the security for it. One caution belongs on the record: the 8-point de-gearing is a lender judgment, not a formula — Domain 10's sizing shows what governs it — so the honest presentation of this result quotes the gearing response as the assumption it is, and re-runs it if the credit committee lands somewhere else.

1.2.2 Cash, not profit, is the binding constraint

The principle. Profit is an opinion about periods (Domain 2's accrual model); **cash pays debt service.** Projects die of cash exhaustion, usually while reporting profits.

WORKED EXAMPLE

Worked example 1.2.2 — profitable and out of cash.

1. **Setup.** In its first operating quarter a project company recognises revenue of USD 10,000,000 against costs of USD 8,000,000. But customers have paid only 7,000,000 of the revenue (receivables +3,000,000); spare-parts inventory was built up by 1,000,000; and suppliers extended 500,000 of additional credit (payables +500,000).
2. **Formula.** Operating cash flow = profit – Δ receivables – Δ inventory + Δ payables.
3. **Substitution.** $2,000,000 - 3,000,000 - 1,000,000 + 500,000$.
4. **Result.** Profit **+USD 2,000,000**; operating cash flow **–USD 1,500,000**.
5. **Interpretation.** The same quarter is a success in the income statement and a crisis in the bank account: a 2.0m "profitable" company is 1.5m short of the cash its debt service assumed. This is why lenders size and test debt against **CFADS** — cash flow available for debt service (defined fully in Domain 10) — and why every model in Domain 6 is a cash model first. Domain 2 builds the full accrual-to-cash bridge. Three things worth extracting before moving on. **The breakeven is 1,500,000 of receivables.** Holding the inventory build and the supplier credit where they are, operating cash flow crosses zero when receivables rise by $2,000,000 - 1,000,000 + 500,000 = 1,500,000$ — which on quarterly revenue of 10,000,000 is **13.6875 days** of sales, on a 91.25-day quarter. The company did not miss that threshold by a little: at 3,000,000 its receivables are **27.3750 days**, twice the level at which the quarter turns cash-negative. **The drain compounds if the pattern is structural rather than seasonal.** A first quarter's working-capital build is a genuine one-off — the balance sheet is being filled — but the same absorption repeated through the year is **6,000,000** of cash gone against 8,000,000 of annual profit, and telling those two cases apart is the whole of the analysis. **The shortfall has to be funded before it is explained.** A 1,500,000 hole is met from a working-capital facility, a funded reserve or an equity call, and the working-capital line is among the most commonly omitted items in a sources-and-uses statement — the same class of defect as the unfunded reserve Domain 13 (KA 13.2.3) found in Kestrel's own funding plan, discovered late because such statements are reviewed for arithmetic, which always balances, rather than for completeness, which does not.

On a financed project the same divergence does not merely embarrass a management report — it walks a covenant, and the distance to that covenant is best stated in the one unit an operating team controls, because collection days are something a team can be held to and a currency amount is not.

WORKED EXAMPLE**Worked example 1.2.2b — Kestrel's cash gap, in days of receivables.**

- Setup.** Kestrel's first operating year (Domain 2): revenue **USD 12,000,000**; **CFADS 6,984,000** before working-capital movements and **6,384,000** after, the difference being **600,000** absorbed into receivables and spares. Debt service is the master instalment **5,009,635.23**. The facility's financial covenant is a **DSCR** of **1.20×** (Domain 10, KA 10.2.1).
- Formula.** $DSCR = CFADS \div \text{debt service}$. Covenant $CFADS = 1.20 \times \text{debt service}$. Headroom = actual $CFADS - \text{covenant } CFADS$. Days of revenue = amount $\div$ annual revenue $\times 365$.
- Substitution.** $6,984,000/5,009,635.23$ and $6,384,000/5,009,635.23$; covenant cash $1.20 \times 5,009,635.23$; headroom $6,384,000 - 6,011,562.28$; days $\times 365/12,000,000$.
- Result.**

	USD	DSCR	Days of revenue
CFADS before working capital	6,984,000	1.3941	—
Working capital absorbed	(600,000)	(0.1198)	18.2500
CFADS as documented	6,384,000	1.2743	—
Covenant floor at 1.20×	6,011,562.28	1.2000	—
Remaining headroom	372,437.72	0.0743	11.3283
Total working-capital tolerance from 6,984,000	972,437.72	0.1941	29.5783

Sensitivity: **50,096.35** of **CFADS** — **1.5238 days** of revenue — moves **DSCR** by 0.01×. 5. **Interpretation.** The project has **29.58 days** of revenue-equivalent working-capital tolerance before a 1.20× covenant fails, and it has already spent **18.25** of them — **61.70 % of the tolerance, consumed in the first operating year and reported as normal.** What remains is **11.33 days**, which is the sentence to put in front of an operations director, because "the covenant is eleven days of collections away" is actionable in a way that "headroom is 372,438" is not. Four professional readings follow. **The two DSCR figures are the same project.** 1.3941 and 1.2743 differ by nothing but a definition of **CFADS**, and Domain 10's case study records a sponsor arguing for the higher one; the facility's documented definition decides, and a ratio quoted without its definition is not a ratio. **The sensitivity is the number to memorise.** At this debt-service level roughly a day and a half of receivables is worth 0.01× of **DSCR** — which is also, not coincidentally, the materiality threshold Domain 13 set for its model audit (KA 13.2.2), so the two disciplines are calibrated to the same unit. **Working capital is recoverable and that is exactly what makes it dangerous.** The 600,000 is not a loss; it comes back if collections normalise, which is why it attracts less scrutiny than a cost overrun of the same size — and a covenant test is measured on the date it falls, not on the date the cash eventually arrives. **The direction of the next movement is not symmetric.** Growth, indexation and a rising tariff all increase the receivables balance, so a project whose revenue is escalating is consuming headroom at an increasing rate unless collection days improve, which is the honest reason a first-year covenant test is the one lenders watch hardest. The caution: the day translation assumes the whole absorption behaves like receivables on this revenue base; a spares build is not collectable and does not respond to a collections campaign, so the instruction to an operations team must name which days it is asking for.

1.2.3 Leverage, risk and the bankability triangle

Leverage amplifies. Debt is cheaper than equity, and fixed: whatever the project earns, debt service is owed. That fixity cuts both ways.

WORKED EXAMPLE

Worked example 1.2.3 — the two faces of leverage.

1. **Setup.** A project costs USD 100,000,000 and produces steady operating cash of USD 12,000,000 per year. Compare an all-equity structure with 70 % debt (USD 70,000,000, interest-only at 6.0 % = 4,200,000 per year), in the base case and with cash down 25 % and 50 %.
2. **Formula.** Unlevered return = cash / 100,000,000. Equity cash = cash – 4,200,000; levered return = equity cash / 30,000,000.
3. **Substitution.** Base: $12.0 - 4.2 = 7.8$ on 30. Down 25 %: $9.0 - 4.2 = 4.8$. Down 50 %: $6.0 - 4.2 = 1.8$.
4. **Result.**

Scenario	Project cash	Unlevered return	Equity cash	Levered return
Base	12,000,000	12.0 %	7,800,000	26.0 %
–25 %	9,000,000	9.0 %	4,800,000	16.0 %
–50 %	6,000,000	6.0 %	1,800,000	6.0 %
–65 %	4,200,000	4.2 %	0	0.0 %

1. **Interpretation.** Leverage more than doubles the base-case equity return (26 % vs 12 %) — and makes the downside three times steeper (26 → 6 % as cash halves, versus 12 → 6 % unlevered). At a 65 % cash decline the equity earns nothing and the lender is next in line. Gearing is chosen, not maximised: Domain 9 structures it, Domain 10 shows how lenders cap it with coverage ratios sized precisely against scenarios like this table. Three structural facts sit inside that table and are worth extracting, because each one is a check a reviewer can run in a single line. **The 26 % is an identity, not a coincidence.** $r_{\text{equity}} = r_{\text{unlevered}} + (D/E) \times (r_{\text{unlevered}} - r_{\text{debt}})$, so $12.0 \% + (70/30) \times (12.0 \% - 6.0 \%) = 12.0 \% + 2.333333 \times 6.0 \% = 26.0000 \%$ — exactly the table's base-case row. Read it as the sentence it is: **the levered return is the unlevered return plus the gearing ratio times the spread the project earns over its debt.** That is where the amplification comes from, it is why the amplification is linear in D/E , and it gives an instant audit of any levered-return figure presented without its workings. **The crossover is where the spread vanishes.** When the project's unlevered return equals the cost of debt — here at project cash of exactly $100,000,000 \times 6.0 \% = 6,000,000$ — the spread term is zero and the levered and unlevered returns coincide at 6.0 %, which is the –50 % row's apparent coincidence. Above that cash level leverage helps; below it, leverage hurts, and the identity says so with a sign. A structure is therefore not "geared for return" in any general sense: it is geared for return only in the states of the world where the project out-earns its debt, and the whole downside case is the region where the arrangement runs in reverse. **The cliff is a property of the debt's shape, not of the gearing.** The 65 % decline in the last row is the distance to zero equity cash for interest-only debt, and interest-only debt is the exception in project finance rather than the rule; the next example moves the cliff by more than half its distance without changing the gearing, the rate or the project by one dollar.

WORKED EXAMPLE**Worked example 1.2.3b — the same 70 % gearing, amortising: where the cliff really is.**

- Setup.** The identical project and structure — 100,000,000 of capital cost, 70,000,000 of senior debt at 6.0 %, 30,000,000 of equity, steady operating cash of 12,000,000 — but the debt amortises over **12 years** on the master facility's terms rather than paying interest only. The lender's financial covenant is a **DSCR** of **1.20×**.
- Formula.** Level instalment = $\text{debt} \div AF(r, n)$. Equity cash = project cash – instalment; cash-on-cash return = equity cash $\div$ equity. **DSCR** = project cash $\div$ instalment. The cliff is the cash level at which equity cash reaches zero; the covenant bites where **DSCR** = 1.20.
- Substitution.** $AF(0.06, 12) = 8.383844$; $70,000,000/8.383844 = 8,349,392.06$. Equity cash $12,000,000 - 8,349,392.06$. **DSCR** = $12,000,000/8,349,392.06$. Covenant cash $8,349,392.06 \times 1.20$.
- Result.**

	Interest-only (WE 1.2.3)	Amortising over 12 years
Annual debt service	4,200,000	8,349,392.06
Of which year-one interest	4,200,000	4,200,000
Of which principal repaid	nil	4,149,392.06
Equity cash at 12,000,000	7,800,000	3,650,607.94
Cash-on-cash return on 30,000,000	26.0000 %	12.1687 %
DSCR at base case	2.8571	1.4372
Cash at which the 1.20× covenant fails	5,040,000	10,019,270.47 — a 16.5061 % decline
Cash at which equity cash reaches zero	4,200,000 — a 65.0000 % decline	8,349,392.06 — a 30.4217 % decline

- Interpretation.** Two conclusions, and they point in opposite directions, which is why this example matters more than its arithmetic. **The first is a warning about the metric.** The headline equity return collapsed from 26.00 % to **12.1687 %** — barely above the 12.0 % unlevered return — and the project did not get worse by one cent. Year-one interest is **identical at 4,200,000** in both columns; the entire difference is the **4,149,392.06** of principal repaid, and principal repayment is a return of capital, not a cost. The amortising equity is better off than the cash-on-cash figure implies, because it also owns a claim that is de-levering by 4,149,392 in the first year and by more in every year after it. Single-period cash-on-cash return is therefore the wrong instrument for judging a levered structure whenever debt amortises, and the right one is the equity **IRR** over the whole life (Domain 4's measure, applied to the structure in Domain 9, KA 9.1.4) — which is exactly why an interest-only illustration of leverage, WE 1.2.3 included, flatters every structure it is applied to. **The second is a warning about the cliff, and it is the one that reaches a credit committee.** The distance to zero equity cash more than halved, from a 65.00 % decline to **30.42 %** — and the covenant bites far earlier still, at a **16.51 %** decline in project cash. Rank them: the lender's protection engages at –16.51 %, the equity's own cash runs out at –30.42 %, and the interest-only reading suggested –65.00 %. An analyst who models leverage interest-only and reports the resilience of the structure has overstated the equity's cushion by a factor of roughly four, and the error is invisible in the base case, where every number looks fine. The caution to carry: the amortising column is not "worse". It is a **different**

bargain — a structure that repays principal converts operating cash into ownership and buys future distribution capacity, which is why sculpted and back-ended profiles exist and why Domain 10's sizing levers include the repayment shape and not only the amount. What is unarguable is that the three thresholds in the table are the ones a leader must be able to state from memory about their own project. Fig 1.2.2 draws all three lines together, and the geometry is worth more than the table: two straight lines of identical slope, offset by the principal repayment, crossing the unlevered line at two very different places.

The bankability triangle. Three tests every financing must pass simultaneously: **value** (the project is worth doing — Domain 4), **cash** (the flows arrive in the periods that need them — Domains 6–8), and **risk allocation** (each hazard sits with a party able and bound to bear it — Domains 11–12). A project strong on two corners and weak on one is not two-thirds bankable; it is unbankable until the corner is fixed. **Bankability** (built fully in Domain 5) is precisely the state of passing all three tests in the eyes of the capital being asked to commit.




Fig 1.2.1 — The bankability triangle




Fig 1.2.2 — Where leverage helps, and where the cliff is

AI in this KA

Scenario tables like 1.2.3's are ideal machine work — and the place where a subtly wrong fixed-charge assumption (interest-only vs amortising; Domain 3's shapes) silently reshapes every row. WE 1.2.3b measures the damage: the same gearing, rate and project, and a cliff that moves from a 65.00 % cash decline to 30.42 %, with the covenant at 16.51 %. The governed pattern: the machine drafts the grid; the analyst re-derives one row by hand and checks the boundary case (where equity cash crosses zero) analytically; the leader reads the downside rows first, because that is what the structure is actually being designed against.

The verification that is specific to a foundations model. Ask the tool for the identity, not only the table. A grid that cannot reproduce $r_{\text{equity}} = r_{\text{unlevered}} + (D/E) \times (r_{\text{unlevered}} - r_{\text{debt}})$ on its own base-case row has an error in it somewhere, and the check costs one line; a grid whose rows satisfy the identity is still wrong if the fixed charge is the wrong shape, so the second check is to confirm that the debt service in the table equals $\text{debt} \div AF(r, n)$ for the documented tenor. Those are the first two entries on the reviewer's list at 1.A.3, and they are the two worth running before any other.

■ KEY TERMS — KA 1.2

Term	Meaning
CFADS	Cash flow available for debt service (name fixed here; machinery in Domain 10).
Working capital drag	Cash absorbed by receivables and inventory ahead of profit.
Leverage / gearing	Debt's share of funding; amplifier of equity return and risk.
Fixed charge	Debt service owed regardless of performance.
Bankability triangle	Value + cash + risk allocation, passed together.
Levered-return identity	$r_e = r_u + (D/E) \times (r_u - r_d)$; amplification is linear in gearing and proportional to the spread over the debt rate.
Leverage crossover	The cash level at which the unlevered return equals the cost of debt, so gearing neither adds nor subtracts.
Equity cliff	The cash level at which debt service consumes all project cash; a function of the debt's shape, not only its size.
Cost of retention	The present value of the capital-structure change lenders impose when a risk is retained; the sponsor's true reservation price for transferring it.

■ SAMPLE MCQS — KA 1.2

MCQ 1.2-A [1.2.2 · Application] A company reports quarterly profit of 2,000,000 while receivables rose 3,000,000, inventory rose 1,000,000 and payables rose 500,000. Its operating cash flow is:

- A. +2,000,000
- B. -1,500,000 ✓ CORRECT
- C. +500,000
- D. -2,500,000

Rationale: $2.0 - 3.0 - 1.0 + 0.5 = -1.5\text{m}$. A stops at profit; C nets only the payables against profit and forgets the asset build; D subtracts the payables increase instead of adding it — supplier credit is a cash source.

MCQ 1.2-B [1.2.3 · Application] In the leverage example (70m debt, interest-only 6 %; equity 30m), project cash of 9,000,000 produces a levered equity return of:

- A. 9.0 %
- B. 16.0 % ✓ CORRECT
- C. 26.0 %
- D. 30.0 %

Rationale: $(9.0 - 4.2)/30 = 16.0 \%$. A is the unlevered return; C is the base-case levered return; D divides project cash by equity without paying the lender first.

MCQ 1.2-C [1.2.3 · Analysis] A project shows strong NPV and well-allocated risks, but its revenue arrives seasonally while debt service is quarterly and level. The bankability verdict is:

- A. bankable — two of three corners suffice

- B. unbankable as structured: the cash corner fails; reshape the debt profile or add liquidity support ☒ **CORRECT**
- C. unbankable permanently — reject the project
- D. bankable if the sponsors accept a higher equity IRR

Rationale: The triangle is conjunctive: mistimed cash defeats value and allocation. The cure is structural (sculpted or seasonal debt service, reserve accounts — Domains 9–10), not rejection (C) and not a return adjustment that changes nothing about timing (D).

MCQ 1.2-D [1.2.3 · Application] The same project (100,000,000 cost, 12,000,000 of annual operating cash, 70,000,000 of senior debt at 6.0 %, 30,000,000 of equity) is financed with debt **amortising over 12 years** rather than interest-only. $AF(0.06, 12) = 8.383844$. The base-case cash-on-cash equity return is:

- A. 12.1687 % ☒ **CORRECT**
- B. 26.0000 %
- C. 40.0000 %
- D. 12.0000 %

Rationale: Instalment $70,000,000/8.383844 = 8,349,392.06$; $(12,000,000 - 8,349,392.06)/30,000,000 = 12.1687\%$ (WE 1.2.3b). B is the interest-only reading, which charges only the 4,200,000 of interest; C divides project cash by equity and never pays the lender at all; D concludes that amortisation makes leverage exactly neutral — close, and wrong by the 17 basis points that are the whole of the remaining spread benefit.

MCQ 1.2-E [1.2.2 · Application] Kestrel's documented **CFADS** is 6,384,000, debt service is 5,009,635 and the covenant is 1.20×; annual revenue is 12,000,000. Expressed in days of revenue, the remaining covenant headroom is:

- A. 11.33 days ☒ **CORRECT**
- B. 18.25 days
- C. 29.58 days
- D. 1.52 days

Rationale: Headroom $6,384,000 - 6,011,562 = 372,438$; $372,438/12,000,000 \times 365 = 11.33$ days (WE 1.2.2b). B is the working capital already absorbed, which is history rather than headroom; C is the total tolerance measured from the pre-working-capital **CFADS** of 6,984,000, so it double-counts the 600,000 already spent; D is the sensitivity — the days worth 0.01× of **DSCR** — mistaken for the headroom itself.

MCQ 1.2-F [1.2.1 · Evaluation] A contractor offers to take a construction risk for 1,350,000; the sponsors' expected cost of the risk is 900,000, and lenders have said they will de-gear from 70 % to 62 % of a 60,000,000 envelope if it is retained. $k_e = 15.42\%$, $k_d = 6.0\%$, $AF(0.08, 12) = 7.536078$. The sound conclusion is:

- A. refuse: the quote is loaded 50 % above expected cost
- B. accept: retention costs 3,407,513 in present value through the capital structure, so the transfer creates 2,057,513 of value ☒ **CORRECT**
- C. accept only if the contractor reduces the price to 900,000
- D. indifferent: risk transfer is value-neutral by construction

Rationale: $4,800,000 \times (0.1542 - 0.0600) \times 7.536078 = 3,407,513.04$ (WE 1.2.1). A compares the quote with the risk's own expected cost and ignores where a retained risk is actually paid for; C

demands a price at which no contractor would accept the risk, since the transferee must be paid for uncertainty as well as expectation; D denies the gain from trade that the equity-debt spread creates.

MCQ 1.2-G [1.2.3 · Evaluation] An analyst's paper on the WE 1.2.3 project — 100,000,000 of capital cost, 12,000,000 of steady operating cash, 70,000,000 of senior debt at 6.0 % and 30,000,000 of equity — reports that the structure "absorbs a 65 % fall in project cash before the equity's own cash runs out", having modelled the debt as interest-only when the facility amortises over 12 years and carries a 1.20× DSCR covenant. Each objection below is a fair one. Which is the more decisive for the credit committee?

- A. the paper overstates the cushion that matters: on the amortising facility the equity's cash exhausts at a 30.42 % decline and the 1.20× covenant engages at 16.51 %, so the reported resilience is roughly four times the distance to the first consequence ✓ CORRECT
- B. the paper's 26.0000 % cash-on-cash return is overstated, since the amortising structure returns 12.1687 %
- C. the paper should have measured the equity with an IRR over the whole life rather than a single-period return
- D. the paper omits the tax shield on the interest charge

Rationale: A and B follow from the same substitution, but the committee is buying downside protection, and only A quantifies it — the covenant bites at −16.51 %, the equity's cash runs out at −30.42 %, and the paper reported −65.00 % (WE 1.2.3b). B is true and second-order, and on its own it is a misleading correction: the **4,149,392.06** of principal repaid is a return of capital rather than a cost, so the amortising equity is better off than 12.1687 % implies. C is a sound methodological point that quantifies nothing by itself. D is true of both columns equally — year-one interest is identical at 4,200,000 — so it cannot be an objection to this paper.

MCQ 1.2-H [1.2.3 · Comprehension] The levered-return identity is $r_e = r_u + (D/E) \times (r_u - r_d)$. Which statement restates what it says about a structure geared 70/30 against debt costing 6.0 %?

- A. gearing adds return in every state of the world, because debt is cheaper than equity
- B. gearing adds 2.333333 times whatever the project earns above 6.0 % and subtracts 2.333333 times whatever it earns below it, so one structure amplifies in both directions ✓ CORRECT
- C. gearing raises the equity return by the difference between the cost of equity and the cost of debt
- D. gearing raises the equity return wherever the project's unlevered return exceeds the equity holders' required return

Rationale: the identity multiplies the **spread over the debt rate** by the debt-to-equity ratio, so its sign follows the spread: at an unlevered 12.0 % it adds **14.0000** points to reach 26.0000 %, and at an unlevered 4.0 % it subtracts **4.6667** points to −0.6667 % (WE 1.2.3). A ignores the sign; below the crossover — project cash of 6,000,000 on this structure — leverage subtracts. C names the wrong spread: the identity uses $r_u - r_d$, not $k_e - k_d$. D substitutes the equity's required return for the debt rate and so puts the crossover in the wrong place.

■ SELF-CHECK — KA 1.2

1. Why do lenders test CFADS rather than profit? — Debt service is paid in cash; accrual profit can coexist with cash exhaustion (WE 1.2.2).
2. State leverage's two faces in one sentence each. — It multiplies the equity return on the same project cash; it makes every downside steeper because debt service is fixed.

3. Why is the triangle conjunctive? — Each corner defeats the financing alone: no value → no equity; no cash timing → default risk regardless of value; no allocation → risk premia or collapse at close.
4. State the levered-return identity and what it implies below the crossover. — $r_e = r_u + (D/E) \times (r_u - r_d)$; where $r_u < r_d$ the spread term is negative and gearing reduces the equity return.
5. Why does amortisation move the equity cliff so far? — Debt service rises from interest alone to interest plus principal (4,200,000 → 8,349,392), halving the cash decline the equity can absorb, from 65.00 % to 30.42 %, with the covenant engaging at 16.51 %.
6. Where is a retained risk paid for? — In the capital structure: lenders de-gear, equity replaces debt, and the cost is the equity-debt spread on the substituted amount.

KNOWLEDGE AREA 1.3

Ethics, fiduciary awareness and responsible AI

Topics: 1.3.1 obligations and duties · 1.3.2 conflicts and independence · 1.3.3 the responsible-AI principle in finance.

1.3.1 Obligations and duties

The project finance leader acts inside a lattice of duties: **fiduciary-type duties** to the employer or client (loyalty, care, confidentiality); **contractual duties** under mandates and finance documents; **statutory duties** (companies law, anti-bribery and corruption, sanctions, market conduct); and **professional duties** — competence, candour, and records that let others check the work. Two standing disciplines follow. Candour about numbers: forecasts are presented with their assumptions and sensitivities, never as certainties (Domain 4, KA 4.3.3); an optimistic case knowingly presented as a base case is a misrepresentation, whatever the spreadsheet says. Candour about limits: this book's own rule — educational reference, not individualized advice; jurisdiction-specific matters go to qualified counsel and advisers — is the same professional humility applied to oneself.

1.3.2 Conflicts and independence

Project finance concentrates conflicts because the same institutions recur in many roles: the adviser who would earn a success fee on close; the sponsor-affiliated contractor pricing the EPC; the bank advising the government while lending to bidders. The professional machinery is disclosure and separation: conflicts are declared before engagement, managed with information barriers or declined; advice and self-interest are never silently blended. The leader's test for any arrangement is the daylight test — would every party, seeing the full fee and relationship map, still regard the advice as independent? Where the answer wavers, independence has already failed. (Case study B applies this to a live tender; Domain 13's diligence streams exist partly to give lenders advice that passes the test.)

Why the commercial argument runs the same way as the duty. The duty to disclose does not depend on what disclosure costs, and a professional who needs the arithmetic before deciding has already answered a different question. But the arithmetic is worth having for one specific reason: partners and committees do sometimes ask to "weigh it commercially", and the leader who can show that the commercial case points the same way removes the last excuse for not disclosing. The structure of the calculation is what carries the lesson.

WORKED EXAMPLE**Worked example 1.3.2 — the conflict priced at discovery.**

1. **Setup.** Fictitious throughout. An advisory firm holds a mandate advising a grantor on a toll-road tender. It is offered a second, unrelated mandate from the lead sponsor of one of the bidding consortia. Declining that second mandate — or accepting it, disclosing it and living with the barriers — would cost the firm the **250,000** fee at risk on the second engagement. If instead the relationship is not disclosed and is later discovered, the firm's own estimates are: the unpaid balance of the tender mandate, **900,000**, forfeited; the loss of its public-sector practice in that jurisdiction — **three mandates a year at 850,000 for five years**; and **400,000** of legal and professional-indemnity cost. On the grantor's side the discovered conflict forces a re-run: **1,100,000** to re-appoint an adviser, **2,100,000** of fresh evaluation and legal cost, and **three bidders' abortive bid costs at 1,800,000 each**.
2. **Formula.** Expected value of concealment = cost avoided by not disclosing – (probability of discovery × loss on discovery). The **breakeven discovery probability** $p^* = \text{cost avoided} \div \text{loss on discovery}$.
3. **Substitution.** Franchise loss $3 \times 850,000 \times 5 = 12,750,000$; total private loss $900,000 + 12,750,000 + 400,000$. $p^* = 250,000 \div 14,050,000$. Grantor's re-run $1,100,000 + 2,100,000 + 3 \times 1,800,000$.
4. **Result.** Loss on discovery to the firm **USD 14,050,000**; breakeven discovery probability **1.7794 %**. Cost imposed on others **USD 8,600,000**. Total value destroyed **USD 22,650,000** against a **250,000** saving — a ratio of **90.6000 to 1**. Expected value of concealment at a 10 % discovery probability: **–1,155,000**; at 25 %: **–3,262,500**; at 50 %: **–6,775,000**.
5. **Interpretation.** Concealment pays only if the chance of discovery is below **1.78 %**, and in a competitive tender that number is not remotely available: the losing bidders have every incentive to look, professional relationships in a single jurisdiction's infrastructure market are small and traceable, and the discovery event does not require anyone to prove that the advice was actually biased — Case study B turns on exactly that point. So **the expected value of concealment is negative at every plausible probability**, which is the first useful result. The second is structural, and it is the one to carry: **the calculation has no upside term**. What concealment "buys" is bounded above by the fee at risk on the engagement being hidden — 250,000 here — while what it risks is the franchise, which is a multiple of any single fee because it is the discounted value of every future fee. Any framing in which non-disclosure appears to have a large benefit has mis-specified the benefit, and the reviewer's cue is to ask what, precisely, is on the left-hand side. Third, note **who bears the loss**: 14,050,000 falls on the firm and 8,600,000 on parties who had no part in the decision — the grantor's programme and three bidders' abortive costs — which is why this is an ethical question and not a risk-appetite question. A firm entitled to gamble its own franchise is not entitled to gamble other people's. And the boundary of the arithmetic: this is expected-value reasoning applied to a **duty**, and duties are not tradeable. The correct use of the table is to close a commercial argument that should never have been opened; the wrong use is to invite the calculation wherever the duty is inconvenient, and a leader who reaches for it more than once has a culture problem rather than a disclosure problem. Counsel pointer: whether an undisclosed relationship gives losing bidders a right of challenge, what remedies attach and what disclosure a procurement regime positively requires are jurisdiction-specific and time-variable questions for qualified counsel; nothing here states the law of any jurisdiction.

1.3.3 The responsible-AI principle in finance

The suite principle — **AI proposes; the professional verifies, decides and remains accountable** — lands hardest in finance, where machine output looks like the work product itself (a model, a memo, a covenant summary). Domain 16 builds the full governance architecture; the foundations fixed here:

- **Verification is not optional and not delegable to the tool.** Golden-answer checks for calculations (the discipline this book applies to itself); source-tracing for claims; document-against-summary checks for AI-read contracts.
- **Accountability cannot be transferred.** "The model said so" is never a defence — the signing professional owns the output as if hand-made.
- **Confidentiality travels with the data.** Deal information entering an AI tool is a disclosure; it happens only within approved, contracted environments.
- **Material AI use is disclosed** within the team and, where it touches deliverables, to the client — the daylight test again, applied to method.

What the verification duty actually asks for. "Check the output" is not an instruction until it distinguishes two different objects. Verifying a **number** means recomputing it from stated inputs by an independent route and reconciling to the digit — the discipline this book applies to itself, and the reason every figure in this domain carries a derivation. Verifying a **claim** — that a transaction happened, that a clause says what a summary says it says, that a market convention is current — cannot be done by recomputation at all; it requires tracing the assertion to a source that exists and is the right version. The two failure modes are different, they are caught by different habits, and the second is the one that costs a negotiation. A verification record that satisfies both is short: what was checked, by whom, against what, on what date, and what was found. Anything shorter is an assertion that checking happened.

WORKED EXAMPLE**Worked example 1.3.3 — the precedent that did not exist, priced.**

1. **Setup.** Fictitious throughout. Preparing for Kestrel's term-sheet negotiation, an analyst asks a general-purpose AI tool for comparable senior margins on recent water-concession financings. The summary returned is fluent, cites five transactions and reports comparable pricing at **175 basis points**. Verified pricing on the transactions that actually exist is **235 basis points**; two of the five cited deals cannot be traced to any public record. On the strength of the 175, the sponsor anchors its position there and holds it for **nine weeks** before accepting 235. Kestrel's cost of pre-close delay is Domain 13's **USD 124,133.33 per calendar week** (KA 13.1.3, derived from Domain 5's forgone **CFADS** of 17,733.33 a day on a 30/360 basis). The facility is 42,000,000 over 12 years; $AF(0.06, 12) = 8.383844$.
2. **Formula.** Cost of the episode = weeks lost × cost of delay. Value the false benchmark appeared to offer = margin difference × facility, discounted over the tenor. Breakeven probability of the negotiation succeeding = cost ÷ value.
3. **Substitution.** $9 \times 124,133.33 \times (0.0235 - 0.0175) \times 42,000,000 = 252,000$ a year; $252,000 \times 8.383844$. Then $1,117,200 \div 2,112,729$.
4. **Result.** Cost of the nine weeks **USD 1,117,200**. Present value of the 60-basis-point prize, had it been real: **USD 2,112,729**. Breakeven success probability **52.8795 %**. Realised benefit: **nil**.
5. **Interpretation.** The unverified figure cost **1,117,200** and delivered none of the **2,112,729** it appeared to promise — and the cost was incurred not by using AI but by allowing an unsourced number to become a negotiating position. Four readings. **The breakeven is the discipline, not the loss.** Even if the 175 had been genuine, spending nine weeks to win it required better than a **52.88 %** chance of the lender conceding — which is the question a negotiating team should have asked on day one and did not, because the benchmark's apparent authority made the position feel free. Any negotiating position held on a critical path has a breakeven success probability, and computing it converts stubbornness into a decision. **The cost of verification was trivial and the loss was not.** Tracing five cited transactions to public records is an hour's work; it would have found the two that do not exist and would have changed the position before it was taken. That asymmetry — hours against a million — is the whole economic case for the verification duty, and it is why "we did not have time to check" inverts the arithmetic. **The failure is not machine-specific, which is why the control is not machine-specific.** A stale internal benchmark spreadsheet produces the identical loss, and so does a scenario grid built before the debt's shape is settled (WE 1.2.3b); what the machine changes is the fluency, and therefore the probability that an unsourced figure survives into a decision unchallenged. The control is accordingly a rule about numbers, not about tools: **no benchmark enters a negotiating position without a source line naming the transaction, the document and the date.** And **the accountability sits with a person.** No part of the 1,117,200 is recoverable from a tool vendor, and none of it would have been mitigated by the tool being an approved one (MCQ 1.3-C). Domain 16 builds the governance architecture that makes this systematic, including how to measure a tool's error rate on your own material rather than trusting a general claim; the foundational point is smaller and prior: **a number without a source is not evidence, and a professional who presents one has made an assertion in their own name.**

■ KEY TERMS — KA 1.3

Term	Meaning
Fiduciary awareness	Acting in the principal's interest with loyalty, care and confidentiality.
Conflict of interest	An interest that could bias judgment; declared, managed or declined.
Daylight test	Would full disclosure of interests leave the advice trusted?
Responsible-AI principle	AI proposes; the professional verifies, decides, remains accountable.
Verification duty	The named human's obligation to check machine output before reliance.
Breakeven discovery probability	Cost avoided by concealment ÷ loss on discovery; the arithmetic that has no upside term.
Source line	The transaction, document and date behind a benchmark; without it a figure is an assertion, not evidence.
Verifying a number vs a claim	Recomputation by an independent route; versus tracing an assertion to a source that exists.

■ SAMPLE MCQS — KA 1.3

MCQ 1.3-A [1.3.1 · Analysis] An analyst is asked to present the upside case as the base case "because the committee needs confidence". The professional response is:

- A. comply — labels are a presentation choice
- B. decline: presenting a knowingly optimistic case as the base misrepresents the forecast; offer the honest base with sensitivities instead ☒ **CORRECT**
- C. comply, but keep a private note of the true base
- D. resign immediately without discussion

Rationale: Candour about numbers is a duty, not a style (A); a private note documents the misrepresentation without preventing it (C); B both refuses the breach and offers the legitimate route to confidence — evidence. D skips the professional obligation to fix the problem before escalating personal exits.

MCQ 1.3-B [1.3.2 · Application] A bank advising a grantor on a tender also wishes to lend to one of the bidders. The minimum acceptable handling is:

- A. proceed — different departments are involved
- B. disclose the dual role to the grantor, and either obtain informed consent with effective information barriers or decline one role ☒ **CORRECT**
- C. keep the lending discussion confidential until after award
- D. advise the grantor to select that bidder

Rationale: Disclosure plus genuine separation (or declination) is the standing machinery; department labels alone are not barriers (A); concealment converts a conflict into misconduct (C); D is the conflict operating in the open.

MCQ 1.3-C [1.3.3 · Recall] Under the PCI responsible-AI principle, responsibility for an AI-drafted covenant summary used in a credit paper rests with:

- A. the AI vendor
- B. the model itself

- C. the professional who verified, signed and used it ☒ **CORRECT**
- D. nobody, if the tool was approved

Rationale: Accountability cannot be delegated to software or its supplier; tool approval governs which tools may be used, never who answers for the output.

MCQ 1.3-D [1.3.2 · Application] Disclosing a second mandate would cost a firm the 250,000 fee at risk on it. If concealed and later discovered, the firm loses 900,000 of unpaid fees, 12,750,000 of jurisdictional franchise and 400,000 of legal cost. The breakeven probability of discovery is:

- A. 1.7794 % ☒ **CORRECT**
- B. 27.7778 %
- C. 1.9608 %
- D. there is no breakeven — concealment can never pay at any probability

Rationale: $250,000/14,050,000 = 1.7794\%$ (WE 1.3.2). B divides by the 900,000 of forfeited fees alone and ignores the franchise, which is the largest term; C counts the franchise and drops the forfeited fees and legal cost. D is the answer a reader gives from the duty rather than from the arithmetic — the duty is indeed unconditional, but the calculation does have a finite breakeven, and being able to state it is what closes a commercial argument.

MCQ 1.3-E [1.3.3 · Application] A negotiating position taken on an unverified AI-reported benchmark held Kestrel's close nine weeks at a cost of delay of 124,133.33 per week. The cost of the episode was:

- A. USD 1,117,200 ☒ **CORRECT**
- B. USD 2,112,729
- C. USD 252,000
- D. USD 124,133

Rationale: $9 \times 124,133.33 = 1,117,200$ (WE 1.3.3). B is the present value of the 60-basis-point prize the false benchmark appeared to offer — the amount at stake, not the amount spent; C is one year of that margin difference undiscounted; D prices a single week.

MCQ 1.3-F [1.3.3 · Comprehension] Under the responsible-AI principle as fixed in this domain, which statement is correct?

- A. an approved tool's output may be relied on without further checking, since approval is the control
- B. verifying a number and verifying a claim are different acts: the first is independent recomputation, the second is tracing the assertion to a source that exists and is the right version ☒ **CORRECT**
- C. AI output must be disclosed to the client in every case, however immaterial
- D. confidentiality obligations do not attach to data entered into an AI tool, because no third party reads it

Rationale: 1.3.3 separates the two verification acts precisely because they fail differently and are caught by different habits. A confuses tool governance with output accountability (MCQ 1.3-C); C overstates the rule, which attaches to material use touching deliverables; D is wrong on the foundational point that entering deal data into a tool is itself a disclosure.

MCQ 1.3-G [1.3.3 · Evaluation] After an unverified benchmark cost Kestrel **1,117,200** of delay (WE 1.3.3), four controls are proposed. Which should the leader adopt first?

- A. prohibit general-purpose AI tools for market and precedent research

- B. require that no benchmark enter a negotiating position without a source line naming the transaction, the document and the date ☒ **CORRECT**
- C. procure an enterprise AI tool whose licence carries a vendor indemnity
- D. require a second analyst to review every AI-generated summary before it is circulated

Rationale: the loss arose because an unsourced number became a negotiating position, and a stale internal spreadsheet produces the identical loss — so the control that matches the failure is a rule about numbers rather than about tools (1.3.3). A is defensible and narrower than the risk: it forgoes a genuine accelerant while leaving the human failure mode untouched. C buys a commercial remedy the profession cannot rely on — on Kestrel's facts none of the 1,117,200 was a loss the licence reached, and what a particular indemnity in fact covers is a question for the contract and for counsel rather than a planning assumption — and tool approval governs which tools may be used, never who answers for the output (MCQ 1.3-C). D would probably have caught this instance and is the right second control, applied to material items; as a blanket rule it charges a second analyst against every summary, most of which never reach a negotiation.

MCQ 1.3-H [1.3.1 · Evaluation] A board asks for "one number" for the incremental cost of the limited-recourse route, having been shown **5,202,128** built on a 140-basis-point margin differential and a 40 % enforcement recovery. The most professional response is:

- A. give the 5,202,128 without qualification, since the board asked for a single figure
- B. give 5,202,128 as the base case, name the two parameters that move it most, and state the consequence — at a 50 % recovery the breakeven rises to 127.6910 % and the route cannot pay at any probability ☒ **CORRECT**
- C. decline to give a single figure, because the enforcement recovery is unknowable
- D. give the figure computed on the 50 % recovery, as the more prudent of the two

Rationale: candour about numbers means presenting a forecast with its assumptions and sensitivities, never as a certainty (1.3.1), and B does what the board asked while disclosing what would change the answer. A presents an estimate as a fact. C is a defensible instinct that fails the duty from the other side — declining to quantify leaves the judgment to whoever will. D substitutes one point estimate for another, and an unlabelled prudence misrepresents a forecast exactly as an unlabelled optimism does (MCQ 1.3-A).

■ SELF-CHECK — KA 1.3

1. State the daylight test. — Would every party, seeing the full relationship and fee map, still trust the advice as independent?
2. What three checks make AI-assisted work professionally usable? — Recomputed numbers (golden checks), traced sources, document-against-summary verification — by a named human.
3. Why does confidentiality bind AI use? — Data entering a tool is a disclosure; it must stay within approved, contracted environments.
4. Why does the concealment calculation have no upside term? — What concealment buys is bounded by the fee at risk on the hidden engagement; what it risks is the franchise, the value of every future fee.
5. What must accompany a benchmark before it enters a negotiating position? — A source line: the transaction, the document and the date — because a number without a source is an assertion made in the presenter's own name.

— Advanced topics — Domain 1

1.A.1 Where the ring-fence leaks

The ring-fence is a legal construction, not a law of nature, and a leader who treats it as absolute has bought containment they may not own. Five leaks recur, and only the first is widely discussed.

Operational disregard. The isolation that lenders relied on assumes the SPV is run as a separate undertaking. Where accounts are commingled, board minutes are not kept, affiliate contracts are not at arm's length, staff are indistinguishable from the parent's and the SPV has no independent decision-making, a court asked whether the entities should be treated as one may find that they should. The disciplines that preserve the fence are unglamorous and cheap — the SPV's own bank accounts, its own books, its own minuted board, written affiliate agreements priced as third parties would price them — and they are cheapest to install at inception and almost impossible to reconstruct in a dispute.

Cross-default in the sponsor's documents. This is the leak that most often defeats the purpose of the structure, and it is not in the project's documents at all. A parent whose own revolving facility defines an event of default to include a material subsidiary's insolvency, or whose covenants capture guarantees and contingent obligations, has converted a contained project failure into a corporate event. The finance leader's obligation is therefore to read the **parent's** debt documents before certifying that the project is ring-fenced — a step routinely omitted because it belongs to a different team.

Economic recourse without the label. A support that is not called a guarantee may still behave as one: an equity bridge drawn against the parent's lines, a debt-service-reserve letter of credit issued on the parent's credit, an availability undertaking with an uncapped indemnity buried in a schedule. The test is not what the instrument is called but **whose balance sheet answers if it is called** — the same discipline that makes the recourse sentence a three-limbed one (who, until when, capped at what).

Behavioural recourse. Lenders price the probability that a sponsor of standing will not walk away from a project bearing its name, and sophisticated sponsors know they are being priced on it. This expectation appears in no document and is not enforceable, and it is real: it is one reason the margin differential in WE 1.1.2 is narrower for a well-known sponsor than the legal recourse position alone would justify. The leader's task is to notice when a negotiation is trading on it, because a benefit taken today on an implicit promise is a support obligation the board has never approved.

The fence works in both directions. The construction that stops a failing project from reaching the parent also stops the parent from helping it without consent: distributions are locked up, additional debt is prohibited, and voluntary equity injections are often permitted only on terms lenders control. Sponsors are regularly surprised by this at the first stress event, which is the wrong time to discover it.

Counsel pointer: whether, when and on what basis a court will look through a corporate structure — and what disclosure or consolidation an applicable financial-reporting framework requires — is jurisdiction-specific, fact-specific and changes over time. These are questions for qualified counsel and the reporting adviser at structuring, not matters on which any book can state a universal position.

1.A.2 Sponsor support as a contingent claim

A recourse position on the spectrum of Fig 1.1.1 is a contingent claim, and treating it as one converts an argument about principle into a computation. Domain 5 (KA 5.2.3) records Kestrel's sponsor

support: cost-overflow undertakings of **10 % of the 60,000,000 capital cost — 6,000,000 — subscribed pro rata**. Two numbers follow immediately. The **effective recourse fraction** — support ÷ senior debt — is $6,000,000/42,000,000 = 14.2857\%$, which places the financing quantitatively on the spectrum rather than gesturally, and is the figure to put in a board paper in place of the words "limited recourse". And because lenders will price the facility differently without the support, the support has a market value the sponsors can compare against their own view of it.

WORKED EXAMPLE

Worked example 1.A.2 — what is the cost-overflow undertaking worth?

1. **Setup.** Lenders indicate that, without the 6,000,000 of cost-overflow support, Kestrel's senior margin would be **40 basis points** wider on the full 42,000,000 for the 12-year term. The support is capped at 6,000,000, uncalled unless overruns exceed contingency. $AF(0.06, 12) = 8.383844$.
2. **Formula.** Value of the support to the sponsors = present value of the margin saving it buys. Breakeven call probability $p^* = \text{that present value} \div \text{the amount at risk if called}$.
3. **Substitution.** $0.0040 \times 42,000,000 = 168,000$ a year; $168,000 \times 8.383844$. Then $1,408,485.78 \div 6,000,000$, and again against an expected draw of $6,000,000 \times 0.55$.
4. **Result.** The support buys **USD 1,408,485.78** of present-value margin saving. Against the full cap, the breakeven call probability is **23.4748 %**. Against an expected draw of 55 % of the cap if a call occurs — **3,300,000** — it is **42.6814 %**.
5. **Interpretation.** The sponsors should give the undertaking if they believe the chance of it being called is below the breakeven, and the two breakevens — **23.47 %** and **42.68 %** — are the whole lesson: **the same support, the same fee saving, and a threshold that nearly doubles depending on how the contingent claim is shaped**. A cap is not an exposure. What matters is the distribution of the draw given a call, and a sponsor negotiating the cap while ignoring the likely draw is negotiating the less important parameter. Two further readings. The margin differential is the lenders' price for the risk, and the sponsors' own probability estimate is theirs; the transaction happens because the two differ, which is the risk-transfer logic of 1.2.1 appearing on the recourse spectrum rather than in an EPC contract. And the arithmetic makes the sunset negotiable on evidence: a support that falls away at the completion test is a shorter claim than one running to final maturity, so a sponsor asked to extend the sunset can price the extension instead of arguing about it. The honest limits: 40 basis points is an indication and lenders may respond to withdrawn support by reducing gearing instead — in which case the WE 1.2.1 arithmetic applies rather than this one — and the estimate of a call probability on a single project is a judgment with no sample behind it, which is why the output a board should be given is the breakeven, against which its own judgment can be tested, and not a valuation. Counsel pointer: whether such an undertaking is enforceable as drafted, how it is characterised for accounting and disclosure, and whether it constitutes a guarantee for regulatory purposes are jurisdiction- and framework-specific matters for counsel and the reporting adviser.

1.A.3 The reviewer's foundations eye

The invariants below hold by construction. Each is one line to check, and any violated line means a defect somewhere upstream — the foundations-level analogue of Domain 3's factor-table checks and Domain 4's appraisal invariants (KA 4.A.5), and wired into this programme's golden-answer harness.

- **The recourse sentence has three limbs.** Who stands behind what, until when, capped at what. A recourse description missing a limb is incomplete, not concise; the missing limb is usually the cap.
- **Levered return.** $r_e = r_u + (D/E) \times (r_u - r_d)$. Substitute the base case back: WE 1.2.3's illustration gives $12.0\% + 2.333333 \times 6.0\% = 26.0000\%$. Where $r_u = r_d$ the two returns coincide; where $r_u < r_d$ gearing subtracts.
- **The equity cliff is debt service, not debt.** Equity cash reaches zero where project cash equals debt service — 4,200,000 interest-only, 8,349,392.06 amortising on the same 70,000,000. Any "leverage resilience" claim quoted without the repayment shape is unverifiable.
- **Debt service reconciles to the annuity factor.** $\text{debt} \div AF(r, n)$ must reproduce the instalment: $42,000,000/8.383844 = 5,009,635.23$. If it does not, the tenor, the rate or the convention in the table is not the one in the facility.
- **Coverage identity.** $DSCR \times \text{debt service} = CFADS$, and the covenant cash follows as $1.20 \times 5,009,635.23 = 6,011,562.28$. Reverse the reported ratio to test it, and expect the rounding: $1.2743 \times 5,009,635.23 = 6,383,778.17$ against a CFADS of 6,384,000, a difference of **221.83** that is entirely the ratio's four-decimal rounding — a larger residual than that means the numerator or the denominator is not the one reported. A ratio quoted without its CFADS definition is not a ratio at all (WE 1.2.2b).
- **The cash bridge's signs.** Operating cash flow = profit – Δ receivables – Δ inventory
- Δ payables. Supplier credit is a source, so an increase in payables is added while an increase in receivables is subtracted: if the two movements are in the same direction and appear in the bridge with the same sign, there is a sign error.
- **Duration is capped.** A level stream's Macaulay duration cannot exceed $(1 + r)/r$ — 13.5 years at 8 % — however long the tenor. Deferral adds exactly the deferral; escalation adds a little; a quoted duration without its discount rate is not a number.
- **Breakevens are ratios of a spend to what it avoids.** Recourse: incremental cost $\div$ exposure removed. Risk transfer: the transfer price against the cost of retention. Disclosure: cost avoided $\div$ loss on discovery. A breakeven above 100 % means the configuration cannot pay at any probability — an impossible configuration, not a worthless idea (the reading Domain 13 applies to detection rates).
- **The triangle is conjunctive.** Value, cash and risk allocation, together. Two corners is zero, not two-thirds; and the cure for a failed corner is structural.
- **Every number carries a source.** Computed figures carry their derivation; asserted figures carry the transaction, document and date. A benchmark without a source line is the presenter's own assertion, whoever or whatever drafted it.

— Industry variations — Domain 1

The foundations flex by sector mainly in who the counterparties are — and, because recourse is priced against the exposure a failure creates, each sector's counterparty shape changes the arithmetic of WE 1.1.2 as well as the vocabulary.

- **Power and water.** The offtaker is often a state utility, so sovereign credit and political risk enter the stakeholder map (Domain 11) and the effective credit ceiling on the financing is usually the sovereign's rather than the project's. The practical consequence for this domain: the enforcement recovery that drives the recourse breakeven is high in a contracted availability structure and collapses if the offtake terminates, so the recovery assumption — not the margin — is where the route decision is really decided.
- **Transport.** The "offtaker" may be the travelling public, so demand risk reshapes the whole triangle: the cash corner becomes probabilistic rather than contracted, lenders size against a stressed patronage case, and gearing falls. Lower gearing means less debt to contain, which raises the recourse breakeven of WE 1.1.2 — one reason toll-road sponsors contribute more equity and argue harder about the ramp-up forecast than availability-payment sponsors ever do.
- **Social PPPs.** The grantor's availability payment makes government the cash engine, handback condition a first-order obligation, and the concession term the binding constraint on tenor — which matters directly for WE 1.1.4, because a fixed grantor payment with no indexation carries a shorter duration than an indexed stream of the same tenor, and is correspondingly harder for liability-driven capital to use without hedging.
- **Digital infrastructure.** Corporate credit-tenants replace state offtakers, so the credit analysis becomes a corporate one and refresh cycles shorten every horizon: shorter contracted terms mean shorter debt, which mechanically steepens the amortisation and moves the equity cliff of WE 1.2.3b closer, whatever the gearing.
- **Natural resources.** The market itself is the offtaker, so hedging policy joins the foundations and the "cash" corner of the triangle is a price-distribution rather than a contract. Enforcement recovery is unusually low on a single-purpose processing asset with no contracted revenue, which makes the exposure term large and the recourse breakeven correspondingly easy to clear — one sectoral reason ring-fenced structures are reached for here despite volatile cash.

The leader's first map in any new sector: who pays, under what compulsion, and what can stop them.

— Case study — Domain 1: how Kestrel chose project finance (water)

Situation. Kestrel's sponsor group — an international water operator at **55 %**, a regional infrastructure fund at **35 %** and an industrial partner at **10 %** (the shares Domain 5, KA 5.2.3 carries) — faced a **USD 60,000,000** plant with a 25-year availability offtake. Corporate borrowing was available to the operator at attractive rates; neither of the other two could guarantee anything beyond its equity.

Analysis. Corporate route: cheapest debt, fastest close — but the operator alone carries 100 % of construction and performance risk on its balance sheet, the fund cannot participate on equal terms, and a project failure would impair the operator's whole credit. Project route: an SPV with limited-recourse debt (completion and cost-overrun support only), 70/30 gearing — **42,000,000** of senior debt at 6.0 % over 12 years against **18,000,000** of equity — pricier debt and eighteen months of structuring, but risk contained at the ring-fence, the partners aligned through one shareholders' agreement, and lender diligence pressure-testing every assumption (the discipline dividend of 1.2.1).

The leverage logic of WE 1.2.3 gave the equity story; the triangle gave the test — value (Domain 4's **+16,179,360** NPV at 8 %), cash (the availability stream priced in Domain 3), risk (allocated through the contract matrix built later in Domain 12).

The numbers on the table. WE 1.1.2 is this meeting's paper. The limited-recourse route costs **USD 5,202,128** more in present value — **2,843,128** of margin differential over the 12 years and **2,359,000** of close-cost premium — which is **12.3860 %** of the debt raised. Set against the **10,073,997** of enforcement exposure the ring-fence removes in the modelled downside, the route requires a **51.6392 %** probability of that downside to pay for itself, and nobody in the room believed anything close to it. The board approved it anyway, and the minute records why in three lines: without the ring-fence the fund cannot participate, so the operator would have had to fund all **18,000,000** of equity alone; the exposure being insured is correlated with the operator's own access to capital, so its cost in the bad state exceeds the expected shortfall used in the calculation; and the 4.60 % corporate rate consumes borrowing capacity the operator has already earmarked for two other projects.

The decision. Project finance — not because it was cheaper (it was not, by 5,202,128), but because it made the partnership possible, contained a correlated tail rather than an expected loss, and converted lender scrutiny into project quality. The recourse position was minuted in the three-limbed form: the sponsors stand behind cost overruns pro rata (55/35/10), to a cap of **6,000,000** — **14.2857 %** of senior debt — until the completion test, after which the obligation falls away. WE 1.A.2 prices that undertaking at **1,408,486** of margin saving, which the board accepted as good value against its own view of the call probability.

What the domain teaches here. The financing route is a risk and partnership decision before it is a cost decision; the cheapest debt attached to the wrong recourse shape is the expensive option. And the arithmetic's job was not to make the decision but to make its price explicit: a board that approves 5,202,128 of incremental cost knowingly, with the three reasons minuted, has governed the choice. A board told only that "project finance is the market standard" has not.

— Case study B — Domain 1: the adviser with two hats (transport tender)

Situation. A grantor's financial adviser on a toll-road tender was discovered — after preferred-bidder selection — to hold an advisory mandate for the winning consortium's lead sponsor on an unrelated deal, undisclosed. The losing bidders challenged; the award was suspended pending review.

What happened. The review found no evidence the evaluation was slanted — and it did not matter. The undisclosed relationship alone failed the daylight test: the tender was re-run with a new adviser at a cost of fourteen months and the grantor's credibility, and the adviser's firm lost its public-sector practice in the jurisdiction. A one-line disclosure at engagement, with barriers or a declined mandate, would have cost the firm the **250,000** fee at risk on the second mandate, and nothing else.

The bill. WE 1.3.2 prices this case on the firm's own estimates. Private loss on discovery: **900,000** of forfeited fees, **12,750,000** of jurisdictional franchise over five years and **400,000** of legal and indemnity cost — **USD 14,050,000**. Cost imposed on parties who had no part in the decision: **1,100,000** to re-appoint an adviser, **2,100,000** of fresh evaluation and legal work, and **5,400,000** of abortive bid costs across three bidders — **USD 8,600,000**. Total **USD 22,650,000** against a 250,000 saving, **90.6 times over**, and a breakeven discovery probability of **1.7794 %** that was never remotely achievable in a tender with losing bidders holding a reason to look.

What the domain teaches here. Conflicts are priced at discovery, not at occurrence — and the price is paid in time, trust and franchise, not fees. Independence is an asset that only disclosure can insure. Note also **where the 8,600,000 landed:** on the grantor's programme and on three bidders, none of whom chose the risk. That is what distinguishes this from a commercial gamble a firm is entitled to take with its own franchise, and it is why the duty is unconditional rather than a matter of expected value — the arithmetic corroborates the answer, it does not produce it.

— Executive perspective — Domain 1

What a project finance director cannot delegate in this domain:

- **The recourse position.** Exactly what the sponsor stands behind, until when, capped at what — the director signs this sentence personally and re-reads it before every support call.
- **The price of that position, stated.** The incremental cost of the chosen route, the exposure it removes, and the failure probability that would make the two equal (Toolkit 1.T.4) — with the recovery assumption and the discount rate on the face of the paper. A director who cannot produce those three numbers has approved a cost without seeing it; a director who treats them as the decision has mistaken an input for a judgment.
- **The three thresholds.** The project cash at which the covenant fails, at which equity cash reaches zero, and at which distributions lock up — quoted from memory, and always with the debt's repayment shape attached, because the interest-only version of any of them is roughly twice as reassuring as the truth (WE 1.2.3b).
- **The stakeholder map's honesty.** Every party's real incentive, including the uncomfortable ones, on one page the board has seen.
- **The cash question.** Asked in every meeting until it embarrasses no one: will the cash arrive, and who is exposed if it does not?
- **The conflicts register.** Kept current, disclosed early, tested against daylight — because the director's own relationships are usually the largest entries.
- **The AI accountability line.** Named humans own machine output; the director owns the culture that makes that real (Domain 16 gives the machinery; Domain 1 gives the law).

— Calculation exercises — Domain 1

Exercise 1.1 Profit 3,500,000; receivables +2,200,000; inventory +900,000; payables +600,000. Operating cash flow? Solution. $3.5 - 2.2 - 0.9 + 0.6 = \text{+USD } 1,000,000$. Common error: sign on payables (supplier credit is a source: +0.6, not -0.6; the wrong sign gives -0.2m and a false alarm).

Exercise 1.2 The WE 1.2.3 project refinances to 80 % debt (80,000,000 interest-only at 6.5 %). Rebuild the base-case levered return and the cash decline at which equity income reaches zero. Solution. Debt service $80 \times 0.065 = 5,200,000$; equity 20,000,000; base equity cash $12.0 - 5.2 = 6.8 \rightarrow 34.0\%$. Zero at project cash = 5,200,000 — a **56.6667 % decline** (from 12.0). Versus the 70/30 case: eight points more base return (34 vs 26 %, on a third less equity) bought a materially nearer cliff (-56.6667 % vs -65.0000 %). Common error: comparing levered percentages without comparing the cliffs.

Exercise 1.3 Classify: (a) parent guarantees debt until completion test, then released; (b) parent comfort letter, non-binding; (c) no support, reserves funded from cash flow. Solution. (a) limited recourse; (b) effectively non-recourse in law — comfort letters are generally not enforceable guarantees (jurisdiction-specific; counsel confirms); (c) non-recourse with structural mitigation. Common error: treating a comfort letter as recourse — lenders price it as goodwill, not security.

Exercise 1.4 A sponsor compares routes for a **30,000,000** facility over **10 years**: project finance at **5.8 %** with close costs of 2,000,000, or a corporate facility at **4.5 %** with close costs of 300,000. Cash costs are compared at 8.0 %. The modelled downside leaves **7,500,000** of debt unrecovered after enforcement. Compute the incremental cost of the limited-recourse route and the breakeven failure probability. Solution. $AF(0.058, 10) = 7.430333 \rightarrow \text{instalment } 30,000,000/7.430333 = 4,037,504.15$; $AF(0.045, 10) = 7.912718 \rightarrow 3,791,364.65$; differential **246,139.50** a year. $AF(0.08, 10) = 6.710081 \rightarrow PV \text{ **1,651,616.08** }$. Close-cost premium $2,000,000 - 300,000 = 1,700,000$. Incremental cost **USD 3,351,616.08**; $p^* = 3,351,616.08/7,500,000 = 44.6882 \%$. Common error: dividing the incremental cost by the 30,000,000 facility (11.1721 %) instead of by the exposure removed — that ratio is a cost intensity and answers a different question.

Exercise 1.5 Take Exercise 1.2's 80/20 structure (80,000,000 of senior debt at 6.5 %, 20,000,000 of equity, project cash 12,000,000) and amortise the debt over **10 years** instead of paying interest only. Recompute the base-case equity return, the **DSCR** and the cliff. Solution. $AF(0.065, 10) = 7.188830 \rightarrow \text{instalment } 80,000,000/7.188830 = 11,128,375.20$. Equity cash $12,000,000 - 11,128,375.20 = 871,624.80 \rightarrow 4.3581 \%$ on 20,000,000. $DSCR = 12,000,000/11,128,375.20 = 1.0783$. Equity cash reaches zero at project cash of 11,128,375.20 — a decline of only **7.2635 %**, against **56.6667 %** on the interest-only reading. The structure is not financeable: a 1.0783 **DSCR** would not clear any commercial coverage requirement, and a 7.26 % tolerance is inside the noise of an operating year. Common error: reporting Exercise 1.2's 34.0 % return as the structure's economics without stating the repayment shape — the same 80 % gearing is a strong story interest-only and an unbankable one amortising over ten years.

Exercise 1.6 At a discount rate of **6.0 %**, compute the Macaulay duration of a level stream of (a) 20 payments and (b) 25 payments, and state the ceiling. Solution. $D = (1 + r)/r - n/[(1 + r)^n - 1]$. Ceiling $1.06/0.06 = 17.6667 \text{ years}$. (a) $17.666667 - 20/(1.06^{20} - 1) = 8.6051 \text{ years}$. (b) $17.666667 - 25/(1.06^{25} - 1) = 10.0722 \text{ years}$. Five extra years of tenor bought **1.4671** years of duration — the marginal return on tenor falls away as the ceiling approaches. Common error: quoting a duration without its rate; at 8 % the same 25-payment stream has a duration of **9.2254 years** and a ceiling of 13.5.

Exercise 1.7 A project reports **CFADS** of **4,800,000** against debt service of **4,000,000**, on annual revenue of **9,000,000**. The covenant is a **DSCR** of **1.15×**. State the **DSCR**, the headroom in currency and in days of revenue, and the days worth 0.01× of **DSCR**. Solution. $DSCR = 4,800,000/4,000,000 = 1.2000$. Covenant cash $1.15 \times 4,000,000 = 4,600,000$; headroom **200,000**, which is $200,000/9,000,000 \times 365 = 8.1111 \text{ days}$ of revenue. A 0.01× movement in **DSCR** is $0.01 \times 4,000,000 = 40,000$ of **CFADS**, or **1.6222 days**. Common error: computing headroom against the reported ratio rather than the covenant — the distance from 1.2000 to 1.15 is 0.05×, which is 200,000, not the 800,000 by which **CFADS** exceeds debt service.

— Practitioner's toolkit — Domain 1

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 1.T.1 — Stakeholder map (one page per project)

Per party: name and role · what they optimise · contract binding them (Domain 12 reference) · cash flows to/from the SPV · veto points and consents · relationship owner. Rule: the map is board-visible and includes the uncomfortable incentives.

Toolkit 1.T.2 — Financing-route decision record

Options considered (corporate / limited recourse / non-recourse / hybrid) · recourse sentence per option (who stands behind what, until when, capped at what) · pricing and cost deltas · partnership and balance-sheet effects · risk containment analysis (triangle test per option) · decision, rationale, decision-maker, date.

Toolkit 1.T.3 — Conflicts and AI-use register

Conflicts: relationship · parties affected · disclosure date · handling (barriers/consent/ declined) · review date. AI use: tool and environment · data classification cleared · verification steps and named verifier · disclosure status. One register, one owner, standing agenda item.

Toolkit 1.T.4 — Recourse-cost worksheet (one per financing route considered)

The arithmetic of WE 1.1.2, in the order a decision paper needs it, so that the incremental cost of a recourse position is always a stated number rather than an impression.

Inputs. Facility amount · tenor · indicative all-in rate on each route · close costs itemised per route (diligence, model audit, legal, perfection, arrangement) · comparison discount rate and why · the downside scenario in one sentence · outstanding debt at the modelled failure date · enforcement recovery assumption, with its basis.

Computed. Instalment per route ($\text{amount} \div \text{AF}(r, n)$) · annual differential · PV of the differential · close-cost premium · **incremental cost** · exposure removed · **breakeven failure probability** · incremental cost as a share of debt raised · the same breakeven recomputed at ± 10 percentage points of recovery.

Judgment, recorded separately from the arithmetic. What the structure buys that the exposure term does not value — partnership capacity, correlation with the parent's own funding, borrowing capacity preserved · the form the lenders' response to any retained risk will take (margin or gearing — WE 1.2.1) · the recourse sentence in three limbs · decision, decision-maker, date.

Rule. The recovery assumption and the discount rate are named on the face of the paper. A breakeven presented without them is not reviewable.

— Exam preparation — Domain 1

The traps. Recourse classifications (comfort letter $\neq$ guarantee — Exercise 1.3) · payables sign in the cash bridge (Exercise 1.1) · levered-return arithmetic that skips debt service (MCQ 1.2-B distractor D) · reading the triangle as two-out-of-three · "sponsor" meaning equity investor in this book's project-finance chapters (terminology registry) · assigning AI accountability anywhere but the signing professional · dividing a recourse route's incremental cost by the facility rather than by the

exposure removed (Exercise 1.4) · quoting an equity return or a "cliff" without stating whether the debt amortises (WE 1.2.3b, Exercise 1.5) · treating an asset's life as its duration, or quoting a duration without its discount rate (WE 1.1.4, Exercise 1.6) · measuring covenant headroom from the reported ratio instead of from the covenant (Exercise 1.7) · comparing a risk-transfer quote with the risk's expected cost instead of with the cost of retention (WE 1.2.1) · reading a breakeven above 100 % as an arithmetic error rather than as an impossible configuration.

Reflection questions.

1. Take a project you know: write its recourse sentence in under 25 words. Who stands behind what, until when, capped at what?
2. Which corner of the bankability triangle does your current project stress most — and what structural (not cosmetic) fix would close it?
3. What in your team's current AI usage would fail the daylight test if disclosed in full — and what changes tomorrow because you asked?
4. For your current financing: what is the incremental cost of its recourse position, what exposure does that position remove, and what failure probability would make the two equal? If nobody can answer, who approved the cost?
5. State your project's three thresholds from memory — the cash level at which the covenant fails, the level at which equity cash reaches zero, and the level at which the lender's coverage test for distributions locks up. If the second is much further away than you expected, check whether your mental model has the debt amortising.

— Domain 1 summary

Project finance funds single-purpose assets against their own cash, made possible by the ring-fenced SPV and priced along the recourse spectrum; the leader's role is the financial integrity of that machine across the whole lifecycle, under one recurring question — will the cash arrive, and who is exposed if it does not? The recourse position on that spectrum is computable: Kestrel's limited-recourse route costs **5,202,128** more in present value than a corporate facility and removes **10,073,997** of enforcement exposure, so it repays itself only at a **51.6392 %** failure probability — a breakeven that falls toward **28.2224 %** with scale and is unachievable below about **13,702,087** of debt. That the number is high and the structure is still correct is the domain's most professional lesson: the arithmetic prices a mean, the sponsor is insuring a correlated tail, and the ring-fence also buys a partnership the arithmetic cannot see — which is why it is a decision input and never the decision. The discipline's logic triangulates value, cash and risk. Financing amplifies project quality but never substitutes for it, and its one genuine value channel is computable too: a risk the SPV retains is paid for in the capital structure, at **3,407,513** of present value for 4,800,000 of equity substituted for debt at a 942-basis-point spread, which is nearly four times the risk's own expected cost and the sponsor's true reservation price for transferring it. Cash, not profit, binds — a profitable quarter can be a cash crisis, and Kestrel's own first year absorbed **18.25 days** of revenue into working capital leaving **11.33 days** before a 1.20× covenant fails. Leverage multiplies returns and steepens every downside, on an identity — $r_e = r_u + (D/E) \times (r_u - r_d)$ — that also locates the crossover below which gearing subtracts, and the equity cliff belongs to the debt's shape: the same 70 % gearing tolerates a 65.00 % cash decline interest-only and **30.42 %** amortising, with the covenant engaging at **16.51 %**. Timing has its own arithmetic and its own trap: a 15-year availability stream has a Macaulay duration of **6.5945 years**, and no level stream at 8 % can exceed **13.5** at any tenor, so matching an asset's life is not matching its duration. Around the technique stands the profession: fiduciary-grade candour about numbers and limits, conflicts managed in daylight — where the breakeven discovery probability is **1.7794 %** and the calculation has no upside term —

and machine assistance governed by the suite principle, whose foundational demand is that a benchmark carry a source line before it becomes a negotiating position, the omission that cost Kestrel **1,117,200** for nothing. Domain 2 builds the accounting the cash bridge assumed; Domain 5 takes Kestrel from concept to bankability.

02

DOMAIN 2

Accounting and Financial-Statement Foundations

— Why this domain exists

Domain 1 established that **cash, not profit, is the binding constraint** — and then left an obligation outstanding: if profit is not the thing that pays debt service, why does anyone compute it, and how do you get from one to the other? This domain discharges that obligation. It builds the accrual model and what recognition actually means (KA 2.1); assembles the three statements and the articulation that binds them into one system (KA 2.2); works the treatments that decide a project's reported numbers — working capital, revenue and cost recognition, capital versus operating expenditure, provisions (KA 2.3); and closes with ratio interpretation and the interfaces between project reporting and corporate accounts (KA 2.4). A project finance leader is not an accountant, and this domain does not try to make one. It makes something more specific: a leader who can read a set of statements, find the cash inside them, and tell when an accounting choice has changed the picture without changing the economics.

Learning objectives. After this domain a candidate can: explain accrual accounting and the recognition tests that drive it, and quantify the divergence between the two bases on one period's trading; describe each of the three statements and what question it answers; **articulate** a statement set — complete a balance sheet from the movements, prove it balances, and derive the cash-flow statement by both the indirect and the direct method to the same figure; explain how working capital consumes cash, compute its effect on **CFADS** and therefore on a coverage ratio, and restate a coverage covenant as a collection-period threshold; measure progress on an over-time contract by an input and an output method and compute the recognition consequence, including the immediate charge on an onerous contract; distinguish capital from operating expenditure, quantify the profit effect while showing pre-tax cash is unaffected, and identify the one circumstance in which cash is not unaffected; measure a decommissioning provision at present value and compute its first-year accretion and depreciation; interpret a full ratio set, including the leverage identity that links return on capital to return on equity and the comparison against Domain 9's **WACC**; quantify the five meanings of "spend" and reconcile them to one identity; explain deferred tax and compute a deferred tax liability; and govern AI-assisted analysis of financial statements.

The master statements. Kestrel Water SPC — whose loan, appraisal and financing decision Domains 1, 3 and 4 built — now reports its **first full operating year**. The plant cost **USD 60,000,000** (Domain 4's **I₆**), depreciated straight-line over **25 years**. The senior loan is Domain 3's **USD 42,000,000 at 6.0 % over 12 years**, so year-one interest is **USD 2,520,000** and the annual instalment is **USD 5,009,635.23**, of which **2,489,635.23** is principal. Revenue is **USD 12,000,000**, cash operating costs **USD 4,500,000**, and tax is charged at **20 %**. The opening balance sheet at the commercial operations date is plant **60,000,000**, cash **nil**, senior debt **42,000,000** and equity **18,000,000**, with no receivables or payables. Every figure in KA 2.1–2.4 derives from these.

KNOWLEDGE AREA 2.1

The accrual model

Topics: 2.1.1 accrual versus cash accounting · 2.1.2 recognition · 2.1.3 the statements as one system.

2.1.1 Accrual versus cash accounting

Definitions. **Cash accounting** records a transaction when money moves. **Accrual accounting** records the effects of transactions when they occur, regardless of when money moves — revenue when it is earned, expenses when they are incurred. Accrual is the basis of general-purpose financial reporting because cash timing is a poor guide to performance: a project that invoices in December and collects in February did the work in December, and a cash-basis account would report a loss followed by a windfall.

The two bases answer different questions, and a finance leader needs both:

Basis	Answers	Where it governs
Accrual	Did we perform profitably in this period?	Statutory accounts, covenants defined on profit, tax
Cash	Can we pay what falls due?	Debt service, drawdowns, liquidity, CFADS (Domain 10)

The professional consequence. Accrual and cash diverge, and the divergence is information, not noise. A project reporting healthy profit while operating cash falls is telling you something precise — usually that working capital is absorbing the difference (KA 2.3.1). Domain 1's worked example was exactly this case; this domain now shows the machinery that produces it.

WORKED EXAMPLE

Worked example 2.1.1 — the same year on both bases, quarter by quarter.

- Setup.** Kestrel's first operating year, before financing and tax, so that the two bases are compared on trading alone. Revenue accrues evenly at **USD 3,000,000** a quarter and cash operating costs at **USD 1,125,000** a quarter, giving accrual **EBITDA** of **USD 1,875,000** every quarter and **USD 7,500,000** for the year. Collections lag: receivables close the four quarters at **1,200,000 · 1,050,000 · 950,000 · 900,000**, having opened at nil, and payables at **450,000 · 400,000 · 350,000 · 300,000**, also from nil. Compute **EBITDA** on a cash basis for each quarter and for the year.
- Formula.** Cash received = revenue – Δreceivables. Cash paid = cash operating cost – Δpayables. Cash-basis **EBITDA** = cash received – cash paid. Divergence = cash-basis – accrual **EBITDA**.
- Substitution.** Quarter one: **3,000,000 – 1,200,000** received; **1,125,000 – 450,000** paid. Quarter two: **3,000,000 – (1,050,000 – 1,200,000)** received; **1,125,000 – (400,000 – 450,000)** paid. Quarters three and four follow the same pattern on their own movements.
- Result.**

Quarter	Accrual EBITDA	Cash received	Cash paid	Cash-basis EBITDA	Divergence
Q1	1,875,000	1,800,000	675,000	1,125,000	(750,000)
Q2	1,875,000	3,150,000	1,175,000	1,975,000	+100,000
Q3	1,875,000	3,100,000	1,175,000	1,925,000	+50,000
Q4	1,875,000	3,050,000	1,175,000	1,875,000	nil
Year	7,500,000	11,100,000	4,200,000	6,900,000	(600,000)

1. **Interpretation.** The two bases disagree by **600,000** over the year, and the disagreement is not an opinion about performance — it is the closing net working-capital position, receivables 900,000 less payables 300,000, to the dollar. That is the invariant worth carrying out of this Knowledge Area: **cumulative accrual result minus cumulative cash result equals the net working-capital balance on the balance sheet**, which is why an unexplained divergence is always findable and always sits in a named account. Three further readings. First, the pattern of the quarters is the information, not the annual total: quarter one diverges by 750,000 because the trading cycle is being built from nothing, and quarters two to four converge as it stabilises — a start-up profile, not a deterioration, and a reader who saw only quarter one would draw the opposite conclusion. Second, **quarter four is the quarter in which the two bases agree, and it agrees for a reason that has nothing to do with performance**: receivables and payables each fell by 50,000, so the net movement was nil. Agreement between profit and cash is evidence that working capital did not move, and nothing more. Third, cash accounting is not the conservative choice it is often taken to be — it is merely **late**. It reported 600,000 less than accrual this year, and it will report 600,000 more in the year the trading cycle stops growing or unwinds, because over the life of the project the two bases must sum to the same number. The professional caution is the mirror image: a project whose cash result flatters its accrual result is often a project in decline, releasing working capital as volumes fall — the effect Domain 15 (KA 15.1.2) tracks through the operating phase, where it makes a deteriorating project report an improving covenant ratio.

2.1.2 Recognition

Definition. Recognition is recording an item in the statements as an asset, liability, income or expense. It is governed by tests, not by preference, and the tests are the substance of what accounting standards do. Described in principle (IFRS is the framework referenced throughout this book by name):

- An **asset** is a present economic resource controlled by the entity as a result of past events — recognised when it exists and can be measured reliably. Control, not legal title, is the operative idea.
- A **liability** is a present obligation to transfer an economic resource as a result of past events. A future intention is not a liability, however certain it feels.
- **Income and expenses** are recognised as the underlying changes in assets and liabilities occur, which is why revenue recognition follows performance (KA 2.3.2) rather than invoicing.

Measurement then asks at what amount — historical cost, amortised cost, fair value — and the choice materially changes reported figures without changing any cash flow. That sentence is the whole reason a finance leader reads statements sceptically: **recognition and measurement policies are part of the answer, so they must be part of the question.**

Applying the tests. The tests are worth more as a procedure than as prose, because the same four questions dispose of almost every item a project throws up. Take them in order — is there a present obligation or resource? did a past event create it? is settlement or inflow probable? can it be measured reliably? — and stop at the first "no". Six items from Kestrel's own first year, each disposed of by a different failed test:

Item	Present obligation / resource?	From a past event?	Probable?	Reliably measurable?	Treatment
Unpaid supplier invoices for delivered chemicals	yes	yes	yes	yes	Recognise a payable
Membrane replacement expected in year seven	no — no obligation to a third party yet	—	—	—	Nothing ; a future cost, disclosed only in commentary
Site-restoration obligation created by the concession	yes	yes, on construction	yes	yes, at present value	Recognise a provision (KA 2.3.4)
Offtaker's disputed abatement claim assessed as possible	yes, contingent	yes	no — possible, not probable	yes	Disclose as a contingent liability
Insurance recovery on a pump failure, insurer not yet confirmed	resource, contingent	yes	probable but not virtually certain	yes	Disclose as a contingent asset; do not recognise
Board's resolution to fund a year-two upgrade	no — an intention	—	—	—	Nothing

Two points the table makes better than a paragraph can. The **asymmetry is deliberate**: the contingent liability is disclosed on probable while the contingent asset is recognised only on virtually certain, so an entity in an identical factual position on both sides of a dispute reports the downside earlier than the upside. And **the failing test names the argument**: when two professionals disagree about an item, they are almost never disagreeing about all four questions, and identifying which one is contested — usually probability, occasionally measurement — converts an impasse into a specific evidential question. Which framework applies, and how these tests are expressed within it, is a matter for the entity's finance function and auditors; the procedure is transferable, the conclusion is not.

2.1.3 The statements as one system

The three primary statements are not three reports; they are three views of one set of facts, locked together by identities:

Assets = Liabilities + Equity (the balance sheet identity)
 Closing equity = Opening equity + Profit – Distributions (+ capital contributed)
 Closing cash = Opening cash + Operating + Investing + Financing cash flows

Because they share one underlying record, a change in one propagates to all three — the property called **articulation**, demonstrated arithmetically in KA 2.2.4. Articulation is the reader's single most powerful tool: a statement set that does not articulate contains an error or an omission, and finding where it fails localises the problem immediately.

AI in this KA

Statement analysis is a genuine AI strength — extracting line items, restating across periods, flagging unusual movements — and it has a specific, dangerous blind spot: a model reads the numbers fluently and the policies not at all. Two projects with identical economics and different capitalisation or revenue-recognition policies produce different statements, and an assistant comparing them will report a difference in performance that does not exist. The governed habit: ask what policy produced each figure before comparing any two entities or periods, and verify extracted line items against the source statement. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 2.1

Term	Meaning
Accrual basis	Recognising the effects of transactions when they occur, not when cash moves.
Recognition	Recording an item in the statements, subject to definition and measurement tests.
Measurement	The amount at which a recognised item is carried (cost, amortised cost, fair value).
Articulation	The locking of the three statements to one underlying record via identities.
Accounting policy	The permitted choice that shapes reported figures without changing cash.

■ SAMPLE MCQS — KA 2.1

MCQ 2.1-A [2.1.1 · Analysis] A project reports rising profit and falling operating cash flow over three quarters, with no change in accounting policy. The most likely explanation is:

- A. the profit figures must be erroneous
- B. working capital is absorbing cash — receivables and/or inventory are growing faster than payables ☒ **CORRECT**
- C. depreciation has increased
- D. the two measures are unrelated, so no explanation is needed

Rationale: Accrual profit and operating cash diverge principally through working-capital movements (KA 2.3.1). C would raise operating cash relative to profit (a non-cash charge added back), and D denies the articulation the statements are built on.

MCQ 2.1-B [2.1.2 · Application] A sponsor board has firmly resolved to fund a plant upgrade next year. At this year end this is:

- A. a liability, because the decision is certain
- B. not a liability — there is no present obligation from a past event; an intention is not an obligation ☒ **CORRECT**
- C. a provision, because the amount is estimable
- D. a contingent asset

Rationale: Liability recognition requires a present obligation arising from a past event (2.1.2). Certainty of intent is irrelevant; a provision (C) still requires an obligation to exist, and D inverts the direction entirely.

MCQ 2.1-C [2.1.3 · Recall] A statement set where the cash-flow statement's closing cash does not equal the balance sheet's cash indicates:

- A. a normal difference in presentation
- B. an error or omission — the statements articulate to one record, so they must reconcile
✓ CORRECT
- C. the use of accrual rather than cash accounting
- D. a foreign-currency effect that requires no action

Rationale: Articulation is an identity (2.1.3). FX and presentation differences are disclosed and reconciled, not left unbalanced — an unreconciled set is a defect, and locating the break is the reader's fastest diagnostic.

MCQ 2.1-D [2.1.1 · Analysis] Over its first year a project reports accrual EBITDA of 7,500,000 and cash-basis EBITDA of 6,900,000. Receivables closed at 900,000 and payables at 300,000, both having opened at nil. The 600,000 difference is best described as:

- A. an error, since the two measures should agree over a full year
- B. the closing net working-capital balance — the divergence is the balance sheet, and it reverses when the trading cycle stops growing ✓ CORRECT
- C. evidence that the accrual figures are optimistic
- D. a timing difference that will never reverse

Rationale: Cumulative accrual result less cumulative cash result equals net working capital (2.1.1), so the divergence is locatable in named accounts and is a growth profile rather than a quality-of-earnings verdict. A denies the identity; C reads a timing effect as a judgment; D is wrong because the balances unwind — cash accounting is late, not conservative.

MCQ 2.1-E [2.1.2 · Evaluation] An insurer has indicated it will probably meet a claim, and the amount is reliably estimable. The entity also faces a counterclaim it assesses as probable and estimable. The correct treatment of the pair is:

- A. recognise both, since both are probable and estimable
- B. recognise neither, since both are disputed
- C. recognise the counterclaim as a provision; disclose the insurance recovery, which requires virtual certainty to be recognised ✓ CORRECT
- D. net the two and recognise the difference

Rationale: The recognition thresholds are deliberately asymmetric — probable for an obligation, virtually certain for a contingent asset (2.1.2) — so an entity in the same factual position on both sides reports the downside first. A applies one threshold to both; B ignores that the counterclaim passes its tests; D offsets two items that arise from different events, which the recognition tests are applied to individually.

MCQ 2.1-F [2.1.1 · Comprehension] Kestrel's first year reports accrual EBITDA of 7,500,000 and cash-basis EBITDA of 6,900,000, and 2.1.1 concludes that cash accounting is "not the conservative choice — merely late". Which statement restates that claim correctly?

- A. the cash basis reports a lower result in every period, which is why it is the prudent basis for a lender

- B. the 600,000 the cash basis has not yet reported is the closing net working-capital balance, and it is reported in whichever later period the trading cycle stops growing or unwinds — over the project's life the two bases sum to the same figure ✓ CORRECT
- C. the cash basis is late because customers pay in arrears, so the 600,000 difference is permanent
- D. the two bases differ because accrual accounting charges depreciation, which a cash basis cannot recognise

Rationale: the cumulative gap is a balance-sheet position — receivables 900,000 less payables 300,000 — and balance-sheet positions unwind, so what separates the bases is timing rather than prudence (2.1.1). A is wrong in both directions: a project releasing working capital reports **more** on a cash basis, which is how a declining project flatters its cash result (Domain 15, KA 15.1.2). C treats a reversing balance as permanent. D names a real difference that is irrelevant here, because the comparison is struck at **EBITDA**, above any depreciation charge.

■ SELF-CHECK — KA 2.1

1. Which basis governs debt service, and which governs covenants defined on profit? — Cash for debt service; accrual for profit-defined covenants. A leader needs both.
2. Why is an intention never a liability? — Recognition requires a present obligation arising from a past event.
3. What does a failure to articulate tell you? — That there is an error or omission, and where the break occurs localises it.
4. What does the cumulative gap between accrual and cash results equal? — The net working-capital balance: 900,000 receivables less 300,000 payables = 600,000.
5. When profit and cash agree in a period, what has that told you? — That working capital did not move. It is not evidence of quality either way.

KNOWLEDGE AREA 2.2

The three statements and their articulation

Topics: 2.2.1 the income statement · 2.2.2 the balance sheet · 2.2.3 the cash-flow statement · 2.2.4 articulation demonstrated.

2.2.1 The income statement

What it answers: did the entity perform profitably in the period? Its project-finance-relevant structure runs down from revenue through the layers a lender reads:

WORKED EXAMPLE**Worked example 2.2.1 — Kestrel's first operating year.**

1. **Setup.** Revenue USD 12,000,000; cash operating costs USD 4,500,000; plant USD 60,000,000 depreciated straight-line over 25 years; senior interest USD 2,520,000 (Domain 3's year-one figure); tax 20 %.
2. **Formula.** $\text{EBITDA} = \text{revenue} - \text{cash operating costs}$; $\text{EBIT} = \text{EBITDA} - \text{depreciation}$; profit before tax = $\text{EBIT} - \text{interest}$; net income = $\text{PBT} - \text{tax}$. Depreciation = $(\text{cost} - \text{residual}) / \text{useful life}$.
3. **Substitution.** $\text{EBITDA} = 12,000,000 - 4,500,000$; depreciation = $60,000,000 / 25$; $\text{EBIT} = 7,500,000 - 2,400,000$; $\text{PBT} = 5,100,000 - 2,520,000$; tax = $2,580,000 \times 0.20$.
4. **Result.**

Line	USD
Revenue	12,000,000
Cash operating costs	(4,500,000)
EBITDA	7,500,000
Depreciation	(2,400,000)
EBIT	5,100,000
Interest	(2,520,000)
Profit before tax	2,580,000
Tax at 20 %	(516,000)
Net income	2,064,000

1. **Interpretation.** Four layers, four different questions. **EBITDA** approximates the cash the operation generates before financing, tax and the accounting for past capital spend — which is why lenders start there (Domain 10). **EBIT** charges the asset's consumption, so it measures operating performance including capital intensity. **PBT** is after the cost of the capital structure. **Net income** is the shareholders' accounting return — and note it is USD 2,064,000 while **EBITDA** is USD 7,500,000: on a capital-intensive, levered project the gap between the two is mostly depreciation and interest, and confusing them is the commonest error in project financial conversation. The margins make the shape explicit: **62.50 % EBITDA margin, 17.20 % net margin** — the 45.30 points between them are the price of the asset and the loan, and they are almost entirely fixed, which is what makes the statement so revenue-sensitive.

That sensitivity is computable and it is the most useful thing this statement will tell a leader. Because every line below revenue except tax is fixed in the short run, a **1 % revenue fall (120,000) costs 96,000 of net income after tax relief — 4.6512 % of it**. Net income is therefore **4.6512 times** as revenue-elastic as revenue itself, and any conversation that treats a "small" revenue miss as a small profit miss is out by that factor. Push the same arithmetic to its two breakevens and the domain's central claim falls out as a comparison:

- **Profit breakeven.** Net income reaches nil when **EBITDA** covers depreciation and interest: $2,400,000 + 2,520,000 = 4,920,000$, so revenue of **USD 9,420,000 — a 21.50 % fall**.

- **Cash breakeven.** DSCR reaches 1.00 when CFADS equals debt service. With $CFADS = 0.8 \times EBITDA + 984,000 - 600,000$, that needs EBITDA of **USD 5,782,044.04** and revenue of **USD 10,282,044.04** — a **14.32 %** fall.

The cash constraint binds first, and by a wide margin: 14.32 % against 21.50 %. A project can be comfortably profitable and unable to pay, which is Domain 1's thesis restated as two numbers on one income statement, and it is the reason every covenant that matters in Domain 10 is struck on cash. Two cautions before the figures are used. The cash breakeven above holds depreciation, interest, tax rate and the working-capital movement constant while revenue moves, which is a first-order approximation and not a forecast: in practice receivables fall with revenue, so the true cash breakeven sits a little further out (Domain 15, KA 15.1.2 measures that feedback). And the 20 % tax charge is a charge on positive profit — below the profit breakeven the relationship bends, because relief for losses is jurisdiction-specific and may be deferred, capped or unavailable (KA 2.A.1; Domain 6, KA 6.2.3). A reviewer should check which of the two breakevens a management pack is quoting, because they are seven revenue points apart and only one of them causes a default.

2.2.2 The balance sheet

What it answers: what does the entity own and owe at a point in time? For an SPV the structure is unusually clean — one asset of consequence and one financing structure — which makes it the ideal place to see that **a balance sheet is not assembled, it is derived:** given the opening position and the period's movements, every closing line including cash is determined, and the balance is a proof rather than a presentation.

WORKED EXAMPLE

Worked example 2.2.2 — completing Kestrel's balance sheet, and proving it.

1. **Setup.** Opening position at the commercial operations date: plant **60,000,000**, cash **nil**, senior debt **42,000,000**, equity **18,000,000**, no receivables or payables. Year-one movements from Worked example 2.2.1 and the schedule in Domain 3: depreciation **2,400,000**, net income **2,064,000**, receivables up **900,000**, payables up **300,000**, principal repaid **2,489,635.23**, no distributions and no further contributions. Derive every closing line, including cash, and prove the sheet balances.
2. **Formula.** Plant, net = cost – accumulated depreciation. Closing debt = opening debt – principal repaid. Closing equity = opening equity + net income – distributions + contributions. Closing cash = operating cash flow – capex – principal – distributions. Then test $assets = liabilities + equity$.
3. **Substitution.** Plant $60,000,000 - 2,400,000$; debt $42,000,000 - 2,489,635.23$; equity $18,000,000 + 2,064,000 - 0 + 0$; cash $3,864,000 - 0 - 2,489,635.23 - 0$.
4. **Result.**

Assets	USD	Liabilities and equity	USD
Plant, net	57,600,000.00	Payables	300,000.00
Receivables	900,000.00	Senior debt	39,510,364.77
Cash	1,374,364.77	Equity (18,000,000 + 2,064,000)	20,064,000.00
Total assets	59,874,364.77	Total	59,874,364.77

The sheet balances to the cent, with **nothing plugged**: cash was derived from the cash-flow statement and equity from the profit, and the equality is the consequence.

1. **Interpretation.** The single most valuable thing in the table is the cash figure, because it arrives twice by different routes and the two routes are an identity worth memorising:

Operating cash flow – principal repaid = 3,864,000.00 – 2,489,635.23 = 1,374,364.77 CFADS – total debt service = 6,384,000.00 – 5,009,635.23 = 1,374,364.77

The two are equal because CFADS exceeds operating cash flow by exactly the interest paid, and debt service exceeds principal by exactly the same interest — so the interest cancels. That is the arithmetic bridge between the accountant's statement and the lender's ratio, and it is why Domain 9 records **1,374,364.77** as Kestrel's annual distributable cash at 70 % gearing (KA 9.1.4) while this domain records it as the closing cash balance: they are one number seen from two disciplines. Three consequences follow, and each is a reviewer's check.

The cash balance is a claim already spoken for. Domain 6 (KA 6.2.2) takes the same year forward with the facility's reserve requirement in place and splits this exact balance into a **1,252,408.81** debt-service-reserve instalment and a **121,955.96** distribution — and **1,252,408.81 + 121,955.96 = 1,374,364.77**, to the cent. A leader reading this balance sheet as free liquidity would be reading 1,374,364.77 of cash of which **91.1264 %** is contractually restricted before anyone decides anything, leaving **8.8736 %** genuinely at the sponsors' disposal.

The asset is consumed on paper while it produces cash. Depreciation reduced the carrying amount by 2,400,000 with no payment, so the balance sheet reports the asset getting smaller in the year the project first performed. Over the 12-year loan the plant's carrying amount falls to **31,200,000** while the debt falls to nil — the two lines converge for unrelated reasons, and any covenant expressed as a ratio of debt to book asset value moves every year without a transaction. In a regulated utility a second asset value runs beside this one on its own profile (see the industry variations at the end of this domain).

The debt balance falls by principal only. Of the 5,009,635.23 instalment, 2,520,000 is interest (an expense) and **2,489,635.23** is principal (a balance-sheet movement, not an expense) — exactly Domain 3's schedule. That split is why debt service never appears as a single line in the income statement, and why a reader who looks only at profit cannot see whether the loan is being repaid. It also explains a figure that surprises boards: equity rose by 2,064,000 while capital employed **fell** by 425,635.23, because the principal repaid exceeded the retained profit. Growth in equity and growth in the business are different things, and on an amortising project financing they routinely point in opposite directions.

2.2.3 The cash-flow statement

What it answers: where did cash come from and go? Three sections: **operating** (the trading cycle), **investing** (asset purchases and disposals), **financing** (debt drawn and repaid, equity contributed, distributions paid). The indirect method — the one a project leader will usually meet — starts from profit and undoes the accruals:

```
Net income
+ non-cash charges (depreciation, amortisation, provisions)
- increases in receivables and inventory      (cash absorbed)
+ increases in payables                      (cash released)
= operating cash flow
```

The **direct method** instead reports the gross cash flows themselves — collected from customers, paid to suppliers, paid in interest, paid in tax. It is rarer in published accounts and far more useful in a project, because a lender's questions are about the gross flows and the indirect method conceals every one of them behind a net movement.

WORKED EXAMPLE

Worked example 2.2.3 — the same operating cash flow, built the other way.

1. **Setup.** Kestrel's year one as above: revenue 12,000,000, cash operating costs 4,500,000, receivables up 900,000, payables up 300,000, interest paid 2,520,000, tax paid 516,000. Depreciation of 2,400,000 does not appear at all, because no cash moved. Build operating cash flow directly.
2. **Formula.** Cash collected from customers = revenue – Δ receivables. Cash paid to suppliers and employees = cash operating costs – Δ payables. Operating cash flow = collections – payments – interest paid – tax paid.
3. **Substitution.** $12,000,000 - 900,000$; $4,500,000 - 300,000$; then $11,100,000 - 4,200,000 - 2,520,000 - 516,000$.
4. **Result.**

Direct method	USD
Cash collected from customers	11,100,000
Cash paid to suppliers and employees	(4,200,000)
Interest paid	(2,520,000)
Tax paid	(516,000)
Operating cash flow	3,864,000

Identical to the indirect method's **3,864,000** (KA 2.2.4). Two methods, one number, no depreciation anywhere in sight.

1. **Interpretation.** The two methods cannot disagree — they are the same account read from opposite ends — so the value of building both is diagnostic, and it is considerable. **The direct method surfaces a collection ratio the indirect method hides:** Kestrel collected **92.50 %** of the revenue it recognised (11,100,000 of 12,000,000). That single percentage is the operational question behind the whole of KA 2.3.1, and it is invisible in a statement whose only working-capital line is a net 600,000. It also gives the days figures directly — **27.3750 days** of sales outstanding and **24.3333 days** of payables on cash costs, at a 365-day convention — which is what makes a covenant translatable into an instruction to a collections team (KA 2.3.1B).

The more consequential point is about the **interest line**, and it is where careless comparison does real damage. Kestrel's presentation classifies interest paid within operating activities. Had it been classified within financing — a presentation choice permitted in some framework applications and mandatory in none universally — operating cash flow would have been $3,864,000 + 2,520,000 = \mathbf{6,384,000}$, which is precisely the documented **CFADS** figure. Nothing about the project changed; a single classification decision moved reported operating cash flow by **65.2174 %** of itself. Two professional consequences. **Never compare operating cash flow across two entities without checking where each puts interest** — on these figures the classification alone is worth 65.2174 % of the reported number, so it can exceed the difference being analysed without any difference in trading existing at all. And **the identity CFADS = operating cash flow + interest paid holds only**

on the operating-classification presentation; Domain 6 (KA 6.2.2) uses it as a model check, and a reviewer applying it to a financing-classified statement would double-count the interest and overstate **CFADS** by 2,520,000.

2.2.4 Articulation demonstrated

WORKED EXAMPLE

Worked example 2.2.4 — from profit to cash, and proving it ties.

1. **Setup.** Kestrel's income statement above, plus the balance-sheet movements: receivables rose **USD 900,000**, payables rose **USD 300,000**. Derive operating cash flow.
2. **Formula.** Operating cash = net income + depreciation – Δ receivables + Δ payables.
3. **Substitution.** $2,064,000 + 2,400,000 - 900,000 + 300,000$.
4. **Result. Operating cash flow USD 3,864,000** — against net income of USD 2,064,000. The reconciliation: depreciation adds back **+2,400,000** (a charge that moved no cash), working capital absorbs **–600,000** net.
5. **Interpretation.** Read the bridge in both directions. Profit understates the period's cash by the depreciation of an asset paid for years ago; working capital takes back 600,000 of it to fund growth in the trading cycle. Both facts are invisible in the income statement and decisive for a lender. Note also what operating cash flow is **not**: it is before debt principal (a financing flow) and before capex — so a project can show positive operating cash and still fail to cover its obligations. Domain 10's coverage ratios exist precisely to test the thing this statement does not.

The ratio between the two ends of the bridge is worth naming and worth distrusting. Kestrel's **cash conversion — operating cash flow ÷ net income — is 1.8721**, and a reader trained to regard a figure above 1.0 as healthy would file that as reassuring. It is not a quality signal at all: it is arithmetically guaranteed to exceed 1.0 on any capital-intensive project whose depreciation charge (2,400,000) exceeds its working-capital absorption (600,000), and it would stay above 1.0 in a year of collapsing collections. **A high cash conversion on an infrastructure asset measures capital intensity, not performance.** The diagnostic content is in the two components separately — the non-cash add-back, which is fixed by an accounting policy set years ago, and the working-capital movement, which is this period's operational news.

Three checks a reviewer should run on any such bridge before relying on it. **Tie the add-back to the income statement:** depreciation in the cash-flow statement must equal the income-statement charge to the dollar, and a difference means either an impairment, a disposal or an error, all three of which need explaining. **Tie the working-capital lines to the balance-sheet deltas:** the –900,000 and +300,000 must reconcile to the movement in the receivable and payable accounts, and a "net working capital" single line that cannot be decomposed is the commonest place a modelling plug hides (Domain 6, KA 6.4.1). And **check the sign convention on payables**, which is the error the exercises at the end of this domain are built to catch: an increase in payables is supplier credit and therefore a cash source, and reversing it turns the working-capital absorption from 600,000 into 1,200,000, taking **CFADS** to 5,784,000 and the reported **DSCR** from **1.2743 to 1.1546** — a covenant breach and a lock-up, on a project whose trading did not change. One sign is worth **0.1198** of coverage.

Finally, one line further on, the bridge continues past operating cash flow to the only figure a sponsor ultimately cares about: $3,864,000 - 2,489,635.23 = 1,374,364.77$ of cash left after the loan has been

served (KA 2.2.2). Everything Domain 15 does with waterfalls and lock-ups happens inside that number.



Fig 2.2.1 — Kestrel's accrual-to-cash bridge

AI in this KA

Where it earns its place. The articulation checks of this Knowledge Area are ideal machine work, because each is a stated identity with a numeric answer — the eight invariants listed in 2.A.3 and checklisted in Toolkit 2.T.3. An assistant can run all of them across every period of a statement set in seconds and report where the first break occurs, which is precisely the diagnostic KA 2.1.3 says localises a problem — and it is tedious enough that humans skip it.

Where it fails, specifically. It cannot tell you whether the right number balanced. Two failures recur. A model will happily reconcile a statement set in which interest paid is classified in financing and then apply the $CFADS = \text{operating cash flow} + \text{interest}$ identity anyway, overstating $CFADS$ by the whole interest charge (2.2.3) — the identity is presentation-dependent and the presentation is not detectable from the arithmetic. And where a working-capital movement is presented as a single net line, an assistant asked to reconcile it will often accept the net figure as evidence rather than reporting that the decomposition is missing, which is where a plug hides (Domain 6, KA 6.4.1). Require the check to name its inputs, and check the classification yourself. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 2.2

Term	Meaning
EBITDA	Earnings before interest, tax, depreciation and amortisation.
EBIT	Operating profit after depreciation; performance including capital consumption.
Depreciation	(cost – residual)/useful life; a non-cash charge for asset consumption.
Indirect method	Deriving operating cash flow from profit by undoing accruals.
Direct method	Reporting the gross operating cash flows: collections, supplier payments, interest, tax.
Working-capital movement	Change in receivables, inventory and payables; absorbs or releases cash.
Principal versus interest	Principal is a balance-sheet movement; only interest is an expense.
Cash conversion	Operating cash flow ÷ net income; on a capital-intensive asset it measures capital intensity, not quality.
Capital employed	Debt plus equity; the base a return on capital is measured against.

■ SAMPLE MCQS — KA 2.2

MCQ 2.2-A [2.2.1 · Application] Revenue 12,000,000; cash operating costs 4,500,000; depreciation 2,400,000; interest 2,520,000; tax 20 %. Net income is:

- A. USD 2,580,000
- B. USD 2,064,000 ✓ **CORRECT**
- C. USD 4,080,000
- D. USD 7,500,000

Rationale: $PBT\ 2,580,000 \times (1 - 0.20) = 2,064,000$. A is PBT before tax; C taxes EBIT instead of PBT; D is EBITDA.

MCQ 2.2-B [2.2.4 · Application] Net income 2,064,000; depreciation 2,400,000; receivables +900,000; payables +300,000. Operating cash flow is:

- A. USD 4,464,000
- B. USD 3,864,000 ✓ **CORRECT**
- C. USD 3,264,000
- D. USD 2,064,000

Rationale: $2,064,000 + 2,400,000 - 900,000 + 300,000 = 3,864,000$. A omits the working-capital movements; C subtracts the payables increase instead of adding it (supplier credit is a cash source); D stops at profit.

MCQ 2.2-C [2.2.2 · Analysis] Kestrel's annual instalment is 5,009,635, of which 2,520,000 is interest. The income statement expense and the balance-sheet effect are:

- A. expense 5,009,635; debt falls by 5,009,635
- B. expense 2,520,000; debt falls by 2,489,635 ✓ **CORRECT**
- C. expense 2,489,635; debt falls by 2,520,000
- D. expense 5,009,635; debt unchanged

Rationale: Only interest is an expense; principal is a balance-sheet movement. A expenses the whole instalment (the classic error), C reverses the two components, D ignores repayment.

MCQ 2.2-D [2.2.3 · Recall] Repayment of debt principal appears in the cash-flow statement under:

- A. operating activities
- B. investing activities
- C. financing activities ☒ **CORRECT**
- D. it does not appear, being a balance-sheet movement

Rationale: Principal flows are financing. D confuses the income statement's silence on principal with absence from the cash-flow statement, where every cash movement appears.

MCQ 2.2-E [2.2.2 · Application] Opening cash nil; operating cash flow 3,864,000; principal repaid 2,489,635.23; no capex, distributions or contributions. Plant is 57,600,000 net, receivables 900,000, payables 300,000 and closing debt 39,510,364.77. Closing cash and total assets are:

- A. cash 1,374,364.77; total assets 59,874,364.77 ☒ **CORRECT**
- B. cash 3,864,000.00; total assets 62,364,000.00
- C. cash (1,145,635.23); total assets 57,354,364.77
- D. cash 1,374,364.77; total assets 58,500,000.00

Rationale: Cash = 3,864,000 – 2,489,635.23, and total assets are the three lines summed. B omits the principal repayment (treating debt service as invisible to cash); C deducts the whole 5,009,635.23 instalment, double-counting the interest already inside operating cash flow; D omits the cash balance from the asset total.

MCQ 2.2-F [2.2.3 · Evaluation] Two otherwise identical projects report operating cash flow of 3,864,000 and 6,384,000. The second classifies interest paid within financing activities. The soundest conclusion is:

- A. the second project generates 2,520,000 more cash from operations
- B. the figures are not comparable: the 2,520,000 difference is a classification of interest, and restating one presentation makes them identical ☒ **CORRECT**
- C. the second project must have lower interest costs
- D. the first project has a working-capital problem

Rationale: The classification of interest paid moves reported operating cash flow by the whole interest figure without changing any cash (2.2.3). A and C read a presentation choice as an economic difference — the specific error the **CFADS** identity is exposed to; D invents a cause the statements do not support.

MCQ 2.2-G [2.2.1 · Evaluation] A management pack reports Kestrel's 1.20× **DSCR** covenant headroom correctly — a 3.8796 % revenue fall — and then adds that "the project breaks even at a 21.50 % fall in revenue". Each statement below is true on Kestrel's first-year figures. Which is the more decisive objection to that second sentence?

- A. the profit breakeven sits at revenue of 9,420,000 — a 21.50 % fall — which is the figure quoted
- B. the cash breakeven, where **DSCR** reaches 1.00, sits at revenue of 10,282,044 — a 14.32 % fall — so it binds **7.18** revenue points earlier, and it, not the profit breakeven, is the point at which the facility stops being paid ☒ **CORRECT**
- C. net income is 4.6512 times as revenue-elastic as revenue itself, so profit falls 4.6512 % for every 1 % of revenue lost

- D. the sentence is harmless, because the reader has already been given the covenant test, which bites long before either breakeven

Rationale: both breakevens are correctly computed, and only one of them is the point at which cash stops covering debt service, so the pack has quoted the slacker of the two and told the reader the project is 21.5 points from trouble when on its own chosen measure it is 14.3 (2.2.1). A restates the pack's own figure and objects to nothing. C is true and is a sensitivity rather than a threshold — it says how fast profit moves, not where anything breaks. D is the strongest of the wrong answers and is a good point aimed at the wrong target: the covenant does bite first, at 3.8796 % (KA 2.4.2), and a correctly stated covenant elsewhere in the pack does not license a misstated breakeven beside it — a breakeven is not invalidated by the existence of a tighter test above it, nor excused by one.

MCQ 2.2-H [2.2.4 · Comprehension] Kestrel's cash conversion — operating cash flow ÷ net income — is 1.8721. Which statement shows the ratio has been understood?

- A. collection is efficient: the project turns each unit of profit into 1.87 units of cash
- B. a figure above 1.0 is close to guaranteed on a capital-intensive asset, because depreciation of 2,400,000 exceeds the working-capital absorption of 600,000; the diagnostic content is in those two components separately, not in the ratio ✓ CORRECT
- C. the ratio exceeds 1.0 because the project is profitable, and would fall below 1.0 in a loss-making year
- D. the ratio measures earnings quality, and 1.87 indicates a low risk of revenue being recognised early

Rationale: the numerator adds back a charge fixed by a depreciation policy set years earlier and deducts this period's working-capital movement, so the ratio measures capital intensity and would stay above 1.0 through a year of collapsing collections (2.2.4). A and D read a structural arithmetic property as an operational or a quality signal — the specific misreading the passage exists to correct. C offers a mechanism the arithmetic does not have: the add-back does not depend on profitability at all.

■ SELF-CHECK — KA 2.2

1. Why is *EBITDA* USD 7,500,000 while net income is USD 2,064,000? — Depreciation, interest and tax lie between them; on a capital-intensive levered project that gap is structural.
2. State the accrual-to-cash bridge for Kestrel. — $2,064,000 + 2,400,000 \text{ depreciation} - 900,000 \text{ receivables} + 300,000 \text{ payables} = 3,864,000$.
3. What obligations does operating cash flow not cover? — Debt principal and capex; hence Domain 10's coverage ratios.
4. Derive Kestrel's closing cash two ways. — Operating cash flow 3,864,000 less principal 2,489,635.23, or *CFADS* 6,384,000 less debt service 5,009,635.23; both give 1,374,364.77 because the interest cancels.
5. Which two revenue breakevens does the income statement carry, and which binds? — Profit breakeven at revenue 9,420,000 (−21.50 %) and cash breakeven at 10,282,044.04 (−14.32 %); cash binds first.
6. Why is a cash conversion ratio above 1.0 not reassuring on its own? — Because depreciation exceeding the working-capital movement guarantees it on a capital-intensive asset.

KNOWLEDGE AREA 2.3

Project-relevant treatments

Topics: 2.3.1 working capital · 2.3.2 revenue and cost recognition · 2.3.3 capital versus operating expenditure · 2.3.4 provisions and contingencies.

2.3.1 Working capital and why lenders care

Definition. Working capital is the cash tied up in the trading cycle — receivables plus inventory less payables. Growth in it **consumes** cash; reduction **releases** it. For a project, the dominant driver is the gap between doing work and being paid for it, which is why payment terms are a financing decision (Domain 1's cash discipline; Domain 14's drawdowns).

WORKED EXAMPLE

Worked example 2.3.1 — what working capital does to a coverage ratio.

1. **Setup.** Kestrel's **EBITDA** USD 7,500,000; tax USD 516,000; the net working-capital increase of USD 600,000 from KA 2.2.4. Annual debt service USD 5,009,635 (Domain 3). Compute the **DSCR** — Domain 10's central ratio — first ignoring working capital, then including it.
2. **Formula.** $CFADS = EBITDA - \text{tax} - \Delta \text{working capital}$; $DSCR = CFADS \div \text{debt service}$.
3. **Substitution.** Ignoring WC: $7,500,000 - 516,000 = 6,984,000$; $\div 5,009,635$. Including WC: $6,984,000 - 600,000 = 6,384,000$; $\div 5,009,635$.
4. **Result.** **DSCR 1.39** ignoring working capital; **1.27** including it — a fall of **0.12** from one balance-sheet movement.
5. **Interpretation.** A fall of **0.12 in the coverage ratio** may decide whether a covenant holds (typical senior covenants sit at 1.20–1.30, so this project is comfortable at 1.39 and much closer to the line at 1.27). The lesson is definitional rather than arithmetical: **CFADS is a defined term in the finance documents, and whether it is struck before or after working-capital movements changes the ratio it produces.** A leader who quotes a **DSCR** without knowing its **CFADS** definition is quoting an opinion. Domain 10 builds the full machinery; Domain 13's model audit checks that the model implements the documented definition.

Two refinements make the point operational rather than merely cautionary. First, the sensitivity is linear and easy to carry: because debt service is fixed at 5,009,635.23, **every 50,096.35 of working-capital absorption costs 0.01 of DSCR** — so the ratio can be managed in the same units as a collections target. Second, the direction of the definitional choice is not neutral between the parties. Excluding working capital produces the higher ratio in a growing project and the lower ratio in a shrinking one, which means a sponsor arguing for exclusion at financial close is arguing for a definition that will turn against it in the first year of decline. The definitional fight is therefore not "which number is bigger" but **which number is stable**, and stability is what a lender is buying.

WORKED EXAMPLE**Worked example 2.3.1B — the covenant restated as a collection period.**

- Setup.** The same year. Kestrel's **CFADS** before working capital is **6,984,000** and debt service **5,009,635.23**. Payables are held at **300,000**. The facility carries a **1.20×** financial covenant, a **1.25×** distribution condition and a **1.15×** lock-up (Domain 10, KA 10.4). Revenue is 12,000,000 and receivables opened at nil, so closing receivables are the year's absorption. Express each threshold as a maximum days-sales-outstanding figure at a 365-day convention, and compute the position at a 45-day collection period.
- Formula.** **CFADS** trigger = threshold × debt service. Allowable net absorption = 6,984,000 – trigger. Allowable closing receivables = allowable absorption + payables. **DSO** = receivables ÷ revenue × 365.
- Substitution.** For the 1.20× test: $1.20 \times 5,009,635.23 = 6,011,562.28$; $6,984,000 - 6,011,562.28 = 972,437.72$; $972,437.72 + 300,000 = 1,272,437.72$; $1,272,437.72 / 12,000,000 \times 365$.
- Result.**

Test	Threshold	CFADS trigger	Allowable receivables	Maximum DSO	Days of headroom
Distribution condition	1.25×	6,262,044.04	1,021,955.96	31.0845 days	3.7095
Financial covenant	1.20×	6,011,562.28	1,272,437.72	38.7033 days	11.3283
Distribution lock-up	1.15×	5,761,080.51	1,522,919.49	46.3221 days	18.9471

Actual **DSO** is **27.3750 days**. At a 45-day collection period receivables would be **1,479,452.05**, absorption **1,179,452.05**, **CFADS** **5,804,547.95** and **DSCR** **1.1587** — below the covenant and inside the lock-up.

- Interpretation.** This is the translation that makes an accounting statement usable by the people whose behaviour determines it. **The distribution condition is a 31-day collection covenant.** Nothing in the finance documents says so, no operations dashboard reports it, and the entire margin between a dividend and no dividend is **3.7095 days** of collection — less than one invoice cycle. Whether that is inside the observed variability of a given offtaker's payment run is an empirical question for that project's own collection history, and answering it is the point: 3.7095 days, not the 1.25 in the term sheet, is the number a finance director should put in front of the collections team.

Read the sensitivity as a unit rate and it becomes a management metric: at 12,000,000 of revenue **one day of DSO is 32,876.71 of cash and 0.006563 of DSCR**, so a one-week slip in payment behaviour costs **0.0459** of coverage. Three cautions on over-applying the result. It assumes payables stay at 300,000; a project that funds a receivables slip by stretching its own suppliers converts a covenant problem into a supply-chain problem and a possible default under the operating contracts, which is a worse trade than it looks. It assumes revenue is unchanged, so it isolates collection risk from demand risk — the two are separated in Domain 7 for exactly this reason, and a fall in revenue reduces receivables and flatters the ratio at the same time as it destroys the cash. And the 365-day convention matters: the finance documents may compute on 360 days, which tightens every threshold in the table by **1.3889 %** — the 1.25× test becomes **30.6587 days** rather than 31.0845 —

so the convention belongs on the defined-terms sheet (Toolkit 2.T.1) rather than in a modeller's habit. The remedy Case study A reaches — a working-capital facility sized against the slip, and collections given a named owner — is the operational answer to an accounting problem, which is the whole reason this Knowledge Area exists.

A coverage covenant is a collections covenant

CFADS before working capital 6,984,000 · payables 300,000 · debt service 5,009,635.23 · revenue 12,000,000

One day of DSO is 32,876.71 of cash and 0.006563 of DSCR; the line is straight because debt service is fixed

50,096.35 of working-capital absorption costs exactly 0.01 of coverage




Fig 2.3.1 — The covenant as a collection period

2.3.2 Revenue and cost recognition

The principle. Revenue is recognised as performance occurs — when control of the promised goods or services transfers to the customer — not when the invoice is raised or the cash arrives. For long-duration work this means recognising **over time** as the obligation is satisfied, which requires a defensible measure of progress. IFRS 15 is the reference framework, described here in principle only.

Measuring progress uses either **input** methods (costs incurred relative to total expected costs — the familiar percentage-of-completion approach) or **output** methods (units delivered, milestones surveyed). The choice matters and is not free: an input measure can be distorted by inefficiency (spending more "earns" more revenue) and an output measure by lumpy deliverables. This is the same measurement-integrity problem the delivery book handles as earned value (PML-AI, Domain 7, KA 7.3.1) — and the two disciplines should use the same progress evidence, because a project claiming 60 % complete for revenue and 48 % for earned value has a story to explain.

Costs follow performance symmetrically: costs of fulfilling the obligation are expensed as incurred, certain fulfilment costs may be capitalised, and **expected losses are recognised immediately and in full** the moment a contract is expected to be loss-making — a deliberate asymmetry that stops a known loss being spread quietly across future periods.

WORKED EXAMPLE**Worked example 2.3.2 — the same progress, two measures, and then a loss.**

- Setup.** This example sits on the other side of Kestrel's construction contract: the EPC contractor's own accounts, not the SPV's. The lump-sum price is **USD 48,000,000** (Domain 14's master construction). At the quarter-five data date the contractor has incurred costs of **USD 27,000,000** and estimates **USD 15,000,000** to complete; the SPV has certified **61 %** of the milestone schedule (Domain 14, KA 14.2.1). Compute revenue and profit to date on a cost-input measure and on a milestone-output measure. Then suppose a re-forecast puts the cost to complete at **USD 22,500,000**.
- Formula.** Input progress = costs incurred ÷ expected total costs. Revenue to date = price × progress. Profit to date = revenue to date – costs incurred. Onerous test: expected total costs > price = recognise the whole expected loss immediately; the period charge is the swing from the cumulative position already recognised.
- Substitution.** Expected total cost 27,000,000 + 15,000,000 = 42,000,000; input progress 27,000,000 / 42,000,000; input revenue 48,000,000 × 0.642857...; output revenue 48,000,000 × 0.61. Revised total cost 27,000,000 + 22,500,000.
- Result.**

Measure	Progress	Revenue to date	Cost to date	Profit to date
Cost input	64.2857 %	30,857,142.86	27,000,000	3,857,142.86
Milestone output	61.0000 %	29,280,000.00	27,000,000	2,280,000.00
Difference	3.2857 points	1,577,142.86	—	1,577,142.86

On the re-forecast, expected total cost of **49,500,000** against a price of 48,000,000 makes the contract **onerous** by **1,500,000**. The cumulative position must move from +3,857,142.86 to –1,500,000, so the charge in the period is **USD 5,357,142.86 — 3.5714 times** the loss itself.

- Interpretation.** Three results, each with a professional edge. **The two progress measures differ by 1,577,142.86 of profit on an identical set of facts**, which is **26.2857 %** of the contract's whole expected margin of 6,000,000 — so the choice of measure is not a presentational detail, it is a quarter of the job's reported profitability. And the direction is diagnostic rather than arbitrary: the input measure is ahead because costs have run faster than certifications, which is precisely the pathology KA 2.3.2 warns about — under a cost-input measure, **inefficiency earns revenue**. The gap between 64.2857 % and 61 % is the contractor spending 3.2857 points of the job without producing 3.2857 points of it, and reporting the difference as performance.

The onerous-contract swing is the number that surprises boards. A 1,500,000 loss produced a 5,357,142.86 charge, because recognising a loss also requires unwinding the profit already taken. The multiple is not a quirk of these figures: it is $1 + \text{profit recognised} \div \text{loss}$, so the further into a contract the reversal comes, the larger the swing, and a contract that turns at 90 % complete produces a charge that can dwarf the loss it reports. That is a property of the arithmetic, not a claim about any market: wherever it operates, a reported result is stable until the reversal and then abrupt, which is why a lender to a contractor reads the contract portfolio's cost-to-complete forecasts and not its profit history.

The two disciplines must reconcile. The SPV's earned value on this scope shows $\text{CPI} = 1.0000$ by construction, because on a fixed-price milestone certification the amount certified is the amount budgeted (Domain 14, KA 14.2.1) — so the cost overrun that is plainly visible in the contractor's

books is structurally invisible in the SPV's. Neither party is wrong and neither number is useless; what is dangerous is a monitoring regime that reads only one of them. The discipline is to require the same progress evidence to support both, and to treat a divergence between the certified percentage and the contractor's cost-based percentage as the leading indicator it is (the delivery-side treatment is PML-AI, Domain 7, KA 7.3.1). Whether an input or an output measure is permitted, and how a loss-making contract must be presented, is a matter for the entity's framework, finance function and auditors; the arithmetic above is transferable, the conclusion is not.

2.3.3 Capital versus operating expenditure

The distinction. **Capital expenditure (capex)** creates or enhances an asset with benefits beyond the current period; it is capitalised to the balance sheet and depreciated over its useful life. **Operating expenditure (opex)** is consumed in the period and expensed immediately. The same cash outflow, classified differently, produces very different profit.

WORKED EXAMPLE

Worked example 2.3.3 — the same USD 1,200,000, two treatments.

1. **Setup.** Kestrel spends USD 1,200,000 on a control-system overhaul. If it extends the asset's capability it is capex, depreciated over 10 years; if it restores existing performance it is maintenance opex.
2. **Formula.** Capex year-one charge = spend ÷ useful life. Opex year-one charge = full spend.
3. **Substitution.** Capex: $1,200,000/10 = 120,000$. Opex: $1,200,000$.
4. **Result.** Year-one profit is **USD 1,080,000 lower** under the opex treatment. **Cash is identical in both cases** — USD 1,200,000 leaves the account either way.
5. **Interpretation.** This is the clearest demonstration in the domain that accounting choice moves reported performance without moving economics, and it cuts both ways. Capitalising flatters current profit and burdens future periods with depreciation; it also inflates the asset base against which returns are measured. Because the classification is judgment applied to facts — does this enhance or merely restore? — it is a standing area of audit attention, and a leader should expect to justify it rather than assert it. Note the covenant consequence: profit-based covenants respond to the choice while cash-based ones (DSCR) do not, which is part of why lenders prefer cash-based tests (Domain 10).

Two refinements, and the second is the one a careful reader should insist on. **Over the ten years the two treatments charge the identical 1,200,000**, so the choice is entirely about timing: capitalising defers 1,080,000 of charge into years two to ten, at 120,000 a year, and by year ten the cumulative profit under both treatments is the same to the dollar. Anyone presenting capitalisation as an improvement in performance is presenting a nine-year loan against the future, and the interest on it is paid in depreciation.

And the claim that "cash is identical" holds only where the accounting choice does not drive the tax deduction. Kestrel's illustration assumes tax depreciation follows accounting depreciation — a simplification stated as one (KA 2.A.1; Domain 6, KA 6.2.3). Where instead the deduction follows the accounting treatment, at a 20 % tax rate and an 8 % discount rate the two paths give: relief of **240,000 in year one** if expensed, against $120,000 \times 20\% = 24,000$ a year for ten years if capitalised, whose present value at $AF(8\%, 10) = 6.710081$ is **161,041.95**. The expensing route is worth **USD 78,958.05** of present value — **6.5798 %** of the spend — and that is a cash difference, arising purely from a classification argument. The professional position is therefore precise rather than slogan-like: **the capex/opex choice does not change the pre-tax cash flow,**

and may well change the after-tax cash flow. Whether it does is jurisdiction-specific, because in many regimes the tax base is computed independently of the accounts, and the answer for a particular entity is a matter for qualified tax advice rather than for this book. What a leader should never do is argue the classification because of the tax outcome; the classification follows the facts, and the tax follows the classification.

2.3.4 Provisions and contingencies

Definitions. A **provision** is a liability of uncertain timing or amount, recognised when a present obligation exists from a past event, settlement is probable, and a reliable estimate can be made (IAS 37 is the reference framework, in principle). A **contingent liability** fails one of those tests — typically because settlement is only possible rather than probable — and is **disclosed, not recognised**. A **contingent asset** is treated still more cautiously: disclosed when probable, recognised only when virtually certain, an asymmetry that deliberately resists optimism.

Project-relevant instances: **decommissioning and site-restoration obligations** (recognised at the present value of the expected cost when the obligation arises — often at construction, decades before the spend, and a major balance-sheet item for energy and resources projects); **warranty and defect obligations**; **onerous contracts** (the loss recognised in full, per 2.3.2); and **disputed claims**, where the provision/disclosure boundary is genuinely contested and legal advice governs. The leader's discipline here is narrow and important: **a provision is not a reserve to be created in good years and released in bad ones** — that is earnings management, and the recognition tests exist to prevent it.

WORKED EXAMPLE

Worked example 2.3.4 — measuring and unwinding a restoration obligation.

1. **Setup.** The master statements in KA 2.2 present Kestrel without a restoration obligation, for exposition. Suppose instead the concession requires the intake and outfall works to be removed at the end of the 25-year life, at an expected cost of **USD 4,500,000** in the money of year 25, and that a **5.0 %** discount rate is applied. The obligation arises on construction. Compute the amount recognised, the first-year charges, the cash effect, and the sensitivity to the rate.
2. **Formula.** Provision at recognition = expected cost $\div$ $(1 + r)^n$. The same amount is added to the asset's cost and depreciated over the life. Each year: accretion (a finance charge) = opening provision $\times$ r ; depreciation of the restoration asset = initial provision $\div$ life. Closing provision = opening + accretion.
3. **Substitution.** 4,500,000 / 1.05^{25} ; accretion 1,328,862.47 $\times$ 0.05; depreciation 1,328,862.47 / 25.
4. **Result.**

Line	USD
Provision recognised at construction	1,328,862.47
Added to the asset's cost (60,000,000 → 61,328,862.47)	1,328,862.47
Year-one accretion (finance charge)	66,443.12
Year-one depreciation of the restoration asset	53,154.50
Year-one charge against profit	119,597.62
Year-one cash effect	nil
Provision at the end of year one	1,395,305.60

1. **Interpretation.** Start with the invariant, because it disciplines everything else: **depreciation of 1,328,862.47 over the life plus accretion of 3,171,137.53 over the life sums to exactly 4,500,000 — the cash eventually paid.** Accrual accounting has not invented a cost; it has allocated a known future payment across the periods that caused it, and the provision accretes to precisely the settlement amount in the year it falls due. That is the cleanest available demonstration of what recognition does and does not do.

The professional content is in three places. **The charge is real and the cash is nil**, so a profit-based covenant is exposed to this obligation from the first year of operation while **DSCR** is untouched for twenty-five years: 119,597.62 is **5.7945 %** of Kestrel's net income, enough to matter in a tight profit test and invisible in every coverage ratio the lender computes. Domain 8 (KA 8.4) makes the complementary point on the cash side — the spend falls after the loan matures, so it reduces the tail that Domain 10's **PLCR** of **1.9431** measures without appearing in any ratio the lender tests.

The balance sheet then moves with interest rates rather than with the obligation. Re-measure at **4.0 %** and the provision becomes **1,688,025.61 — 27.0279 %** higher; at **6.0 %** it becomes **1,048,493.84, 21.0984 %** lower. Nothing about the works, the cost or the concession has changed. A reader comparing two projects' balance sheets, or one project across two years, must establish the discount rate before treating the movement as news; where the rate is re-measured annually the provision line is one of the noisiest on an infrastructure balance sheet.

And the tax treatment is where the arithmetic stops being transferable. Many regimes deny a deduction until the expenditure is actually incurred, which would make this charge non-deductible for twenty-five years and create a deferred tax asset whose recoverability depends on there being taxable profit in the year of settlement — by which time the project may have none. The recognition trigger, the discount rate basis, the treatment of subsequent changes in estimate and the deductibility are all framework- and jurisdiction-specific and are matters for the entity's auditors and qualified tax advisers; and because the existence of the obligation usually turns on the concession or permit wording, its scope is a question for counsel before it is a question for accountants.

AI in this KA

These four treatments are exactly where AI assistance is least reliable, because each turns on judgment applied to specific facts: is this capex or maintenance, is settlement probable, does control transfer over time. A model will produce a confident answer that reads like a conclusion and is actually a summary of how similar questions are usually answered. The governed position: use AI to marshal the facts, locate the relevant framework and draft the argument on both sides; never to reach the conclusion. Conclusions on recognition and measurement belong to the entity's finance function and auditors, and jurisdiction-specific treatment to qualified advisers — the boundary this book applies to itself (Domain 1, KA 1.3.1).

■ KEY TERMS — KA 2.3

Term	Meaning
Working capital	Receivables + inventory – payables; growth consumes cash.
CFADS	Cash flow available for debt service — a defined term whose definition changes the ratio.
Days sales outstanding (DSO)	Receivables ÷ revenue × days in the convention; the collection period a covenant can be restated in.
Input / output progress measures	Cost-based vs delivery-based measures of performance to date.
Onerous contract	An expected-loss contract; the loss is recognised immediately and in full.
Capex / opex	Capitalised and depreciated vs expensed in the period; identical pre-tax cash, different profit.
Provision / contingent liability	Recognised (present obligation, probable, estimable) vs disclosed.
Accretion	The finance charge that unwinds the discount on a provision, taking it to the settlement amount.

■ SAMPLE MCQS — KA 2.3

MCQ 2.3-A [2.3.1 · Application] EBITDA 7,500,000; tax 516,000; working-capital increase 600,000; debt service 5,009,635. DSCR including the working-capital movement is:

- A. 1.39
- B. 1.27 ✓ **CORRECT**
- C. 1.50
- D. 1.20

Rationale: $CFADS = 7,500,000 - 516,000 - 600,000 = 6,384,000$; $\div 5,009,635 = 1.27$. A excludes the working-capital movement (the definitional point of the example); C ignores tax as well; D is a typical covenant threshold, not this calculation.

MCQ 2.3-B [2.3.3 · Application] USD 1,200,000 is spent on an overhaul. Capitalised over 10 years versus expensed immediately, the year-one differences are:

- A. profit lower by 1,200,000 if capitalised; cash differs
- B. profit lower by 1,080,000 if expensed; cash identical ✓ **CORRECT**
- C. profit identical; cash lower by 1,080,000 if expensed
- D. profit lower by 120,000 if expensed; cash identical

Rationale: Expensing charges 1,200,000 against capitalising's 120,000 — a 1,080,000 difference — and the cash outflow is the same either way. A inverts which treatment charges more; C confuses which statement is affected; D states the capitalised charge as the difference.

MCQ 2.3-C [2.3.4 · Analysis] A contractor faces a claim it considers possible but not probable, with a reliably estimable amount. The treatment is:

- A. recognise a provision, since the amount is estimable
- B. disclose as a contingent liability; recognition requires probable settlement ✓ **CORRECT**
- C. no disclosure, since settlement is not probable

D. recognise a contingent asset

Rationale: Estimability alone is insufficient — probability of settlement is the failed test, so disclosure rather than recognition (2.3.4). C hides information users need; D reverses the direction.

MCQ 2.3-D [2.3.2 · Analysis] A contractor recognises revenue on 60 % completion using a cost-input measure while its earned-value system reports 48 % complete. The soundest reading is:

- A. no issue — the two systems serve different purposes
- B. the divergence needs explaining: an input measure inflated by inefficiency can recognise revenue ahead of performance ✓ **CORRECT**
- C. the earned-value figure must be wrong
- D. revenue should be restated to 48 % automatically

Rationale: Cost-input measures reward spending, so inefficiency can raise apparent progress (2.3.2) — the gap is a signal to investigate, not to dismiss (A) or resolve by assumption (C, D).

MCQ 2.3-E [2.3.1 · Application] CFADS before working capital 6,984,000; payables held at 300,000; revenue 12,000,000; receivables opened at nil; debt service 5,009,635.23. The maximum days sales outstanding consistent with a 1.20× covenant, at a 365-day convention, is:

- A. 27.3750 days
- B. 31.0845 days
- C. 38.7033 days ✓ **CORRECT**
- D. 45.0000 days

Rationale: The 1.20× trigger is CFADS 6,011,562.28, allowing 972,437.72 of absorption and therefore receivables of 1,272,437.72 — $1,272,437.72 / 12,000,000 \times 365$. A is the actual position, not the limit; B is the 1.25× distribution threshold, the commonest confusion because both appear in the same clause; D is the scenario that breaches, at DSCR 1.1587.

MCQ 2.3-F [2.3.4 · Application] A restoration obligation of 4,500,000 falls due in 25 years and is discounted at 5.0 %. The amount recognised and the first-year charge against profit are:

- A. provision 4,500,000; charge 180,000
- B. provision 1,328,862.47; charge 119,597.62 ✓ **CORRECT**
- C. provision 1,328,862.47; charge 66,443.12
- D. provision 1,328,862.47; charge nil, since no cash moves

Rationale: The provision is recognised at present value, and the first year carries both accretion 66,443.12 and depreciation of the capitalised restoration asset 53,154.50. A recognises the undiscounted amount; C takes the accretion alone and forgets the asset it created; D confuses a nil cash effect with a nil charge.

MCQ 2.3-G [2.3.2 · Analysis] A contractor has recognised 3,857,142.86 of cumulative profit on a 48,000,000 contract when a re-forecast makes expected total costs 49,500,000. The charge in the period is:

- A. 1,500,000 — the expected loss
- B. 5,357,142.86 — the expected loss plus the reversal of profit already recognised ✓ **CORRECT**
- C. 1,500,000 spread over the remaining life of the contract
- D. nil until the loss is actually incurred

Rationale: The cumulative position must move from +3,857,142.86 to −1,500,000, so the period charge is the whole swing (2.3.2). A forgets the reversal; C is precisely what immediate recognition exists to prevent; D applies a cash-basis instinct to an accrual test.

MCQ 2.3-H [2.3.1 · Evaluation] At financial close a sponsor presses for **CFADS** to be defined before working-capital movements, which on the first year's figures would report **DSCR** of 1.3941 rather than 1.2743. Advising the sponsor, the soundest position is:

- A. press for the exclusion: it buys 0.1198 of reported coverage on identical cash, and a further 18.25 days of collections of covenant headroom with it
- B. press for the definition that is the more stable rather than the higher today — exclusion flatters a growing trading cycle and turns against the sponsor in the first year of decline, when a shrinking cycle releases cash the covenant would then ignore ✓ CORRECT
- C. accept the lenders' inclusive definition, because cash-based tests are always the more conservative and conservatism protects the sponsor
- D. leave **CFADS** undefined and rely on the financial model's treatment, which both parties have reviewed

Rationale: the definitional choice is not neutral across the life of the facility — excluding working capital raises the ratio while the cycle grows and lowers it while the cycle unwinds — so a sponsor optimising the first test period is buying a definition that bites later (2.3.1), and stability is what a lender is actually paying for. A is the arithmetic correctly done against the wrong objective, treating one period as the covenant's life. C reaches a defensible destination by an argument that is not true, and an untrue argument will not survive the negotiation. D is the weakest of the four: an undefined term is settled later by whoever is enforcing it, and Domain 13's model audit tests the model against the documented definition, which must therefore exist. The finance leader's contribution here is the arithmetic across the facility's life; the drafting of the definition, and what it will mean on enforcement, are matters for the facility's counsel.

MCQ 2.3-I [2.3.3 · Evaluation] Kestrel's 1,200,000 control-system overhaul restores existing performance rather than extending capability. The finance director observes that capitalising it would protect a profit-based covenant; the tax adviser observes that, in a regime where the deduction follows the accounting treatment, expensing is worth **78,958** of present value. The finance leader should recommend:

- A. capitalise — the covenant is the larger financial exposure, and the classification is a judgment either way
- B. expense — the 78,958 is a genuine cash benefit, and this book's own discipline puts cash ahead of profit
- C. classify on the facts: the works restore performance, so expense them, and manage the covenant consequence separately and transparently with the lender ✓ CORRECT
- D. capitalise, and disclose the judgment in the notes so that users can adjust for it

Rationale: the classification follows the facts and the tax follows the classification, never the reverse (2.3.3). A and B both let a desired outcome choose the accounting, and B is the more seductive because its objective — cash — is the one this book otherwise privileges; the argument is still inverted. D bolts good disclosure practice onto an unsupportable treatment, and disclosure does not cure a classification the facts do not support. Where the capex/opex boundary falls for a particular project is a matter for the entity's finance function and auditors, and the deductibility a matter for qualified tax advisers in the relevant jurisdiction.

■ SELF-CHECK — KA 2.3

1. Why can two projects with identical economics report different *DSCRs*? — Because *CFADS* is a defined term; its definition (e.g. before or after working capital) changes the ratio.
2. What does the capex/opex choice change, and what does it not? — Reported profit and the asset base; pre-tax cash is unchanged, and after-tax cash may not be.
3. When is a provision recognised rather than disclosed? — Present obligation from a past event, probable settlement, reliable estimate.
4. State Kestrel's 1.25× distribution condition as a collection period. — A maximum *DSO* of 31.0845 days against an actual 27.3750 — headroom of 3.7095 days.
5. Why does an onerous-contract charge exceed the loss? — Because the profit already recognised must be reversed as well: $1 + \text{profit recognised} \div \text{loss}$, here 3.5714 times.
6. What does a provision's accretion plus its depreciation sum to over the life? — The settlement amount, 4,500,000; accrual accounting allocates timing, not totals.

KNOWLEDGE AREA 2.4

Ratio interpretation and project interfaces

Topics: 2.4.1 the ratio families · 2.4.2 interest cover and the leverage view · 2.4.3 project systems and corporate reporting.

2.4.1 The ratio families

Ratios are comparisons, and their only value is in what they are compared against — the same entity over time, or a genuine peer on the same policies (KA 2.1.2's warning). Four families:

Family	Asks	Examples
Liquidity	Can it pay what falls due soon?	Current ratio, quick ratio
Leverage	How much of the funding is debt?	Debt/equity, debt/ <i>EBITDA</i>
Coverage	Can earnings or cash service the debt?	Interest cover, <i>DSCR</i> (Domain 10)
Return	What is earned on the capital used?	Return on equity, return on capital employed

For project finance the **coverage** family dominates, because a ring-fenced SPV's whole credit case is whether its cash flow services its debt (Domain 1, KA 1.1.2). But a set read together says more than any member of it, and the completed balance sheet of KA 2.2.2 makes it possible to compute the whole set and then test it against something external — the cost of capital Domain 9 derived.

WORKED EXAMPLE**Worked example 2.4.1 — Kestrel's full ratio set, and what it is worth against the cost of capital.**

- Setup.** From the completed statements: **EBITDA** 7,500,000; **EBIT** 5,100,000; net income 2,064,000; receivables 900,000; cash 1,374,364.77; payables 300,000; senior debt 39,510,364.77; equity 20,064,000. Opening debt was 42,000,000 and opening equity 18,000,000. The senior rate is 6.0 % and the tax rate 20 %. Domain 9 (KA 9.1.4) derived the project **WACC** at **7.9860 %**, the cost of equity at 70 % gearing at **15.42 %** and the equity **IRR** at **12.5311 %**.
- Formula.** Current ratio = current assets ÷ current liabilities. Debt/equity = debt ÷ equity. Gearing = debt ÷ (debt + equity). Net debt = debt – cash. Return on capital employed = **EBIT** ÷ (debt + equity), and after tax = **EBIT**(1 – T) ÷ (debt + equity). Return on equity = net income ÷ equity. After-tax cost of debt = rate × (1 – T). The leverage identity is **ROE** = **ROCE**_after-tax + (D/E) × (ROCE_after-tax – k_d after tax).
- Substitution.** (900,000 + 1,374,364.77) / 300,000; 39,510,364.77 / 20,064,000; 39,510,364.77 / 59,574,364.77; 39,510,364.77 – 1,374,364.77; 5,100,000 / 59,574,364.77; 2,064,000 / 20,064,000; and on opening bases 4,080,000 / 60,000,000 and 2,064,000 / 18,000,000.
- Result.**

Ratio	Value	Basis
Current ratio	7.5812	no inventory; cash is 60.4285 % of current assets
Debt/equity	1.9692	closing balances
Gearing	66.3211 %	closing; 70.00 % at financial close
Net debt	38,136,000.00	debt less cash
Net debt/ EBITDA	5.0848	against gross 5.2680
ROCE , pre-tax	8.5607 %	EBIT ÷ closing capital employed
ROCE , after tax, opening capital	6.8000 %	4,080,000 ÷ 60,000,000
ROE , closing equity	10.2871 %	
ROE , average equity	10.8449 %	0.5578 points higher on the same profit
ROE , opening equity	11.4667 %	the basis on which the leverage identity is exact
After-tax cost of debt	4.8000 %	6.0 % × (1 – 0.20)

- Interpretation.** Four readings, in ascending order of usefulness.

The leverage identity holds exactly — but only on one basis. On opening balances, **6.8000 %** + **2.3333** × (**6.8000 %** – **4.8000 %**) = **11.4667 %**, which is the return on opening equity to the digit. That is the whole of what gearing does: it earns the spread between the return on capital and the after-tax cost of debt, 2.0000 points here, and multiplies it by the debt-to-equity ratio. Two corollaries follow immediately. Leverage is accretive only while **ROCE** exceeds the after-tax cost of debt, and it becomes destructive below it at the same multiple — the reason Domain 9 treats gearing as a risk transfer rather than a value creator. And **the identity breaks the moment the bases are mixed**: computed on closing equity the same year's **ROE** is 10.2871 %, on average equity 10.8449 %, on opening equity

11.4667 % — a spread of **1.1796 points on identical performance**, purely from a choice of denominator. A reviewer's first question about any return ratio is which balance it uses, and the answer is right in a footnote or it is nowhere.

The accounting return is below the cost of capital, and the project is still worth doing. After-tax ROCE of 6.8000 % against a WACC of 7.9860 % is a shortfall of **1.1860 points**, and yet Domain 4 computed an NPV of **+16,179,360** at 8 % and an IRR of **12.19 %** on the same project. Both are correct. A first-year accounting return is a single-period ratio on a fully-depreciating asset at its maximum carrying amount, and it rises mechanically as the asset depreciates and the debt amortises: with EBIT unchanged, year two's after-tax ROCE is already **6.8486 %**, because capital employed fell 425,635.23 without anything happening. **Accounting returns are the wrong instrument for judging project economics** — that is what Domains 3 and 4 exist for — and a board comparing a project's first-year ROCE with a corporate hurdle rate will reject investments it should make.

ROE is not the equity return either. The 10.2871 % here sits **5.1329 points below** the 15.42 % Domain 9 identifies as the cost of equity at this gearing, and **2.2440 points below** the 12.5311 % equity IRR the same structure actually delivers over twelve years. An accounting ROE on one early year of a long-dated asset is not comparable with either, and quoting it against a required return is a category error, not a conservative estimate.

The liquidity ratios are the least informative in the set and the most often quoted. A current ratio of 7.5812 looks extraordinary and means very little: 60.4285 % of those current assets is a cash balance of which **91.1264 % is contractually restricted** (KA 2.2.2), and the payables it is measured against are a single month of chemicals and power. On a ring-fenced SPV with a reserve account and a defined waterfall, liquidity is governed by the finance documents, not by a ratio — which is precisely why lenders covenant coverage and leave the current ratio to general-purpose analysis.

Six returns, one project, one year — and none of them is the project's return

The identity is exact on opening bases: $6.8000 + 2.3333 \times (6.8000 - 4.8000) = 11.4667$

On closing equity the same profit gives 10.2871 %, on average equity 10.8449 % — 1.1796 points from the denominator alone

Year-one accounting return sits below WACC on a project whose NPV is +16,179,360 and IRR 12.19 %




Fig 2.4.1 — Kestrel's return ladder, year one

2.4.2 Interest cover and the leverage view

WORKED EXAMPLE

Worked example 2.4.2 — Kestrel's cover and gearing.

1. **Setup.** EBIT USD 5,100,000; interest USD 2,520,000; senior debt at year end USD 39,510,365; EBITDA USD 7,500,000.
2. **Formula.** Interest cover = EBIT ÷ interest. Debt/EBITDA = debt ÷ EBITDA.
3. **Substitution.** $5,100,000 / 2,520,000$; $39,510,365 / 7,500,000$.
4. **Result.** Interest cover **2.02×**; debt/EBITDA **5.27×**.
5. **Interpretation.** Both are true and they point in different directions, which is the point of reading a set. Cover of 2.02× says earnings comfortably absorb the interest charge; debt of 5.27× EBITDA says the balance sheet is heavily geared — normal for contracted infrastructure and alarming for a merchant business, because what makes high leverage tolerable is **revenue certainty**, not the ratio itself (Domain 7's revenue models; Domain 11's risk allocation). Note too that interest cover is an accrual measure and ignores principal entirely: Kestrel must also find USD 2,489,635 of principal, which is why DSCR (1.27 including working capital, 2.3.1) is the ratio a lender actually covenants.

Three refinements turn this from a pair of numbers into a judgment. **There are two interest covers and they differ materially.** On EBIT the ratio is **2.0238×**; on EBITDA — the variant often called cash interest cover — it is **2.9762×**, because depreciation of 2,400,000 is added back. Neither is wrong and the gap between them is 0.9524 of coverage, so a covenant defined on "interest cover" without specifying the numerator has left almost a full turn of coverage to interpretation. That is the same definitional exposure as CFADS (KA 2.3.1), on a ratio nobody thinks of as contestable.

The tighter covenant is not the one that looks tighter. Suppose the facility carried both a 1.20× DSCR covenant and a 2.00× interest-cover covenant — an entirely ordinary pairing. The DSCR test bites at CFADS of 6,011,562.28, a headroom of **372,437.72**, which at Kestrel's 0.80 cash-to-revenue gearing is **465,547.16** of revenue, or **3.8796 %**. The interest-cover test bites at EBIT of $2.00 \times 2,520,000 = 5,040,000$, a headroom of only **60,000** of EBIT and therefore of revenue — **0.5000 %**. The DSCR covenant tolerates **7.7591 times** as large a revenue miss as the interest-cover covenant does. A lender adding an interest-cover test "for comfort" beside a coverage test has, on these numbers, created the binding covenant and quite possibly not noticed; a sponsor negotiating hard on the DSCR threshold while conceding the interest-cover threshold has negotiated the wrong clause. **Which covenant binds is an arithmetic question to be answered at close, not a matter of convention** — and the answer belongs on the covenant dashboard (Domain 10, Toolkit 10.T.2) in revenue units, not ratio units.

Finally, leverage measured on book values decays without any transaction. Debt/EBITDA of 5.2680× falls every year as principal amortises, even if the project never improves: it is a statement about an amortisation schedule as much as about the business. Net debt/EBITDA of **5.0848×** is lower again, and the 0.1832 difference is entirely the cash balance — **91.1264 % of which is a restricted reserve** (KA 2.2.2). Whether a covenant is struck on gross or net debt, and whether restricted cash counts, is worth more than most of the basis-point negotiation that surrounds it.

2.4.3 Project systems and corporate reporting

A project's cost system and the corporate accounts describe the same money in different languages, and the interfaces are where reconciliation errors and disputes live. The four that matter:

- **Commitments versus actuals.** A purchase order commits funds; accounting recognises cost on delivery or performance. Project systems track both; the ledger recognises one (PML-AI, Domain 7, KA 7.2.1).
- **Accruals at period end.** Work received but not invoiced must reach the ledger, or cost performance flatters and then lurches — the same defect PML-AI diagnoses as a stepped [CPI](#).
- **Capitalisation boundaries.** Which project costs form part of the asset (and from what date capitalisation begins and ends) determines both the depreciation base and reported profit (2.3.3). Borrowing costs during construction are a specific instance — capitalised into the asset while it is being built, expensed thereafter.
- **Cut-off and period discipline.** A cost is in one period only. Projects run continuously and ledgers close monthly; every reconciliation dispute is ultimately a cut-off question.

The leader's obligation is not to run these reconciliations but to insist they exist and to know which number is being quoted. "The project has spent USD 40 million" can mean committed, incurred, invoiced, paid or capitalised — five different figures, all defensible, differing by material amounts. How material is worth computing once, because the answer changes how the question is asked ever afterwards.

WORKED EXAMPLE

Worked example 2.4.3 — five answers to "how much has the project spent?"

1. **Setup.** Kestrel's construction at the quarter-five data date, on Domain 14's figures. Cumulative certified spend is **33,945,403** (KA 14.2.1: [AC](#) of 33,480,000 on the control accounts plus 465,403 of certified variations). Remaining committed contract value is **18,720,000** and approved-but-uncertified variations **840,000**. Of the certified value, **1,205,403** has been received but not yet invoiced. Against invoices raised, **1,200,000** of retention is withheld (the 5 % regime capped at 2.5 % of the contract price — Domain 14, KA 14.3.2), **358,000** of trade invoices are approved and unpaid, and of the **4,800,000** advance payment made at contract signature **61 %** has been recovered against certifications. Of the amounts incurred, **620,000** of owner's general and administrative costs fail the capitalisation test, and capitalised interest incurred to date is **677,923** (the 2,114,597 total less the 1,436,674 remaining — KA 14.1.1). Produce all five figures and reconcile them.
2. **Formula.** Committed = incurred + open commitments. Invoiced = incurred – accrued not invoiced. Cash paid = invoiced – advance recovery applied – retention withheld – unpaid invoices + the advance itself. Capitalised = incurred – non-capitalisable costs + capitalised interest. Then test the reconciliation.
3. **Substitution.** Open commitments $18,720,000 + 840,000 = 19,560,000$; invoiced $33,945,403 - 1,205,403$; advance recovered $4,800,000 \times 0.61 = 2,928,000$; paid $32,740,000 - 2,928,000 - 1,200,000 - 358,000 + 4,800,000$; capitalised $33,945,403 - 620,000 + 677,923$.
4. **Result.**

Measure	USD	What it is
Committed	53,505,403	Contractual entitlement placed, whether performed or not
Capitalised	34,003,326	The carrying amount added to the asset
Incurred	33,945,403	Value received and certified, invoiced or not
Paid	33,054,000	Cash out of the account, including the unrecovered advance
Invoiced	32,740,000	Supplier claims received into the ledger

The reconciliation, which must close exactly:

Cash paid 33,054,000 + retention withheld 1,200,000 + trade invoices approved and unpaid 358,000 + certified value not yet invoiced 1,205,403 + open commitments 19,560,000 – unrecovered advance payment (1,872,000) = committed 53,505,403 ✓

1. **Interpretation.** The headline is the **spread of 20,451,403** between the largest and smallest answer — **34.0857 %** of the whole 60,000,000 envelope — on a single date, from one ledger, with every figure defensible and auditable. That is the arithmetic behind the discipline: a question answered with a number rather than with a measure is not an answer.

Three specific traps sit inside the reconciliation, and each has cost projects money.

Capitalised exceeds incurred. By **57,923** here, which offends the intuition that the balance-sheet figure must be a subset of what has been spent. It exceeds because capitalised interest of 677,923 enters the asset without any supplier ever invoicing for it, while 620,000 of owner's costs leave through the income statement. A reviewer reconciling a fixed-asset note to a cost report and expecting the asset to be the smaller number will look for an error that is not there — and, worse, may not look for the 620,000 that genuinely did fail the capitalisation test (KA 2.3.3), which is the item with a covenant consequence.

The two figures that look closest are the least related. Incurred (33,945,403) and paid (33,054,000) differ by only **891,403**, which reads as near-agreement and is nothing of the kind: it is the net of four unrelated items — retention, unpaid invoices, uninvoiced value and an unrecovered advance — totalling **4,635,403** gross, or **5.2001 times** the apparent gap. Two of those items push one way and two the other, and a change in any of them moves cash without moving cost. A cash forecast built by adjusting the cost report for "the usual lag" is built on the coincidence that the four currently offset.

The advance payment carries the opposite sign to everything else. The unrecovered 1,872,000 is cash gone and value not yet received — a prepayment asset, not a cost — so it reduces committed spend when reconciling from cash. It is the single most common sign error in a construction cash reconciliation, and the reason Domain 14 (KA 14.3.2) treats the advance and its recovery as a named line rather than a netting adjustment.

The leader's habit that follows is small and non-negotiable: **name the measure in the sentence.** "The project has incurred 33.9 million, paid 33.1 million and committed 53.5 million" takes nine more words than "the project has spent 34 million" and forecloses an entire class of dispute. The figures also serve different decisions — the in-balance test uses commitments (Domain 14, KA 14.2.3), the drawdown uses certified value, the accounts use the capitalised amount, and treasury uses cash — so there is no single "right" answer to be settled on, only a right measure for each question. The split between capitalisable and non-capitalisable cost illustrated here is indicative; where the capitalisation boundary falls for a particular project is a framework-and-facts question for the entity's finance function and auditors.

AI in this KA

Where it earns its place. Ratio computation across many periods and entities, restatement onto a common basis, and — most valuably — the translation this Knowledge Area is built on: taking a covenant threshold and expressing it in revenue, days or driver units so that the binding test can be identified rather than assumed. That is mechanical arithmetic on stated definitions, it is the work practitioners most often leave undone, and it is verifiable line by line.

Where it fails, specifically. Three failures, each of which produces a confident wrong answer rather than an error message. An assistant asked for "return on equity" will pick a denominator without saying which, and opening, average and closing bases differ by **1.1796 points** on Kestrel's single year (2.4.1) — the leverage identity then appears to fail and the model will rationalise the discrepancy rather than report the inconsistency. An assistant comparing two entities' ratios will not ask what policies produced the inputs, so a capitalisation difference (2.3.3) reads as a performance difference. And asked how much a project has spent, it will return whichever of the five measures the source document happened to contain, with no indication that four others exist (2.4.3). The governed habit is to require every ratio to arrive with its numerator, denominator, basis and defining document named — and to treat a ratio that cannot state them as unreported. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 2.4

Term	Meaning
Interest cover	$\text{EBIT} \div \text{interest}$; an accrual coverage measure that ignores principal.
Cash interest cover	$\text{EBITDA} \div \text{interest}$; the same test with depreciation added back — 0.9524 higher for Kestrel.
Debt/EBITDA	A leverage measure; tolerable level depends on revenue certainty.
ROCE / ROE	Return on capital employed and on equity; linked by the leverage identity, exact only on consistent bases.
Leverage wedge	$(D/E) \times (\text{ROCE after tax} - k_d \text{ after tax})$; the amount gearing adds to ROE, and subtracts when the spread is negative.
Capitalisation boundary	Which costs and which dates form part of the asset.
Cut-off	Assigning a transaction to exactly one period.
Commitment vs actual vs paid	Distinct measures of "spend" that must never be conflated.
Unrecovered advance	Cash paid for value not yet received; a prepayment asset that reconciles with the opposite sign.

■ SAMPLE MCQS — KA 2.4

MCQ 2.4-A [2.4.2 · Application] EBIT 5,100,000 and interest 2,520,000. Interest cover is:

- A. 1.27×
- B. 2.02× ✓ CORRECT
- C. 2.98×
- D. 0.49×

Rationale: $5,100,000 / 2,520,000 = 2.02$. A is the DSCR from 2.3.1; C uses EBITDA in the numerator; D inverts the ratio.

MCQ 2.4-B [2.4.2 · Analysis] A project shows interest cover $2.02\times$ and debt/EBITDA $5.27\times$. The soundest interpretation is:

- A. the ratios contradict each other, so one must be wrong
- B. earnings service the interest comfortably while leverage is high — tolerable given contracted revenue, but dependent on that certainty ☒ **CORRECT**
- C. the project is over-leveraged regardless of revenue structure
- D. interest cover is the only relevant measure for a lender

Rationale: The two measure different things and both are true (2.4.2); what makes high leverage acceptable is revenue certainty. D ignores principal, which is why DSCR is covenanted.

MCQ 2.4-C [2.4.3 · Analysis] A sponsor asks "how much has the project spent?". The professional response is:

- A. quote the paid figure, as it is the most conservative
- B. ask which measure is meant — committed, incurred, invoiced, paid or capitalised — since they differ materially and all are defensible ☒ **CORRECT**
- C. quote the committed figure, as it is the most complete
- D. quote the capitalised figure, since it appears in the accounts

Rationale: Five defensible figures exist (2.4.3); answering without establishing which one is meant guarantees a later dispute. Each of A, C and D picks one arbitrarily.

MCQ 2.4-D [2.4.1 · Evaluation] A project's first operating year shows after-tax return on capital employed of 6.8000 % against a WACC of 7.9860 %, while the appraisal recorded an NPV of +16,179,360 and an IRR of 12.19 %. The soundest conclusion is:

- A. the appraisal was over-optimistic and should be revisited
- B. a single early-year accounting return on a fully-carried asset is not comparable with a lifetime discounted return; both figures are correct ☒ **CORRECT**
- C. the project is destroying value and should be restructured
- D. the WACC must be wrong, since the project was approved

Rationale: Accounting ROCE in year one is measured on the asset at its maximum carrying amount and rises mechanically as it depreciates (2.4.1) — year two is already 6.8486 % on unchanged EBIT. A and C treat a single-period ratio as a verdict on lifetime economics, the error Domains 3 and 4 exist to prevent; D reverses the logic of appraisal.

MCQ 2.4-E [2.4.2 · Analysis] A facility carries both a $1.20\times$ DSCR covenant and a $2.00\times$ interest-cover covenant. CFADS is 6,384,000, debt service 5,009,635.23, EBIT 5,100,000, interest 2,520,000, revenue 12,000,000 and the cash-to-revenue gearing 0.80. The binding covenant is:

- A. the DSCR covenant, because coverage tests are stricter in project finance
- B. the interest-cover covenant: it tolerates a 0.5000 % revenue fall against the DSCR covenant's 3.8796 % ☒ **CORRECT**
- C. neither — they bite at the same point by construction
- D. it cannot be determined without the lock-up threshold

Rationale: Restating both in revenue units gives 60,000 of headroom on interest cover against 465,547.16 on DSCR, a factor of 7.7591 (2.4.2). A substitutes convention for arithmetic; C asserts a relationship that does not exist; D treats a separate distribution test as necessary to a covenant comparison.

MCQ 2.4-F [2.4.3 · Analysis] At a construction data date a project has incurred 33,945,403 and capitalised 34,003,326. The most likely explanation is:

- A. an error, since capitalised cost cannot exceed cost incurred
- B. capitalised interest entered the asset without a supplier invoice, more than offsetting costs that failed the capitalisation test ✓ CORRECT
- C. the asset has been revalued upwards
- D. retention withheld has been added to the asset

Rationale: Capitalised interest of 677,923 exceeds the 620,000 of non-capitalisable owner's costs, so the asset legitimately carries 57,923 more than the cost report shows (2.4.3). A applies an intuition the reconciliation disproves; C invents a transaction; D confuses a payment timing item with a cost.

MCQ 2.4-G [2.4.2 · Evaluation] A sponsor has one amendment's worth of negotiating capital left on a facility carrying a 1.20× DSCR covenant and a 2.00× interest-cover covenant whose numerator is not defined. On Kestrel's figures the DSCR test tolerates a 3.8796 % revenue fall and the interest-cover test 0.5000 %. The amendment worth pursuing is:

- A. reduce the DSCR covenant to 1.15×, the largest single ratio concession available
- B. address the interest-cover test — delete it, or define its numerator as EBITDA, which is worth 0.9524 of coverage — because it is the binding covenant and tolerates under a seventh of the revenue miss the DSCR test does ✓ CORRECT
- C. seek a longer cure period on both covenants, which protects the sponsor whichever test fails
- D. leave both thresholds and negotiate the margin instead, since covenant levels are conventional while pricing is not

Rationale: restated in revenue units the interest-cover test bites at 60,000 of headroom against DSCR's 465,547 — a factor of **7.7591** — so the remaining capital belongs on the clause that will actually be breached, and an undefined numerator is the cheapest defect in the facility to fix (2.4.2). A concedes ground where none is needed: even at 1.15× the coverage test remains far slacker than the interest-cover test. C is genuinely useful and second-best — a cure period buys time after a breach rather than preventing one, and changes nothing about which test binds. D asserts a convention the arithmetic contradicts, and trades away protection on a covenant that can default the facility for basis points that cannot.

■ SELF-CHECK — KA 2.4

1. Why does project finance emphasise coverage over return ratios? — A ring-fenced SPV's credit case is whether its cash services its debt.
2. What does interest cover ignore? — Principal repayment; hence DSCR.
3. Name the five meanings of "spend". — Committed, incurred, invoiced, paid, capitalised.
4. State the leverage identity and where it fails. — $ROE = ROCE_{at} + (D/E)(ROCE_{at} - k_{d,at})$; exact on consistent (opening) bases, and broken by mixing opening, average and closing denominators — worth 1.1796 points of ROE here.
5. Which of Kestrel's two possible covenants binds, and by how much? — The 2.00× interest-cover test, tolerating a 0.5000 % revenue fall against the DSCR covenant's 3.8796 %.
6. Why can capitalised cost exceed cost incurred? — Capitalised interest enters the asset without an invoice, while non-capitalisable costs leave through the income statement.

— Advanced topics — Domain 2

2.A.1 Deferred tax, in principle

Accounting profit and taxable profit differ — most commonly because tax depreciation (capital allowances) runs on a different profile from accounting depreciation. Where the difference is **temporary**, deferred tax recognises the future consequence: accelerated tax depreciation reduces tax now and creates a **deferred tax liability** that unwinds as the difference reverses. For project models the practical significance is that **cash tax and accounting tax are different lines with different timing**, and it is cash tax that enters **CFADS** (Domain 6's model, Domain 10's ratios). Modelling accounting tax as if it were cash tax is a standard model-audit finding.

WORKED EXAMPLE

Worked example 2.A.1 — the deferred tax liability Kestrel's first year creates.

1. **Setup.** The master statements assume tax depreciation equals accounting depreciation, so no temporary difference arises and tax of 516,000 is both charged and paid. Suppose instead the jurisdiction grants **declining-balance capital allowances at 15 %** on the 60,000,000 base, with losses carried forward — the assumption Domain 6 (KA 6.2.3) prices on the cash side. Accounting depreciation stays at 2,400,000 and the tax rate at 20 %. To isolate the fixed-asset difference, assume no deferred tax asset is recognised on the carried-forward loss — an assumption stated because it is itself a recognition judgment, and one returned to below. Compute the temporary difference, the deferred tax liability, the accounting tax charge and the resulting net income, and identify when the difference begins to reverse.
2. **Formula.** Temporary difference = carrying amount – tax written-down value. Deferred tax liability = temporary difference × tax rate. Total tax charge = current (cash) tax + movement in the deferred tax liability. The difference begins to reverse in the first year the capital allowance falls below accounting depreciation.
3. **Substitution.** Year-one allowance $60,000,000 \times 0.15 = 9,000,000$, so tax written-down value 51,000,000 against a carrying amount of 57,600,000; difference 6,600,000; liability $6,600,000 \times 0.20$. Domain 6 computes the year's cash tax as **nil**, the allowance and interest having produced a tax loss of 4,020,000 carried forward.
4. **Result.**

Line	Master assumption	15 % declining balance
Accounting depreciation	2,400,000	2,400,000
Capital allowance claimed	2,400,000	9,000,000
Carrying amount / tax written-down value	57,600,000 / 57,600,000	57,600,000 / 51,000,000
Temporary difference	nil	6,600,000
Deferred tax liability	nil	1,320,000
Current (cash) tax	516,000	nil
Total tax charge	516,000	1,320,000
Net income	2,064,000	1,260,000
CFADS / DSCR	6,384,000 / 1.2743	6,900,000 / 1.3773

1. **Interpretation.** The two columns describe the same project in the same year, and **they move in opposite directions**: net income falls by **804,000** while **DSCR** rises by **0.1030**. That opposition is the whole content of this topic. Accelerated allowances defer cash tax, which is good for coverage; the deferred tax charge that records the future consequence is bad for profit; and an entity reporting both is neither better nor worse off than the accounting suggests. A sponsor presenting the profit column to a board and the coverage column to lenders is presenting two true statements and one misleading impression.

Three disciplines follow. **The liability is not a debt and must not be treated as one.** It is not owed to anyone on any date, carries no interest and is not enforceable; leverage covenants defined on "total liabilities" rather than on financial indebtedness can capture it, and a covenant that tightens because a tax authority granted an allowance is a drafting accident worth finding before signature. **The reversal is datable, and the date matters.** With a 15 % declining balance the allowance falls below 2,400,000 for the first time in **year 10** (2,084,552.52 against 2,400,000), the temporary difference peaks in **year 9** at **24,502,983.22** — a deferred tax liability of **4,900,596.64** — and unwinds thereafter. So the profile is a decade of profit suppressed by deferred tax followed by years of profit flattered by its release, on a project whose trading may be perfectly flat: any trend read off the profit line across that turning point is an artefact. **And the deferred tax asset side is where optimism hides.** Where the allowance creates a tax loss, recognising a deferred tax asset on it requires convincing evidence of future taxable profit against which to use it, which is a forecast, not a fact. Whether such an allowance regime exists, whether losses carry forward and for how long, whether a deferred tax asset may be recognised, and at what rate the balances are measured are all jurisdiction-specific and subject to legislative change over a twelve-year loan; the arithmetic above is transferable, the treatment is a matter for qualified tax advice, and Domain 11's risk register — not the model's base case — is where a legislative assumption belongs.

2.A.2 Leases and off-balance-sheet intuitions

Under current thinking a lessee generally recognises a right-of-use asset and a lease liability, so the older intuition that operating leases keep obligations off the balance sheet no longer holds (IFRS 16 is the reference framework, in principle). Two consequences for a finance leader: leverage ratios computed across periods spanning the change are not comparable, and covenant definitions written before it may capture or exclude lease liabilities in ways nobody intended — a live reason to read the definitions in finance documents rather than assume them.

The size of the effect is worth computing, because the intuition is usually wrong in an instructive way. Suppose Kestrel leases its intake corridor and site access for **USD 500,000** a year over ten years, discounted at **6.0 %**. At $AF(6\%, 10) = 7.360087$ the liability recognised is **USD 3,680,043.53** — **9.3141 %** of the senior debt, a substantial-looking addition. Yet the leverage ratio barely moves, because the same change removes 500,000 from operating costs and replaces it with depreciation and interest:

Measure	Before	After
Debt for the ratio	39,510,364.77	43,190,408.30
EBITDA	7,500,000	8,000,000
Debt/EBITDA	5.2680×	5.3988×

A liability of 3,680,043.53 moved the ratio by **0.1308** — because the numerator and the denominator both rose. Compute it the way an unwary analyst would, adding the liability while leaving EBITDA untouched, and the answer is **5.7587×**, an apparent deterioration of 0.4907 that is **3.75 times** the real one. Two conclusions, and neither is about leases. **A ratio is only comparable when every line in it is restated consistently**, which is the same discipline as KA 2.4.1's return bases. And **the covenant definition decides the outcome, not the accounting framework**: where the test is struck on "financial indebtedness" as defined in the facility agreement, a lease liability recognised under a reporting framework may not enter the covenant at all, and the ratio the lender enforces does not move by 0.1308 or by anything else. Which of those applies to a given facility is a question for the finance documents and for counsel, and is exactly the sort of matter Toolkit 2.T.1 exists to record.

2.A.3 The reviewer's statement eye

Invariants to test on any statement set before relying on it: the balance sheet balances; closing cash on the cash-flow statement equals balance-sheet cash; closing equity equals opening plus profit less distributions plus contributions; depreciation in the cash-flow statement equals the income-statement charge; the movement in debt equals drawings less principal repaid; principal appears in financing and interest in operating (or as disclosed); working-capital movements reconcile to balance-sheet deltas; and any ratio quoted can be recomputed from the face of the statements. A set that fails any of these has an error, an omission, or a policy that needs explaining — and the failure point localises it.

2.A.4 Distributable reserves — the constraint that is not in the waterfall

A cash waterfall says what money is available to distribute (Domain 15, KA 15.2.3). It does not say what an entity is permitted to distribute, and in most company-law systems those are different questions with different answers. The permission side typically turns on **accumulated realised profits** — a balance-sheet test on retained earnings, not a cash test — so an SPV can hold cash the finance documents release and still be unable lawfully to pay it out.

The point is easiest to see at the end of construction, where it bites hardest. The master statements in KA 2.2 capitalise the whole 60,000,000 envelope into the plant, for exposition; take instead Worked example 2.4.3's illustration, in which **620,000** of owner's general and administrative costs fail the capitalisation test and are expensed, so that plant is carried at **59,380,000** and retained earnings open at **-620,000**. Kestrel then reaches its commercial operations date with no distributable reserve whatever, while holding cash and having satisfied every condition to a drawdown. Year one's net income of 2,064,000 restores the balance to **1,444,000**, and Domain 6's

first-year distribution of **121,955.96** is **8.4457 %** of it — comfortable, but only because the year was profitable. Three consequences a leader should hold.

The binding test can switch between cash and reserves without warning. In year one the constraint is cash and the waterfall: 121,955.96 of distributable cash against 1,444,000 of reserves. In a year with an accounting loss — a deferred tax charge (2.A.1), a decommissioning re-measurement (2.3.4), an impairment — the reserves can become the binding constraint while **CFADS** is untouched, so a project passing its **DSCR** test comfortably makes no distribution at all. That is the mirror image of Case study B and it surprises sponsors more, because nothing in the finance documents predicts it.

Accounting judgments therefore have a distribution consequence even where covenants are cash-based. The capitalisation boundary decided how much of the owner's cost was expensed; expensing it created the negative opening reserve. A decision taken on technical accounting grounds during construction set the date on which equity could first be paid.

And this is a legal question before it is an accounting one. What constitutes a distributable profit, whether interim accounts may support a distribution, what solvency or net-asset test applies alongside it, and what the consequences of an unlawful distribution are for the directors who declared it and the shareholders who received it, vary materially between jurisdictions and are matters for counsel in the jurisdiction of incorporation. The practical discipline is narrow: **include a distributable-reserves line beside the distributable-cash line in every distribution paper**, and confirm the legal test with counsel once per financing rather than once per dividend.

— Industry variations — Domain 2

- **Energy and resources.** Decommissioning provisions are first-order balance-sheet items, recognised decades before the cash flows; commodity revenue makes recognition timing and hedge accounting material.
- **Transport concessions and PPPs.** The central question is what the operator actually holds — a financial asset (an unconditional right to cash from the grantor), an intangible right to charge users, or a mixture — and the answer changes the whole statement profile for identical economics. Framework treatment is specialised and advice-led.
- **Water and regulated utilities.** Regulatory asset bases and their depreciation profiles may diverge from statutory accounting; two "asset values" coexist and must never be conflated.
- **Digital infrastructure.** Shorter useful lives and heavy refresh capex make the capex/opex boundary (2.3.3) a recurring judgment with large profit consequences.
- **Construction and EPC.** Over-time revenue recognition and onerous-contract provisions are the operative treatments, and the input-versus-output progress choice (2.3.2) is where accounting and project controls must agree or explain.

— Case study — Domain 2: the profitable year that nearly broke a covenant (water)

Situation. Kestrel Water SPC's first operating year closes on the figures above: net income USD 2,064,000, **EBITDA** USD 7,500,000 — a good year by any account. The finance director's draft lender report quotes **DSCR 1.39** and describes headroom as comfortable against the facility's **1.25** distribution condition.

Which threshold, and why it matters that the report picked one. Kestrel's facility tests coverage at the three levels tabulated in KA 2.3.1B — a 1.25× distribution condition, a 1.20× financial covenant and a 1.15× lock-up trigger, whose consequences Domain 10 (KA 10.4) builds. The draft report compared its figure against the distribution condition alone, which is the least severe of the three and the only one whose failure costs a dividend rather than triggering an event of default.

The problem. The facility's definition of **CFADS** is struck **after** movements in working capital. Kestrel's receivables had grown USD 900,000 as the offtaker's payment process settled into a slower rhythm than modelled, against a USD 300,000 rise in payables — a net USD 600,000 absorbed. On the documented definition, **CFADS** is USD 6,384,000 and **DSCR** is **1.27**, not 1.39. Headroom against the 1.25 distribution condition is USD 0.02 of ratio — **USD 121,956 of cash** — not the comfortable margin reported. Against the 1.20 covenant the headroom is **USD 372,438**, or **5.8 %** of **CFADS**, which is the figure Domain 10 (WE 10.2.1) computes and the one a board paper should carry. And note what the definitional choice cost: on the pre-working-capital figure the covenant headroom would have looked like **USD 972,438**, so **USD 600,000 — 61.7 % of the apparent margin — was never there.**

The margin, restated in the units that caused it. The board's question — how close was this? — has a better answer than 0.02 of ratio. Kestrel's **DSCR** of 1.2743 corresponds to a collection period of **27.3750 days**; the 1.25 distribution condition is reached at **31.0845 days** and the 1.20 covenant at **38.7033 days** (KA 2.3.1B). The comfortable margin the draft report described was therefore **3.7095 days of collection** before the dividend stopped, and 11.3283 days before the covenant failed. At **32,876.71 of cash and 0.006563 of DSCR per day**, the offtaker's payment run slipping by a single week would have cost 0.0459 of coverage on its own. Expressed that way the finding was actionable inside a fortnight; expressed as two decimal places of a ratio it had sat in three consecutive board packs.

What was done. The report was corrected before issue. More consequentially, the near-miss changed three things: collections became a monitored operational metric with a named owner (not a finance afterthought), reported weekly in days rather than quarterly in dollars; the model's working-capital assumptions were re-based on nine months of actual collection behaviour rather than the financial-close assumption; and the treasury team sized a working-capital facility as a liquidity buffer, calibrated on the observed distribution of the offtaker's payment dates against the **1,021,955.96** of receivables that the 1.25× condition tolerates. The following year's **DSCR** came in at 1.41 on the documented definition.

What the domain teaches here. The professional content is definitional, and then it is translational. A ratio is only as good as the defined term inside it, and the definition lives in the finance documents, not in convention — that is the first lesson and the one that corrected the report. The second is the one that changed the company: **a covenant that is not expressed in a unit someone owns is not being managed.** "Maintain **DSCR** above 1.25" is owned by nobody; "keep **DSO** below 31 days" is owned by a named person with a weekly number. It also shows the accrual/cash divergence of KA 2.1.1 doing real damage — a genuinely profitable year came within USD 100,000 of a covenant breach because of a balance-sheet movement no one was watching, and the movement was 3.7 days long.

— Case study B — Domain 2: capitalised into a better-looking year (digital infrastructure)

Situation. A data-centre operator overhauled cooling across three sites for USD 9,000,000, capitalised as an enhancement and depreciated over 12 years — a year-one charge of USD 750,000 rather than USD 9,000,000, lifting reported profit by USD 8,250,000 relative to expensing it.

What happened. The auditors challenged the classification: on inspection, roughly two-thirds of the spend restored the original design capacity rather than extending it, which is maintenance. The restatement moved USD 6,000,000 into operating expense, turned a reported profit into a loss, and breached a profit-based covenant in a holding-company facility. No cash flow changed at any point, and the project's **DSCR** — a cash-based test — was unaffected throughout.

What the domain teaches here. Accounting classification is judgment applied to facts, and it is auditable. The wider lesson is why lenders to projects prefer cash-based covenants: the **DSCR** was indifferent to a classification argument that flipped the profit-based test from comfortable to breached. A leader should know which of their covenants are exposed to accounting judgment and which are not.

— Case study C — Domain 2: the quarter the progress measures disagreed (construction / EPC)

Situation. The contractor building Kestrel's plant reports quarterly on a **USD 48,000,000** lump-sum contract. At the quarter-five data date it had incurred **USD 27,000,000** and forecast **USD 15,000,000** to complete, so on its cost-input measure the job was **64.2857 %** done and it recognised revenue of **30,857,142.86** and cumulative profit of **3,857,142.86**. The SPV, on the same date, had certified **61 %** of the milestone schedule — output revenue of 29,280,000 and cumulative profit of 2,280,000 on the same costs. Two systems, one job, **1,577,142.86** apart, which is **26.2857 %** of the contract's whole expected margin.

How the gap was read, and misread. The contractor's commercial team treated the 3.2857-point difference as a certification lag: the works were in place and the SPV's engineer had not yet signed. The SPV's technical adviser read the same gap the other way — costs were running ahead of physical progress on the marine works, where a seabed condition had required additional grouting that was not a variation. Both explanations fit the numbers, and the systems could not adjudicate between them, because on a fixed-price milestone certification the SPV's own earned value shows **CPI = 1.0000** by construction (Domain 14, KA 14.2.1) and can therefore never see a contractor cost overrun at all. What settled it was neither system but the evidence underneath: grouting quantities against the design, which supported the adviser.

What followed. The re-forecast raised the cost to complete to **USD 22,500,000**, taking expected total costs to **49,500,000** against the 48,000,000 price. The contract was **onerous by 1,500,000**, and because 3,857,142.86 of profit had already been recognised, the charge in the quarter was **USD 5,357,142.86 — 3.5714 times** the loss it reported. The contractor's quarterly result moved from a modest profit to a substantial loss on a job whose physical progress had not changed at all that quarter. Nothing in the SPV's accounts moved: the price was fixed, so the SPV's cost, asset and **DSCR** were untouched, and its exposure was entirely to the contractor's solvency and to the delay that the additional works implied — which is where a lender's monitoring should have been looking, and was not.

What the domain teaches here. KA 2.3.2 supplies the mechanics — that neither an accounting percentage nor a certified percentage can settle a progress dispute on its own (PML-AI, Domain 7, KA 7.3.1), and that the onerous charge is dominated by the reversal rather than by the loss. What the quarter adds is the consequence for the party whose accounts do not move: **a fixed price protects the SPV's statements and not the SPV.** The counterparty risk a loss-making contract creates appears nowhere in the SPV's accounts, so it has to be monitored through the contractor's — a diligence and covenant-design question (Domain 12, KA 12.1; Domain 14, KA 14.2.1) rather than an accounting one. It is also why what settled this dispute was grouting quantities and not a percentage: where two measurement systems disagree, the adjudicating evidence is always underneath both of them.

— Executive perspective — Domain 2

What a project finance director cannot delegate in this domain:

- **The definitions.** [CFADS](#), [EBITDA](#), "net debt", "spend" — the director asks what the defined term is in the documents before quoting any ratio built on it (Case study A).
- **The accrual/cash bridge.** Being able to explain, unprompted, why profit and cash differ this period — and what is absorbing the difference.
- **The policy exposures.** Which covenants can be moved by an accounting judgment (capex/opex, revenue timing, provisions) and which cannot.
- **Working capital as an operational matter.** Collections and payment terms are cash decisions with covenant consequences, owned by named people, not finance hygiene — expressed as a days target (31 days, not 1.25×) so that somebody can act on it.
- **The interface discipline.** Insisting project and ledger reconcile, and never letting the five meanings of "spend" circulate interchangeably.
- **Knowing which covenant binds.** Not which covenant sounds strictest: the director can state, in revenue units, which single test fails first — for Kestrel a 0.5000 % revenue fall on interest cover against 3.8796 % on [DSCR](#).
- **Refusing accounting returns as project verdicts.** A first-year [ROCE](#) below [WACC](#) on a project with a +16,179,360 [NPV](#) is arithmetic, not news, and a director who cannot say why will approve and reject the wrong things.
- **The permission to distribute, not just the cash to distribute.** Distributable reserves and distributable cash are different tests with different answers (2.A.4), and only one of them is in the waterfall.

— Calculation exercises — Domain 2

Exercise 2.1 Revenue 15,000,000; cash operating costs 5,800,000; asset 75,000,000 depreciated over 30 years; interest 2,100,000; tax 20 %. Build the income statement to net income. Solution. [EBITDA 9,200,000](#); depreciation $75,000,000/30 = 2,500,000$; [EBIT 6,700,000](#); [PBT 4,600,000](#); tax [920,000](#); net income [3,680,000](#). Common error: taxing [EBIT](#) rather than [PBT](#) (giving 1,340,000 and overstating tax by 420,000).

Exercise 2.2 From Exercise 2.1, receivables rose 1,100,000, inventory rose 200,000 and payables rose 450,000. Compute operating cash flow. Solution. $3,680,000 + 2,500,000 - 1,100,000 - 200,000$

+ 450,000 = **USD 5,330,000**. Common error: signing payables negative — supplier credit is a cash source.

Exercise 2.3 Using Exercise 2.1–2.2 and annual debt service of 4,400,000, compute **DSCR** both before and after working-capital movements ($CFADS = EBITDA - \text{tax} [- \Delta WC]$). Solution. Before: $(9,200,000 - 920,000)/4,400,000 = 8,280,000/4,400,000 = \mathbf{1.88}$. After: $\Delta WC 1,100,000 + 200,000 - 450,000 = 850,000$; $7,430,000/4,400,000 = \mathbf{1.69}$. Common error: using net income instead of **EBITDA** in **CFADS** (double-counting interest, which debt service already includes).

Exercise 2.4 USD 2,400,000 is spent on plant modification, capitalised over 8 years versus expensed. State the year-one profit difference and the cash difference. Solution. Capitalised charge $2,400,000/8 = \mathbf{300,000}$; expensed **2,400,000**; profit difference **USD 2,100,000**; cash difference **nil** before tax. Common error: assuming a cash difference because the profit effect is large — and the opposite error of asserting there can never be one, since where the tax deduction follows the accounting treatment the timing of relief differs (2.3.3).

Exercise 2.5 Continue Exercises 2.1–2.3. The project opened the year with plant 75,000,000, cash nil, senior debt 52,500,000 and equity 22,500,000, and no receivables, inventory or payables. Debt service was 4,400,000 including 2,100,000 of interest. There were no distributions, contributions or capex. Complete the closing balance sheet and prove it balances. Solution. Principal $4,400,000 - 2,100,000 = \mathbf{2,300,000}$; closing cash $5,330,000 - 2,300,000 = \mathbf{3,030,000}$; plant net **72,500,000**; closing debt **50,200,000**; closing equity $22,500,000 + 3,680,000 = \mathbf{26,180,000}$. Assets $72,500,000 + 1,100,000 + 200,000 + 3,030,000 = \mathbf{76,830,000}$; liabilities and equity $450,000 + 50,200,000 + 26,180,000 = \mathbf{76,830,000}$. Check by the second route: $CFADS - \text{debt service} = 7,430,000 - 4,400,000 = \mathbf{3,030,000}$, the same cash. Common error: deducting the whole 4,400,000 instalment from operating cash flow, which double-counts the interest already inside it and understates cash by 2,100,000.

Exercise 2.6 The same project's facility carries a **1.60× DSCR** covenant, with **CFADS** struck after working capital. Inventory stays at 200,000 and payables at 450,000. Revenue is 15,000,000 and receivables opened at nil. Express the covenant as a maximum days-sales-outstanding figure at a 365-day convention, and state the headroom in days. Solution. **CFADS** before working capital $9,200,000 - 920,000 = \mathbf{8,280,000}$; trigger $1.60 \times 4,400,000 = \mathbf{7,040,000}$; allowable absorption **1,240,000**; allowable receivables $1,240,000 - 200,000 + 450,000 = \mathbf{1,490,000}$; maximum **DSO** $1,490,000/15,000,000 \times 365 = \mathbf{36.2567 \text{ days}}$ against an actual $1,100,000/15,000,000 \times 365 = \mathbf{26.7667 \text{ days}}$ — headroom **9.4900 days**. Actual **DSCR** after working capital is **1.6886**. Common error: forgetting that inventory consumes and payables release, so the allowable receivables figure is not the allowable absorption figure.

Exercise 2.7 A concession requires site restoration costing USD 6,000,000 in 20 years, discounted at 6.0 %. Compute the provision recognised, the year-one accretion, the year-one depreciation of the restoration asset, the total year-one charge and the year-one cash effect. Solution. Provision $6,000,000/1.06^{20} = \mathbf{1,870,828.36}$; accretion $1,870,828.36 \times 0.06 = \mathbf{112,249.70}$; depreciation $1,870,828.36/20 = \mathbf{93,541.42}$; total charge **205,791.12**; cash effect **nil**. The provision closes year one at **1,983,078.06** and the total charged over the 20 years is **6,000,000** — the settlement amount. Common error: charging accretion alone and forgetting that recognising the provision also created a depreciable asset.

Exercise 2.8 From Exercises 2.1 and 2.5, compute the current ratio, debt/equity, net debt, net debt/EBITDA, pre-tax ROCE on closing capital employed, interest cover, and then test the leverage identity on opening balances. Solution. Current ratio $4,330,000/450,000 = 9.6222$; debt/equity $50,200,000/26,180,000 = 1.9175$; net debt $50,200,000 - 3,030,000 = 47,170,000$; net debt/EBITDA 5.1272 ; ROCE $6,700,000/76,380,000 = 8.7719\%$; interest cover $6,700,000/2,100,000 = 3.1905\times$. Identity: after-tax ROCE on opening capital $5,360,000/75,000,000 = 7.1467\%$; after-tax cost of debt $2,100,000/52,500,000 \times 0.80 = 3.2000\%$; D/E 2.3333 ; $7.1467 + 2.3333 \times (7.1467 - 3.2000) = 16.3556\%$, equal to $3,680,000/22,500,000 = 16.3556\%$ to the digit. Common error: testing the identity with ROCE on closing capital and ROE on closing equity, which breaks it and produces a "discrepancy" that is only a change of denominator.

Exercise 2.9 At a construction data date a project reports committed 24,000,000, cash paid 14,600,000, retention withheld 700,000, approved unpaid invoices 260,000, certified value not yet invoiced 540,000 and an unrecovered advance payment of 900,000. Compute open commitments, incurred and invoiced. Solution. Open commitments $24,000,000 - 14,600,000 - 700,000 - 260,000 - 540,000 + 900,000 = 8,800,000$; incurred $14,600,000 + 700,000 + 260,000 + 540,000 - 900,000 = 15,200,000$; invoiced $15,200,000 - 540,000 = 14,660,000$. Common error: adding the unrecovered advance rather than deducting it — it is cash paid for value not yet received, so it reconciles with the opposite sign to every other item.

Exercise 2.10 An asset costs 75,000,000, is depreciated straight-line over 30 years and attracts capital allowances at 20 % on a declining balance. The tax rate is 20 %. Compute the deferred tax liability at the end of year two and the year-two deferred tax charge. Solution. Year-one allowance $15,000,000$, tax written-down value $60,000,000$, carrying amount $72,500,000$, difference $12,500,000$, liability $2,500,000$. Year-two allowance $0.20 \times 60,000,000 = 12,000,000$, tax written-down value $48,000,000$, carrying amount $70,000,000$, cumulative difference $22,000,000$, liability $4,400,000$. The year-two charge is the movement, $1,900,000$, which equals $0.20 \times (12,000,000 - 2,500,000)$. Common error: computing the liability on the year's difference in charges rather than on the cumulative difference between carrying amount and tax written-down value — the two coincide in year one and diverge every year after, so the error is invisible exactly once.

Exercise 2.11 A contractor on a 30,000,000 fixed-price contract has incurred 12,000,000 and forecasts 13,000,000 to complete. Compute progress, revenue and cumulative profit on a cost-input measure. Then the forecast to complete rises to 20,000,000: state the expected loss and the charge in that period. Solution. Expected total cost $25,000,000$; progress $12,000,000/25,000,000 = 48.0000\%$; revenue $30,000,000 \times 0.48 = 14,400,000$; profit to date $2,400,000$. Revised total cost $32,000,000$, so the contract is onerous by $2,000,000$; the cumulative position must move from $+2,400,000$ to $-2,000,000$, giving a period charge of $4,400,000 - 2.2000$ times the loss. Common error: recognising the 2,000,000 loss and leaving the 2,400,000 of recognised profit in place, which overstates the cumulative result by 2,400,000 and spreads a known loss into the future.

— Practitioner's toolkit — Domain 2

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 2.T.1 — Defined-terms sheet (one per financing)

For each term used in a covenant or report — [CFADS](#), [EBITDA](#), net debt, distributable cash, project costs — record: the **document and clause** defining it, the definition in plain words, what is included and excluded (working capital? cash tax or accrued? maintenance capex?), the model line implementing it, and the person who confirmed the match. A ratio quoted without a row here is not reportable (Case study A).

Toolkit 2.T.2 — Accrual-to-cash bridge (standing monthly schedule)

Net income · + depreciation and amortisation · + other non-cash charges (provisions) · – Δreceivables · – Δinventory · + Δpayables · = operating cash flow · – capex · – principal · – distributions · = movement in cash, **tied to the cash balance**. Rule: it is published even in good months, because its purpose is to make divergence visible before it is material.

Toolkit 2.T.3 — Statement-integrity checklist

- [] Balance sheet balances; closing cash ties to the cash-flow statement.
- [] Closing equity = opening + profit – distributions + contributions.
- [] Depreciation in the cash-flow statement equals the income-statement charge.
- [] Debt movement = drawings – principal repaid; only interest is expensed.
- [] Working-capital movements reconcile to balance-sheet deltas.
- [] Every quoted ratio recomputable from the face of the statements, on its defined terms.
- [] Capitalisation boundary and any policy change disclosed and explained.
- [] Return ratios state their basis (opening, average or closing) — the leverage identity holds on one basis only, and mixing them moved Kestrel's [ROE](#) by 1.1796 points.
- [] Interest paid identified as operating or financing, and the [CFADS](#) identity applied only to the operating presentation.
- [] Cash split into unrestricted and reserve balances; 91.1264 % of Kestrel's was restricted.
- [] Each covenant restated in revenue units, so the binding test is known rather than assumed.
- [] Distributable reserves stated beside distributable cash in any distribution paper.

— Exam preparation — Domain 2

The traps. Expensing the whole debt instalment instead of interest only (MCQ 2.2-C) · taxing [EBIT](#) rather than PBT (Exercise 2.1) · signing payables the wrong way in the cash bridge (Exercise 2.2) · using net income in [CFADS](#) and double-counting interest (Exercise 2.3) · assuming a cash difference from a capex/opex choice, or asserting there can never be one (Exercise 2.4) · deducting the whole instalment from operating cash flow when deriving closing cash (Exercise 2.5) · confusing the distribution threshold's [DSO](#) limit with the covenant's (MCQ 2.3-E) · quoting a [DSCR](#) without its [CFADS](#) definition (2.3.1) · reading an interest classification as an economic difference in operating cash flow (MCQ 2.2-F) · recognising a provision on estimability alone without probability (2.3.4) · charging a provision's accretion and forgetting the asset it created (Exercise 2.7) · recognising an onerous loss without reversing the profit already taken (MCQ 2.3-G, Exercise 2.11) · mixing opening, average and closing bases in a return ratio, which breaks the leverage identity (Exercise 2.8) · computing a deferred tax liability on the year's difference in charges rather than the cumulative temporary difference (Exercise 2.10) · adding rather than deducting an unrecovered advance in a spend reconciliation (Exercise 2.9) · assuming capitalised cost cannot exceed cost incurred (MCQ 2.4-F) · treating accounting tax as cash tax (2.A.1) · comparing leverage across a period spanning a policy

change, or restating only the numerator (2.A.2) · treating distributable cash as permission to distribute (2.A.4).

Reflection questions.

1. For your current financing: what exactly does **CFADS** include, and where is that written down?
2. Which of your covenants could be moved by an accounting judgment rather than a change in economics — and who reviews those judgments?
3. When someone last told you what a project had "spent", which of the five measures was it — and did you ask?
4. Restate your tightest covenant in a unit somebody owns — days of collection, points of availability, a unit cost. Who is that person, and do they know?
5. If your project were to report an accounting loss in a year of unchanged cash flow, could it still lawfully distribute — and who has confirmed that?

— Domain 2 summary

Accrual accounting records effects when they occur and cash accounting records money when it moves; both matter, because covenants are written on each and they diverge in ways that are information rather than noise. Recognition and measurement are governed by tests, and the policies chosen shape reported figures without touching economics — which is why statements are read sceptically and why the three of them, locked together by articulation, are stronger evidence than any one alone. Kestrel's first year demonstrates the machinery end to end: **EBITDA** 7,500,000 descending through depreciation, interest and tax to net income 2,064,000, then bridged back to operating cash flow of 3,864,000 by adding non-cash depreciation and deducting the 600,000 that working capital absorbed — the same 600,000 that separates the year's accrual and cash results and sits, findable, as the closing net working-capital balance. The same bridge built by the direct method gives the identical 3,864,000 out of gross flows that are far more useful: 11,100,000 collected, **92.50 %** of revenue recognised. From there the statements close themselves. Deducting the 2,489,635.23 of principal — a balance-sheet movement, not an expense — leaves cash of **1,374,364.77**, which is also **CFADS** less debt service, which is also Domain 9's annual distributable cash, which Domain 6 then splits exactly into a 1,252,408.81 reserve instalment and a 121,955.96 distribution; and the balance sheet totals **59,874,364.77** on both sides with nothing plugged. Two breakevens sit inside the same income statement and they settle the book's opening claim: profit reaches nil at a 21.50 % revenue fall and coverage reaches 1.00 at 14.32 %, so **the cash constraint binds first, by seven revenue points**.

The project-relevant treatments each carry a professional edge. Working capital moved Kestrel's **DSCR** from 1.39 to 1.27 on the documented **CFADS** definition, within USD 100,000 of a covenant — and restated in the unit that caused it, the whole dividend rested on **3.7095 days** of collection, against a covenant reached at 38.7033 days. The capex/opex choice moved a year's profit by 1,080,000 on 1,200,000 of spend while pre-tax cash was unchanged, though where the deduction follows the accounting the after-tax difference is a real **78,958.05** of present value. Revenue recognition follows performance, and an input measure running 3.2857 points ahead of certification was worth 1,577,142.86 of profit before a re-forecast turned it into a 5,357,142.86 charge — **3.5714 times** the 1,500,000 loss it reported, because the profit already taken must be reversed. Provisions are measured, not chosen: a 4,500,000 restoration obligation is recognised at **1,328,862.47**, charges **119,597.62** in its first year with no cash effect, moves 27.0279 % on a 100-basis-point change of rate, and accretes to exactly the amount eventually paid.

Ratios are comparisons whose value lies in what they are compared against. Read as a set they yield the leverage identity — $6.8000\% + 2.3333 \times (6.8000\% - 4.8000\%) = 11.4667\%$, exact on opening bases and broken by mixing them — a first-year after-tax **ROCE 1.1860 points below** Domain 9's **WACC** on a project with a +16,179,360 **NPV**, and the discovery that a 2.00× interest-cover covenant would bind **7.7591 times** sooner than the 1.20× **DSCR** covenant beside it. And the five meanings of "spend" differ by **20,451,403** — 34.0857 % of the envelope — on one date, reconciling to a single identity in which the unrecovered advance carries the opposite sign and the capitalised figure legitimately exceeds the incurred one. Domain 3 supplies the discounting these statements are valued with; Domain 6 turns them into a model and adds the reserve account that spends the closing cash balance; Domain 10 turns **CFADS** into the covenants a lender actually enforces; and Domain 15 watches the working-capital line move against the project in both directions.

03

DOMAIN 3

Time Value of Money and Financial Mathematics

— Why this domain exists

Every judgment a project finance leader makes — whether an investment is worth making (Domain 4), how much debt a project can carry (Domain 10), what a concession's payment stream is worth (Domain 7), whether a delay destroys value (Domain 8) — reduces at some point to one question: what is money at one date worth at another date? Time value of money (TVM) is the machinery that answers it. This domain builds that machinery from first principles: interest and growth (KA 3.1), the annuity family and loan schedules that debt structures are made of (KA 3.2), and the adjustments — inflation, escalation and currency — that separate a defensible model from a spreadsheet accident (KA 3.3). Nothing in this domain is optional equipment: the financial models of Domain 6 are, in the end, disciplined arrangements of exactly these calculations, and the coverage ratios lenders live by (Domain 10) are discounted cash flows wearing covenants.

Learning objectives. After this domain a candidate can: distinguish simple and compound interest and compute either; move any cash amount across time with $FV(x)$ and $PV(x)$ and read a discount-factor table; value level streams with annuity and perpetuity formulae, and **indexed (growing) streams** with the real-rate identity that collapses them onto the same machinery; build and check a loan schedule in all four shapes a term sheet offers — annuity, level-principal, bullet and repayment holiday — and compute the **outstanding balance at any date** two independent ways; **solve the inverse problems**, finding the rate implied by a price and the term implied by a payment; convert between nominal, periodic and effective rates and say what a payment frequency does that a compounding frequency does not; keep nominal and real quantities consistent using the Fisher relation, and **price the error** when they are mixed; escalate costs and revenues defensibly, including caps, floors and indexation lags; state how currency and forward rates enter project cash flows and prove that the two routes to a hedged value agree; apply a day-count convention over a full year and across a whole facility; and apply the governed-AI rule to any machine-produced calculation of these kinds.

The master financing. One fictional project runs through this domain and returns in Domains 4, 6 and 10. **Kestrel Water SPC** is a special-purpose company developing a seawater desalination plant inside a **USD 60,000,000** capital envelope funded 70/30. Its senior lenders offer a **USD 42,000,000** loan repayable over **12 years at 6.0 %** annual interest, against **USD 18,000,000** of equity; the offtaker will pay an **availability payment of USD 5,600,000 per year for 25 years**; Kestrel's board evaluates offers at a discount rate of **8.0 %**. Two further figures from the sibling domains are used here as given inputs rather than re-derived: Kestrel's documented first-year cash available for debt service, **CFADS USD 6,384,000** (Domain 2, KA 2.2; Domain 10, KA 10.1.1), which lets every schedule in this domain be read for its coverage consequence, and the **USD 840,000** arrangement fee inside the funding envelope (Domain 6, KA 6.2.1), which lets the domain's inverse-rate machinery be demonstrated on a real term sheet. All of these numbers are used repeatedly below — by the end

of the domain the reader can price every side of Kestrel's deal, and every quoted figure ties to the digit across Domains 4, 6, 9 and 10.

KNOWLEDGE AREA 3.1

Interest and value

Topics: 3.1.1 simple and compound interest · 3.1.2 present and future value · 3.1.3 discount factors.

3.1.1 Simple and compound interest

Definitions. Interest is the price of money over time. Under **simple interest** the charge accrues on the original principal only:

$$FV(x) = x \times (1 + r \times n) \quad \text{— simple interest}$$

Under **compound interest** each period's interest joins the principal and itself earns interest:

$$FV(x) = x \times (1 + r)^n \quad \text{— compound interest}$$

where x is the amount today (currency), r the interest rate per period (ratio) and n the number of periods (count). Project finance is a compound-interest world: loans, discounting, escalation and returns all compound. Simple interest survives only in narrow corners — short-duration instruments, some penalty-interest clauses, and certain Islamic-finance structures that avoid interest altogether and price time differently (Domain 9, KA 9.3).

The principle. Compounding is growth on growth. Its effect looks negligible over one or two periods and decisive over ten: the gap between the two formulae widens geometrically, which is why long-life infrastructure — concessions of 25 to 40 years — is acutely sensitive to the rate used.

WORKED EXAMPLE**Worked example 3.1.1 — the same deposit, two rules.**

1. **Setup.** USD 100,000 is placed for 3 years at 8.0 % per year. Compare simple and compound growth.
2. **Formula.** Simple: $FV(x) = x(1 + rn)$. Compound: $FV(x) = x(1 + r)^n$, with $x = 100,000$, $r = 0.08$, $n = 3$.
3. **Substitution.** Simple: $100,000 \times (1 + 0.08 \times 3) = 100,000 \times 1.24$. Compound: $100,000 \times 1.08^3 = 100,000 \times 1.259712$.
4. **Result.** Simple: **USD 124,000**. Compound: **USD 125,971** (125,971.20 at full precision).
5. **Interpretation.** Three years of compounding adds USD 1,971 over simple interest — under 2 %, which is precisely why the shortcut survives: at short horizons it is nearly right, and a professional who tests it only at short horizons will keep using it. The divergence is worth knowing as a curve rather than as a single fact. The ratio of compound to simple accumulation is **1.0159** at year 3, **1.0495** at year 5, **1.0986** at year 7, **1.1286** at year 8 — so the gap first passes ten per cent in year **7.0493** — **1.1994** at year 10 and **2.2828** at year 25, where compounding reaches **6.848475** times the principal against simple interest's 3.0. Two invariants fall out of the same arithmetic and are worth carrying. First, the **interest-on-interest** term — the part of the growth that simple interest cannot see, being $(1+r)^n - 1 - rn$ — is 0.0197 of the principal at year 3, 0.2109 at year 8, and passes **1.0** in year **15.1679**: at 8 %, interest on interest overtakes the entire original principal in the sixteenth year, and USD 100,000 has by then earned USD 114,594 of it. Second, the crossover year depends only on r , not on the amount, so the shape above is transferable to any principal at 8 % and can be recomputed for any other rate in one line. The professional habit this example teaches: never extrapolate a short-horizon intuition to a long-horizon contract, and be specifically suspicious of any "conservative simplification" whose error grows with tenor — the direction of that error is almost always in the borrower's favour and against the model (MCQ 3.1-C makes the point as an examination item; KA 3.3.2 finds the same defect in escalation).




Fig 3.1.1 — Simple versus compound growth of USD 100,000 at 8 %

3.1.2 Present and future value

Definitions. Compounding runs both ways. **Future value** carries an amount forward; **present value** brings a future amount back:

$$FV(x) = x \times (1 + r)^n$$

$$PV(x) = x / (1 + r)^n$$

$PV(x)$ answers the only question a bid evaluation, a settlement offer or a buy-out negotiation really asks: what is that future money worth today, at the return I could otherwise earn? The rate r used in this role is called the **discount rate**; choosing it is a Domain 4 judgment (and, for a levered project, a Domain 9/10 conversation) — this KA takes it as given.

WORKED EXAMPLE**Worked example 3.1.2 — pricing a deferred receipt.**

1. **Setup.** Kestrel will receive a USD 500,000 connection rebate exactly 5 years from now. The board discounts at 7.0 % for this risk. What is the rebate worth today?
2. **Formula.** $PV(x) = x / (1 + r)^n$, with $x = 500,000$, $r = 0.07$, $n = 5$.
3. **Substitution.** $PV(x) = 500,000 / 1.07^5 = 500,000 / 1.402552$.
4. **Result.** **USD 356,493** (356,493.09 at full precision; indicatively $\approx$ SAR 1,336,849 at **USD 1 $\approx$ SAR 3.75**).
5. **Interpretation.** A five-year wait at 7 % costs the rebate just under 29 % of its face value. The number is a decision rule, not a valuation: USD 356,493.09 is the **indifference price**, so a counterparty offering USD 380,000 today should be accepted and one offering USD 330,000 declined, and the whole of the professional judgment sits in the 7 %. Move the rate one point either way and the indifference price moves to **USD 373,629.09** at 6 % or **USD 340,291.60** at 8 % — a **USD 33,337.49** spread, **9.3515 %** of the value at 7 %, from two hundred basis points of opinion — which is why a review of any discounted number begins with the rate rather than the arithmetic. Two cautions belong with the result. The rate must reflect **this cash flow's** risk, not the project's average risk: a rebate payable by a creditworthy utility under a signed connection agreement is a different instrument from the project's equity, and discounting it at the project hurdle understates it — the risk-matching discipline Domain 4 (KA 4.1.1) sets out. And $PV(x)$ is silent on **whether the money arrives at all**: discounting handles timing, not credit, and a counterparty who may not pay is a probability question that belongs in the cash flow or in an explicit credit adjustment, never smuggled into r without saying so (Domain 7, KA 7.4; Domain 11, KA 11.2).

Common pitfall. Discounting with simple interest — $500,000 / (1 + 0.07 \times 5) = 370,370$ — overstates the value by USD 13,877 here. The error grows with horizon and rate; audit any model whose discount factors were "simplified".

WORKED EXAMPLE**Worked example 3.1.2b — reading an offer as a rate.**

1. **Setup.** The same USD 500,000 rebate, five years out. Rather than asking what the rebate is worth at Kestrel's rate, ask what rate the counterparty's cash offer implies. Two offers are on the table: **USD 380,000** and **USD 330,000**. What return is each offering Kestrel for giving up the wait?
2. **Formula.** Invert $PV(x) = x/(1+r)^n$: $r = (x / PV(x))^{(1/n)} - 1$. This is the third of the four TVM unknowns — value, rate, term, payment — and the one project finance uses most often under other names (yield, all-in cost, implied return).
3. **Substitution.** $r = (500,000/380,000)^{(1/5)} - 1 = 1.315789^{0.2} - 1$; and $r = (500,000/330,000)^{(1/5)} - 1 = 1.515152^{0.2} - 1$.
4. **Result.** The USD 380,000 offer implies **5.6422 %**; the USD 330,000 offer implies **8.6654 %**. The identity check: substituting the exact $PV(x)$ of 356,493.09 returns **7.0000 %** — the rate the board started with, recovered to the last digit.
5. **Interpretation.** The inversion changes the conversation. "Is 380,000 enough?" is a matter of opinion; "the offer pays 5.6422 % for five years and our required return for this risk is 7 %" is a matter of record, and the second sentence is the one that survives a board minute. The arithmetic also exposes where the decision is genuinely difficult: the USD 330,000 offer implies **8.6654 %**, comfortably above the 7 % hurdle, so **taking the money is the value-creating choice even though it looks like the worse price** — the larger cash sum is the worse deal and the smaller one the better, which is exactly the reversal that intuition gets wrong and the reason the calculation is done at all. Three professional cautions. The implied rate is only comparable to a required return of the **same basis**: this is a nominal rate over a whole number of years with a single cash flow, so no timing or compounding adjustment is hiding in it, whereas an implied rate on a stream must be solved rather than derived in closed form (KA 3.2.3, WE 3.2.3b). The inversion assumes the future amount is **certain**; where it is not, the implied rate is a promised yield and not an expected return, and the difference is the counterparty's default probability. And the sign convention matters: a solved rate above the hurdle favours **accepting cash today** for a receivable and **rejecting** it for a payable, because the same arithmetic run on an obligation Kestrel owes points the other way. Domain 4 (KA 4.1.2) develops the same inversion on a multi-period stream, where it acquires a name, **IRR**, and a set of pathologies this single-flow case cannot have.

3.1.3 Discount factors

Definition. The **discount factor** for period t is the present value of one currency unit received at t :

$$DF(t) = 1 / (1 + r)^t \quad \text{so that} \quad PV(x \text{ at } t) = x \times DF(t)$$

Discount factors are how models industrialise discounting: compute the factor row once, multiply every cash-flow row by it (Domain 6, KA 6.1). They also make review fast — an experienced reviewer reads a factor table the way a scheduler reads float.

At $r = 10 \%$:

t (years)	1	2	3	4	5
$DF(t)$	0.9091	0.8264	0.7513	0.6830	0.6209

Two sanity rules a reviewer applies on sight: factors must **decline monotonically**, and each factor must equal the previous factor divided by $(1 + r)$. A factor table that violates either has a hard-coded cell or a broken formula — a Domain 6 model-check classic (KA 6.4).




Fig 3.1.2 — Discount-factor curves at 6 %, 10 % and 14 %

Rounding discipline. Factors are displayed to four decimals but **calculations use full precision**. Multiplying a USD 900,000,000 programme cash flow by a four-decimal factor can move results by tens of thousands; the display is for the reader, never for the arithmetic (see the registry's decimal-arithmetic rule).

WORKED EXAMPLE**Worked example 3.1.3b — the factor row that checks itself.**

1. **Setup.** Kestrel's senior facility runs 12 years at 6.0 %. Build the discount-factor row for $t = 1 \dots 12$, and establish the two relationships that let a reviewer validate the whole column — and the annuity factor that will price the loan in KA 3.2 — without re-adding twelve numbers.
2. **Formula.** $DF(t) = 1/(1+r)^t$. The annuity factor is the **sum** of the row, $AF(r,n) = \sum DF(t)$ for $t = 1 \dots n$, and it satisfies the closed form $AF(r,n) = (1 - DF(n))/r$, which rearranges to the reviewer's identity $AF(r,n) \times r = 1 - DF(n)$.
3. **Substitution.** $DF(1) = 1/1.06 = 0.943396$, $DF(2) = 0.889996$, ... , $DF(12) = 1/1.06^{12} = 0.496969$. Adding all twelve gives **8.383844**. The closed form gives $(1 - 0.4969693636)/0.06$. The identity gives 8.3838439404×0.06 against $1 - 0.4969693636$.
4. **Result.** $\sum DF(t) = AF(0.06, 12) = \mathbf{8.383844}$ (8.3838439404 at full precision), and both sides of the identity equal **0.5030306364**. Repeating the exercise on Kestrel's 25-year evaluation horizon at 8 %: $DF(25) = \mathbf{0.1460179049}$, $AF(0.08, 25) = \mathbf{10.674776}$, and $10.6747761886 \times 0.08 = 0.8539820951 = 1 - 0.1460179049$.
5. **Interpretation.** The identity is the cheapest audit tool in the domain. A model's annuity factor and its discount-factor row are usually computed in different places by different formulae — one a closed form, one a column — and the identity is the only check that ties them together, so it catches the specific defect that a column is right and a summary cell is wrong, or vice versa. It also has diagnostic content beyond pass or fail: **because $1 - DF(n)$ can never exceed 1, $AF(r,n)$ can never exceed $1/r$** — 16.6667 at 6 %, 12.5 at 8 % — which gives a reviewer an instant ceiling on any annuity factor and immediately condemns an annuity factor larger than the reciprocal of the rate, whose two usual causes are a tenor typed into the rate cell and a rate entered as 6 rather than 0.06. Two further readings. The ratio $AF(r,n) \div (1/r)$ is exactly $1 - DF(n)$, so Kestrel's 25-year factor at 8 % already captures **85.3982 %** of what a perpetuity would be worth, and its 12-year factor at 6 % only **50.3031 %** of one: a quarter-century of contracted payments is most of forever, while a twelve-year loan is barely half of it. That single comparison explains why concession tails are worth arguing about and loan tails are not, and it is the arithmetic behind Domain 10's treatment of **PLCR** (KA 10.2.2) as real but weak security. And the row's own arithmetic is the reason for the rounding rule stated above: the four-decimal $DF(12)$ of 0.4969 rather than 0.4969693636 shifts the derived AF by 0.0011561 and Kestrel's instalment by roughly **USD 691** a year — small, visible, and entirely avoidable. The caution: an identity that holds is evidence about the formulae, not about the rate. A factor row built on the wrong r satisfies every check in this example perfectly.

AI in this KA

Spreadsheet copilots will happily draft TVM formulae, and large-language-model assistants will "explain" a discount factor with perfect fluency and an inverted exponent. The governed position (the PCI principle: **AI proposes; the professional verifies, decides and remains accountable**) is mechanical here because verification is cheap: recompute one factor by hand, check monotonicity, check $DF(1) \times (1+r) = 1$. An AI-drafted factor row that no human recomputed is not a calculation; it is a claim.

■ KEY TERMS — KA 3.1

Term	Meaning
Simple interest	Interest accruing on original principal only: $FV(x) = x(1 + rn)$.
Compound interest	Interest accruing on principal and accumulated interest: $FV(x) = x(1 + r)^n$.
Present value $PV(x)$	Today's worth of a future amount at discount rate r .
Future value $FV(x)$	The compounded worth of an amount at a future date.
Discount rate	The rate r used to move value across time; the required return for the risk.
Discount factor $DF(t)$	$1/(1+r)^t$; the PV of one unit received at t .

■ SAMPLE MCQS — KA 3.1

MCQ 3.1-A [3.1.2 · Application] A payment of USD 500,000 is due in 5 years; the discount rate is 7 %. Its present value is closest to:

- A. USD 370,370
- B. USD 356,493 ✓ CORRECT
- C. USD 381,448
- D. USD 701,276

Rationale: $500,000 / 1.07^5 = 356,493$. A discounts with simple interest $(1 + 0.35)$; C uses four years instead of five; D compounds forward instead of discounting back.

MCQ 3.1-B [3.1.3 · Application] At a 10 % discount rate, the discount factor for year 3 is:

- A. 0.7000
- B. 0.8264
- C. 0.7513 ✓ CORRECT
- D. 0.6830

Rationale: $1/1.10^3 = 0.7513$. A subtracts 10 % three times (simple); B is the year-2 factor; D is the year-4 factor — the two most common off-by-one-period errors.

MCQ 3.1-C [3.1.1 · Analysis] A lender quotes 25-year money and a borrower's analyst tests affordability using simple interest "as a conservative shortcut". The analyst's error is that:

- A. simple interest overstates the debt cost, so the test is merely too strict
- B. compound growth exceeds simple growth over long horizons, so the shortcut materially understates the true accumulation ✓ CORRECT
- C. the two methods converge over long horizons, so the shortcut is harmless
- D. simple interest cannot be computed for horizons beyond ten years

Rationale: Compounding produces growth on growth: at 8 % over 25 years the compound multiple is ≈ 6.85 versus 3.0 simple — the shortcut is anti-conservative, the opposite of the analyst's claim (so A is wrong); the methods diverge rather than converge (C); D is arithmetic nonsense.

MCQ 3.1-F [3.1.2 · Application] USD 250,000 is invested at 7 % compound for 6 years. Its future value is closest to:

- A. USD 355,000
- B. USD 350,638

- C. USD 375,183 ☒ **CORRECT**
- D. USD 166,586

Rationale: $250,000 \times 1.07^6 = 375,183$. A is simple interest ($1 + 0.07 \times 6$); B compounds only 5 years; D divides instead of multiplying — discounting when the question asks for growth.

MCQ 3.1-D [3.1.3 · Recall] Which statement about discount factors is an invariant a reviewer can test without knowing the project?

- A. $DF(t)$ rises when cash flows are contracted
- B. $DF(t+1) = DF(t) / (1 + r)$ for every t ☒ **CORRECT**
- C. $DF(t)$ equals $1 - r \times t$
- D. factors below 0.5 indicate an error

Rationale: Each factor is the prior factor discounted one more period — B holds for any r . A confuses risk of flows with the factor row; C is the simple-interest approximation; D is false — any long horizon at a normal rate passes 0.5 (see Fig 3.1.2).

MCQ 3.1-E [3.1.2 · Application] At 9 %, which is worth more today: USD 400,000 in 2 years, or USD 470,000 in 4 years?

- A. the 470,000 — larger amounts always win
- B. the 400,000: PV 336,672 vs 332,960 ☒ **CORRECT**
- C. the 470,000: PV 395,590 vs 336,672
- D. they are equal at 9 %

Rationale: $400,000/1.09^2 = 336,672$; $470,000/1.09^4 = 332,960$ — the earlier, smaller amount wins by USD 3,712. A ignores discounting entirely; C discounts the 470,000 across only two periods instead of four; D asserts an equality the arithmetic denies.

MCQ 3.1-G [3.1.2 · Analysis] A counterparty offers **USD 380,000 today** to extinguish an obligation to pay USD 500,000 in exactly five years. The annual rate of return the offer implies for the party giving up the wait is closest to:

- A. 4.80 %
- B. 5.64 % ☒ **CORRECT**
- C. 6.32 %
- D. 7.00 %

Rationale: $(500,000/380,000)^{(1/5)} - 1 = 5.6422\%$. A divides the USD 120,000 premium by the future amount and by five ($120,000/500,000/5$) — a simple return computed on the wrong base; C annualises the 31.5789 % total premium by dividing by five, the simple-interest shortcut of KA 3.1.1 applied to a rate; D is the board's own required return, which is what the implied rate must be compared against, not the answer to the question asked.

MCQ 3.1-H [3.1.3 · Comprehension] A reviewer wants one arithmetic test that ties a twelve-row discount-factor column to the single annuity-factor cell that summarises it, without re-adding the column. The correct relationship is:

- A. $AF(r,n) \times r = 1 - DF(n)$ ☒ **CORRECT**
- B. $AF(r,n) = n \times DF(n)$
- C. $AF(r,n) \times DF(n) = 1$
- D. $AF(r,n) = 1/r - DF(n)$

Rationale: At 6 % over 12 years, $8.383844 \times 0.06 = 0.503031 = 1 - 0.496969$ (WE 3.1.3b). B averages the row by its last term and gives 5.963632; C inverts a relationship that holds for no r (here 4.166514); D drops the division of $DF(n)$ by r from the closed form and gives 16.169697 — each a plausible-looking rearrangement, and each falsifiable in one cell.

MCQ 3.1-I [3.1.2 · Evaluation] Kestrel will receive a USD 500,000 connection rebate in five years from a creditworthy utility under a signed connection agreement. A board member proposes discounting it at the project's 8.0 % appraisal rate "for consistency"; the treasurer proposes 6.0 %, the rate on the project's own senior debt. The values are **340,291.60** at 8 % and **373,629.09** at 6 %. The sound recommendation is:

- A. use 8.0 % — one project, one discount rate, and consistency is the stronger discipline
- B. use a rate that reflects this cash flow's risk, which is a contracted receivable from a strong counterparty rather than the project's equity risk; state the rate chosen, and put any doubt about payment into the cash flow or an explicit credit adjustment rather than inside r
- ☒ **CORRECT**
- C. use 6.0 %, because the rebate will be applied to reduce senior debt, which makes the debt rate the opportunity cost
- D. use 8.0 % and additionally reduce the 500,000 for the risk of non-payment, capturing both effects

Rationale: the discount rate must match the risk of the flow being discounted, and discounting handles timing rather than credit (3.1.2) — the two hundred basis points between the proposals move this single receipt by **33,337.49**, or **9.3515 %** of its value at 7 %. A applies a portfolio convention to an instrument of different risk and so understates it. C is the most defensible of the wrong answers and still picks its rate from the use of the money rather than the risk of receiving it. D uses the right technique for credit — an explicit haircut — and then leaves in place a rate set for a riskier flow, charging the same risk twice.

■ SELF-CHECK — KA 3.1

- Why must discount factors decline monotonically? — Because $(1+r)^t$ grows with t for any positive r ; a rising factor implies a negative rate or a broken formula.
- Your model shows $DF(4) = 0.6830$ and $DF(5) = 0.6209$ at 10 %. One cell check confirms both. Which? — $0.6830 / 1.10 = 0.6209$: each factor is the prior factor divided by $(1+r)$.
- A colleague says "8 % for three years is 24 %". — Only under simple interest; compounded it is $1.08^3 - 1 = 25.97 \%$, and the gap widens every further year.
- What is the largest annuity factor possible at 8 %, and why? — 12.5, the perpetuity factor $1/r$, because $AF(r, n) \times r = 1 - DF(n)$ and $1 - DF(n) < 1$ for every finite n .
- An offer of cash today implies a 8.6654 % return against a 7 % hurdle. Should it be accepted for a receivable, and for a payable? — Accepted for a receivable (the market is paying more than the risk requires) and refused for a payable, where the same rate is the cost of settling early.

KNOWLEDGE AREA 3.2

Annuities and loan schedules

Topics: 3.2.1 annuities and perpetuities · 3.2.2 loan schedules · 3.2.3 compounding frequency and effective rates.

3.2.1 Annuities and perpetuities

Definitions. An **annuity** is a level stream — the same amount each period for n periods. Project finance is built from annuities and near-annuities: availability payments, capacity charges, lease rentals, O&M fees, debt service. The present value of an ordinary annuity (payments at period-ends) of amount A :

$$PV(\text{annuity}) = A \times AF(r, n) \quad \text{where} \quad AF(r, n) = (1 - (1 + r)^{-n}) / r$$

$AF(r, n)$ is the **annuity factor** — the sum of the discount factors $DF(1) \dots DF(n)$. A **perpetuity** is the limiting case as $n \rightarrow \infty$:

$$PV(\text{perpetuity}) = A / r$$

WORKED EXAMPLE

Worked example 3.2.1 — valuing Kestrel's availability stream.

1. **Setup.** Kestrel's offtaker will pay USD 3,000,000 per year for 20 years under an early tariff proposal, paid annually in arrears. The board discounts at 9.0 %. Value the stream.
2. **Formula.** $PV = A \times AF(r, n)$, $AF(r, n) = (1 - (1+r)^{-n})/r$, with $A = 3,000,000$, $r = 0.09$, $n = 20$.
3. **Substitution.** $AF(0.09, 20) = (1 - 1.09^{-20})/0.09 = 9.128546$; $PV = 3,000,000 \times 9.128546$.
4. **Result.** **USD 27,385,637** (using the full-precision factor).
5. **Interpretation.** Twenty years of payments are worth barely nine years' worth of face value — discounting at 9 % has priced away more than half the nominal USD 60,000,000 total. Sensitivity: at a 10 % rate the factor falls to 8.513564 and the value to USD 25,540,691 — a 6.7 % value loss for one point of rate, the shape of sensitivity every concession bidder lives with (Domain 7, KA 7.4).

Common pitfall — the rounded factor. Using a four-decimal factor (9.1285) gives USD 27,385,500 — USD 137 adrift here, but scale the stream by 100× and the drift is five figures. Factors are display; arithmetic is full precision (KA 3.1.3).

Timing variants. An **annuity-due** (payments in advance, common in leases and some availability regimes) is worth $(1 + r)$ times the ordinary annuity; a **deferred annuity** starts after a gap and is discounted twice — as a stream, then back across the deferral. Misreading the payment convention in a concession agreement misprices the whole stream by one period's discounting — check the contract, not the habit (Domain 12, KA 12.2).

WORKED EXAMPLE**Worked example 3.2.1b — the lease quoted in advance.**

1. **Setup.** Kestrel's operations base is leased at USD 500,000 per year for 5 years, payable **in advance**. Discount rate 8.0 %. Value the obligation.
2. **Formula.** $PV(\text{due}) = A \times AF(r, n) \times (1 + r)$, with $A = 500,000$, $r = 0.08$, $n = 5$.
3. **Substitution.** $AF(0.08, 5) = 3.992710$; ordinary value $500,000 \times 3.992710 = 1,996,355$; due value $1,996,355 \times 1.08$.
4. **Result.** **USD 2,156,063** (2,156,063.42). The in-advance convention adds USD 159,708 — exactly one period's discounting on the whole stream.
5. **Interpretation.** Eight per cent of the stream's value hangs on one word in the lease. Reading "payable annually in advance" as an ordinary annuity is the commonest annuity mistake in diligence reviews (Domain 13, KA 13.1) — and it always flatters the tenant's model. The correction is worth holding as an invariant rather than as a formula: **the ratio of an annuity-due to an ordinary annuity is exactly $(1 + r)$, whatever A and whatever n** — here $2,156,063.42 \div 1,996,355.02 = 1.08$ to every digit — so a reviewer who suspects a convention error does not need to rebuild the stream. Divide the model's answer by the ordinary-annuity answer and read the result: 1.00 means arrears, $1 + r$ means advance, and anything else means a third defect is present as well. Two cautions. The $(1 + r)$ factor is **one period's** rate, so on a quarterly-in-advance lease the adjustment is $1 + r/4$ and not $1 + r$ — applying the annual factor to a quarterly stream overstates the correction roughly fourfold, which is the error that follows the error. And the direction is asymmetric in consequence: on a **receivable** stream the in-advance reading raises value and flatters the seller, while on a **payable** stream — a lease, an availability payment Kestrel owes, an O&M fee — it raises the liability, so the same mistake is optimistic in one place and prudent in the other, and a model containing both conventions read wrongly does not self-correct. The lease clause, not the model's habit, decides (Domain 12, KA 12.2).

WORKED EXAMPLE**Worked example 3.2.1c — the deferred availability stream.**

1. **Setup.** A grantor variant offers Kestrel the same USD 5,600,000 $\times$ 25-year availability supplement, but with the **first payment at the end of year 4** (a three-year deferral while the plant ramps up). Discount rate 8.0 %.
2. **Formula.** $PV = A \times AF(r, n) / (1 + r)^d$, $d = 3$ (the stream's own valuation point sits at the end of year 3, one period before its first payment).
3. **Substitution.** $5,600,000 \times 10.674776 = 59,778,747$ (the stream valued at end-year 3); $59,778,747 / 1.08^3 = 59,778,747 / 1.259712$.
4. **Result.** **USD 47,454,296.**
5. **Interpretation.** The three-year wait costs USD 12.3 million — a fifth of the stream's value — which is precisely what the grantor saves by deferring. Any negotiation over payment timing is a negotiation over value at compound rates; Case study A prices the whole family of such trades.

The indexed stream — the annuity family's fourth member. Almost no real project stream is level. Availability payments index, tariffs escalate, O&M fees rise with a labour index, and a level annuity is therefore the exception rather than the rule. A stream growing at a constant rate g per

period is a **growing (indexed) annuity**, and it does not need a new machine — it needs one substitution:

$$PV(\text{indexed}) = A \times AF(r^*, n) \quad \text{where} \quad r^* = (1 + r)/(1 + g) - 1$$

with A the amount in **period-0 money** and the period- t payment $A(1 + g)^t$. r^* is the **growth-adjusted (real, if g is inflation) discount rate**. The limiting case as $n \rightarrow \infty$, valid only where $r > g$, is the growing perpetuity $PV = A(1 + g)/(r - g)$.

WORKED EXAMPLE**Worked example 3.2.1d — the indexed availability payment, and the identity that prices it.**

1. **Setup.** A grantor variant offers Kestrel the 25-year availability supplement of **USD 5,600,000** in year-0 terms, but **fully indexed at 2.5 % a year**, so the first payment is 5,740,000 and the last is larger again. Discount rate 8.0 %. Value the indexed stream, and value the reshaping that would leave the grantor no worse off than the level USD 5,600,000 offer.
2. **Formula.** $PV = \sum A(1+g)^t/(1+r)^t$ for $t = 1 \dots 25$, which equals $A \times AF(r^*, n)$ with $r^* = (1+r)/(1+g) - 1$. For the value-neutral reshaping, solve for the base payment A' such that $A' \times AF(r^*, 25) = 5,600,000 \times AF(r, 25)$.
3. **Substitution.** $r^* = 1.08/1.025 - 1 = 0.0536585366$; $AF(r^*, 25) = 13.591332$; $PV = 5,600,000 \times 13.591332$. Direct summation of all 25 terms is computed alongside as the check. For the reshaping, $A' = 59,778,746.66 \div 13.591332$.
4. **Result.** Indexed stream **USD 76,111,457** (76,111,457.28 by both routes, identical to the cent). Against the level stream's **USD 59,778,747**, indexation at 2.5 % is worth **USD 16,332,711**, a **27.3219 %** uplift. The value-neutral reshaping is a base payment of **USD 4,398,299** — a first payment of **4,508,257** rising to **8,154,201** in year 25, crossing the level 5,600,000 in **year 10** (5,630,195).
5. **Interpretation.** The identity is the most useful single line in this Knowledge Area, and it deserves to be read in both directions. Forwards, it says an indexed stream needs no new formula: **escalating the flows at g and discounting at r gives exactly the same answer as leaving the flows in period-0 money and discounting at r^*** — which is the Fisher consistency rule of KA 3.3.1 arriving early, in stream form, and is why the same arithmetic reappears there priced as an audit defect (WE 3.3.1b). Backwards, it is a trap detector. The characteristic error is to escalate the flows **and** discount them at the growth-adjusted rate, which counts the indexation twice: here that produces **USD 99,768,254**, an overstatement of **USD 23,656,797** or **31.0818 %** — a third of the value of the largest single item in the concession, from one substitution made twice. The defect survives review because both halves look right in isolation and neither cell is wrong on its own. The second reading is commercial. Indexation is not a detail of drafting; at 2.5 % on a 25-year stream it is worth **27.3219 %** of the stream, so a grantor who agrees to full indexation without repricing the base payment has made a concession larger than most of what the parties spent the negotiation arguing about — which is exactly why real grantors do the reshaping, and why the arithmetic above is a bid-preparation calculation rather than an academic one. Note what the reshaping actually does: **it holds present value constant and moves risk**. Both packages are worth 59,778,747 to Kestrel at 8 %, but the indexed one pays **19.4954 %** less in year one, crosses over in year 10, and pays a nominal total of **USD 153,991,976** against the level stream's 140,000,000 — so it is worse for early **DSCR** (Domain 10, KA 10.2.1) and better for inflation protection, and the choice between them is a risk-allocation decision that a present value cannot make. Three cautions. The formula requires **g constant**; a contractual index with caps, floors or a lag is not a constant **g** , and KA 3.3.2 shows what each does to the value. **$r > g$** is required for the perpetuity form and merely advisable for the annuity form: at **$r \leq g$** the finite sum still exists but the value becomes extremely sensitive to **n** , and a model that prices a 40-year stream with **g** close to **r** is reporting an artefact of its own tenor assumption. And **r^* must never be presented as the project's discount rate**. It is an arithmetic device inside one valuation; a board paper that quotes 5.3659 % as Kestrel's hurdle has confused a substitution with a policy.

3.2.2 Loan schedules

The three canonical shapes. A loan of principal P over n periods at rate r can be scheduled three ways, and a project finance leader must read all three on sight:

Shape	Rule	Debt-service profile	Where seen
Annuity (equal instalment)	Payment $A = P \times r / (1 - (1+r)^{-n})$ each period	Level total; interest share falls, principal share rises	Most project term loans; mortgages
Level principal	Principal P/n each period + interest on balance	Front-loaded total, declining	Some ECA and development-bank facilities (Domain 9)
Bullet	Interest only; principal entire at maturity	Low until the final balloon	Bonds; mini-perm structures; refinancing plays (Domain 15)
Repayment holiday (grace)	Interest only for k periods, then annuity over the remaining $n - k$	Low, then a step up to a heavier level	Ramp-up periods; construction-to-operations transitions

WORKED EXAMPLE

Worked example 3.2.2 — Kestrel's senior loan.

- Setup.** USD 42,000,000, 12 annual instalments, 6.0 % — annuity shape. Find the instalment and build the first three schedule rows.
- Formula.** $A = P \times r / (1 - (1+r)^{-n})$, with $P = 42,000,000$, $r = 0.06$, $n = 12$. Each row: interest = opening balance $\times r$; principal = $A - \text{interest}$; closing = opening — principal.
- Substitution.** $A = 42,000,000 \times 0.06 / (1 - 1.06^{-12}) = 42,000,000 / 8.383844$.
- Result.** $A = \text{USD } 5,009,635$ per year (5,009,635.23; indicatively $\approx$ SAR 18,786,132). Schedule:

Year	Opening balance	Interest (6 %)	Principal	Closing balance
1	42,000,000	2,520,000	2,489,635	39,510,365
2	39,510,365	2,370,622	2,639,013	36,871,351
3	36,871,351	2,212,281	2,797,354	34,073,997

- Interpretation.** The instalment never changes; its composition does — year 1 is 50.30 % interest, and by the final year almost all principal, with interest down to 283,564. Two checks a reviewer runs instantly: the closing balance after year 12 must be exactly zero (a residual means a formula error), and total principal across all rows must equal P . Both need one honest qualification that separates a real model check from a superstition. The instalment is **5,009,635.233987873150895272537** at full precision; run the schedule on the printed 5,009,635.23 and the year-12 closing balance is **USD 0.06**, not zero. That is not an error — it is twelve rounding decisions, and a schedule that closes at six cents on a 42,000,000 facility is correct while one that closes at 6,000 is not. The reviewer's rule is therefore **"zero to within accumulated display rounding, and materially zero to a stated tolerance"**, and the tolerance should be written into the model-check sheet rather than left to taste (Domain 6, KA 6.4). The composition path itself carries the professional content. Interest falls from 2,520,000 to 283,564 — a factor of **8.8869** — while principal rises from 2,489,635 to 4,726,071, and the ratio of final-year to first-year principal is exactly $(1 + r)^{(n-1)} = 1.06^{11} = \mathbf{1.8983}$, an invariant that

holds for any annuity loan and gives a reviewer a one-line test of the whole principal column. The interest share of the first instalment, **50.30 %**, is not a coincidence either: it is $1 - DF(n)$ from WE 3.1.3b, since first-year interest divided by the instalment is $P \times r \div (P \times r / (1 - DF(n)))$. Two consequences that matter downstream. Because interest falls and the instalment does not, the **tax shield declines every year** while debt service does not, so a project's after-tax cash profile is not flat even when its debt service is (Domain 6, KA 6.2.2; Domain 9, KA 9.2.2). And because the loan is level while **CFADS** in a ramping project is not, **the annuity's constant instalment guarantees that the binding coverage period is the earliest one** — Kestrel's **DSCR** of $6,384,000 \div 5,009,635.23 = 1.2743$ is a year-one number and every later year is better on level cash, which is exactly the property Domain 10 (KA 10.1.3) exploits when it sculpts. This schedule is the direct input to Kestrel's debt service line — and therefore to its **DSCR**, **LLCR** and **PLCR** — in Domains 6 and 10.

WORKED EXAMPLE

Worked example 3.2.2b — the same loan, level-principal.

1. **Setup.** Kestrel's ECA co-lender offers the same USD 42,000,000 over 12 years at 6.0 % but on a **level-principal** schedule. Build the first two rows and the final row, and compare lifetime interest across all three shapes.
2. **Formula.** Principal each year $P/n = 42,000,000/12 = 3,500,000$; interest = opening balance $\times 6\%$; total = principal + interest.
3. **Substitution.** Year 1: $3,500,000 + 42,000,000 \times 0.06$. Year 2: $3,500,000 + 38,500,000 \times 0.06$. Year 12: $3,500,000 + 3,500,000 \times 0.06$.
4. **Result.** Year 1 **USD 6,020,000** · year 2 **USD 5,810,000** · year 12 **USD 3,710,000** — a declining profile. Lifetime interest: level-principal **USD 16,380,000** · annuity **USD 18,115,623** · bullet **USD 30,240,000**.
5. **Interpretation.** Level-principal is the cheapest shape in total interest because principal retires fastest — but its year-1 debt service is USD 1,010,365 heavier than the annuity's, exactly when a ramping project is cash-poorest. The two crossovers are worth having in the head, because they are where the argument between a treasurer and a credit officer actually happens. The **annual payment** crossover is in **year 6**: level-principal costs more than the annuity in years 1 to 5 and less from year 6, the exact parity point falling at **year 5.8113**. The **cumulative cash** crossover is much later: level-principal is still 653,648 of cumulative cash ahead of the annuity at the end of year 10 and only moves behind during **year 11**, finishing 1,735,623 cheaper. So for ten of the twelve years the "cheaper" shape has taken more money out of the project, and the 1,735,623 lifetime advantage is collected almost entirely in the last two years. Read against Kestrel's coverage that is decisive: at documented **CFADS** of 6,384,000 the level-principal year-1 **DSCR** is $6,384,000 \div 6,020,000 = 1.0605$, against the annuity's **1.2743** — the same loan, the same rate, the same lender, and one shape fails a 1.20× covenant in its first test period while the other clears it. Shape selection is a cash-timing decision, not a cost minimisation: Domain 10 (KA 10.1) sizes debt against the early-year coverage this choice determines, and the honest professional statement of the trade is that **level-principal buys 1,735,623 of interest with 1,010,365 of first-year coverage headroom**, which is a good trade for a project with flat contracted cash from day one and a bad one for anything that ramps.

WORKED EXAMPLE**Worked example 3.2.2c — the repayment holiday, and the cliff it builds.**

1. **Setup.** Kestrel's ramp-up is slower than the base case assumes, so the sponsor asks for a **three-year repayment holiday**: interest only in years 1 to 3, then full amortisation of the unchanged USD 42,000,000 across years 4 to 12. Same 6.0 %, same 12-year maturity. Find the instalment, the lifetime interest, and the coverage consequence.
2. **Formula.** Interest-only service = $P \times r$. Amortising instalment over the remaining periods $A_h = P \times r / (1 - (1+r)^{-(n-k)})$ with $n - k = 9$. Lifetime interest = $k \times P \times r + [(n - k) \times A_h - P]$. Coverage per period = $CFADS \div \text{debt service}$.
3. **Substitution.** Years 1-3: $42,000,000 \times 0.06 = 2,520,000$. Years 4-12: $42,000,000 \times 0.06 / (1 - 1.06^{-9}) = 42,000,000 \div 6.801692$. Interest: $3 \times 2,520,000 + (9 \times A_h - 42,000,000)$.
4. **Result.** Instalment years 4-12 **USD 6,174,934** (6,174,933.87). Lifetime interest **USD 21,134,405**, against the plain annuity's **18,115,623** — the holiday costs **USD 3,018,782** more. Coverage: year 1 **DSCR 2.5333**, year 4 **DSCR 1.0339**.
5. **Interpretation.** The holiday does exactly what it is asked to do and creates exactly the problem nobody asks about. Years 1 to 3 are luxurious — a **DSCR** of 2.5333 against a 1.20× covenant is more headroom than the project will ever have again — and year 4 is a **cliff**: the instalment jumps **145.0371 %** from 2,520,000 to 6,174,934 in a single step, coverage falls to **1.0339**, and the project misses a 1.30× requirement by **USD 1,643,414** of **CFADS** ($6,174,933.87 \times 1.30 = 8,027,414.03$ needed against 6,384,000 available). The structure is not merely tight; it is **unbankable as drawn**, and it would have been described in the sponsor's own term sheet as a concession in the sponsor's favour. That is the professional point: a holiday granted on an unchanged maturity does not reduce debt service, it **concentrates** it, and the concentration lands on whichever operating year the sponsor was least willing to model. Three further readings. The interest cost of the holiday, 3,018,782, is not a fee anybody negotiated — it is the arithmetic consequence of leaving 42,000,000 outstanding for three extra years at 6 %, and it is knowable in advance to the cent, which means a sponsor who accepts a holiday without pricing it has given away a computable amount for a cash-flow convenience. The fix is structural rather than arithmetic: **extend the maturity by the holiday** and the instalment returns to a manageable level, which is why holidays and tenor extensions are negotiated together and why a holiday on a fixed concession end-date is nearly always a bad trade (the concession, not the lender, is the binding constraint — Domain 5, KA 5.4). And the reviewer's test is a period one: **a holiday makes the first amortising period the binding coverage test, not the first period**, so any covenant model that reports "minimum **DSCR**" from year 1 onwards without inspecting the step is reporting the wrong minimum. Domain 10 (KA 10.1.2) sizes debt against exactly this binding period; Domain 14 (KA 14.4) meets the same cliff where a construction-period holiday runs into a delayed commercial operation date.

WORKED EXAMPLE**Worked example 3.2.2d — what is still owed, and how to know twice.**

1. **Setup.** Kestrel's sponsor is approached in year 7 about a refinancing, and separately needs to report debt outstanding for a covenant certificate. On the annuity schedule of WE 3.2.2, what is the principal outstanding immediately after the year-7 instalment — and how is that figure proved without the schedule?
2. **Formula.** Two independent routes must agree. The **recursion**: carry the schedule forward row by row, $\text{closing} = \text{opening} - (A - \text{opening} \times r)$. The **closed form**: the outstanding balance after k payments is the present value of the payments that remain, $B_k = A \times AF(r, n - k)$.
3. **Substitution.** Recursion: twelve rows of $\text{opening} \times 0.06$, subtracted from 5,009,635.23, as tabulated in WE 3.2.2. Closed form: $5,009,635.23 \times AF(0.06, 5) = 5,009,635.23 \times 4.212364$.
4. **Result.** Closed form **USD 21,102,406.02**; recursion on the printed instalment **USD 21,102,406.08** — agreement to **six cents**, the accumulated display rounding of seven instalments. The same test at other dates: after year 3, **34,073,997.24** against **34,073,997.29**; after year 5, **27,965,694.73** against **27,965,694.78**.
5. **Interpretation.** The balance formula does four distinct jobs. It is a **check**: two routes computed from different data — one from a rate and a remaining tenor, one from a running balance — must agree, and where they do not, the defect is in the schedule and not in the formula, because the closed form has nowhere to hide an error. It is a **reporting tool**: covenant certificates, **LLCR** denominators and security-value tests all need debt outstanding at a date, and Domain 10 (KA 10.2.2) uses precisely this figure. It is a **prepayment price**: B_k is what the borrower owes to walk away, before any break cost or prepayment fee the facility may add, which sit on top of B_k rather than instead of it. And it is a **refinancing base**: the year-7 figure of 21,102,406 is the amount a refinancing must raise, and the fact that it is **50.2438 %** of the original 42,000,000 after seven of twelve years tells the sponsor immediately that the annuity's principal retirement is back-loaded — half the loan is still outstanding at 58.33 % of the term. Two cautions. The closed form assumes the schedule has run **exactly as contracted**: one missed or partial payment, one capitalised amount, one cash sweep, and the recursion is right while the formula is wrong, so the formula is a check on an unbroken schedule and an error on a restructured one (Domain 15, KA 15.3 handles the restructured case). And the remaining interest is not the remaining balance: after year 7 Kestrel still owes $5 \times 5,009,635.23 = 25,048,176.15$ of cash, of which **USD 3,945,770.13** is interest not yet accrued — a figure that appears in no ledger and is not a liability, which is why balance-sheet debt and total future debt service are different numbers and a covenant that names one must not be tested with the other (Domain 2, KA 2.1).




Fig 3.2.1 — Anatomy of an annuity loan: Kestrel's USD 42,000,000, 12 years at 6 %




Fig 3.2.2 — Three shapes, one loan: annual debt service under annuity, level-principal and bullet




Fig 3.2.3 — Outstanding principal, not debt service: Kestrel's USD 42,000,000 under four shapes

Reading the balance path rather than the payment path. Figure 3.2.2 shows what the project pays; Figure 3.2.3 shows what it still owes, and the second is the picture a credit officer wants, because **lifetime interest is r multiplied by the area under the balance path** and refinancing exposure is the height of that path at maturity. The four areas order themselves exactly as the interest totals do, which is why the ordering needs no memorising: level principal encloses the least ($16,380,000 \div 0.06 = 273,000,000$ balance-years), then the annuity (18,115,623), then the holiday (21,134,405), then the bullet (30,240,000, the maximum possible for the tenor because the balance never falls at all). Two diagnostic readings a reviewer takes straight off the chart. The **half-life of the principal** — the date at which half the loan has been retired — is year **6.0000** for level principal, **7.0281** for the annuity, **8.0833** for the holiday and never for the bullet; a shape whose half-life sits past the midpoint of its tenor has a back-loaded credit exposure whatever its instalment looks like. And the **height at maturity** is the refinancing question in one number: nil for three of the shapes and 42,000,000 for the fourth.

Common pitfall — the bullet that looks cheap. A bullet's early debt service is a fraction of an annuity's, and a cash-strapped sponsor will feel the temptation. The full price appears at maturity as refinancing risk — the balloon must be refinanced at whatever the market then charges (Domain 15, KA 15.3). Case study B prices this trade.

3.2.3 Compounding frequency and effective rates

Definitions. A quoted **nominal annual rate** i_{nom} compounded m times per year applies i_{nom}/m per period. The **effective annual rate (EAR)** is the once-a-year rate that produces the same growth:

$$\text{EAR} = (1 + i_{\text{nom}} / m)^m - 1$$

WORKED EXAMPLE**Worked example 3.2.3 — the same 6 %, four ways.**

1. **Setup.** A facility is quoted at "6 % nominal". Find the effective annual rate if compounding is annual, semi-annual, quarterly and monthly.
2. **Formula.** $\text{EAR} = (1 + 0.06/m)^m - 1$ for $m = 1, 2, 4, 12$.
3. **Substitution.** $m=4$: $(1 + 0.015)^4 - 1 = 1.061364 - 1$.
4. **Result.** Annual **6.000 %** · semi-annual **6.090 %** · quarterly **6.136 %** · monthly **6.168 %**.
5. **Interpretation.** "Six per cent" is not one price; it is four prices in this example alone, and the differences compound over a 12-year loan. Three things are worth extracting. The **increments shrink**: annual to semi-annual costs **9.0000** basis points, semi-annual to quarterly a further **4.6355**, quarterly to monthly a further **3.1426**, and monthly to daily only **1.5350** — so the whole range from once a year to continuous compounding (KA 3.A.1) is **18.3655 basis points**, of which the first step alone is half. That bounds the argument: a negotiation over compounding frequency is a negotiation over at most 18 basis points at this rate, which is worth knowing before spending negotiating capital on it, and worth knowing so that a misread frequency is recognised as a small error rather than assumed to be a large one. The **direction is invariant**: $\text{EAR} \geq i_{\text{nom}}$ always, with equality only at $m = 1$, so a model reporting an effective rate below its nominal has a defect, full stop (3.A.4). And the practical rule stands independent of the arithmetic: term sheets are compared on effective rates, never on quoted nominals — and loan models must use the **periodic** rate i_{nom}/m with $n \times m$ periods, not the EAR with n years, or debt service will be misstated (Domain 6, KA 6.3; WE 3.2.3c prices exactly that substitution on Kestrel). The caution that belongs here is a scale one: 18 basis points on Kestrel's 42,000,000 is small, but the same misread on a floating-rate facility repriced quarterly across a portfolio is a systematic error rather than a rounding one, and systematic errors do not average out.

WORKED EXAMPLE**Worked example 3.2.3b — the fee-inclusive cost, solved rather than added.**

1. **Setup.** Kestrel's mandate is USD 42,000,000 at 6.0 % over 12 years, with an **arrangement fee of USD 840,000** (2.0 % of the facility) deducted from the first drawdown — the figure sitting in the funding envelope at Domain 6, KA 6.2.1. A second lender offers the same amount and tenor at **6.15 % with no fee**. Which facility is cheaper, and by how much?
2. **Formula.** A fee cannot be added to a rate; it must be **solved out of the stream**. The all-in effective cost is the rate r_{all} satisfying $\sum A/(1 + r_{all})^t = \text{net proceeds}$, where A is the contractual instalment (computed on the **gross** principal at the **contract** rate) and net proceeds are what the project actually receives. Solve numerically — there is no closed form.
3. **Substitution.** Instalment unchanged at $42,000,000 \times 0.06/(1 - 1.06^{-12}) = 5,009,635.23$; net proceeds $42,000,000 - 840,000 = 41,160,000$. Solve $\sum 5,009,635.23/(1 + r_{all})^t = 41,160,000$ for $t = 1 \dots 12$. For the comparison, $42,000,000 \times 0.0615/(1 - 1.0615^{-12})$.
4. **Result.** All-in cost of the fee facility **6.3704 %** (6.370442 %) — a premium of **37.04 basis points** over the 6.00 % headline. The rival at 6.15 % with no fee has an all-in cost of exactly **6.1500 %** and an instalment of **USD 5,050,914** (5,050,913.67, or 41,278.44 a year more than 5,009,635.23). **The 6.15 % facility is cheaper, by 22.04 basis points.**
5. **Interpretation.** The result reverses the intuition that a lower coupon is a lower cost, and it does so for a reason worth naming: an upfront fee is paid **once, at time zero, undiscounted**, while a margin is paid across twelve years on a declining balance, so a fee is a far more expensive way to deliver the same nominal amount of money to a lender. The exchange rate between the two is the number to carry: on this facility **each 1.00 % of upfront fee is worth 18.38 basis points of margin** (a 420,000 fee prices at 6.183800 %), so 2.0 % of fee is worth about 37 basis points and a borrower comparing "6.00 % plus 2 %" against "6.15 % flat" is comparing 37 against 15 and should say so in one sentence. Run the inversion the other way and the negotiating position sharpens further: the fee that would make the 6.00 % facility exactly as expensive as the 6.15 % rival is **USD 343,244**, or **0.8172 %** of the facility — so the arranger's 840,000 is **USD 496,756 more** than the market-equivalent fee, and that is the number to put on the table, not a complaint about fees in general. Four cautions. The comparison is only valid where the two facilities have the **same amount, tenor, shape and security**; change any of those and the all-in rates are no longer commensurable, which is why Domain 9 (KA 9.3.3) builds a formal like-for-like tranche sheet before quoting all-in costs and why this example is about the method rather than about term-sheet negotiation. Fees that are **capitalised** rather than deducted behave differently — the project borrows the fee, so principal and instalment both rise while proceeds stay at 42,000,000, and the all-in cost is not the same number. Commitment fees on **undrawn** amounts cannot enter this calculation at all without a drawdown profile, because their base is unknown until the construction schedule is fixed (Domain 14, KA 14.2). And the solved rate is a **cost of debt, not a return**: it is what Kestrel pays, and the arranger's own yield differs because the arranger may sell down part of the loan (Domain 13, KA 13.4). What the example establishes for the rest of the book is the discipline: **no rate enters a comparison until it has been solved from the actual stream.**

WORKED EXAMPLE**Worked example 3.2.3c — paying twice a year at the same rate, and the error that hides in it.**

1. **Setup.** Kestrel's lenders propose **semi-annual** debt service instead of annual: 24 payments, the nominal 6.0 % applied as 3.0 % a period. A modeller, wanting to keep the model annual, instead uses the **effective annual rate of 6.09 %** across 12 annual periods. Compute the true semi-annual schedule, the modeller's schedule, and the difference.
2. **Formula.** True: $S = P \times (i_{\text{nom}}/m)/(1 - (1 + i_{\text{nom}}/m)^{-(n \times m)})$ with $m = 2$, $n \times m = 24$; annual cash = 2S. Modeller's: $A_w = P \times \text{EAR}/(1 - (1 + \text{EAR})^{-n})$ with $\text{EAR} = 1.03^2 - 1$ and $n = 12$.
3. **Substitution.** $S = 42,000,000 \times 0.03/(1 - 1.03^{-24}) = 42,000,000 \div 16.935542$. Then $A_w = 42,000,000 \times 0.0609/(1 - 1.0609^{-12})$.
4. **Result.** Semi-annual instalment **USD 2,479,991** (2,479,991.47), annual cash **USD 4,959,983** (4,959,982.94), lifetime interest **USD 17,519,795**. The modeller's annual schedule gives **USD 5,034,383** a year and lifetime interest **USD 18,412,592** — overstating annual debt service by **USD 74,400** and lifetime interest by **USD 892,797**. For reference, the annual-payment facility of WE 3.2.2 costs 5,009,635.23 a year and 18,115,623 of interest.
5. **Interpretation.** Two results, and the surprising one first. **Paying twice a year at the same nominal rate is cheaper in total interest, not dearer** — 17,519,795 against the annual schedule's 18,115,623, a saving of 595,828 — because principal begins retiring six months earlier and every subsequent interest charge is levied on a smaller balance. The frequency of payment and the frequency of compounding pull in opposite directions, and conflating them is the error that makes this topic feel counter-intuitive: more frequent **compounding** raises cost (WE 3.2.3), more frequent **amortisation** lowers it. The honest price of the semi-annual structure is therefore not interest but **liquidity**: the project must find 2,479,991 twice a year instead of 5,009,635 once, and its annual-equivalent cost — the single year-end payment stream with the same present value at the same rate — is **5.8188 %** against the annual facility's 6.0000 %, so a sponsor who values the mid-year cash at more than 18 basis points should prefer the annual shape and one who does not should prefer the semi-annual. That is a treasury decision with a computable threshold, which is the only kind worth having. The second result is the modelling one. The EAR-with-annual-periods substitution is **not a conservative simplification, it is a different loan** — it overstates annual debt service by 74,400 and understates **DSCR** from **1.2871** to **1.2681**, so on this occasion the error happens to be prudent on coverage while being wrong on cash, and on a sculpted or seasonal profile the direction reverses. There is no rule of thumb available: the substitution must simply not be made. Note that it is undetectable by every check in Toolkit 3.T.2 — the schedule closes at zero, total principal equals the loan, and the payment recomputes correctly against its own stated rate — which places it squarely in the **document-conformance** layer of a model audit rather than the arithmetic layer (Domain 13, KA 13.2.1). The facility agreement names the periods; the model implements the periods named.

AI in this KA

Amortisation is where AI-assisted modelling earns its keep — and where it must be caged. Generating a 360-row monthly schedule is exactly the mechanical work a copilot does well; whether the schedule uses the periodic rate correctly, honours the day-count convention in the actual facility agreement, and zeroes the final balance is exactly what it gets wrong silently. The governed workflow

(Domain 6, KA 6.4; Domain 16): AI drafts the schedule; the professional runs the three deterministic checks (final balance zero; Σ principal = P ; payment recomputed independently) before any output leaves the model.

■ KEY TERMS — KA 3.2

Term	Meaning
Annuity / annuity-due	Level periodic stream, in arrears / in advance; the due form is worth $(1 + r)$ times the ordinary.
Annuity factor $AF(r, n)$	$(1 - (1+r)^{-n})/r$; PV of 1 per period for n periods; can never exceed $1/r$.
Perpetuity / growing perpetuity	Level stream forever, $PV = A/r$; growing at $g < r$, $PV = A(1+g)/(r - g)$.
Growing (indexed) annuity	Stream growing at g ; $PV = A \times AF(r^*, n)$ with $r^* = (1+r)/(1+g) - 1$.
Growth-adjusted rate r^*	$(1+r)/(1+g) - 1$; an arithmetic device inside one valuation, never a project hurdle.
Annuity, level-principal, bullet, holiday	The four canonical loan shapes a term sheet offers.
Repayment holiday (grace)	Interest-only periods followed by amortisation over the shortened remainder; concentrates rather than reduces service.
Outstanding balance B_k	$A \times AF(r, n - k)$; the PV of the payments that remain, and the prepayment base.
Balloon / refinancing risk	The bullet's maturity principal and the risk of the rate then prevailing.
Nominal rate / EAR	Quoted annual rate with compounding frequency / its once-a-year equivalent; $EAR \geq i_{nom}$ always.
All-in effective cost	The rate solved from the actual stream against net proceeds; fees are never added to a rate.

■ SAMPLE MCQS — KA 3.2

MCQ 3.2-A [3.2.2 · Application] A USD 42,000,000 loan is repaid by 12 equal annual instalments at 6 %. The instalment is closest to:

- A. USD 3,500,000
- B. USD 2,520,000
- C. USD 5,009,635 ✓ CORRECT
- D. USD 5,706,454

Rationale: $42,000,000 \times 0.06 / (1 - 1.06^{-12}) = 5,009,635$. A divides principal by 12 and ignores interest; B is interest-only on the full balance; D uses a 10-year annuity factor — the wrong-tenor error.

MCQ 3.2-B [3.2.3 · Application] A 6 % nominal rate compounded quarterly has an effective annual rate of:

- A. 6.00 %
- B. 6.09 %
- C. 6.14 % ✓ CORRECT
- D. 6.17 %

Rationale: $(1 + 0.015)^4 - 1 = 6.136\% \approx 6.14\%$. A is the nominal itself; B is semi-annual compounding; D is monthly — each a frequency misread.

MCQ 3.2-C [3.2.1 · Analysis] Two otherwise identical concession bids value the same 20-year availability stream. Bid X used the full-precision annuity factor; Bid Y rounded the factor to four decimals. The most defensible statement is:

- A. the bids differ by an amount that grows with the size of the stream, and only X's practice passes model audit ☒ **CORRECT**
- B. rounding the factor is conservative, so Y understates value and is safer
- C. the difference is always immaterial because four decimals is industry standard
- D. Y's approach is wrong only if the discount rate exceeds 10 %

Rationale: Factor rounding error scales linearly with the cash flows and has no consistent conservative direction (B, D wrong); materiality depends on scale, not convention (C wrong); model audit standards require full-precision arithmetic with display-only rounding.

MCQ 3.2-F [3.2.1 · Analysis] A wayleave pays USD 800,000 per year; the discount rate is 8 %. Modelling it as a 30-year annuity instead of a perpetuity understates its value by:

- A. USD 993,773 — the present value of the post-year-30 tail ☒ **CORRECT**
- B. nothing material — thirty years is effectively forever
- C. USD 4,000,000 — one-third of the perpetuity value
- D. it overstates value, because perpetuities are riskier

Rationale: Perpetuity $800,000/0.08 = 10,000,000$; 30-year annuity $800,000 \times 11.257783 = 9,006,227$; the gap — 9.9 % of value — is the discounted tail. B waves away a million dollars; C invents a fraction; D confuses valuation arithmetic with a risk adjustment that belongs in the rate, not the formula choice.

MCQ 3.2-D [3.2.1 · Application] A 5-year, USD 500,000-per-year lease payable **in advance** is valued at 8 %. Its present value is closest to:

- A. USD 1,996,355
- B. USD 2,156,063 ☒ **CORRECT**
- C. USD 2,500,000
- D. USD 1,848,477

Rationale: Annuity-due = ordinary annuity $\times (1+r)$: $500,000 \times 3.992710 \times 1.08 = 2,156,063$. A prices it as an ordinary annuity (the classic misread); C is the undiscounted total; D divides the ordinary value by 1.08 — the adjustment applied backwards.

MCQ 3.2-E [3.2.2 · Analysis] For the same principal, tenor and rate, which repayment shape has the lowest lifetime interest, and why?

- A. the annuity — its instalments are level, so interest is averaged down
- B. the bullet — deferral shrinks the money's time exposure
- C. level-principal — the balance falls fastest, so less principal is outstanding for less time ☒ **CORRECT**
- D. all three are equal because rate and tenor are equal

Rationale: Interest is rate $\times$ outstanding balance $\times$ time; level-principal retires balance fastest (Kestrel: 16.38m vs 18.12m annuity vs 30.24m bullet). A's "averaging" is not a mechanism; B reverses the truth — the bullet maximises exposure; D ignores the balance path entirely.

MCQ 3.2-G [3.2.1 · Application] A 25-year availability payment of USD 5,600,000 in year-0 terms is **fully indexed at 2.5 %** a year; the discount rate is 8.0 %. Its present value is closest to:

- A. USD 59,778,747
- B. USD 76,111,457 ☒ **CORRECT**
- C. USD 99,768,254
- D. USD 104,363,636

Rationale: $r^* = 1.08/1.025 - 1 = 5.3659\%$, $AF(r^*, 25) = 13.591332$, $PV = 5,600,000 \times 13.591332 = 76,111,457$ (WE 3.2.1d). A values the stream as level and ignores the indexation entirely; C escalates the flows **and** discounts at r^* , the double-count of WE 3.2.1d; D applies the growing-perpetuity form $A(1+g)/(r - g)$ and so values a stream that never ends.

MCQ 3.2-H [3.2.2 · Evaluation] Kestrel's sponsor obtains a three-year repayment holiday on the unchanged USD 42,000,000 / 12-year / 6.0 % facility, against a **1.30× minimum DSCR** covenant. The instalment for years 4 to 12 becomes USD 6,174,934 and year-4 **DSCR** falls to 1.0339 against documented **CFADS** of 6,384,000. The soundest professional conclusion is:

- A. the holiday is cash-neutral, since the same principal is repaid over the same maturity and the lender's return is unchanged
- B. the holiday is prudent: a year-1 **DSCR** of 2.5333 against a 1.30× covenant shows the structure is comfortably covered
- C. the holiday concentrates rather than reduces debt service, costs USD 3,018,782 of extra interest and misses the covenant by USD 1,643,414 of **CFADS** ☒ **CORRECT**
- D. the holiday reduces lifetime interest, because principal repayment is deferred and interest accrues on a smaller average balance

Rationale: Lifetime interest rises from 18,115,623 to 21,134,405 and the binding test moves from year 1 to year 4, where $6,174,933.87 \times 1.30 = 8,027,414.03$ is needed against 6,384,000 available (WE 3.2.2c), so the holiday must be paired with a maturity extension or a smaller drawing. A ignores the three extra years of interest on an undiminished balance; B reads a single non-binding period as the covenant position, the specific error a holiday induces; D reverses the direction — deferring principal leaves the balance larger, not smaller, so interest rises.

MCQ 3.2-I [3.2.3 · Application] Kestrel's USD 42,000,000 / 12-year / 6.0 % facility carries an USD 840,000 arrangement fee deducted from proceeds. Its all-in effective cost is closest to:

- A. 6.0000 %
- B. 6.1667 %
- C. 6.3704 % ☒ **CORRECT**
- D. 8.0000 %

Rationale: Solving $\Sigma 5,009,635.23/(1 + r)^t = 41,160,000$ over 12 years gives 6.3704 % (WE 3.2.3b). A quotes the headline and ignores the fee; B spreads the 2.0 % fee straight-line across twelve years and adds 16.67 basis points to the coupon — the "amortise the fee" error, which omits the time value of paying it at once; D adds the whole 2.0 % to the rate, an error of a full 163 basis points in the same direction.

MCQ 3.2-J [3.2.2 · Comprehension] The closed form $B_k = A \times AF(r, n - k)$ gives Kestrel's principal outstanding after seven of twelve years as **21,102,406**. Which statement shows what the formula is, and is not?

- A. it is the total of the instalments still to be paid, so after year 7 Kestrel owes 25,048,176

- B. it is the present value of the payments that remain, which makes it a check on a schedule that has run exactly as contracted and simply wrong on one that has been restructured, swept or capitalised ☒ **CORRECT**
- C. it is the prepayment price, so a borrower settling early pays B_k and nothing further
- D. it equals the original principal less seven years of principal at the loan's average rate of retirement

Rationale: the formula discounts the remaining contractual payments, which is why it agrees with the schedule recursion to a few cents and why any departure from the contract breaks the formula rather than the schedule (3.2.2). A confuses cash still to be paid with principal outstanding: the difference, **3,945,770.13**, is interest not yet accrued and is not a liability. C is nearly right and materially wrong — B_k is the base, and break costs or prepayment fees sit on top of it. D describes level-principal retirement; an annuity's principal is back-loaded, which is why **50.2438 %** of the loan is still outstanding after 58.33 % of the term.

MCQ 3.2-K [3.2.3 · Analysis] Two like-for-like offers on the same 42,000,000, 12-year, annuity-shaped, equally secured facility: 6.00 % with an 840,000 arrangement fee deducted from proceeds — an all-in cost of 6.3704 % — or 6.15 % with no fee. The treasurer recommends the first, "because the coupon is lower and the fee is a one-off". The best response is:

- A. agree: the 6.00 % coupon governs debt service, and the fee is a transaction cost outside the cost of funds
- B. take the 6.15 % facility, which is cheaper by **22.04** basis points — and put a number on the table, since the fee that would equalise the two is **343,244**, so the arranger is asking **496,756** more than the market-equivalent fee ☒ **CORRECT**
- C. take the 6.15 % facility, because an upfront fee is always a more expensive way to pay a lender than margin
- D. reject both and require the arranger to convert the fee to margin at 16.67 basis points, being the 2.0 % fee spread across the twelve-year tenor

Rationale: a fee is paid once and undiscounted while a margin is paid across a declining balance, so each 1.00 % of upfront fee costs **18.38** basis points of margin on this facility — making 2.0 % of fee worth about 37 and the 15-basis-point coupon difference the cheaper of the two (WE 3.2.3b). A treats the instalment as the cost of funds and ignores that the project receives only 41,160,000. C reaches the right verdict from an overstated rule: the exchange rate is computable, and a fee below 343,244 would make the 6.00 % facility the cheaper one. D is the "amortise the fee" error — dividing a fee by the tenor omits the time value of paying it at time zero, and 16.67 basis points is under half the 37.04 the stream actually gives.

■ SELF-CHECK — KA 3.2

1. What two instant checks validate any amortising schedule, and what tolerance applies? — Final closing balance zero and total principal equal to the loan, both **to within accumulated display rounding**: on Kestrel the printed instalment leaves USD 0.06, which is correct, while 6,000 would not be.
2. Why is an annuity-due worth $(1+r) \times$ the ordinary annuity? — Every payment arrives one period earlier, so each escapes one period of discounting; the ratio is $(1 + r)$ whatever A and n , which makes it a one-line convention test.
3. A term sheet quotes "5.9 % monthly"; another "6.0 % annual". Which is dearer? — The first: $(1 + 0.059/12)^{12} - 1 = 6.06$ % effective, above 6.00 %.

4. State the two ways to compute debt outstanding after seven of twelve years, and why both are needed. — The schedule recursion and $B_k = A \times AF(r, n - k)$; they are computed from different data, so agreement is evidence and disagreement localises the defect to the schedule.
5. Why can an upfront fee not be converted to a margin by dividing it by the tenor? — Because it is paid once and undiscounted while a margin is paid across a declining balance: on Kestrel each 1.00 % of fee is worth **18.38** basis points, not the 8.33 that division would give.
6. A stream indexes at g and is discounted at r . Name the defect that produces a value 31.0818 % too high. — Escalating the flows and also discounting at r^* , counting the indexation twice (WE 3.2.1d).

KNOWLEDGE AREA 3.3

Real-world adjustments: inflation, escalation and currency

Topics: 3.3.1 nominal and real rates · 3.3.2 inflation and escalation · 3.3.3 currency effects · 3.3.4 day-count conventions.

3.3.1 Nominal and real rates — the Fisher relation

Definitions. A **nominal** rate i_{nom} is quoted in money terms; a **real** rate i_{real} is measured in purchasing power, after inflation π . They are linked by the **Fisher relation**:

$$(1 + i_{\text{nom}}) = (1 + i_{\text{real}}) \times (1 + \pi) \quad \text{so} \quad i_{\text{real}} = (1 + i_{\text{nom}})/(1 + \pi) - 1$$

The subtraction shortcut $i_{\text{real}} \approx i_{\text{nom}} - \pi$ is a first-order approximation only — usable for intuition, never for models.

WORKED EXAMPLE**Worked example 3.3.1 — the real cost of Kestrel's equity hurdle.**

1. **Setup.** Kestrel's shareholders require a 9.0 % nominal return; inflation is expected at 3.0 %. What real return are they actually demanding?
2. **Formula.** $i_{\text{real}} = (1 + i_{\text{nom}})/(1 + \pi) - 1$, with $i_{\text{nom}} = 0.09$, $\pi = 0.03$.
3. **Substitution.** $i_{\text{real}} = 1.09 / 1.03 - 1 = 1.058252 - 1$.
4. **Result.** **5.83 %** real (5.8252 % at full precision). The subtraction shortcut says 6.00 % — **17.4757 basis points** high.
5. **Interpretation.** Seventeen basis points sounds academic until it is applied to a 25-year stream, and WE 3.3.1b prices it exactly: on Kestrel's 5,600,000 support stream the shortcut understates value by **USD 1,204,318**, which is **0.2151** of one year's payment. That is the right way to carry the error — as a fraction of a payment rather than as a percentage of a rate — because it is the form in which a board will recognise it. Note the direction: the subtraction shortcut always gives a real rate that is **too high** (it omits the $i_{\text{real}} \times \pi$ cross term), so it always **understates** the value of a real stream, and a bidder using it is systematically bidding low. Note also that the error scales with $i_{\text{nom}} \times \pi$, so it is trivial at 2 % inflation and serious at 10 %: at a 9 % nominal rate and 10 % inflation the shortcut gives -1.00 % against an exact -0.9091 %, and the sign of the real rate — the thing the whole calculation exists to establish — is preserved only by accident. Models must live entirely in one world — nominal cash flows with nominal rates, or real with real. **Mixing them is the single most common TVM defect found in model audits** (Domain 6, KA 6.4; Domain 13, KA 13.2), and the next example is the reason that sentence is a finding rather than an opinion.

WORKED EXAMPLE**Worked example 3.3.1b — the consistency rule, priced four ways.**

1. **Setup.** Kestrel's 25-year support stream is worth **USD 5,600,000 a year in year-0 purchasing power**. Inflation is 3.0 %, so the nominal receipt in year t is $5,600,000 \times 1.03^t$. The board's nominal hurdle is 9.0 %, its real hurdle the 5.8252 % just derived. Value the stream the two consistent ways and the two inconsistent ways, and price each defect.
2. **Formula.** Consistent nominal: $\sum 5,600,000 \times 1.03^t / 1.09^t$. Consistent real: $5,600,000 \times AF(i_{\text{real}}, 25)$. Defect 1 — real flows at the nominal rate: $5,600,000 \times AF(0.09, 25)$. Defect 2 — nominal flows at the real rate: $\sum 5,600,000 \times 1.03^t / 1.058252^t$.
3. **Substitution.** $i_{\text{real}} = 1.09/1.03 - 1 = 0.0582524272$; $AF(i_{\text{real}}, 25) = 12.998413$; $AF(0.09, 25) = 9.822580$. The nominal route is summed term by term as the independent check on the identity.
4. **Result.**

Treatment	Present value	Against the truth
Nominal flows at 9.0000 %	72,791,113	—
Real flows at 5.8252 %	72,791,113	identical to the cent
Real flows at 9.0000 % (defect)	55,006,446	−17,784,667 , −24.4325 %
Nominal flows at 5.8252 % (defect)	100,366,400	+27,575,287 , +37.8828 %
Real flows at the 6.00 % shortcut	71,586,794	−1,204,318, −1.6545 %

1. **Interpretation.** The first two rows are the entire content of the Fisher relation and they are worth stating as a theorem rather than a rule of thumb: **the two consistent treatments are arithmetically identical, not merely close.** 72,791,112.66 both ways, to the cent, which means a modeller can choose whichever world the source documents live in and be provably right — and means that a difference between a real model and a nominal model of the same project is not a basis difference to be reconciled but an **error to be found**. The two defective rows are why this is the domain's most expensive defect. Discounting real flows at a nominal rate deducts inflation twice and destroys **24.4325 %** of the value — on this stream 17,784,667, or **3.1758 years' worth of payments**, and on a project of Kestrel's size enough to turn a fundable concession into a rejected one. The mirror error inflates value by **37.8828 %** and is the more dangerous of the two, because a model that overstates a support stream by 27.6 million produces a bid that wins and then fails to service its debt. Note the **asymmetry**: the two errors are not equal and opposite, since compounding is multiplicative, so a reviewer cannot reason that "the errors will roughly cancel across a portfolio". Three professional points. **The defect is invisible in the outputs and obvious in the inputs**, which is why the audit control is a single declared basis per model — the "one world" line in the assumption register (3.T.1) — rather than a plausibility check on the answer. **The defect's most damaging form is the partial one**: a model that indexes revenue and forgets to index operating cost, or indexes both and leaves a fixed-price O&M contract nominal, is mixing worlds within the cash flow rather than between the flow and the rate, and it produces an error of no predictable sign — which is why Domain 6 (KA 6.4) makes the convention list a model-check artefact and Domain 8 (KA 8.2) escalates each cost line against its own named index. And the choice of world is not free even though the answer is identical: **lenders' covenants, tax computations and depreciation allowances are nominal constructs**, so a real model must be converted to nominal before any covenant or tax line can be computed at all, which is why project models are nearly always built nominal and interpreted in real terms rather than the reverse (Domain 6, KA 6.2.2; Domain 10, KA 10.2.1).




Fig 3.3.3 — One stream, four treatments: what mixing nominal and real costs

3.3.2 Inflation and escalation

Definitions. **Inflation** is the general price level's drift; **escalation** is the contractual or forecast growth of a specific price — a tariff indexed to CPI, labour rates under a collective agreement, steel under a commodity formula. An amount x escalating at rate e for n periods becomes $x \times (1 + e)^n$. Escalation compounds, exactly like interest — and like interest, it is routinely underestimated over long horizons.

WORKED EXAMPLE

Worked example 3.3.2 — an O&M contract's third-year price.

- Setup.** Kestrel's O&M contract prices year-0 services at USD 10,000,000, escalating 4.0 % annually. What is the year-3 price?
- Formula.** $x_n = x_0 \times (1 + e)^n$, with $x_0 = 10,000,000$, $e = 0.04$, $n = 3$.
- Substitution.** $10,000,000 \times 1.04^3 = 10,000,000 \times 1.124864$.
- Result.** USD 11,248,640.
- Interpretation.** Simple-escalation thinking says "+12 %" (USD 11,200,000); compounding adds USD 48,640 by year 3 and the gap widens every year after. In a 25-year operating model the compound-vs-simple escalation choice changes lifecycle cost by whole percentage points — Domain 8 (KA 8.2) builds the full escalated cash-flow machinery on this rule.

Indexation discipline. Real contracts escalate on published indices with definitions, lags, caps and floors (Domain 7, KA 7.3; Domain 12). A model's escalation assumptions must cite the contractual index and its mechanics, not a bare percentage — the toolkit's escalation register (3.T.3) exists for

exactly this. Three of those mechanics have arithmetic that this Knowledge Area must supply rather than name, because each is easy to concede without pricing:

- an **indexation cap** replaces g with $\min(g, \text{cap})$ in every period, so its value is the difference between two growing annuities;
- an **indexation lag** — indexing on the previous period's published figure, the usual arrangement because indices are published in arrears — shifts the whole escalated series back one period, and is therefore worth exactly one period's indexation on the whole stream;
- **partial indexation** at a weighting w (a tariff indexed at, say, 70 % of CPI) replaces g with $w \times g$, not with the index itself, and the difference compounds.

WORKED EXAMPLE**Worked example 3.3.2b — the cap, the lag, and what each is worth.**

1. **Setup.** Kestrel's O&M contract is **USD 2,700,000** a year at base date — the non-power element of the documented USD 4,500,000 of cash operating cost (Domain 2, KA 2.2; the remaining 1,800,000 is electricity, passed through under the water-purchase agreement — Domain 11, KA 11.2.2) — for the 25-year operating life. The sponsor's forecast index runs at **4.0 %**; the draft contract offers full indexation. Kestrel's negotiators want a **3.0 % cap**, and separately want the usual **one-year publication lag** written in. Value the uncapped obligation, the capped obligation and the lagged-and-capped obligation at the 8.0 % project discount rate, and price each concession.
2. **Formula.** Each is a growing annuity (KA 3.2.1): $PV = A \times AF(r^*, n)$ with $r^* = (1 + r)/(1 + g) - 1$. Capped: the same with $g = 3.0 \%$. Lagged: the period- t payment becomes $A(1 + g)^{t-1}$ rather than $A(1 + g)^t$, so the whole stream divides by $(1 + g)$.
3. **Substitution.** Uncapped: $r^* = 1.08/1.04 - 1 = 3.846154 \%$, $AF = 15.879244$, $PV = 2,700,000 \times 15.879244$. Capped: $r^* = 1.08/1.03 - 1 = 4.854369 \%$, $AF = 14.301981$, $PV = 2,700,000 \times 14.301981$. Lagged: the capped figure $\div 1.03$.
4. **Result.** Uncapped **USD 42,873,960** · capped **USD 38,615,349** · capped and lagged **USD 37,490,630**. The **cap is worth USD 4,258,610** (9.9329 % of the uncapped obligation); the **lag is worth a further USD 1,124,719**; together they remove **USD 5,383,329** from the obligation. In the final year the capped price is **5,653,200** against the uncapped **7,197,758** — a single-year saving of 1,544,558.
5. **Interpretation.** The cap is worth **USD 4,258,610** — 7.10 % of Kestrel's entire 60,000,000 capital envelope — and it is a one-line drafting change with no cash cost to either party at signature. That is the finding: **indexation mechanics are among the highest-value-per-word terms in a project contract, and they are routinely agreed without being valued**. Three readings make the number usable. As a **level annual equivalent** the cap is worth $4,258,610.20 \div AF(0.08, 25) = \text{USD } 398,941$ a year, which is the form to put beside a fee or a price concession when trading it — a counterparty asking 300,000 a year for the cap is offering a good deal and one asking 600,000 is not. As a **conditional** value it is worth nothing if the index runs at or below 3.0 % and rises steeply above it: at a 5.0 % outturn the same cap is worth **USD 9,157,382**, more than double, so the cap is an option on inflation and its value is convex in the outturn — which means valuing it at the single-point forecast systematically understates it, and a proper treatment stresses the index (Domain 7, KA 7.4; Domain 11, KA 11.3). And the lag's value is an exact identity worth remembering because it needs no computation: **a one-period indexation lag on a fully indexed stream is worth $1 - 1/(1 + g)$ of the stream** — here 2.9126 %, giving 1,124,719 on 38,615,349 — so a model that ignores a contractual lag overstates an indexed cost, and understates an indexed revenue, by that fixed fraction. Three cautions. A cap is only worth this much if it is **cumulative rather than annual in effect**: a contract capping each year's increase at 3.0 % is what has been valued here, whereas a contract capping the increase at 3.0 % but permitting catch-up when the index later falls back is worth materially less, and the two are distinguished by a subordinate clause. A cap on a **cost** helps the payer while a cap on a **revenue** index hurts the receiver, so the same clause is worth +4,258,610 on the O&M contract and -4,258,610 on a tariff, and a project holding both must value them together rather than celebrating one. And caps, floors and collars are **enforceability- and drafting-sensitive** where the named index ceases publication, is rebased, or is redefined by its publisher: the fallback mechanism is the clause that matters most and is valued least, and

its drafting is a matter for **qualified legal counsel in the governing jurisdiction** rather than for the model (Domain 12, KA 12.2).




Fig 3.3.1 — What 3 % inflation does to USD 1,000,000 of purchasing power




Fig 3.3.2 — Compound versus simple escalation of a USD 10,000,000 cost at 4 %

3.3.3 Currency effects

The problem. Project cash flows often arrive in one currency while debt service, equipment or returns are owed in another. Two rates matter: the **spot rate** now, and the **forward rate** at which future exchange can be contracted. Forwards are priced off interest differentials (covered interest parity, stated here in its textbook form):

$$F \approx S \times (1 + i_{\text{quote}}) / (1 + i_{\text{base}})$$

WORKED EXAMPLE**Worked example 3.3.3 — a one-year SAR/USD forward.**

1. **Setup.** Spot USD 1 = SAR 3.7500 (the indicative peg rate used throughout this book). One-year money costs 5.0 % in USD and 5.5 % in SAR. Estimate the one-year forward.
2. **Formula.** $F = S \times (1 + i_{\text{SAR}}) / (1 + i_{\text{USD}})$, with $S = 3.7500$.
3. **Substitution.** $F = 3.7500 \times 1.055 / 1.05$.
4. **Result.** SAR 3.7679 per USD.
5. **Interpretation.** The forward is not a forecast; it is arithmetic — the rate at which borrowing in one currency and lending in the other breaks even. A project that leaves a currency mismatch unhedged is not "expecting the spot to hold"; it is running an open position whose size Domain 11 (KA 11.3) teaches you to measure and whose contractual mitigations Domain 12 allocates. The direction is the part worth internalising, because it is counter-intuitive and it decides how a forward strip looks on a page: the **higher-interest-rate currency trades at a forward discount**, so SAR — the 5.5 % currency here — buys fewer USD forward than spot, moving from 3.7500 to 3.7679. That is not a market view about Saudi Arabia; it is the only rate at which a bank can hedge the position without giving money away, and any model showing a gain from receiving in the higher-rate currency and converting forward has either mispriced the forward or is quietly forecasting. **Assumption honesty:** actual pegs, spreads and convertibility restrictions are jurisdiction- and time-specific; every currency figure in this book is illustrative.

WORKED EXAMPLE**Worked example 3.3.3b — two routes to one hedged value, and why they must agree.**

1. **Setup.** A grantor variant pays Kestrel **SAR 20,000,000 a year for five years**, annually in arrears, while Kestrel's debt service and its board reporting are in USD. Spot **USD 1 = SAR 3.7500**; five-year money costs **5.0 % in USD** and **5.5 % in SAR**. Value the stream in USD by both available routes.
2. **Formula. Route 1 — discount then convert:** value the stream in SAR at the SAR rate, then convert the single figure at spot: $PV_USD = [C \times AF(i_SAR, n)] \div S$. **Route 2 — convert then discount:** convert each year's receipt at that year's forward $F_t = S \times [(1 + i_SAR)/(1 + i_USD)]^t$, then discount the resulting USD flows at the USD rate: $PV_USD = \sum (C/F_t)/(1 + i_USD)^t$.
3. **Substitution.** Route 1: $AF(0.055, 5) = 4.270284$; $20,000,000 \times 4.270284 = 85,405,690$ SAR; $\div 3.7500$. Route 2: forwards **3.7679 · 3.7858 · 3.8038 · 3.8219 · 3.8401**, giving USD receipts **5,308,057 · 5,282,900 · 5,257,863 · 5,232,944 · 5,208,143**, each discounted at 5.0 %.
4. **Result.** Route 1 **USD 22,774,851** (22,774,850.54). Route 2 **USD 22,774,851** — the same figure to the cent. Individual discounted amounts: $5,055,292 \cdot 4,791,746 \cdot 4,541,940 \cdot 4,305,156 \cdot 4,080,717$.
5. **Interpretation.** The agreement is not a coincidence and it is not an approximation; it is **covered interest parity, and it is the reason a currency conversion cannot create or destroy value on its own**. That single fact retires a whole family of bad arguments heard in project reviews: "we should take payment in the stronger currency", "converting at forward rates improves the return", "the FX gain funds the contingency". If two internally consistent routes to the same hedged cash flow give different answers, the difference is a defect — a spot rate used where a forward belongs, a foreign stream discounted at the domestic rate, or an inconsistent tenor — and the reviewer's test is to run both routes and demand agreement, which costs one column. Note where the real exposure actually lives, because parity removes only the arithmetic question. **Route 2 requires the forwards to be contracted, not merely computed:** an uncontracted forward is a forecast wearing a formula, and the position remains open. The residual risks after a full hedge are the ones that matter in practice — **basis** (the hedge tenor rarely matches the cash-flow tenor exactly), **counterparty credit** on the hedge provider, the **cost** of the hedge itself (parity is a mid-market identity; a real bank quotes a spread on both sides, and the spread is the only part of this calculation that is genuinely a cost), and **convertibility and transfer** — the ability to move money at all, which no forward can hedge and which is a political-risk question (Domain 11, KA 11.3; Domain 12 allocates it). The professional caution: parity holds where **both currencies' money markets are freely accessible at the quoted rates**, which is exactly what fails in the jurisdictions where projects most need hedging, and pegged-currency arrangements are policy choices that can be changed. Currency-mismatch structures, exchange-control consents and the enforceability of hedge collateral are matters for **qualified legal and tax counsel in the relevant jurisdictions**; no treatment in this book should be read as applying universally.

3.3.4 Day-count conventions

The problem. "Three months' interest" is not one number. Facility agreements specify a **day-count convention** — how days are counted and over what year they are divided — and the convention moves real money on large balances:

Convention	Rule	Typical home
30/360	Every month 30 days, year 360	Bonds, some term loans
actual/360	Actual days elapsed, year 360	Money markets, most floating-rate loans
actual/365	Actual days elapsed, year 365	Sterling markets, some jurisdictions

WORKED EXAMPLE**Worked example 3.3.4 — one quarter, three conventions.**

- Setup.** Interest accrues on Kestrel's USD 42,000,000 drawn balance at 6.0 % for one calendar quarter that contains **92 actual days**. Compute the interest under each convention.
- Formula.** Interest = balance × rate × (days counted / year basis).
- Substitution.** 30/360: $42,000,000 \times 0.06 \times 90/360$. actual/360: $\times 92/360$. actual/365: $\times 92/365$.
- Result.** 30/360 **USD 630,000** · actual/365 **USD 635,178** · actual/360 **USD 644,000**.
- Interpretation.** The spread between conventions is USD 14,000 on one quarter of one drawdown — and actual/360 is systematically the most expensive because it counts every real day over a short year. Models must implement the convention named in the facility agreement (Domain 12), and the assumption register (3.T.1) records it per instrument; "6 % divided by 4" is not a convention, it is a guess. Note which comparisons are and are not fair here: 30/360 and actual/360 differ **because the numerator differs** (90 against 92, a calendar accident that reverses in February), while actual/360 and actual/365 differ **because the denominator differs**, which is a systematic uplift and not an accident. Only the second of those two differences persists over a full year, and WE 3.3.4b computes what it is worth.

WORKED EXAMPLE**Worked example 3.3.4b — the same convention across a whole year, and across the facility.**

1. **Setup.** Take Kestrel's USD 42,000,000 balance at 6.0 % and step back from the quarter to the term. What does the actual/360 convention cost over one full 365-day year, what quoted rate is it equivalent to, and what does it do to the 12-year annuity schedule and its coverage?
2. **Formula.** Over a full year, actual/360 charges $\text{balance} \times \text{rate} \times 365/360$, so the convention is arithmetically a rate uplift of $365/360 = 1.0138889$ — an **effective simple annual rate** of $i_{\text{nom}} \times 365/360$. Rebuild the annuity on that rate: $A' = P \times r' / (1 - (1 + r')^{-12})$.
3. **Substitution.** $42,000,000 \times 0.06 \times 365/360$ against $42,000,000 \times 0.06$. Then $r' = 0.06 \times 365/360 = 0.0608333333$ and $A' = 42,000,000 \times 0.0608333333 / (1 - 1.0608333333^{-12})$.
4. **Result.** One year of interest **USD 2,555,000** under actual/360 against **USD 2,520,000** under 30/360 — an uplift of **USD 35,000**, or **1.3889 %** of all interest. The convention is equivalent to a quoted rate of **6.0833 %** — **8.33 basis points** above the headline. Across the twelve-year annuity the instalment rises from 5,009,635.23 to **USD 5,032,548** (5,032,547.52, +22,912 a year) and lifetime interest from 18,115,623 to **USD 18,390,570** — **USD 274,947** more. **DSCR** falls from **1.2743** to **1.2685**. In a leap year the same balance accrues **USD 2,562,000**.
5. **Interpretation.** The convention is worth **8.33 basis points** and appears in no rate comparison anyone runs. That is the professional point, and it generalises: **the day-count basis belongs in the all-in cost calculation of WE 3.2.3b, on the same footing as a fee**, because 1.3889 % of all interest on Kestrel's facility is USD 274,947 — **73.82 %** of one year's covenant headroom at a 1.20× requirement ($6,384,000 - 1.20 \times 5,009,635.23 = 372,437.72$), and more than the difference many borrowers spend weeks negotiating out of the margin. Three readings. The uplift is **exactly 365/360 and independent of the rate, the balance and the tenor**, which makes it the easiest sensitivity in the domain to carry in the head: any actual/360 facility costs 1.3889 % more interest than the same facility on a 365-day basis, and 1.6667 % more than 30/360 in a 366-day year ($366/360$). The **DSCR** consequence of **0.0058** is small in isolation and is exactly the kind of small consistent bias that matters on a structure sized to 1.20×, because it is present in every period rather than in one. And the convention interacts with the payment calendar: on 30/360 every period is identical, so a model can use a single periodic rate, whereas on actual/360 or actual/365 **each period's day count differs**, February and leap years included, so a properly built model needs a date-driven interest calculation rather than a rate divided by a frequency — which is a model-architecture requirement (Domain 6, KA 6.1) and not a refinement. The caution: conventions are **contractual, not conventional**. Market practice differs by currency, product and jurisdiction and changes over time; the only authority is the facility agreement's own definition, and where a facility is silent or ambiguous on the basis, the point is one for **qualified legal counsel in the governing jurisdiction** before the model is built on an assumption.

AI in this domain — the systematic view

TVM is deterministic, which makes it the safest place in finance to use machine assistance and the most dangerous place to trust it unchecked: a wrong exponent produces a plausible number, not an absurd one. The domain's governed workflow, applied wherever Domains 4-16 discount anything:

1. **AI proposes** — drafts the factor table, schedule or escalated series.

2. **Deterministic checks** — the sixteen invariants of 3.A.4, of which four catch the errors a machine assistant specifically makes: $AF(r, n) \times r = 1 - DF(n)$ (a generated factor column against its own summary cell), $B_k = A \times AF(r, n - k)$ against the recursion (a generated schedule against itself), the real-versus-nominal identity (a generated indexed stream, where the double-count of WE 3.2.1d is the single most likely machine output), and $EAR \geq i_{nom}$ (a frequency conversion). Plus one hand-recomputed cell per block, by a different method than the one generated.
3. **Assumption register** — rate, basis (nominal/real), compounding frequency, **payment frequency**, day-count basis, timing convention, index (with lag, cap and weighting) and currency of every stream written down (toolkit 3.T.1). This is where machine assistance is weakest and it is not a modelling weakness: a copilot cannot know which convention the facility agreement names, and it will produce a defensible schedule against the wrong one without signalling any uncertainty (WE 3.2.3c is the archetype — every check passes, the document is not implemented).
4. **The professional decides and remains accountable** — no AI-produced number reaches a board paper, bid or lender report without a named human owner (Domain 16, KA 16.4).

What must not be delegated, stated precisely. The three inverse operations of this domain — solving for a rate (WE 3.1.2b, 3.2.3b), solving for a term, and solving for a value-neutral payment (Case study A) — are where machine assistance is most useful and most dangerous, because a numerical solver returns a plausible root without telling anyone which root, whether the function was monotone, or whether the stream it solved was the stream in the contract. Require the **stream** to be shown alongside the solved rate, not merely the rate; require the solution to be **verified by substitution** (discount the stream at the solved rate and confirm it returns the net proceeds to the cent, as WE 3.2.3b does); and record the **net-proceeds definition** used, because that single definitional choice moves the answer more than any arithmetic in the calculation.

■ KEY TERMS — KA 3.3

Term	Meaning
Nominal / real rate	Money-terms rate / purchasing-power rate; linked by Fisher.
Fisher relation	$(1+i_{nom}) = (1+i_{real})(1+\pi)$; the subtraction shortcut always overstates i_{real} .
Consistency rule	One world per model; the two consistent treatments are identical to the cent, so a difference is an error and not a basis.
Inflation π / escalation e	General price drift / specific contractual price growth.
Indexation	Contractual escalation by a published index, with lags, caps, floors and weightings.
Indexation cap / lag / weighting	$\min(g, \text{cap})$ per period $\cdot$ index published in arrears, worth $1 - 1/(1+g)$ of the stream $\cdot$ partial indexation at $w \times g$.
Spot / forward rate	Exchange rate now / contracted for a future date.
Covered interest parity	Forward $\approx$ spot $\times$ interest-ratio; the no-arbitrage forward, and the reason two routes to one hedged value agree.
Day-count basis	The contractual numerator and denominator for accruing interest; actual/360 is a $365/360$ uplift on all interest.

■ SAMPLE MCQS — KA 3.3

MCQ 3.3-A [3.3.1 · Application] Nominal return 9 %, inflation 3 %. The real return is closest to:

A. 6.00 %

- B. 5.83 % ☒ **CORRECT**
- C. 12.27 %
- D. 3.00 %

Rationale: $1.09/1.03 - 1 = 5.83\%$. A is the subtraction approximation; C multiplies $1.09 \times 1.03 - 1$ (compounding inflation on instead of off); D confuses the inflation rate itself with the real return.

MCQ 3.3-B [3.3.2 · Application] A USD 10,000,000 cost escalating at 4 % per year is, in year 3:

- A. USD 11,200,000
- B. USD 10,400,000
- C. USD 12,486,400
- D. USD 11,248,640 ☒ **CORRECT**

Rationale: $10,000,000 \times 1.04^3 = 11,248,640$. A escalates simply ($3 \times 4\%$); B stops at one year; C applies four periods' escalation with a decimal slip.

MCQ 3.3-C [3.3.1 · Analysis] A model discounts real (uninflated) cash flows at the sponsor's nominal 9 % hurdle. The result:

- A. overstates value, because inflation is counted twice
- B. understates value, because inflation is removed from the flows but still charged in the rate ☒ **CORRECT**
- C. is correct if inflation is below 5 %
- D. is correct because discount rates are always nominal

Rationale: Real flows with a nominal rate deduct inflation twice — once from the flows, once inside the rate — so value is systematically understated. The consistency rule admits no threshold (C) and no default (D); A reverses the direction of the error.

MCQ 3.3-F [3.3.1 · Application] A model shows a nominal cash flow of USD 2,000,000 in year 5; inflation is 3 %. Its value in today's purchasing power (real terms) is:

- A. USD 2,000,000 — real and nominal are equal at year 5
- B. USD 1,725,218 ☒ **CORRECT**
- C. USD 1,700,000
- D. USD 2,318,548

Rationale: $2,000,000 / 1.03^5 = 1,725,218$ — deflating by the price level, not discounting for time value (that happens separately, at a real rate). A ignores five years of inflation; C deflates simply ($2,000,000 \times (1 - 0.03 \times 5) = 1,700,000$); D multiplies by 1.03^5 — inflating instead of deflating.

MCQ 3.3-D [3.3.4 · Application] A USD 42,000,000 balance accrues at 6 % over a 92-day quarter. Under **actual/360** the interest is:

- A. USD 630,000
- B. USD 635,178
- C. USD 644,000 ☒ **CORRECT**
- D. USD 620,548

Rationale: $42,000,000 \times 0.06 \times 92/360 = 644,000$. A is 30/360 (90/360); B is actual/365; D uses 90/365 — mixing the two conventions' halves.

MCQ 3.3-E [3.3.2 · Analysis] A 25-year operating model escalates O&M at "4 % simple" to be "conservative". The effect is:

- A. conservative — simple escalation always overstates cost
- B. anti-conservative — compound escalation exceeds simple by an amount that grows every year, so late-life costs are materially understated ☒ **CORRECT**
- C. neutral — the choice only redistributes cost between years
- D. correct — operating contracts always escalate simply

Rationale: Escalation compounds (contracts index on last year's indexed price): by year 25 the compound multiple $1.04^{25} \approx 2.67$ far exceeds the simple 2.00. A claims the reverse; C ignores the widening gap; D asserts a contractual universal that KA 3.3.2's indexation discipline contradicts.

MCQ 3.3-G [3.3.1 · Analysis] A 25-year stream worth USD 5,600,000 a year **in year-0 purchasing power** is valued against a 9.0 % nominal hurdle with inflation at 3.0 %. Which statement is correct?

- A. discounting the nominal (escalated) flows at 9.0 % and discounting the level real flows at 5.8252 % both give USD 72,791,113 — they are arithmetically identical ☒ **CORRECT**
- B. discounting the level real flows at 9.0 % is correct, and gives USD 55,006,446
- C. discounting the nominal flows at 5.8252 % is correct, and gives USD 100,366,400
- D. the real treatment is an approximation of the nominal treatment and the two differ by the inflation cross term

Rationale: The Fisher relation makes the two consistent treatments equal to the cent (WE 3.3.1b). B is the double-deduction defect, understating value by 24.4325 %; C is the mirror defect, overstating it by 37.8828 %; D asserts an approximation where an identity holds — the cross term is inside *i_{real}*, which is why the subtraction shortcut, and not the exact relation, is the approximation.

MCQ 3.3-H [3.3.2 · Evaluation] An O&M obligation of USD 2,700,000 at base date runs 25 years and is fully indexed; the forecast index is 4.0 % and the discount rate 8.0 %. A negotiator secures a **3.0 % cap** on annual indexation. The value of that concession to the payer is closest to:

- A. nil — the cap only bites if the index exceeds 3.0 %, which is a future event
- B. USD 398,941
- C. USD 1,544,558
- D. USD 4,258,610 ☒ **CORRECT**

Rationale: $2,700,000 \times [AF(3.846154 \%, 25) - AF(4.854369 \%, 25)] = 42,873,960 - 38,615,349 = 4,258,610$ (WE 3.3.2b). A contradicts its own premise — the forecast is 4.0 %, so on the stated assumptions the cap bites in every period; B is the correct value expressed as a **level annual equivalent** ($\div AF(0.08, 25)$), a right number answering a different question; C is the **year-25 single-period** saving, undiscounted and counted once.

MCQ 3.3-I [3.3.4 · Application] A USD 42,000,000 balance accrues at 6.0 % on an **actual/360** basis across a full 365-day year. The interest charged, and the quoted rate the convention is equivalent to, are:

- A. 2,520,000 and 6.0000 %
- B. 2,555,000 and 6.0833 % ☒ **CORRECT**
- C. 2,562,000 and 6.1000 %
- D. 2,485,479 and 5.9178 %

Rationale: $42,000,000 \times 0.06 \times 365/360 = 2,555,000$, and $0.06 \times 365/360 = 6.0833\%$ (WE 3.3.4b). A is the 30/360 figure, which charges 360 days over 360; C is a 366-day leap year on the same convention; D inverts the fraction to $360/365$, the direction error that makes an expensive convention look cheap.

MCQ 3.3-J [3.3.1 · Analysis] A model audit finds that a project's real model values Kestrel's 25-year support stream at **55,006,446** while its nominal model values the same stream at **72,791,113**. The modeller proposes to "reconcile the two bases and present the pair as a range". The reviewer should:

- A. accept — a real and a nominal view of one project legitimately differ, and a range is the honest presentation
- B. reject the proposal and require the defect to be found: the two consistent treatments are arithmetically identical to the cent, so a **17,784,667** difference is an error, and this one carries the signature of real flows discounted at the nominal 9.0 % rate ✓ CORRECT
- C. accept the nominal figure and delete the real model, since covenants, tax and depreciation are nominal constructs
- D. average the two, document the choice as an assumption, and proceed

Rationale: the Fisher relation makes the consistent nominal and consistent real valuations equal, so a difference is not a basis to be reconciled but a defect to be located — and its size, **-24.4325 %**, identifies which defect it is (WE 3.3.1b). A dignifies an error as a perspective. C reaches a defensible destination by the wrong route: the model must indeed be nominal before any covenant or tax line can be computed, but deleting the real model conceals the error instead of fixing it, and the real model may well be the correct one. D averages a right number with a wrong one and calls the result an assumption.

MCQ 3.3-K [3.3.2 · Evaluation] Kestrel's 3.0 % cap on the indexation of a 2,700,000 O&M base is worth **4,258,610** in present value at the sponsor's 4.0 % index forecast — a level annual equivalent of **398,941**. The contractor offers to remove the cap in exchange for cutting the base price by 500,000 a year. The soundest recommendation is:

- A. accept: 500,000 a year exceeds the cap's level annual equivalent by **101,059** a year, so the trade creates value
- B. refuse on these terms: the cap is an option on the index and its value is convex in the outturn, so a single-point valuation understates it — at a 5.0 % outturn the cap is worth **9,157,382**, a level annual equivalent of **857,852**, and the trade must be priced against a stressed index ✓ CORRECT
- C. refuse, because a project should never exchange a contractual protection for a price concession
- D. accept, provided the 500,000 reduction is itself indexed at 3.0 % so that the two legs escalate together

Rationale: the cap pays nothing at or below 3.0 % and more the further the index runs above it, so its expected value exceeds its value at the mean forecast, and 500,000 a year buys away protection worth 857,852 a year in precisely the state the protection exists for (WE 3.3.2b). A is the arithmetic correctly done at one point of a convex payoff — the commonest way an option is given away. C forgoes a class of trade that is frequently value-creating; the objection is to the price, not the principle. D improves the fixed leg — an indexed 500,000 is worth **7,150,991** against **5,337,388** level — and still leaves the payer short in the stressed states, so it changes the price without answering the objection.

MCQ 3.3-L [3.3.4 · Comprehension] A facility accrues interest on an **actual/360** basis. Which statement restates what that convention does?

- A. it charges interest on actual days elapsed, so the cost depends on how many days each period happens to contain and averages out across a full year
- B. over a full year it charges $365/360$ of the interest a 365-day basis would — a **1.3889 %** uplift on all interest, independent of the rate, the balance and the tenor, and equivalent on a 6.0 % facility to a quoted **6.0833 %** ✓ CORRECT
- C. it is the market standard for floating-rate lending, so it carries no cost relative to the quoted rate
- D. it lowers the effective cost, because dividing by 360 rather than 365 produces a smaller daily rate

Rationale: the denominator is short by five days while the numerator counts them, so the uplift is exactly $365/360$ over a full year and does not average away (WE 3.3.4b) — **8.33** basis points at 6 %, **35,000** on Kestrel's 42,000,000 balance for one year and **274,947** across the twelve-year schedule. A describes the numerator effect, which does reverse between a short February and a 92-day quarter, and misses the denominator effect, which does not. C confuses prevalence with price. D inverts the arithmetic: a smaller denominator produces a larger daily rate.

■ SELF-CHECK — KA 3.3

1. State the consistency rule. — Nominal flows with nominal rates, real flows with real rates; never mixed in one calculation. The two consistent treatments give the identical figure, so any difference between a real and a nominal model of one project is a defect, not a basis.
2. Why does a 25-year concession make the Fisher shortcut dangerous? — The 17.4757 bp error (at 9 %/3 %) compounds across every one of 25 discount factors, and on Kestrel's stream it understates value by USD 1,204,318, or 0.2151 of one year's payment.
3. Is a forward rate a forecast? — No: it is the no-arbitrage consequence of today's spot and the two interest rates, and it is only a hedge once it is **contracted**.
4. What is a one-year indexation lag worth on a stream indexed at g ? — Exactly $1 - 1/(1 + g)$ of the stream — 2.9126 % at $g = 3$ % — which needs no computation once it is recognised.
5. Two routes value the same SAR stream in USD and differ by 400,000. What is the finding? — A defect, not a basis difference: covered interest parity makes the routes identical, so a spot rate has been used where a forward belongs, or a foreign stream has been discounted at the domestic rate.
6. Why does an actual/360 facility not appear more expensive in a rate comparison? — Because the uplift lives in the day-count definition rather than the quoted rate; it is worth 8.33 basis points at 6 %, and it belongs in the all-in cost alongside fees.

— Advanced topics — Domain 3

3.A.1 Continuous compounding

As compounding frequency $m \rightarrow \infty$, $(1 + r/m)^{mn} \rightarrow e^{rn}$. USD 100,000 at 8 % for 3 years compounds continuously to $100,000 \times e^{0.24} = \text{USD } 127,124.92$ — against 125,971.20 annually. In project work continuous compounding appears mainly in derivative pricing and some academic

appraisal literature; its practical value here is as a bound: no compounding frequency can push growth beyond e^{rn} .

Two quantities make the bound usable. First, the **continuously compounded equivalent** of a quoted annual rate is $\ln(1 + i)$: 6.0 % annual is **5.8269 %** continuous ($\ln 1.06 = 0.0582689081$) and 8.0 % annual is **7.6961 %**. Second, the bound is **tight**, which is the practically important fact: at 6 %, monthly compounding gives an effective 6.1678 % against the continuous limit's 6.1837 %, so everything from monthly to instantaneous fits inside **1.5873 basis points** — of which daily compounding already uses 1.5350 (KA 3.2.3 gives the full ladder). A model arguing about compounding frequency beyond monthly is arguing about less than two basis points, and a model whose continuous and monthly results differ by more than that has an error rather than a refinement.

One confusion is worth naming because the numbers invite it. The continuous equivalent of 6 %, **5.8269 %**, sits within two basis points of the real rate derived in KA 3.3.1 from a 9 % nominal and 3 % inflation, **5.8252 %**. The two have nothing to do with each other — one is $\ln(1 + i)$, the other is $(1 + i_{\text{nom}})/(1 + \pi) - 1$ — and a model that quotes "5.83 %" without saying which it means has lost the audit trail on the most confusable pair of numbers in the domain. Label rates by their construction, not by their value.

3.A.2 Irregular timing and period conventions

Real cash flows do not arrive on anniversary dates. Three conventions bridge the gap: **exact-date discounting** (each flow discounted by its actual day count — the XNPV approach, standard in transaction models); the **mid-period convention** (flows treated as arriving mid-period, appropriate for continuous operations revenue); and **period-end** (conservative for receipts, default in lender base cases). The convention is an assumption — it belongs in the assumption register, it changes results by up to half a period's discounting, and model audits (Domain 13, KA 13.2) check that one convention is applied everywhere.

WORKED EXAMPLE**Worked example 3.A.2 — the payment on day 500.**

1. **Setup.** A USD 1,000,000 completion payment falls on **day 500** from the valuation date; the discount rate is 9.0 % annual. Compare exact-date discounting with the period-end habit of "call it year 2".
2. **Formula.** Exact-date: $PV = x / (1 + r)^{(days/365)}$.
3. **Substitution.** $1,000,000 / 1.09^{(500/365)} = 1,000,000 / 1.09^{1.36986}$.
4. **Result. USD 888,650.** "Year 2" rounding gives 841,680 — **USD 46,970 low**; "year 1" gives 917,431 — USD 28,781 high.
5. **Interpretation.** Bucketing a mid-period flow to the nearer anniversary mis-states value by up to half a period's discounting — nearly 5 % here. Transaction models discount on dates; period models declare mid-period or period-end explicitly and apply it everywhere. The convention chosen matters less than its disclosure and consistency. The scale of "less than its disclosure" is worth pricing on the master thread rather than left as a maxim. Kestrel's 25-year support stream is worth **USD 59,778,747** on the period-end convention; on the **mid-period** convention every flow moves half a year earlier, so the whole stream multiplies by $1.08^{0.5} = 1.0392305$, giving **USD 62,123,896** — **USD 2,345,149**, or **3.9230 %**, from a convention choice that no cash flow and no contract has changed. On the **annuity-due** reading (a full period earlier) it is **USD 64,561,046** — 8.0 % above period-end and a further **3.9230 %** above mid-period, each step being the same $1.08^{0.5}$ factor applied again. Three points follow. The three conventions **bracket** rather than approximate one another: for a continuously earning operating revenue the mid-period convention is the accurate one and period-end is the conservative one, so period-end is not "right" — it is a deliberate 3.9230 % understatement, and describing it as prudence is only honest if the size of the prudence is stated. The convention must be **the same on both sides of the coverage ratio**: applying mid-period to revenue and period-end to debt service manufactures 3.92 % of **DSCR** out of nothing, which is a document-conformance failure rather than a rounding one, and debt service is contractually dated so it is never a matter of convention at all. And the multiplier is **exactly $(1 + r)^{0.5}$ regardless of the stream's shape or length**, which makes the whole adjustment a single cell and the whole check a single division — a reviewer suspecting a convention mismatch divides the two models' present values and looks for 1.0392305 (Domain 6, KA 6.1; Domain 13, KA 13.2.1).

3.A.3 Term structures — when one rate is not enough

A single flat r assumes money has the same price at every horizon. Markets disagree: rates form a **term structure**, and precise valuation discounts each period's flow at that period's rate (equivalently, its own $DF(t)$ from a curve). Project models typically justify a flat rate as a deliberate simplification of a curve — acceptable when documented and stress-tested (Domain 6, KA 6.4), a silent error when inherited unexamined from a template.

WORKED EXAMPLE**Worked example 3.A.3 — flat rate versus the curve.**

1. **Setup.** A contractor is owed USD 1,000,000 at the end of each of years 1 and 2. The spot curve prices 1-year money at 5.0 % and 2-year money at 7.0 %; the model uses a flat 6.0 %. How far wrong is the flat rate?
2. **Formula.** Curve: $PV = x/(1 + r_1) + x/(1 + r_2)^2$. Flat: $PV = x/(1+r) + x/(1+r)^2$.
3. **Substitution.** Curve: $1,000,000/1.05 + 1,000,000/1.07^2 = 952,381 + 873,439$. Flat: $943,396 + 889,996$.
4. **Result.** Curve **USD 1,825,820**; flat **USD 1,833,393** — the flat model overstates value by **USD 7,573** (0.4 %).
5. **Interpretation.** The flat 6 % "averages" the curve but misprices both flows — too harsh on the near one, too kind on the far one — and the errors do not cancel unless the stream is symmetric around the average tenor. For a two-flow example the drift is small. The audit question is never "is the rate reasonable?" but "which curve does this rate summarise, and has the summary been stress-tested?"

WORKED EXAMPLE**Worked example 3.A.3b — the same question at concession scale.**

1. **Setup.** The two-flow example above understates the problem, so put the curve against Kestrel's own 25-year support stream of **USD 5,600,000 a year**. Assume a documented upward-sloping spot curve rising **10 basis points a year** from **6.00 %** for one-year money to **8.40 %** for 25-year money — an illustrative shape, chosen to be simple enough to reproduce and steep enough to matter. The board's model uses a flat **8.0 %**. How wrong is the flat rate, and what flat rate would have been right?
2. **Formula.** Curve: $PV = \sum 5,600,000 / (1 + r_t)^t$ with $r_t = 0.060 + 0.0010 \times (t - 1)$. Flat: $5,600,000 \times AF(0.08, 25)$. The **PV-equivalent flat rate** is the r solving $5,600,000 \times AF(r, 25) = PV(\text{curve})$.
3. **Substitution.** Twenty-five terms discounted at their own rates, against $5,600,000 \times 10.674776$; then solve $AF(r, 25) = 63,564,261.78 \div 5,600,000 = 11.350761$.
4. **Result.** Curve **USD 63,564,262**; flat 8 % **USD 59,778,747**. The flat rate **understates the stream by USD 3,785,515**, or **6.3325 %**. The PV-equivalent flat rate is **7.2946 %** — not the curve's arithmetic mean of 7.20 %, and 70.54 basis points below the rate the board used.
5. **Interpretation.** The two-flow example drifted by 0.4 %; the concession drifts by **6.3325 %** and USD 3,785,515 — more than twice the 1,778,747 by which Case study A's whole support decision turns — which is the honest scale of the "flat rate as a simplification" question and the reason this Advanced topic exists. Three readings. **The equivalent flat rate is not the average rate.** 7.2946 % against an arithmetic mean of 7.2000 % — the discrepancy arises because discount factors are convex in the rate and because the near years carry more weight, so averaging a curve understates the equivalent flat rate on a rising curve and the direction reverses on an inverted one. Anyone who computes a flat rate by averaging a curve should expect to be wrong by tens of basis points, with a sign that depends on the curve's slope and the stream's shape. **The sign of the error depends on the slope, not on the level.** Against this rising curve the flat 8 % understates a receivable and would overstate a payable of the same shape, so a model using one flat rate for both the support stream and the O&M obligation biases both in the same direction and therefore biases the net position twice. And **the summary is legitimate if it is stated:** a flat 7.2946 % reproduces the curve's answer for this stream exactly, so a model can defensibly use it provided the documentation says which curve it summarises, for which cash-flow profile, and that re-shaping the stream invalidates the summary. That last clause is the one that fails in practice: a flat rate inherited from a previous transaction's template is a summary of a curve nobody has seen, for a stream nobody has matched, and Domain 6 (KA 6.4) treats it as an unsourced input rather than an assumption.

3.A.4 The reviewer's TVM eye

Experienced reviewers do not recompute everything; they run invariants. Each of the following is cheap, is independent of the project, and localises a defect rather than merely detecting one — which is why the list is worth learning as a list:

Invariant	What a violation localises	Source
Discount factors decline monotonically	The factor formula or its exponent	3.1.3
$DF(t+1) = DF(t)/(1+r)$; $DF(1) \times (1+r) = 1$	A hard-coded factor cell	3.1.3
$AF(r,n) \times r = 1 - DF(n)$	A mismatch between a factor column and its annuity summary	3.1.3b
$AF(r,n) < 1/r$ always	A rate entered as a percentage, or a tenor in the rate cell	3.1.3b
Annuity-due $\div$ ordinary annuity = $(1 + r)$ exactly	A payment-timing convention read against the contract	3.2.1b
Indexed stream = $A \times AF(r^*, n)$ by two routes	Double-counted indexation in an escalating stream	3.2.1d
Schedule closes at zero to display-rounding tolerance	Instalment, rate or period-count error	3.2.2
Σ principal = P ; final $\div$ first principal = $(1 + r)^{(n-1)}$	The principal column	3.2.2
$B_k = A \times AF(r, n - k)$ equals the recursion	The schedule, not the formula	3.2.2d
$EAR \geq i_{nom}$, equality only at $m = 1$	A compounding-frequency misread	3.2.3
All-in cost $>$ contract rate whenever a fee is deducted	A fee added to a rate instead of solved from the stream	3.2.3b
Real and nominal treatments agree to the cent	A mixed-basis model — an error, never a basis difference	3.3.1b
Real $<$ nominal whenever $\pi > 0$	An inverted Fisher relation	3.3.1
Two routes to a hedged FX value agree	A spot rate used where a forward belongs	3.3.3b
actual/360 interest = 30/360 interest $\times$ 365/360 over a full year	A day-count basis not implemented as documented	3.3.4b
Mid-period $\div$ period-end present value = $(1 + r)^{0.5}$	A timing convention applied inconsistently	3.A.2

Any violated invariant is a defect somewhere — find it before anyone downstream builds on it. The converse deserves equal emphasis and is the reason this section is an Advanced topic rather than a checklist: **every invariant above can hold while the answer is wrong.** They test formulae, not inputs. A model built on the wrong rate, the wrong tenor, the wrong index or the wrong world passes all sixteen, which is why the assumption register (3.T.1) and the invariants (3.T.2) are two controls and not one.

— Industry variations — Domain 3

The machinery is universal; its parameters are sectoral, and a project finance leader reads the sector before trusting any inherited rate, tenor or convention:

- **Power and renewables.** Long contracted tenors (20–35 years) make value acutely curve-sensitive (3.A.3) and escalation-sensitive (3.3.2); availability and capacity payments are near-annuities, so the annuity family does most of the valuation work. Debt sculpting to seasonal cash flows (Domain 10) starts from monthly, not annual, discounting.

- **Transport concessions.** Patronage risk pushes discount rates up and makes single-rate valuation least defensible — scenario-based rates and revenue stress tests (Domain 7, KA 7.4) ride directly on this domain's factors.
- **Water and regulated utilities.** Regulatory reset cycles (often 5-yearly) partition the horizon: within-period flows discount at financing rates; across resets, the real/nominal discipline (3.3.1) dominates because regulators commonly work in real terms while lenders live in nominal.
- **Digital infrastructure.** Shorter economic lives and refresh capex compress tenors: bullet and mini-perm shapes (3.2.2) with deliberate refinancing (Domain 15) are standard, so the balloon-risk arithmetic of Case B is daily practice, not a cautionary tale.
- **Oil, gas and mining.** Commodity-linked revenue makes escalation assumptions (3.3.2) the loudest value driver, and multi-currency operations make the day-count and FX conventions (3.3.3–3.3.4) contractual battlegrounds rather than back-office detail.
- **Social infrastructure PPPs.** Availability payments in advance are common — the annuity-due reading (WE 3.2.1b) is the difference between winning and mispricing a bid.

— Case study — Domain 3: choosing between an upfront grant and an availability stream (water / PPP)

Situation. Kestrel Water SPC's grantor offers two support packages for the desalination concession, and the board must choose one at financial close:

- **Package U:** a single upfront capital grant of **USD 58,000,000** at completion.
- **Package S:** an availability supplement of **USD 5,600,000 per year for 25 years**, paid annually in arrears from completion.

Kestrel evaluates support at its 8.0 % project discount rate. The grantor's advisers privately evaluate at 10 %.

Analysis. The stream's value to Kestrel: $AF(0.08, 25) = (1 - 1.08^{-25})/0.08 = 10.674776$; $PV = 5,600,000 \times 10.674776 = \text{USD } 59,778,747$ — worth **USD 1,778,747 more** than the upfront grant. To the grantor's advisers at 10 %: $AF(0.10, 25) = 9.077040$; $PV = 5,600,000 \times 9.077040 = \text{USD } 50,831,424$ — worth **USD 7,168,576 less** than the grant they would otherwise pay today.

The decision. Both sides prefer a different package from the same facts — a discount-rate wedge, not a disagreement about arithmetic. Kestrel takes the stream (worth more at 8 %); the grantor is glad to give it (cheaper at 10 %); the deal closes with both counterparties better off by their own measure. The board minute records the rate, the convention (annual, in arrears) and the sensitivity: the stream's advantage to Kestrel disappears if its discount rate rises past **8.3570 %** — the **breakeven rate** at which $AF(r, 25) \times 5,600,000 = 58,000,000$, i.e. $AF = 10.357143$, which is only **35.70 basis points** of headroom above the 8.0 % the board used. That is a thin margin for a decision of this size, and it is the number the minute must carry rather than the 1,778,747, because the surplus is the output and the rate is the assumption.

The negotiating range, which the two-package framing conceals. The offer on the table is one point inside a range, and the range is computable. The payment at which **Kestrel** is exactly indifferent between stream and grant is $58,000,000 \div AF(0.08, 25) = 58,000,000 \div 10.674776 = \text{USD } 5,433,369$; the payment at which the **grantor** is exactly indifferent is $58,000,000 \div AF(0.10, 25) = 58,000,000 \div 9.077040 = \text{USD } 6,389,748$. Any annual payment between those two figures leaves both parties better off than the grant, so the whole negotiation is a **USD 956,379 a year** band — and the grantor's proposed 5,600,000 sits only **17.4231 %** of the way into it. Expressed in present value, the joint gain created by choosing the stream over the grant is **USD 8,947,323** (exactly the wedge

$5,600,000 \times [AF(0.08, 25) - AF(0.10, 25)]$, of which Kestrel's 1,778,747 is **19.8802 %** and the grantor's 7,168,576 is 80.1198 %. Both parties gain; one gains four times as much; and the standard analysis — "the stream is worth more to us than the grant, so accept it" — is what causes the 80/20 split, because it stops at the sign of the surplus rather than computing the range. A hybrid makes the same point in a form a negotiator can table: a **USD 29,000,000 grant plus a stream at the grantor's own indifference price** of $29,000,000 \div 9.077040 = \text{USD } 3,194,874$ a year is worth **USD 63,104,566** to Kestrel — a surplus of **USD 5,104,566**, nearly three times the 1,778,747 on offer, at no cost to the grantor by its own measure.

What the domain teaches here. Valuation is always at a rate, for a party; streams and lumps are only comparable through $PV(x)$; and the negotiation surface between two parties' rates is where structuring value lives (Domain 7 revisits this as tariff design; Domain 9 as the grant-versus-support decision). Three cautions keep the arithmetic honest. The grantor's 10 % is **inferred, not disclosed** — real counterparties do not publish their discount rates, and the range above is only as good as the inference, so the professional practice is to compute the range across a plausible band of counterparty rates and negotiate against the conservative end. A payment stream and a grant differ in more than value: the stream carries **25 years of grantor credit and political risk** while the grant is cash at completion, and Domain 11 (KA 11.2) is where that difference is priced rather than inside r without saying so. And a package that is value-neutral to the grantor may be **fiscally or legally unavailable** to it — appropriation rules, budget-year constraints, state-aid and public-accounting treatments of long-term commitments differ by jurisdiction, are frequently decisive, and are matters for the grantor's own counsel and auditors rather than for this arithmetic.

— Case study B — Domain 3: the bullet that had to be refinanced (energy / refinancing)

Situation. A 30 MW peaking-plant SPV borrowed **USD 30,000,000** for 7 years. The sponsor chose a **bullet** (interest-only at 7.5 %, principal at maturity) over the lenders' preferred **annuity** shape, to keep early cash for distributions.

The two prices. Annuity instalment: $A = 30,000,000 \times 0.075 / (1 - 1.075^{-7}) = \text{USD } 5,664,009$ per year; total paid 39,648,066, of which interest **USD 9,648,066**. Bullet: interest $30,000,000 \times 0.075 = 2,250,000$ per year — total interest **USD 15,750,000**, plus the full USD 30,000,000 due in year 7. The bullet pays **USD 6,101,934 more interest** for the privilege of deferral — and retains the entire principal as **refinancing risk**.

Was the choice wrong? The arithmetic says no. Before judging the sponsor, price the deferral properly. The bullet's cash-flow advantage is $5,664,009.46 - 2,250,000 = \text{USD } 3,414,009$ a year in **years 1 to 6**, against a disadvantage of $32,250,000 - 5,664,009.46 = \text{USD } 26,585,991$ in year 7. Discount that difference stream and the indifference rate — the rate at which deferral is worth exactly nothing — comes out at **exactly 7.5000 %**, the loan rate itself. That is not a coincidence and it is the case study's central result: **the bullet's 6,101,934 of extra nominal interest is not a cost at all, it is precisely the price of the deferral at the contract rate**, so a sponsor whose alternative use of cash earns more than 7.5 % is right to defer, and one whose alternative earns less is wrong. At the sponsor's 15 % equity cost the deferral is worth **+USD 2,925,601** in present value (at 12 %, +2,010,232; at 10 %, +1,226,084; at 20 %, +3,933,661). **The sponsor's decision was value-creating on its own numbers, and the "USD 6,101,934 more interest" headline that condemns it is double-counting the time value the deferral exists to capture.**

What happened. At year 7 the credit market had repriced: the refinancing cleared at 9.8 %, and the new 7-year annuity instalment on the rolled principal became $30,000,000 \times 0.098 / (1 - 1.098^{-7}) =$

6,121,646 — against 5,664,009 had the original annuity simply been running to zero, an increase of **USD 457,636 a year**. Distributions locked up under the new facility's covenants for two years (Domain 10, KA 10.4). Note what the annuity's balance path (Fig 3.2.3) would have delivered instead: an outstanding balance at the end of year 6 of $5,664,009.46 \times AF(0.075, 1) = \text{USD } 5,268,846$, so the annuity structure faced the same repriced market with **17.5628 %** of the exposure the bullet carried.

What the domain teaches here. A schedule shape is a risk allocation, not a formatting choice: the annuity retires rate risk continuously; the bullet stores it at maturity, priced at a rate nobody today knows. Deferral has a computable minimum cost (the interest differential) and an uncomputable tail (the refinancing market) — leadership means pricing the first honestly and sizing the second deliberately (Domain 15, KA 15.3). The precise lesson is sharper than "bullets are dangerous", and it is the one worth carrying: the **priced** part of the bullet is fair — the sponsor paid 7.5 % for the deferral and would have been right to take it against any use of cash earning more — and the **unpriced** part is what destroyed the value. The failure was not choosing the bullet; it was choosing it without buying anything against the refinancing exposure: no forward-starting hedge, no committed refinancing facility, no amortising sinking-fund reserve, no tenor that outlived the credit cycle. A structure whose entire risk sits in one date is a structure that needs an instrument attached to that date, and the discipline is to separate the two decisions — **defer, priced at the contract rate; and hedge the tail, priced separately** — rather than to let a good answer to the first question stand in for no answer to the second.

— Executive perspective — Domain 3

What a project finance director cannot delegate in this domain:

- **The rate.** Analysts compute with a discount rate; directors own it. Whoever sets r sets the answer — the choice is a governance act (Domain 4 gives it method; Domain 3 makes its power visible).
 - **The world.** Nominal or real, once, for the whole model — and the director asks which, out loud, at the first model review.
 - **The conventions.** In-arrears vs in-advance, compounding frequency, day counts, escalation indices: each is small, each moves millions at scale, and together they are why the assumption register (3.T.1) is a board-visible artefact, not analyst hygiene.
 - **The range, not the surplus.** When a counterparty offers a choice, the director's question is not "which option is worth more to us?" but "what is the band inside which both parties prefer this option, and where in that band does the offer sit?" On Kestrel's support decision the band is **USD 956,379 a year** wide and the offer sits **17.4231 %** into it, capturing **19.8802 %** of a joint gain of USD 8,947,323 — a fact that no calculation of the surplus alone reveals, and the single highest-return use of this domain's arithmetic in a negotiation (Case study A).
 - **The small terms, priced.** Analysts negotiate margins because margins are quoted. The director asks what the unquoted terms are worth, and the answers on Kestrel are uncomfortable: an indexation cap USD 4,258,610, a repayment holiday USD 3,018,782, a day-count basis USD 274,947, an arrangement fee 37.04 basis points against a margin argument worth 15. Nothing in that list requires new information — only that somebody compute it before signature rather than after.
 - **The verification culture.** The invariants of 3.A.4 cost minutes; unverified TVM in a signed bid costs careers. The director's question is never "who computed this?" but "who recomputed this?" — and, where AI drafted it, the answer must name a human. The professional honesty this domain
-

demands is that the invariants prove the **formulae** and never the **basis**: a model can pass every check in this chapter and still implement a loan the facility agreement does not contain, which is why the director's second question is "against which document?"

— Calculation exercises — Domain 3

Exercise 3.1 A land payment of USD 850,000 falls due in 8 years; the applicable discount rate is 11 %. Value it today. Solution. $PV = 850,000 / 1.11^8 = 850,000 / 2.304538 = \text{USD } 368,838$ (368,837.52). Common error: using $n = 7$ gives 409,410 — an off-by-one from counting "in 8 years" as 7 compounding periods.

Exercise 3.2 A USD 2,500,000 equipment loan is repaid monthly over 20 years at a 5.0 % nominal annual rate compounded monthly. Find the monthly payment. Solution. Periodic rate $0.05/12 = 0.004167$; $n = 240$; $A = 2,500,000 \times 0.004167 / (1 - 1.004167^{-240}) = \text{USD } 16,499$ per month (16,498.89). Common error: using the EAR (5.116 %) with 20 annual periods misstates debt service materially.

Exercise 3.3 Convert a 12 % nominal rate compounded monthly to its effective annual rate. Solution. $(1 + 0.01)^{12} - 1 = 1.126825 - 1 = 12.68 \%$. Common error: reporting 12 % — the nominal — as "the rate" in a comparison against an annually-compounded 12.5 % offer, which is in fact cheaper.

Exercise 3.4 A transmission wayleave pays USD 1,200,000 per year indefinitely; the discount rate is 8.5 %. Value the perpetuity. Solution. $PV = 1,200,000 / 0.085 = \text{USD } 14,117,647$. Common error: applying a long annuity factor (say 30 years, $AF = 10.694$) "as approximately forever" understates value by $\approx 9 \%$.

Exercise 3.5 A market forecast promises a 12 % nominal return with 5 % inflation. State the real return, exactly and by the shortcut, and the shortcut's error. Solution. Exact: $1.12/1.05 - 1 = 6.67 \%$ (6.6667 %). Shortcut: $12 - 5 = 7.00 \%$. The shortcut overstates the real return by **33 basis points** — material over any long horizon.

Exercise 3.6 A concession tariff is worth USD 4,000,000 a year at base date and indexes fully at 3.0 % for 15 years, paid annually in arrears. The discount rate is 9.0 %. Value the stream. Solution. $r^* = 1.09/1.03 - 1 = 5.8252 \%$; $AF(r^*, 15) = 9.824117$; $PV = 4,000,000 \times 9.824117 = \text{USD } 39,296,469$. Common error 1: valuing it as a level annuity at 9 % — $4,000,000 \times 8.060688 = 32,242,754$, understating by 7,053,715 (17.95 %) by ignoring the indexation. Common error 2: escalating the flows **and** discounting at r^* — 48,651,797, overstating by 9,355,328 (23.81 %) by counting the indexation twice.

Exercise 3.7 On Kestrel's annuity schedule (USD 42,000,000, 12 years, 6.0 %, instalment 5,009,635.23), state the principal outstanding immediately after the year-9 instalment, and prove it without the schedule. Solution. $B_9 = A \times AF(r, n - k) = 5,009,635.23 \times AF(0.06, 3) = 5,009,635.23 \times 2.673012 = \text{USD } 13,390,815$ (13,390,814.83 by formula; 13,390,814.89 by recursion on the printed instalment — agreement to six cents). Common error: assuming principal

retires evenly and computing $42,000,000 - 9 \times 2,489,635 = 19,593,285$, overstating the balance by 6,202,470 because the annuity's principal component grows by $(1 + r)$ every year.

Exercise 3.8 A USD 25,000,000 facility is repayable in 8 equal annual instalments at 5.5 %, with a 1.5 % arrangement fee deducted from proceeds. Compute the instalment and the all-in effective cost. Solution. Instalment $25,000,000 \times 0.055 / (1 - 1.055^{-8}) = \text{USD } 3,946,600$ (3,946,600.30). Net proceeds $25,000,000 \times 0.985 = 24,625,000$. Solving $\sum 3,946,600.30 / (1 + r)^t = 24,625,000$ over 8 years gives **5.8794 %** — a premium of **37.94 basis points** on a 1.5 % fee, because the tenor is short and an upfront fee is spread over fewer periods. Common error: adding $1.5 \% \div 8 = 18.75$ basis points to the coupon to get 5.6875 %, which understates the cost by more than half; the shorter the tenor, the worse that approximation becomes.

Exercise 3.9 A USD 20,000,000 facility runs 10 years at 7.0 % with the first **two years interest-only**. Find the instalment for years 3 to 10 and the extra interest the holiday costs. Solution. $A_h = 20,000,000 \times 0.07 / (1 - 1.07^{-8}) = 20,000,000 \div 5.971299 = \text{USD } 3,349,355$ (3,349,355.25), against a plain 10-year instalment of 2,847,550.05. Lifetime interest $2 \times 1,400,000 + (8 \times 3,349,355.25 - 20,000,000) = \text{USD } 9,594,842$ against **USD 8,475,501** — the holiday costs **USD 1,119,341** and raises the instalment by 17.62 %. Common error: assuming the holiday is free because the maturity is unchanged; the interest on two years of undiminished principal is the cost, and it is knowable at signature.

Exercise 3.10 Spot $\text{USD } 1 = \text{SAR } 3.7500$; three-year money costs 5.0 % in USD and 5.5 % in SAR. State the three-year forward and the USD value today of a receipt of SAR 10,000,000 in three years. Solution. $F_3 = 3.7500 \times (1.055/1.05)^3 = \text{SAR } 3.8038$ per USD. The USD amount receivable at year 3 is $10,000,000 \div 3.8038 = \text{USD } 2,628,931$; converting at spot instead would show **USD 2,666,667**, overstating the hedged receipt by 37,736. Common error: using the spot rate for a future flow — the SAR is the higher-interest currency, so it trades at a forward discount, and spot conversion of a future foreign receipt systematically flatters the model.

Exercise 3.11 A cost of USD 5,000,000 at base date escalates for 10 years on an index forecast at 5.0 %; the contract caps annual indexation at 3.0 %. The discount rate is 8.0 %. Value the cap. Solution. Uncapped $r^* = 1.08/1.05 - 1 = 2.8571 \%$, $AF = 8.592732$, $PV = 5,000,000 \times 8.592732 = \text{USD } 42,963,658$. Capped $r^* = 1.08/1.03 - 1 = 4.8544 \%$, $AF = 7.776638$, $PV = \text{USD } 38,883,189$. The cap is worth **USD 4,080,469**, or 9.50 % of the uncapped obligation. Common error: valuing the cap as the final-year price saving $(5,000,000 \times (1.05^{10} - 1.03^{10}) = 1,424,891)$ — a single period, undiscounted, in place of a stream.

— Practitioner's toolkit — Domain 3

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 3.T.1 — TVM assumption register (one row per modelled stream)

Field	Discipline it enforces
Stream name & source document	Every number traces to a contract or estimate
Currency	Mismatches surface (KA 3.3.3)
Nominal or real	The consistency rule (3.3.1), stated not assumed
Rate & its owner	The director owns r (Executive perspective)
Rate construction (quoted / EAR / continuous / growth-adjusted r^*)	The domain's most confusable pair sit two basis points apart (3.A.1)
Compounding frequency and payment frequency, separately	They are different levers and pull in opposite directions (WE 3.2.3c)
Day-count basis	Worth 8.33 bp at 6 % on actual/360, and invisible in a rate (WE 3.3.4b)
Timing convention (arrears/advance/mid-period)	Half-period errors caught (3.A.2)
Escalation index, lag, cap/floor, weighting	Contractual, not invented (3.3.2, WE 3.3.2b)

Toolkit 3.T.2 — Schedule QA checklist

- [] Payment recomputed independently of the model (different implementer or method).
- [] Final balance zero **to a stated tolerance** (display rounding only); Σ principal = original loan.
- [] Outstanding balance at one interior date agrees between the recursion and $A \times AF(r, n - k)$.
- [] Final-year principal $\div$ first-year principal = $(1 + r)^{(n-1)}$ on an annuity schedule.
- [] Periodic rate = nominal / **compounding** frequency; period count = years $\times$ **payment** frequency; the two frequencies confirmed separately against the facility agreement.
- [] Day-count basis implemented as named, and its 365/360-type uplift reflected in the all-in cost.
- [] Binding coverage period identified by inspection of the service profile, not assumed to be period 1 (holidays, sculpting and step-ups move it).
- [] Discount factors monotone; $DF(1) \times (1 + r) = 1$; $AF(r, n) \times r = 1 - DF(n)$; $AF(r, n) < 1/r$.
- [] Display rounding only — full precision beneath every printed figure.
- [] AI-drafted content marked, and its human verifier named (Domain 16, KA 16.4).

Toolkit 3.T.3 — Escalation register

For each escalating line: base amount and base date · index (publisher, series, definition) · lag · formula (full/partial indexation, weightings) · cap/floor · compounding basis · the clause reference in the contract. A model whose escalation register is complete can survive a Domain 13 model audit; one whose escalation is "4 % because last year" cannot.

Toolkit 3.T.4 — Rate comparison worksheet (one column per offer)

Never compare quoted rates. Build one column per competing facility and require every row to be filled before any comparison is spoken aloud:

Row	Why it is on the sheet
Facility amount · tenor · repayment shape	Only like-for-like offers are comparable (3.2.2)
Quoted rate · compounding frequency · payment frequency	Three different things behind one number (3.2.3, WE 3.2.3c)
Day-count basis, and its rate equivalent	Worth 8.33 bp at 6 % on actual/360 (WE 3.3.4b)
Upfront fees — deducted or capitalised	The two are not the same calculation (WE 3.2.3b)
Commitment fee and expected undrawn profile	Cannot be priced without a drawdown schedule (Domain 14)
Net proceeds actually received	The denominator of the all-in solve
Contractual instalment, recomputed independently	The numerator of the all-in solve
All-in effective cost, solved from the stream	The only comparable figure (WE 3.2.3b)
Fee-to-margin equivalence at this tenor	The negotiating currency: 18.38 bp per 1 % on Kestrel
First-period and minimum debt service, with DSCR	Cost is not the only variable (Domain 10)
Prepayment terms and break costs above B_k	Add to the balance formula, never replace it (WE 3.2.2d)

Two mandatory footers: the method statement ("all-in costs solved from each stream against net proceeds; no fee added to a rate") and the named individual who recomputed each column.

— Exam preparation — Domain 3

The calculation traps. Off-by-one periods ("in year 5" vs "after 5 years") · simple-for- compound substitution · rounded discount factors in the arithmetic · annuity-due priced as ordinary · EAR used as the periodic rate, or as an annual rate over n years (WE 3.2.3c) · nominal/real mixing · escalation applied simply · **indexation counted twice** (escalating the flows and discounting at r^* — WE 3.2.1d) · a growing perpetuity used where a finite indexed annuity belongs · an annuity factor exceeding $1/r$ · tenor mismatch in annuity factors (the 3.2-A distractor D) · a fee divided by the tenor and added to the coupon instead of solved from the stream · a repayment holiday assumed to be free, and its binding coverage period assumed to be period 1 · an outstanding balance estimated as $P - k \times \text{first-year principal}$ · an indexation cap valued at its final-year saving rather than as a stream · a contractual indexation lag ignored · a day-count basis omitted from an all-in comparison, or its fraction inverted · spot conversion of a future foreign receipt · treating a forward as a forecast · a flat rate assumed to be a curve's arithmetic mean.

Reflection questions.

1. Your CFO asks for "the value of the concession". What three questions must you answer before any number is defensible? (At what rate; in which world — nominal or real; under which timing conventions.)
2. A lender and a sponsor disagree about the value of the same payment stream. Under what conditions are both right — and where does that create negotiating room? (Case study A: a USD 956,379-a-year band, of which the standard offer captures 17.4231 %.)
3. Which invariant checks would have caught the last TVM error you saw in the wild — and why didn't they run? (3.A.4; toolkit 3.T.2.)
4. A model passes every check in 3.A.4 and every line of Toolkit 3.T.2, and its debt-service schedule is nevertheless wrong. Name two ways that can be true, and say which control catches each. (A

valid amortisation the facility does not provide for, and a right calculation on the wrong basis: the assumption register and document conformance, not the invariants — WE 3.2.3c, Domain 13 KA 13.2.1.)

5. Your team has negotiated 15 basis points off a margin. Name three terms elsewhere in the same term sheet that are each worth more, and state their values on Kestrel's facility. (A 2.0 % arrangement fee, 37.04 bp; an actual/360 day-count basis, 8.33 bp and USD 274,947 of interest; a three-year repayment holiday, USD 3,018,782 — and, outside the facility, an indexation cap worth USD 4,258,610.)

— Domain 3 summary

Money's value is a function of time, and this domain built the complete conversion machinery: compounding and discounting ($FV(x)$, $PV(x)$, $DF(t)$), together with the inverse operations that solve a stream for its rate; the annuity family that prices every level **and indexed** stream from availability payments to debt service ($AF(r, n)$, perpetuities, the growth-adjusted rate r^* , the four loan shapes, the outstanding-balance formula and their risk meanings); frequency and effective-rate honesty, including the distinction between compounding frequency and payment frequency; and the real-world adjustments — Fisher-consistent inflation treatment, contract-grade escalation with caps, lags and weightings, no-arbitrage currency forwards, and day-count bases that move real money.

Four results carry beyond the domain. The **consistency identity**: the nominal and real treatments of one stream are equal to the cent, so any difference is a defect and not a basis — and mixing them moves Kestrel's support stream by -24.4325% or $+37.8828\%$. The **indexation identity**: $PV = A \times AF(r^*, n)$, which prices every escalating stream with the machinery already built and whose misuse, counting indexation twice, overstates value by 31.0818% . The **all-in discipline**: no rate enters a comparison until it has been solved from the actual stream, because on Kestrel each 1% of upfront fee is worth 18.38 basis points and a day-count basis is worth 8.33 more. And the **shape-is-risk result**: the same loan under four schedules costs between 16,380,000 and 30,240,000 of interest and produces first-year coverage between 1.0605 and 2.5333, so choosing a repayment shape is a risk allocation, and the deferral inside a bullet is fairly priced at the contract rate while the tail it leaves is not priced at all.

Its discipline is as important as its formulae: one world per model, full precision beneath displayed rounding, conventions in the assumption register, the sixteen invariants of 3.A.4 run on every schedule, and machine-drafted arithmetic verified by a named human before anyone relies on it. Every discounted number in the thirteen domains that follow stands on this one.

04

DOMAIN 4

Investment Appraisal and Capital Budgeting

— Why this domain exists

Domain 3 taught how to move money across time; this domain teaches how to decide with it. Investment appraisal is where analysis meets commitment: the techniques here — net present value, internal rates of return, payback, profitability, equivalent annual value — are how a project finance leader turns forecast cash flows into a defensible yes, no, or not-this-one. The measures are deliberately plural because each answers a different question: NPV measures value created; IRR measures the return embedded in the flows; payback measures exposure; the profitability index measures value per scarce dollar; equivalent annual value compares unlike lifetimes. Leadership in this domain means knowing which question the decision actually asks — and refusing to let a single seductive percentage (usually IRR) answer all of them. Domain 6 industrialises these calculations in the financial model; Domain 10 replays them from the lender's side of the table.

Learning objectives. After this domain a candidate can: compute and interpret NPV and explain why it is the primary measure of value; compute IRR, recognise its pathologies (multiple roots, scale-blindness, reinvestment assumption) and know when it misleads; compute MIRR and state what it fixes and what it does not; apply payback and discounted payback as exposure measures, not value measures; rank with the profitability index under capital rationing; compare unequal lives with equivalent annual value; resolve NPV-IRR conflicts on mutually exclusive projects; and subject any machine-produced appraisal to the family's verification rule.

The master appraisal. The Kestrel Water SPC financing of Domain 3 now faces its investment decision. Building the plant requires $I_0 = \text{USD } 60,000,000$ today; the operating model forecasts **net cash inflows of USD 8,900,000 per year for 15 years**; the board's discount rate remains **8.0 %**. Every KA below interrogates this one decision from a different angle.

KNOWLEDGE AREA 4.1

The discounted measures: NPV, IRR and MIRR

Topics: 4.1.1 net present value · 4.1.2 IRR and its pathologies · 4.1.3 MIRR.

4.1.1 Net present value

Definition. NPV discounts every cash flow to today and nets off the investment:

$$NPV = \sum CF_t / (1 + r)^t - I_0$$

A positive NPV means the project returns more than the capital's required return r — it creates value; a negative NPV destroys it. NPV's authority rests on three properties no rival measure shares: it is **additive** (portfolio NPV is the sum of project NPVs), it is **scale-aware** (twice the project, twice the NPV), and it embeds the **correct reinvestment assumption** (cash thrown off is assumed to earn r , the opportunity cost — not the project's own return).

WORKED EXAMPLE

Worked example 4.1.1 — should Kestrel build?

1. **Setup.** I_0 = USD 60,000,000; net inflows USD 8,900,000 per year for 15 years (in arrears); r = 8.0 %.
2. **Formula.** For a level stream, $NPV = A \times AF(r, n) - I_0$ (Domain 3, KA 3.2).
3. **Substitution.** $AF(0.08, 15) = 8.559479$; $NPV = 8,900,000 \times 8.559479 - 60,000,000 = 76,179,360 - 60,000,000$.
4. **Result.** $NPV = +\text{USD } 16,179,360$ ($\approx$ SAR 60.7 million indicatively).
5. **Interpretation.** At the board's 8 % the plant is worth USD 16.2 million more than it costs — build, on these forecasts. The phrase carrying the professional weight is on these forecasts: NPV is only as honest as the cash flows and the rate beneath it, which is why Domain 6's model discipline and this domain's sensitivity habits (KA 4.3.3) are part of the appraisal, not decoration around it.




Fig 4.1.1 — Kestrel's NPV profile

Which cash flow belongs in the appraisal. Before any formula, a category rule that decides more appraisals than the arithmetic does: the flows discounted here are the project's **free cash flows** — operating receipts less operating costs, less tax on operating profit, less capital expenditure and

working-capital movements — and they contain **no financing flows at all**. No interest, no loan drawdown, no repayment, no dividend. The reason is not convention but double-counting: the cost of the financing is already inside r . Put interest in the numerator and in the discount rate and the project is charged twice for its debt; a viable project is then rejected by an error that no reviewer of the spreadsheet's arithmetic will ever find, because every cell is correct. The mirror-image discipline is that if you do discount equity cash flow — after debt service — you must use the cost of equity, not the project rate (KA 4.A.3 prices that mistake for Kestrel; it is worth 25.2 million of NPV).

Two consequences follow for the master appraisal. The 8,900,000 is a project-level figure, so the 8 % it meets is a project-level rate — a weighted average cost of capital, which Domain 9 derives properly and KA 4.A.3 reconciles. And sunk costs stay out: Kestrel's feasibility and transaction spend — the development capital Domain 5 tracks as already at risk before this decision — appears nowhere in the numerator, because a cost that cannot be avoided by deciding no is not part of the decision. Note the discipline this cuts both ways: spend that is still avoidable belongs in the flows even if it has already been contracted, and a capital item absorbed into the 60,000,000 budget (Domain 5's corridor re-route is the thread's example) is part of I_0 rather than a sunk cost, however early it was committed. The development spend that this appraisal excludes belongs in the record of what the development stage cost, which is Domain 5's question, not this one's.

Worked example 4.1.1b — the same money, later.

The level 8,900,000 a year is a convenience. Real plants ramp: commissioning takes a year, the offtaker's demand builds, and full output arrives in year three. Kestrel's engineers restate the forecast with the **identical total** — so that timing is the only variable.

1. **Setup.** $I_0 = 60,000,000$; inflows 4,600,000 (year 1), 6,700,000 (year 2), then 9,400,000 for years 3–15. Total nominal inflow $4,600,000 + 6,700,000 + 13 \times 9,400,000 = \mathbf{133,500,000}$, exactly the level case's $8,900,000 \times 15$. $r = 8\%$.
2. **Formula.** Discount the two irregular years individually and treat the tail as a deferred annuity: $PV = CF_1 \cdot DF(1) + CF_2 \cdot DF(2) + CF_{3-15} \cdot [AF(r, 15) - AF(r, 2)]$. The bracketed term is Domain 3's deferred-annuity device (KA 3.2.1) — the 15-year factor less the two years that are not in the stream.
3. **Substitution.** $DF(1) = 0.925926$, $DF(2) = 0.857339$, $AF(0.08, 15) - AF(0.08, 2) = 8.559479 - 1.783265 = 6.776214$; $PV = 4,600,000 \times 0.925926 + 6,700,000 \times 0.857339 + 9,400,000 \times 6.776214 = 4,259,259 + 5,744,170 + 63,696,411$.
4. **Result.** $PV = 73,699,840$; $NPV = +\mathbf{USD\ 13,699,840}$ — against +16,179,360 on the level profile. The ramp costs **USD 2,479,520**, or 15.3 % of the project's value.
5. **Interpretation.** Not one dollar of revenue was lost; 2.48 million of value was, purely by arriving later. This is the single most under-appreciated number in early-stage appraisal, because the level-annuity shortcut is how almost every screening model is built and the ramp is how almost every plant actually starts. Two professional consequences follow. First, a screening NPV computed on a level profile is an upper bound, and should be labelled as one. Second, commissioning acceleration is worth real money that is invisible in a level model: pulling the ramp forward by one year here is worth roughly the same order as the whole ramp penalty, which is why Domain 14's drawdown and completion tests carry the commercial weight they do. The reviewer's question is therefore never "what is the NPV?" but "on what profile?"

Worked example 4.1.1c — the convention that is worth three million.

Annual flows do not arrive on 31 December. Cash accrues through the year, so discounting every year's inflow as though it landed on the final day systematically understates value. The **mid-period convention** discounts each year's flow from its mid-point instead.

1. **Setup.** The master appraisal, discounted (a) at year-end and (b) at mid-year.
2. **Formula.** Shifting every flow half a period earlier multiplies the whole present value by $(1 + r)^{0.5}$: $PV_{mid} = PV_{end} \times (1 + r)^{0.5}$. (Discounting each flow individually from $t - 0.5$ gives the identical result; the single multiplier is the audit-friendly route.)
3. **Substitution.** $PV_{end} = 8,900,000 \times 8.559479 = 76,179,360$; $(1.08)^{0.5} = 1.0392305$; $PV_{mid} = 76,179,360 \times 1.0392305$.
4. **Result.** $PV_{mid} = 79,167,914$; **NPV = +USD 19,167,914** against +16,179,360 at year-end — a convention difference of **USD 2,988,553**, or 18.5 % of the reported value.
5. **Interpretation.** Neither number is wrong; the silence is. Almost three million of reported value turns on a modelling choice that appears in no formula and is rarely written down, and the same choice applied to a competing project changes both NPVs — which is why comparisons across projects modelled by different teams are unsafe until the convention is confirmed. The discipline is simple and non-negotiable: **the convention is declared in the assumption register, applied to every line including terminal values, and held constant across every option in a decision.** A useful reviewer's shortcut falls out of the algebra: the ratio between the two conventions is always $(1 + r)^{0.5}$, so at 8 % any correctly mid-period model reports about 3.9 % more present value than the year-end version of itself. A gap of a different size means the convention was applied to some lines and not others.

4.1.2 IRR and its pathologies

Definition. The internal rate of return is the discount rate at which NPV is zero — the break-even price of capital:

$$NPV(IRR) = 0$$

For Kestrel: solve $8,900,000 \times AF(r, 15) = 60,000,000 \rightarrow AF = 6.741573 \rightarrow \text{IRR} = 12.19\%$. Read against an 8 % hurdle, the project clears with 4.19 points to spare — the same verdict as NPV, expressed as a margin of safety rather than a value.

Worked example 4.1.2 — solving the rate, then proving it.

No closed form exists for r in an annuity of fifteen terms, so the IRR is always solved — by a spreadsheet's iteration, by interpolation between tabulated factors, or by bisection. What matters professionally is not which route you take but that you then **verify the answer against the equation it is supposed to satisfy**.

1. **Setup.** The master appraisal. Find r such that $8,900,000 \times AF(r, 15) = 60,000,000$.
2. **Formula.** The target factor is $AF = I_0 / A = 60,000,000 / 8,900,000 = 6.741573$. Bracket it between two rates whose factors straddle the target, then interpolate linearly: $r \approx r_{low} + (AF_{low} - AF_{target}) / (AF_{low} - AF_{high}) \times (r_{high} - r_{low})$.
3. **Substitution.** $AF(0.12, 15) = 6.810864$ (too high — NPV is still +616,694) and $AF(0.13, 15) = 6.462379$ (too low — NPV is −2,484,828), so the root lies between. Interpolating: $0.12 + (6.810864 - 6.741573) / (6.810864 - 6.462379) \times 0.01$.
4. **Result.** Interpolation gives **12.1988 %**; bisection to full precision gives **IRR = 12.192120 %**. The interpolation is high by **0.67 of a basis point**.

5. **Interpretation.** Three lessons sit in that small error. First, linear interpolation across a convex factor function always overstates the root, and the error grows with the width of the bracket — a one-point bracket is accurate to under a basis point, a five-point bracket is not. Second, the verification is free and mandatory: substitute the root back and confirm $NPV(IRR) = 0$, which at 12.192120 % it does to the cent. Third, and least obvious, **the rounding you publish is not innocent.** Quoting "12.19 %" and substituting that leaves a residual NPV of **+6,751**; quote 12.1921 % and the residual falls to **+65**. A reviewer testing the invariant against a two-decimal IRR will find a non-zero residual and must know whether they are looking at a rounding artefact or a defect. The convention that resolves it: **publish the rate to two decimals, retain it unrounded in the model, and run the substitution test on the retained value.**

Why decision-makers love it — and where it lies. A percentage needs no context, which is precisely its danger. The three standing pathologies:

1. **Multiple roots.** IRR is a polynomial root; flows that change sign more than once can have more than one. The classic mining/decommissioning shape — invest, harvest, pay to restore — $(-1,000,000, +2,300,000, -1,320,000)$ — satisfies $NPV = 0$ at **both 10 % and 20 %**; between them NPV is positive (about +1,890 at 15 %), outside, negative. Quoting "the IRR" of such a project is meaningless; NPV at the actual cost of capital remains well defined.
2. **Scale-blindness.** A 40 % IRR on USD 100,000 creates less value than 15 % on USD 20,000,000. IRR ranks intensity, NPV ranks money; mutually exclusive choices need money (KA 4.3.1).
3. **The reinvestment fiction.** IRR mathematically assumes interim cash is reinvested at the IRR itself — flattering for high-IRR projects, since no treasury desk reinvests at 28 %. MIRR (4.1.3) exists to repair exactly this.

Worked example 4.1.2b — the project with two rates, mapped.

Asserting that a sign-changing project has two IRRs is easy; seeing what its value actually does is what stops a practitioner quoting one of them. Kestrel's sponsor also holds a small quarry concession: extract for a year, then pay to restore.

1. **Setup.** Flows $(-1,000,000; +2,300,000; -1,320,000)$ at $t = 0, 1, 2$. Two sign changes, so up to two roots.
2. **Formula.** $NPV(r) = -1,000,000 + 2,300,000/(1+r) - 1,320,000/(1+r)^2$. Substituting $x = 1/(1+r)$ makes it a quadratic in x , which is why there are at most two roots — the polynomial degree, not the project, sets the limit.
3. **Substitution.** Evaluate across the range rather than at one point:

Discount rate	0 %	5 %	10 %	14.7826 %	15 %	20 %	25 %	30 %
NPV (USD)	-20,000	-6,803	0	+1,894	+1,890	0	-4,800	-11,834

1. **Result.** Zeros at exactly **10 % and 20 %**; the maximum NPV of **+1,894** occurs at **14.7826 %**; and the undiscounted sum is **negative** (−20,000).
2. **Interpretation.** Read the row and the pathology stops being abstract. The project creates value only for costs of capital between 10 % and 20 % — a shape that inverts every instinct trained on ordinary projects, where more expensive capital always destroys value. Here a higher discount rate shrinks the year-2 restoration liability faster than it shrinks the year-1 receipt, so cheap capital is the enemy. Note also the first cell: at a zero discount rate the concession loses 20,000 in plain cash, which means it is not a good project that discounting flatters — it is a project whose entire case rests on the time value of a liability. Two rules follow. **Quote no IRR when signs change more than once**; report NPV at the actual cost of capital, plus the range over which the sign holds, because that range is the real risk statement. And treat a decommissioning obligation

as a financing question as much as an engineering one: whether the restoration is funded from a sinking fund, a bond or the balance sheet changes the flows this table is drawn from (Domain 15 takes this up).

Common pitfall — comparing IRRs across different tenors. A 3-year 18 % and a 15-year 13 % are not ordered: the short project leaves twelve years of reinvestment risk the percentage hides. The honest comparison is NPV over a common horizon, or EAV (KA 4.2.3).

4.1.3 MIRR — the modified internal rate of return

Definition. MIRR discounts outflows at the finance rate and compounds inflows to the terminal date at an explicit reinvestment rate, then reads the single rate connecting the two:

$$\text{MIRR} = (\text{FV}(\text{inflows at } r_{\text{reinvest}}) / \text{PV}(\text{outflows at } r_{\text{finance}}))^{(1/n)} - 1$$

WORKED EXAMPLE

Worked example 4.1.3 — Kestrel's honest percentage.

1. **Setup.** The master appraisal, with both finance and reinvestment rates set to the 8 % opportunity cost.
2. **Formula.** Terminal value of the inflows $\text{TV} = A \times \text{FVAF}(r, n)$ where $\text{FVAF}(0.08, 15) = (1.08^{15} - 1)/0.08 = 27.152114$; then $\text{MIRR} = (\text{TV}/I_0)^{(1/15)} - 1$.
3. **Substitution.** $\text{TV} = 8,900,000 \times 27.152114 = 241,653,814$; $\text{MIRR} = (241,653,814 / 60,000,000)^{(1/15)} - 1 = 4.027564^{(1/15)} - 1$.
4. **Result.** **MIRR = 9.73 %** — against an IRR of 12.19 %.
5. **Interpretation.** Two and a half points of Kestrel's IRR were the reinvestment fiction. MIRR is single-valued even for sign-changing flows and states its reinvestment assumption in the open — which is why credit committees increasingly ask for it alongside IRR. It remains a rate: still scale-blind, still not additive. The order of authority stands: **NPV decides; rates explain.**

Worked example 4.1.3b — MIRR when the two rates are honestly different.

Setting both rates to 8 % was a simplification that made MIRR comparable to NPV. In practice the two rates answer different questions and are rarely equal: money is raised at the cost of the facility that funds the outflows, and reinvested at whatever the treasury can actually earn on short-dated deposits. Kestrel's case makes the gap concrete — a senior facility at 6.0 % against a treasury policy that permits only investment-grade short paper at 4.0 % — and adds the mid-life outflow every real asset has.

1. **Setup.** $I_0 = 60,000,000$ at $t = 0$; a **membrane replacement of 6,000,000 at the end of year 8**; inflows 8,900,000 per year for 15 years. Finance rate $r_f = 6.0 \%$ (the debt the outflows draw on); reinvestment rate $r_i = 4.0 \%$ (treasury policy). Horizon 15 years.
2. **Formula.** $\text{MIRR} = [\text{FV}(\text{inflows at } r_i) / \text{PV}(\text{outflows at } r_f)]^{(1/n)} - 1$, with $\text{FV} = A \times \text{FVAF}(r_i, n)$ and every outflow discounted at r_f to $t = 0$.
3. **Substitution.** $\text{PV}(\text{outflows}) = 60,000,000 + 6,000,000 / 1.06^8 = 60,000,000 + 3,764,474 = 63,764,474$. $\text{FVAF}(0.04, 15) = 20.023588$, so $\text{FV}(\text{inflows}) = 8,900,000 \times 20.023588 = 178,209,930$. $\text{MIRR} = (178,209,930 / 63,764,474)^{(1/15)} - 1 = 2.794815^{(1/15)} - 1$.
4. **Result.** **MIRR = 7.09 %** — against 9.73 % at an 8 % reinvestment rate and an IRR of 12.19 %.

5. **Interpretation.** More than five points of the headline IRR have now been accounted for, and the accounting is worth reading in order — one change at a time, so that the three parts sum to the whole. **2.46 points** were the reinvestment fiction at the opportunity cost (12.1921 % IRR against 9.7327 % MIRR at an 8 % reinvestment rate). A further **2.21 points** disappear when the reinvestment rate alone is moved from the project's own 8 % opportunity cost to the 4 % the treasury can genuinely earn (MIRR 7.5273 %, still on the original outflow). The membrane replacement, discounted at the 6.0 % finance rate, takes the last **0.44 points** (MIRR 7.0920 %). Those three add to **5.10 points**, which is exactly the gap between the published IRR and the honest MIRR — and a decomposition whose parts do not sum is the first sign that two changes have been made at once and one of them attributed twice. That is the whole point of MIRR: it does not make the project worse, it makes the assumptions visible, and every point it strips out was a point the IRR was quietly asserting. Note carefully what this does **not** mean. A MIRR of 7.09 % below the 8 % hurdle is not an accept/reject signal. Discount the same flows properly at the 8 % project rate — the membrane costs $6,000,000 \times 0.540269 = 3,241,613$ in present value — and the project is worth **+12,937,747**, with an IRR of **11.4250 %**: comfortably viable, on flows that produced a MIRR two-thirds of a point below the hurdle. MIRR's terminal-value construction is not a discounted value measure and cannot be read against a discount rate as though it were one. Doing so is the commonest misuse of the measure, and it kills good projects. **MIRR ranks and explains; it never decides.**

AI in this KA

Appraisal is where optimisation pressure meets a suggestible tool: an assistant asked to "get the IRR above 12 %" will find assumptions that do. The governed workflow inverts the prompt — AI is asked to attack the appraisal (which assumptions move NPV most? where does the IRR become multiple?), the analyst reruns the golden checks (NPV at the stated rate recomputed independently; IRR verified by substitution back into the NPV equation; MIRR's terminal value re-derived), and the professional owns the recommendation. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 4.1

Term	Meaning
NPV	Σ discounted cash flows – investment; the primary value measure.
IRR	The rate at which NPV = 0; the flows' embedded return.
NPV profile	NPV plotted against the discount rate; IRR is its zero-crossing.
Multiple roots	Two or more IRRs when flow signs change more than once.
Reinvestment assumption	NPV assumes interim cash earns r ; IRR assumes it earns the IRR.
MIRR	Single rate from explicit finance and reinvestment rates.
Free cash flow (project)	Operating cash after tax, capex and working capital, before all financing flows — the only stream the project rate may discount.
Mid-period convention	Discounting each year's flow from its mid-point; multiplies year-end PV by $(1 + r)^{0.5}$.
Deferred annuity factor	$AF(r, n) - AF(r, k)$; prices a level stream that starts after year k .
Ramp profile	A build-up to full output; costs value against a level profile even at identical totals.
Sunk cost	Spend that no decision can avoid; excluded from every appraisal flow.

■ SAMPLE MCQS — KA 4.1

MCQ 4.1-A [4.1.1 · Application] A project costs USD 60,000,000 and returns USD 8,900,000 per year for 15 years; the discount rate is 8 % ($AF = 8.559479$). Its NPV is:

- A. +USD 16,179,360 ✓ CORRECT
- B. +USD 73,500,000
- C. –USD 16,179,360
- D. +USD 76,179,360

Rationale: $8,900,000 \times 8.559479 - 60,000,000 = +16,179,360$. B is the undiscounted surplus ($8.9 \times 15 - 60$); C reverses the sign (investment minus value); D forgets to deduct the investment at all.

MCQ 4.1-B [4.1.2 · Analysis] A project's cash flows are –1,000,000, +2,300,000, –1,320,000. Which statement is correct?

- A. its IRR is 10 %
- B. its IRR is 20 %
- C. it has two IRRs (10 % and 20 %), so decision by IRR is indeterminate and NPV at the cost of capital must decide ✓ CORRECT
- D. it has no IRR, so it must be rejected

Rationale: Two sign changes admit two roots — both 10 % and 20 % zero the NPV, which is positive between them. A and B are each half the truth and therefore wrong as "the" IRR; D confuses indeterminate ranking with non-viability — at a 15 % cost of capital the NPV is (slightly) positive.

MCQ 4.1-C [4.1.3 · Application] Using an 8 % finance and reinvestment rate, the master appraisal's terminal value of inflows is USD 241,653,814 on an investment of USD 60,000,000 over 15 years. MIRR is closest to:

- A. 12.19 %
- B. 9.73 % ☒ **CORRECT**
- C. 8.00 %
- D. 26.85 %

Rationale: $(241,653,814/60,000,000)^{(1/15)} - 1 = 9.73 \%$. A is the unmodified IRR; C is the reinvestment rate itself; D divides the 4.03× money multiple by 15 as if returns were simple.

MCQ 4.1-D [4.1.1 · Analysis] Which property justifies NPV's primacy over IRR for accept/reject and ranking decisions?

- A. NPV is easier to compute
- B. NPV is expressed as a percentage
- C. NPV is additive and scale-aware, and assumes reinvestment at the opportunity cost ☒ **CORRECT**
- D. NPV never requires a forecast

Rationale: The three structural properties of 4.1.1. A is irrelevant and untrue at scale; B describes IRR, not NPV; D is false — NPV consumes the same forecasts as every measure.

MCQ 4.1-E [4.1.1 · Comprehension] Why are interest and loan repayments excluded from the cash flows that a project discount rate is applied to?

- A. because lenders require their flows to be kept confidential
- B. because the cost of the financing is already represented inside the discount rate, so including it in the cash flows charges the project for its debt twice ☒ **CORRECT**
- C. because interest is not a cash flow
- D. because interest is a sunk cost

Rationale: The discount rate is the cost of capital, debt included; putting debt service in the numerator as well double-counts it and rejects viable projects with arithmetic that is individually correct in every cell (4.1.1). C is plainly false — interest is paid in cash. D confuses a cost that cannot be avoided by deciding no with one that recurs because of the decision. The mirror discipline: equity cash flow, after debt service, is discounted at the cost of equity instead.

MCQ 4.1-F [4.1.3 · Comprehension] A paper reports the same 15-year project twice: IRR 12.19 %, and MIRR 9.73 % computed with both the finance and the reinvestment rate set to the 8 % cost of capital. No cash flow and no rate has changed between the two lines. The 2.46-point gap exists because:

- A. MIRR discounts the inflows twice, once to today and once to the terminal date
- B. IRR's arithmetic assumes interim cash is reinvested at the IRR itself, while MIRR compounds it at the rate stated — so the gap is the price of the reinvestment assumption, made explicit ☒ **CORRECT**
- C. MIRR uses the risk-free rate rather than the cost of capital
- D. the two measures answer the same question and one of them must have been mis-computed

Rationale: Nothing about the project changed; only the reinvestment assumption became explicit, and 12.19 % – 9.73 % is what that assumption was worth (4.1.3). A misdescribes the construction — inflows are compounded forward once and the result is annualised. C names a rate MIRR does not

use. D is the misreading the item exists to close off: the two measures differ by construction, so a gap is expected rather than evidence of error, and it runs in this direction whenever the IRR exceeds the reinvestment rate.

MCQ 4.1-G [4.1.3 · Evaluation] A sponsor's paper reports IRR 12.19 %, MIRR 7.09 % on a 4 % treasury reinvestment rate, and NPV +12,937,747 at the 8 % project rate. A committee member moves to reject, on the grounds that MIRR is below the hurdle. The soundest response is that:

- A. the motion is correct — any return measure below the hurdle disqualifies the project
- B. MIRR is not a discounted value measure and cannot be read against a discount rate; the accept/reject test is the positive NPV at the owned rate, and MIRR's role here is to show how much of the 12.19 % was the reinvestment assumption ✓ CORRECT
- C. the motion is correct, because the treasury rate is the true opportunity cost
- D. MIRR should be removed from the paper to avoid confusing the committee

Rationale: MIRR is built from a terminal value, not a present value, so a hurdle comparison is a category error even though both are quoted as percentages (4.1.3). B also identifies MIRR's legitimate contribution — quantifying the reinvestment fiction — which is exactly why D is the wrong remedy: the answer to a misread disclosure is a better-explained disclosure, not less of it. C substitutes the reinvestment rate for the cost of capital, which are different quantities answering different questions.

MCQ 4.1-H [4.1.1 · Evaluation] Two teams appraise competing plants. Team A reports NPV +16,179,360 on a level 15-year inflow discounted at year-end; Team B reports +19,167,914 on the same 8 % rate using the mid-period convention. The board must choose one plant. The professionally sound handling is to:

- A. prefer Team B's plant, which shows the higher NPV
- B. average the two conventions to be even-handed
- C. restate both appraisals on a single declared convention before comparing, and record the convention in the assumption register — the 2,988,553 gap here is a modelling choice, not a difference in value ✓ CORRECT
- D. prefer Team A's plant, because year-end discounting is conservative

Rationale: $(1 + r)^{0.5}$ at 8 % is 1.0392305, so mid-period reporting adds about 3.9 % of present value to any project modelled that way; comparing across conventions ranks the modellers, not the plants (4.1.1c). A and D each let the convention decide. B produces a number that describes neither project and belongs to no convention — the appearance of fairness with none of the substance.

■ SELF-CHECK — KA 4.1

1. State the master appraisal's three verdicts and their meanings. — NPV +16.18m (value created at 8 %); IRR 12.19 % (break-even rate, 4.19-point margin); MIRR 9.73 % (return with honest 8 % reinvestment).
2. Why does a mining-with-restoration cash flow break IRR? — Two sign changes → up to two roots; "the" IRR does not exist.
3. What single question decides between NPV and IRR when they disagree? — Which project adds more money at the actual cost of capital — NPV's answer, by construction.
4. The forecast total is unchanged but the profile ramps over two years. What happens to NPV, and why? — It falls (16.18m → 13.70m, a loss of 2.48m): no revenue is lost, only its timing, and timing is what discounting prices.

5. A colleague reports 3.9 % more NPV than you on identical flows and the same rate. What is the first thing to check? — The discounting convention: $(1.08)^{0.5} - 1 = 3.92\%$ is exactly the mid-period premium at 8 %.
6. You substitute a published IRR of 12.19 % back into the NPV equation and get +6,751 rather than zero. Defect or artefact? — Artefact of two-decimal rounding; the unrounded 12.192120 % returns zero. Run the test on the retained value, not the printed one.

KNOWLEDGE AREA 4.2

The complementary measures

Topics: 4.2.1 payback and discounted payback · 4.2.2 profitability index · 4.2.3 equivalent annual value.

4.2.1 Payback and discounted payback

Definitions. **Payback** is the time until cumulative cash inflows repay the investment; **discounted payback** repeats the question in present-value terms. Neither measures value — both measure **exposure**: how long the capital is at risk before it has come home.

WORKED EXAMPLE

Worked example 4.2.1 — how long is Kestrel's money in the ground?

1. **Setup.** The master appraisal: $I_0 = 60,000,000$; inflows 8,900,000 per year; $r = 8\%$.
2. **Formula.** Payback = I_0 / A for a level stream. Discounted payback: the smallest n with $A \times AF(r, n) \geq I_0$, interpolated within the crossing year.
3. **Substitution.** Simple: $60,000,000 / 8,900,000 = 6.74$. Discounted: after year 10 the cumulative PV is $8,900,000 \times 6.710081 = 59,719,724$ — USD 280,276 short; year 11's discounted flow is $8,900,000 \times 0.428883 = 3,817,057$; fraction $280,276 / 3,817,057 = 0.07$.
4. **Result.** Payback **6.74 years**; discounted payback **10.07 years**.
5. **Interpretation.** The gap between the two numbers — three and a third years — is the price of time value: nominal repayment by year 7 does not return the capital's worth until year 10. For a 15-year concession, ten years of exposure is a risk fact the board should see beside the +16.2m NPV, not instead of it. The standing rule: **payback screens; NPV decides**. Payback's known biases — it ignores everything after the cut-off and penalises long-life infrastructure precisely for being long-lived — make it a veto-check, never a ranking.



Fig 4.2.1 — Two paybacks: cumulative cash versus cumulative present value

Worked example 4.2.1b — payback when the flows are not level.

I_0 / A works only for a level stream. Real payback is read off the cumulative column and interpolated inside the year that crosses — and the ramp profile of 4.1.1b shows why the shortcut flatters.

1. **Setup.** The ramped forecast: 4,600,000 · 6,700,000 · then 9,400,000 for years 3-15; I_0 = 60,000,000; r = 8 %. Total inflow identical to the level case.
2. **Formula.** Find the first year t where cumulative inflow $\geq I_0$, then $\text{payback} = (t - 1) + (I_0 - \text{cumulative at } t - 1) / CF(t)$. For discounted payback, run the same procedure on the cumulative present values.
3. **Substitution.** Cumulative nominal: 4,600,000 · 11,300,000 · 20,700,000 · 30,100,000 · 39,500,000 · 48,900,000 · **58,300,000** (year 7) · 67,700,000 (year 8). The crossing is in year 8: shortfall 60,000,000 - 58,300,000 = 1,700,000, and 1,700,000 / 9,400,000 = 0.1809.
4. **Result.** Payback **7.18 years** against the level case's 6.74; discounted payback **10.91 years** against 10.07.
5. **Interpretation.** The ramp adds **0.44 years** of nominal exposure and **0.84 years** of discounted exposure on cash flows whose fifteen-year total is identical to the pennies. The asymmetry is the lesson: discounting punishes late money twice — once in the value measure and again in the exposure measure — so a ramp is worse for a lender's tenor test than a sponsor's undiscounted payback rule reveals. This is also the cleanest available demonstration that **payback is a function of the profile, not of the total**, which is why "payback under five years" is such a poor policy: it can be satisfied or failed by rescheduling commissioning without changing a single dollar of forecast revenue. Interpolation within the crossing year assumes cash accrues evenly through it; where it does not — a seasonal offtake, a single annual availability payment — say so and report the payback to the whole year instead of inventing a decimal the data cannot support.

4.2.2 The profitability index

Definition. Value created per unit of scarce capital:

$$PI = PV(\text{future cash flows}) / I_0$$

Kestrel: $76,179,360 / 60,000,000 = **1.270**$ — each invested dollar buys USD 1.27 of present value. PI ranks efficiency and earns its keep in exactly one situation: **capital rationing** (KA 4.3.2), where the question is not "is this project good?" but "which portfolio of good projects fits the budget?". Unconstrained, PI adds nothing to NPV and can mis-rank mutually exclusive projects of different scale — the same scale-blindness as IRR, in ratio form.

Two definitions, one point apart. PI is published in two forms and the difference is exactly 1.000. The **gross** (or absolute) index used above is $PV(\text{inflows}) / I_0$ and its accept threshold is **1.0**. The **net** index is NPV / I_0 — the same information restated, threshold **0.0**. Kestrel's are **1.269656** and **0.269656**. Neither is wrong; a paper that does not say which it uses is, and a rationing table that mixes the two ranks projects by which analyst filled the row. Because the two differ by a constant they always produce the **same ranking**, which is why the ambiguity survives so long undetected — it corrupts the threshold, not the order.

WORKED EXAMPLE

Worked example 4.2.2 — the index, its invariant, and what the ramp does to it.

1. **Setup.** The master appraisal ($PV = 76,179,360$, $I_0 = 60,000,000$, $NPV = +16,179,360$) and the ramped profile of 4.1.1b ($PV = 73,699,840$). $r = 8\%$; $IRR = 12.192120\%$.
2. **Formula.** $PI = PV / I_0$; the invariant to test is $PI > 1 \Leftrightarrow NPV > 0$ **at the same rate**, with equality at the IRR by construction.
3. **Substitution.** Level: $76,179,360 / 60,000,000$. Ramped: $73,699,840 / 60,000,000$. At the IRR: $8,900,000 \times AF(0.12192120, 15) / 60,000,000$.
4. **Result.** Level **PI = 1.269656**; ramped **PI = 1.228331**; at the IRR **PI = 1.000000** exactly.
5. **Interpretation.** The third figure is the useful one. $PI = 1$ at the IRR is not a coincidence but a definition seen from another angle — the IRR is the rate at which the project returns exactly its capital in present value — and it gives a reviewer a second, independent way to audit a published IRR without re-solving anything: compute PI at the quoted rate and it must come to one. The first two figures carry a different lesson: the ramp costs 4.13 points of index, and index points are the currency of a rationing decision. A project that ranks third on a level-profile screening table can rank fifth once profiles are modelled honestly, and the two projects it displaced are the ones that never got funded. **Screen on the profile you will actually build.**

4.2.3 Equivalent annual value

Definition. EAV converts an NPV over a life of n years into the level annual amount with the same present value:

$$EAV = NPV / AF(r, n)$$

Its natural habitat is **unequal lives**: comparing a 3-year asset with a 5-year asset by raw NPV smuggles in the assumption that the world ends when the shorter one does.

WORKED EXAMPLE**Worked example 4.2.3 — two pumps, unequal lives.**

1. **Setup.** Kestrel must choose a dosing-pump system. **System A:** costs 5,000,000, runs 3 years, operating cost 800,000 per year. **System B:** costs 7,600,000, runs 5 years, operating cost 500,000 per year. Same duty; $r = 8\%$. (Costs, so lower is better.)
2. **Formula.** $PV \text{ of cost} = \text{capex} + \text{opex} \times AF(r, n)$; equivalent annual cost $EAV = PV / AF(r, n)$.
3. **Substitution.** A: $5,000,000 + 800,000 \times 2.577097 = 7,061,678$; $EAV = 7,061,678 / 2.577097$.
B: $7,600,000 + 500,000 \times 3.992710 = 9,596,355$; $EAV = 9,596,355 / 3.992710$.
4. **Result.** A: **USD 2,740,168 per year.** B: **USD 2,403,469 per year** — B is cheaper by USD 336,699 every year, despite the 52 % higher purchase price.
5. **Interpretation.** Raw PV comparison (7.06m vs 9.60m) points the wrong way because it prices three years against five. EAV puts both on a per-year footing under the standard assumption that each system is replaced in kind at the end of its life. When that assumption fails — technology shifts, the duty ends — model the actual replacement chain instead (Domain 8's lifecycle costing).

Worked example 4.2.3b — the master appraisal's value, per year.

EAV is usually introduced as an unequal-lives device, which undersells it. Applied to a single project it answers a question boards ask constantly and NPV answers badly: how much is this worth per year?

1. **Setup.** The master appraisal: $NPV = +16,179,360$ over 15 years at 8 %.
2. **Formula.** $EAV = NPV / AF(r, n)$; the invariant is $EAV \times AF(r, n) = NPV$.
3. **Substitution.** $16,179,360 / 8.559479$; then multiply back.
4. **Result.** **EAV = USD 1,890,227 per year**, and $1,890,227 \times 8.559479 = 16,179,360$ — the invariant closes to the cent.
5. **Interpretation.** Two readings, both useful in a board room. First, the plant creates about 1.89 million a year of value beyond the cost of the capital tied up in it — a figure that can be set against an annual operating budget, an annual availability payment or a management fee in a way that a lump present value cannot. Second, and more revealing, the annual inflow decomposes **exactly**: capital recovery $I_0 / AF(r, n) = 60,000,000 / 8.559479 = 7,009,773$ plus value created 1,890,227 sums to **8,900,000**, the inflow itself. So **21.24 % of every year's cash is value and 78.76 % is the capital coming home** — and the first of those numbers is the honest answer to "how much margin do we have?" Note what this decomposition also gives for free: 7,009,773 is precisely the annual inflow at which NPV would be zero, so the breakeven analysis of KA 4.3.3 is already implicit in the EAV arithmetic. One identity, three uses.

Worked example 4.2.3c — the same pump choice, proved a second way.

EAV assumes like-for-like replacement in perpetuity. The assumption is testable: replace each system in kind over a **common horizon** — the lowest common multiple of the two lives — and compare present values directly, with no annualisation at all. If the two methods disagree, one of them has been mis-applied.

1. **Setup.** System A (5,000,000 capex, 3-year life, 800,000 p.a. opex) against System B (7,600,000 capex, 5-year life, 500,000 p.a.). $r = 8\%$. LCM of 3 and 5 is **15 years**: five cycles of A against three of B.
2. **Formula.** $PV_{\text{chain}} = \sum PV_{\text{cycle}} / (1 + r)^{(k \cdot \text{life})}$ for $k = 0 \dots (\text{cycles} - 1)$, where PV_{cycle} is the one-life present value of costs.

3. **Substitution.** $PV_cycle(A) = 5,000,000 + 800,000 \times 2.577097 = 7,061,678$, repeated at $t = 0, 3, 6, 9, 12$. $PV_cycle(B) = 7,600,000 + 500,000 \times 3.992710 = 9,596,355$, repeated at $t = 0, 5, 10$.
4. **Result.** Chain A = **23,454,406**; chain B = **20,572,442**; B is cheaper by **2,881,964** over the common horizon. Cross-check through the annual route: $EAV_A \times AF(0.08, 15) = 2,740,168 \times 8.559479 = 23,454,406$ and $EAV_B \times AF(0.08, 15) = 2,403,469 \times 8.559479 = 20,572,442$ — **identical to the cent**.
5. **Interpretation.** The methods agree because they are the same statement: an equivalent annual cost multiplied by any horizon's annuity factor reconstructs the chain cost over that horizon. That exact agreement is worth more than the answer, because it is the family's verification rule applied to a decision rather than a formula — two independent routes, one number, and any disagreement localises the error immediately. What the chain view adds is **visibility of the assumption**: laid out over fifteen years, the five replacement events for A and three for B are explicit, and a reviewer can ask whether a fifth generation of the same pump will really be available and priced at 5,000,000 in year twelve. Where the honest answer is no — and for anything with a technology curve it usually is — neither method should be trusted past the first replacement, and the comparison becomes a staged one (KA 4.A.4). EAV's convenience is that it hides the chain; its danger is exactly the same.

AI in this KA

Screening portfolios is high-volume, formulaic work — the natural first place an organisation automates appraisal, and the first place systematic error industrialises. Two governed habits: the screening tool's formulae are validated once against this domain's golden examples (the registry pattern, checked by the Institute's verification suite), and every auto-screened rejection above a materiality line gets a human review — a portfolio can lose its best project to one wrong sign convention, silently, forever.

■ KEY TERMS — KA 4.2

Term	Meaning
Payback / discounted payback	Years for cumulative (discounted) inflows to repay I_0 ; exposure measures.
PI	PV of inflows / I_0 ; value per scarce dollar, for rationing.
EAV	NPV (cost PV) converted to a level annual equivalent via $AF(r, n)$.
Unequal lives	The comparison EAV exists to make honest.
Replacement chain	The explicit alternative when like-for-like replacement fails.
Gross vs net PI	PV/I_0 (threshold 1.0) vs NPV/I_0 (threshold 0.0); same ranking, different threshold.
Capital-recovery annuity	$I_0 / AF(r, n)$; the annual inflow at which NPV is exactly zero.
Common horizon (LCM)	Comparing replacement chains over the lowest common multiple of the lives.

■ SAMPLE MCQS — KA 4.2

MCQ 4.2-A [4.2.1 · Application] For the master appraisal (60m in, 8.9m/yr, 8 %), the discounted payback is closest to:

A. 6.74 years

- B. 10.07 years ☒ **CORRECT**
- C. 8.00 years
- D. 15.00 years

Rationale: Cumulative PV reaches 59.72m after year 10; the 0.28m shortfall is 7 % of year 11's 3.82m discounted flow → 10.07. A is the simple payback; C confuses the discount rate with a duration; D is the whole life.

MCQ 4.2-B [4.2.3 · Application] System A (PV of costs 7,061,678 over 3 years, $AF = 2.577097$) versus System B (PV 9,596,355 over 5 years, $AF = 3.992710$). The correct comparison and choice is:

- A. raw PV: A is cheaper, choose A
- B. equivalent annual cost: A 2,740,168 vs B 2,403,469 — choose B ☒ **CORRECT**
- C. equivalent annual cost: A 2,353,893 vs B 1,919,271 — choose B
- D. purchase price: A is cheaper, choose A

Rationale: Unequal lives require EAV: $7,061,678/2.577097 = 2,740,168$ vs $9,596,355/3.992710 = 2,403,469$. A and D compare unlike horizons; C divides each PV by its raw life in years ($\div 3$ and $\div 5$), annualising without discounting — the right instinct with the wrong arithmetic.

MCQ 4.2-C [4.2.1 · Analysis] A board adopts "payback under 5 years" as its sole investment criterion. The predictable portfolio distortion is:

- A. none — payback is conservative, so the portfolio is safe
- B. systematic bias against long-lived infrastructure and toward short-cycle projects, regardless of value created ☒ **CORRECT**
- C. excessive investment in high-NPV projects
- D. elimination of all risk

Rationale: Payback ignores everything beyond its cut-off, so a 15-year concession with NPV +16m loses to a 4-year project with NPV +1m. That is a value distortion, not conservatism (A); C reverses the effect; D confuses shorter exposure with no risk.

MCQ 4.2-D [4.2.2 · Recall] The profitability index earns its place in appraisal when:

- A. projects are mutually exclusive and differ in scale
- B. capital is rationed and the question is which portfolio of positive-NPV projects fits the budget ☒ **CORRECT**
- C. cash flows change sign more than once
- D. lives are unequal

Rationale: PI ranks value per scarce dollar — the rationing question exactly. A is where PI (like IRR) mis-ranks by scale; C is MIRR's territory; D is EAV's.

MCQ 4.2-E [4.2.2 · Comprehension] A screening pack reports one project at "PI 1.27" and another at "PI 0.31". Before any comparison, the analyst must establish that:

- A. both indices use the same definition — gross PV/I_0 (threshold 1.0) or net NPV/I_0 (threshold 0.0) — because the two differ by exactly 1.000 ☒ **CORRECT**
- B. the second project has been rejected, since its index is below 1.0
- C. both projects have the same life
- D. the discount rate exceeds the IRR in both cases

Rationale: The two published forms differ by a constant, so a mixed table corrupts the accept threshold while leaving the ranking intact — which is why the defect survives review (4.2.2). B commits exactly that error: 0.31 on the net definition is a healthy project. C matters for EAV, not PI. D is unrelated to either definition.

MCQ 4.2-F [4.2.1 · Comprehension] The master appraisal's simple payback is 6.74 years and its discounted payback 10.07 years, on identical cash flows. What does the three-and-a-third-year gap between the two figures tell the board?

- A. that discounting has removed three and a third years of cash flow from the forecast
- B. that repaying the 60,000,000 in nominal cash by year seven does not return the capital's worth until year ten — the gap is the price of time value, and both figures measure exposure duration rather than value ☒ **CORRECT**
- C. that the 8 % rate is too high for a fifteen-year concession
- D. that the two measures disagree, so one of them has been computed on the wrong cash flows

Rationale: The same flows produce both numbers; the later crossing is what it costs to require recovery in present value rather than in nominal cash, and neither figure says anything about how much value the project creates (4.2.1). A confuses discounting a stream with shortening it. C reads a rate judgement out of an arithmetic consequence that holds at every positive rate. D treats an expected relationship — discounted payback is always the later of the two unless $r = 0$ — as a defect.

MCQ 4.2-G [4.2.3 · Evaluation] An asset manager must choose between a 3-year and a 5-year dosing system. EAV favours the 5-year system by 336,699 a year; the 15-year replacement chain favours it by 2,881,964 in present value; the two agree exactly. The plant, however, is on a concession with **seven years** left to run and no renewal right. The soundest position is that:

- A. choose the 5-year system — both methods agree, and agreement is the strongest evidence available
- B. choose the 3-year system, because it is cheaper to buy
- C. neither number answers the question asked: both price perpetual like-for-like replacement, and over a seven-year duty the relevant comparison is the actual cost of each option to concession end, including residual value or removal ☒ **CORRECT**
- D. average the two methods and choose the cheaper

Rationale: The exact agreement of EAV and the chain method is real but proves only internal consistency — they encode the same assumption, so agreeing cannot validate it (4.2.3c). A mistakes consistency for applicability. Over a seven-year duty the 3-year system implies two full cycles and one stranded year, the 5-year implies one cycle and two stranded years, and residual value decides; that is a different calculation, not a correction to these. D averages two answers to a question nobody asked.

MCQ 4.2-H [4.2.1 · Evaluation] A sponsor's board holds a standing rule: reject anything with discounted payback beyond nine years. The Kestrel appraisal shows NPV +16,179,360, IRR 12.19 % and discounted payback 10.07 years. The professionally sound recommendation is to:

- A. reject the project, since the rule is clear
- B. recommend the project on its value, and put the rule itself to the board as the decision it actually is — a stated tolerance for exposure duration that here costs 16.18 million of value, with the exposure disclosed rather than hidden ☒ **CORRECT**
- C. reprofile the model until payback falls under nine years
- D. reject the project but note the NPV in an appendix

Rationale: Payback screens and NPV decides (4.2.1); a screening rule that vetoes a positive-NPV project is a policy choice about exposure, and the leader's obligation is to surface it with the value at stake attached, not to let a threshold decide silently. C is model manipulation to satisfy a rule — the dishonesty of MCQ 4.3-C's distractor D in a different costume. A and D both apply the rule as though it were an appraisal result; D adds the pretence of disclosure while burying the finding where it changes nothing.

■ SELF-CHECK — KA 4.2

1. Why is discounted payback always later than simple payback? — Discounting shrinks every inflow, so the cumulative line climbs more slowly (equal only if $r = 0$).
2. State Kestrel's PI and its meaning. — 1.270: each dollar invested buys 1.27 dollars of present value.
3. What assumption does EAV smuggle in, and when must you drop it? — Like-for-like replacement in perpetuity; drop it when the duty ends or technology shifts, and model the real chain.
4. Decompose Kestrel's 8,900,000 annual inflow. — 7,009,773 capital recovery (I_0 / AF) + 1,890,227 value created (EAV); 78.76 % / 21.24 %.
5. What single figure proves a published IRR without re-solving it? — PI at that rate: it must equal 1.000 exactly.
6. The ramp profile of 4.1.1b has the same fifteen-year total. What does it do to payback? — Lengthens it: 6.74 → 7.18 nominal, 10.07 → 10.91 discounted. Payback prices the profile, not the total.

KNOWLEDGE AREA 4.3

Decision contexts: exclusivity, rationing and judgment

Topics: 4.3.1 mutually exclusive investments · 4.3.2 capital rationing · 4.3.3 the limits of the numbers.

4.3.1 Mutually exclusive investments

The conflict. Choosing one project instead of another is where NPV and IRR famously disagree. Kestrel's board weighs two intake designs (same risk class, $r = 8\%$):

Design	I_0	Net inflow × 5 yrs	NPV @ 8 %	IRR
P (compact)	5,000,000	2,000,000	+2,985,420	28.65 %
Q (full-scale)	20,000,000	6,000,000	+3,956,260	15.24 %

IRR shouts P; NPV says Q adds USD 970,840 more money. The tie-breaker is the **incremental project** Q–P: invest a further 15,000,000 for a further 4,000,000 per year — an incremental IRR of **10.42 %**, above the 8 % cost of capital. The extra capital earns its keep, so take the bigger project. **Rule: when exclusivity forces a choice, rank by NPV; use incremental IRR only to narrate the same answer.** (At any hurdle above 10.42 % the ranking genuinely flips — the crossover rate is where the two NPV profiles intersect.)




Fig 4.3.1 — Two NPV profiles and the crossover

Worked example 4.3.1 — the crossover, derived exactly and then proved.

The crossover rate is usually read off a chart. Deriving it takes one line of algebra, and the derivation produces a check that no chart can give.

- Setup.** P: I_0 5,000,000, inflow 2,000,000 for 5 years. Q: I_0 20,000,000, inflow 6,000,000 for 5 years. Same risk class.
- Formula.** The profiles intersect where their NPVs are equal, which is where the **incremental** project Q–P has zero NPV — so the crossover rate is the incremental IRR. Setting $2,000,000 \cdot AF - 5,000,000 = 6,000,000 \cdot AF - 20,000,000$ gives $4,000,000 \cdot AF = 15,000,000$, i.e. $AF(r, 5) = 3.750000$.
- Substitution.** Solve $AF(r, 5) = 3.75$ for r ; then substitute the root back into **both** original projects.
- Result. Crossover = 10.424845 %.** At that rate $NPV_P = 2,000,000 \times 3.75 - 5,000,000 = 2,500,000$ and $NPV_Q = 6,000,000 \times 3.75 - 20,000,000 = 2,500,000$ — **equal, exactly, to the dollar.**
- Interpretation.** The exactness is the point. Because the crossover falls out of a single factor value (3.750000), both NPVs at that rate are round by construction, and any model reporting a crossover where the two NPVs differ has an error — in the flows, in the factor, or in the root. Read the geometry with the algebra and the whole decision becomes legible: below 10.42 % the extra 15,000,000 that Q requires earns more than that capital costs, so Q leads; above it, P leads; at the 8 % hurdle Q leads by 970,840, which is 2.42 points of hurdle away from indifference. That last figure is the one to put in the paper, because it answers the question a director will actually ask — how wrong would our rate have to be to change this decision? Here: 2.42 points, a comfortable margin. Where the answer comes back at twenty basis points, the ranking is not a finding but a coin toss with decimals, and the choice should be made on the qualitative grounds instead — and recorded as having been made that way.

Discount rate	0 %	8 %	10.4248 %	15 %	15.2382 %	20 %	28.6493 %
NPV_P (USD)	5,000,000	2,985,420	2,500,000	1,704,310	1,666,667	981,224	0
NPV_Q (USD)	10,000,000	3,956,260	2,500,000	112,931	0	−2,056,327	−5,000,000
Leader	Q	Q	tie	P	P	P	P

Two features of the row deserve a moment. Q's profile is **steeper** — its zero-crossing is at 15.24 % against P's 28.65 % — because Q's value is concentrated in the same five years but on three times the capital; steepness is duration-and-scale sensitivity made visible. And P's IRR of 28.65 %, the number that would have won the argument in most rooms, corresponds to a rate at which Q has already destroyed exactly five million. A percentage that high tells you the small project is efficient; the table tells you the organisation would be poorer for choosing it.

The two cross-cells are exact, and that is a third invariant. At either project's own IRR the annuity factor is pinned by that project's own ratio I_0 / A , so the other project's NPV there is a round number by construction. At P's IRR the factor is $5,000,000 / 2,000,000 = 2.500000$, so $NPV_Q = 6,000,000 \times 2.5 - 20,000,000 = -5,000,000$ to the dollar; at Q's IRR the factor is $20,000,000 / 6,000,000 = 3.333333...$, so $NPV_P = 2,000,000 \times 10/3 - 5,000,000 = 1,666,667$. A profile table whose cross-cells are not round has been drawn on a published two-decimal rate rather than the retained one — the rounding trap of 4.1.2 reappearing in a presentation table instead of a check block, and a defect worth catching because a reader who spots it will trust nothing else in the exhibit.

4.3.2 Capital rationing

The problem. When the budget cannot fund every positive-NPV project, maximise **NPV per budget dollar** — rank by PI and pack the budget:

Project	I_0 (m)	NPV (m)	PI	Cumulative I_0
W	8	2.40	1.300	8
X	12	3.00	1.250	20 ← budget
Y	10	2.20	1.220	—
Z	6	1.02	1.170	—

With a USD 20m budget the PI ranking funds **W + X for NPV +5.40m**; the tempting "biggest NPV first, then fill" (X, then Y won't fit, then W) lands on the same 5.40m here, but the next-best feasible set (W + Y, +4.60m) shows what a wrong packing costs. Discipline points: PI packing is exact only when projects are divisible or the budget binds once — lumpy multi-period rationing is an optimisation problem (Domain 6's model does it honestly); and rationing itself deserves challenge, because turning away a 1.17-PI project is a financing failure as often as a screening success (Domain 9).

Worked example 4.3.2 — the ranking rule that funds the wrong portfolio.

The table above is the comfortable case: PI order and value maximisation coincide. Add one small, attractive project and they part company — which is why "rank by PI and fill the budget" must be taught as a heuristic and never as a rule.

- Setup.** The same USD 20,000,000 budget, now with five candidates. All are independent, all have positive NPV, and each is indivisible — you fund it or you do not.

Project	I ₀ (USD)	NPV (USD)	PI
W	8,000,000	2,400,000	1.3000
V	4,000,000	1,160,000	1.2900
X	12,000,000	3,000,000	1.2500
Y	10,000,000	2,200,000	1.2200
Z	6,000,000	1,020,000	1.1700

1. **Formula.** Greedy PI: take projects in descending index order, skipping any that no longer fits, until the budget is exhausted. Then compare against the value-maximising set found by **enumerating every feasible combination** — with five projects there are 31 non-empty subsets, of which **16** fit the budget (all five singles, nine of the ten pairs, and two of the ten triples; no set of four can fit, since the four cheapest already total 28,000,000), so exhaustive search is a minute's work, not a research problem.
2. **Substitution.** Greedy takes W (8,000,000; 12,000,000 left), then V (4,000,000; 8,000,000 left), then skips X (12,000,000 — will not fit) and Y (10,000,000 — will not fit), then takes Z (6,000,000; 2,000,000 left and nothing to spend it on). Enumeration tests all sixteen feasible sets.
3. **Result.** Greedy funds **W + V + Z for NPV +4,580,000** on 18,000,000 spent. The value-maximising set is **W + X for NPV +5,400,000** on 20,000,000 spent exactly. Greedy leaves **USD 820,000 of value unfunded** — and leaves 2,000,000 of budget unspent while doing it.
4. **Interpretation.** The mechanism is worth naming, because it is not an arithmetic slip: greedy PI maximises value per dollar committed, and the budget constraint asks for value per dollar available. V, with the second-best index, is what causes the damage — taking it consumes four million that then cannot be combined with X's twelve, and the fragment left over is unusable. High-index small projects are the classic trap, and they are precisely the ones a screening committee finds most attractive. Three disciplines follow. **Use PI to shortlist, then enumerate or optimise** — the exhaustive check is cheap up to about twenty candidates and standard solvers handle the rest (Domain 6). **Report the unspent budget**, because 2,000,000 idle beside a rejected 1,020,000-NPV project is a visible symptom of the defect. And **report the runner-up set with its value**, so the board sees the cost of the packing it approved rather than a single list presented as though it were the only one. Note finally that this whole exercise assumes the budget is genuinely fixed; 4.3.2's standing challenge applies with more force here, since 820,000 of foregone value is a strong argument for finding two million more.

Where the budget binds twice. A single-period budget is already a simplification. Real capital plans bind in each of several years, and a project's spend profile — not just its total — decides whether it fits. A two-year-spend project can be feasible on totals and infeasible in year one, and no index computed on total I₀ can see that. This is the point at which appraisal hands the problem to modelling: the constraint set belongs in the model with one row per period, and the answer is an optimisation the spreadsheet performs and the professional interrogates (Domain 6, KA 6.3). What appraisal keeps is the obligation to state which constraints were imposed, because a portfolio is only optimal with respect to the constraints someone chose to write down.

4.3.3 The limits of the numbers

Every measure in this domain consumes forecasts and a rate, and both are judgments wearing decimals. The professional frame: **appraisal quantifies; it does not decide strategy**. Numbers cannot see option value (the pilot that buys the right to scale), strategic foreclosure (the market position lost by not building), or the asymmetry of forecast error (Domain 8's ranges belong beside

every point NPV). The board paper this domain endorses shows: NPV at the owned rate; the sensitivity of that NPV to the two or three assumptions that dominate it; IRR/MIRR as narrative; exposure via discounted payback; and the explicit statement of what the numbers cannot price. Anything less is theatre with spreadsheets.

Worked example 4.3.3 — the two numbers that replace a point estimate.

A single NPV invites a single question ("is it positive?"). Two constructions turn the same model into a decision document: the **breakeven** — how far can the dominant assumption fall before value disappears — and the **two-way table** that shows where the sign changes across the pair of assumptions that actually dominate.

1. **Setup.** The master appraisal: $I_0 = 60,000,000$, inflow 8,900,000 for 15 years, $r = 8\%$. The two dominating assumptions are the annual net inflow (a function of tariff and availability) and the discount rate.
2. **Formula.** Breakeven inflow: set $NPV = 0$, so $A^* = I_0 / AF(r, n)$ — the capital-recovery annuity already computed in 4.2.3b. Breakeven rate: the IRR. Then tabulate $NPV = A \cdot m \cdot AF(r, 15) - I_0$ across multipliers m and rates r .
3. **Substitution.** $A^* = 60,000,000 / 8.559479 = 7,009,773$, which is $(8,900,000 - 7,009,773) / 8,900,000 = 21.24\%$ below the base case. The rate breakeven is the IRR, 12.1921 %, which is 4.19 points above the hurdle.
4. **Result.**

Inflow vs base	6 %	7 %	8 %	9 %	10 %	12.1921 %
80 % (7.12m)	+9,151,213	+4,848,348	+943,488	-2,607,898	-5,844,714	-12,000,000
90 % (8.01m)	+17,795,114	+12,954,391	+8,561,424	+4,566,114	+924,697	-6,000,000
100 % (8.90m)	+26,439,016	+21,060,435	+16,179,360	+11,740,127	+7,694,108	0
110 % (9.79m)	+35,082,918	+29,166,478	+23,797,296	+18,914,140	+14,463,518	+6,000,000

The final column is computed on the **retained** IRR (12.192120 %), not the published two-decimal figure, and it is exact for a reason worth knowing: at the IRR the present value of the base inflow equals I_0 by definition, so scaling the inflow by a multiplier m gives $NPV = m \times I_0 - I_0 = (m - 1) \times I_0$ — $60,000,000 \times (-0.20, -0.10, 0, +0.10)$. Run the same column on the published 12.19 % instead and every cell shifts by roughly six thousand while the 100 % cell stops being zero. Either convention is defensible; **mixing them inside one exhibit is not**, and this column is the standing example of the discipline in 4.1.2 — publish two decimals, retain the root, compute from the root.

1. **Interpretation.** The table says something no point estimate can: the project survives a **21.24 % revenue shortfall** at the board's rate, and survives a 20 % shortfall at any rate up to about 8.2 % — but a 20 % shortfall combined with a 9 % cost of capital destroys value. The professional discipline is to read the **joint** cell rather than two separate sensitivities, because the two assumptions are not independent in reality: the conditions that depress a water project's availability revenue (a weak offtaker, a stressed sector) are the same conditions that raise its cost of capital, so the down-left cells of this table are not remote corners but a coherent scenario. That is the difference between sensitivity analysis and scenario analysis, and Domain 8 formalises it. Two further readings for the board paper. The 21.24 % headroom is the figure to negotiate against — it tells the sponsor how much tariff can be conceded before the investment case, not merely the profit, is gone. And the bottom-right cell (**+6,000,000** at the IRR on a 110 % case) shows that even the breakeven rate is a breakeven only for the base case; an IRR is a statement about one forecast, and quoting it without the forecast is the omission this whole Knowledge Area

exists to prevent. The linearity of that last column — exactly ten per cent of I_0 per ten per cent of inflow — is also the sharpest available statement of how little an IRR contains: at the rate where the project is worth nothing on the base forecast, a tenth more revenue is worth precisely a tenth of the outlay, and no percentage can carry that information because it has divided the scale out.

AI in this KA

Ranking under constraints is combinatorial — machine territory — and constraint errors are silent. The governed pattern from Domain 6 applies unchanged: the optimiser proposes the portfolio; the analyst verifies the constraint set against reality (is the budget truly annual? are W and X really independent?); golden checks re-verify the NPVs being packed; and the leader owns the strategic overrides the model cannot see (4.3.3) — recorded as decisions, not adjustments smuggled into assumptions.

■ KEY TERMS — KA 4.3

Term	Meaning
Mutually exclusive	Choosing one forecloses the other; rank by NPV.
Incremental IRR	IRR of the difference project; narrates the NPV ranking.
Crossover rate	Rate where two NPV profiles intersect and rankings flip.
Capital rationing	Budget binds before value runs out; pack by PI.
Option value	Value of flexibility the static NPV cannot see.
Greedy PI packing	Descending-index selection; a heuristic that can leave value and budget unused.
Breakeven inflow	$I_0 / AF(r, n)$; the revenue level at which NPV reaches zero.
Two-way sensitivity	NPV tabulated across the two dominating assumptions jointly, not separately.
Indivisible project	Funded whole or not at all; the reason enumeration replaces sorting.

■ SAMPLE MCQS — KA 4.3

MCQ 4.3-A [4.3.1 · Application] P: NPV +2,985,420, IRR 28.65 %. Q: NPV +3,956,260, IRR 15.24 %. Cost of capital 8 %; only one may proceed. The correct choice is:

- A. P — higher IRR
- B. Q — higher NPV, confirmed by an incremental IRR of 10.42 % above the hurdle ✓ CORRECT
- C. P — lower investment is always safer
- D. both, split the budget

Rationale: Exclusive choices rank by money added: Q adds USD 970,840 more, and the extra 15m earns 10.42 % > 8 %. A is the scale-blindness pathology; C prices fear, not value; D violates the premise.

MCQ 4.3-B [4.3.2 · Application] Budget USD 20m. Projects (I_0 , NPV): W (8, 2.4), X (12, 3.0), Y (10, 2.2), Z (6, 1.02). The value-maximising funded set is:

- A. X and Y
- B. W and X: NPV +5.40m ✓ CORRECT
- C. W, Y and Z

D. X and Z

Rationale: PI order W (1.300), X (1.250) packs the budget exactly for +5.40m. A needs 22m; C needs 24m; D fits (18m) but yields +4.02m — a 1.38m sacrifice for leaving W unfunded.

MCQ 4.3-C [4.3.3 · Analysis] A pilot plant shows NPV –800,000, but building it creates the option to deploy at 20× scale if the technology proves. The appraisal-sound treatment is:

- A. reject — negative NPV is disqualifying
- B. approve by overriding the NPV silently
- C. present the static NPV alongside an explicit valuation (or structured judgment) of the scaling option, and decide on the combined case, recorded as such ✓ CORRECT
- D. raise the forecast cash flows until NPV turns positive

Rationale: Static NPV cannot see option value; the remedy is to price or judge the option in the open. A discards real value; B and D are the same dishonesty at different altitudes — one hides the judgment, the other disguises it as a forecast.

MCQ 4.3-D [4.3.1 · Recall] The crossover rate of two NPV profiles is:

- A. the rate at which both projects' NPVs equal zero
- B. the rate at which the two NPVs are equal — above it, the ranking flips ✓ CORRECT
- C. the average of the two IRRs
- D. the cost of capital

Rationale: Crossover is the intersection of profiles (equivalently the incremental project's IRR). A describes two separate IRRs; C is arithmetic superstition; D is a property of the firm, not of the pair.

MCQ 4.3-E [4.3.2 · Comprehension] Why does ranking indivisible projects by descending profitability index sometimes fund a portfolio worth less than the best feasible one?

- A. because the index is computed at the wrong discount rate
- B. because the index maximises value per dollar committed, while the budget constraint asks for value per dollar available — so a high-index small project can consume capital that a larger project then cannot use, stranding a fragment ✓ CORRECT
- C. because the index ignores the discount rate entirely
- D. because indivisible projects always have lower NPVs

Rationale: The mechanism, not an arithmetic error: greedy selection is exact for divisible projects and only a heuristic for lumpy ones (4.3.2). A and C misdescribe the index, which is built from a present value at the project rate. D is simply untrue.

MCQ 4.3-F [4.3.3 · Comprehension] A water project's sensitivity exhibit tabulates NPV across annual net inflow (80 % to 110 % of base) and discount rate (6 % to 10 %) jointly. Taken one at a time, the project survives a 20 % inflow shortfall and survives a 9 % cost of capital; taken together, those two movements destroy value. Why must the analyst read the joint cells rather than the two single-assumption sensitivities?

- A. because joint cells are easier to compute
- B. because the assumptions are correlated in reality — the conditions that depress availability revenue also tend to raise the cost of capital — so the combined case is a coherent scenario rather than a remote corner ✓ CORRECT
- C. because single-assumption sensitivities are arithmetically invalid
- D. because the discount rate has no effect on NPV in isolation

Rationale: Individually the project survives a 20 % revenue shortfall and survives a 9 % rate; jointly it does not, and correlation makes that combination realistic rather than extreme (4.3.3). C is false — one-way sensitivities are valid, merely insufficient. D contradicts the table's own rows.

MCQ 4.3-G [4.3.2 · Evaluation] A committee's rationing pack presents one funded set, ranked by PI, spending 18,000,000 of a 20,000,000 budget for NPV +4,580,000. You establish overnight, by enumeration, that a feasible set spends the full 20,000,000 for +5,400,000. Every NPV in the pack is correct. The board meets tomorrow and the pack has already circulated. The soundest course is to:

- A. let the recommendation stand and log the finding for the next cycle: 820,000 is 15 % of the value on the table but the pack's arithmetic is sound, and re-opening a circulated recommendation the night before a board costs the committee credibility it will need later
- B. table a one-page addendum carrying the enumerated set, the 2,000,000 the recommendation leaves unspent and the runner-up set with its NPV, so the board approves a portfolio knowing that the packing it was offered costs 820,000 ✓ CORRECT
- C. withdraw the recommendation and present both sets without one, on the grounds that choosing between them is the board's decision rather than the committee's
- D. keep the PI ranking as the recommendation, since greedy indexing is the committee's established method, and record the enumeration in an appendix for completeness

Rationale: The defect is disclosure, not arithmetic, and the remedy is proportionate to it: one page, in time, changes the decision the board actually takes (4.3.2). A is a real argument — process discipline has value and the number is not enormous — but it trades 820,000 of shareholder value for the committee's comfort, and the asymmetry decides it. C over-corrects: the committee is paid to recommend, and handing up two sets with no view transfers work rather than judgement. D is the subtlest wrong answer, because it discloses the finding while leaving it where nothing depends on it — an appendix that contradicts the recommendation is not disclosure, it is cover.

MCQ 4.3-H [4.3.3 · Evaluation] A sponsor's appraisal shows Kestrel surviving a 21.24 % revenue shortfall at the board's rate. In tariff negotiation the offtaker asks for a 15 % reduction. The soundest use of that headroom figure is:

- A. concede up to 21.24 %, since the project remains value-positive throughout
- B. treat 21.24 % as the point at which the investment case fails, not as negotiating room — a 15 % concession leaves 6.24 points of revenue headroom against every other adverse assumption combined, and on the reduced tariff the project breaks even at a cost of capital of 9.28 %, so barely 1.3 points of rate movement would exhaust what remains ✓ CORRECT
- C. refuse any reduction, since the base case is the only defensible position
- D. concede 15 % and re-run the model to show a positive NPV afterwards

Rationale: Breakeven headroom is a buffer against all remaining uncertainty, not a budget to spend on one counterparty; consuming three-quarters of it in a negotiation leaves the project exposed to the correlated rate movement the table already prices (4.3.3). A spends the entire buffer. C mistakes a forecast for a position. D is B's arithmetic with the judgement removed — the model will indeed show a positive NPV, which is precisely why the number alone cannot settle it.

■ SELF-CHECK — KA 4.3

1. Why does incremental IRR always agree with NPV on a pairwise choice? — It tests whether the difference project clears the hurdle, which is exactly what the NPV difference measures.
2. When does PI packing fail as a rationing rule? — Lumpy projects and multi-period budget constraints; then it's an optimisation, not a sort.

3. Name three things a positive NPV cannot tell the board. — Exposure duration; sensitivity concentration; the value of flexibility and strategic position outside the modelled flows.
4. Both NPVs at a computed crossover rate come to 2,500,000 exactly. Coincidence? — No: the crossover falls out of one factor value ($AF = 3.75$), so both NPVs are determined by it. Unequal NPVs at a reported crossover are proof of an error.
5. State Kestrel's revenue headroom and what it is for. — 21.24 % (breakeven inflow 7,009,773); it is the buffer against every remaining adverse assumption, not room to concede in one negotiation.
6. Greedy PI selects W, V, Z for +4,580,000 on an 18,000,000 spend. What two facts must the board be shown? — The 2,000,000 unspent, and the runner-up set (W + X, +5,400,000) — together they disclose the 820,000 the packing costs.

— Advanced topics — Domain 4

4.A.1 Reading NPV profiles like a professional

The profile (Fig 4.1.1) compresses the whole appraisal into one curve: its height at 0 % is the undiscounted surplus; its slope measures duration-sensitivity (long-dated flows steepen it); its zero-crossing is the IRR; and the distance between the hurdle and the crossing is the margin for rate error. Two profiles per decision (Fig 4.3.1) add the crossover — the complete geometry of a mutually exclusive choice. A reviewer who asks for the profile instead of the point estimate has converted an argument about numbers into an inspection of shape.

4.A.2 Inflation-consistent appraisal

The Fisher discipline of Domain 3 (KA 3.3.1) binds hardest here: nominal flows with the nominal rate, or real flows with the real rate — and the same world for every line, including the terminal value. The classic appraisal defect is a nominal hurdle (board-set, inflation-inclusive) discounting real flows (an engineer's "today's money" forecast): NPV is systematically understated and good projects die politely. The assumption register names the world; the reviewer checks one line item end to end.

4.A.3 Where the 8 % comes from — reconciling the hurdle to the structure

Every worked example in this domain has taken the board's 8.0 % as given. That is legitimate pedagogy and indefensible practice: a rate assumed is a conclusion assumed, and this domain's own sensitivity table shows a single point of rate moving Kestrel's NPV by roughly four and a half million. The rate must be **derived from the structure that will actually be signed**, and the derivation belongs to Domain 9. Closing that loop here is what turns four chapters into a book.

What Domain 9 derives. At the proposed structure — 70 % senior gearing, 42,000,000 of debt at 6.0 % over 12 years, an after-tax cost of debt of 4.80 % and a re-levered cost of equity of 15.42 % — the weighted average cost of capital is $WACC = 0.70 \times 4.80 + 0.30 \times 15.42 = 7.9860\%$ (Domain 9, KA 9.1.4). Domain 9 also reports the WACC at the **coverage-binding** gearing, the most debt the lenders' cover test will actually carry, at **8.0001 %**.

What the difference is worth. Recomputing the master appraisal at each rate:

Rate	Source	AF(r , 15)	NPV (USD)
7.9860 %	Domain 9 WACC at the proposed 70/30 structure	8.56680051	+16,244,525
8.0000 %	the board's stated appraisal hurdle	8.55947869	+16,179,360
8.0001 %	Domain 9 WACC at the coverage-binding gearing	8.55942642	+16,178,895

The board's round 8 % sits **1.40 basis points above** the structure's true cost of capital and so understates value by **USD 65,164** — about **46,546 per basis point**. Three things follow, in ascending order of importance.

First, the direction is conservative, and that is not an accident to be corrected quietly: rounding a hurdle up biases against investment, which is a defensible policy so long as it is a stated policy rather than an artefact of preferring round numbers. Second, the magnitude licenses the simplification. Sixty-five thousand on a sixteen-million NPV is 0.40 % — immaterial to this decision, and a domain that reported the appraisal to four decimal places while the forecast carries a 21 % breakeven band would be practising false precision. **State the rounding, quantify it once, and then use the round number.** Third — and this is the finding worth carrying — the two Domain 9 rates are **1.40 basis points apart from the board rate in opposite directions**, and the gap between the proposed structure and the coverage-binding one is only 1.41 basis points of WACC. The appraisal is therefore insensitive to the financing structure, while the sponsors' return is not: across the same gearing range Domain 9 shows equity IRR moving 184.61 basis points. That asymmetry is the professional point. **Gearing barely changes what the project is worth; it changes who gets it.** A director who reads only the project NPV will see nothing happen as the structure is negotiated, and will therefore not be in the room where the value moves.

The category error this reconciliation protects against. Because 7.9860 % is a project rate, it discounts project free cash flow (KA 4.1.1). Apply it to equity cash flow — after debt service — and it overstates equity value grossly. Run the mistake in reverse, discounting the project's 8,900,000 at the 15.42 % cost of equity, and $AF(0.1542, 15) = 5.730514$ gives an NPV of **−8,998,423**: a viable project rejected by **25,177,784** of pure category error. Neither number is a rounding issue; both are the same failure to keep the numerator and the denominator in the same world. The reviewer's test is one line long: whose cash flow is this, and whose rate is that?

4.A.4 Staged investment, and what the option to abandon is actually worth

KA 4.3.3 says static NPV cannot see option value. That is true and, left there, useless — it reads as licence to approve anything by asserting an option. The arithmetic below prices one, and the result is not the one most sponsors expect.

The situation. Kestrel's 8,900,000 forecast is an expectation over two states of the world: a strong offtake case at **10,400,000** with probability **0.6**, and a weak case at **6,650,000** with probability **0.4**. (Check the mean: $0.6 \times 10,400,000 + 0.4 \times 6,650,000 = 8,900,000$ — the master thread's figure, exactly.) A one-year pilot would resolve which state obtains before the 60,000,000 is committed.

Build now. NPV = +16,179,360, as computed throughout. Because NPV is linear in the annual inflow, this is identical to the probability-weighted NPV of the two states: $0.6 \times 29,018,578 + 0.4 \times (-3,079,467) = 16,179,360$. The strong state is worth +29,018,578; the weak state **destroys 3,079,467**.

Stage instead. Pay for the pilot, wait a year, learn, then build only in the strong state. Expected value at $t = 1$ is $0.6 \times 29,018,578 = 17,411,147$; discounted one year at 8 %, that is **16,121,432** at $t = 0$, before the pilot's cost.

The result that matters. Even with a **free** pilot, staging is worth **57,928 less** than building now. The option to abandon is genuinely valuable — it avoids $0.4 \times 3,079,467 = 1,231,787$ of expected loss — but a year's delay costs slightly more than that, because deferring a 16.18-million NPV by a year at 8 % forgoes about 1.20 million. Net of a pilot cost of any size, staging loses. **The breakeven pilot cost here is negative**, which is the arithmetic's way of saying the option is not worth having on these numbers.

What changes the answer — and it is not the mean. Hold the expectation at exactly 8,900,000 and widen the spread: a 50/50 split between **12,000,000** and **5,800,000**. Build-now NPV is unchanged at +16,179,360, because the mean is unchanged. But the weak state now destroys **10,355,024**, so the abandonment option avoids $0.5 \times 10,355,024 = 5,177,512$ of expected loss, and staging is worth $0.5 \times 42,713,744 / 1.08 = 19,774,882$ — a gain over building now of **3,595,521**, which is the most a rational sponsor would pay for the pilot.

Same expected inflow (8,900,000) · same build-now NPV · opposite conclusions

Narrow spread p = 0.6 / 0.4		Wide spread p = 0.5 / 0.5	
strong state · inflow 10,400,000 NPV +29,018,578		strong state · inflow 12,000,000 NPV +42,713,744	
weak state · inflow 6,650,000 NPV -3,079,467		weak state · inflow 5,800,000 NPV -10,355,024	
Build now	+16,179,360	Build now	+16,179,360
Stage (free pilot)	+16,121,432	Stage (free pilot)	+19,774,882
abandonment option avoids	+1,231,787	abandonment option avoids	+5,177,512
staging is worth -57,928		staging is worth +3,595,521	

Fig 4.4.1 — What flexibility is worth: the same mean, two spreads

The three rules this arithmetic supports. One: the value of waiting is driven by the **spread** of outcomes, not their mean — an identical expected case can make staging worthless or worth 3.6 million. Two: delay is never free, and its cost is roughly $r \times \text{NPV}$ per year of deferral, so staging pays only where the downside it avoids is larger than the value it postpones. Three: the option must be real. A pilot that cannot actually stop the project — because the land is bought, the turbines are ordered, or the political commitment is made — avoids nothing, and its value is zero however elaborately it is modelled. This is where "option value" most often becomes the rationalisation that 4.3.3 warns about: the test is not whether flexibility exists in the model but whether the organisation would genuinely walk away, and who has the authority to make it do so (Domain 5's stage gates, and the governance question behind them).

4.A.5 The reviewer's appraisal eye

The invariants: NPV at 0 % equals the raw flow sum; NPV at the IRR equals zero (substitute it back — the cheapest IRR audit that exists); MIRR lies between the reinvestment rate and the IRR; $PI > 1 \Leftrightarrow NPV > 0$ at the same rate; $EAV \times AF(r, n)$ reproduces the NPV; incremental IRR above the hurdle $\Leftrightarrow$ the bigger project's NPV is higher. Any violated line is a defect somewhere — the appraisal analogue of Domain 3's factor-table checks, and wired into this programme's golden-answer harness.

The fuller list, in the order a reviewer should run it:

- **No financing flow in the numerator** when a project rate is in the denominator, and no project rate on an equity stream (4.A.3 prices the error at 25,177,784 for Kestrel).
- **Sunk costs absent**; the decision flows are the avoidable ones only.
- **NPV at 0 % equals the arithmetic sum** of the flows. One subtraction, and it catches a surprising share of sign and offset errors.
- **NPV at the retained (unrounded) IRR is zero**. Against a two-decimal published rate expect a small residual — for Kestrel +6,751 at 12.19 % — and know it for a rounding artefact, not a defect.
- **PI at the IRR equals 1.000000**, which audits the IRR a second way without re-solving it.
- **Capital recovery plus EAV reconstructs the annual inflow**: $I_0/AF + NPV/AF = A$ ($7,009,773 + 1,890,227 = 8,900,000$).
- **$EAV \times AF(r, H)$ reproduces the replacement-chain PV** over any horizon H ($2,740,168 \times 8.559479 = 23,454,406$).
- **Both NPVs are equal at a reported crossover rate** — exactly, since one factor value determines both (2,500,000 each for P and Q at 10.424845 %).
- **Sign changes counted**; more than one and no single IRR may be quoted.
- **One discounting convention throughout**, stated; a mid-period model reports exactly $(1 + r)^{0.5}$ more present value than its year-end self (3.92 % at 8 %) — a different ratio means the convention was applied to some lines only.
- **The rate reconciles to a structure**, with the gap to the derived WACC quantified rather than assumed away (1.40 bp and 65,164 here).
- **Rationing packs disclose the unspent budget and the runner-up set**. Neither is optional: the greedy heuristic's 820,000 shortfall is invisible without them.
- **Every probability-weighted appraisal reconciles to its own expected case**: the weighted NPV of the states equals the NPV of the mean forecast, because NPV is linear in the flows. A discrepancy means the states were built inconsistently.

— Industry variations — Domain 4

- **Regulated utilities and availability PPPs**. Contracted revenue narrows the forecast range, so appraisal battles concentrate on the rate (and the regulator's allowed return); NPV margins are thin and Fisher errors (4.A.2) are decision-changing.
- **Merchant power and commodities**. The forecast is the battlefield: point NPVs are close to meaningless without the scenario set (Domain 7's stress tests), and payback recovers status as a survival measure — how long must prices hold?

- **Oil, gas and mining.** Decommissioning liabilities put the sign-change pathology (4.1.2) on almost every appraisal: MIRR and NPV are standing practice, "the IRR" is treated with suspicion by convention.
- **Technology and corporate transformation.** Option value (4.3.3) dominates: staged investments are the norm, and static NPV is a floor, not an answer. Rationing is annual and lumpy — the optimisation caveat of 4.3.2 is the daily reality.
- **Public-sector appraisal.** Where a government publishes appraisal guidance, the discount rate is a matter of policy rather than of estimation — typically a centrally set social time preference or social discount rate — distributional effects sit beside NPV, and the method is prescribed rather than chosen. The rate, its basis and the required sensitivities differ by jurisdiction and are revised over time, so the applicable guidance is read at the date of the appraisal rather than assumed; what generalises is only the shape, that the numbers travel with a governance file, which is the direction this domain pushes every sector.
- **Real estate and social infrastructure.** Terminal value dominates: a large share of NPV can sit in a single residual figure at the horizon, so the appraisal's centre of gravity moves from the cash-flow years to the exit assumption, and the sensitivity that matters is on that one line. Payback is close to meaningless where the return is a capital event rather than a stream.
- **Renewables with contracted offtake, then merchant exposure.** The profile splits: contracted cash for the tariff term, market cash afterwards. Appraising the two segments at one rate is the standing error, since their risk is not the same — the disciplined treatment discounts each on its own basis and discloses the split, which is a Domain 9 conversation this domain must set up correctly rather than average away.

A cross-sector caution on tax. Every figure in this domain is pre-tax at the project level, and where tax appears in an appraisal its treatment is jurisdiction-specific — the availability and timing of capital allowances or depreciation deductions, the deductibility of interest and any limitation on it, loss carry-forward rules, and withholding on distributions all vary by country and change over time. This domain therefore states the arithmetic and refuses to state the treatment: what belongs in the appraisal is the after-tax operating cash flow **computed on written advice for the specific jurisdiction and structure**, with the advice referenced in the assumption register. Where a comparison spans jurisdictions, the correct disclosure is one set of flows per tax regime, not a blended rate that describes none of them. Presenting one country's treatment as though it were general is the most common way an otherwise sound appraisal becomes indefensible.

— Case study — Domain 4: the intake decision, taken properly (water / desalination)

Situation. Kestrel's board must (1) confirm the plant investment, (2) choose between intake designs P and Q, and (3) allocate the sponsor group's residual USD 20m development budget across four unrelated feeder projects (W–Z of KA 4.3.2). One meeting, three different appraisal questions.

The decisions. Build: NPV +16.18m at 8 %, IRR 12.19 %, MIRR 9.73 %, discounted payback 10.07 years — build, with the exposure noted and the two dominating assumptions (tariff escalation, availability) sensitivity-tested per KA 4.3.3. Intake: Q over P — +970,840 more NPV, incremental IRR 10.42 % over the extra 15m; the 28.65 % on P is recorded as the intensity it is, not the ranking it isn't. Budget: W + X for +5.40m, with the un-funded 1.17-PI project Z referred to Domain 9's financing question rather than silently killed.

What the domain teaches here. Three questions, three measures, one hierarchy: NPV decided all three calls; IRR, MIRR, PI and payback each explained a facet the board needed narrated. The minute records rates, worlds (nominal), sensitivity owners and the option-value judgments — the appraisal file is the governance file.

How the meeting actually went, and the two things that nearly went wrong. The build paper arrived showing a level 8,900,000 profile. The finance director's first question was the one KA 4.1.1b exists to prompt — on what profile? — and the restatement on the engineers' ramp took the NPV to **+13,699,840**, still comfortably positive but 2,479,520 lower, and moved discounted payback from 10.07 to **10.91 years**, past the nine-year screening rule the board had been applying without having voted on it. That is the first near-miss: on the level profile the rule was never triggered and would never have been examined. It was examined here, and the board resolved to treat exposure duration as a disclosed characteristic rather than a veto — a decision minuted with the 16.18-million value at stake attached to it, exactly as MCQ 4.2-H frames the choice.

The second near-miss came from the intake comparison. The paper's recommendation was P, on a 28.65 % IRR against Q's 15.24 %, and it took the incremental test to reverse it: 15,000,000 more capital earning **10.4248 %** against an 8 % cost, worth **970,840** more in value. What made the reversal stick rather than becoming a contest of percentages was the crossover figure and its distance from the hurdle — **2.42 points**. The director could say, in one sentence, that the rate would have to be wrong by more than two and a half points to change the answer. A ranking defended that way survives the meeting; a ranking defended by "NPV is the better measure" does not.

The rate was the last item, not the first. The board's 8.0 % was carried into the paper as a standing assumption. The reconciliation of KA 4.A.3 was tabled alongside it: Domain 9's derived WACC at the proposed structure is **7.9860 %**, so the hurdle is 1.40 basis points conservative and understates value by **65,164** — immaterial, and now on the record as immaterial rather than unexamined. The same table carried the finding that mattered more: the WACC at the coverage-binding gearing is 8.0001 %, so **the project's value is almost indifferent to the financing structure while the sponsors' return moves by 184.61 basis points across it**. The board's conclusion was procedural and correct — the gearing negotiation is a shareholder-return question, and it belongs on the agenda as one, not buried in an appraisal input.

— Case study B — Domain 4: the fund that bought percentages (infrastructure fund)

Situation. An infrastructure fund with a 9 % cost of capital repeatedly preferred short-tenor, high-IRR deals — the P-shape — over long-tenor concessions at 13–15 % IRR. Five years on, its realised portfolio return trailed its own reported deal IRRs by nearly four points.

What happened. The gap was the reinvestment fiction industrialised: each 25–30 % IRR assumed its distributions would earn the same, but the fund redeployed at market rates — when it could redeploy at all. MIRR at honest reinvestment rates (the 4.1.3 arithmetic) had flagged the true economics of every deal; it was computed, and filed. The long concessions it passed over went to competitors who now hold them, on a comparison the fund never actually made.

The four points, computed. The wedge is not an impression; it falls out of the fund's own records in three lines. The representative deal committed **10,000,000** and returned **20,000,000** three years later — a doubling, so its IRR is $2^{(1/3)} - 1 = 25.9921 \%$, and that rate is achieved only if the money is recommitted on the day it comes back. It was not. The fund's average interval between realisation and recommitment ran about **six months**, held in cash at **2.0 %**, which makes each recycling cycle 3.5 years long and multiplies capital by $2 \times 1.02^{0.5} = 2.019901$ per cycle. The realised compound

return is therefore $2.019901^{(1/3.5)} - 1 = 22.2467\%$ — a wedge of **374.54 basis points**, which is the "nearly four points" the investors eventually measured and the fund could not explain. In the two years when origination slowed and the interval ran nearer twelve months, the cycle multiple was $2 \times 1.02 = 2.040000$ over four years and the realised rate fell to **19.5109 %**, a wedge of **648.12 basis points**. Nothing was misstated at any point: every deal returned exactly what was reported, and the entire wedge lived in the interval between deals, which appears in no deal's IRR because no deal's IRR contains it.

The comparison the fund thought it was making. A representative declined concession committed the same **10,000,000** against **1,800,000 a year for twelve years** — $AF(r, 12) = 5.555556$, so an IRR of **14.4284 %**, and an NPV at the fund's 9 % cost of capital of **+2,889,305**. Set the three figures side by side and the fund's strategic argument changes shape:

	Believed	Actual at a six-month gap	Actual at a twelve-month gap
Short-deal book	25.9921 %	22.2467 %	19.5109 %
Declined concession	14.4284 %	14.4284 %	14.4284 %
Advantage claimed	1,156.38 bp	781.84 bp	508.26 bp

The honest conclusion is narrower than the one a reader expects, and stating it that way is the point. **The short-deal strategy was still the better one** — it compounded faster than the concession at every redeployment gap the fund actually ran, and it bought liquidity and optionality besides. What the fund got wrong was not the choice but the **margin**, and therefore its own confidence: it declined 14.4284 % believing it held an eleven-and-a-half-point advantage when it held under eight, and in the slow years barely five. And there is a threshold at which the argument inverts altogether. Solving $[2 \times 1.02^g]^{(1/(3 + g))} - 1 = 14.4284\%$ gives a **breakeven redeployment gap of 2.5119 years**: at that average interval the recycled short-deal book earns precisely what the concession it refused would have earned. The fund never approached that gap — but it had no instrument that would have told it if it had, because the gap was measured by nobody and appeared in no report. That is the difference between being right and knowing you are right, and only one of the two survives a bad year.

The variable this makes visible. Between a six-month and a twelve-month gap the fund's realised return moves **273.58 basis points**, or roughly **46 basis points of fund return per month** of average idle capital. No deal-level metric contains that number, and it is larger than any plausible improvement in deal selection. **Origination capacity, not screening skill, was the fund's highest-return investment**, and the arithmetic that says so is three lines long and was available from the first realisation.

What the domain teaches here. A portfolio of intensities is not a portfolio of value. IRR's flattery compounds at fund level because short deals recycle the fiction; NPV and MIRR discipline is not academic tidiness — over a fund's life it is the difference between the return promised and the return delivered.

Why it was rational for everyone involved. The uncomfortable part of this case is that no one behaved dishonestly. The investment committee's mandate was expressed as a target IRR, its incentive compensation was measured against realised deal IRRs, and its quarterly reporting to investors ranked deals by the same measure. Each of those is a defensible instrument in isolation; together they made the reinvestment fiction the fund's operating assumption, and MIRR — computed, filed, never tabled — was the only document in the building that disagreed. The lesson is therefore not about a measure but about a **measurement system**: where the mandate, the incentive and the report all speak in percentages, no amount of NPV literacy in the analyst pool will change

the decisions, because the analysts are not the ones deciding. Changing the outcome required changing the mandate.

The case is an original illustration and no view is expressed on any real fund. Note also that how fund performance may be measured, presented and marketed to investors — and how carried interest is calculated against it — is regulated in most jurisdictions and governed by the fund's own constitutional documents. The appraisal point here is arithmetical; changing a mandate, an incentive formula or an investor report is a matter for the fund's counsel and its regulator, not for a measurement argument alone.

What a corrected pack looks like. The remedy the fund eventually adopted is worth stating because it is cheap and general. Every deal paper now carries four figures beside the IRR: **NPV at the fund's cost of capital in money**, so scale is visible; **MIRR at the treasury's actual reinvestment rate**, so the fiction is priced; the **tenor**, so nothing is compared across horizons without EAV; and the **redployment assumption for distributions**, named and owned. The single most effective of the four was the third. Once tenor sat in the same row as the percentage, the committee stopped comparing a three-year 28 % with a fifteen-year 13 % as though the comparison meant something — which is the error 4.1.2's pitfall names, and the one that had quietly cost the fund four points of realised return.

— Executive perspective — Domain 4

What a project finance director cannot delegate in this domain:

- **The hurdle.** As in Domain 3: whoever sets r sets the answer. The director owns the rate, its world (nominal or real), and the standing sensitivity band around it.
- **The measure hierarchy.** NPV decides; rates and ratios explain. The director enforces this in every paper — and personally reads the profile, not the point.
- **The exclusivity discipline.** Incremental thinking (Q–P) is the director's question in the room: "what does the extra money earn?" beats "which percentage is bigger?" every time.
- **The honesty of rejections.** Under rationing, what was not funded and why is board information; a rejected 1.17-PI project is a financing gap wearing a screening verdict.
- **The unpriced.** Option value, strategic position, forecast asymmetry — the director's overrides are legitimate exactly when they are explicit, minuted and owned (4.3.3).
- **The profile.** Every screening NPV built on a level annuity is an upper bound. The director asks on what profile? before asking anything else, because the ramp is worth 2.48 million on this project and is invisible in the formula that produced the headline.
- **The category question.** Whose cash flow, and whose rate? One sentence, asked of every paper. It is the cheapest control in the domain and the failure it prevents is the largest — 25.2 million here.
- **The measurement system, not the measure.** Case study B's fund lost four points of realised return with competent analysts, because its mandate, its incentives and its investor reporting all spoke in percentages. A director who fixes the appraisal template and leaves the mandate alone has fixed nothing.
- **Screening rules as decisions.** A payback or PI threshold that vetoes a positive-NPV project is a policy choice about exposure, and the director's job is to put it to the board with the foregone value attached — not to let a threshold decide silently and call the result prudence.

- **Reconciliation, not assumption.** The hurdle is reconciled to the structure that will be signed (Toolkit 4.T.4) before the paper circulates. Where the gap is immaterial, saying so on the record is itself the deliverable; an unexamined rate is a conclusion nobody owns.

— Calculation exercises — Domain 4

Exercise 4.1 $I_0 = 12,000,000$; net flows 3,000,000 · 4,000,000 · 5,000,000 · 5,000,000 in years 1–4; $r = 10\%$. Compute the NPV. Solution. $PV = 3/1.10 + 4/1.10^2 + 5/1.10^3 + 5/1.10^4$ (millions) = 2,727,273 + 3,305,785 + 3,756,574 + 3,415,067 = 13,204,699; **NPV = +1,204,699**. Common error: discounting year 1 at $t = 0$ (no discount) shifts every factor one period and overstates NPV by $\approx 1.19m$.

Exercise 4.2 $I_0 = 9,000,000$; level inflow 1,500,000 for 10 years. Find the IRR. Solution. $AF(r, 10) = 9/1.5 = 6.0$; solving gives **IRR = 10.56 %** ($AF(10\%) = 6.145$, $AF(11\%) = 5.889$ bracket it). Common error: reading the payback reciprocal ($1.5/9 = 16.7\%$) as the IRR — that shortcut holds only for perpetuities.

Exercise 4.3 $I_0 = 10,000,000$; inflows 2,600,000 for 6 years; reinvestment and finance rate 7%. Compute MIRR. Solution. $FVAF(0.07, 6) = 7.153291$; $TV = 18,598,556$; **MIRR = $(1.859856)^{(1/6)} - 1 = 10.90\%$** . Common error: compounding the inflows for 6 periods each (rather than to a common terminal date) inflates TV and the rate.

Exercise 4.4 Machine C1: 3,000,000 capex, 4-year life, 250,000/yr opex. Machine C2: 4,200,000, 6-year life, 150,000/yr. Same duty; $r = 9\%$. Choose. Solution. C1: $PV = 3,000,000 + 250,000 \times 3.239720 = 3,809,930$; **EAV = 1,176,006**. C2: $PV = 4,200,000 + 150,000 \times 4.485919 = 4,872,888$; **EAV = 1,086,263**. **Choose C2** — cheaper by 89,743 per year. Common error: comparing PVs across unequal lives (which picks C1).

Exercise 4.5 Budget 25,000,000. Projects (I_0 ; NPV): A (10; 2.60) · B (15; 3.30) · C (8; 1.84) · D (7; 1.40). Fund the best set. Solution. PIs: A 1.260 · C 1.230 · B 1.220 · D 1.200. **Greedy PI packing fails here:** A + C + D fits (25) for +5.84m, but **A + B (25 exactly) yields +5.90m**. With lumpy projects the rule is: use PI to shortlist, then enumerate feasible sets (or optimise). This is the 4.3.2 caveat as arithmetic.

Exercise 4.6 $I_0 = 18,000,000$ today; nothing in years 1–2 while the asset is built; then 3,600,000 per year for years 3–12; $r = 9\%$. Compute the NPV. Solution. Deferred annuity: $AF(0.09, 12) - AF(0.09, 2) = 7.160725 - 1.759111 = 5.401614$; $PV = 3,600,000 \times 5.401614 = 19,445,811$; **NPV = +1,445,811**. Common error: using $AF(0.09, 10) = 6.417658$ for "ten years of cash" without deferring it — that treats the stream as starting in year 1 and gives +5,103,568, overstating NPV by 3,657,757. The count of payments is right and their position is wrong, which is why the deferred form subtracts the factor for the years you do not receive rather than counting the years you do.

Exercise 4.7 A model reports a present value of 41,250,000 on year-end discounting at 7%. Restate it on the mid-period convention. Solution. Multiply by $(1.07)^{0.5} = 1.0344080$: **PV = 42,669,332**, an uplift of **1,419,332** (3.44 %). Common error: multiplying by $1 + r/2 = 1.035$, which is a linear approximation to a compound adjustment; it happens to be close here

(42,693,750, out by 24,418) and drifts as the rate rises. The exact multiplier is the square root of the annual factor, at every rate.

Exercise 4.8 $I_0 = 25,000,000$ at $t = 0$ and a further 4,000,000 outflow at the end of year 5; inflows 5,200,000 per year for 12 years. Finance rate 6.5 %, reinvestment rate 3.5 %. Compute MIRR. Solution. $PV(\text{outflows}) = 25,000,000 + 4,000,000 \times 0.729881 = 27,919,523$; $FVAF(0.035, 12) = 14.601962$, so $TV = 5,200,000 \times 14.601962 = 75,930,201$; $MIRR = (75,930,201 / 27,919,523)^{(1/12)} - 1 = 2.719609^{(1/12)} - 1 = \mathbf{8.6948 \%}$. Common error: using one rate for both roles — at 6.5 % throughout the answer becomes 10.2790 %, overstating by 158 basis points, and the overstatement is exactly the reinvestment assumption MIRR was chosen to remove.

Exercise 4.9 $I_0 = 32,000,000$; level inflow 4,400,000 for 20 years; $r = 7.5 \%$. Compute the NPV, the EAV, the capital-recovery annuity and the revenue headroom, and show they reconcile. Solution. $AF(0.075, 20) = 10.194491$; $NPV = 4,400,000 \times 10.194491 - 32,000,000 = \mathbf{+12,855,762}$; $EAV = 12,855,762 / 10.194491 = \mathbf{1,261,050}$; capital recovery = $32,000,000 / 10.194491 = \mathbf{3,138,950}$. Reconciliation: $3,138,950 + 1,261,050 = 4,400,000$, the inflow itself — so **28.66 % of each year's cash is value** and the breakeven inflow is 3,138,950, i.e. **28.66 % below base**. Common error: computing headroom off the NPV (12,855,762 / 60,000,000-style ratios) rather than off the annuity; the two answer different questions and only the annuity form is the revenue breakeven.

Exercise 4.10 Two exclusive designs, both 6-year lives, $r = 8 \%$: **S** (I_0 7,000,000, inflow 2,100,000) and **T** (I_0 16,000,000, inflow 4,300,000). Rank them, find the crossover, and verify it. Solution. $AF(0.08, 6) = 4.622880$. **S**: $NPV \mathbf{+2,708,047}$, $IRR \mathbf{19.9054 \%}$. **T**: $NPV \mathbf{+3,878,383}$, $IRR \mathbf{15.6321 \%}$. IRR prefers **S**; NPV prefers **T** by 1,170,335. Incremental project **T–S** is $(-9,000,000; +2,200,000 \times 6)$, so $AF = 9,000,000 / 2,200,000 = 4.090909$ and the **crossover is 12.1767 %** — above the 8 % hurdle, so **T** stands. Verification: at 12.1767 % both $NPVs$ are **1,590,909**, identical. Common error: stopping at the NPV ranking without the crossover. The hurdle here is 4.18 points below indifference, which is the sentence that defends the decision; without it the recommendation is an assertion about which measure to prefer.

Exercise 4.11 $I_0 = 30,000,000$; $r = 10 \%$; 15-year inflows either 5,400,000 (probability 0.55) or 3,200,000 (0.45). A one-year study would resolve which. What is the most the study can be worth? Solution. $AF(0.10, 15) = 7.606080$. Expected inflow = $0.55 \times 5,400,000 + 0.45 \times 3,200,000 = 4,410,000$, so build-now $NPV = \mathbf{+3,542,811}$. State $NPVs$: good **+11,072,829**, bad **-5,660,546**; the weighted average is $0.55 \times 11,072,829 + 0.45 \times (-5,660,546) = 3,542,811$, confirming linearity. Staging builds only in the good state: $0.55 \times 11,072,829 / 1.10 = \mathbf{5,536,415}$, so the **maximum study cost is 1,993,604**. Common error: valuing the option as the avoided loss alone ($0.45 \times 5,660,546 = 2,547,246$) and paying up to that — it ignores the delay cost of postponing a positive- NPV project by a year, which is the 553,641 difference between the two figures.

— Practitioner's toolkit — Domain 4

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 4.T.1 — The appraisal one-pager (per decision)

Decision question (accept/reject · exclusive choice · rationing) · cash-flow source and world (nominal/real, per 3.T.1) · rate and its owner · **NPV at the owned rate** · profile sketch or IRR/MIRR · discounted payback · PI (if rationing) · EAV (if unequal lives) · two-way sensitivity on the dominating assumptions · unpriced factors, stated · recommendation and the named accountable approver.

Toolkit 4.T.2 — IRR pathology checklist

- [] Sign changes counted; more than one → MIRR + NPV only, "the IRR" banned from the paper.
- [] Scale stated beside every percentage (I_0 and NPV in money).
- [] Tenors aligned before any cross-project rate comparison (else EAV).
- [] Reinvestment assumption named; MIRR computed when $IRR > \text{hurdle} + 5$ points.
- [] IRR substituted back: $NPV(IRR)$ recomputes to zero.
- [] Incremental IRR computed for every exclusive pair; agrees with NPV ranking.

Toolkit 4.T.3 — Rationing worksheet

Columns: project · I_0 · NPV · PI · strategic notes/dependencies. Steps: rank by PI → shortlist to $\sim 2 \times$ budget → enumerate feasible sets (lumpy) → record funded set, rejected set with reasons, and the financing referral for high-PI rejects (Domain 9). Two mandatory disclosure lines at the foot of the table: **budget unspent** and **runner-up set with its NPV** — without them a greedy result is indistinguishable from an optimum (WE 4.3.2's 820,000).

Toolkit 4.T.4 — Hurdle-rate reconciliation sheet

One page, completed before the appraisal is circulated rather than after it is challenged.

Line	Entry	Kestrel worked
Rate used in the appraisal	as stated in the paper	8.0000 %
Derived WACC at the proposed structure	from the funding model (Domain 9)	7.9860 %
Derived WACC at the coverage-binding structure	the most debt the cover test carries	8.0001 %
Gap, in basis points	used – derived	+1.40 bp
Gap, in NPV	recompute; do not estimate	65,164 (0.40 % of NPV)
Direction	conservative or optimistic, stated	conservative
Materiality conclusion	with the threshold that decided it	immaterial
Whose cash flow is discounted	project free cash flow, or equity after debt service	project
Matching rate for that stream	WACC for project flow, k_e for equity flow	WACC
Discounting convention	year-end or mid-period, applied to every line	year-end
Rate owner	named individual, not a committee	finance director

The ninth and tenth lines are the ones that catch career-shortening errors: a project rate on an equity stream is worth 25,177,784 of misstatement on this project alone (KA 4.A.3), and a convention applied inconsistently is worth 3.9 % of present value at 8 %.

— Exam preparation — Domain 4

The calculation traps. Forgetting to deduct I_0 (MCQ 4.1-A distractor D) · discounting from $t = 0$ (Exercise 4.1) · payback reciprocal as IRR (Exercise 4.2) · ranking exclusives by IRR (4.3.1) · greedy PI with lumpy budgets (Exercise 4.5) · comparing PVs across unequal lives (Exercise 4.4) · quoting one IRR for sign-changing flows (4.1.2) · MIRR terminal value mis-compounded (Exercise 4.3) · nominal/real mixing imported from Domain 3 · counting the years you receive rather than deferring by the years you do not (Exercise 4.6) · the linear $1 + r/2$ in place of $(1 + r)^{0.5}$ for mid-period (Exercise 4.7) · one rate doing both MIRR jobs (Exercise 4.8) · headroom computed off NPV instead of the annuity (Exercise 4.9) · valuing an abandonment option at the avoided loss and forgetting the delay cost (Exercise 4.11).

The judgement traps — the ones that cost more than arithmetic. Reading MIRR against the hurdle as though it were an IRR (MCQ 4.1-G) · comparing NPVs modelled on different discounting conventions (MCQ 4.1-H) · mixing gross and net PI in one table (MCQ 4.2-E) · treating the exact agreement of two methods as evidence that their shared assumption holds (MCQ 4.2-G) · letting a screening threshold veto value without putting the threshold to the board (MCQ 4.2-H) · presenting a greedy packing as an optimum (MCQ 4.3-G) · spending breakeven headroom in a negotiation as though it were margin rather than the buffer against everything else (MCQ 4.3-H) · discounting an equity stream at a project rate, or the reverse (4.A.3) · asserting an option that the organisation has no authority to exercise (4.A.4).

Fluency drills. Each should take under a minute with a factor table: $AF(0.08, 15) = 8.559479$ and therefore breakeven inflow on 60,000,000 is 7,009,773 · a mid-period model reports 3.92 % more PV than its year-end self at 8 % · PI at the IRR is 1.000000 · $I_0/AF + NPV/AF = A$ · a crossover falls out of one factor value, so both NPVs there are equal · a two-sign-change project has no quotable IRR · deferring a positive NPV by a year costs about $r \times NPV$.

Reflection questions.

1. Your board paper shows one number: "IRR 22 %". List the five questions this domain obliges you to ask before anyone votes. (Scale? Sign changes? Tenor? Reinvestment? NPV at our rate?)
2. When is a negative-NPV decision defensible — and what must the record contain? (4.3.3: explicit option/strategic value, owned and minuted.)
3. Which invariant of 4.A.5 would have caught the last appraisal error you saw? (Most often: $NPV(IRR) \neq 0$ on substitution, or $EAV \times AF \neq NPV$.)
4. Your organisation's appraisals all use a round hurdle rate nobody has reconciled to a funding structure. Draft the three lines of Toolkit 4.T.4 you would need to complete before the next paper, and say what you would do if the gap came back at fifty basis points rather than 1.40. (Recompute at the derived rate, disclose direction and magnitude, and at fifty basis points — worth roughly 2.3 million here — stop using the round number.)
5. A sponsor proposes a 3,000,000 pilot to "de-risk" a project whose land is already purchased and whose political commitment is public. What is the pilot worth, and why? (Nothing as an option: the organisation cannot walk away, so no downside is avoided. It may still be worth paying for as engineering de-risking — but that is a cost of the project, not option value, and must be presented as one.)

6. Two teams' appraisals of competing plants differ by 3.9 % of present value on identical rates. What do you check first, and what does it tell you about comparing the two recommendations? (The discounting convention — $(1.08)^{0.5} - 1$; until both are restated on one convention the comparison ranks the modellers rather than the plants.)

— Domain 4 summary

Appraisal turns Domain 3's machinery into decisions, under one hierarchy: **NPV decides; everything else explains.** NPV earns primacy by additivity, scale-awareness and the honest reinvestment assumption; IRR narrates a margin of safety but carries three standing pathologies — multiple roots, scale-blindness, the reinvestment fiction — of which MIRR repairs only the last; payback and its discounted form measure exposure, never value; PI ranks value per scarce dollar under rationing (with the lumpy-budget caveat proven in Exercise 4.5); EAV makes unequal lives commensurable. Mutually exclusive choices resolve by NPV, narrated by incremental IRR and the crossover geometry; rationing resolves by disciplined packing plus the financing question for what was turned away; and the limits of the numbers — options, strategy, forecast asymmetry — are stated in the open, as owned judgments.

Three findings from this domain's arithmetic outlast the formulae. **Timing is priced even when totals are not:** the ramp profile of 4.1.1b moves not one dollar of forecast revenue and costs 2,479,520 of value, which is why a level-annuity screening NPV is an upper bound and should be labelled as one. **Conventions and categories move more money than measures do:** the mid-period choice is worth 2,988,553 on this project and appears in no formula, and discounting project cash flow at the 15.42 % cost of equity instead of the 7.9860 % project rate would have destroyed a viable investment by 25,177,784 — neither is a modelling subtlety, and both are caught by one sentence asked of every paper. And **the hurdle must be reconciled, not assumed:** the board's round 8 % is 1.40 basis points and 65,164 away from the structure's derived cost of capital, which is immaterial here and is now on the record as immaterial rather than unexamined — while the same reconciliation surfaces the finding that matters more, that gearing barely changes what the project is worth and moves the sponsors' return by 184.61 basis points.

The reviewer's invariants of 4.A.5 make each of these testable rather than merely asserted, and every printed result above is independently recomputed in this programme's golden-answer harness. The Kestrel thread continues into Domain 5 (is the project bankable, not merely valuable?), Domain 6 (the model that industrialises every calculation this domain taught) and Domain 9, which derives the rate this domain has now stopped taking on trust.

02

PART TWO

Structuring and modelling

Domains 5–9 — development and bankability, financial modelling, revenue and demand, cost and contingency, and funding structure: how a project becomes financeable.



05

DOMAIN 5

Project Development and Bankability

— Why this domain exists

Domain 4 established that Kestrel Water SPC is **valuable** — NPV +USD 16,179,360 at 8 %, IRR 12.19 %, PI 1.270. It left open the question that decides whether the project happens: **is it financeable?** A valuable project with an unsigned offtake, an unregistered corridor, an unproven technology or an unfundable minority sponsor does not get built, and no positive NPV repairs any of those. Bankability is not a stronger form of value but a different test, and it is **conjunctive** — every condition must pass, because lenders lending against project cash alone have no balance sheet to fall back on and therefore no appetite for one unresolved fatal condition.

That structure is the domain's central claim, and it has three computable consequences. **The weakest condition governs the whole:** six conditions each around 90 % likely give a joint probability of close near 55 %, so effort on the strongest is nearly worthless while effort on the weakest is worth several times as much (KA 5.3). **Development spend is an option premium, not a project cost:** it buys the right to continue, is mostly spent on projects that never close, and must be judged across a portfolio and killed early (KA 5.1) — the finance twin of the gate economics PML-AI Domain 3 (KA 3.3.1) priced for delivery, differing only in what holding the gate costs. And **bankability is a set of contracts and dates, not an opinion:** the sponsor group and its vehicle (KA 5.2) and the construction and readiness package (KA 5.4) either deliver the conditions on the timetable or impose a cost this domain quantifies to the day.

Learning objectives. After this domain a candidate can: place development kill gates where irreversibility steps up; compute cost per closed project, close rate and breakeven close rate across a development portfolio; compute a feasibility gate's net value, breakeven detection probability and the bid-window risk at which it stops paying; explain what an SPV achieves and what its ring-fence does not; compute per-sponsor equity, several-liability support exposure and the dilution consequence of a funding default; value an equity bridge and show it is neutral at the bridge rate; compute a condition set's joint probability, the marginal gain from lifting each condition and the breakeven close probability; price a technology premium as lost debt capacity using Domain 10's sizing rule; compute the full cost of a slip in the commercial operations date and size a performance buy-down that restores lenders' coverage; and govern AI use across screening, document review and readiness assessment.

The master project, at its development stage. Kestrel Water SPC continues from Domains 1–4 and 10. Capital cost **USD 60,000,000**, funded **70/30** as **USD 42,000,000** of senior debt at **6.0 % over 12 years** (annual instalment **USD 5,009,635.23**; $AF(0.06, 12) = 8.383844$) plus **USD 18,000,000** of equity. Operating life **25 years**; documented first-year **CFADS USD 6,384,000** (6,984,000 before working-capital movements) on revenue of **12,000,000** and cash operating costs of **4,500,000**. Coverage at close (Domain 10): **DSCR 1.2743 = LLCR 1.2743, PLCR 1.9431**, covenant cash trigger **6,011,562**, annual headroom **372,438**. This domain adds three development facts earlier chapters did not need: the **portfolio** that produced Kestrel (40 screened opportunities, USD

14,800,000 of programme spend, two closes), the **sponsor group** behind the 18,000,000 (water operator 55 %, infrastructure fund 35 %, industrial partner 10 %, with a several 6,000,000 overrun support), and the **two-year construction window** whose commercial operations date the whole structure is priced against.

KNOWLEDGE AREA 5.1

Concept and feasibility

Topics: 5.1.1 the development lifecycle and where its gates belong · 5.1.2 development spend as an option premium · 5.1.3 the feasibility gate and the kill decision.

5.1.1 The development lifecycle and where its gates belong

Definition. Project development is the pre-financial-close work that converts an opportunity into a financeable transaction — identifying the payer, securing site and consents, selecting technology and contractors, negotiating the revenue contract, structuring the financing, satisfying every condition precedent. It runs through origination and screening, concept and prefeasibility, feasibility, transaction and bid, and close, with spend intensity rising by roughly an order of magnitude at each step while information improves only gradually. That asymmetry — **commitment rising faster than knowledge** — is the economics of the whole phase, and everything before close is spent at sponsors' risk with no financing to reimburse it.

Gates belong where **irreversibility steps up** — before feasibility spend, before bid submission, before signature — not on the calendar; the design rule and its failure mode (gates that have never stopped anything) are PML-AI Domain 3's, KA 3.3.1. What differs in finance is the price of holding the gate: in delivery it is elapsed time against a cost of delay, while in development it is a **forgone option** — a bid window that closes, a site optioned by a competitor, a procurement that runs without you. The budget must also separate **pursuit costs** (expensed, belonging to the programme), **study and adviser costs** (often capitalisable at close where the framework and the facility permit — Domain 2's rules, jurisdiction-sensitive) and **at-risk commitments** (option premiums, bid bonds, long-lead reservations: cash forfeited if the project dies), because without that split a kill decision cannot answer its only question — how much of this is already gone?

5.1.2 Development spend as an option premium


Definition. Each stage of development spend buys a **real option**: the right, not the obligation, to spend the next and larger tranche. It must therefore be evaluated as a **portfolio** — the closes pay for the abandonments — and the correct unit is the **cost per closed project across everything pursued**, not the cost of the deal that closed.

WORKED EXAMPLE**Worked example 5.1.2 — what did Kestrel's financing actually cost to originate?**

1. **Setup.** Kestrel's sponsor group runs a four-stage water and utilities funnel. In the year of Kestrel's origination it **screened 40** opportunities at USD 25,000 each; **12** advanced to concept at USD 250,000 each; **5** entered feasibility and bid at USD 1,200,000 each; **2** were carried to close at a further USD 2,400,000 each. Value per close is Domain 4's Kestrel **NPV, USD 16,179,360** (cited, not re-derived).
2. **Formula.** Stage spend = count × unit cost; programme spend = Σ stage spend; cost per close = programme spend ÷ closes; close rate = closes ÷ screened; breakeven closes = programme spend ÷ value per close.
3. **Substitution.** $40 \times 25,000 = 1,000,000$; $12 \times 250,000 = 3,000,000$; $5 \times 1,200,000 = 6,000,000$; $2 \times 2,400,000 = 4,800,000$; per close = $14,800,000/2$; breakeven = $14,800,000/16,179,360$.
4. **Result.** Programme spend **USD 14,800,000**; cost per closed project **USD 7,400,000**; close rate **5.0 %** (stage conversions 30.0 %, 41.67 %, 40.0 %); portfolio value **32,358,720**, net **+17,558,720**, value multiple **2.1864×**; **breakeven at 0.9147 closes — a breakeven close rate of 2.29 %**.
5. **Interpretation.** The honest cost of Kestrel's financing is **7,400,000, not the 2,400,000** on its own charge code, and the difference is the premium paid for having found it at all; a sponsor that measures only the winners under-prices development, under-resources screening and is annually surprised by the expense line. The **breakeven close rate of 2.29 % against an achieved 5.0 %** gives the programme **2.19×** of margin — it could halve its hit rate and still create value — which converts "development is expensive" into "development stops paying below one close in 44 screenings", the sentence a budget is actually defended with (the exact breakeven is one close in 43.73). And sensitivity runs through value per close and late-stage conversion, not screening cost: the 1,000,000 of screening is 6.8 % of programme spend and buys the whole funnel, while one lost late-stage project costs 2,400,000 outright — so the governance conclusion is counter-intuitive and consistent, **screen more widely and kill earlier**. The caution: value per close is a forecast (Domain 4, KA 4.3.3), so a programme justified on optimistic deal **NPVs** has hidden its true breakeven and must be re-tested against **realised** value.

Forty screened opportunities buy two financings — and the two must repay all forty

Stage spend is the premium paid for the option to continue; only the last stage is spent on projects that close



Development cost per closed project 7,400,000

Close rate $2/40 = 5.0\%$. At a sponsor value of 16,179,360 per close the programme breaks even at

0.9147 closes — a breakeven close rate of 2.29 %, less than half the rate achieved

Fig 5.1.1 — The development funnel as an option premium

5.1.3 The feasibility gate and the kill decision

Definition. A feasibility gate is the point at which a project must demonstrate that its **fatal conditions** are capable of being satisfied before the transaction tranche is committed. Its function is not to improve the project but to **stop the unfinanceable ones while stopping is cheap**. The characteristic pathology is the reverse: a project with one unresolvable condition is carried late because everything else about it is attractive, and dies in diligence having consumed the whole transaction budget plus abortive adviser fees.

WORKED EXAMPLE**Worked example 5.1.3 — the gate that pays, and the bid window that kills it.**

1. **Setup.** Of the five projects entering feasibility, the sponsor group's own post-mortem record on comparable pursuits puts at **40 %** the share carrying a fatal bankability condition (a pipeline statistic, not a market one). A conditions review costs **USD 180,000** per project and detects such a flaw with probability **0.75**. A flaw surviving the gate is found in diligence, by which point the project has spent its **2,400,000** transaction tranche plus **900,000** of abortive external fees — **3,300,000** wasted. The gate adds **8 weeks**, and in a competitive concession procurement that carries a **10 %** probability of missing the bid window, forgoing a project worth **16,179,360**.
2. **Formula.** The gate-net-value structure of PML-AI Domain 3 (KA 3.3.1), applied to development waste rather than build rework: waste without the gate = $P(\text{flaw}) \times \text{waste}$; with the gate = $\text{gate cost} + P(\text{flaw}) \times P(\text{miss}) \times \text{waste}$; net value is the difference. Breakeven detection solves $\text{gate} + P(\text{flaw})(1 - p) \times \text{waste} = P(\text{flaw}) \times \text{waste}$. Option cost of delay = $P(\text{window missed}) \times \text{value per close}$.
3. **Substitution.** Without: $0.40 \times 3,300,000$. With: $180,000 + 0.40 \times 0.25 \times 3,300,000$. Breakeven $p = 1 - (1,320,000 - 180,000) / (0.40 \times 3,300,000)$. Window: $0.10 \times 16,179,360$.
4. **Result.** Expected waste **1,320,000** without the gate, **510,000** with it — **gate net value USD 810,000 per project entering feasibility**, or **4,050,000** across five. The gate pays down to a **detection probability of 13.64 %**. But the bid-window option cost is **1,617,936**, so net value becomes **−USD 807,936**, and the **breakeven window-miss probability is 5.01 %**.
5. **Interpretation.** The same gate is worth +810,000 in a bilateral negotiation and −807,936 in a competitive tender, and nothing about the gate changed — only what the delay costs. That is the finance-specific lesson: **in development, elapsed time is priced as a lost option, not as a carrying cost**, and the option can be worth nine times the study fee. The **13.64 % breakeven detection rate** is a very low bar, which is why conditions reviews almost always pay when they run in parallel: a reviewer who can read a title register, a grid-queue position and an offtaker's credit standing inside the existing timetable is close to free money. The **5.01 % breakeven window-miss probability** is what the gate's design is negotiated with — run the review concurrently, stage it behind a two-week fatal-flaw screen, or bid conditionally; a gate whose delay risk is left unquantified will be abolished by the first commercial team that misses a deadline, taking the 810,000 with it. The caution: the 40 % flaw rate and 0.75 detection rate are **empirical claims about your own pipeline**, so a programme that has never recorded why its abandoned projects died cannot populate them — which makes the abandoned-project post-mortem the first artefact to build.

AI in this KA

Screening is the strongest legitimate machine application here: assembling opportunity long lists, extracting site and consent facts from public registers, tabulating comparables, first-pass filtering. Two boundaries. **A machine must never own the kill decision** — a kill destroys an option irreversibly and the model cannot see the strategic value the funnel exists to build; automated rejections above a materiality line get a named human reviewer. And **a model will report a condition as satisfied when it has found a document that mentions it**: the 40 % flaw rate of 5.1.3 is populated by exactly those conditions — an easement that stops 200 metres short, a permit issued to a predecessor entity, an offtaker whose credit sits in another group company. Verification

runs to the primary source on every fatal condition, sampled and signed. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 5.1

Term	Meaning
Financial close	The point at which funding documents become effective and drawdown is available.
Option premium (development)	Stage spend buying the right, not the obligation, to spend the next tranche.
Development cost per close	Programme spend ÷ closes; the honest cost of one financing.
Breakeven close rate	Programme spend ÷ (value per close × opportunities screened).
At-risk commitment	Option premiums, bid bonds, reservations — cash forfeited if the project dies.
Fatal condition	A condition whose failure ends the project regardless of everything else.

■ SAMPLE MCQS — KA 5.1

MCQ 5.1-A [5.1.2 · Application] A programme spends 1,000,000 screening, 3,000,000 on concept, 6,000,000 on feasibility and bid and 4,800,000 carrying two projects to close. Development cost per closed project is:

- A. USD 2,400,000
- B. USD 7,400,000 ☒ **CORRECT**
- C. USD 4,800,000
- D. USD 14,800,000

Rationale: $14,800,000/2 = 7,400,000$. A is the closing-stage unit cost, excluding the portfolio that produced the winners; C is the whole closing stage undivided; D attributes the entire programme to one project.

MCQ 5.1-B [5.1.2 · Analysis] A programme spends 14,800,000 across a funnel of 40 screened opportunities and delivers 16,179,360 of value per close. Its breakeven close rate is closest to:

- A. 5.00 %
- B. 2.29 % ☒ **CORRECT**
- C. 45.74 %
- D. 91.47 %

Rationale: $\text{breakeven closes} = 14,800,000/16,179,360 = 0.9147$; $\div 40 = 2.29\%$. A is the achieved close rate; C divides by the 2 closes achieved rather than the 40 screened; D quotes the breakeven closes as if it were a percentage.

MCQ 5.1-C [5.1.3 · Application] A fatal flaw is present with probability 0.40 and costs 3,300,000 if it survives to diligence. A gate costing 180,000 detects it with probability 0.75. The gate's net value, ignoring elapsed time, is:

- A. USD 1,320,000
- B. USD 810,000 ☒ **CORRECT**
- C. USD 990,000
- D. USD 330,000

Rationale: $1,320,000 - [180,000 + 0.40 \times 0.25 \times 3,300,000] = 810,000$. A is the expected waste without the gate; C omits the gate's 180,000 cost; D is the residual expected waste after it.

MCQ 5.1-D [5.1.3 · Analysis] A gate worth **+810,000** per project before elapsed time is counted adds 8 weeks and so carries a 10 % chance of missing a bid window on a project worth 16,179,360. The correct conclusion is:

- A. the gate still pays, since 810,000 is positive
- B. as designed it destroys 807,936 of value, so it should be run concurrently or staged rather than abolished ☒ **CORRECT**
- C. it should be abolished, since delay always dominates in competitive procurement
- D. bid-window risk is not a financial cost and is excluded

Rationale: $810,000 - 0.10 \times 16,179,360 = -807,936$ against a 5.01 % breakeven window-miss probability — the design, not the review, is at fault. A ignores the option cost; C forfeits 810,000 of detection value; D is the omission the arithmetic exists to prevent.

MCQ 5.1-E [5.1.2 · Comprehension] A colleague who has only worked on projects after financial close asks why the development budget is called a premium rather than a cost. The statement that best conveys the idea is:

- A. it is money already spent, and therefore irrelevant to any forward-looking decision
- B. each stage buys the right, but not the obligation, to commit the next and larger tranche, so it is judged across everything pursued rather than against the deal that closed ☒ **CORRECT**
- C. it is part of the closed project's true capital cost and belongs in that project's capital expenditure
- D. it is the fee paid to a landowner for an option over a site, held until the project proceeds

Rationale: the word marks what the money buys — optionality across a portfolio in which the closes pay for the abandonments, which is why the honest unit is 7,400,000 per close and not 2,400,000. A states the sunk-cost rule, which governs whether to continue but says nothing about what the spend purchased; C is the separate and jurisdiction-sensitive question of capitalisation (5.1.1); D names one at-risk commitment inside the budget and mistakes the part for the whole.

MCQ 5.1-F [5.1.2 · Evaluation] A development director defends next year's budget with the programme's own record: cost per closed project 7,400,000, an achieved close rate of 5.0 % against a breakeven close rate of 2.29 %, and therefore 2.19 times of margin. Value per close is the deal teams' appraisal NPV of 16,179,360. The soundest position to put to the board is that:

- A. the budget is justified as presented, because 2.19 times of margin is comfortable
- B. the ranking and the margin are the right instruments, but a breakeven computed on appraised value is itself a forecast, so it must be restated against **realised** value per close before it is relied on ☒ **CORRECT**
- C. the budget cannot be defended, because most of the spend is written off
- D. screening should be cut first, since it is the stage that funds the projects later abandoned

Rationale: treating a modelled value per close as an observed one is the judgement failure, and 5.1.2 requires the programme to be re-tested against realised value — a programme justified on optimistic deal NPVs has hidden its true breakeven. C mistakes the design of an option portfolio for waste: the closes are meant to pay for the abandonments. D attacks the 1,000,000 of screening, the smallest of the four stages and the one that buys the whole funnel, when the governance conclusion is to screen more widely and kill earlier.

■ SELF-CHECK — KA 5.1

1. Why measure development spend per closed project? — The spend buys options across a portfolio, so closes must repay abandonments: 7,400,000, not 2,400,000, is Kestrel's origination cost.
2. What replaces "cost of delay" as the price of a development gate? — The forgone option: 5.01 % of value per close is Kestrel's breakeven window-miss probability.
3. Where do development gates belong? — Where irreversibility steps up: before feasibility spend, before bid submission, before signature.

KNOWLEDGE AREA 5.2

Sponsors and special-purpose vehicles

Topics: 5.2.1 sponsors and what each brings · 5.2.2 the SPV and the limits of its ring-fence · 5.2.3 the shareholders' agreement: shares, support and dilution · 5.2.4 funding the equity and the equity bridge.

5.2.1 Sponsors and what each brings

Definition. A **sponsor** in this book's project-finance sense is an equity investor promoting the project — distinct from PML-AI's use of the word for the accountable owner of a business case (terminology registry). Sponsors contribute four separable things, and a group is assembled to assemble them: **capital**, **capability** (operating, technical or construction competence lenders will underwrite), **access** (market position, offtake relationships, host-country standing) and **credit** (a balance sheet able to stand behind the support obligations of 5.2.3). Each archetype supplies some and lacks others: an **industrial** sponsor brings technology and O&M capability but raises conflict questions where it also supplies the EPC or O&M contract; a **fund** brings capital and structuring discipline with a finite life and no operating capability; a **contractor** brings completion commitment and the suspicion that its equity is a device to win the works; a **host-country partner** brings consents and durability and is usually the smallest and least creditworthy holder (Case study B). The task at group formation is to state in the shareholders' agreement **what each sponsor is relied on for**, because that is what is tested at close — and a group whose only creditworthy member is also the contractor will find its completion support discounted for correlation, since the party guaranteeing completion is the party whose failure causes the claim.

5.2.2 The SPV and the limits of its ring-fence

Definition. A **special-purpose vehicle** is the ring-fenced legal entity created to own, finance and operate a single project; Domain 1 (KA 1.1.3, Fig 1.1.2) established it as the hub of the contract structure. It achieves risk containment (a failed project's creditors reach the vehicle, not the sponsors, beyond agreed support), security (lenders take security over the whole of a single-purpose entity, so enforcement delivers a working project rather than assets scattered through a group), clean cash (one set of flows, so **CFADS** is measurable and the waterfall enforceable) and credit separation (the project stands on its own contracts, not the weakest sponsor's rating). Its costs are extra documentation layers, standalone audit, tax and secretarial functions, and lender restrictions on the vehicle's own decisions.

What it does not do, each of which has surprised a sponsor:

- It does not survive **contractual reach-through**: completion guarantees, cost-overflow support, equity commitment letters, O&M performance guarantees and EPC parent guarantees each puncture the fence deliberately, and their aggregate is the sponsor's real exposure (5.2.3).
- It does not decide **accounting consolidation**, which turns on control and the applicable reporting framework — a jurisdiction-specific question for the sponsor's own auditors — nor simplify **tax**, since an added entity brings withholding questions and thin-capitalisation limits that can cap deductible interest, all for qualified tax counsel and all capable of changing after-tax cash.
- It does not remove **reputational exposure**, nor by itself deliver **bankruptcy remoteness**, which is engineered by restrictions in the constitutional and finance documents.

5.2.3 The shareholders' agreement: shares, support and dilution

Definition. The shareholders' agreement fixes the vehicle's economics and control: each sponsor's **equity share**, the **funding obligation** for base equity and support commitments, the **liability basis** for those commitments, reserved matters, transfer restrictions, deadlock resolution and the **default and dilution mechanics** applied when a shareholder fails to fund. The most consequential term is the liability basis: under **several** liability each sponsor owes its own share and no more, while under **joint and several** liability each may be pursued for the whole. Lenders prefer the latter because it converts a group of commitments into one strong one; sponsors resist it because it makes each of them the backstop for the least creditworthy member. Most limited-recourse structures land on several liability with **credit support** — a bank letter of credit or acceptable parent guarantee — required from any sponsor whose own credit falls below the lenders' threshold.

WORKED EXAMPLE

Worked example 5.2.3 — what each Kestrel sponsor has actually committed.

1. **Setup.** Kestrel's USD 60,000,000 capital cost is funded **70/30**: USD 42,000,000 senior debt and **USD 18,000,000** equity, held by a **water operator at 55 %**, an **infrastructure fund at 35 %** and an **industrial partner at 10 %**. The facility requires a **several cost-overflow support of 10 % of capital cost**, subscribed pro rata.
2. **Formula.** $D/E = \text{debt} \div \text{equity}$. Per sponsor: $\text{equity} = \text{total equity} \times \text{share}$; $\text{support} = \text{support pool} \times \text{share}$; $\text{committed} = \text{equity} + \text{support}$.
3. **Substitution.** $42,000,000/18,000,000$; $\text{pool} = 60,000,000 \times 0.10 = 6,000,000$; $18,000,000 \times 0.55$ and $6,000,000 \times 0.55$; and so on.
4. **Result.** Gearing **2.3333 : 1** (debt 70.0 % of capex).

Sponsor	Share	Base equity	Several support	Total committed
Water operator	55 %	9,900,000	3,300,000	13,200,000
Infrastructure fund	35 %	6,300,000	2,100,000	8,400,000
Industrial partner	10 %	1,800,000	600,000	2,400,000
Group	100 %	18,000,000	6,000,000	24,000,000

Group committed capital is **40.0 % of capital cost**, not the 30 % headline; every sponsor is committed **33.3 %** beyond its equity share. 5. **Interpretation.** The gap between the **30 % headline** and the **40 % commitment** is where sponsor boards are most reliably surprised, and it matters

three ways. For **capital planning**, the fund's board approved 6,300,000 and is exposed to 8,400,000 — a difference that belongs in its own commitment register, not a footnote. For **credit**, the partner's 2,400,000 is the smallest number in the table and the likeliest to fail: a 10 % holder is frequently the least creditworthy member, so lenders will require its support to be backed by a letter of credit as a condition precedent — a **timetable risk** outside the sponsors' control, which Case study B prices at eleven weeks. For **negotiation**, each point of support costs the group 600,000, so a lender's move from 10 % to 15 % is a 3,000,000 increase worth pricing against a coverage or tenor concession (Domain 10's four levers). The professional caution is the liability basis: make the support **joint and several** and each sponsor's worst case becomes its own equity plus the **whole** 6,000,000 pool, so the partner's exposure rises from 2,400,000 to **7,800,000** — a factor of **3.25** — while the operator's rises only from 13,200,000 to **15,900,000**, or **20.5 %**. Two words in one clause transfer most of the small holder's protection to the large ones, which is why lenders ask for them and why a small holder must not sign them lightly. It is a question for qualified counsel in the governing jurisdiction, not a modelling assumption.

5.2.4 Funding the equity, and the equity bridge

Equity may be funded **pro rata** with debt, **front-ended** (lenders' preference — sponsors' money at risk before theirs), **back-ended** (sponsors' preference, permitted only against a firm commitment), or through an **equity bridge loan** that funds the equity portion during construction and is repaid by the sponsors at completion against their commitment letters.

Price the bridge on Kestrel. Construction runs **two years**; pro rata the sponsors would contribute **9,000,000 at close** and **9,000,000 a year later**; a bridge at **5.5 %** funds both and is repaid at $t = 2$. Bridge interest is $9,000,000 \times (1.055^2 - 1) = 1,017,225$ plus $9,000,000 \times 0.055 = 495,000 = 1,512,225$, so the repayment is **19,512,225**. Discounted at the bridge rate the two profiles are **identical at USD 17,530,806** ($19,512,225/1.055^2$ against $9,000,000 + 9,000,000/1.055$) — a difference of **zero**. At the sponsors' **12 %** equity requirement — an indicative sponsor hurdle used for illustration here, not a derived cost of equity; Domain 9 (KA 9.1.3) builds Kestrel's **k_e** up from its components — the bridge profile is worth **15,555,026** against **17,035,714**, a **saving of USD 1,480,688**, or **8.69 %**.

The identity is the point: **an equity bridge creates no project value**. It is an arbitrage between the bridge rate and the sponsors' required return — a 6.5-point spread over an average deferral of about eighteen months — so the saving is **a financing return, not a project return**, and the equity **IRR** uplift it produces is exactly the flattery Domain 4 (KA 4.1.2) warned about, since the money simply went in later. Two further consequences: the bridge is **only available against firm commitments**, converting an equity-timing preference into a credit-quality test the group may fail; and it **adds 1,512,225 to project cost**, which if capitalised into senior debt consumes coverage by the mechanism 5.4.2 quantifies.

AI in this KA

Strong: extracting funding obligations, liability bases, reserved matters, transfer restrictions and default mechanics from a shareholders' agreement into a structured commitment register — the artefact 5.2.3 shows most sponsor boards lack — and reconciling it to the finance documents' conditions precedent so no support obligation is discovered late; and maintaining per-sponsor exposure across a portfolio of vehicles, where one sponsor's aggregate several commitments across ten SPVs is a number no single project team can see. **Not here:** liability basis and default consequences are **legal conclusions**, and a summary reporting "several" where the clause says otherwise misstates a balance sheet by a factor. Every such reading is verified against the executed document by qualified counsel, with verifier and date recorded.

■ KEY TERMS — KA 5.2

Term	Meaning
Sponsor (project finance)	Equity investor promoting the project; brings capital, capability, access and credit.
Special-purpose vehicle (SPV)	The ring-fenced single-purpose entity that owns, finances and operates the project.
Several liability	Each sponsor owes only its own share; joint and several exposes each to the whole.
Cost-overflow support	A sponsor commitment to fund construction cost above budget, up to a cap.
Committed capital	Base equity + support commitments; the real exposure (40.0 % of capex for Kestrel).
Equity bridge loan	Construction-period facility funding equity, repaid by sponsors at completion.

■ SAMPLE MCQS — KA 5.2

MCQ 5.2-A [5.2.3 · Application] Equity of 18,000,000 is split 55/35/10, with a several cost-overflow support of 10 % of a 60,000,000 capital cost subscribed pro rata. The 35 % sponsor's total committed capital is:

- A. USD 6,300,000
- B. USD 8,400,000 ✓ CORRECT
- C. USD 2,100,000
- D. USD 12,300,000

Rationale: $18,000,000 \times 0.35 = 6,300,000$ plus $6,000,000 \times 0.35 = 2,100,000$. A is base equity only, **25.0 % below** the committed figure — the omission the example corrects, and the same gap seen the other way round as the 33.3 % that support adds to every sponsor's equity share; C is the support alone; D reads the support as joint and several, adding the whole 6,000,000 pool.

MCQ 5.2-B [5.2.3 · Analysis] The 55 % sponsor holds 9,900,000 of an 18,000,000 equity ticket and subscribes pro rata to a 6,000,000 cost-overflow support pool. The agreement is amended from several to joint and several liability for that support. The 55 % sponsor's worst-case exposure becomes:

- A. unchanged at 13,200,000
- B. 15,900,000 — its own 9,900,000 of equity plus the whole 6,000,000 pool ✓ CORRECT
- C. 24,000,000
- D. 6,000,000

Rationale: the sponsor becomes pursuable for the entire support commitment: $9,900,000 + 6,000,000$, a 20.5 % rise against a 3.25× rise for the 10 % holder. A is the several answer; C is the group's total committed capital, applicable only if equity subscriptions were also joint and several; D omits the sponsor's own equity.

MCQ 5.2-C [5.2.4 · Analysis] An equity bridge at 5.5 % replaces pro-rata equity of 9,000,000 at $t = 0$ and $t = 1$ with 19,512,225 at $t = 2$. At 5.5 % both profiles are worth 17,530,806. The correct conclusion is:

- A. the bridge creates 1,512,225 of value

- B. it creates no value at the bridge rate; its benefit is entirely the spread between the bridge rate and the sponsors' required return ☒ **CORRECT**
- C. it destroys 1,512,225 of value
- D. it is value-neutral at every discount rate

Rationale: identical present values prove neutrality at that rate; at 12 % the saving is 1,480,688. A treats accrued interest as a gain; C treats it as a pure cost and ignores the deferral; D generalises the identity beyond the rate at which it holds.

MCQ 5.2-D [5.2.2 · Analysis] A sponsor states that the SPV caps its exposure at its equity subscription. The most accurate correction is:

- A. correct — that is the purpose of the ring-fence
- B. the fence is punctured by every support obligation given, and consolidation, tax and reputational consequences are decided outside it ☒ **CORRECT**
- C. incorrect — sponsors are always liable for all project debt
- D. correct, provided the vehicle is bankruptcy-remote

Rationale: committed capital, not subscribed equity, is the exposure (5.2.3), and consolidation and tax turn on control and framework. C describes full recourse, which limited-recourse structures exist to avoid; D confuses insolvency engineering with the scope of contractual support.

MCQ 5.2-E [5.2.3 · Evaluation] Kestrel's lenders ask that the several cost-overrun support rise from 10 % to 15 % of the 60,000,000 capital cost, taking group committed capital from 24,000,000 (40.0 % of capex) to 27,000,000 (45.0 %) and the industrial partner's commitment from 2,400,000 to 2,700,000 — an amount its own credit already requires to be backed by a letter of credit. The best recommendation to the sponsor board is:

- A. accept the 15 %, since the liability basis is unchanged and each sponsor still funds only its own share
- B. accept it only against a priced concession on coverage, tenor or margin, because the 3,000,000 is 600,000 a support point and is worth trading against the levers the lenders control ☒ **CORRECT**
- C. offer joint and several liability over the existing 6,000,000 pool instead, holding group committed capital at 40.0 % of capital cost
- D. refuse, since committed capital above 40 % of capital cost makes a limited-recourse structure uncommercial

Rationale: the request is a transfer of construction risk to the sponsors whose price is exactly knowable — 600,000 a point (5.2.3) — which makes it tradeable against the coverage, tenor, margin and sizing levers of Domain 10; conceding 3,000,000 unpriced is the failure. A is true, and is why the request reads as modest, but treating an unpriced 3,000,000 as costless is the error. C is genuinely defensible and some lenders prefer it, but it holds the pool flat by moving the partner's worst case from 2,400,000 to 7,800,000, a 3.25× rise on the least creditworthy member whose letter of credit is already a timetable risk, while the operator's rises only 20.5 % — and the liability basis it trades away is a term for qualified counsel in the governing jurisdiction, not a modelling choice (5.2.3). D invents a threshold: 45.0 % is high and negotiable, not uncommercial.

MCQ 5.2-F [5.2.4 · Evaluation] Kestrel's equity bridge at 5.5 % adds 1,512,225 of interest to project cost and lifts the sponsors' equity IRR, because their money goes in later. The finance lead is asked how to put it to the investment committee. The soundest presentation:

- A. leads with the improved equity IRR, since equity is what the committee is being asked to commit
- B. reports the 1,480,688 of saving as a financing return earned at the sponsors' own required return, states that the project return is unchanged, and discloses both the 1,512,225 added to project cost and the firm commitments the bridge depends on ☒ **CORRECT**
- C. omits the bridge from the return presentation altogether, because it creates no project value
- D. adds the 1,480,688 to the project NPV as a financing benefit

Rationale: the two funding profiles are identical in present value at the bridge rate — 17,530,806 either way — so the bridge is an arbitrage between that rate and the sponsors' 12 % requirement, and it is reported as what it is (5.2.4). A presents a change in timing as project performance, the flattery Domain 4 (KA 4.1.2) warns of. C suppresses a real cost that consumes coverage if it is capitalised. D books a financing return inside a project measure, which is the same error with a decimal point.

MCQ 5.2-G [5.2.2 · Comprehension] An SPV is said to deliver both **credit separation** and **bankruptcy remoteness**. The two differ in that:

- A. they are one property, described from the lender's side and the sponsor's side
- B. credit separation is an outcome of how the project is underwritten — on its own contracts rather than on the weakest sponsor's rating — while bankruptcy remoteness has to be built into the vehicle's constitution and its finance documents, and incorporating a single-purpose entity does not deliver it ☒ **CORRECT**
- C. credit separation is a legal state and bankruptcy remoteness is a rating outcome
- D. credit separation applies during construction and bankruptcy remoteness during operations

Rationale: 5.2.2 lists credit separation among the things the vehicle achieves and bankruptcy remoteness among the things it does **not** achieve by itself. A and C collapse a commercial assessment into a documentary construct, and it is the confusion behind the belief that a single-purpose entity is insolvency-proof; D invents a timing distinction the structure does not make.

■ SELF-CHECK — KA 5.2

1. State Kestrel's per-sponsor committed capital and the group total. — 13,200,000 / 8,400,000 / 2,400,000, totalling 24,000,000 — 40.0 % of capital cost against a 30 % headline.
2. Name three things an SPV does not achieve. — It does not defeat contractual support, does not decide accounting consolidation, and does not remove tax or reputational exposure.
3. What is an equity bridge worth, and to whom? — Nothing to the project; to the sponsors, 1,480,688 — 8.69 % — the spread between the 5.5 % bridge rate and their 12 % requirement over the deferral.

KNOWLEDGE AREA 5.3**The bankability test**

Topics: 5.3.1 bankability as a conjunction · 5.3.2 the revenue model and the offtake · 5.3.3 permits, land and consents · 5.3.4 technology and its price.

5.3.1 Bankability as a conjunction

Definition. Bankability is the degree to which a project's contracts, risks and cash flows support limited-recourse financing on acceptable terms (terminology registry). It is not a score and not a probability of success: it is the state in which **every** condition a lender requires is satisfied, on the timetable, in documents. The structural consequence is that bankability composes **multiplicatively**, and that one fact reorganises how a development programme is run.

WORKED EXAMPLE**Worked example 5.3.1 — six conditions, one probability, and where the effort belongs.**

1. **Setup.** Kestrel's lenders require six conditions, each with an assessed probability of being satisfied on the target close timetable: **offtake / revenue model 0.92; permits and consents 0.90; land and site tenure 0.95; technology (proven and guaranteed) 0.88; EPC wrap (fixed price, date certain) 0.93; financing market and credit approval 0.85.** Remaining development spend to close is **2,400,000**; value on close is **16,179,360**.
2. **Formula.** Assuming independence, joint probability = $\prod p_i$. Marginal gain from lifting condition i from p to $p' = \prod p_i \times (p'/p - 1)$. Expected value of continuing = **joint probability $\times$ value $-$ remaining spend**. Breakeven close probability = **remaining spend $\div$ value**. Uniform probability needed for a joint target J over k conditions = $J^{(1/k)}$.
3. **Substitution.** $0.92 \times 0.90 \times 0.95 \times 0.88 \times 0.93 \times 0.85$; weakest lift $\times 0.95/0.85$; strongest lift $\times 0.98/0.95$; continue test $0.547190 \times 16,179,360 - 2,400,000$; uniform requirement $0.90^{(1/6)}$.
4. **Result.** Joint probability of close **0.5472 (54.72 %)** — against an **arithmetic mean of the six conditions of 90.5 %**. Lifting the **weakest** (financing, $0.85 \rightarrow 0.95$) gives **61.16 %**, a gain of **6.4375 points**; lifting the **strongest** (land, $0.95 \rightarrow 0.98$) gives **56.45 %**, a gain of **1.7280 points** — the weakest link is worth **3.7255 $\times$** more. Six conditions all at 0.98 still give only **88.58 %**; a **90 % joint probability requires every condition at 98.26 %**. Expected value of continuing = $8,853,191 - 2,400,000 = +6,453,191$; the **breakeven close probability is 14.83 %**.
5. **Interpretation.** The 54.72 % changes behaviour because almost every development team reports the 90.5 %: asked how the project is looking, they average their conditions and answer "about 90 per cent", wrong by 36 points. Three professional uses follow. **Resource allocation inverts:** the ranking of conditions by marginal gain — not by importance or by who is shouting — is the work plan, and 3.7 $\times$ more value sits in the financing condition than in the land condition. **The continue/kill test separates from the condition test:** at a breakeven close probability of only **14.83 %**, expected value says "continue" on almost anything, which is precisely why a development programme cannot be governed by expected value alone and needs the fatal condition rule of 5.1.3. And the **uniform requirement of 98.26 %** explains what practitioners observe without deriving: bankable projects are not projects with good conditions, they are projects with **no open condition** — what conditions precedent (5.A.2) exist to enforce. The professional caution is independence: these conditions are correlated, usually positively (a supportive host government helps permits, land and financing together), which makes the true joint probability **higher** than the product, while clustered failures fatten the downside. Report the **ranking**, which is robust, and treat 54.72 % as a disciplined lower bound with its assumption stated — never as a forecast.

Six conditions averaging 90.5 % give a 54.7 % chance of financial close

Bars: each condition met on the target timetable. Line: the running product. Lifting the weakest from 0.85 to 0.95 adds 6.44 points; lifting the strongest every condition would need 0.9826 for a 0.90 joint




Fig 5.3.1 — Bankability as a conjunction

5.3.2 The revenue model and the offtake

Definition. The **revenue model** is the mechanism by which the project is paid, and it is diligenced first because every other condition is contingent on it. The bankability question is not "how much revenue?" but "**who is contractually obliged to pay, how much, for how long, and what can lawfully stop them?**" Domain 7 builds the taxonomy; the development-stage test has five components.

Component	The test	Why it is a bankability condition
Volume or availability	Does the payer pay for availability (Kestrel's structure) or for what is sold?	Merchant risk moves required coverage by 0.2× or more, and debt capacity by millions (Domain 10)
Tenor	Does contracted revenue extend beyond loan maturity with margin?	A 12-year loan against a 7-year offtake has five unfunded years; Kestrel's 25-year offtake is why its PLCR is 1.9431
Counterparty credit	Can the payer pay, from what source, and is the obligation supported?	An offtake is worth the offtaker's ability to pay; creditworthy signature, not signature, is the condition
Indexation	Is every material cost either indexed in the tariff or fixed in a contract of matching tenor?	An unindexed O&M cost inside an indexed tariff is a slow structural margin loss (Domain 3, KA 3.3.2)
Termination and change in law	Does termination compensation repay outstanding debt in non-default scenarios?	Debt sized on that assumption but documented without it is unbankable at close, not at signature

The recurring error sits in the third row: teams treat signature as satisfaction of the revenue condition when the lenders' condition is a creditworthy payer. The remedy is structural — a guarantee, letter of credit or escrow, or resizing to what the weaker credit supports — and it must be established **before** debt is sized, because every ratio in Domain 10 assumes it.

5.3.3 Permits, land and consents

Definition. The **consent set** is the complete list of governmental and third-party permissions the project needs to be built, to operate and to be financed; the **land and tenure set** is the complete list of rights to occupy, cross and use land for the asset and all its corridors. Both are bankability conditions, because security over a project that may not lawfully operate or remain where it is built is worthless.

Two artefacts organise the work. **The consent register** lists every permission with issuing authority, statutory basis, lead time, dependency, expiry, transferability to the SPV and attached conditions — because a permit with unsatisfiable conditions is a refusal with a delay — and identifies which consents drive the critical path, since consents are the development activities least susceptible to acceleration by money. **The land register** does the same for freehold, leasehold, easements, rights of way, wayleaves and access, and its characteristic failure is the **linear asset**: the plant sits on one parcel, but the pipeline, cable, access road or outfall crosses many, and a single unregistered easement over a few hundred metres can stop an otherwise complete project (Case study A).

Environmental and social consent deserves separate naming. Lenders on limited-recourse infrastructure commonly require environmental and social risk to be assessed and managed to a defined standard, and many financial institutions have voluntarily adopted the **Equator Principles**, a lender framework under which participating institutions apply agreed environmental and social requirements to the projects they finance and which in turn refers to the **IFC Performance Standards**. Whether either applies, in what version and with what categorisation is a matter for the specific lenders and project; both are named here for identification only, neither is reproduced or summarised as a source of requirements, and neither body is associated with this book. The duty is to establish the applicable requirement early, because retrofitting a stakeholder-engagement or resettlement process to a completed design is the most expensive rework in infrastructure development.

5.3.4 Technology, the bankable track record and its price

Definition. A technology is **bankable** when lenders will lend against its performance without recourse to sponsors — which requires operating references at comparable scale and duty, a supplier able to stand behind performance guarantees, and an independent technical adviser's opinion the lenders accept. **First-of-a-kind** is not a technical description but a financing category, and it has a price.

Price it on Kestrel. The proven process was sized at a target **DSCR** of **1.30×** on **CFADS** of **6,384,000** over 12 years at 6.0 %. A variant using a novel membrane arrangement would cut operating cost, but the technical adviser cannot supply operating references at scale and the credit committee would require **1.45×** on unchanged cash. Using Domain 10's sizing rule (max debt service = **CFADS** ÷ target **DSCR**; max debt = that × **AF(0.06, 12)** = 8.383844): at 1.30×, $6,384,000/1.30 = 4,910,769$ supports **USD 41,171,123**; at 1.45×, $6,384,000/1.45 = 4,402,759$ supports **USD 36,912,041**. The **capacity loss is USD 4,259,082**, gearing falls from 68.6 % to **61.5 %** of capital cost, and the 4,259,082 must be found as **additional equity**.

The variant must therefore save more than the cost of 4,259,082 of equity displacing debt, and since equity is the more expensive money the threshold is high: at a 12 % equity requirement against 6 %

debt the annual pre-tax cost of that substitution is about **255,545** ($4,259,082 \times 6$ points of spread), which the operating saving must beat before any allowance for the technology's own performance risk. That is the arithmetic behind a maxim — **project finance is a poor place to innovate** — and two refinements keep it honest. The coverage premium is not the only lever: an extended supplier guarantee, a larger maintenance reserve, output insurance, or a first-loss contribution from a development-finance or concessional lender (Domain 9, KA 9.3–9.4) can each buy the ratio back down, and pricing those against 4,259,082 is the negotiation. And the premium is **not permanent** — the same technology at its fourth installation is a different credit. The caution runs the other way too: bankable is not the same as good, and a leader who lets the lenders' comfort choose the engineering has outsourced a 25-year lifecycle decision to a credit committee whose horizon is 12 years (Domain 8).

AI in this KA

Earns: building and maintaining the consent and land registers from source documents; extracting defined terms, tenors, indexation formulae, termination provisions and conditions precedent into a structured condition set; and re-running the conjunction of 5.3.1 whenever an assessed probability changes, so the marginal-gain ranking stays current instead of being computed once for a board paper. **Must not go:** the probabilities themselves are professional judgment informed by counterparties and counsel, and a model asked to supply them produces confident numbers with no evidential basis — a false precision that propagates into a 54.72 % that looks computed and is invented. Nor may a model conclude that a condition is **satisfied**: satisfaction is a legal state, evidenced by a document, verified by counsel and recorded. Every condition in an AI-built register is traced to a primary document by a named person, probabilities carry the assessor's name and date, and extraction is sampled against source.

■ KEY TERMS — KA 5.3

Term	Meaning
Bankability	The degree to which contracts, risks and cash flows support limited-recourse financing on acceptable terms.
Conjunctive test	Composition by multiplication: every condition must pass, so the weakest governs.
Marginal gain (condition)	Joint probability $\times (p/p - 1)$; the correct ranking of development effort.
Breakeven close probability	Remaining development spend $\div$ value on close (14.83 % for Kestrel).
Consent register	Every permission with authority, lead time, dependency, expiry, transferability and conditions.
Linear-asset tenure risk	Corridor rights whose single gap can stop an otherwise complete project.
First-of-a-kind premium	The coverage, reserve or insurance cost of unproven technology, payable in equity.

■ SAMPLE MCQS — KA 5.3

MCQ 5.3-A [5.3.1 · Application] Six bankability conditions have probabilities 0.92, 0.90, 0.95, 0.88, 0.93 and 0.85. The joint probability of close, assuming independence, is closest to:

- A. 90.5 %
- B. 54.72 % ✓ CORRECT

- C. 85.0 %
- D. 43.0 %

Rationale: the product is 0.5472. A is the arithmetic mean — the error the example corrects; C quotes the weakest condition as though the others were certain; D sums the six shortfalls (0.57) and subtracts the total from one, over-counting the failures by treating them as mutually exclusive.

MCQ 5.3-B [5.3.1 · Analysis] In a six-condition set whose joint probability is 0.5472, one week of effort can lift either the financing condition from 0.85 to 0.95 or the land condition from 0.95 to 0.98. The value-maximising choice is:

- A. land, because 0.98 is the higher absolute probability
- B. financing, which adds 6.44 points against land's 1.73 — a factor of 3.73 ✓ CORRECT
- C. either, since both raise one condition by a similar amount
- D. neither, because correlation makes the calculation meaningless

Rationale: marginal gain is the joint probability times the proportional lift: $0.5472 \times (0.95/0.85 - 1) = 6.4375$ points against $0.5472 \times (0.98/0.95 - 1) = 1.7280$. A ranks by level rather than gain; C ignores that a proportional lift on a low base moves the product much more; D discards a ranking correlation does not reverse.

MCQ 5.3-C [5.3.4 · Application] A credit committee raises the target DSCR from 1.30× to 1.45× for lack of operating references. On CFADS of 6,384,000 over 12 years at 6 % (AF = 8.383844), the additional equity required is closest to:

- A. USD 4,259,082 ✓ CORRECT
- B. USD 6,300,000
- C. USD 508,011
- D. USD 4,910,769

Rationale: capacity falls from 41,171,123 to 36,912,041. B applies the 0.15 ratio increase to the 42,000,000 of debt as though ratio points were percentages of principal; C is the fall in annual debt service; D is the maximum debt service at 1.30×, a per-period figure mistaken for a capital sum.

MCQ 5.3-D [5.3.2 · Analysis] A project has a signed 20-year offtake with a counterparty whose payment obligations are unsupported and whose credit lenders assess as weak. The correct conclusion is:

- A. bankable — a signed long-tenor offtake is the strongest possible condition
- B. the revenue condition fails on counterparty credit; it is repaired by credit support or by resizing, not by the contract's length ✓ CORRECT
- C. bankable if the tariff is indexed
- D. unbankable permanently

Rationale: an offtake is worth the offtaker's ability to pay, so tenor and indexation do not cure credit (A, C). D overstates: credit support and resizing are the standard structural remedies.

MCQ 5.3-E [5.3.1 · Evaluation] A gate paper reports: "The six conditions average 90.5 %, so the project is about ninety per cent likely to close. Expected value of continuing is +6,453,191 against a breakeven close probability of 14.83 %, and the remaining effort will be shared evenly across the six." Each of the four observations below is defensible. Which should the reviewer press first?

- A. the 90.5 %, which overstates the 54.72 % joint probability by 35.78 points

- B. the even effort split, since marginal gain ranks the financing condition $3.7255\times$ above the land condition
- C. the expected-value verdict, because a 14.83 % breakeven makes "continue" the answer on almost anything, so the decision actually turns on whether any of the six conditions is fatal and unresolvable ✓ CORRECT
- D. the independence assumption, since these six conditions are positively correlated

Rationale: A and B are both right and both must be corrected, but neither can change the decision the paper asks for — A changes what is reported and B changes the work plan, and on either the arithmetic still says continue. Only C reaches the commitment of the remaining 2,400,000, which expected value cannot govern in a conjunctive test and which the fatal-condition rule exists to decide (5.1.3, 5.3.1). D points the wrong way: positive correlation raises the true joint probability above the product, so it strengthens the case for continuing rather than weakening it.

MCQ 5.3-F [5.3.4 · Comprehension] A supplier describes its new membrane arrangement as "fully proven — three pilot units have run for two years". A colleague asks what more the word bankable could require. The best restatement is:

- A. bankable means technically demonstrated, so a two-year pilot record settles it
- B. bankable is a financing category rather than a technical description: it is the state in which lenders will lend against the technology's performance without recourse to the sponsors ✓ CORRECT
- C. bankable means the technology is the lowest lifecycle-cost option available
- D. bankable means the supplier has issued a performance guarantee

Rationale: the question the word answers is whose money is at risk if performance disappoints, which is why the test is operating references at comparable scale and duty, a supplier able to stand behind its guarantees, and an independent technical adviser's opinion the lenders accept (5.3.4). A is the supplier's sense of the word, and pilot scale is precisely what the financing definition excludes; C is the engineering question, and the domain's own caution is that bankable and good are not the same; D names one necessary component, and a guarantee is worth only the guarantor's balance sheet.

MCQ 5.3-G [5.3.4 · Evaluation] The novel membrane variant would cut operating cost, but the credit committee requires $1.45\times$ rather than $1.30\times$ for want of operating references: debt capacity falls from 41,171,123 to 36,912,041, so 4,259,082 must be found as equity at an annual substitution cost of about 255,545. The engineering team argues the variant is the better plant. The soundest position is that:

- A. the variant should be adopted, because a 25-year lifecycle decision must not be made on a 12-year lender's view
- B. the variant should be rejected, because project finance is a poor place to innovate
- C. the coverage premium is one of several priced levers — an extended supplier guarantee, a larger maintenance reserve, output insurance or a first-loss contribution can each buy the ratio back down — so the decision is whether the operating saving plus any mitigant beats 4,259,082 of equity, not whether to defer to the committee ✓ CORRECT
- D. the target ratio should be negotiated back to $1.30\times$, since the underlying cash flow is unchanged

Rationale: 5.3.4 states both halves and neither settles it alone: bankable is not the same as good, so A's warning is real, and the arithmetic is real too. What makes C sounder is that it prices the choice and keeps the engineering decision with the engineers, which is exactly the negotiation Domain 9

(KA 9.3–9.4) supplies instruments for. A hands a financing constraint no answer; B is the maxim used as a substitute for the calculation; D misreads the ratio as an opinion rather than an output of the credit — the references are missing whatever the sponsors would prefer.

■ SELF-CHECK — KA 5.3

1. Why does averaging bankability conditions mislead? — Conditions compose multiplicatively: six averaging 90.5 % give a 54.72 % joint probability, a 36-point error.
2. What uniform per-condition probability does a 90 % joint probability require over six conditions? — $0.90^{1/6} = \mathbf{98.26\%}$, which is why bankable projects have no open condition rather than good ones.
3. State Kestrel's first-of-a-kind premium in money. — $1.45\times$ instead of $1.30\times$ costs 4,259,082 of debt capacity, payable as equity, at an annual substitution cost of about 255,545.

KNOWLEDGE AREA 5.4

Construction and operational readiness

Topics: 5.4.1 completion risk and the EPC wrap · 5.4.2 the cost of a slip in the commercial operations date · 5.4.3 completion tests, performance guarantees and buy-down · 5.4.4 operational readiness.

5.4.1 Completion risk and the EPC wrap

Definition. Completion risk is the risk that the project is not delivered on time, to cost and to the performance the financing was sized on. It dominates limited-recourse structures because during construction the project has **all** the debt and **none** of the cash flow: nothing absorbs a shock, and every day of delay is financed.

The standard mitigation is the **EPC wrap**: one contractor takes **fixed-price, date-certain, turnkey** responsibility for the whole works, so interface risk sits with the contractor rather than the SPV. Its components are each a bankability condition — a fixed lump-sum price with defined change mechanics; a date certain with **delay liquidated damages** (5.4.2); **performance guarantees** with performance damages or **buy-down** (5.4.3); performance security sized to the residual exposure; a defects-liability period; and a parent guarantee where the contracting entity is thinly capitalised (Domain 12 drafts these; Domain 11 allocates the risks behind them). Whether a given damages rate, cap or security instrument is enforceable as drafted is jurisdiction-specific and belongs to counsel, not to the model; what this domain computes is the **cash** each provision would have to deliver to be adequate. The wrap's price is the **wrap premium** — a contractor pricing interface and schedule risk it does not control charges for it, and the charge is material enough that a multi-package alternative must be compared against it on interface exposure and price together, never on price alone — and its two failure modes are **multi-package delivery without a wrap**, where the SPV holds every interface dispute, and **a wrap exceeding the contractor's capacity to stand behind it**, since damages and guarantees are worth only the guarantor's balance sheet.

5.4.2 The cost of a slip in the commercial operations date

Definition. The **commercial operations date (COD)** is the contractual date from which the project is treated as operating: revenue begins, the operating-period covenant regime starts, and construction debt converts to term debt. A slip costs money in two distinct and frequently confused

ways — **extra interest during construction** on debt already drawn, and **forgone CFADS** — and the whole delay-damages negotiation is an attempt to price them.

WORKED EXAMPLE

Worked example 5.4.2 — Kestrel's COD slips 180 days.

- Setup.** At the scheduled COD the facility is fully drawn at **42,000,000** at **6.0 %**; operating **CFADS** would have been **6,384,000** per year; the EPC contract carries **delay liquidated damages of USD 20,000 per day** capped at **10 % of the 48,000,000 EPC price**. Interest and daily rates use a **30/360** basis (a common convention; the applicable basis is a negotiated term, and actual/360 or actual/365 would shift these figures slightly). The concession's expiry was fixed at award — **27 years from scheduled financial close** — so a slip **shortens operations rather than extending the term**.
- Formula.** Daily extra interest = drawn debt × rate ÷ 360; daily forgone **CFADS** = annual **CFADS** ÷ 360; damages coverage = daily damages ÷ daily economic cost; cap-binding day = cap ÷ daily damages. Coverage consequence: new instalment = new debt ÷ **AF(0.06, 12)**, then **DSCR** and the covenant trigger per Domain 10.
- Substitution.** $42,000,000 \times 0.06/360 = 7,000$; $6,384,000/360 = 17,733.33$; $20,000/24,733.33$; $4,800,000/20,000$; $43,260,000/8.383844$.
- Result.**

Item	Per day	180 days	360 days
Extra interest on drawn debt	7,000.00	1,260,000	2,520,000
Forgone CFADS	17,733.33	3,192,000	6,384,000
Total economic cost	24,733.33	4,452,000	8,904,000
Delay damages at 20,000/day	20,000.00	3,600,000	4,800,000 (capped)
Uncovered, borne by the SPV	4,733.33	852,000	4,104,000

Damages recover **80.86 %** of the daily cost; the **cap binds at day 240**. If the 1,260,000 of extra interest is **capitalised**, debt becomes 43,260,000, the instalment rises to **5,159,924.29**, **DSCR** falls from 1.2743 to **1.2372**, the covenant cash trigger rises to **6,191,909**, and annual headroom falls from **372,438 to 192,090.85** — **51.6 %** of what it was. Funded as equity instead, equity rises to **19,260,000** and gearing moves from 70.0/30.0 to **68.6/31.4 (D/E 2.1807)**. 5. **Interpretation.** Three conclusions live in that table. **The damages rate is mis-calibrated, by a knowable amount.** A rate of 20,000 against a daily cost of 24,733.33 leaves equity carrying 4,733.33 per day, and the negotiating position is not "higher damages" but "damages calibrated to interest plus forgone **CFADS**" — a computation the contractor can check and therefore argue about honestly. The commonest calibration error is to size on the **forgone CFADS alone**, which covers only 71.7 % of the cost; the omitted 7,000 per day is 28.3 % and the most certain component of all, because it accrues whether or not the plant would have run well. **The cap is where the structure actually breaks.** Below day 240 damages absorb most of the pain; beyond it every further day costs the SPV the full 24,733.33, so a 360-day slip leaves **4,104,000** uncovered — which is why lenders test the delay scenario against the cap rather than the rate, and why cost-overflow support (5.2.3) and contingency (Domain 8, KA 8.3) exist for the tail the cap does not reach. **A construction event becomes a permanent operating constraint:** capitalising 1,260,000 of interest halves the covenant headroom Domain 10 measured, for the whole 12-year loan life, on a project otherwise exactly as forecast. The structural choice — capitalise into debt or fund with equity — is therefore a choice about **where the slip**

lands, on coverage or on equity return, and it belongs to the sponsors before the event, in the funding documents.

The value view answers a different question. The cash table is the right basis for calibrating damages; it is not the sponsors' loss. Discounting quarterly at Domain 4's 8 % (quarterly rate **1.942655 %**, **CFADS** 1,596,000 per quarter, concession 108 quarters from close), the operating stream is worth **60,150,401** at close on time and **57,491,504** if COD slips 180 days — a **present-value loss of 2,658,897**, less than the naive 3,192,000 of "six months of **CFADS**", because what is truly lost is the final half-year of a 25-year stream discounted 27 years, while the rest is merely deferred by two quarters. Adding the 1,260,000 of interest gives a total value loss of **3,918,897** — **24.2 %** of Domain 4's entire **NPV** of 16,179,360, destroyed by six months. Against that, 3,600,000 of damages received at the delayed COD is worth **2,969,909** at close, leaving a net loss of **948,988**, or **5.9 %** of the project **NPV**. That pair — 24.2 % gross, 5.9 % net — is the most useful single statement of what an EPC delay-damages regime is for.

5.4.3 Completion tests, performance guarantees and buy-down

Definition. Completion is not a date but a **test**. Financing documents distinguish **mechanical completion** (built and safe to commission), **provisional or substantial completion** (defined performance demonstrated, triggering COD and often conversion to term debt) and **final completion** (punch list cleared, reliability run passed, documentation delivered). Lenders' test is usually the strictest, and it commonly includes a **reliability run** — sustained output over a continuous period — because a single-point test can be passed by a plant that cannot hold it. Where the plant completes but **underperforms**, the remedy is **performance liquidated damages** or a **buy-down**: a payment calibrated so that coverage returns to the sized level, usually applied to prepay debt.

WORKED EXAMPLE**Worked example 5.4.3 — sizing the buy-down for a 3 % output shortfall.**

1. **Setup.** Kestrel completes at **97 %** of guaranteed output. Revenue is **12,000,000** at full output; cash operating costs are **4,500,000**, of which **85 % is fixed** (3,825,000) and 15 % varies with output (675,000). Depreciation is **2,400,000**, interest **2,520,000**, cash tax **20 %**, and the working-capital movement is **600,000** as in Domain 2's **CFADS** derivation. The sized **DSCR** was **1.2743** against debt service of **5,009,635.23**.
2. **Formula.** Revenue and variable cost scale with output, fixed cost does not; **EBITDA** = revenue – cash operating cost; **CFADS** = **EBITDA** – cash tax – Δ working capital (Domain 2, KA 2.3.1). At constant target coverage debt is proportional to **CFADS**, so buy-down = debt $\times$ (**CFADS** shortfall $\div$ base **CFADS**).
3. **Substitution.** $12,000,000 \times 0.97 = 11,640,000$; $3,825,000 + 675,000 \times 0.97 = 4,479,750$; **EBITDA** = 7,160,250; $7,160,250 - 2,400,000 - 2,520,000 = 2,240,250$; $\text{tax} \times 0.20 = 448,050$; **CFADS** = $7,160,250 - 448,050 - 600,000$; buy-down = $42,000,000 \times (6,384,000 - 6,112,200) / 6,384,000$.
4. **Result.** **EBITDA** falls to **7,160,250** — a fall of **339,750**, or **4.53 %**, on a 3 % output shortfall (**operating leverage 1.510×**). **CFADS** falls to **6,112,200** and **DSCR** to **1.2201**; covenant headroom collapses from 372,438 to **100,638**, so a 3 % shortfall consumes **73.0 %** of it. The buy-down restoring sized coverage is **USD 1,788,158**, reducing debt to **40,211,842**.
5. **Interpretation.** The **1.510×** **operating leverage** is what sponsors most often fail to carry into a performance-guarantee negotiation: because most of a plant's cash operating cost is fixed, a small output shortfall produces a proportionately larger cash shortfall, so a guarantee negotiated in **output percentage** must be converted into **cash** before anyone agrees it is adequate. The **73 % of headroom consumed by a 3 % shortfall** is the sentence for the board paper: a shortfall well inside most people's intuition of "close enough" leaves the project 100,638 of annual cash from a covenant breach, with all the lock-up consequences of Domain 10 (KA 10.4.2). And the **1,788,158 buy-down** demonstrates an identity worth carrying: at constant coverage **debt scales linearly with CFADS**, so the buy-down is simply debt times the proportional **CFADS** shortfall — computable in a negotiation, on one line, without a model. Two cautions: a buy-down restores the lenders' position, not the sponsors' — equity has permanently lost 271,800 of annual cash and gained only a smaller loan — and performance damages are **capped** like delay damages, so establish the shortfall at which the cap is exhausted and check the project is still bankable there.

5.4.4 Operational readiness

Definition. **Operational readiness** is the state in which the project can be operated to the standard the revenue contract requires from the first day of the operating period. It is a bankability condition that is systematically under-managed, because the construction contract has an owner with a deadline and readiness usually does not. The readiness set, each item with an owner, a date and evidence: an **operating organisation** (O&M contract with a creditworthy operator, or an in-house team recruited and trained); **permits to operate**, distinct from permits to construct, frequently issued later and occasionally conditional on demonstrated performance, so the consent register must separate the two; **spares, consumables and supply** with tenor matching the offtake; **metering** on which the revenue contract pays, calibrated and accepted by both parties, since a tariff paying on measured availability is only as good as the meter and the dispute process behind it; **insurance transition**, construction cover replaced by operating cover with lender endorsements in force on day one, a gap being both an uninsured exposure and an event of default; **reporting readiness** — model

updated to actuals, first covenant test date and compliance certificate scheduled, reserve accounts funded (Domain 10, KA 10.3), because a first covenant test failed for want of a report is a breach on a performing project; and **handover of the record** — as-built documentation, warranties, manuals and a defect list with owners and dates.

The financing consequence is direct: the covenant regime starts at COD, so a project reaching COD operationally unready spends its first test period generating exactly the shortfall 5.4.3 priced, with no track record and no goodwill. Readiness therefore runs as a **separate workstream with its own gate**, held before COD is declared — and the uncomfortable implication is accepted: **declaring COD early to start revenue can be the most expensive decision in the project**, because it converts a construction problem the contractor owns and damages cover into an operating problem equity owns and nothing covers.

AI in this KA

The strong application is **readiness and completion evidence assembly**: tracking hundreds of completion-test, permit-to-operate, insurance, spares and documentation items against owners and dates, reconciling the punch list to defects-liability obligations, and flagging items whose evidence is missing before COD is declared — list discipline at a scale humans do badly, and cheap to verify because each item resolves to a document. Machine-assisted **COD forecasting** is legitimate with one non-negotiable control: the forecast COD drives the arithmetic of 5.4.2, so a model-produced date entering a lender report has become a representation and must carry the named person who owns it. **Where it must not go**: declaring a completion test passed, or the project ready to operate, is a professional certification with contractual and safety consequences — a machine may assemble the evidence and must never make the call; and attributing a 3 % shortfall to design, construction, operation or feed conditions decides who pays under which contract. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 5.4

Term	Meaning
Completion risk	Risk of not delivering on time, to cost and to sized performance — all debt, no cash flow.
EPC wrap	Read here only as what makes completion risk bankable: one contractor answerable for the whole works, so lenders face a single counterparty. Defined and priced in Domain 12, KA 12.1.
Commercial operations date (COD)	Contractual start of operations: revenue, term debt and the operating covenant regime.
Interest during construction	Interest accruing on drawn debt before revenue; 7,000 per day for Kestrel.
Delay liquidated damages	Daily payment for late completion; calibrate to interest plus forgone CFADS .
Damages cap	The ceiling beyond which every further day is borne by the SPV (day 240 for Kestrel).
Buy-down	Payment applied to prepay debt so sized coverage is restored after a performance shortfall.
Operating leverage (plant)	EBITDA shortfall ÷ output shortfall; 1.510× for Kestrel at 85 % fixed cost.
Operational readiness	Capability to operate to contract standard from the first day of the operating period.

■ SAMPLE MCQS — KA 5.4

MCQ 5.4-A [5.4.2 · Application] Debt of 42,000,000 is fully drawn at 6.0 %; annual CFADS would be 6,384,000; 30/360 applies. The daily economic cost of a COD slip is:

- A. USD 17,733.33
- B. USD 24,733.33 ☒ **CORRECT**
- C. USD 7,000.00
- D. USD 26,400.00

Rationale: $42,000,000 \times 0.06/360 = 7,000$ of interest plus $6,384,000/360 = 17,733.33$ of forgone CFADS. A is the forgone-CFADS side alone — the calibration error leaving 28.3 % uncovered; C is the interest alone; D uses the pre-working-capital CFADS of 6,984,000 (Domain 2's other definition, 19,400 per day).

MCQ 5.4-B [5.4.2 · Analysis] The daily economic cost of a COD slip is 24,733.33. Delay damages are 20,000 per day, capped at 10 % of a 48,000,000 EPC price. For a 360-day slip the SPV bears:

- A. nothing — the damages cover the delay
- B. USD 4,104,000, because the cap binds at day 240 against an economic cost of 8,904,000 ☒ **CORRECT**
- C. USD 1,704,000
- D. USD 8,904,000

Rationale: cap = $4,800,000$, binding at $4,800,000/20,000 = 240$ days; cost = $360 \times 24,733.33 = 8,904,000$; uncovered = $4,104,000$. A ignores the cap; C computes damages as though all 360 days were payable (7,200,000) and subtracts; D omits recovery altogether.

MCQ 5.4-C [5.4.2 · Analysis] A facility of 42,000,000 over 12 years at 6 % (AF = 8.383844) carries a 1.20× cash covenant against CFADS of 6,384,000, leaving annual headroom of 372,438. 1,260,000 of extra construction interest is capitalised, taking debt to 43,260,000 at the same tenor and rate. The most important consequence for the operating period is:

- A. none — the debt is repaid over the same period
- B. annual covenant headroom falls from 372,438 to 192,090.85, roughly halving it for the whole loan life ☒ **CORRECT**
- C. the loan tenor extends
- D. CFADS falls by 1,260,000

Rationale: the instalment rises to $43,260,000/8.383844 = 5,159,924.29$, DSCR falls to 1.2372 and the 1.20× trigger rises to 6,191,909. A ignores that debt service rises; C is a possible structural response, not an automatic consequence; D confuses a financing cost with cash generation, which is unchanged.

MCQ 5.4-D [5.4.3 · Application] A 3 % output shortfall reduces CFADS from 6,384,000 to 6,112,200 against debt of 42,000,000. The buy-down restoring the originally sized coverage is:

- A. USD 271,800
- B. USD 1,788,158 ☒ **CORRECT**
- C. USD 1,260,000
- D. USD 4,259,082

Rationale: at constant coverage debt is proportional to CFADS, so the buy-down is $42,000,000 \times 271,800/6,384,000$. A is the annual CFADS shortfall, not the debt adjustment; C is the COD-slip interest of 5.4.2; D is the technology premium of 5.3.4 — correct numbers in the wrong place.

MCQ 5.4-E [5.4.2 · Evaluation] Kestrel's daily economic cost of delay is 24,733.33 against delay damages of 20,000 per day capped at 4,800,000, so damages recover 80.86 % of the daily cost and the cap binds on day 240. Lenders stress a 360-day slip, in which the SPV bears 4,104,000 — 1,704,000 of daily shortfall plus 2,400,000 for the 120 days beyond the cap. The contractor will concede either the rate or the cap, not both. The better recommendation is:

- A. take the rate to 24,733.33, removing the 4,733.33 per day the calibration analysis identifies
- B. take the cap, because with the cap held at 4,800,000 a full-cost daily rate merely brings the cap forward from day 240 to day 194.07 and recovers not one dollar more in the 360-day case the lenders test ☒ **CORRECT**
- C. take neither and rely on the 6,000,000 of cost-overflow support, which covers the 4,104,000
- D. take the rate, since a damages cap is a matter for counsel and cannot be priced

Rationale: $4,800,000/24,733.33 = 194.07$ days, so at 360 days recovery is the cap on either concession and the uncovered 4,104,000 does not move; the rate helps only for slips shorter than 194 days. A is the right calibration aimed at the wrong lever for the scenario the credit committee actually runs — a defensible answer that buys nothing in the case being tested. C is available and is part of what the support exists for, but it converts a contractor obligation into sponsor cash at par and consumes 68.4 % of a pool that must also absorb overruns (5.2.3). D is false as stated: the cap's economic effect is a number, and it has just been priced. Whether a given rate or cap is enforceable as drafted — as liquidated damages rather than as a penalty — is indeed a question for qualified counsel in the governing jurisdiction, and it is a question worth asking; but it is not a reason to leave the cap unpriced, and it is the cap rather than the rate that the 360-day case turns on.

MCQ 5.4-F [5.4.4 · Evaluation] COD falls due in 30 days. The readiness gate reports the revenue meter not yet accepted by the offtaker and the permit to operate outstanding. The commercial team wants to declare COD on the contractual date to start the 17,733.33 per day of CFADS the delay is costing. Holding COD for 30 days costs 742,000 of economic cost, of which delay damages recover 600,000, leaving 142,000 with the SPV. The better recommendation is:

- A. declare COD, since 532,000 of forgone CFADS over 30 days outweighs a 142,000 net holding cost
- B. hold COD until the readiness gate clears, because 142,000 is the entire price of holding while declaring transfers a contractor-owned, damages-covered problem to equity at the moment the covenant regime begins ☒ **CORRECT**
- C. declare COD and agree with the contractor that delay damages continue to accrue until the readiness items close
- D. hold COD and capitalise the 210,000 of construction interest into the facility, so equity funds nothing

Rationale: $30 \times 24,733.33 = 742,000$ against $30 \times 20,000 = 600,000$ leaves 142,000, while an unaccepted meter and a missing permit to operate put the tariff and the first covenant test at risk on a plant that is otherwise performing (5.4.4). A compares the revenue with a cost the contractor is largely paying, which is the arithmetic that makes early declaration look attractive. C is the incoherent option: damages run to COD, so declaring it extinguishes the recovery being relied on. D is a real structural choice and the weaker one — capitalising 210,000 lifts the instalment to 5,034,683.41, takes DSCR from 1.2743 to 1.2680 and cuts annual covenant headroom from 372,438 to 342,380, a loss of 30,058 a year for the whole twelve-year loan life, to avoid a one-off 142,000.

MCQ 5.4-G [5.4.3 · Evaluation] Kestrel completes at 97 % of guaranteed output: **CFADS** falls from 6,384,000 to 6,112,200, **DSCR** to 1.2201, and a buy-down of 1,788,158 restores the originally sized 1.2743. The project director proposes reporting the position as restored. The soundest professional judgement is that:

- A. it is restored: sized coverage is back to 1.2743, so the project is as underwritten
- B. the buy-down restores the **lenders'** position only; equity has permanently lost 271,800 a year and holds a smaller loan, and the output shortfall at which the performance-damages cap is exhausted must be established and bankability tested there ✓ CORRECT
- C. the buy-down over-compensates, because debt falls by 1,788,158 while annual cash falls by only 271,800
- D. no buy-down is needed, because 1.2201 still clears the $1.20 \times$ covenant

Rationale: a buy-down is calibrated to the lenders' coverage, not to the sponsors' return (5.4.3). C compares a capital sum with an annual flow: at constant coverage debt is proportional to **CFADS**, so $42,000,000 \times 271,800/6,384,000$ is exactly the adjustment that restores the ratio. D is the dangerous answer because it is arithmetically true and leaves the project 100,638 of annual cash from a breach, 73.0 % of its headroom consumed, with the cap question unasked.

MCQ 5.4-H [5.4.1 · Comprehension] A sponsor asks what an EPC wrap changes, given that the same works are being built either way. The best statement of what it achieves is that it:

- A. reduces the cost of the works, because one contractor buys the packages more cheaply
- B. makes completion risk bankable by placing fixed-price, date-certain responsibility for the whole works with one contractor, so interface risk sits there rather than with the SPV — at the price of a wrap premium for risk the contractor does not wholly control ✓ CORRECT
- C. removes completion risk from the project entirely
- D. transfers completion risk to the lenders, who price it in the margin

Rationale: the wrap is read here only as what makes completion risk bankable — lenders face a single counterparty (5.4.1) — and it is not free: a contractor pricing interface and schedule risk charges for it, which is why a multi-package alternative must be compared on interface exposure and price together. A inverts the usual outcome, since splitting packages is what tends to price lower. C forgets that damages and guarantees are worth only the guarantor's balance sheet. D describes no part of a limited-recourse structure, in which lenders take completion risk only where support runs out.

■ SELF-CHECK — KA 5.4

1. What two costs make up a COD slip, and which is more often omitted? — Extra interest on drawn debt (7,000 per day) and forgone **CFADS** (17,733.33 per day); the interest is omitted, and it is the more certain of the two.
2. Why does a 3 % output shortfall cut **EBITDA** by 4.53 %? — Operating leverage: 85 % of cash operating cost is fixed, so **EBITDA** falls faster than output ($1.510\times$), and **CFADS** with it — by 4.26 % once tax and working capital are taken.
3. Why can declaring COD early be the most expensive decision in a project? — It converts a construction problem the contractor owns and damages cover into an operating problem equity owns and nothing covers, at the moment the covenant regime begins.

— Advanced topics — Domain 5

5.A.1 Development as a portfolio of real options, and the discipline of abandonment

Volatility increases option value: a project whose eventual value is highly uncertain is worth more to hold than one with the same expected value and no uncertainty, because the downside can be abandoned and the upside cannot be capped — the honest financial reason to hold some genuinely speculative pursuits, valid only while the sponsor can still walk away cheaply. More important, **the option dies as commitment accrues:** a bid bond posted, an equipment slot reserved, a jurisdictional reputation staked, each converts option into obligation, so the abandonment decision belongs before each of them, exactly where 5.1.1 puts the gates. The pathology to name is the **sunk-cost carry:** a project retained because 10,000,000 has been spent. Spent money is relevant only to the post-mortem; the question is whether the remaining spend is justified by the remaining probability — the 14.83 % breakeven of 5.3.1, so low that a disciplined programme needs a second, categorical rule: **kill on a fatal condition regardless of expected value.**

5.A.2 Conditions precedent: the bankability list made contractual

The conditions of KA 5.3 become **conditions precedent** (CPs) in the finance documents — the itemised, evidenced list satisfied before first drawdown — and reading a CP schedule as the bankability test in contractual form converts judgment into a critical path with named owners. **CPs are ordered by dependency, not importance:** a permit requiring a land instrument, requiring a board resolution, requiring a shareholders' agreement amendment is a four-link chain whose duration is the sum, so the close date is set by the longest chain rather than the hardest item. **The categories behave differently:** sponsor CPs (corporate authorisations, equity commitments, credit support) are within the group's control and therefore forgivable in timetable terms, while third-party CPs (permits, offtaker approvals, letters of credit from banks that are not the lenders) are not — each is the kind of timetable risk that made Case study B's eleven weeks. And **waived CPs are not satisfied CPs:** a condition waived to permit close, or converted into a post-close undertaking, remains open with a deadline and a consequence, and the register must track it past close, because Domain 10's covenant regime will test it and Domain 13's close checklist will be audited against it.

5.A.3 The reviewer's bankability eye

Invariants to test on any development or bankability paper. **The conjunction is computed, not averaged,** with its independence assumption stated (5.3.1). **The weakest condition is identified and resourced** — the marginal-gain ranking exists, is current, and matches the work plan. **Development cost is stated per closed project across the portfolio,** with the breakeven close rate on the page (5.1.2). **Every gate's option cost is quantified,** not just its study cost (5.1.3). **Committed capital, not subscribed equity, is the exposure figure,** with the liability basis in the document's own words (5.2.3). **Contracted revenue tenor exceeds loan tenor with margin,** and the offtaker's credit — not merely its signature — has been assessed (5.3.2). **The consent and land registers cover corridors, not only the site,** and permits to operate are separated from permits to construct (5.3.3, 5.4.4). **Delay damages are calibrated to interest plus forgone CFADS on the facility's day-count convention,** with the cap-binding day stated (5.4.2). **Performance guarantees are converted from output percentages into cash through operating leverage,** and the buy-down is computed as debt × the proportional CFADS shortfall (5.4.3). **Every capitalised construction cost is traced to its coverage consequence** — headroom after the event, not

before. And **every condition has an owner, a date, an evidence reference and a named verifier**, the single discipline separating a bankability assessment from an opinion.

— Industry variations — Domain 5

- **Water and desalination (Kestrel's sector).** Availability-based offtakes with a public or utility payer make the revenue condition strong and move the battle to **consents, water source and discharge rights, and linear assets** — intake, outfall and pipeline corridors, where Case study A's tenure failure lives. Technology is usually proven, so the first-of-a-kind premium is rare and expensive when it appears.
- **Contracted power and renewables.** The binding conditions are **grid connection and curtailment terms** — a queue position is a development asset with a value and a date — and increasingly storage and shaping obligations that turn a simple offtake into an availability product. Portfolios are large and cheap per pursuit, so the funnel of 5.1.2 runs at far higher screened counts and lower close rates.
- **Transport concessions.** Land assembly and route consent dominate the timetable; **traffic and demand studies** substitute for the offtake and are diligenced as such; and public procurement makes the **bid window a hard date** — the case in which 5.1.3's option cost most often defeats a good gate.
- **Digital infrastructure.** Power availability and grid capacity are the critical consents, tenant credit is the offtake condition, and **short asset lives** thin the tail Domain 10's **PLCR** measures. Sponsor groups are frequently three-party with a thin local holder — Case study B's shape.
- **Oil, gas and mining.** Resource definition replaces the offtake as the primary condition, revenue is usually **merchant**, and social licence and closure obligations extend the consent set decades beyond the loan. Development spend per pursuit is an order of magnitude larger and close rates correspondingly lower, making the portfolio discipline of 5.1.2 the whole business rather than an overhead on it.
- **Social infrastructure PPPs.** Conditions are relatively standardised and the payer is usually a public authority, so bankability turns on **contract precedent and affordability approval** rather than technology; the risk is political and budgetary, and termination-compensation provisions do more of the credit work than anything in the physical asset.

— Case study — Domain 5: the easement nobody registered (water)

Situation. Kestrel's feasibility study cleared the plant site — a 14-hectare coastal parcel on a long lease — and reported the **land and site tenure condition satisfied at 0.95**. The project's 4.6 km product-water pipeline crossed eleven third-party parcels under easements granted to the host municipality in an earlier scheme. Nine were registered. Two, covering **1.8 km through a single agricultural holding**, existed only as a decades-old exchange of letters, and the holding had since been sold twice. The bid was submitted, preferred-bidder status awarded, and the defect surfaced in **lender legal diligence eleven weeks before scheduled close**.

What happened. The transaction stopped: lenders would not treat an unregistered corridor right as security-worthy, and no title insurance was available on terms the credit committee would accept. Three options existed — negotiate fresh easements with an owner who now knew the project's position, pursue a statutory route through the municipality in an election period, or **re-route** the 1.8

km along an existing road reserve. The sponsors re-routed, at an additional capital cost of **1,400,000** and a **nine-month** delay to close and therefore to COD. The concession's expiry had been fixed at award, so the operating period shortened rather than shifting.

The arithmetic. Discounting quarterly at 8 % (quarterly rate 1.942655 %, **CFADS** 1,596,000 per quarter, concession 108 quarters from the original scheduled close), the operating stream was worth **60,150,401** on the original timetable and **56,199,935** with COD nine months later — a present-value loss of **3,950,466**, or **6.57 %** of the stream. The 3,600,000 of feasibility and transaction spend already at risk was carried nine months at the sponsors' 12 %, costing **319,368**. With the re-route, the defect cost **USD 5,669,834** — **35.0 %** of Domain 4's entire project **NPV**. A title-and-consents review at the feasibility gate, of exactly the kind priced in Worked example 5.1.3, would have cost **180,000**: the defect cost **31.5 times** the review that would have found it, and would have found it while re-routing was a design choice rather than a crisis.

How it resolved. Close occurred nine months late on the original 42,000,000 / 18,000,000 structure, the 1,400,000 re-route being absorbed by construction contingency inside the unchanged 60,000,000 capital budget, so neither the debt nor the equity ticket moved. Lenders required as a condition precedent a **complete registered-title schedule for every corridor parcel** with counsel's opinion. The sponsor group changed two things permanently: the feasibility gate acquired a mandatory corridor-tenure review for every linear asset, run **concurrently** with technical feasibility so that it adds no elapsed time (the 5.1.3 remedy), and the bankability register stopped recording "land" as one condition, splitting it into **site tenure** and **corridor tenure** with separate probabilities and owners.

What the domain teaches here. A condition assessed at 0.95 was two conditions, one of them near zero, and the conjunction (5.3.1) could not reveal that because the register's granularity was wrong. Bankability failures are rarely failures of judgment about a known condition; they are failures to have decomposed a condition into the things that must independently be true. And the gate arithmetic of 5.1.3 is vindicated as such arithmetic usually is — not by the gates held, but by the 5,669,834 paid for the one that was not.

— Case study B — Domain 5: the ten per cent that could not fund (digital infrastructure)

Situation. A **240,000,000** hyperscale data-centre campus was developed by a three-sponsor consortium: an anchor operator at **55 %**, an infrastructure fund at **35 %** and a local partner at **10 %** contributing land assembly, grid liaison and permitting. Funding was **70/30** — **168,000,000** of senior debt and **72,000,000** of equity — with a **several cost-overrun support of 10 % of capital cost** subscribed pro rata, so committed capital was **52,800,000 / 33,600,000 / 9,600,000**, the local partner's comprising 7,200,000 of base equity and **2,400,000** of support.

What happened. Grid works and a mid-construction shift to higher-density cooling, to meet the anchor tenant's revised rack plan, produced a **16,000,000** overrun. Support was called pro rata: **8,800,000** from the operator, **5,600,000** from the fund, **1,600,000** from the local partner. The partner could not fund; its balance sheet was committed elsewhere and its 2,400,000 support had been accepted at close on a parent undertaking rather than a bank letter of credit. Under the shareholders' agreement the operator funded the partner's share, credited at a **punitive 1.25× conversion**.

The arithmetic. Post-overrun equity became **50,400,000** (operator: 39,600,000 + 8,800,000 + 1,600,000 × 1.25), **30,800,000** (fund) and **7,200,000** (partner), totalling **88,400,000** — so shares moved from 55/35/10 to **57.0136 % / 34.8416 / 8.1448**. The overrun bought no additional revenue,

so equity value (the present value of distributions, **96,000,000**) was unchanged by it. Had the partner funded, it would hold 10 % of 96,000,000 = 9,600,000 having paid 1,600,000, a net **8,000,000**; having declined, it holds 8.1448 % = **7,819,005** and kept its cash. **Declining therefore cost it 180,995 — 11.3 % of the 1,600,000 it withheld**; at a par conversion the cost would have been **145,455**. For dilution to price the default at the full 1,600,000 the multiplier would have to be **13.50×** — far outside the range such clauses use, and at that level a conversion whose enforceability counsel would have to test before anyone relied on it. The conclusion is uncomfortable and general: **in a small-stake structure, dilution cannot price a funding default**. It is a discount, not a deterrent.

How it resolved. The operator funded, took the dilution credit and — because dilution was inadequate — invoked the agreement's alternative remedy, converting the shortfall into a **shareholder loan at 15 %**, so the partner owed **1,840,000** after one year, **2,116,000** after two and **2,433,400** after three, subordinated to senior debt and repayable from its distributions. The lenders, exposed to the support commitment rather than to the sponsors' internal arrangements, required for the remainder of construction that the partner's undrawn support be **backed by a bank letter of credit**; arranging it took **eleven weeks**, during which the next drawdown was blocked — and that delay was the practical cost of the whole episode.

What the domain teaches here. The 10 % holder is the structural weak point of a sponsor group (5.2.3): smallest number, likeliest to be least creditworthy, able to stop a drawdown for a sum trivial against the project. **Credit support belongs at close, not at default** — the eleven weeks were available at close for a letter-of-credit fee and were paid for in full later. And **remedies must be priced, not assumed**: a group that had computed the 180,995 against 1,600,000 before signing would have known its dilution clause was decorative, and would have negotiated the shareholder-loan remedy, a drag-along or a call option on the defaulting share instead.

— Executive perspective — Domain 5

What a project finance director cannot delegate in this domain:

- **The conjunction, and the ranking that follows.** The joint probability of close, computed and not averaged, with the marginal-gain ranking driving the work plan. A director who accepts "about 90 per cent" from six 90 per cent conditions has accepted a 36-point error (5.3.1).
- **The fatal-condition kill.** Expected value justifies continuing almost anything at a 14.83 % breakeven; only a categorical rule kills a project with an unresolvable condition (5.A.1).
- **The development portfolio's economics.** Cost per closed project (7,400,000, not 2,400,000), the close rate and the breakeven close rate — the numbers a development budget is defended with (5.1.2).
- **Committed capital and the liability basis.** What the group has actually promised (24,000,000, 40 % of capex, not the 30 % headline), on what basis, and whether the weakest sponsor's share is credit-supported at close (5.2.3, Case study B).
- **The damages calibration.** Whether delay and performance damages are calibrated to interest plus forgone **CFADS** and converted from output percentages into cash, and where each cap binds (5.4.2, 5.4.3).
- **The COD declaration.** It is the director's, taken against evidence of operational readiness rather than a revenue start date, because the covenant regime begins the same day (5.4.4).

— Calculation exercises — Domain 5

Exercise 5.1 A programme screens 60 opportunities at 30,000 each; 15 advance to concept at 200,000 each; 6 enter feasibility and bid at 900,000 each; 3 are carried to close at 1,800,000 each. Each close delivers sponsor value of 11,000,000. Compute programme spend, cost per close, the close rate, the value multiple and the breakeven close rate. Solution. Stage spend $1,800,000 + 3,000,000 + 5,400,000 + 5,400,000 = 15,600,000$; per close $15,600,000/3 = 5,200,000$; close rate $3/60 = 5.0 \%$; portfolio value **33,000,000**, net **+17,400,000**, multiple **2.1154x**; breakeven closes $15,600,000/11,000,000 = 1.4182$, breakeven close rate $1.4182/60 = 2.36 \%$. Common error: dividing only the closing-stage spend by the closes ($5,400,000/3 = 1,800,000$), which prices the winners and ignores the portfolio that produced them — a **65 %** understatement.

Exercise 5.2 Five bankability conditions have probabilities 0.95, 0.90, 0.80, 0.96 and 0.92. Compute the joint probability of close, identify the weakest, and compare the gain from lifting it to 0.92 with the gain from lifting the 0.90 condition to 0.96. Solution. Joint = $0.95 \times 0.90 \times 0.80 \times 0.96 \times 0.92 = 0.6041$ (**60.41 %**), against an arithmetic mean of **90.6 %**. The weakest is 0.80; lifting it to 0.92 multiplies the product by 1.15 for **69.47 %**, a gain of **9.0616 points**. Lifting 0.90 to 0.96 multiplies by 1.0667 for **64.44 %**, a gain of **4.0274 points** — so the weakest link is worth **2.250x** more. Common error: reporting the arithmetic mean (90.6 %) as the probability of close, a 30-point overstatement; the next commonest is ranking by absolute lift (0.12 against 0.06) rather than by proportional lift applied to the whole product.

Exercise 5.3 A 90,000,000 project is funded with 25,000,000 of equity held 40/30/20/10, and the facility requires a several cost-overrun support of 12 % of capital cost subscribed pro rata. State each sponsor's committed capital, the group total as a percentage of capex, and the uplift over headline equity. Solution. Support pool $90,000,000 \times 0.12 = 10,800,000$.

Share	Equity	Support	Committed
40 %	10,000,000	4,320,000	14,320,000
30 %	7,500,000	3,240,000	10,740,000
20 %	5,000,000	2,160,000	7,160,000
10 %	2,500,000	1,080,000	3,580,000

Group committed **35,800,000**, or **39.78 %** of capital cost against a 27.8 % equity headline; the uplift is a uniform **43.2 %** for every sponsor, because support is subscribed pro rata. Common error: quoting the 10 % sponsor's exposure as its 2,500,000 of equity and omitting the 1,080,000 of several support — **30.2 % below** the 3,580,000 a lender will nonetheless call, the same gap that reads as a 43.2 % uplift when taken the other way round.

Exercise 5.4 Debt of 50,000,000 is fully drawn at 7.0 %; annual CFADS would be 8,000,000; delay damages are 25,000 per day capped at 8 % of a 60,000,000 EPC price; 30/360 applies. For a 150-day COD slip compute the daily economic cost, the total cost, damages recovered, the shortfall, and the cap-binding day. Solution. Daily interest $50,000,000 \times 0.07/360 = 9,722.22$; daily forgone CFADS $8,000,000/360 = 22,222.22$; total **31,944.44 per day**. Over 150 days: interest **1,458,333.33**, forgone CFADS **3,333,333.33**, total **4,791,666.67**. Damages $150 \times 25,000 = 3,750,000$, leaving **1,041,666.67**; coverage $25,000/31,944.44 = 78.26 \%$. The cap $60,000,000 \times 0.08 = 4,800,000$ binds at $4,800,000/25,000 = 192$ days. Common error: calibrating the damages

rate on the forgone **CFADS** alone (22,222.22 per day) and omitting the interest, which is **30.43 %** of the daily cost and its most certain component.

Exercise 5.5 A credit committee will size debt at a target **DSCR** of 1.30× on proven technology or 1.50× on a first-of-a-kind configuration. **CFADS** is 8,000,000; the loan runs 14 years at 6.5 % ($AF(0.065, 14) = 9.013842$). Compute debt capacity under each and the equity consequence. Solution. At 1.30×: service $8,000,000/1.30 = 6,153,846.15$, capacity $\times 9.013842 = 55,469,799$. At 1.50×: service **5,333,333.33**, capacity **48,073,826**. The capacity loss is **7,395,973**, to be found as equity — exactly **13.33 %** of the 1.30× capacity, because at constant **CFADS**, tenor and rate the ratio is $1 - 1.30/1.50$. Common error: treating the 0.20 increase in the target ratio as a 20 % reduction in debt, which overstates the loss by roughly 3.7 million; the reduction is 13.33 %.

— Practitioner's toolkit — Domain 5

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 5.T.1 — The bankability condition register

One row per condition, decomposed to the level at which something must independently be true (Case study A's lesson: "land" is at least two rows — site tenure and corridor tenure). Columns: condition · what must be true, in evidential terms · the document that will prove it · owner · target date · dependency · **assessed probability of satisfaction on the timetable**, with assessor and date · the corresponding condition precedent once drafted · status and verifier. Footer, recomputed at every update: **the product of the probabilities** (never the mean), the joint probability of close, and the conditions ranked by **marginal gain** — the next period's work plan. Rule: a condition with no evidential test is not a condition but a hope, and is recorded as such.

Toolkit 5.T.2 — Sponsor commitment and support schedule

One row per sponsor. Columns: equity share · base equity commitment · each support commitment separately (cost overrun, completion, equity commitment letter, O&M or supply guarantee, debt-service undertaking) with its cap and its **liability basis in the words of the document** · **total committed capital** · sunset or release trigger for each obligation · credit support required by lenders and whether it is **in place at close** · the default and dilution mechanic, with **the cost of declining a call computed** for a representative call size (Case study B's 180,995 against 1,600,000). Footer: group committed capital as a percentage of capital cost, and the identity of the weakest credit in the group. Rule: no board approves an equity share without seeing the committed-capital column.

Toolkit 5.T.3 — COD-slip and readiness pack

Two parts, maintained from twelve months before COD. **The slip calculator**: drawn debt $\times$ rate $\div$ day-count (state the convention) = daily interest; annual **CFADS** $\div$ day-count = daily forgone cash; the sum = **daily economic cost**; the damages rate and its **coverage percentage**; the **cap and the day it binds**; the coverage consequence of capitalising the extra interest (new instalment, **DSCR**, covenant trigger, **headroom before and after**); and the structural decision — capitalise or fund with equity — recorded in advance. **The readiness gate checklist**, held before COD is declared: O&M contract executed and operator mobilised · permits **to operate** issued, listed separately from construction permits · initial spares and supply contracts with matching tenor · revenue metering calibrated and accepted by the payer · operating insurance in force with lender endorsements · reserve accounts

funded · model updated to actuals, first covenant test date and compliance certificate scheduled · as-built documentation, warranties and punch list with owners and dates. Rule: **COD is declared against this checklist, by a named person, or it is not declared.**

— Exam preparation — Domain 5

What is assessed. The conjunctive nature of bankability and its arithmetic; development spend as an option premium measured across a portfolio; gate economics adapted to development, where holding costs a forgone option rather than a carry; the SPV's purposes and the limits of its ring-fence; per-sponsor equity, several-liability support and dilution mechanics; the equity bridge's neutrality at the bridge rate; the components of a bankable revenue model; the consent and tenure sets including corridors; the price of unproven technology in lost debt capacity; and the full cost of a COD slip and a performance shortfall, including the coverage consequence.

The calculations to do under time pressure. The product of a condition set and the marginal gain from lifting one condition (5.3.1) · programme spend, cost per close and breakeven close rate (5.1.2) · gate net value and breakeven detection probability (5.1.3) · committed capital per sponsor and the group total as a share of capex (5.2.3) · debt capacity at two target coverage ratios using Domain 10's rule (5.3.4) · daily and total COD-slip cost, damages coverage and the cap-binding day (5.4.2) · the new instalment, **DSCR** and headroom after capitalising construction interest (5.4.2) · **EBITDA** and **CFADS** under an output shortfall with a fixed/variable split, and the buy-down that restores sized coverage (5.4.3).

The traps.

- Averaging condition probabilities instead of multiplying them — a 36-point error (5.3.1, MCQ 5.3-A).
- Ranking condition effort by absolute probability rather than marginal gain (5.3.1, MCQ 5.3-B).
- Quoting development cost per deal rather than per close (5.1.2, MCQ 5.1-A).
- Counting a gate's study cost but not its option cost (5.1.3, MCQ 5.1-D).
- Treating subscribed equity as sponsor exposure and omitting several support (5.2.3, MCQ 5.2-A).
- Reading several liability where the document says joint and several, or the reverse (5.2.3, MCQ 5.2-B).
- Presenting the equity bridge's saving as project value when it is neutral at the bridge rate (5.2.4, MCQ 5.2-C).
- Treating a signed offtake as a satisfied revenue condition without testing the offtaker's credit (5.3.2, MCQ 5.3-D).
- Applying a change in target **DSCR** to the principal as though ratio points were percentages (5.3.4, MCQ 5.3-C).
- Calibrating delay damages on the forgone **CFADS** alone and omitting interest during construction — 28.3 % of the daily cost on Kestrel, 30.43 % in Exercise 5.4 (5.4.2, MCQ 5.4-A).
- Ignoring the damages cap, which is where the exposure actually sits (5.4.2, MCQ 5.4-B).
- Forgetting that capitalised construction interest is a permanent coverage cost (5.4.2, MCQ 5.4-C).
- Sizing a buy-down on the annual cash shortfall rather than on debt × the proportional **CFADS** shortfall (5.4.3, MCQ 5.4-D).

How the domain connects. Domain 4 supplied the value this domain tests for financeability, and Domain 1 the recourse spectrum and SPV that make limited-recourse structures possible. Forward: Domain 6 models the structure assembled here; Domain 7 builds the revenue models 5.3.2 only

classifies; Domain 8 supplies the estimate classes, contingency and delay arithmetic behind the development budget and the overrun support; Domain 9 supplies the capital sources, including the concessional money that can buy down a first-of-a-kind premium; Domain 10 sizes and covenants the debt these conditions permit; Domain 11 allocates the risks the conditions represent and Domain 12 documents them; Domain 13 converts the condition register into conditions precedent and closes; Domain 14 monitors the construction whose slip 5.4.2 prices. PML-AI Domain 3 (KA 3.3.1) is the delivery twin of this domain's gate economics, and the difference between them — elapsed time against forgone option — is the most useful single idea a finance leader can carry between the two disciplines.

— Domain 5 summary

Bankability is a **conjunction**, and that is the domain's whole argument. Kestrel's six conditions — offtake 0.92, permits 0.90, land 0.95, technology 0.88, EPC wrap 0.93, financing 0.85 — average **90.5 %** and multiply to a **54.72 %** probability of close; lifting the weakest to 0.95 adds **6.4375 points** while lifting the strongest to 0.98 adds **1.7280**, a **3.7255×** difference that reorders the whole work plan; and a 90 % joint probability would require every condition at **98.26 %**, which is why bankable projects are projects with no open condition rather than projects with good ones. The spend that buys those conditions is an **option premium** measured across a portfolio: 40 screened opportunities, USD 14,800,000 of programme spend and two closes make Kestrel's honest origination cost **7,400,000**, not the 2,400,000 on its own charge code, against a **breakeven close rate of 2.29 %** on an achieved 5.0 %. A feasibility gate costing 180,000 against a 40 % fatal-flaw rate and a 3,300,000 late-discovery waste is worth **810,000 per project** and pays down to a **13.64 %** detection rate — but an 8-week delay carrying a 10 % chance of missing a bid window costs **1,617,936**, turning the same gate **negative by 807,936** and setting a **5.01 %** breakeven window-miss probability: in development, elapsed time is priced as a lost option, not a carrying cost. The group behind Kestrel's 18,000,000 has committed **24,000,000 — 40.0 % of capital cost** — as 13,200,000 / 8,400,000 / 2,400,000 on a several basis, every sponsor exposed **33.3 %** beyond its equity share and each exposed to the whole 6,000,000 pool if the basis becomes joint and several; its equity bridge at 5.5 % is **exactly value-neutral at the bridge rate** (17,530,806 either way), worth **1,480,688** only because the sponsors discount at 12 %. Unproven technology has a price: **1.45×** **instead of 1.30×** **costs 4,259,082** of debt capacity, payable in equity. A slip in the commercial operations date costs **24,733.33 per day** — 7,000 of interest on drawn debt and 17,733.33 of forgone **CFADS** — so a 180-day slip costs **4,452,000** against damages of 3,600,000, leaves **852,000** with equity, and if its interest is capitalised cuts covenant headroom from **372,438 to 192,090.85** for the whole loan life, with the cap binding at **day 240** beyond which every day is the SPV's; in value terms the same slip destroys **3,918,897**, 24.2 % of the project **NPV**, and 948,988 after damages. A 3 % output shortfall cuts **CFADS** to **6,112,200** through **1.510×** operating leverage, consuming **73.0 %** of covenant headroom, and is repaired by a buy-down of **1,788,158** — debt times the proportional **CFADS** shortfall. Case study A paid **5,669,834**, 35.0 % of the project's **NPV**, for an unregistered 1.8 km easement a 180,000 review would have found; Case study B proved a 1.25× dilution clause prices a 1,600,000 funding default at **180,995** and would need a **13.50×** multiplier to price it properly — so credit support belongs at close, not at default. Domain 6 now models the structure this domain assembled; Domain 10 sizes the debt its conditions permit.

06

DOMAIN 6

Financial Modelling and Model Governance

— Why this domain exists

Every number in Domains 3 to 5 and 10 came out of a model, and not one of those domains examined the model. Domain 4 decided to build on an **NPV** of **+16,179,360**. Domain 10 negotiated debt capacity against a **CFADS** of **6,384,000** and a **DSCR** of **1.2743**. Domain 5 priced a commercial-operations-date slip at **24,733.33** a day. Each is the output of one workbook, produced by one analyst, reviewed by whoever had time — and each has been quoted without its basis, its horizon or its checks attached. That is the gap this domain closes.

The central claim is worth stating plainly: **a financial model's authority comes from its architecture and its checks, not from its answers**. Two competent analysts modelling the same project on the same contracts will produce different numbers, and the difference will almost never be arithmetic. It will be basis (pre-tax or post-tax, accrual or cash, before or after working capital), horizon (fifteen years of evaluation or twenty-five of concession), convention (annual or quarterly periods, interest on opening or average balances) and case (the sponsor's escalation or the lender's flat line). On Kestrel's own figures one project supports five arithmetically correct net present values spanning **USD 29,545,516** — which is why a model output quoted without its basis and horizon is not information but decoration.

Learning objectives. After this domain a candidate can: design a three-block architecture with a single timeline and defend each convention chosen; build a sources-and-uses statement in which capitalised interest is computed rather than assumed, identify its balancing line and test that line against policy; quantify how period length and interest convention change capitalised interest, the depreciation base and after-tax value; distinguish accounting depreciation from tax allowances and compute the coverage and debt-capacity consequences; build a debt schedule that closes to zero, run a cash waterfall through reserve funding to distributions, and compute an equity return and an equity payback; state and test the six arithmetic invariants a project model must satisfy, explain why a balancing balance sheet is necessary and not sufficient, and localise an error from the check that fails; reconcile two models of one project into a basis bridge; build a one-at-a-time sensitivity table with elasticities, state honestly what it cannot see, and convert ratio headroom into input breakevens; compute the net value, breakeven fee, breakeven error rate and breakeven detection rate of a model audit and show why timing matters more than price; and govern AI-assisted modelling with controls specific enough to fail.

The master model. Kestrel Water SPC continues from Domains 1–5 and 10. Capital cost **USD 60,000,000** funded **70/30** as **USD 42,000,000** of senior debt at **6.0 % over 12 years** (annual instalment **USD 5,009,635.23**; year-one interest **2,520,000**, principal **2,489,635**) plus **USD 18,000,000** of equity. Operating life **25 years**; revenue **12,000,000**, cash operating costs **4,500,000**, **EBITDA** **7,500,000**, depreciation **2,400,000**, **EBIT** **5,100,000**, cash tax **516,000**,

documented first-year **CFADS USD 6,384,000** (6,984,000 before working-capital movements). Coverage at close (Domain 10): **DSCR 1.2743 = LLCR 1.2743, PLCR 1.9431**, covenant cash trigger **6,011,562**, six-month DSRA **2,504,818**. Appraisal (Domain 4): **NPV +16,179,360** at 8 %, **IRR 12.19 %**, **MIRR 9.73 %**, **PI 1.270**. This domain adds the assumptions those chapters did not need and could not do without: the **eight-quarter construction drawdown** funded 70/30 against certified spend, the **EPC price of 48,000,000** (Domain 5) inside a **60,000,000 envelope** whose balancing line is contingency at **3,645,403**, capitalised interest of **2,114,597**, the **2.967 % escalation** that reconciles Domain 4's appraisal to Domain 2's **CFADS**, the DSRA funded from operating cash over two years, and the two cases — sponsor and bank — that every subsequent number has to be labelled against.

KNOWLEDGE AREA 6.1

Model architecture

Topics: 6.1.1 the three-block rule · 6.1.2 the timeline as the model's spine · 6.1.3 basis, horizon and case — the labels without which an output means nothing.

6.1.1 The three-block rule

Definition. A project financial model is organised into three strictly separated blocks: **inputs** (every assumption, each entered exactly once, in one place, with a source), **calculations** (formulae only, no constants), and **outputs** (presentation only, no calculation). Nothing flows backwards: outputs never feed calculations, calculations never contain assumptions, inputs never contain formulae.

Why the separation carries the weight. It is not tidiness; it is what makes a model auditable by a stranger in the time a stranger has. An assumption entered once can be changed once, so a scenario is a switch rather than a search-and-replace across sheets — which is why models without the separation end up with scenarios that differ in ways nobody intended. A calculation block containing no constants can be **read**: any number inside a formula is by construction a defect, so review reduces to scanning for numerals. And an output block that computes nothing cannot disagree with the model, which removes the most damaging class of audit finding — the summary page that no longer ties to the engine behind it.

The cardinal defect is the hard-coded constant. A tax rate typed into a formula, a tariff escalator embedded in a growth row, a debt margin buried in an interest calculation: each is invisible to a reviewer, survives every scenario switch, and produces a model that is stable in the wrong answer. Two further rules earn their place. **One row, one formula, copied across**: a row whose formula changes mid-timeline is invisible in the printed output and usually marks the point where somebody patched a symptom. And **sign discipline stated once and enforced everywhere** — either convention works, and mixing them produces a model that adds a cost to a revenue and balances anyway.

6.1.2 The timeline as the model's spine

Definition. The timeline is a single row of periods with, for each period, its start and end dates, its day count on the stated convention, and a set of mutually exclusive **flags** — construction, operations, loan life, post-loan tail — that every calculation multiplies by instead of testing dates itself.

The flags convert scattered date logic into arithmetic that can be checked by addition. Kestrel's annual model runs **27 periods** — two construction and twenty-five operating — and its quarterly

construction model runs **eight**. The invariants are trivial to state and therefore trivial to test: construction flags sum to the construction period, operating flags to the operating life, no period carries two flags, and all flags sum to the model length. A model in which those four additions hold cannot have a period that is silently both building and operating, which is the defect that puts revenue into a construction quarter or capitalised interest into an operating year.

Periodicity is an economic choice, not a presentation one. Coarser periods do not merely round; they systematically misstate anything that compounds within a period. Worked example 6.2.1 prices this on Kestrel: the same drawdown profile at the same 6.0 % returns capitalised interest of **2,114,597** quarterly and **1,247,352** annually — an understatement of **867,245**, or **41.01 %**, before a single assumption has been challenged.

The conventions that must be stated once, in the inputs block: day count (30/360, actual/360, actual/365 — Domain 5's slip calculation used 30/360 and said so); whether flows arise at period end, start or mid-period; whether interest accrues on the opening or the average balance; and whether the first period is a stub. None is a matter of taste; each changes printed results, and a model that does not state them cannot be reproduced.

6.1.3 Basis, horizon and case

Definition. Every model output carries three labels without which it is meaningless: its **basis** (pre-tax or post-tax; accrual or cash; before or after working capital; levered or unlevered), its **horizon** (the number of periods valued, and what is assumed about value beyond them), and its **case** (which set of assumptions was switched on).

WORKED EXAMPLE

Worked example 6.1.3 — one project, five correct net present values.

1. **Setup.** Kestrel, on the master model. Domain 4 appraised net inflows of **8,900,000** a year for **15 years** against $I_0 = 60,000,000$ at **8.0 %**. Domain 2 documented a first-year **CFADS** of **6,384,000**. The concession's operating life is **25 years**. Reconcile the two figures and value the project on each defensible basis and horizon.
2. **Formula.** Domain 4's present value of inflows is $8,900,000 \times AF(0.08, 15)$. An **EBITDA** stream starting at 7,500,000 and escalating at g has present value $\Sigma 7,500,000 (1+g)^{(t-1)} / (1.08)^t$; solve for the g that reproduces it. Post-tax unlevered free cash flow, with revenue, cash costs and working capital all indexed at the same g and depreciation fixed at 2,400,000, reduces to $FCF(t) = 5,400,000 (1+g)^{(t-1)} + 480,000$ (the second term is the depreciation shield, $0.20 \times 2,400,000$).
3. **Substitution.** $8,900,000 \times 8.559479 = 76,179,360$. Solving the escalating **EBITDA** stream over 15 years at 8 % gives $g = 2.967 \%$, reproducing a present value of 76,180,021 — **661** above Domain 4's 76,179,360, or 0.001 %. Then value $FCF(t)$ at 8 % over 15 and 25 years, at $g = 2.967 \%$ and at $g = 0$.
4. **Result.**

#	Basis	Horizon	Case	NPV at 8 %
1	Pre-tax operating cash (Domain 4)	15 years	escalating	+16,179,360
2	Post-tax, unlevered, after working capital	15 years	$g = 2.967\%$	−1,041,835
3	Post-tax, unlevered, after working capital	25 years	$g = 2.967\%$	+19,875,251
4	Post-tax, unlevered, after working capital	25 years	flat (bank case)	+2,767,684
5	Post-tax, unlevered, after working capital	15 years	flat	−9,670,265

The widest defensible spread is **29,545,516** — from −9,670,265 to +19,875,251 — on one asset, one contract set and one discount rate. 5. **Interpretation.** Not one of those five figures is an error, and the reconciliation proves it: Domain 4's 8,900,000 is precisely what Kestrel's year-one EBITDA of 7,500,000 becomes as a fifteen-year level equivalent at 2.967 % escalation, so the two models agree on the asset and disagree only about what to measure. The spread decomposes cleanly and each component is a decision somebody must own. **Basis** moves the fifteen-year answer from +16,179,360 to −1,041,835: cash tax and working capital cost the project **17,221,195** of present value, and whoever approves an appraisal on a pre-tax basis has approved that omission. **Horizon** moves the post-tax answer from −1,041,835 to +19,875,251: ten further years of a twenty-five-year concession are worth **20,917,086**, so a fifteen-year evaluation of a twenty-five-year asset is not conservatism, it is a valuation of a different asset. **Case** moves the twenty-five-year answer from +19,875,251 to +2,767,684: the lender's refusal to give credit for escalation is worth **17,107,567** of the sponsor's case, which is why escalation is negotiated as hard as margin. The professional consequence is a rule, not a caution: **no NPV, IRR or coverage ratio leaves a model without its basis, horizon and case attached to it in the same sentence.** And the reviewer's habit that follows is the **basis bridge** — a reconciliation from the appraisal number the board remembers to the financing number the lenders enforce, showing every step between them. Kestrel's bridge is four lines long and worth 29.5 million; a project without one is carrying that exposure undocumented.

AI in this KA

Where it earns its place. Architectural conformance is machine-checkable and tedious, the ideal combination: scanning a calculation block for embedded numerals, finding rows whose formula changes mid-timeline, listing inputs referenced from more than one place, testing the flag additions, and diffing two versions into a change list a human can read. A large model has tens of thousands of cells and a reviewer has two days; this is the part of review that should never be done by a person.

Where it must not go. An assistant must not choose the model's conventions, and in practice it will: asked to "build a construction model" it picks an annual timeline with opening-balance interest, because that is the simplest defensible construction — and Worked example 6.2.1 prices that choice at 867,245. Nor may it decide the basis, horizon or case; those are governance decisions with owners, and a model whose horizon was chosen by a tool is a model nobody has approved.

Verification, concretely. Require the tool to output the conventions it assumed as an explicit list, and check that list against the term sheet and the assumption register line by line. Re-derive one period of the timeline by hand — dates, day count, flags — and confirm the four flag additions. For any machine-generated architecture review, confirm a sample of at least ten flagged cells against the workbook before the findings are reported: a false positive in an architecture review costs more credibility than the defect it replaced. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 6.1

Term	Meaning
Three-block architecture	Inputs, calculations, outputs — strictly separated; no back-flow.
Hard-coded constant	An assumption typed inside a formula; invisible to review and immune to scenarios.
Timeline flags	Mutually exclusive period markers (construction, operations, loan life, tail) that calculations multiply by.
Periodicity	Period length; an economic choice because compounding happens within periods.
Basis	Pre/post-tax, accrual/cash, before/after working capital, levered/unlevered.
Horizon	Periods valued, and the treatment of value beyond them.
Case	The named set of assumptions switched on (sponsor case, bank case, downside).
Basis bridge	The documented reconciliation between two models of one project.

■ SAMPLE MCQS — KA 6.1

MCQ 6.1-A [6.1.3 · Analysis] Kestrel's appraisal shows NPV +16,179,360 (pre-tax operating cash, 15 years) and its financing model shows +2,767,684 (post-tax unlevered, flat, 25 years). The correct conclusion is:

- A. the financing model contains an error of 13,411,676
- B. the appraisal is optimistic and should be discarded
- C. both are correct on their stated basis, horizon and case, and the required deliverable is the bridge between them ☒ **CORRECT**
- D. the difference is the interest tax shield

Rationale: Worked example 6.1.3 reconciles them exactly — the appraisal's 8,900,000 is the fifteen-year level equivalent of an EBITDA stream escalating at 2.967 %, and the gap is basis, horizon and case. A and B assume one number must be wrong; D names a term that is absent from both, since each figure here is unlevered.

MCQ 6.1-B [6.1.2 · Application] Kestrel's construction spend is modelled with the same profile and the same 6.0 % rate on an annual rather than a quarterly timeline, interest accruing on the opening balance in both. Capitalised interest changes from 2,114,597 to:

- A. 2,114,597 — periodicity does not affect a total
- B. 1,247,352, an understatement of 867,245 ☒ **CORRECT**
- C. 2,427,554
- D. 8,458,388

Rationale: Coarse periods ignore intra-period draws, so the opening balance on which interest accrues is far too small (6.1.2, Worked example 6.2.1). A assumes periodicity is presentational; C is the quarterly figure on the average-balance convention; D multiplies the quarterly figure by four, confusing periods with rates.

MCQ 6.1-C [6.1.1 · Analysis] A reviewer finds a 20 % tax rate typed inside three calculation formulae rather than referenced from the inputs block. The most serious consequence is:

- A. the model is harder to read

- B. the tax rate cannot be changed
- C. scenario switches silently leave the tax rate unchanged, so every case in the model is internally inconsistent in a way no output reveals ✓ CORRECT
- D. the model will not balance

Rationale: The hard-coded constant survives the scenario switch, so the downside case is run at the base-case tax rate and nothing on any output page says so (6.1.1). A understates it; B is false — it can be changed, three times, which is the problem; D is wrong, because a consistent wrong number balances perfectly (6.4.1).

MCQ 6.1-D [6.1.1 · Comprehension] A modeller adds a subtotal formula to a summary page and defends it: "it is only a sum". The statement that best conveys why the three-block rule forbids it is:

- A. spreadsheets round subtotals differently from the cells beneath them
- B. an output block that computes anything can disagree with the engine behind it, and a summary page that no longer ties to the model is the most damaging class of audit finding ✓ CORRECT
- C. it enlarges the file and slows recalculation
- D. subtotals belong in the inputs block, where they can be changed in one place

Rationale: the separation exists so that each block can be read for one kind of defect — inputs for wrong assumptions, calculations for embedded constants, outputs for nothing at all, because they compute nothing (6.1.1). A invents a rounding problem; C is a performance claim, not the principle; D inverts the architecture, since the inputs block holds no formulae.

MCQ 6.1-E [6.1.3 · Evaluation] A board paper reports "NPV +16,179,360, IRR 12.19 %" with no labels. The financing model shows +2,767,684 post-tax unlevered over 25 years on the flat case, and an unlevered post-tax IRR of 8.54 % against an 8 % hurdle. All four corrections below are legitimate. Which most changes the decision the board is being asked to take?

- A. attach basis, horizon and case to both figures, as the standing rule requires
- B. state that basis alone — cash tax and working capital — costs 17,221,195 of present value over the fifteen-year horizon
- C. put the twenty-five-year post-tax flat case in front of them — +2,767,684, and an asset return of 8.54 % against an 8 % hurdle — because that is the basis on which the decision is close ✓ CORRECT
- D. disclose the full defensible spread of 29,545,516, from −9,670,265 to +19,875,251

Rationale: A is the standing rule and its breach is why the defect arose, but a labelled +16,179,360 still tells the board a comfortable story; B is one of the three components of the gap and leaves horizon and case unaddressed; D discloses without recommending and invites a board to choose its own number from a range. Only C changes what the board is deciding, by showing the basis on which the asset barely clears its hurdle (6.1.3, 6.3.3) — after which the bridge, the labels and the spread are all supporting material.

MCQ 6.1-F [6.1.2 · Evaluation] An assistant is asked to build Kestrel's construction model and, unprompted, chooses an annual timeline with interest on the opening balance. Capitalised interest comes out at 1,247,352 against the quarterly opening-balance figure of 2,114,597 — an understatement of 867,245, or 41.01 %. The modeller observes that every check in the model passes. The soundest position is that:

- A. the choice is acceptable, because both conventions are defensible and the checks pass

- B. periodicity and the interest accrual base are economic choices with a named owner, must be stated in the conventions sheet, and here have understated the depreciable base by 867,245 as well as the interest — a defect no check in the model can see ✓ CORRECT
- C. the annual timeline is wrong and a quarterly one is always required
- D. the difference is immaterial at 3.52 % of the envelope

Rationale: an assistant must not choose the model's conventions, and this is the choice it makes (6.1.2, and the AI boundary in KA 6.1): the 41 % error needs the coarse timeline and the opening-balance base together, since an annual model on average balances lands within 367,022 of the quarterly answer. B is sounder than C because the pairing, not the period length, is the defect — and the understatement propagates, cutting annual depreciation by 34,690 and the present value of the tax it shelters by 74,061. A is the reasoning that lets a convention error survive review; D misquotes a share of the envelope as a measure of a 41 % error in one line.

■ SELF-CHECK — KA 6.1

1. State the four additions that test a timeline. — Construction flags sum to the construction period; operating flags to the operating life; no period carries two flags; all flags sum to the model length.
2. Why is a hard-coded constant worse than a wrong constant? — A wrong constant is visible in the inputs and can be challenged; a hard-coded one is invisible, immune to scenarios and therefore stable in the wrong answer.
3. State the three labels every model output must carry. — Basis, horizon, case (6.1.3); without them the spread on Kestrel is 29,545,516 and the number conveys nothing.

KNOWLEDGE AREA 6.2

Construction and operating models

Topics: 6.2.1 sources and uses, and capitalised interest · 6.2.2 the operating model and the articulation check · 6.2.3 depreciation, tax allowances and the line most often modelled wrongly.

6.2.1 Sources and uses, and capitalised interest

Definition. The **sources-and-uses statement** lists everything the project must pay for between mandate and commercial operations (uses) against everything that funds it (sources), and the two totals are identical by construction. **Interest during construction (IDC)**, or capitalised interest, is the interest accruing on debt drawn before the asset earns revenue; it is a use of funds like any other, is itself funded, and enters the depreciable asset base.

The identity and the balancing line. Sources equal uses is an identity, not a check — a model can always be made to satisfy it. What makes it informative is knowing **which line balances**. The funding envelope is fixed first, by what sponsors will commit and lenders will lend, and one use absorbs the residual: usually contingency, sometimes owner's costs. The discipline has three steps: let one line balance; **test that line against policy** (is the resulting contingency inside the band lenders require for this technology and contract structure?); and if it is not, the envelope is wrong, not the table. One corollary catches plugged tables at a glance: **the balancing line is never a round number**.

WORKED EXAMPLE**Worked example 6.2.1 — Kestrel's construction funding, and what the timeline costs.**

- Setup.** A **60,000,000** envelope funded **70/30** — 42,000,000 senior debt at 6.0 %, 18,000,000 equity — with every use, capitalised interest included, funded in that proportion against certified spend. Committed uses: EPC price **48,000,000** (Domain 5), owner's costs and land **3,600,000**, capitalised development costs **1,800,000**, arrangement and financing fees at 2.0 % of the facility, **840,000**. Construction runs **eight quarters** with a certified spend profile of **6, 9, 13, 16, 17, 15, 13 and 11 per cent**. Interest accrues quarterly at 6.0 %/4 on the **opening** debt balance (draws treated as made at period end). Fees and development costs are funded at financial close. Compute capitalised interest, the balancing contingency, and the cost of running the same model annually.
- Formula.** For each quarter: $\text{interest} = \text{opening debt balance} \times 0.015$; $\text{funding requirement} = \text{certified spend} + \text{interest}$; $\text{debt draw} = 0.70 \times \text{requirement}$; $\text{equity draw} = 0.30 \times \text{requirement}$; $\text{closing balance} = \text{opening} + \text{debt draw}$. Contingency solves $\text{fees} + \text{development} + \text{EPC} + \text{owner's costs} + \text{contingency} + \text{IDC}(\text{contingency}) = 60,000,000$, and the profile applies to the **certified-spend base** — EPC plus owner's costs plus contingency.
- Substitution.** Close: requirement 2,640,000, debt draw 1,848,000. The certified-spend base solves to **55,245,403**, so quarter 1's 6 % is 3,314,724. Quarter 1: $\text{interest} = 1,848,000 \times 0.015 = 27,720$; $\text{requirement} = 3,314,724 + 27,720 = 3,342,444$; debt draw 2,339,711; closing balance 4,187,711. Iterating to quarter 8 gives a closing balance of exactly 42,000,000 and cumulative equity of exactly 18,000,000.
- Result.**

Uses	USD	Sources	USD
EPC contract price	48,000,000	Senior debt drawn	42,000,000
Owner's costs and land	3,600,000	Equity contributed	18,000,000
Capitalised development costs	1,800,000		
Arrangement and financing fees (2.0 %)	840,000		
Contingency (balancing line)	3,645,403		
Interest during construction	2,114,597		
Total uses	60,000,000	Total sources	60,000,000


Capitalised interest is **3.52 %** of the envelope. Contingency is **7.59 %** of the EPC price. On an **average**-balance interest convention IDC rises to **2,427,554** (+312,957); on an **annual** timeline with opening-balance interest it collapses to **1,247,352** (−867,245, or −41.01 %); on an annual timeline with average-balance interest it is **2,481,619**. 5. **Interpretation.** Three results leave this example. **The convention is worth more than most of the assumptions people argue about.** A 41 % swing in capitalised interest from period length alone dwarfs a 10-basis-point margin negotiation, and it is invisible in every output the model prints. It also propagates: 867,245 of understated IDC understates the depreciable base by the same amount, annual depreciation by **34,690**, and the present value of the tax it shelters — 20 % over 25 years at 8 % — by **74,061**. Small, but silent: a reviewer finds it in one line and a board never sees it. **The pairing of a coarse timeline with an opening-balance convention is the defect, not either choice alone.** An annual model on average balances lands within 367,022 of the quarterly answer, so the 41 % error requires both mistakes together — which is why convention lists must be read as a set. **And the balancing line is**

evidence. Kestrel's 3,645,403 of contingency is 7.59 % of the EPC price, inside the band a lender would expect for proven water-treatment technology under a full EPC wrap (Domain 5, KA 5.4.1; Domain 8, KA 8.1.2 tests that percentage against estimate class), so the envelope is credible. Had the residual come out at 2 %, the correct response would not have been to accept a thin contingency but to conclude that a 60,000,000 envelope does not fund this project — a financing conversation, not a modelling one. **Contingency is what is left, and what is left must still be defensible;** the arithmetic cannot tell you which of those two is binding.

Every use is funded 70/30, and capitalised interest is a use like any other

Blue: certified construction spend. Crimson: interest during construction, 2,114,597 in total — 3.52 % of the 60,000,000 envelope

The same profile on an annual timeline with opening-balance interest returns 1,247,352 — an understatement of 867,245, or 41.01 %



Sources 60,000,000 = uses 60,000,000, and the balancing line is the contingency: 3,645,403, or 7.59 % of the EPC price

Fig 6.2.1 — Construction funding and interest during construction

6.2.2 The operating model and the articulation check

Definition. The operating model produces, for every operating period, an income statement, a balance sheet and a cash-flow statement that **articulate** — each derived from the same calculations, so that the three cannot disagree — and from that cash-flow statement it derives **CFADS** on the facility's documented definition.

Domain 2 built the three statements and Domain 10 built the ratios; the modelling content here is the linkage, and one identity does most of the work. Where interest paid is classified in operating cash flow, **CFADS equals operating cash flow plus interest paid** — because **CFADS** is struck before all debt service and operating cash flow is struck after the interest half of it. That single line converts **CFADS** from an assertion into something a reviewer can tie to a statement, which is the whole point of building the statements at all.

WORKED EXAMPLE**Worked example 6.2.2 — Kestrel's first operating year, proved three ways.**

- Setup.** Opening balance sheet at the commercial operations date: plant 60,000,000, cash nil, debt 42,000,000, equity 18,000,000. Year one: revenue 12,000,000, cash operating costs 4,500,000, depreciation 2,400,000, interest 2,520,000, tax at 20 % of taxable profit, receivables up 900,000, payables up 300,000. Debt service 5,009,635.23 of which principal 2,489,635.23. The facility requires a six-month DSRA of **2,504,818**, funded from operating cash in two equal annual instalments of **1,252,409**, ranking above distributions (Domain 10, KA 10.3.3). Distributions are the residual, subject to the 1.20× test.
- Formula.** $EBITDA = \text{revenue} - \text{cash costs}$; $EBIT = EBITDA - \text{depreciation}$; taxable profit = $EBIT - \text{interest}$; operating cash flow = net income + depreciation – $\Delta \text{receivables} + \Delta \text{payables}$; $CFADS = \text{operating cash flow} + \text{interest paid}$; distributable cash = $CFADS - \text{debt service} - \text{reserve funding}$; closing cash = operating cash flow – principal – distributions.
- Substitution.** $EBITDA$ 7,500,000; $EBIT$ 5,100,000; taxable profit 2,580,000; tax 516,000; net income 2,064,000. Operating cash $2,064,000 + 2,400,000 - 900,000 + 300,000$. $CFADS$ $3,864,000 + 2,520,000$. Distributions $6,384,000 - 5,009,635.23 - 1,252,408.81$.
- Result.** Operating cash flow **3,864,000**; $CFADS$ **6,384,000** — reconciling to the documented figure exactly; $DSCR$ **1.2743**; distributable cash **121,956**.

Closing balance sheet	USD		USD
Plant, net	57,600,000	Payables	300,000
Receivables	900,000	Senior debt	39,510,365
Cash (restricted, DSRA)	1,252,409	Equity	19,942,044
Total assets	59,752,409	Total	59,752,409

- Interpretation.** The balance sheet balances to the cent, closing cash equals the DSRA balance, and $CFADS$ ties to the cash-flow statement through the interest line — three independent confirmations of internal consistency. What the year says about the project is more interesting than any of them. Equity receives **121,956** in its first operating year: **0.68 %** of the 18,000,000 contributed, on a project with a healthy $DSCR$ and a positive NPV . That is not distress, it is the ordinary arithmetic of a leveraged project with a reserve to build, and it is the number sponsors most reliably fail to model before close — Domain 10's Case study B is the same error with a board attached. Three consequences follow. **Reserve funding is a claim on early cash, and early cash is all the equity has:** a distribution forecast struck before reserve funding is an aspiration. **The residual is where modelling risk concentrates** — the distribution's elasticity to revenue is **73.8** against the $CFADS$ elasticity of 1.4098, so the equity line is about **52 times** more revenue-sensitive than the coverage ratio, and a **1.36 %** revenue miss (162,608 of revenue) erases the first-year distribution entirely. And **the restricted-cash label is load-bearing:** the 1,252,409 in the DSRA is on the balance sheet, is not available to the business, and a liquidity statement showing it as cash is wrong in exactly the way that matters.

6.2.3 Depreciation, tax allowances and the line most often modelled wrongly

Definitions. Accounting depreciation allocates the cost of an asset over its useful life under the applicable financial-reporting framework — Kestrel's 60,000,000 over 25 years, straight line, **2,400,000** a year. Tax depreciation, or capital allowances, is what the tax authority permits to be

deducted, on its own profile and its own base. **Cash tax** is what is actually paid. They are three different numbers, and only the last enters **CFADS**.

Domain 2 established the principle (KA 2.A.1) and named the standard finding: modelling accounting tax as if it were cash tax. This is where it is priced.

WORKED EXAMPLE

Worked example 6.2.3 — what a tax assumption is worth.

- Setup.** Kestrel's base model, following Domain 2, assumes tax depreciation equals accounting depreciation — a simplification, chosen for exposition and stated as one. Suppose instead the jurisdiction grants **declining-balance capital allowances at 15 %** on the 60,000,000 base, with tax losses carried forward without limit. Compute cash tax for the first five operating years and the consequences for coverage and debt capacity. (Rates, profiles, loss-carry rules and the availability of any allowance are jurisdiction-specific and change; the arithmetic below is transferable, the treatment is not, and the treatment is a matter for qualified tax advice in the relevant jurisdiction.)
- Formula.** Allowance in year t = 15 % of the written-down value; taxable profit = **EBITDA** – allowance – interest – losses brought forward; cash tax = 20 % of taxable profit if positive, otherwise nil with the loss carried forward.
- Substitution and result.**

Year	Allowance	Interest	Taxable profit	Loss carried forward	Cash tax
1	9,000,000	2,520,000	(4,020,000)	4,020,000	nil
2	7,650,000	2,370,622	(6,540,622)	6,540,622	nil
3	6,502,500	2,212,281	(7,755,403)	7,755,403	nil
4	5,527,125	2,044,440	(7,826,968)	7,826,968	nil
5	4,698,056	1,866,528	(6,891,552)	6,891,552	nil

Year-one **CFADS** becomes $7,500,000 - \text{nil} - 600,000 = 6,900,000$, a **DSCR** of **1.3773** against 1.2743 — **0.1030** of coverage from a tax assumption alone. At Domain 10's 1.30× sizing target, debt capacity rises from **41,171,123** to **44,498,864**: an extra **3,327,741** of debt, and therefore 3,327,741 less equity. 4. **Interpretation.** The comparison is not between a right and a wrong model but between two assumptions about a jurisdiction, and the gap between them is **more than four times the 828,877 debt-capacity shortfall Domain 10's entire negotiation was fought over**. That is why the tax line is both the most commonly mis-modelled row in project finance and the most consequential: technically difficult, jurisdiction-specific, liable to change during the loan's life, and sitting directly in **CFADS**, so every coverage ratio and sizing calculation inherits it. Four disciplines follow. **The tax line traces to a written opinion**, not to a modeller's understanding, and the opinion's date and scope go in the assumption register. **Cash tax and accounting tax are separate rows**, always, even where they happen to be equal — a model that conflates them cannot represent the year in which they diverge. **Tax losses carry in a stated balance with a stated expiry rule**, since losses that vanish or persist wrongly misstate cash tax for a decade. And **the sponsor case must not bank an allowance regime the lenders will not credit**: sizing debt on 44,498,864 because a fifteen-per-cent allowance exists today embeds a legislative forecast in a twelve-year loan — a risk for Domain 11's register, not a benefit. The honest presentation shows both, states which case governs which decision, and puts the 3,327,741 of capacity difference in front of the credit committee rather than inside the model.

AI in this KA

Where it earns its place. Building a first-pass construction and operating model from a term sheet, a spend curve and stated conventions is fast machine work, and so is the surrounding apparatus: the sources-and-uses skeleton, the loss-carry-forward logic, the articulation checks, and the assumption register drafted from the model's own input block so that register and model cannot drift apart.

Where it must not go. It must not select the tax treatment. Worked example 6.2.3 shows that choice moving debt capacity by 3,327,741, and an assistant asked about capital allowances will produce a fluent, jurisdiction-neutral answer that is nobody's tax opinion. The same prohibition covers the useful life behind accounting depreciation, whether a cost is capitalised or expensed (Domain 2, KA 2.3.3), and whether an allowance survives a change of control — advice questions with named professional owners.

Verification, concretely. Recompute one construction quarter and one operating year by hand and tie all three statements; it is a dozen operations and it catches structural error immediately. Confirm the implied effective tax rate period by period against the statutory rate and the explained differences — the check that catches Worked example 6.4.1's failure. Require every tax input to carry the reference and date of the opinion supporting it, and reject the model, not the input, where that reference is absent.

■ KEY TERMS — KA 6.2

Term	Meaning
Sources and uses	The funding requirement against its funding; identical totals by construction.
Interest during construction (IDC)	Interest accruing before revenue; a funded use, and part of the depreciable base.
Balancing line	The use that absorbs the residual of a fixed envelope; must be tested against policy.
Articulation	The three statements derived from one calculation set, so they cannot disagree.
CFADS tie	CFADS = operating cash flow + interest paid, where interest is classified as operating.
Capital allowance	Tax depreciation on the tax authority's profile and base; not accounting depreciation.
Restricted cash	Reserve balances on the balance sheet that are not available to the business.

■ SAMPLE MCQS — KA 6.2

MCQ 6.2-A [6.2.1 · Application] Kestrel's committed uses are 48,000,000 of EPC, 3,600,000 of owner's costs, 1,800,000 of development costs and 840,000 of fees, inside a 60,000,000 envelope, with capitalised interest computed at 2,114,597. The contingency is:

- A. 3,600,000
- B. 3,645,403 ✓ CORRECT
- C. 5,760,000
- D. 6,000,000

Rationale: $60,000,000 - 48,000,000 - 3,600,000 - 1,800,000 - 840,000 - 2,114,597 = 3,645,403$ (6.2.1). A is a plausible round number and therefore the tell-tale of a plugged table; C omits

capitalised interest from the deduction; D applies a 10 % rule of thumb to the envelope instead of computing the residual.

MCQ 6.2-B [6.2.2 · Application] Operating cash flow is 3,864,000 and interest paid, included in operating cash flow, is 2,520,000. CFADS is:

- A. 1,344,000
- B. 3,864,000
- C. 6,384,000 ✓ CORRECT
- D. 8,904,000

Rationale: CFADS = operating cash flow + interest paid (6.2.2). A deducts interest a second time; B forgets that operating cash flow is already struck after interest; D adds interest a second time to a CFADS already struck before debt service, a figure no definition produces — and principal, a financing flow, never enters operating cash flow at all.

MCQ 6.2-C [6.2.3 · Analysis] A model of a project with flat revenue and level annuity debt service shows cash tax of 516,000 against taxable profit of 2,580,000 in year one and, in year eight, cash tax of 766,771 against taxable profit of 3,833,856. The statutory rate is 20 %. A reviewer should conclude:

- A. the tax line is wrong, because cash tax has risen while revenue is flat
- B. the effective rate is 20.0 % in both years, so the tax line is consistent; cash tax rises because the interest deduction falls as the loan amortises ✓ CORRECT
- C. the model has omitted deferred tax
- D. the loss carry-forward has been applied incorrectly

Rationale: $516,000/2,580,000 = 766,771/3,833,856 = 20.0\%$; the rise is the amortising interest deduction, the mechanism behind the year-12 minimum of 6.4.1 (6.2.3, KA 6.4.1). A mistakes a correct behaviour for an error; C and D name plausible defects for which there is no evidence here.

MCQ 6.2-D [6.2.3 · Analysis] Under 15 % declining-balance allowances Kestrel pays no cash tax for five years, lifting year-one DSCR from 1.2743 to 1.3773 and debt capacity at 1.30× from 41,171,123 to 44,498,864. The sound treatment is:

- A. size the debt at 44,498,864, since the allowance exists
- B. ignore the allowance, since lenders will not credit it
- C. model both, state which case governs which decision, and put the 3,327,741 of capacity difference — and the legislative risk in it — in front of the credit committee ✓ CORRECT
- D. average the two capacities

Rationale: The difference is an assumption about a jurisdiction over a twelve-year loan, so it is disclosed and owned rather than banked or suppressed (6.2.3). A embeds a legislative forecast in a financing; B discards a real economic benefit; D is arithmetic without meaning.

MCQ 6.2-E [6.2.1 · Evaluation] A comparable water project is modelled exactly as Kestrel was, inside a fixed 60,000,000 envelope, but with higher committed uses; the balancing contingency solves to 1,152,000 — 2.4 % of its 48,000,000 EPC price, against Kestrel's 3,645,403 at 7.59 %. Sources equal uses to the cent. The soundest recommendation is:

- A. accept the table, since sources equal uses and the identity is satisfied
- B. report that a 60,000,000 envelope does not fund this project on a defensible contingency — a financing conversation about the envelope, not an adjustment to the table ✓ CORRECT

- C. hold contingency at 7.59 % of the EPC price and let capitalised interest become the balancing line instead
- D. present the contingency as 1,200,000, a cleaner figure, with the approximation noted

Rationale: the identity is satisfied by construction and therefore proves nothing; what makes the balancing line informative is testing it against policy, and 2.4 % sits below the band a lender would expect for this technology and contract structure (6.2.1). A treats an identity as a check. C is the defensible-looking alternative and is the more dangerous answer: capitalised interest is computed from the drawdown profile, the rate and the interest convention, so making it the plug converts a derived quantity into an assumption and buries the funding gap in the one line nobody re-derives. D destroys the single tell that catches a plugged table, since a balancing line is never a round number.

MCQ 6.2-F [6.2.2 · Evaluation] A sponsor's investment-committee paper shows first-operating-year distributions struck as **CFADS** less debt service — 1,374,365 — because the DSRA is described in the paper as "a balance-sheet item". Modelled through the waterfall the distribution is 121,956, or 0.68 % of the 18,000,000 contributed, after 1,252,409 of reserve funding. The soundest position is that:

- A. the paper is acceptable, since the reserve is indeed on the balance sheet and is repaid at maturity
- B. the paper overstates the first distribution by an order of magnitude: reserve funding ranks above distributions, so a distribution forecast struck before it is an aspiration, and the 1,252,409 held in the DSRA is restricted cash unavailable to the business ✓ CORRECT
- C. the paper is acceptable if a footnote records the reserve requirement
- D. the paper is wrong because it ignores the lock-up test, which is the operative constraint at this coverage

Rationale: early cash is all the equity has, and the reserve is a claim on it ranking above distributions (6.2.2, 6.3.2). A and C treat a ranking in the waterfall as a disclosure matter. D names a real test that does not bite here — at a **DSCR** of 1.2743 the $1.15 \times$ lock-up is not engaged, so the paper's error is the omitted reserve, not the omitted test; picking the wrong reason is how a correct objection gets dismissed.

MCQ 6.2-G [6.2.3 · Comprehension] Kestrel's accounting depreciation is 2,400,000 a year and its year-one cash tax is 516,000. Accounting depreciation, tax depreciation and cash tax are best described as:

- A. three names for one charge, presented on different bases
- B. three different numbers — an allocation of cost under the reporting framework, a deduction on the tax authority's own base and profile, and the amount actually paid — of which only the last enters **CFADS** ✓ CORRECT
- C. three deductions that all enter **CFADS**, at different points in the waterfall
- D. two accounting measures and one forecast, so only the accounting figures are auditable

Rationale: only cash actually paid reduces cash available for debt service, which is why cash tax and accounting tax are separate rows even in years when they are equal (6.2.3). A is the conflation Domain 2 (KA 2.A.1) names as the standard finding; C puts non-cash charges inside a cash measure; D invents an audit distinction — every one of the three is evidenced, and the tax line traces to a dated written opinion.

■ SELF-CHECK — KA 6.2

1. State the **CFADS** tie and why it matters. — **CFADS** = operating cash flow + interest paid; it converts **CFADS** from an assertion into a figure tied to a statement.

2. What does Kestrel's first-year distribution of 121,956 tell a sponsor? — That reserve funding consumes almost all first-year equity cash, and that the residual is far more sensitive to revenue than the coverage ratio is.
3. Why must cash tax and accounting tax be separate rows even when equal? — Because a model that conflates them cannot represent the year in which they diverge, and it will diverge.

KNOWLEDGE AREA 6.3

Debt schedules, the cash waterfall and returns

Topics: 6.3.1 the debt schedule and its circularity · 6.3.2 the waterfall in the model · 6.3.3 project return and equity return.

6.3.1 The debt schedule and its circularity

Definition. The debt schedule is the period-by-period record of opening balance, drawings, interest, scheduled principal, prepayments and closing balance, for each facility separately. It is the denominator of every coverage ratio (Domain 10, KA 10.3.3) and therefore load-bearing for covenant compliance.

Its arithmetic is Domain 3's amortisation table and needs no re-derivation; its **invariants** are what a modeller owns. The closing balance at maturity is zero; total scheduled principal equals total drawings; each period's interest equals the balance on which it accrues times the rate for the days in the period, on the stated convention; and debt service equals interest plus scheduled principal, tying to the schedule the facility agreement annexes. Kestrel's twelve years satisfy all four: principal rises from **2,489,635** in year one to **4,726,071** in year twelve, interest falls from **2,520,000** to **283,564**, the closing balance is **zero**, and the principal column sums to **42,000,000** exactly.

Circularity, and the convention that removes it. Capitalised interest depends on the debt balance; the balance depends on drawings; drawings include the funding of capitalised interest. In a workbook that is a circular reference, with three honest resolutions. **Charge interest on the opening balance** and the circularity disappears, because the period's interest is fixed before its draw — Worked example 6.2.1's choice, at a cost of 312,957 against the average-balance answer. **Iterate to convergence**, which is more accurate and needs either the workbook's iterative calculation or a documented macro. **Solve algebraically**, which for simple structures is best because it is deterministic. What is not acceptable is an undocumented iteration whose convergence nobody has tested, or a switch left off: both produce results that depend on the order in which someone pressed the keys. **The circularity resolution is a documented convention with a named owner, and the model states which one it uses.**

Two structural features belong in the schedule explicitly rather than as adjustments: a **cash sweep** applies a defined share of surplus cash to prepayment, so the schedule carries a prepayment row that changes future interest; and **sculpted** service (Domain 10, KA 10.1.3) sets each period's debt service from that period's **CFADS**, which is itself circular through the tax deduction — the same three resolutions apply, and the same requirement to say which.

6.3.2 The waterfall in the model

Definition. The cash waterfall is the contractual priority order in which each period's cash is applied. In a model it is a column of sequential deductions, each with a **test** and each producing a balance that can be nil but never negative.

Kestrel's order, per Domain 10 KA 10.3.3: cash operating costs, then cash tax, then **senior debt service**, then **reserve funding and top-ups**, then subordinated debt if any, then — only if every distribution test passes — **distributions to equity**. Three requirements make the difference between a waterfall and a subtraction.

Every tier is floored at zero and the shortfall is carried, not lost. A tier that goes negative has silently netted its shortfall against a later one, which is the defect that makes a distressed case look survivable. The correct construction pays what is available, records the shortfall, and applies the documented consequence — reserve drawing, lock-up, event of default.

Tests are modelled, not assumed. The distribution test is a formula with a threshold, so the model must show cash trapped when it fails. Kestrel's lock-up bites at a **DSCR** of 1.15×, a **CFADS** of **5,761,081**; a model whose distribution row is simply the residual after debt service has modelled an arithmetic identity, not a facility.

Reserve movements are two-directional and ranked. Funding a reserve is a use above distributions; drawing on it is a source; releasing it at maturity is a source. Kestrel's DSRA is funded at 1,252,409 in each of the first two operating years, sits at 2,504,818 for the rest of the loan, and **releases in year twelve** — which is why year twelve's distribution is 3,431,895 against year eleven's 980,580, and why a model that omits the release understates the equity return without touching any coverage ratio.

6.3.3 Project return and equity return

Definitions. The **project return** values the asset before financing: unlevered post-tax free cash flow against total capital cost. The **equity return** values the sponsors' position: equity drawn during construction against distributions actually received after every prior claim in the waterfall. They answer different questions and are routinely conflated.

WORKED EXAMPLE**Worked example 6.3.3 — what Kestrel actually returns, to whom, and when.**

- Setup.** The master model on the **bank case**: revenue flat at 12,000,000, cash tax computed on the real interest schedule so that **CFADS** declines as the interest deduction amortises, **DSRA** funded over two years and released in year twelve. Equity is drawn 30 % of each period's funding requirement — **8,203,951** in construction year one and **9,796,049** in year two. Compare with the **sponsor case**, identical but with revenue, cash costs and working capital escalating at the 2.967 % of Worked example 6.1.3.
- Formula.** Unlevered free cash flow = **EBITDA** – 20 % × (**EBITDA** – depreciation) – Δworking capital; project **NPV** = **PV** at 8 % – 60,000,000; project **IRR** solves **NPV** = 0. Distribution in period *t* = **CFADS**(*t*) – debt service – reserve funding + reserve release; equity **IRR** solves the present value of draws and distributions to zero.
- Substitution.** Unlevered free cash flow $7,500,000 - 0.20 \times 5,100,000 - 600,000 = 5,880,000$, level for 25 years; $\times AF(0.08, 25) = 5,880,000 \times 10.674776$. Equity flows: –8,203,951, –9,796,049, then 121,956 · 92,080 · 1,312,821 · ... · 980,580 · 3,431,895, then 5,880,000 for thirteen years.
- Result.**

Measure	Bank case	Sponsor case
Project (unlevered, post-tax) NPV at 8 %	+2,767,684	+19,875,251
Project IRR (unlevered, post-tax)	8.54 %	—
Equity IRR	9.83 %	13.52 %
Total distributions over 25 years	90,507,502	151,536,729
Money multiple on 18,000,000	5.028×	8.419×
Equity payback from financial close	14.67 years	—

- Interpretation.** Set these beside Domain 4's appraisal — **IRR 12.19 %**, discounted payback **10.07 years** — and the gap is the lesson. On a post-tax, twenty-five-year, flat-revenue basis the asset earns **8.54 %**, barely above the 8 % hurdle; the equity earns **9.83 %**, and the difference is leverage doing what leverage does. Domain 4's 12.19 % is neither: a pre-tax return over a fifteen-year horizon, sitting above both. Anyone who remembers "the project returns 12 %" has remembered a number describing no party's position. **Leverage pushes equity cash to the far side of the loan.** The 14.67-year equity payback against Domain 4's 10.07-year discounted payback is a different question, not a contradiction: equity waits for the loan to be repaid and the reserve released, and the first two operating years return **121,956** and **92,080** on 18,000,000 contributed. A sponsor whose investment committee expects distributions in year one has misread the waterfall, not the project. **The case, not the asset, produces most of the return.** The 3.69-point difference between 9.83 % and 13.52 % comes entirely from a 2.967 % escalation assumption — which is why escalation is contested in offtake negotiation (Domain 7) and why an equity **IRR** without its case is worthless. The habit that follows: state the escalation at which the equity return meets the sponsor's hurdle, and ask whether it is contracted, indexed to a published index, or hoped for. Finally, **the multiple and the rate tell different stories on purpose** — 5.028× over twenty-five years is 9.83 % a year, and a board shown only the multiple has been shown a long horizon dressed as a return.

AI in this KA

Where it earns its place. Solving a sculpted schedule, testing a cash sweep across hundreds of cases and computing rates of return over a scenario grid is root-finding and iteration at volume — work at which a human is slow and no more accurate. Generating the waterfall's test logic from the drafted priority order and then attacking that logic with adversarial cash flows is equally strong: the failure cases are enumerable, and a machine will enumerate them.

Where it must not go. It must not decide the waterfall's order or the tests' thresholds, which are terms of the finance documents, read by lawyers rather than inferred from a model. It must not choose the circularity resolution silently — an assistant picks whichever converges, and Worked example 6.2.1 prices that choice. And it must not be the source of a quoted return: an equity IRR is a number with a case attached, and the case is a governance object.

Verification, concretely. Substitute any machine-produced IRR back into the present-value equation and confirm it returns zero (Domain 4, KA 4.A.5 — the cheapest audit that exists). Run the waterfall with a CFADS low enough to fail every tier and confirm that no tier goes negative, that the shortfall is carried, and that the lock-up traps cash rather than the model netting it away. Re-derive one period's interest and principal by hand and tie to the annexed schedule. And require the tool to state, in words, which case it ran.

■ KEY TERMS — KA 6.3

Term	Meaning
Debt schedule invariants	Closing balance nil at maturity; Σ principal = drawings; interest ties to balance, rate and days.
Circularity	Interest depends on balance depends on drawings depends on interest; resolved by convention, iteration or algebra.
Waterfall tier	A ranked deduction with a test, floored at zero, with the shortfall carried.
Reserve release	The return of a funded reserve at maturity; a source that lifts the final period's distribution.
Project return	Unlevered post-tax cash against total capital cost; the asset's return.
Equity return	Draws against distributions after every prior claim; the sponsors' return.
Money multiple	Total distributions $\div$ equity contributed; a horizon-blind measure.

■ SAMPLE MCQS — KA 6.3

MCQ 6.3-A [6.3.3 · Analysis] Kestrel's unlevered post-tax IRR is 8.54 %, its bank-case equity IRR is 9.83 %, and Domain 4's appraisal reported 12.19 %. The correct reading is:

- A. the appraisal was wrong by 3.65 points
- B. the asset earns 8.54 %, the equity earns 9.83 % because of leverage, and 12.19 % is a pre-tax fifteen-year figure describing neither party's position ✓ CORRECT
- C. the equity return should exceed the project return by the debt margin
- D. the three should be equal once tax is removed

Rationale: Each measure is correct on its own basis and horizon; conflating them is the defect (6.3.3, 6.1.3). C invents a relationship — the gap depends on gearing, tenor and the shape of distributions; D is false, since horizon alone separates them.

MCQ 6.3-B [6.3.2 · Application] Kestrel's year-twelve distribution is 3,431,895 against year eleven's 980,580, on CFADS that falls between the two years. The explanation is:

- A. a cash sweep
- B. the DSRA of 2,504,818 releasing at final repayment ✓ CORRECT
- C. an error, since CFADS fell
- D. the final principal instalment being smaller

Rationale: The reserve is released when the debt it secures is repaid, a source in the waterfall (6.3.2). C mistakes a modelled contractual event for an inconsistency; D is the opposite of the truth — year twelve's principal, 4,726,071, is the largest of the twelve.

MCQ 6.3-C [6.3.1 · Analysis] A construction model charges interest on the average debt balance and the workbook's iterative calculation is switched off. The consequence is:

- A. interest is understated by a known amount
- B. the model returns a stale or unconverged figure whose value depends on calculation order, so the result is not reproducible ✓ CORRECT
- C. the model will not open
- D. capitalised interest becomes zero

Rationale: Average-balance interest is genuinely circular; without a resolution the answer is whatever the last pass left behind (6.3.1). A describes the opening-balance convention, which is deliberate and quantified at 312,957 on Kestrel; C and D are not how circular references behave.

MCQ 6.3-D [6.3.3 · Application] Kestrel returns 90,507,502 of distributions on 18,000,000 of equity over 25 years — a 5.028× multiple — at an equity IRR of 9.83 %. A board shown only the multiple has been shown:

- A. a complete picture, since the multiple includes every distribution
- B. a long horizon dressed as a return, because the multiple is blind to when the cash arrives ✓ CORRECT
- C. an understatement, since multiples ignore reinvestment
- D. the same information as the IRR

Rationale: A multiple has no time dimension; 5.028× over 25 years is 9.83 % a year (6.3.3, and Domain 4's insistence that rates and ratios explain rather than decide). C reverses the bias; D is false — the same multiple over ten years would be a materially higher rate.

MCQ 6.3-E [6.3.3 · Comprehension] An investment committee member asks why one project has two reported returns, and which of them is the real one. The best restatement is:

- A. the project return is struck before tax and the equity return after it
- B. they answer different questions — the project return values the asset before financing, the equity return values the sponsors' position after every prior claim in the waterfall — so both are real and neither substitutes for the other ✓ CORRECT
- C. the equity return is the project return plus the debt margin
- D. the project return is the lenders' return and the equity return the sponsors'

Rationale: the distinction is whose cash is being measured and after which claims, not a basis difference: on Kestrel both figures are post-tax, and the 8.54 % and 9.83 % differ because leverage reorders the cash (6.3.3). A names a real labelling axis (6.1.3) that is not this one; C invents an arithmetic relationship, when the gap depends on gearing, tenor and the shape of distributions; D miscasts the project return, which measures the asset and not any lender, whose return is its margin.

MCQ 6.3-F [6.3.1 · Evaluation] A construction model charges interest on the average debt balance and resolves the resulting circularity by iteration, with no stated convergence criterion and no named owner. On Kestrel that convention is worth 2,427,554 of capitalised interest against 2,114,597 on the opening-balance convention — a difference of 312,957. The reviewer's best recommendation is:

- A. switch to opening-balance interest, which removes the circularity outright and is the convention the master model uses
- B. keep the average-balance convention but require the resolution to be documented, with a tested convergence criterion and a named owner, because the defect is the undocumented resolution rather than the convention ✓ CORRECT
- C. solve the interest algebraically instead, since a deterministic solution is always preferable
- D. correct the 312,957, which is an overstatement of interest

Rationale: all three resolutions in 6.3.1 are honest, and average-balance interest is the more accurate measure of what the facility will actually charge; what is unacceptable is a resolution whose convergence nobody has tested, because the printed answer then depends on the order in which somebody pressed the keys. A is genuinely defensible and would restore reproducibility, but it buys it by surrendering 312,957 of correctly measured interest when documentation delivers both. C is also defensible and is the better answer for simple structures, but it is a rebuild rather than a control and is not available for a sculpted or swept schedule. D is wrong: 312,957 is the priced cost of a convention, not an error.

MCQ 6.3-G [6.3.3 · Evaluation] A board paper presents Kestrel's equity return as "5.028 times money, 13.52 % IRR", naming no case: the multiple is the **bank** case's, over the whole twenty-five-year concession, while the IRR is the **sponsor** case's, which a 2.967 % escalation assumption alone lifts 3.69 points above the bank case's 9.83 %. The soundest presentation:

- A. leads with the 5.028 times multiple, because it counts every dollar actually distributed
- B. reports the sponsor case, since it is the sponsors' central expectation and they are the investor
- C. reports both cases with their labels, states the horizon the multiple covers, and states whether the 2.967 % escalation is contracted, indexed to a published index or merely assumed ✓ CORRECT
- D. reports the bank case alone, because that is the case the lenders underwrite

Rationale: a multiple has no time dimension, so 5.028 times says nothing about when the cash arrives and a multiple shown without its horizon is a long horizon dressed as a return, while an equity IRR without its case is worthless — and pairing one case's multiple with another's IRR is a figure that describes no case at all (6.3.3). A does exactly that; B presents the more flattering case unlabelled, and would have to carry the sponsor case's own multiple of 8.419 times rather than the 5.028 the paper quotes, when the habit the domain prescribes is to state the escalation at which the return meets the hurdle and ask whether it is a right or a hope; D discards the sponsors' own economics, which is the case the equity decision turns on.

■ SELF-CHECK — KA 6.3

1. Name the four debt-schedule invariants. — Closing balance nil at maturity; Σ principal = drawings; interest ties to balance, rate and day count; debt service = interest + scheduled principal, tying to the annexed schedule.
2. Why must a waterfall tier never go negative? — A negative tier has silently netted a shortfall against a later claim, which makes a distressed case look survivable.

3. State Kestrel's first two operating-year distributions and what they teach. — 121,956 and 92,080 on 18,000,000: reserve funding consumes almost all early equity cash, so distribution forecasts must be struck after reserve funding and lock-up tests.

KNOWLEDGE AREA 6.4

Checks, sensitivity, model audit and AI controls

Topics: 6.4.1 the check block and the six invariants · 6.4.2 sensitivity, scenario and the breakeven translation · 6.4.3 model audit, governance and its economics · 6.4.4 AI-assisted modelling controls.

6.4.1 The check block and the six invariants

Definition. A **check block** is a dedicated output area in which every arithmetic invariant the model must satisfy is computed as a difference that should be nil, with a single aggregate flag that turns red if any check fails. It is built first, not last, and no output is quoted while it is red.

The six invariants a project model must satisfy:

#	Invariant	What its failure localises
1	The balance sheet balances, every period	An omitted flow, or a flow posted once
2	Sources equal uses, every construction period	A funding gap or a double-funded use
3	Closing debt is nil at maturity, for every facility	A schedule error or a missing prepayment
4	Σ scheduled principal = total drawings	A rounding accumulation or a mis-specified profile
5	Cash is never negative in any period or account	A liquidity failure the model has netted away
6	CFADS = operating cash flow + interest paid	A CFADS line built outside the statements

To these belong three ratio-level checks inherited from Domain 10 (KA 10.A.3): **LLCR** = **DSCR** where cash is level and service is an annuity at the loan rate; **PLCR** $\geq$ **LLCR** wherever a tail exists; and the **minimum DSCR** over the loan life reported alongside the average. And one that belongs to this domain: the **implied effective tax rate** reconciles, period by period, to the statutory rate plus explained differences.

WORKED EXAMPLE**Worked example 6.4.1 — the error that balances perfectly.**

1. **Setup.** Kestrel's first operating year. A modeller computes tax as 20 % of **EBIT** rather than 20 % of taxable profit — a one-cell error, omitting the interest deduction. Every other formula is correct and consistent. Trace the consequences and identify which check catches it.
2. **Formula.** Correct: $\text{tax} = 20\% \times (\text{EBIT} - \text{interest})$. As modelled: $\text{tax} = 20\% \times \text{EBIT}$. Then propagate through net income, operating cash flow, **CFADS**, **DSCR**, distributable cash, the balance sheet and debt capacity at Domain 10's 1.30× target.
3. **Substitution.** Tax $0.20 \times 5,100,000 = 1,020,000$ against the correct 516,000; net income $2,580,000 - 1,020,000 = 1,560,000$; operating cash flow $1,560,000 + 2,400,000 - 600,000$; **CFADS** $3,360,000 + 2,520,000$.
4. **Result.** **CFADS** **5,880,000** against 6,384,000; **DSCR** **1.1737** against 1.2743 — **below the 1.20× covenant**; distributable cash **−382,044**, so the DSRA cannot be funded on schedule; debt capacity at 1.30× falls from **41,171,123** to **37,920,771**, a shortfall of **3,250,352**. And the balance sheet **balances to the cent**, because the error is propagated consistently: net income is lower, equity is lower by the same amount, and assets tie.
5. **Interpretation.** This is the single most important result in the domain, and it is a negative one: **invariant 1 is necessary and not sufficient**. A consistent wrong number balances perfectly, and a modeller who reports "the model balances" has reported nothing about accuracy. What catches this error is the **effective-rate check**: $1,020,000/2,580,000 = 39.53\%$ against a statutory 20 %, a discrepancy no reader can rationalise. The negative distributable cash catches it too, through invariant 5 — but only if the waterfall is floored rather than allowed to run negative, which is precisely why 6.3.2 insists on the floor. The consequences scale badly in both directions. Understated, as here, the model reports a covenant breach that does not exist, kills 3,250,352 of debt capacity, and sends the sponsors to find equity they do not need. Substituting 3,250,352 of equity for debt at a 6-point spread (a 12 % equity requirement against the 6.0 % achieved on debt) costs 195,021 a year, a present value of **1,469,694** over the twelve years at 8 %. Overstated, the same class of error sizes debt the project cannot service, which is Worked example 6.4.3's illustrative error. The discipline is therefore not "check that it balances" but "**know what each check can and cannot see**": the six invariants test structure, the effective-rate and ratio checks test economics, and only a reconciliation to the documents tests definitions (Domain 10, Toolkit 10.T1).


The other half of the check block: the minimum, not the average. Domain 10 held Kestrel's **CFADS** level "for this illustration" and derived **DSCR** = **LLCR** = 1.2743. The modelled profile does not behave that way, and the reason is 6.2.3's: as the loan amortises the interest deduction shrinks, cash tax rises, and **CFADS** falls against a level instalment.

WORKED EXAMPLE**Worked example 6.4.1b — the minimum the level line hides.**

1. **Setup.** Kestrel's bank case, revenue flat at 12,000,000, cash tax computed on the actual interest schedule. Compute **DSCR** for each of the twelve loan years and compare with the level assumption.
2. **Formula.** $CFADS(t) = 7,500,000 - 0.20 \times (5,100,000 - \text{interest}(t)) - 600,000$; $DSCR(t) = CFADS(t)/5,009,635.23$.
3. **Substitution.** Year 1: interest 2,520,000, cash tax 516,000, **CFADS** 6,384,000. Year 12: interest 283,564, cash tax 963,287, **CFADS** 5,936,713.
4. **Result.** **DSCR** falls monotonically from **1.2743** in year one to **1.1851** in year twelve. The **minimum is 1.1851 — a breach of the 1.20× covenant** — and the average over the loan life is **1.2340**, comfortably above it. Present values move too: **PV** of the modelled **CFADS** at 8 % over 25 years is **65,315,883** against **68,147,771** on the level assumption, so the level line overstates value by **2,831,888**, or **4.34 %**. **LLCR** becomes **1.2395** and **PLCR 1.8555**, against Domain 10's level-case 1.2743 and 1.9431 — the identity breaks, as Domain 10 said it must when cash is not level.
5. **Interpretation.** A model that holds **CFADS** level reports 1.2743 for twelve years and never shows the year in which the project breaches. The mechanism is unglamorous and entirely predictable — the interest tax shield amortises with the loan — and it is missed constantly because it requires the tax line to be modelled period by period rather than assumed. Three professional consequences. **Report the minimum and the year it occurs**, which is Domain 10's rule now earned rather than asserted: the average of 1.2340 passes and the project still breaches. **The escalation assumption decides where the minimum lies.** On the sponsor case, with revenue escalating at 2.967 %, **DSCR** rises from 1.2743 to **1.5940** and the minimum is year one — which is why lenders insist on the flat case: not because they believe it, but because it is the case that finds this defect. **And the fix belongs to sizing, not reporting.** At Domain 10's properly sized **41,171,123** the instalment is 4,910,769 and the year-twelve **DSCR** is **1.2087** — still inside the covenant. The debt level at which the year-twelve minimum is exactly 1.20× is **41,472,081**, so the structure needed **527,919** less debt than the 42,000,000 requested. Domain 10's 828,877 gap, argued on year-one coverage, was already protecting against a year-twelve problem nobody in that negotiation had modelled. That is the most valuable thing a properly built model does: it makes a conservative constraint legible as the specific risk it was guarding.

Coverage falls as the interest deduction falls — and a level CFADS line cannot show it

All three cases start at 1.2743. The escalation assumption decides whether the minimum is in year 1 or year 12



Average DSCR 1.2340 on the bank case — and the average is not the number the covenant tests

Fig 6.4.1 — The minimum coverage a level line hides

6.4.2 Sensitivity, scenario and the breakeven translation

Definitions. **Sensitivity analysis** moves one input at a time and records the effect on outputs. **Scenario analysis** moves a coherent set of inputs together to represent a state of the world. **Elasticity** expresses a sensitivity as a ratio: the percentage change in an output per one per cent change in an input, so that inputs measured in different units can be ranked.

WORKED EXAMPLE

Worked example 6.4.2 — Kestrel's sensitivity table, honestly labelled.

- Setup.** Two cases run in parallel: the **sponsor case** (2.967 % escalation, NPV +19,875,251) and the **bank case** (flat, NPV +2,767,684). NPV is unlevered, post-tax, over 25 years at 8 %; DSCR figures are from the bank case with cash tax on the actual interest schedule. Each input is moved ± 10 %; the capital-cost case assumes the overrun is funded by equity, the lenders' commitment being fixed.
- Formula.** Elasticity = $(\Delta \text{NPV} / \text{NPV}) \div (\Delta \text{input} / \text{input})$.
- Result.**

Input	Sponsor NPV at –10 % / +10 %	Elasticity	Bank NPV at –10 % / +10 %	Elasticity	Bank DSCR yr 1 at +10 %	Bank minimum DSCR at +10 %
Revenue	7,416,691 / 32,333,810	6.27	–6,839,615 / 12,374,983	34.71	1.4540	1.3647
Cash operating cost	24,858,674 / 14,891,827	–2.51	6,610,603 / –1,075,235	–13.88	1.2025	1.1132
Capital cost	25,362,861 / 14,387,640	–2.76	8,255,295 / –2,719,927	–19.83	1.2839	1.1946
Interest rate	19,875,251 / 19,875,251	0.00	2,767,684 / 2,767,684	0.00	1.2432	1.1485
Tax rate	21,439,288 / 18,311,213	–0.79	3,856,511 / 1,678,857	–3.93	1.2640	1.1658
Escalation	17,852,671 / 21,978,907	1.02 / 1.06	not applicable	—	1.2743	1.1851
Discount rate	26,469,750 / 14,022,003	–3.32 / –2.94	7,305,980 / –1,294,646	–16.40 / –14.68	1.2743	1.1851

1. **Interpretation.** Five readings, in order of what a practitioner is paid for.

Revenue dominates, and operating leverage is why. An elasticity of 6.27 means a one per cent revenue miss costs 6.27 % of NPV: cash operating costs are largely fixed, so CFADS amplifies revenue at an elasticity of **1.4098**, and the discount factors and the fixed depreciation shield do the rest. Diligence effort should be allocated in the order of this column, which is the table's real purpose.

Elasticity is a property of the case, not of the project. The same revenue move is 6.27 on the sponsor case and **34.71** on the bank case, because the bank case's base NPV is thin. A tornado drawn on a marginal case looks terrifying and one drawn on a generous case looks reassuring, for the same asset. Never compare elasticities across cases; always label the case.

The interest-rate row is the most instructive line in the table. Unlevered NPV does not move at all — elasticity **0.00** — because financing does not change the asset's cash. But the year-one DSCR falls to **1.2432** and the minimum to **1.1485**, below the lock-up as well as the covenant. A table reporting only NPV would rank interest rate last among Kestrel's risks. **Sensitivity must be run on the outputs the decision turns on**, and for a financing that means coverage, not only value.

The capital-cost row is counterintuitive. A 10 % overrun raises the year-one DSCR to **1.2839**, because the depreciation shield grows with the asset base and cash tax falls while the instalment is unchanged; NPV falls sharply, as it must. A model showing only coverage would report an overrun as good news — which is why no single output is a control.

The asymmetry in the discount-rate row is convexity, not error. –3.32 downward against –2.94 upward is the curvature of the present-value function (Domain 4, KA 4.A.1); a symmetric elasticity reported for a discount rate means somebody has linearised.

What one-at-a-time cannot see — stated precisely, because it is usually stated wrongly. The common objection is that one-at-a-time "misses interactions". On Kestrel it does not: the model is linear in revenue and cash cost, so a joint move of revenue –10 % and cash cost –5 % gives an NPV of **–4,918,155**, exactly the sum of the two individual effects, to the cent. What it genuinely misses is more dangerous. **It says nothing about correlation** — the joint probability of two moves occurring together. Revenue and cost are commonly indexed to related measures, so the realistic downside is a

correlated bundle rather than "revenue –10 %", and one-at-a-time never assigns it a likelihood; that is what scenarios and, where the exposure justifies the parameter work, probabilistic simulation are for. **And it breaks at thresholds.** At revenue –10 % Kestrel's year-one **DSCR** is **1.0947**, below both the 1.20× covenant and the 1.15× lock-up, so distributions are trapped and the equity return collapses by far more than the **NPV** column suggests. Discontinuities — breach, lock-up, cash sweep, tax losses starting or exhausting, a reserve emptying — are where linear intuition fails and a sensitivity table must be replaced by a case.

The breakeven translation. A ratio conveys no magnitude; an input level does. Converting each threshold into the input that crosses it is the most useful single page a model produces:

Threshold	CFADS	Revenue	Fall from base
1.30× sizing target	6,512,526	12,171,368	revenue must rise 1.43 %
1.20× covenant	6,011,562	11,503,416	4.14 %
1.15× lock-up	5,761,081	11,169,441	6.92 %
1.00× (payment fails)	5,009,635	10,167,514	15.27 %

Two of those lines change a conversation. Domain 10 reported covenant headroom as **372,438** of annual cash, **5.83 %** of **CFADS**; in revenue terms the headroom is only **4.14 %**, because **CFADS** amplifies revenue by 1.4098. Quoting headroom as a percentage of **CFADS** to an operations team that manages revenue overstates their room by 41 %. And the first line closes the loop with Domain 10's negotiation: revenue would have to be **1.43 % higher** for the requested 42,000,000 to deliver the 1.30× the credit committee wanted. On the cost side the covenant breaks at cash operating costs of **4,965,547**, **10.35 %** above base, and on the financing side at an interest rate of **7.48 %** against the 6.0 % achieved.

6.4.3 Model audit, governance and its economics

Definition. A **model audit** is an independent review of a financial model against the transaction documents, the model's own logic and its arithmetic, reported as findings by severity. It is a standard condition precedent in limited-recourse financing (Domain 13, KA 13.2) and it is the lenders' control, not the sponsor's convenience.

Model governance is the surrounding apparatus that makes the audit possible and its findings durable: a **version register** (one authoritative file, a version number in the file name and on every printed page, a change log naming the author and the reason); **input provenance** (every external input traced to a source document with its version and date, so that a superseded traffic forecast cannot be silently retained — Case study B); **input lock and change control** after a declared freeze; a **named model owner** and a named reviewer per version; and a **regression suite** of golden answers that the model must still reproduce after any edit.

The economics: is the audit worth its fee and its elapsed time? The shape is Domain 3's gate economics from PML-AI (PML-AI KA 3.3.1 — reviewed here in the same form, on financing rather than delivery parameters), and the answer is more interesting than "yes".

WORKED EXAMPLE**Worked example 6.4.3 — the model audit priced.**

1. **Setup.** Illustrative parameters an organisation must estimate from its own record; the arithmetic, not the parameters, is transferable. Probability that an unaudited model of this class carries a **material** error, $p = 0.35$. Probability the audit detects it, $d = 0.85$. Audit fee **180,000**. The audit adds **two weeks** to financial close; at Kestrel's forgone **CFADS** of **17,733.33** a day on a 30/360 basis (Domain 5, KA 5.4.2, where the concession's expiry is fixed so a slip shortens operations), that elapsed cost is **248,267**. Correcting a detected error pre-close costs 60,000 of model rework plus one further week, **184,133**. The illustrative material error is an **omitted 500,000 annual maintenance provision**: true year-one **CFADS 5,984,000**, a **DSCR** of **1.1945**, and debt capacity at 1.30× of **38,591,479** against 42,000,000 signed — a resize of **3,408,521**.
2. **Formula.** Cost if the error reaches close = amendment fee + advisers + duress premium on the resized equity + reopening delay. Expected cost without audit = $p \times C$. Expected cost with audit = fee + elapsed + $p \times [d \times \text{correction} + (1 - d) \times C]$. Net value = the difference.
3. **Substitution.** C = amendment fee at 0.30 % of 42,000,000 = 126,000, plus advisers 320,000, plus a 200-basis-point duress premium on 3,408,521 of equity raised at short notice for twelve years ($3,408,521 \times 0.02 \times AF(0.08, 12) = 513,738$), plus a ten-week reopening at 24,733.33 a day (forgone **CFADS** plus interest on drawn debt, Domain 5's daily figure) = 1,731,333. Without audit $0.35 \times 2,691,071$. With audit $180,000 + 248,267 + 0.35 \times [0.85 \times 184,133 + 0.15 \times 2,691,071]$.
4. **Result.** $C = 2,691,071$. Expected cost without the audit **941,875**; with it **624,328**. **The audit is worth 317,547**. Its **breakeven fee** is **497,547** — **2.76×** what it costs. Its **breakeven error rate** is $p^* = 20.10\%$: below that, the audit destroys value. Its **breakeven detection rate** is $d^* = 48.81\%$.
5. **Interpretation.** The headline is not 317,547 but what the breakevens do to the argument. **Elapsed time, not fee, decides whether the audit pays.** Run the same audit early, in parallel with other conditions precedent so that it adds no time to close and a detected error costs only its 60,000 of rework, and the net value nearly doubles to **602,744** while the breakeven error rate collapses from 20.10 % to **8.05 %**. The fee is 180,000 and the elapsed cost is 248,267: **the delay costs more than the auditor**. A leader arguing about the fee is arguing about the smaller number, and the negotiation that matters is the timetable. **A weak audit is worse than none**, because below $d^* = 48.81\%$ it consumes the fee and the delay and returns less than it costs — so the auditor's competence on this asset class and this jurisdiction's tax is a commercial question, not a procurement formality. **And the honest caveat sits in p .** An organisation whose material-error rate is genuinely below 20 % cannot justify a late audit on expected value alone, and should not pretend otherwise; what justifies it anyway is that the audit is the lenders' condition precedent, that the distribution of C has a long tail this arithmetic averages away, and that the 20.10 % breakeven is itself an estimate nobody has ever tested on a sample of one project. The defensible position is therefore: audit early, audit competently, and use the arithmetic to argue about timing and scope rather than about whether to audit at all.

6.4.4 AI-assisted modelling controls

The specific opportunity. Four uses are strong enough to change how the work is staffed. **Formula and structure scanning** at whole-workbook scale — embedded constants, mid-row formula changes, inconsistent references, orphaned cells, flag arithmetic: the 6.1.1 rules, enforced

mechanically. **Version diffing** into a human-readable change list, which is what makes a change log trustworthy rather than aspirational. **Adversarial test generation**: the cases that break a waterfall — a **CFADS** failing every tier, a reserve emptying, tax losses exhausting mid-loan — which humans under time pressure reliably fail to imagine. And **documentation from the model**, drafting the assumption register from the input block so the two cannot drift apart.

The specific prohibitions. No AI output is a tax treatment, an accounting policy, a covenant definition, a waterfall order or a legal consequence — each has a named professional owner and a document behind it. No AI-generated case becomes a reported case without a human declaring its basis, horizon and assumptions. No AI edit reaches the authoritative file without appearing in the version diff and the change log with a named human author. And nothing produced by a model whose check block is red is quoted, whatever produced it.

The controls that make this auditable, in the order they bind: a **golden-answer regression suite** — this domain's verified figures (**CFADS** 6,384,000; **DSCR** 1.2743; minimum **DSCR** 1.1851 in year twelve; IDC 2,114,597; contingency 3,645,403; closing balance sheet 59,752,409) rerun after every edit, machine or human, with any change explained before it is accepted; **provenance for every input**, source document and version, because Case study B's failure was a paste and not a formula; **a named human owner per model version**; **sampled manual recomputation** of one construction period and one operating year per version; and **a stated verification sample size** for any machine-produced finding list, every finding confirmed by a human before it is reported.

The arithmetic of an AI pre-check, and why it does not settle the question. Suppose a machine scan costs **8,000**, adds no elapsed time and detects **55 %** of material errors. On Worked example 6.4.3's parameters its net value is **498,481** — above the late audit's 317,547, purely because it consumes no time. As a pre-check before an early audit it cuts the residual error probability from 0.35 to **0.1575** and yields **670,716**, the best of the four options.

Control	Expected cost	Net value
Nothing	941,875	—
Late model audit (2 weeks of delay)	624,328	317,547
AI pre-check alone	443,394	498,481
Early model audit	339,131	602,744
AI pre-check + early model audit	271,159	670,716

And here the arithmetic must be allowed to lose an argument. Expected value ranks the pre-check above the late audit, and a careless reader would conclude that a tool can replace a review. Three reasons it cannot, all about the parameters rather than the sums. The audit is a condition precedent; a sponsor does not get to substitute for it. The detection rate **d** is not constant across error types: a scanner finds structural defects and systematically misses the definitional ones — whether **CFADS** matches the facility's clause, whether the tax treatment is the jurisdiction's, whether the waterfall follows the drafted priority — which are precisely the errors carrying the largest **C**, so treating **d** as independent of error class is itself a model error, and one that biases the comparison toward the cheap control. And nobody has validated 0.55 on this asset class at all. The conclusion the table supports and the arithmetic alone does not: **machine checks are additive to review and never substitutive**, and the honest use of these numbers is to fund the pre-check and move the audit earlier.

■ KEY TERMS — KA 6.4

Term	Meaning
Check block	A dedicated output area computing every invariant as a difference that must be nil.
Elasticity	Percentage change in an output per one per cent change in an input.
Tornado	Sensitivities ranked by magnitude; meaningless without its case labelled.
Breakeven translation	Converting a ratio threshold into the input level that crosses it.
Model audit	Independent review against documents, logic and arithmetic; a lenders' condition precedent.
Input provenance	Every external input traced to a source document, version and date.
Golden-answer regression suite	Verified results rerun after every edit; unexplained change blocks release.
Breakeven fee / error rate / detection rate	The three points at which a review stops adding value.

■ SAMPLE MCQS — KA 6.4

MCQ 6.4-A [6.4.1 · Analysis] A modeller taxes EBIT of 5,100,000 at 20 % instead of taxable profit of 2,580,000. The balance sheet still balances. The check that catches it is:

- A. the balance-sheet check, once the period is recalculated
- B. sources equal uses
- C. the implied effective tax rate — $1,020,000/2,580,000 = 39.53\%$ against a statutory 20 %
☒ **CORRECT**
- D. closing debt nil at maturity

Rationale: A consistently propagated error balances, so invariant 1 is necessary and not sufficient (6.4.1). B and D test construction funding and the debt schedule, neither of which the error touches.

MCQ 6.4-B [6.4.1 · Application] Kestrel's bank case shows DSCR of 1.2743 in year one, 1.1851 in year twelve and an average of 1.2340 against a 1.20× covenant. The reportable position is:

- A. compliant, since the average exceeds the covenant
- B. compliant, since year one exceeds the covenant
- C. a breach in year twelve; the minimum and its year must be reported, because covenants are tested in periods ☒ **CORRECT**
- D. indeterminate without the sponsor case

Rationale: Domain 10's rule, earned here: an average conceals the period that breaches (6.4.1b, KA 10.A.3). D inverts the logic — the sponsor case, in which coverage rises to 1.5940, is the case that hides the problem.

MCQ 6.4-C [6.4.2 · Analysis] Kestrel's unlevered NPV has an elasticity of 0.00 to the interest rate, while a 10 % rate rise takes the minimum DSCR to 1.1485 — below the 1.15× lock-up. The correct inference is:

- A. interest-rate risk is immaterial
- B. the model has an error, since a higher rate must reduce value

- C. sensitivity must be run on the outputs the decision turns on: financing does not change the asset's cash, but it changes coverage, which is what the covenant tests ☒ **CORRECT**
- D. the discount rate and the interest rate should be equal

Rationale: Unlevered cash is financing-independent by construction (6.4.2). A reads only the NPV column, which is exactly the mistake; B misunderstands what unlevered means; D confuses the opportunity cost of capital with the cost of debt.

MCQ 6.4-D [6.4.2 · Application] Domain 10 reported covenant headroom of 372,438 of annual CFADS, 5.83 % of base case. Expressed as revenue, the headroom is:

- A. 5.83 %
- B. 4.14 % ☒ **CORRECT**
- C. 8.22 %
- D. 15.27 %

Rationale: CFADS amplifies revenue by 1.4098, so the covenant breaks at revenue of 11,503,416, a 4.14 % fall (6.4.2). A carries the CFADS percentage across as if the two were interchangeable — overstating the operations team's room by 41 %; C multiplies rather than divides by the elasticity; D is the fall at which payment itself fails.

MCQ 6.4-E [6.4.3 · Analysis] A model audit costs 180,000 and two weeks of delay worth 248,267; $p = 0.35$, $d = 0.85$, $c = 2,691,071$, pre-close correction 184,133. Moving the audit early, so it adds no delay and correction costs only 60,000, changes its net value and breakeven error rate to:

- A. 317,547 and 20.10 %
- B. 602,744 and 8.05 % ☒ **CORRECT**
- C. 941,875 and nil
- D. 497,547 and 20.10 %

Rationale: $941,875 - [180,000 + 0.35 \times (0.85 \times 60,000 + 0.15 \times 2,691,071)] = 602,744$, and $180,000 / (0.85 \times (2,691,071 - 60,000)) = 8.05 \%$ (6.4.3). A is the late-audit answer; C is the expected cost of no control at all; D pairs the late audit's breakeven fee with its breakeven error rate.

MCQ 6.4-F [6.4.1 · Evaluation] On the bank case Kestrel's DSCR falls from 1.2743 to 1.1851 in year twelve, averaging 1.2340 against a 1.20× covenant, on the requested 42,000,000. The credit committee's sizing of 41,171,123 gives a year-twelve DSCR of 1.2087; at 41,472,081 the year-twelve DSCR is exactly 1.20×. The soundest recommendation is:

- A. keep 42,000,000, disclose the year-twelve minimum, and rely on the 1.2340 average
- B. size at 41,472,081 — the largest facility that holds the covenant in every period — and record that the 828,877 the committee withheld was already protecting a year-twelve exposure nobody in that negotiation had modelled ☒ **CORRECT**
- C. size at 41,171,123 as the committee proposed, since 1.2087 clears the covenant with margin
- D. keep 42,000,000 and negotiate the covenant down to 1.15×, matching the lock-up

Rationale: covenants are tested in periods, so the constraint is the minimum and the binding period is year twelve; the correct facility is therefore the largest that satisfies it everywhere (6.4.1, 6.4.1b). A relies on an average that passes while the project breaches. C is defensible and safe, and it is the answer the committee will accept — but it was sized on year-one coverage and clears year twelve by accident, forgoing 300,958 of debt capacity for coverage the covenant does not ask for. D looks like an equivalent trade and is the weakest option: collapsing the covenant onto the 1.15 × lock-up

removes the tier between a distribution trap and an event of default, which is the early warning the whole structure depends on.

MCQ 6.4-G [6.4.4 · Evaluation] On the domain's parameters an AI pre-check is worth 498,481, a late model audit 317,547, an early audit 602,744, and the pre-check with an early audit 670,716. A sponsor proposes replacing the audit with the pre-check, since the pre-check ranks above the late audit on expected value. The soundest position is that:

- A. the substitution is right: 498,481 exceeds 317,547, so the cheaper control is the better one
- B. it should be refused, and both funded — the audit brought earlier and the pre-check added — because the audit is the lenders' condition precedent and the scanner's detection rate is not independent of the error classes that carry the largest cost ✓ CORRECT
- C. both should be refused, because a measured material-error rate below the 20.10 % breakeven means neither pays
- D. the substitution is right provided the pre-check's detection rate is first validated on this asset class

Rationale: machine checks are additive to review and never substitutive (6.4.4): a scanner finds structural defects and systematically misses the definitional ones — whether **CFADS** matches the facility's clause, whether the tax treatment is the jurisdiction's, whether the waterfall follows the drafted priority — which are precisely the errors with the largest cost, so treating detection as constant across error classes biases the comparison toward the cheap control. A does that. C ignores that the audit is a condition the sponsor cannot trade away, and that the tail of the cost distribution is averaged out of the expectation. D fixes the parameter and leaves the governance objection untouched.

MCQ 6.4-H [6.4.2 · Comprehension] A committee asks why the model's sensitivity table cannot answer the question "what happens to Kestrel in a recession". The best explanation is that:

- A. the table's $\pm 10\%$ steps are too small to represent a recession, so the range must be widened
- B. a recession is a state of the world in which several drivers move together, and a table that moves one input at a time carries no view about how they move together or how likely that is — which is the object a scenario is built to represent ✓ CORRECT
- C. the table is reported on value, and a recession is a coverage event, so the defect is the output chosen rather than the technique
- D. the two are the same procedure, so the recession case is the table's rows added together

Rationale: the difference is what each technique can represent, not the size or the number of the moves it makes: one-at-a-time measures the model's response to a single input and is silent on correlation and on behaviour at thresholds, which is what a coherent case exists to carry (6.4.2). A treats a difference in kind as a difference in degree — a wider step is still one input. C names a real discipline in the wrong place: coverage as well as value must be reported for either technique, which is why a table reporting only **NPV** ranks interest-rate risk last on Kestrel. D is the arithmetically tempting answer, because on this linear model a joint move is exactly the sum of the separate ones — and that is the trap, since adding the rows reproduces the number while still assigning the bundle no likelihood.

■ SELF-CHECK — KA 6.4

1. Why is "the model balances" not evidence of accuracy? — A consistently propagated error balances to the cent; invariant 1 tests structure, not economics (6.4.1).

2. What does one-at-a-time sensitivity genuinely miss? — Correlation, and behaviour at thresholds; on a linear model it does not miss the arithmetic of combining moves, which is additive to the cent.
3. What decides whether a model audit pays? — Its elapsed time, not its fee: moving it early lifts net value from 317,547 to 602,744 and cuts the breakeven error rate from 20.10 % to 8.05 %.

— Advanced topics — Domain 6

6.A.1 Probabilistic modelling, and when it earns its cost

Where a one-at-a-time table cannot assign likelihoods, a simulation can — drawing correlated inputs from stated distributions and reporting a distribution of outputs. The attraction is real: it yields the probability of covenant breach over the loan life, which is what a credit committee wants and no sensitivity table can give. The cost is usually understated. A simulation requires **distributions** and a **correlation matrix**, assumptions with far less evidence behind them than the point estimates they replace, and a plausible-looking distribution of **NPV** built on invented correlations is more dangerous than a point estimate because its shape implies knowledge nobody has. The proportionate rule: simulate where the exposure justifies defensible parameter work, report the assumptions as prominently as the results, and never let a distribution's smoothness stand in for evidence. Used well, the deliverable is not a mean **NPV** — roughly what the base case already gave — but a **probability of breach** and the **inputs that drive it**.

6.A.2 Model reuse, templates and the drift problem

Templates are the right answer for organisations that finance repeatedly: they carry conventions, check blocks and a tested waterfall, and they make a new model reviewable on day one. They carry two risks that must be managed rather than hoped away. **Silent inheritance**: a template's tax logic, day-count convention or reserve mechanic is this transaction's only once someone confirms it, and the confirmation is a task with an owner. **Drift**: each transaction improves its copy, none of the improvements returns, and after five deals there are five templates and no standard. The governance answer is a template owner, a versioned template with a change log, a deviation register per transaction ("this model departs from template v4.2 in these six respects, for these reasons") and a post-close pass that promotes genuine improvements back. The reuse argument survives being disciplined; it does not survive being informal.

6.A.3 The reviewer's model eye

Invariants and habits to test on any project model before relying on a single output. The **six invariants** of 6.4.1 all compute to nil, and the check block is visible on the output page rather than hidden in a working sheet. The **implied effective tax rate** reconciles period by period to the statutory rate plus explained differences (Worked example 6.4.1). The **flag additions** of 6.1.2 hold, and no period is both construction and operating. **Sources equal uses in every construction period**, not merely in total. **Capitalised interest** is computed from a drawdown profile, and the interest convention and periodicity are stated (Worked example 6.2.1 — the 41.01 % swing). **CFADS = operating cash flow + interest paid**, and the **CFADS** line reconciles to the facility's definition clause by clause (Domain 10, Toolkit 10.T.1). **Minimum DSCR is reported with the year in which it occurs**, and the level-cash shortcut is not doing the work (Worked example 6.4.1b — 1.1851 in year twelve). **LLCR = DSCR** only where cash is level and service is an annuity at the loan rate; where cash is not level, the divergence is explained and not smoothed. **Every waterfall tier is floored at zero** and

shortfalls are carried; the model has been run with a **CFADS** that fails every tier. **Cash tax, not accounting tax, feeds CFADS**, and tax losses carry with a stated expiry rule. **No calculation cell contains a numeral** other than a period counter. **Every external input has a source document with a version and a date**. And the model file bears a version number that appears on every printed page, so that the paper on the table can be tied to the workbook that produced it. Any violated line is a defect, and the violated line localises it — which is the entire value of building the checks before the answers.

— Industry variations — Domain 6

- **Contracted power and availability PPPs.** Revenue is nearly deterministic, so modelling effort concentrates on the **availability and deduction mechanism** — a formula-heavy translation of the performance regime into cash — and on the tax line. Coverage is thin by design, which makes the minimum-DSCR discipline of 6.4.1b decisive rather than academic.
 - **Merchant power, commodities and mining.** The price deck is the model, and it arrives as a third-party forecast with versions, so 6.4.3's provenance control is the first-order defence (Case study B is this failure in another sector). Lenders size on stressed decks, so the bank case must be genuinely separate from the sponsor case rather than a switch changing one row.
 - **Transport concessions.** Patronage ramps make the level-cash shortcut untenable from period one, so sculpted service (Domain 10, KA 10.1.3) is close to mandatory and the model carries 6.3.1's sculpting circularity openly. Traffic models are separate models, and the interface is where the errors live.
 - **Water and regulated utilities.** Reset cycles create step-changes in revenue at known dates, so the timeline carries a **reset flag** and the model shows coverage across the reset rather than assuming continuity. Regulatory and statutory asset values coexist and must never be conflated.
 - **Digital infrastructure.** Short useful lives and heavy refresh capex make the capital-expenditure profile an operating-model problem: lifecycle capex competes with debt service in the waterfall, and its position relative to **CFADS** is negotiated.
 - **Oil, gas and heavy industry.** Decommissioning provisions and their funding create an end-of-life obligation most templates handle badly, and Domain 4's sign-change pathology (KA 4.1.2) follows directly — a further reason these sectors report **NPV** and treat "the **IRR**" with suspicion.
-

— Case study — Domain 6: the year the level line hid (water)

Situation. Kestrel's financing model went to the lenders' model auditor three weeks before the scheduled close, showing a base-case **DSCR** of **1.2743** held constant across all twelve loan years, a **CFADS** of **6,384,000**, and an **NPV** of **+16,179,360** carried forward from the sponsors' appraisal. The senior facility was **42,000,000** with a **1.20×** covenant and a **1.15×** lock-up. The audit's first substantive finding was not an arithmetic error.

What happened. The auditor asked why **CFADS** was constant when the interest deduction was not, and rebuilt the tax line period by period. Cash tax rose from **516,000** in year one to **963,287** in year twelve as interest fell from **2,520,000** to **283,564**, and **CFADS** fell correspondingly from 6,384,000 to **5,936,713**. The **DSCR** profile declined monotonically to **1.1851** — a **covenant breach in year twelve** — while the twelve-year average stayed at **1.2340**, comfortably compliant. Three further findings followed from the same source: the present value of **CFADS** at 8 % was **65,315,883**, not the

68,147,771 the level line implied, an overstatement of **2,831,888** or **4.34 %**; the **LLCR** was **1.2395**, not the 1.2743 the level-cash identity had produced; and the appraisal **NPV** of +16,179,360 was a **pre-tax** figure over a **fifteen-year** horizon that had been carried into a financing paper without a bridge — the same asset on a post-tax, twenty-five-year, flat-revenue basis is **+2,767,684**.

How it resolved. The sponsors first proposed reporting the average, which the auditor rejected in one line: covenants are tested in periods. They then proposed an equity cure in the affected years, which is arithmetically small — restoring 1.20× in years eleven and twelve costs **21,347** and **74,849**, **96,196** in total — and was rejected for the right reason: a structure that is designed to need a cure has consumed an option it should be holding in reserve (Domain 10, KA 10.4.3). The structure closed instead at Domain 10's independently derived **41,171,123**, at which the instalment is **4,910,769** and the year-twelve **DSCR** is **1.2087**, inside the covenant. The debt level at which the year-twelve minimum is exactly 1.20× is **41,472,081**, so the binding constraint at close remained Domain 10's year-one 1.30× sizing test — 828,877 below the request — and the year-twelve problem was already covered by it. The sponsors funded the difference with equity, as Domain 10's case recorded, and the model went forward with a period-by-period tax line, a minimum-**DSCR** output with its year, and a four-line basis bridge from the appraisal to the financing case.

What the domain teaches here. A model can be arithmetically perfect and still hide the year in which the project breaches, because the hiding is done by an assumption — level cash — and not by an error. The mechanism was entirely predictable: the interest tax shield amortises with the loan. Two habits would have caught it before the auditor did, and both are cheap: report the minimum **DSCR** with its year, and never hold a line constant when a driver underneath it is not. The third lesson is about conservatism. Domain 10's 1.30× requirement looked like a bank being difficult; it was in fact protecting against a year-twelve exposure nobody in that negotiation had modelled. **A well-built model makes a conservative constraint legible as the specific risk it was guarding** — and that, rather than any single output, is what makes it worth its cost.

— Case study B — Domain 6: the forecast that was pasted, not linked (transport)

Situation. A toll-road concession, capital cost **420,000,000**, sought **294,000,000** of senior debt — 70 % gearing — at **6.5 % over 18 years**, on a sizing target of **1.35×** and a **1.30×** covenant. The annuity factor **AF(0.065, 18)** is **10.432466**, giving level debt service of **28,181,255**. The financing model showed steady-state **CFADS** of **38,000,000** and a **DSCR** of **1.3484** — comfortably inside the sizing target. The traffic forecast underneath it came from the technical adviser's separate demand model, imported as **pasted values** into a tab labelled "traffic input v3".

What happened. Eleven weeks before close the technical adviser issued a revised forecast **7 % lower**, reflecting a change to a competing route's toll policy. The revision was circulated, acknowledged and filed. Nobody re-pasted it, because the financing model's traffic tab was an input sheet and the model's change log recorded only formula changes. The lenders' model auditor found it by doing the one thing the sponsor's team had not: checking each external input's document version against the current issue. Rebuilt on the revised forecast, **CFADS** was **35,340,000** and the **DSCR** **1.2540** — **below the 1.30× covenant on the first test date**, and 0.096 below the sizing target the facility had been structured against.

How it resolved. Debt capacity at 1.35× on the revised forecast is $35,340,000 / 1.35 \times 10.432466 = 273,098,787$, so the facility had to fall by **20,901,213** and gearing from 70/30 to **65.0/35.0**. The sponsors funded it. Substituting 20,901,213 of equity for debt, at a 12 % equity requirement against 6.5 % debt over the 18-year tenor, costs $20,901,213 \times 0.055 \times AF(0.08, 18) = 20,901,213 \times 0.055 \times$

9.371887 = **10,773,610** of present value — the true price of a paste. The resize and re-diligence took six weeks; at forgone **CFADS** of **105,556** a day (38,000,000/360) the delay cost **4,433,333**, and re-cutting the schedule, re-running credit approval and re-issuing the information memorandum cost a further **900,000: 5,333,333** in total, over and above the equity substitution the truth required in any event. Had the error reached close, the reopening would have run twelve weeks against drawn debt at **158,639** a day (forgone **CFADS** plus interest on 294,000,000), with a 0.30 % amendment fee of 882,000 and 1,400,000 of advisers — **15,607,667**. **The audit's timing avoided 10,274,333.**

What the domain teaches here. Not one formula in the model was wrong. The defect was a **model boundary** with no provenance control across it, and the change log's scope — formula changes only — guaranteed that an input change would be invisible. Three controls would each have caught it independently: input provenance recording every external input's source document, version and date; a live link or a documented import with a version check rather than a paste; and a golden-answer regression suite, which would have flagged that **CFADS** had not moved when the forecast underneath it had. The economic lesson generalises beyond the sector: **the cost of a model error is set by how late it is found, and the expensive errors are almost never arithmetic.** Domain 13 makes this a diligence stream; here it is a modelling discipline that costs a spreadsheet column.

— Executive perspective — Domain 6

What a project finance director cannot delegate in this domain:

- **The basis, horizon and case of every number quoted upward.** Kestrel supports five correct **NPVs** spanning 29,545,516 (6.1.3). The director owns which one appears in a board paper and insists on the bridge to the others — because the number that survives in an organisation's memory is the one nobody labelled.
- **The tax line's provenance.** It moves debt capacity by 3,327,741 on one allowance assumption (6.2.3), it is jurisdiction-specific, it changes during a loan's life, and it must trace to a dated written opinion. This is the one input a director should be able to name the author of.
- **The minimum, with its year.** Kestrel's average **DSCR** of 1.2340 complies and its year-twelve minimum of 1.1851 breaches (6.4.1b). Averages in covenant reporting are a governance failure wearing a statistic.
- **The audit's timetable, not its fee.** Two weeks of delay cost 248,267 against a fee of 180,000; moving the audit early nearly doubles its value and cuts its breakeven error rate from 20.10 % to 8.05 % (6.4.3). The director's intervention is on the plan, and it must happen months before the auditor is appointed.
- **The distribution profile after reserve funding and lock-up.** 121,956 in operating year one on 18,000,000 of equity, and a 14.67-year equity payback from close (6.2.2, 6.3.3). Boards that have not seen this before close are boards that will be surprised after it.
- **One authoritative file, one named owner, one version on every page.** Case study B cost 5,333,333 and could have cost 15,607,667 because a superseded input survived a change log that did not cover inputs. Model governance is not a modelling matter; it is a control the director signs for.

— Calculation exercises — Domain 6

Exercise 6.1 A project has a **40,000,000** envelope funded **65/35** — 26,000,000 of debt at **7.0 %**, 14,000,000 of equity — with every use funded in that proportion. Committed uses: EPC **33,000,000**, owner's costs **2,500,000**, capitalised development **1,200,000**, arrangement fees at **1.75 %** of the facility. Construction runs **five quarters** with a spend profile of **10, 20, 25, 25 and 20 per cent**; interest accrues quarterly at 7.0 %/4 on the opening debt balance. Compute the fees, capitalised interest and the balancing contingency, and test the contingency against a 5–10 % of EPC policy band. Solution. Fees $26,000,000 \times 0.0175 = 455,000$. Iterating the quarterly draw and interest calculation gives capitalised interest of **849,752**. Contingency balances: $40,000,000 - 33,000,000 - 2,500,000 - 1,200,000 - 455,000 - 849,752 = 1,995,248$, which is **6.05 %** of the EPC price — inside the band, so the envelope is credible. Total uses 40,000,000; debt drawn 26,000,000; equity 14,000,000. Common error: treating contingency as a policy percentage and letting capitalised interest balance instead — which hides an IDC figure nobody has computed and produces a model whose construction interest is a plug.

Exercise 6.2 Net income 3,680,000; depreciation 2,500,000; receivables up 1,100,000; payables up 400,000; interest paid 2,100,000, classified in operating cash flow. Compute operating cash flow and **CFADS**. Solution. Operating cash flow $3,680,000 + 2,500,000 - 1,100,000 + 400,000 = 5,480,000$; **CFADS** $= 5,480,000 + 2,100,000 = 7,580,000$. Common error: deducting interest again to reach **CFADS** ($5,480,000 - 2,100,000 = 3,380,000$) — the interest has already been paid inside operating cash flow, and **CFADS** is struck before all debt service.

Exercise 6.3 A facility of **30,000,000** at **5.5 %** amortises over **10 years** on a level annuity. **EBITDA** is **6,000,000** flat, accounting and tax depreciation both **1,800,000**, the tax rate **25 %**, and the working-capital absorption **250,000** a year. Compute the instalment, the **DSCR** in years 1, 5 and 10, and state the minimum and its year. Solution. $AF(0.055, 10) = 7.537626$; instalment $30,000,000/7.537626 = 3,980,033$. Year 1: interest 1,650,000, cash tax $0.25 \times (6,000,000 - 1,800,000 - 1,650,000) = 637,500$, **CFADS** **5,112,500**, **DSCR** **1.2845**. Year 5: interest 1,093,531, tax 776,617, **CFADS** 4,973,383, **DSCR** **1.2496**. Year 10: interest 207,490, tax 998,128, **CFADS** 4,751,872, **DSCR** **1.1939**. Minimum **1.1939 in year 10** — the final year, as it must be when revenue is flat and the interest deduction amortises. Common error: computing year one and assuming coverage improves as debt falls; the debt service is level, so the only moving part is cash tax, and it moves the wrong way.

Exercise 6.4 On Kestrel's bank case (**CFADS** 6,384,000; instalment 5,009,635.23; covenant 1.20×; **CFADS** $= 0.75 \times \text{revenue} - 2,616,000$), compute the covenant's cash trigger, the revenue at which it is crossed, the fall as a percentage of revenue, and reconcile that percentage with Domain 10's headroom of 5.83 % of **CFADS**. Solution. Trigger $5,009,635.23 \times 1.20 = 6,011,562$. Revenue: $(6,011,562 + 2,616,000)/0.75 = 11,503,416$, a fall of **4.14 %**. The reconciliation is the elasticity: **CFADS** responds to revenue at $0.75 \times 12,000,000/6,384,000 = 1.4098$, so $5.83\%/1.4098 = 4.14\%$. Common error: quoting the **CFADS** percentage to a team that manages revenue, overstating their room by 41 %.

Exercise 6.5 A model audit costs **210,000** and adds delay worth **300,000**. The material-error probability is **0.28**, the detection probability **0.80**, the pre-close correction cost **90,000**, and the cost if the error reaches close **3,400,000**. Compute the audit's net value and its breakeven error rate. Solution. Without the audit $0.28 \times 3,400,000 = 952,000$. With it $210,000 + 300,000 + 0.28 \times$

$(0.80 \times 90,000 + 0.20 \times 3,400,000) = 510,000 + 0.28 \times 752,000 = 720,560$. Net value **231,440**. Breakeven error rate $(210,000 + 300,000)/(0.80 \times (3,400,000 - 90,000)) = 19.26\%$ — below that, the audit destroys value at this timing. Common error: omitting the elapsed cost, which reports a net value of 531,440 and a breakeven error rate of 7.93 %, flattering the control by more than twice.

— Practitioner's toolkit — Domain 6

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 6.T.1 — The model conventions sheet (one page, in the inputs block)

One line per convention, each with the value chosen, the alternative rejected, and the reason: period length (and why); flow timing (period end, start, mid-period); day-count basis; interest accrual base (opening or average balance) **and the circularity resolution chosen**; first-period stub treatment; currency and units; sign convention; rounding, and where it is applied; the basis (pre/post-tax, levered/unlevered, before/after working capital); the horizon and the treatment of value beyond it; and the named case list with the single input that switches between them. Rule: a convention absent from this sheet may not be relied on in a printed output, and the sheet's version matches the model's.

Toolkit 6.T.2 — The check block (built before the first answer)

- [] Balance sheet balances, every period — difference nil.
- [] Sources = uses, every construction period, not only in total.
- [] Closing debt nil at maturity, per facility; Σ scheduled principal = total drawings.
- [] Cash ≥ 0 in every period and every account; every waterfall tier floored, shortfalls carried.
- [] **CFADS** = operating cash flow + interest paid.
- [] Implied effective tax rate = statutory rate + explained differences, period by period.
- [] Timeline flags: four additions hold; no period double-flagged.
- [] Minimum **DSCR and its year** reported beside the average; **LLCR** = **DSCR** only where cash is level and service is an annuity at the loan rate; **PLCR** $\geq$ **LLCR** where a tail exists.
- [] No numeral in any calculation cell other than a period counter.
- [] Golden-answer regression suite reruns clean, or every change is explained and accepted.
- [] Aggregate flag visible on the output page; **no output quoted while it is red**.

Toolkit 6.T.3 — Model governance register (per model, per version)

Columns: version number (appearing on every printed page) · date · author · reviewer · reason for the version · change list (from the version diff, inputs **and** formulae) · check-block status · golden-answer status · **input provenance table** (each external input: source document, its version, its date, who confirmed it against the current issue) · freeze status and change-control authority after freeze · basis, horizon and case list as released · outstanding audit findings by severity with owners and dates · AI-assisted edits, with the tool, the prompt intent, the human author and the diff reference. Front line: **which file is authoritative, who owns it, and what its check block says today**.

— Exam preparation — Domain 6

What is assessed. The three-block rule and the flag invariants; sources and uses with computed capitalised interest and an identified balancing line; the effect of periodicity and interest convention; accounting depreciation against tax allowances, and their coverage and capacity consequences; the three-statement articulation and the **CFADS** tie; debt-schedule invariants and circularity resolutions; waterfall construction, reserve funding and release, and the distribution test; project return against equity return; the six check-block invariants and what each can and cannot see; sensitivity, elasticity, the breakeven translation and the limits of one-at-a-time; and the economics of model audit and AI-assisted controls.

The calculations to do under time pressure. Capitalised interest from a drawdown profile on a stated convention, and the balancing line that follows (6.2.1, Exercise 6.1). Operating cash flow to **CFADS** via the interest tie (6.2.2, Exercise 6.2). Cash tax from taxable profit, and the **DSCR** in a late loan year when the interest deduction has shrunk (6.2.3, 6.4.1b, Exercise 6.3). Minimum **DSCR** and its year. Elasticity from two **NPVs**, and a ratio threshold translated into an input level (6.4.2, Exercise 6.4). Review net value and its three breakevens (6.4.3, Exercise 6.5).

The traps. Quoting an **NPV** without its basis, horizon and case — the 29,545,516 spread (6.1.3, MCQ 6.1-A) · an annual timeline with opening-balance interest, understating capitalised interest by 41.01 % (6.1.2, MCQ 6.1-B) · letting capitalised interest balance the sources-and-uses table instead of contingency (Exercise 6.1) · a round balancing line, which means the table was plugged (6.2.1, MCQ 6.2-A) · deducting interest twice on the way to **CFADS** (6.2.2, MCQ 6.2-B) · taxing **EBIT** instead of taxable profit, which balances perfectly (6.4.1, MCQ 6.4-A) · treating a balancing balance sheet as evidence of accuracy (6.4.1) · reporting average rather than minimum **DSCR** (6.4.1b, MCQ 6.4-B) · holding **CFADS** level when the interest deduction is amortising (6.4.1b, Case study A) · reading only the **NPV** column of a sensitivity table and concluding interest-rate risk is immaterial (6.4.2, MCQ 6.4-C) · comparing elasticities across cases (6.4.2) · carrying a **CFADS** percentage across as a revenue percentage, overstating headroom by 41 % (6.4.2, MCQ 6.4-D) · omitting elapsed time from review economics (6.4.3, Exercise 6.5) · treating an AI detection rate as constant across error classes (6.4.4) · a change log that covers formulae but not inputs (Case study B).

How the domain connects. It industrialises Domain 3's discounting and Domain 4's appraisal and audits both — Worked example 6.1.3 reconciles Domain 4's **NPV** to the financing model — and it implements Domain 2's statements, **CFADS** definition and cash-versus-accounting tax distinction. It supplies the drawdown Domain 5's slip arithmetic priced and the model whose coverage Domain 10 negotiated, earning Domain 10's minimum-**DSCR** rule rather than asserting it. Domains 7, 8 and 9 supply the revenue, cost and funding blocks this architecture consumes; Domain 13 makes the model audit a diligence stream and a condition precedent; Domain 14 runs the construction model against actual drawdowns; Domain 15 operates the waterfall of 6.3.2; Domain 16 generalises 6.4.4's controls into model-risk governance.

— Domain 6 summary

A financial model's authority comes from its architecture and its checks, not from its answers, and Kestrel proves it four times over. **One project supports five arithmetically correct net present values spanning USD 29,545,516** — from -9,670,265 to +19,875,251 — differing only in basis, horizon and case; Domain 4's **+16,179,360** is the pre-tax, fifteen-year member of that family, reconciled to Domain 2's **CFADS** by an implied escalation of **2.967 %** to within 661 of present value, and the required deliverable is the bridge rather than any one number. **Convention is worth more than most contested assumptions:** the same drawdown at the same 6.0 % returns capitalised

interest of **2,114,597** quarterly on opening balances and **1,247,352** annually — a 41.01 % understatement that propagates silently into the depreciation base — while the sources-and-uses table closes at **60,000,000** on a balancing contingency of **3,645,403**, 7.59 % of the EPC price, and a balancing line that is never round. **The tax line is the most consequential row in the model:** a 15 % declining-balance allowance regime would take year-one **CFADS** from 6,384,000 to **6,900,000**, **DSCR** from 1.2743 to **1.3773**, and debt capacity at 1.30× from 41,171,123 to **44,498,864** — a 3,327,741 swing, four times the gap Domain 10's whole negotiation was fought over. **Balancing is necessary and not sufficient:** taxing **EBIT** instead of taxable profit gives a **CFADS** of 5,880,000, a **DSCR** of 1.1737, a debt-capacity shortfall of **3,250,352** — and a balance sheet that balances to the cent, caught only by an implied effective tax rate of **39.53 %** against a statutory 20 %. And **the level-cash shortcut hides a breach:** modelled period by period, Kestrel's coverage declines from 1.2743 to **1.1851 in year twelve** against a 1.20× covenant, while the twelve-year average of **1.2340** complies — which is why the minimum and its year are reported, and why Domain 10's 1.30× sizing test, at **41,171,123** with a year-twelve **DSCR** of 1.2087, was already protecting against a risk nobody in that negotiation had modelled. The first operating year articulates completely — operating cash flow **3,864,000**, **CFADS** **6,384,000** through the interest tie, a closing balance sheet of **59,752,409** on both sides, and a distribution to equity of **121,956**, 0.68 % of the 18,000,000 contributed — and the returns it leads to are honest about who earns what: the asset **8.54 %**, the equity **9.83 %** on the bank case and **13.52 %** with escalation, with equity payback **14.67 years** from close. Sensitivity ranks revenue first at an elasticity of **6.27** on the sponsor case and **34.71** on the bank case — proof that elasticity is a property of the case — reports **0.00** elasticity of unlevered value to the interest rate while the same move drives the minimum **DSCR** to 1.1485, and translates coverage into the language operations use: the covenant breaks at revenue **4.14 %** below base, not the 5.83 % of **CFADS** Domain 10 quoted. Review economics close the domain: a model audit worth **317,547** late and **602,744** early, with breakeven fee **497,547**, breakeven error rate falling from **20.10 %** to **8.05 %** on timing alone, and an AI pre-check worth **498,481** that still cannot substitute for the audit because its detection rate is not independent of the error class it misses. Domain 7 builds the revenue block this architecture consumes, Domain 8 the cost and contingency block, Domain 9 the sources side, Domain 13 the audit as a condition precedent, and Domain 16 the model-risk governance this domain's controls anticipate.

07

DOMAIN 7

Revenue, Demand and Commercial Models

— Why this domain exists

Domains 5 and 6 left one question open. Domain 5 established that a bankable project needs a creditworthy payer under a contract of adequate tenor (KA 5.3.2); Domain 6 built the model that turns a revenue forecast into coverage; Domain 10 sized debt from [CFADS](#) and a target coverage ratio and treated both as given. None of them addressed how the **shape** of the revenue promise — its architecture, not its expectation — determines how much debt exists to be sized. This domain shows where [CFADS](#) and the target ratio come from, and the answer changes the negotiation.

The central claim is a single sentence with expensive consequences: **debt is sized on the worst period a lender will underwrite, so the distribution of revenue matters more than its mean, and two commercial structures with identical expected cash can differ in debt capacity by a quarter of the facility.** Everything in the domain is a corollary. The contracted-to-merchant spectrum (KA 7.1) is a spectrum of dispersion, priced by lenders in required coverage before it is priced in a tariff. Demand-based and concession structures (KA 7.2) put the dispersion inside a payment mechanism whose banded, floored and shared forms are risk-transfer instruments in tariff clothing. Escalation and volume risk (KA 7.3) are the two ways a structure that looked adequate at close stops being adequate later — one slowly and arithmetically, the other quickly and non-linearly. And counterparty credit and stress testing (KA 7.4) make the rest conditional: a contracted stream is worth the payer's ability to pay, and concentration is invisible to the expected-loss calculation a credit committee will nevertheless be shown.

Learning objectives. After this domain a candidate can: place a revenue structure on the contracted-merchant spectrum and state the coverage consequence of its position; distinguish capacity, energy, availability, take-or-pay and merchant mechanisms and compute revenue under an availability-deduction formula; demonstrate that two structures with identical expected [CFADS](#) support materially different debt, and size each correctly; distinguish sponsor, bank and downside cases and model a ramp; compute revenue under banded, floored and shared mechanisms and value the risk transfer they effect; compute effective escalation rates on partly indexed tariffs and cost bases and quantify the resulting margin drift; compute the degree of operating leverage and the [CFADS](#) elasticity to price and to volume and explain why they differ; convert a coverage threshold into a tolerance in each driver a business manages; compute expected loss as probability of default times exposure times loss given default, and demonstrate why it is blind to concentration while the loss distribution is not; price credit enhancement against the coverage it unlocks; design and read a stress matrix and a reverse stress test; and govern AI-assisted demand forecasting, contract extraction and counterparty monitoring.

The master thread. Kestrel Water SPC continues. Its first operating year, established in Domain 2 and modelled in Domain 6 (KA 6.2.2), is revenue **USD 12,000,000**, cash operating costs **4,500,000**,

EBITDA 7,500,000, depreciation 2,400,000, interest 2,520,000, cash tax 516,000 and a working-capital absorption of 600,000, giving **CFADS 6,384,000** against debt service of **5,009,635.23** — a **DSCR** of **1.2743** (Domain 10, KA 10.2.1). This domain opens that revenue line for the first time. The plant's nameplate capacity is **30,000,000 m³ a year** (about 82,192 m³ a day); expected despatch is **24,000,000 m³**, an 80 % load factor; the water-purchase agreement pays **USD 0.50 per m³** of expected despatch, and the cost base splits into **3,600,000 of fixed** cash operating cost and **USD 0.0375 per m³ variable**. Every figure in the domain is built from those five inputs, and one closed form recurs throughout:

$$\text{CFADS} = 0.75 \times \text{revenue} - 0.03 \times \text{volume(m}^3\text{)} - 1,896,000$$

— the **CFADS** bridge of KA 6.2.2 written as a function of the two commercial variables, absorbing the fixed cost, the 20 % tax rate applied to **EBITDA** less depreciation and interest, and the working-capital absorption of 5 % of revenue. Substituting revenue 12,000,000 and volume 24,000,000 returns **6,384,000** exactly. It is the domain's arithmetic engine, and every result below is reproducible from it.

KNOWLEDGE AREA 7.1

Contracted and merchant revenue, tariffs and availability payments

Topics: 7.1.1 the revenue-risk spectrum · 7.1.2 tariff architecture · 7.1.3 availability payments and the deduction mechanism.

7.1.1 The revenue-risk spectrum

Definition. A project's revenue structure sits on a spectrum defined by **who bears the risk that the asset earns less than forecast**. At the contracted end a creditworthy payer is obliged to pay a defined amount whether or not it takes the output, provided the asset is available; at the merchant end the project sells into a market at prices and volumes nobody has promised. Intermediate forms — take-or-pay, capacity plus energy, minimum revenue guarantees, volume bands — allocate the risk in specified proportions.

Why the spectrum, not the mean, governs debt. Domain 10 sized debt as **CFADS** divided by the target **DSCR**, times the annuity factor. Both numerator and divisor move with position on this spectrum, and they move in the same direction, so the effect compounds: merchant revenue lowers the case a lender will underwrite and raises the coverage it requires. That double movement is the domain's first quantitative result.

WORKED EXAMPLE**Worked example 7.1.1 — two structures, one expected cash flow, and 10.7 million of debt.**

- Setup.** Kestrel's offtaker will accept either of two structures for the same plant. **Structure A (availability payment):** a capacity charge of **12,000,000 a year** for making 30,000,000 m³ of capacity available, subject to deduction for unavailability; the offtaker takes all volume risk. **Structure B (volume tariff):** **USD 0.50 per m³** of water actually taken, with no minimum. Independent demand study gives three despatch outcomes: **28,800,000 m³** with probability 0.25, **24,000,000 m³** with probability 0.50 and **19,200,000 m³** with probability 0.25. Cost base and tax as the master thread. Compute **CFADS** and **DSCR** in each outcome, the expected values, and the debt each structure supports.
- Formula.** $CFADS = 0.75R - 0.03V - 1,896,000$; $DSCR = CFADS \div 5,009,635.23$; expected value = $\Sigma(\text{probability} \times \text{outcome})$; debt capacity = $(CFADS \div \text{target } DSCR) \times AF(0.06, 12)$, with $AF(0.06, 12) = 8.383844$ (Domain 3).
- Substitution and result.**

Structure B outcome	Volume (m ³)	Revenue	EBITDA	Cash tax	Δ working capital	CFADS	DSCR
High (p 0.25)	28,800,000	14,400,000	9,720,000	960,000	720,000	8,040,000	1.6049
Base (p 0.50)	24,000,000	12,000,000	7,500,000	516,000	600,000	6,384,000	1.2743
Low (p 0.25)	19,200,000	9,600,000	5,280,000	72,000	480,000	4,728,000	0.9438
Expected	24,000,000	12,000,000	—	—	—	6,384,000	1.2743


Structure A delivers **CFADS** of **6,384,000** with certainty subject to availability. Debt capacity: Structure A at the credit committee's $1.30 \times$ target supports **41,171,123** (Domain 10's figure, unchanged). Structure B, underwritten on the low case at the same $1.30 \times$, supports debt service of 3,636,923 and debt of **30,491,396**; underwritten on expected **CFADS** at a merchant-appropriate $1.50 \times$ it supports **35,681,640**. 4. **Interpretation.** The expected **CFADS** is **identical to the dollar** — 6,384,000 in both structures — and so is the expected **DSCR**, at 1.2743, because **DSCR** is linear in **CFADS** when debt service is fixed. An adviser who reports expected values has reported that the two structures are the same. They differ by **10,679,727 of debt capacity, 25.94 %** of the contracted structure's, and by **11,508,604** against the sponsors' 42,000,000 request. Every dollar of that gap is equity, and Domain 10 showed what a mere 828,877 of it did to the sponsors' return.

Three readings deserve to leave this example. **First, the mean is not a coverage ratio.** Coverage is tested in a period, and lenders underwrite the period they are prepared to be wrong about — commonly a P90 or an explicitly stressed case, never the mean. In the low outcome Structure B's **DSCR** is **0.9438**: debt service is not merely uncovered by covenant, it is unpaid from operating cash. A structure with a one-in-four chance of failing to pay is not a $1.2743 \times$ project with a caveat; it is a different credit. **Second, the case moves as well as the ratio**, and a leader who negotiates only the ratio while letting the case be chosen unopposed has conceded the larger of the two variables. **Third, the risk has a computable price.** Structure A transfers volume risk to the offtaker, who will charge for it in tariff, tenor or termination terms. The question is never "which structure is better" but "is the offtaker's price for taking volume risk less than 10,679,727 of equity plus the return on it?" Asking that question is the professional act.

The same expected CFADS of 6,384,000 — and 10,679,727 less debt

Expected DSCR is 1.2743 in both structures. The lender sizes on the low case, not the mean

Availability: 41,171,123 of debt at 1.30×. Volume tariff: 30,491,396 at 1.30× on the low case



A mean is not a coverage ratio: coverage is tested in the worst period, never in the average one

Fig 7.1.1 — Identical expected cash, different bankability

7.1.2 Tariff architecture

Definition. A **tariff** is the formula by which the payer's obligation is computed; its architecture, not its headline level, determines which party bears which risk. Four building blocks recur across sectors under different names.

Block	What it pays for	Risk it leaves with the project
Capacity / availability charge	Making the asset available, whether or not output is taken	Availability, and therefore reliability and maintenance
Energy / variable / usage charge	Output actually taken, usually at a pass-through or indexed unit rate	Efficiency against a contracted rate; sometimes none
Take-or-pay minimum	A floor volume, paid whether taken or not	Volume above the floor only
Merchant tail	Output sold outside the contract	Price and volume, entirely

The **two-part tariff** — capacity plus variable — is the most common bankable form because it separates the recovery of fixed costs and debt service (which cannot flex) from the recovery of variable costs (which can). Its discipline is a matching test: **the capacity charge should recover fixed cash costs, debt service and the return on capital; the variable charge should recover variable costs at contracted efficiency, no more.** A tariff that recovers fixed costs through a volume-linked charge has converted a fixed obligation into a variable receipt, which is the structural error behind much demand-risk distress. Kestrel's Structure B is that error in pure form: 3,600,000 of fixed cost and 5,009,635 of debt service, recovered per cubic metre.

Take-or-pay and its limits. A floor is worth what the party writing it is good for — Domain 5's creditworthiness condition, with a number attached. Two cautions. Take-or-pay volumes are frequently **make-up** rights rather than pure obligations: the payer pays for volume not taken but may take it later at no further charge, which protects cash timing far less than a summary suggests. And **the floor's tenor must reach the loan's**; an eight-year take-or-pay against a twelve-year loan is a merchant tail with a delay (KA 7.A.2).

7.1.3 Availability payments and the deduction mechanism

Definition. An **availability payment** pays for the asset being available to a defined standard rather than for output, reduced by **deductions** when the standard is not met. The deduction formula, not the headline payment, is where the exposure lives: it converts an operational measure into a cash loss, usually at a multiple, and is routinely modelled as though the multiple were one.

WORKED EXAMPLE

Worked example 7.1.3 — the four points of availability that breach a covenant.

- Setup.** Kestrel adopts Structure A. The capacity charge is **12,000,000**; guaranteed availability is **95 %** of nameplate hours; the deduction is the capacity charge multiplied by the availability shortfall in decimal terms and by a **1.5 × liquidated-damage multiplier**. Output falls in proportion to the shortfall applied to expected despatch, so variable cost falls with it. Compute revenue, **CFADS** and **DSCR** at 93 % and 91 % availability, and find the availability at which the 1.20 × covenant, the 1.15 × lock-up and payment itself fail.
- Formula.** Let s be the shortfall in decimal availability points. Deduction = $12,000,000 \times 1.5 \times s$; revenue = $12,000,000 - 18,000,000 s$; volume = $24,000,000 \times (1 - s)$. Substituting into the **CFADS** bridge gives the linear form **CFADS** = $6,384,000 - 12,780,000 s$.
- Substitution.** At $s = 0.02$: deduction 360,000; revenue 11,640,000; volume 23,520,000. At $s = 0.04$: deduction 720,000; revenue 11,280,000; volume 23,040,000. Thresholds solve $6,384,000 - 12,780,000 s = 5,009,635.23 \times \text{threshold}$.
- Result.**

Availability	Shortfall s	Deduction	Revenue	CFADS	DSCR
95.000 %	—	—	12,000,000	6,384,000	1.2743
93.000 %	2.000 pts	360,000	11,640,000	6,128,400	1.2233
92.086 %	2.914 pts	524,560	11,475,440	6,011,562	1.2000 ← covenant
91.000 %	4.000 pts	720,000	11,280,000	5,872,800	1.1723
90.126 %	4.874 pts	877,351	11,122,649	5,761,081	1.1500 ← lock-up
84.246 %	10.754 pts	1,935,725	10,064,275	5,009,635	1.0000 ← payment fails

- Interpretation.** The operational number a plant manager recognises is availability, and the sentence this table produces belongs on an operations dashboard: **Kestrel breaches its covenant at 92.09 % availability — 2.91 points of headroom against a 95 % guarantee.** That is not comfortable. It is the same headroom Domain 10 reported as 372,438 of annual cash and Domain 6 as a 4.14 % revenue fall, expressed in the unit the people who control it actually manage.

The mechanism is where the arithmetic surprises people. A single point of availability costs **127,800 of CFADS** — the slope of the linear form — of which 180,000 is lost revenue and 52,200 is recovered through lower variable cost, tax and working-capital absorption. **The 1.5 × multiplier is doing most of the damage.** The general slope is $9,000,000 \times \text{multiplier} - 720,000$, so at a multiplier of 1.0 it falls to 8,280,000 and the covenant does not break until **90.502 %** — the negotiated multiplier costs **1.584 percentage points** of operating tolerance. (At a multiplier of 1.0 that slope is exactly the volume term of KA 7.3.2, because a pro-rata deduction is economically identical to losing the output.) Multipliers, caps on cumulative deductions, cure periods, planned-outage allowances and the treatment of force majeure and offtaker-caused unavailability are therefore first-order commercial terms, not schedules for the technical adviser. The caution is blunt: **an availability structure is not a risk-free structure, it is one whose risk has been converted from demand into operations.** Kestrel's revenue is now a function of its own reliability — a risk it controls but must then actually control, with Domain 10's maintenance reserve funded and the outage plan built around the deduction formula rather than engineering convenience.

AI in this KA

Machine assistance earns its place in three tasks. **Extracting the payment mechanism** — charge formulae, deduction multipliers, caps, outage allowances, indexation clauses and their cross-references — is high-volume reading that models do well and humans do inconsistently, and the output is a specification a modeller can implement (Toolkit 7.T.1). **Reconciling the modelled tariff to the contractual tariff** by recomputing a historical invoice from the extracted formula is a genuine test with a right answer. And **monitoring deductions** against availability data as it accrues turns a quarterly surprise into a weekly signal.

Where it must not go: **the deduction formula must never be paraphrased into the model.** A summary rendering "1.5 times the availability shortfall applied to the capacity charge" as a pro-rata reduction understates Kestrel's exposure by a third and moves the covenant breakpoint by 1.584 availability points — an error no downstream check catches, because the model is internally consistent and wrong. And a model must not be asked to choose the structure: Worked example 7.1.1 is arithmetic, but judging what the offtaker's price for volume risk is worth is a commercial decision with an accountable owner. Verification is concrete: recompute one period's revenue from the clause text by hand, at full and at reduced availability, and confirm both against the model before quoting any coverage ratio derived from it. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 7.1

Term	Meaning
Contracted / merchant revenue	Revenue under an obligation to pay / revenue sold into a market with no obligation.
Capacity (availability) charge	Payment for making the asset available, independent of output taken.
Two-part tariff	Capacity charge plus variable charge; separates fixed-cost recovery from output.
Take-or-pay	Contractual floor volume paid whether taken or not; often subject to make-up rights.
Availability deduction	Reduction in the capacity charge for failing the availability standard, commonly at a multiplier.
Deduction multiplier	The factor applied to the availability shortfall; converts one operational point into more than one point of cash.

■ SAMPLE MCQS — KA 7.1

MCQ 7.1-A [7.1.1 · Analysis] Two structures for the same plant have identical expected **CFADS** of 6,384,000 and identical expected **DSCR** of 1.2743. Structure A pays that amount with certainty; Structure B's outcomes are 4,728,000 / 6,384,000 / 8,040,000 with probabilities 0.25 / 0.50 / 0.25. The soundest conclusion is:

- A. the structures are equivalent, since expected coverage is the same
- B. Structure B supports materially less debt, because a lender underwrites a stressed or low case and requires higher coverage for dispersion **✓ CORRECT**
- C. Structure B supports more debt, because its upside outcome is higher
- D. the difference can be resolved by raising the target **DSCR** alone

Rationale: Sizing on the low case at $1.30 \times$ gives 30,491,396 against 41,171,123 — a 10,679,727 gap (7.1.1). A treats a mean as a coverage ratio, which coverage tests never are; C mistakes an upside the lender has no claim on for capacity; D captures only part of the effect, since the case moves as well as the ratio.

MCQ 7.1-B [7.1.3 · Application] A capacity charge of 12,000,000 carries a 95 % availability guarantee and a deduction equal to the charge multiplied by the shortfall and by 1.5. At 91 % availability the deduction is:

- A. USD 480,000
- B. USD 720,000 **✓ CORRECT**
- C. USD 1,620,000
- D. USD 600,000

Rationale: $12,000,000 \times 1.5 \times 0.04 = 720,000$. A omits the $1.5 \times$ multiplier; C applies the multiplier to total unavailability (9 points, $1 - 0.91$) instead of the shortfall against the 95 % guarantee; D applies a 5 % reduction, reading the guarantee as the deduction base.

MCQ 7.1-C [7.1.2 · Analysis] A project recovers all of its fixed cash costs and its entire debt service through a per-unit volume charge with no floor. The structural defect is:

- A. the unit rate will be too low to be commercial

- B. fixed obligations are funded by a variable receipt, so any volume shortfall falls entirely on coverage ☒ **CORRECT**
- C. the tariff cannot be indexed
- D. it prevents the use of an availability standard

Rationale: Matching discipline requires fixed-cost and debt-service recovery in a charge that does not flex with volume (7.1.2). A is a pricing observation, not a structural one; C and D are simply untrue of volume tariffs.

MCQ 7.1-D [7.1.3 · Analysis] Kestrel breaches its $1.20 \times$ covenant at 92.086 % availability. Reducing the negotiated deduction multiplier from 1.5 to 1.0 would move that breakpoint to 90.502 %. The correct reading is:

- A. the multiplier is a technical schedule with no financial consequence
- B. the multiplier costs 1.584 percentage points of operating tolerance and is therefore a first-order commercial term ☒ **CORRECT**
- C. the multiplier only matters if availability falls below 90 %
- D. the breakpoint depends on the tariff level, not the multiplier

Rationale: The multiplier scales the slope of the **CFADS** line against availability, so it scales headroom directly (7.1.3). C inverts the logic — the multiplier is what brings the breakpoint closer; D ignores that the deduction is computed on the charge and the multiplier together.

MCQ 7.1-E [7.1.1 · Evaluation] Kestrel's offtaker will take volume risk under Structure A, but only for a capacity charge of **11,600,000** instead of 12,000,000. **CFADS** becomes 6,084,000, **DSCR** 1.2145, and debt capacity at $1.30 \times$ becomes **39,236,390** — against 41,171,123 at the full charge and 30,491,396 under the volume tariff sized on its low case. The 400,000 a year has a present value of 4,269,910 over the 25-year concession at 8 %. The soundest recommendation is:

- A. reject the reduction: 4,269,910 of present value is surrendered permanently for a one-off financing benefit
- B. accept it: the offtaker's price for taking volume risk is 4,269,910 of concession-life value against 8,744,994 of debt capacity released, so it is well below what the risk transfer is worth ☒ **CORRECT**
- C. accept it, because an availability structure is always more bankable than a volume tariff
- D. reject it and negotiate the $1.30 \times$ target down instead, since the ratio is the variable that matters

Rationale: this is the question KA 7.1.1 says is the professional act — is the offtaker's price for volume risk less than the equity the transfer releases? — and here it is, by a factor of more than two, with 1.2145 still clear of the covenant. A performs half the calculation: the capacity it buys is not a one-off benefit but equity permanently not subscribed. C is the unsupported generality, and 7.1.3 shows what the structure actually does — converts demand risk into operational risk, with the covenant breaking at 92.09 % availability. D inverts the domain's central finding: the case moves as well as the ratio, and the case is the larger of the two variables.

MCQ 7.1-F [7.1.3 · Evaluation] A contract summary renders the deduction clause — the capacity charge multiplied by the availability shortfall and by a $1.5 \times$ liquidated-damage multiplier — as a pro-rata reduction of the charge, and the modeller builds it that way. The model balances and every check in it passes. The soundest professional position is that:

- A. the difference is immaterial while the model is internally consistent and its checks pass

- B. one period's revenue must be recomputed from the clause text by hand, at full and at reduced availability, before any coverage ratio derived from it is quoted: the paraphrase cuts the slope of **CFADS** against availability from 12,780,000 to 8,280,000 — 35.21 % — and moves the covenant breakpoint from 92.086 % to 90.502 % ✓ CORRECT
- C. the deduction schedule belongs to the technical adviser, so the commercial team should work from the summary it was given
- D. the target **DSCR** should be raised to restore the coverage the paraphrase removed

Rationale: the slope is $9,000,000 \times \text{multiplier} - 720,000$, so a multiplier read as 1.0 turns 127,800 of **CFADS** a point into 82,800, and **no downstream check catches it** because the model is internally consistent and wrong (7.1.3). A is precisely the reasoning that lets the error survive review. C misallocates a first-order commercial term to a technical annexe. D prices a definitional error as though it were a risk, which buries it inside a ratio instead of correcting it.

MCQ 7.1-G [7.1.2 · Comprehension] A take-or-pay minimum and an availability payment differ in what each leaves with the project:

- A. they are equivalent, both being contracted revenue from a creditworthy payer
- B. a take-or-pay floor covers volume below a contracted minimum — and is frequently a make-up right, so the payer may take the volume later at no further charge — while an availability payment removes volume risk altogether and substitutes an obligation to be available ✓ CORRECT
- C. take-or-pay transfers operating risk to the payer, while an availability payment retains it
- D. take-or-pay protects against price and an availability payment against cost

Rationale: a floor is worth what the party writing it is good for and often protects cash timing far less than a summary suggests, while an availability structure converts demand risk into operational risk the project must then genuinely manage (7.1.2, 7.1.3). A ignores that the two leave different risks behind. C reverses the availability mechanism, whose whole point is that the project answers for availability. D names risks neither instrument addresses.

■ SELF-CHECK — KA 7.1

1. Why does an expected **DSCR** convey nothing about bankability? — Coverage is tested in a period; lenders underwrite a low or stressed case, and dispersion also raises the required ratio, so the mean moves neither variable.
2. State Kestrel's covenant breakpoint in availability terms and in cash terms. — 92.086 % availability; **CFADS** of 6,011,562, which is 372,438 of annual cash below base (Domain 10).
3. What has an availability structure actually done to a project's risk? — Converted demand risk into operational risk, which the project controls but must then genuinely manage.

KNOWLEDGE AREA 7.2

Demand models, concessions and service revenue

Topics: 7.2.1 demand forecasting and the ramp · 7.2.2 concession payment mechanisms · 7.2.3 subscription and service revenue.

7.2.1 Demand forecasting and the ramp

Definitions. A **demand model** forecasts the quantity of output the market will take at a given price over the asset's life. The **ramp** is the period after commercial operations during which realised demand approaches its mature level as users discover and reorganise around the asset. **Optimism bias** is the tendency of forecasts prepared by parties interested in the project proceeding to exceed outturn — a documented pattern in demand-risk infrastructure, and the reason lenders commission their own market adviser rather than reviewing the sponsors'.

The professional content here is not forecasting technique, which belongs to market specialists, but the **discipline of using a forecast in a financing**. Three practices carry almost all the value.

Separate the cases and name their owners. The **sponsor case** is the sponsors' central expectation; the **bank case** is what lenders will lend against, typically the sponsor case with specified haircuts, a slower ramp, no unindexed growth and a conservative price deck; the **downside case** is the stress the structure must survive. Domain 6 (KA 6.1.3) made this a modelling rule; here it is a commercial one, because the gap between the cases is the gap between the sponsors' return and the lenders' credit — Domain 6 priced it on Kestrel at **17,107,567 of NPV** from the escalation assumption alone.

Model the ramp explicitly and let the debt schedule respond. Level debt service against a rising cash profile wastes coverage late and breaches early, which is the case for sculpting (Domain 10, KA 10.1.3). The recurring error is to model the ramp in the revenue line and then size level debt on the mature year: the ratio computed on year five is met, and the covenant tested in year two is not.

State the forecast's elasticity, not only its level. A demand forecast at a given tariff is an implicit price-elasticity assumption. Where the project sets price — a toll road, a car park, a data-centre re-let — a shortfall can be met by raising price only if elasticity permits; where price is contractual it cannot be met at all. A demand model presented without its elasticity has withheld the one property that determines whether management has a lever.

7.2.2 Concession payment mechanisms

Definition. A **concession** grants a private party the right and obligation to build, finance and operate a public asset for a defined term, with revenue arriving through a payment mechanism the grant defines and the asset handed back at the end. The mechanism is the risk allocation, and the standard family is worth naming because the names travel badly between jurisdictions and sectors.

Mechanism	Who pays	Volume risk sits with	Typical use
Availability payment	The grantor, from budget	The grantor	Social infrastructure, non-tolled roads, some water
Real toll / user charge	Users, directly	The project	Toll roads, ports, car parks
Shadow toll	The grantor, per unit of measured usage	Shared: the project bears volume, the grantor bears price	Roads where user charging is politically unavailable
Volume band	Either, per unit within defined bands at declining rates	Shared by construction	Water, waste, transport with uncertain demand
Minimum revenue guarantee with revenue sharing	Grantor tops up below a floor; shares above a ceiling	Shared symmetrically	Long concessions with contested forecasts

WORKED EXAMPLE**Worked example 7.2.2 — what a volume band is worth.**

- Setup.** Kestrel's offtaker will not accept Structure A's full volume risk but offers a **banded tariff: USD 0.55 per m³** on the first 18,000,000 m³, **USD 0.35** on the next 6,000,000 m³, and **USD 0.10** on anything above 24,000,000 m³. At expected despatch of 24,000,000 m³ the band structure pays exactly 12,000,000, so the headline tariff is unchanged. Using the same three demand outcomes as Worked example 7.1.1, compute revenue, **CFADS** and **DSCR**, the expected values, and the debt capacity on the low case at 1.30 ×.
- Formula.** Banded revenue = $\Sigma(\text{volume in band} \times \text{band rate})$; **CFADS** and **DSCR** as before.
- Result.**

Outcome	Volume (m ³)	Banded revenue	Flat-tariff revenue	CFADS banded	DSCR banded	DSCR flat
High (p 0.25)	28,800,000	12,480,000	14,400,000	6,600,000	1.3175	1.6049
Base (p 0.50)	24,000,000	12,000,000	12,000,000	6,384,000	1.2743	1.2743
Low (p 0.25)	19,200,000	10,320,000	9,600,000	5,268,000	1.0516	0.9438
Expected	24,000,000	11,700,000	12,000,000	6,159,000	1.2294	1.2743

Debt capacity on the low case at 1.30 ×: **33,973,915** banded against 30,491,396 flat — a gain of **3,482,520**. The expected revenue given up is **300,000 a year**, 2.50 % of base revenue, whose present value over the twelve loan years at 6 % is **2,515,153**. 4. **Interpretation.** The band is a risk-transfer instrument dressed as a price list, and its economics are explicit once computed: the sponsors surrender 2,515,153 of present value and receive 3,482,520 of debt capacity, a **net gain of 967,367** before the return on the equity released. Whether that is a good trade depends on the cost of equity against the cost of debt (Domain 9), but the method matters more than the answer: a negotiating team that has not computed it is arguing about band rates without knowing which way it wants them to move.

Two further readings matter more than the headline. **The band compresses the distribution from both ends, and the lender pays for only one end.** **DSCR** dispersion narrows from 0.9438–1.6049 to 1.0516–1.3175: the low tail improves by 0.1078 of coverage and the high tail is surrendered entirely. Since lenders price the low tail and equity owns the high one, a band transfers value **from equity's upside to debt capacity** — which is why sponsors confident in demand resist bands and sponsors who need leverage accept them, and why the same band is a good deal for one shareholder and a poor one for another in the same consortium. **And the low case still breaches.** At 1.0516 the banded structure pays its debt service but fails both the 1.20 × covenant and the 1.15 × lock-up, so the band has bought bankability, not compliance. A band should be sized against the lock-up, not against zero.

7.2.3 Subscription and service revenue

Definition. In **subscription and service models** revenue arrives as recurring payments from a population of customers under contracts materially shorter than the financing, so the revenue risk is **re-contracting risk** rather than volume or price risk. Three measures govern: **annual recurring revenue** (**ARR**, the annualised value of contracts in force), **net revenue retention** (next year's revenue from this year's customers after churn and expansion, as a percentage), and the **weighted-**

average remaining contract term (WARCT), the contract-weighted mean of remaining tenors. Digital infrastructure, managed services and waste all finance on this shape.

WORKED EXAMPLE

Worked example 7.2.3 — the run-off case, and why a 7-year loan was refused.

- Setup.** Halyard Connect Networks (a fictitious SPV) operates a metropolitan fibre network. At financial close, **ARR** is **24,000,000**; cash operating costs are wholly fixed at **13,200,000**, so **EBITDA** is 10,800,000; maintenance capex is **1,800,000** and cash tax is nil in the period by reason of capital allowances (stated as an assumption of the illustration, not a general treatment). Net revenue retention is **93 %**. The contract book is 40 % of **ARR** with five years remaining, 35 % with three years and 25 % with one year. The sponsors seek **40,000,000** of senior debt at **7 % over seven years**. Compute the lenders' run-off case, the coverage it delivers against level debt service, the **WARCT**, and the debt the run-off case actually supports at a $1.30 \times$ target.
- Formula.** Run-off revenue in year $t = \text{ARR} \times 0.93^{(t-1)}$ — contracted revenue only, with no credit for unsigned new sales. **CFADS** = revenue – 13,200,000 – 1,800,000. Level instalment = $40,000,000 \div \text{AF}(0.07, 7)$, with $\text{AF}(0.07, 7) = 5.389289$. Sculpted capacity = $\sum (\text{CFADS}(t) \div 1.30) \times \text{DF}(0.07, t)$ (Domain 10, KA 10.1.3). **WARCT** = $\sum (\text{share} \times \text{remaining term})$.
- Result.**

Year	Run-off revenue	EBITDA	CFADS	DSCR on level service
1	24,000,000	10,800,000	9,000,000	1.2126
2	22,320,000	9,120,000	7,320,000	0.9862
3	20,757,600	7,557,600	5,757,600	0.7757
4	19,304,568	6,104,568	4,304,568	0.5800
5	17,953,248	4,753,248	2,953,248	0.3979
6	16,696,521	3,496,521	1,696,521	0.2286
7	15,527,764	2,327,764	527,764	0.0711

Level instalment **7,422,128.79**. **WARCT 3.30 years** — **47.14 %** of the seven-year tenor. Sculpted debt capacity on the run-off case at $1.30 \times$ is **20,271,839**, **50.68 %** of the 40,000,000 sought. 4. **Interpretation.** The structure fails in **year two**, and the mechanism is worth stating precisely because it is the characteristic failure of service-revenue financings. A 7 % annual revenue decline against a wholly fixed cost base takes **EBITDA** down **15.56 %** in the first year of run-off and **17.13 %** in the second, and **CFADS** down **18.67 %** and then **21.34 %** — the operating-leverage amplification of KA 7.3.2 applied to attrition rather than to demand, and accelerating, because the fixed cost base is a growing share of a shrinking revenue. Net revenue retention of 93 % is in many service markets a perfectly respectable number; against a wholly fixed cost base and a seven-year loan it is a sixth of **EBITDA** in the first year and more thereafter.

The professional consequences are three. **The lender's case is the run-off case, and arguing otherwise is arguing to be lent against unsigned revenue.** Sponsors routinely present a forecast including new sales; the honest response is to present both, with debt sized on the contracted book and the new-sales case shown as the equity story. **The binding metric is WARCT against tenor, not ARR.** At 3.30 years against a seven-year loan, less than half the loan's life is contracted, and the disciplined responses are a shorter tenor, a re-contracting reserve, a cash sweep that retires debt

while the contracted book still exists, or anchor extensions as a condition precedent. **And 20,271,839 is the honest answer, so the negotiation is about the other 19.7 million** — a shorter tenor, a lower amount, extensions before close, or more equity. The sponsors are better served by a leader who computes 50.68 % early than by one who discovers it in credit committee.

AI in this KA

Demand forecasting is the most attractive and most dangerous machine application in this domain. It earns its place in **pattern extraction from usage data** — seasonality, elasticity estimation from observed price and volume, cohort-level churn and expansion behaviour no spreadsheet summary reveals — in **churn and re-contracting prediction** for service models, and in **scenario generation**, producing the coherent bundles a stress matrix needs faster and more consistently than a workshop.

Where it must not go. **A model trained on comparable assets' ramps inherits their optimism bias**, because the training data is forecasts and outturns from projects that were financed — a selected population — and the assistant will not say so. The output must be tested against the base rate that matters: outturn against forecast for comparable assets including those that underperformed, which is precisely the data least likely to be available. **A forecast must never be presented without its case label and its owner**, and a machine-generated forecast has no owner until a named professional adopts it. **And no assistant should select the bank case**, which is a negotiating position rather than an estimate. Verification: reconstruct the forecast's implied elasticity and load factor by hand, check them against the asset's physical and contractual capacity, and require that any forecast used in a financing carry the market adviser's name.

■ KEY TERMS — KA 7.2

Term	Meaning
Ramp	The period during which realised demand approaches its mature level after commercial operations.
Sponsor / bank / downside case	Central expectation · the case lenders will lend against · the stress the structure must survive.
Shadow toll	Grantor pays the project per unit of measured usage; volume risk stays with the project, price risk with the grantor.
Volume band	Declining unit rates across volume tranches; compresses revenue dispersion from both ends.
ARR	Annual recurring revenue: the annualised value of contracts in force.
Net revenue retention	Next year's revenue from this year's customers, after churn and expansion, as a percentage.
WARCT	Weighted-average remaining contract term; the contracted horizon to be compared with loan tenor.
Run-off case	Contracted revenue only, with no credit for unsigned new business.

■ SAMPLE MCQS — KA 7.2

MCQ 7.2-A [7.2.2 · Application] A banded tariff pays 0.55 per m³ on the first 18,000,000 m³, 0.35 on the next 6,000,000 and 0.10 above 24,000,000. At despatch of 19,200,000 m³ revenue is:

A. USD 9,600,000

- B. USD 10,320,000 ☒ **CORRECT**
- C. USD 10,560,000
- D. USD 12,000,000

Rationale: $18,000,000 \times 0.55 + 1,200,000 \times 0.35 = 9,900,000 + 420,000 = 10,320,000$. A applies the flat 0.50 tariff; C applies 0.55 to the whole volume; D is the base-case revenue, which the band does not guarantee.

MCQ 7.2-B [7.2.3 · Analysis] An SPV has ARR of 24,000,000, net revenue retention of 93 % and wholly fixed cash costs of 13,200,000. In the first year of run-off, EBITDA falls by approximately:

- A. 7 %
- B. 15.6 % ☒ **CORRECT**
- C. 18.7 %
- D. it does not fall, because retention is above 90 %

Rationale: EBITDA falls from 10,800,000 to 9,120,000, a fall of **15.56 %** — the 7 % revenue decline amplified by the fixed cost base. A mistakes the revenue decline for the earnings decline; C is the CFADS decline (9,000,000 to 7,320,000, -18.67 %), the right amplification applied to the wrong measure; D misreads a retention rate as a growth rate.

MCQ 7.2-C [7.2.3 · Analysis] A service-revenue SPV has a WARCT of 3.30 years and seeks a seven-year loan. The lender's most likely structural response is:

- A. to accept the tenor, since ARR covers debt service in year one
- B. to size on the contracted run-off case and require a shorter tenor, a re-contracting reserve, a cash sweep or contract extensions before close ☒ **CORRECT**
- C. to size on the sponsor case including new sales, discounted by 10 %
- D. to require an availability guarantee

Rationale: Less than half the loan's life is contracted, so the loan is being asked to bridge uncontracted years (7.2.3). A relies on year one alone; C lends against unsigned revenue; D applies a mechanism from a different revenue architecture.

MCQ 7.2-D [7.2.2 · Analysis] A volume band raises the low-case DSCR from 0.9438 to 1.0516 and lowers the high-case DSCR from 1.6049 to 1.3175, reducing expected revenue by 300,000 a year. The correct characterisation is:

- A. the band destroys value, since expected revenue falls
- B. the band transfers value from equity's upside to debt capacity, and the trade is computable: 2,515,153 of present value surrendered for 3,482,520 of capacity ☒ **CORRECT**
- C. the band has no effect on debt capacity, since expected CFADS still exceeds debt service
- D. the band removes the covenant risk

Rationale: Lenders price the low tail and equity owns the high one, so compressing both is a transfer, not a loss (7.2.2). A ignores the capacity gain; C treats expected cash as the sizing basis; D is false — the low case at 1.0516 still breaches the $1.20 \times$ covenant.

MCQ 7.2-E [7.2.3 · Comprehension] A sponsor complains that its lenders "refuse to count our sales pipeline". The statement that best conveys what a run-off case is:

- A. lenders assume the business stops selling, which is conservatism for its own sake
- B. it values only revenue already under contract, declining at the retention rate, so debt is sized on promises that exist rather than on sales not yet made ☒ **CORRECT**

- C. it is the sponsor case with a standard haircut applied to forecast new sales
- D. it assumes every customer leaves at the end of its current term

Rationale: at 93 % net revenue retention the run-off case takes 24,000,000 of **ARR** to 22,320,000 in the following year — a statement about what is signed, not a prediction that selling stops (7.2.3). A reads a sizing basis as a forecast; C describes a haircut to a sponsor case, which is a different and weaker discipline because it still lends against unsigned revenue; D describes nil retention rather than 93 %.

MCQ 7.2-F [7.2.1 · Evaluation] A sponsor team proposes to present its central forecast as the base case and the same forecast with a flat 10 % haircut as "the bank case". On Kestrel the escalation assumption alone separates the sponsor and bank cases by 17,107,567 of **NPV**. The soundest position is that:

- A. the approach is acceptable, since a 10 % haircut is a conservative adjustment in the sponsors' own favour to concede
- B. the bank case is a negotiating position built from specified haircuts, a slower ramp, no unindexed growth and a conservative price deck, and a haircut with no stated composition cannot be defended line by line — conceding the case unopposed concedes more than the coverage ratio does ✓ CORRECT
- C. the work is unnecessary, because the lenders' market adviser will produce the bank case
- D. only the sponsor case should be presented, leaving the lenders to make their own adjustments

Rationale: the case moves as well as the ratio, and it is the larger of the two sizing variables (7.1.1, 7.2.1); a bank case is also a different object from a downside case, with a different purpose and owner. A dresses an arbitrary percentage as conservatism and cannot survive a question about which line it applies to. C and D hand the case to the counterparty that gains from choosing it, which is how sponsors arrive in credit committee with no position of their own.

■ SELF-CHECK — KA 7.2

1. What distinguishes a bank case from a downside case? — The bank case is what lenders will lend against; the downside case is the stress the structure must survive. They have different purposes and different owners, and conflating them hides both.
2. Why is **WARCT** more informative than **ARR** for a service-revenue financing? — **ARR** measures the size of the contracted book; **WARCT** measures how much of the loan's life it covers, which is the risk being financed.
3. Which tail does a volume band buy, and who pays for it? — It buys the low tail, which lenders price; equity pays for it by surrendering the high tail.

KNOWLEDGE AREA 7.3

Price escalation and volume risk

Topics: 7.3.1 indexation architecture and margin drift · 7.3.2 volume risk and operating leverage · 7.3.3 turning revenue risk into a tolerance.

7.3.1 Indexation architecture and margin drift

Definition. Indexation is the contractual escalation of a price by reference to a published index. Domain 3 (KA 3.3.2) established the compounding arithmetic and the register of index mechanics — publisher, series, definition, lag, cap, floor, compounding basis. This topic addresses the commercial structure those mechanics sit inside: the **indexation architecture**, meaning which proportion of each revenue and cost line escalates, on which index, and what the mismatch is worth.

Each line has three parameters and only the first two are usually negotiated with care: the index, the rate it is expected to run at, and the **indexed share**. A tariff described as "CPI-indexed" may escalate 60 %, 80 % or 100 % of its value; the unindexed remainder is a fixed nominal amount eroding in real terms for the whole concession. Because revenue-side and cost-side shares are set in different negotiations, by different people, at different times, they are almost never matched — and the mismatch compounds.

WORKED EXAMPLE

Worked example 7.3.1 — the 36 basis points that cost 3.27 margin points.

- Setup.** Kestrel's water-purchase agreement indexes **80 %** of the tariff to a consumer price index assumed to run at **2.5 %** a year; the remaining 20 % is fixed for the 25-year concession. On the cost side, **70 %** of the 4,500,000 cash operating cost — labour, chemicals and power — escalates at **3.2 %** under a separate index in the O&M contract; the remaining 30 % is fixed under long-term agreements. Compute revenue, cost, **EBITDA** and the **EBITDA** margin in years 1, 12 (loan maturity) and 25, the effective compound rates, and the value of the unindexed tariff slice.
- Formula.** Revenue in year $t = 12,000,000 \times [0.80 \times 1.025^{(t-1)} + 0.20]$; cost in year $t = 4,500,000 \times 0.70 \times 1.032^{(t-1)} + 4,500,000 \times 0.30$. Effective rate = $(\text{year-25 value} \div \text{year-1 value})^{(1/24)} - 1$.
- Result.**

Year	Revenue	Cash operating cost	EBITDA	Margin
1	12,000,000	4,500,000	7,500,000	62.50 %
5	12,996,604	4,922,970	8,073,634	62.12 %
12	14,996,032	5,804,380	9,191,652	61.29 %
25	19,763,769	8,058,467	11,705,302	59.23 %

Effective compound rates: revenue **2.101 %**, cost **2.457 %** — a gap of **35.7 basis points**. Under full tariff indexation at the same 2.5 % the year-25 margin would be **62.87 %** and **EBITDA 13,646,244**; the present value at 8 % of the **EBITDA** forgone across 25 years by indexing only 80 % is **6,204,143**, of which **2,619,217** falls inside the twelve loan years discounted at 6 %. Under a fully indexed cost base at 3.2 % the year-25 margin would be **51.51 %**. 4. **Interpretation. Neither contractual index is the rate that matters.** The headline gap between a 2.5 % tariff index and a 3.2 % cost index is 70 basis points; the effective rates that partial indexation actually produces are 2.101 % and 2.457 %, a gap of **35.7 basis points**. Half the apparent mismatch is neutralised by the 30 % of cost that does not escalate, so a negotiator working from headline indices has overstated the exposure twofold. The corrective is the same in both directions: **compute effective rates from shares and indices, and negotiate on those.**


The decomposition is where the money is, and it is counter-intuitive. Of the 3.27 margin points lost by year 25, the unindexed 20 % of the tariff accounts for **3.65 points** (the year-25 margin under full tariff indexation is 62.87 %) while the fixed 30 % of the cost base saves **7.72 points** (a fully indexed cost base would end at 51.51 %). The single most valuable term in Kestrel's commercial package is therefore not the tariff index but the fixed-price portion of the O&M contract, worth more than twice what the unindexed tariff slice costs — an insight invisible unless the architecture is decomposed.

The drift is slow, which is why it is dangerous. Nothing breaks: year-12 coverage is a comfortable **1.4253**, because the interest deduction has fallen and the tariff has risen faster than the covenant needs. The damage lands after the loan matures — in refinancing, handback economics and the equity return — so the party most exposed to indexation drift is the party least present in the financing negotiation. Price the whole concession, not the loan life: the tariff index a lender is indifferent to is the one shareholders live with for thirteen years after the lender has gone. **And an index the model assumes is not an index the contract grants.** CPI at 2.5 % is a forecast; entitlement to 80 % of CPI is a term. The first belongs in the sensitivity table, the second in the contract review, and confusing them is how projects end up with an escalation forecast where they needed an escalation right.

Indexation architecture, not the index, decides the margin

Tariff index 2.5 %, cost index 3.2 %; effective rates 2.10 % on revenue and 2.46 % on cost

The unindexed 20 % of the tariff costs 3.65 margin points by year 25; the fixed 30 % of cost saves 7.72



A 36-basis-point gap between effective rates compounds into 3.27 margin points over 25 years

Fig 7.3.1 — Margin drift over the concession

7.3.2 Volume risk and operating leverage

Definition. Operating leverage is the amplification of a change in volume into a larger proportional change in earnings, caused by costs that do not fall when volume does. The **degree of operating leverage** is the ratio of contribution to EBITDA:

$$DOL = \text{contribution} \div \text{EBITDA} = (\text{unit price} - \text{unit variable cost}) \times \text{volume} \div \text{EBITDA}$$

and the corresponding **CFADS elasticity** to a driver is the proportional change in **CFADS** per one per cent change in that driver. Domain 6 (KA 6.4.2) computed Kestrel's **CFADS** elasticity to **revenue** as **1.4098** and used it to convert coverage headroom into a revenue breakeven. This topic supplies the mechanism and one distinction Domain 6 did not need.

WORKED EXAMPLE

Worked example 7.3.2 — why a price miss hurts more than a volume miss.

- Setup.** Kestrel's master thread: price 0.50 per m³, variable cost 0.0375 per m³, volume 24,000,000 m³, fixed cash cost 3,600,000, **EBITDA** 7,500,000, **CFADS** 6,384,000. Compute the degree of operating leverage, the **CFADS** elasticity to price and to volume, and verify each against a finite move.
- Formula.** Contribution = $(0.50 - 0.0375) \times 24,000,000$. From the bridge **CFADS** = $0.75R - 0.03V - 1,896,000$: elasticity to price (revenue moving alone) = $0.75R \div \text{CFADS}$; elasticity to volume (revenue and variable cost and working capital moving together) = $(0.75 \times 0.50 - 0.03) \times V \div \text{CFADS}$.
- Substitution.** Contribution 11,100,000; $\text{DOL} = 11,100,000 \div 7,500,000$. Price elasticity $9,000,000 \div 6,384,000$; volume elasticity $8,280,000 \div 6,384,000$.
- Result.** **DOL 1.4800**. **CFADS** elasticity to **price 1.4098** (reproducing Domain 6's figure exactly); **CFADS** elasticity to **volume 1.2970**. Verification: a 20 % volume fall takes **CFADS** to 4,728,000, a fall of **25.94 %** — 20×1.2970 ; a 10 % price fall takes it to 5,484,000, a fall of **14.10 %** — 10×1.4098 .
- Interpretation.** **A price cut and a volume shortfall of the same revenue magnitude are not the same event.** Losing 10 % of revenue through price costs 14.10 % of **CFADS**; losing the same 10 % through volume costs 12.97 %, because lost volume brings relief on variable cost, cash tax and working-capital absorption. The 1.13-point difference is small at Kestrel because only 20 % of its cash cost is variable; where the variable share is 60 % the two elasticities diverge sharply, and a matrix treating "revenue down 10 %" as one scenario has merged two materially different ones. **Always stress the driver, not the revenue line.**

The generalisation is the useful part, and Domain 10 supplies its test case. Domain 10's Case study B reported a toll road whose 12 % patronage shortfall produced a **17.9 %** fall in **CFADS** — an implied elasticity of **1.4931**. Since a road's cash costs are substantially fixed, elasticity in that limiting case is simply revenue divided by **CFADS**, so the reported outcome implies base revenue of **35,833,333** against cash costs and tax of **11,833,333**. The relationship generalises to a table every practitioner should be able to reconstruct, whose last column answers the only question a board asks:

CFADS as % of revenue	CFADS elasticity to volume (fixed costs)	Volume fall that takes a 1.30 × base to a 1.20 × covenant
80 %	1.2500	6.15 %
67 %	1.4925	5.15 %
60 %	1.6667	4.62 %
40 %	2.5000	3.08 %
20 %	5.0000	1.54 %

Reaching a $1.20 \times$ covenant from a $1.30 \times$ base requires a **CFADS** fall of **7.6923 %** in every row; the demand tolerance that produces it ranges from **6.15 % to 1.54 %** purely on cost structure. **Two projects with the same coverage ratio and the same covenant can have demand tolerances that differ fourfold, and the ratio does not show it.** That is the most important thing this domain has to say to a credit committee, and it is why cost structure belongs in a revenue-risk discussion. High operating leverage is not a defect — it is what makes infrastructure profitable when demand holds — but it must be known, disclosed and matched by a structure that tolerates it: lower gearing, a larger reserve, a floor mechanism (KA 7.A.1) or sculpting.

7.3.3 Turning revenue risk into a tolerance

The principle. A ratio conveys no magnitude and an elasticity conveys no threshold; together they convert a covenant into a sentence an operating team can act on. Domain 6 (KA 6.4.2) established the breakeven translation as a modelling output; the commercial extension is to express it in **each driver the business actually manages**, because different teams control different drivers.

Kestrel's tolerance set, in four units. From a base **DSQR** of 1.2743, the $1.20 \times$ covenant requires **CFADS** of 6,011,562 — a fall of 372,438, or **5.8339 %** (Domain 10). Dividing that **CFADS** tolerance by each elasticity gives:

Driver	Elasticity	Tolerance	Level at which the covenant fails
Price / tariff	1.4098	4.14 %	revenue 11,503,416 (Domain 6)
Volume / despatch	1.2970	4.50 %	22,920,470 m ³ — a loss of 1,079,530 m ³
Availability	—	2.91 points	92.086 % availability (KA 7.1.3)
CFADS	1.0000	5.83 %	6,011,562

Four numbers, one covenant, each right for a different conversation: the commercial team hears 4.14 % on tariff, operations hears 4.50 % on despatch or 2.91 points on availability, finance hears 5.83 % on **CFADS**, and the board hears whichever is smallest. **Quoting the CFADS tolerance to a team that manages volume overstates their room by 30 %** — the same error Domain 6 identified when it observed that a **CFADS** percentage overstates revenue room by 41 %. The lock-up bites earlier still, at **22,194,436 m³**, a **7.52 %** volume fall; since lock-up is what a sponsor actually feels, that is the threshold for the shareholder dashboard.

AI in this KA

Escalation and elasticity work is arithmetically simple and definitionally treacherous — the profile in which machine output is most confidently wrong. The legitimate applications are narrow: **reconciling every escalating line to its index clause** (publisher, series, lag, cap, floor, indexed share), which is Domain 3's escalation register populated by extraction rather than transcription; **recomputing effective compound rates** across a whole revenue and cost base; and **producing the tolerance table** for every covenant and driver combination on demand.

Two failure modes. **An assistant asked for "the escalation rate" returns the headline index, not the effective rate**, because the headline is what the document says while the effective rate requires the indexed share — the parameter most often omitted from a contract summary. Kestrel's 70-basis-point headline against a 35.7-basis-point effective gap is that error in one comparison. **And an elasticity is a property of a case, not of a project** (Domain 6, KA 6.4.2): elasticities computed on a generous case and quoted against a marginal one are meaningless, and machine-generated sensitivity tables are frequently unlabelled as to case. Verification: recompute one escalating line for

one year from the clause text by hand; confirm the effective rate against first- and final-year values; and require every elasticity to carry its case label and base value.

■ KEY TERMS — KA 7.3

Term	Meaning
Indexation architecture	Which proportion of each line escalates, on which index — the negotiated structure, distinct from the index itself.
Indexed share	The proportion of a price that escalates; the remainder is fixed nominal and erodes in real terms.
Effective escalation rate	The compound rate a partly indexed line actually achieves; computable only from shares and indices together.
Margin drift	The slow change in margin caused by a mismatch between effective revenue and cost escalation.
Operating leverage (DOL)	Contribution ÷ EBITDA; the amplification of volume changes into earnings changes.
CFADS elasticity	Proportional change in CFADS per one per cent change in a driver; differs by driver.
Tolerance	The fall in a named driver that takes coverage to a threshold; the operational form of headroom.

■ SAMPLE MCQS — KA 7.3

MCQ 7.3-A [7.3.1 · Application] A tariff indexes 80 % of its value at 2.5 % a year; the remaining 20 % is fixed. Over 24 years the tariff's **effective** compound escalation rate is closest to:

- A. 2.500 %
- B. 2.101 % ✓ CORRECT
- C. 2.000 %
- D. 3.125 %

Rationale: Year-25 revenue is $12,000,000 \times (0.80 \times 1.025^{24} + 0.20) = 19,763,769$, giving $(19,763,769/12,000,000)^{(1/24)} - 1 = 2.101\%$. A is the headline index applied as though the whole tariff escalated; C is the naive $0.80 \times 2.5\%$, which is an approximation valid only over one period; D divides the index by the indexed share instead of multiplying.

MCQ 7.3-B [7.3.2 · Application] Price 0.50 per m³, variable cost 0.0375 per m³, volume 24,000,000 m³, EBITDA 7,500,000. The degree of operating leverage is:

- A. 1.4800 ✓ CORRECT
- B. 1.6000
- C. 1.2970
- D. 0.6757

Rationale: $\text{contribution } 11,100,000 \div \text{EBITDA } 7,500,000 = 1.4800$. B uses revenue rather than contribution ($12,000,000/7,500,000$); C is the CFADS elasticity to volume, a different measure computed after tax and working capital; D inverts the ratio.

MCQ 7.3-C [7.3.2 · Analysis] Two projects each report a base DSCR of 1.30 × against a 1.20 × covenant. Project M's CFADS is 80 % of revenue; Project N's is 40 %. Their demand tolerances are:

- A. identical, since the coverage ratio and covenant are identical

- B. M 6.15 %, N 3.08 % — cost structure halves the tolerance at identical coverage ✓ CORRECT
- C. M 3.08 %, N 6.15 %
- D. indeterminate without the debt amount

Rationale: Both need a 7.6923 % **CFADS** fall; dividing by elasticities of 1.25 and 2.50 gives 6.15 % and 3.08 % (7.3.2). A is the error the table exists to correct; C reverses the relationship — a thinner **CFADS** margin means higher elasticity and less tolerance; D is wrong because the tolerance is a ratio property, independent of scale.

MCQ 7.3-D [7.3.3 · Analysis] Kestrel's **CFADS** tolerance to its covenant is 5.83 %. The figure that should be given to the operations team, which manages despatch, is:

- A. 5.83 %, the **CFADS** tolerance
- B. 4.50 %, the volume tolerance, being 5.83 % divided by the **CFADS** elasticity to volume of 1.2970 ✓ CORRECT
- C. 4.14 %, the revenue tolerance
- D. 7.52 %, the lock-up tolerance

Rationale: Each team needs the tolerance in the driver it controls; quoting the **CFADS** figure to a volume-managing team overstates their room by about 30 % (7.3.3). C is the correct figure for the commercial team, which sets tariff, not for despatch; D is the correct volume figure for the lock-up, a different and later threshold.

MCQ 7.3-E [7.3.1 · Comprehension] A colleague asks what the "indexed share" of a tariff is and why it is recorded separately from the index. The best explanation is:

- A. it is the proportion by which the tariff rises each year
- B. it is the proportion of the tariff's value that escalates; the remainder is a fixed nominal amount eroding in real terms, so the tariff's effective compound rate is lower than its headline index ✓ CORRECT
- C. it is the share of the tariff denominated in the indexed currency
- D. it is the ceiling on annual escalation the contract permits

Rationale: Kestrel indexes 80 % of its tariff to an index assumed at 2.5 %, which compounds to an **effective** 2.101 % over 24 years rather than 2.5 % (7.3.1). A describes the index rate itself; C invents a currency mechanic; D names a different negotiated parameter — a cap limits the index in a period, while the indexed share limits the base the index applies to.

MCQ 7.3-F [7.3.1 · Evaluation] Kestrel's O&M contractor offers a swap: it will index the currently fixed 30 % of the cost base at the same 3.2 %, and in exchange the offtaker will index 100 % of the tariff at 2.5 % rather than 80 %. On the assumed rates the year-25 **EBITDA** margin moves from 59.23 % to **55.85 %** — a loss of 3.38 points — while the present value of **EBITDA** over the 25-year concession at 8 % **rises by 1,516,002**, full tariff indexation adding 6,204,143 and full cost indexation removing 4,688,141. The soundest recommendation is:

- A. reject: the fixed 30 % of the cost base saves 7.7164 margin points by year 25, more than twice the 3.6462 that full tariff indexation adds
- B. accept: 1,516,002 of present value at 8 % over the concession is a real gain, and margin points at a single year are not the decision metric
- C. accept, but only against a cap on the O&M index, because the 1,516,002 holds only at the assumed 3.2 % and the swap exchanges a fixed obligation for an unbounded indexed one ✓ CORRECT
- D. accept, and seek a matching cap on the tariff index so that both sides are symmetrical

Rationale: the two metrics genuinely disagree — the year-25 margin falls while discounted value rises, because the cost escalation compounds on a smaller base and lands later, where discounting bites — and B is right to prefer the discounted figure. What B misses, and C supplies, is that 3.2 % is a forecast while indexation is a term (7.3.1): the tariff's gain is bounded by its index, the cost's loss is not, so the swap is sound conditioned on a cap and speculative without one. A applies the correct decomposition to the wrong horizon, comparing snapshot margin points instead of value over the concession. D concedes the one thing worth keeping, capping the escalation the project receives in order to cap the escalation it pays.

MCQ 7.3-G [7.3.2 · Evaluation] A credit paper presents two projects as equivalent credits: both report a base **DSCR** of $1.30 \times$ against a $1.20 \times$ covenant. Project M's **CFADS** is 80 % of revenue and Project N's is 40 %, so the same 7.6923 % **CFADS** fall is reached by a 6.15 % demand fall in M and a 3.08 % fall in N. The soundest position is that:

- A. they are equivalent for credit purposes, since coverage and covenant are identical
- B. cost structure must be reported beside the ratio, and high operating leverage matched by structure — lower gearing, a larger reserve, a floor mechanism or sculpting — rather than treated as a defect ✓ CORRECT
- C. Project N is simply the weaker credit and should be declined
- D. Project N's covenant should be raised to $1.30 \times$ so that the two tolerances are equalised

Rationale: two projects with the same ratio can have demand tolerances differing fourfold, and the ratio does not show it (7.3.2) — which is why cost structure belongs in a revenue-risk discussion. A is the error the generalised table exists to correct. C treats leverage as a fault, when it is what makes infrastructure profitable while demand holds; the requirement is that it be known, disclosed and matched. D moves the wrong lever: raising the covenant reduces N's tolerance further, since it shortens the distance from base coverage to the trigger.

■ SELF-CHECK — KA 7.3

1. Why is the headline index not the rate that matters? — Because the indexed share determines the effective rate; Kestrel's 70-basis-point headline gap is a 35.7-basis-point effective gap.
2. Why does a price miss cost more **CFADS** than a volume miss of equal revenue? — Lost volume brings relief on variable cost, cash tax and working capital; a price cut brings none.
3. State the one sentence that converts a covenant into an operational instruction. — "Coverage breaks at a 4.50 % fall in despatch, or 1,079,530 m³ of the 24,000,000 forecast."

KNOWLEDGE AREA 7.4

Counterparty credit quality and revenue stress testing

Topics: 7.4.1 counterparty credit and expected loss · 7.4.2 concentration and credit enhancement · 7.4.3 revenue stress testing and the bank case.

7.4.1 Counterparty credit and expected loss

Definition. A contracted revenue stream is a claim on a counterparty, and its value is bounded by that counterparty's ability and willingness to pay. **Expected loss** decomposes it into three estimable parts:

Expected loss = probability of default × exposure at default × loss given default

where **probability of default (PD)** is the likelihood of failure to perform over a stated horizon, **exposure at default (EAD)** is the amount at risk when it happens, and **loss given default (LGD)** is the proportion of that exposure not recovered. In project finance the exposure that matters is rarely the outstanding receivable: it is the **present value of the contracted stream that would be lost**, because the loss event is termination of the revenue, not non-payment of an invoice.

WORKED EXAMPLE

Worked example 7.4.1 — what Kestrel's single offtaker is worth as a credit.

1. **Setup.** Kestrel's water-purchase agreement runs 25 years with a single regional water authority. Mapping its published rating to an internal grade gives an **annual PD of 0.60 %**. If the offtaker fails, Kestrel can re-sell water into a regional merchant market at a discount and expects to recover 55 % of the contracted value, so **LGD is 45 %**. Exposure is taken as the present value of **CFADS** over the loan life at the loan rate — the amount the lenders are relying on. Compute the twelve-year cumulative **PD**, the exposure, the expected loss, and the coverage ratio net of an annualised credit charge. (Rating mappings, recovery assumptions and regulatory capital treatments are institution- and jurisdiction-specific; the arithmetic transfers, the parameters do not.)
2. **Formula.** Cumulative **PD** over n years = $1 - (1 - \text{PD})^n$; $\text{EAD} = \text{CFADS} \times \text{AF}(0.06, 12)$; $\text{EL} = \text{cumulative PD} \times \text{EAD} \times \text{LGD}$; annualised credit charge = $\text{EL} \div \text{AF}(0.06, 12)$.
3. **Substitution.** $1 - 0.994^{12}$; $6,384,000 \times 8.383844$; $0.069671 \times 53,522,460 \times 0.45$; $1,678,031 \div 8.383844$.
4. **Result.** Twelve-year cumulative **PD 6.9671 %**; **EAD USD 53,522,460**; expected loss **USD 1,678,031**, which is **3.135 %** of exposure; annualised credit charge **200,151**, reducing **CFADS** to 6,183,849 and the **DSCR** to **1.2344**.
5. **Interpretation.** The last line is the one worth carrying: **charging the counterparty's expected loss against coverage costs Kestrel 0.0400 of DSCR** — **53.7 %** of its total covenant headroom of 0.0743 — and the project is still compliant. That is a defensible position, and stating it that way converts an opinion ("the offtaker is investment grade") into a quantified one ("the credit is worth four hundredths of a coverage ratio, against 0.0743 of headroom").

Three cautions belong with the arithmetic, each a way the calculation is routinely abused. **PD is not a fact.** It is a mapping from a rating or a model to a number, on a horizon, in a state of the economy; a public-sector offtaker's **PD** in particular is often taken from sovereign or sub-sovereign proxies that assume a support relationship the documents may not create. Present it with its source and horizon, and move it in the sensitivity table like any other assumption. **EAD depends on what the loss event is**, and choosing it is a judgment: the receivable (2,958,904 on 90-day terms — trivial), the present value of contracted **CFADS** over the loan life (53,522,460 — the lenders' exposure, used above), or the present value over the whole concession (much larger — the shareholders'). Three exposures, three expected losses, one correct answer per decision, and quoting the wrong one is how a concentration problem gets presented as a working-capital matter. **And LGD embeds a market and a legal outcome.** Kestrel's 45 % assumes a merchant market exists to re-sell into and that termination compensation, step-in rights and the security package work as drafted — matters for Domain 12 and, in a real transaction, for qualified counsel in the relevant jurisdiction. An **LGD** not traced to those documents is a guess wearing a decimal point.

7.4.2 Concentration and credit enhancement

The result that matters. Expected loss is a linear function of exposure, so **it cannot see concentration**. Splitting one counterparty into four of equal size and equal PD leaves expected loss exactly unchanged, while changing the loss distribution beyond recognition. A credit committee shown only expected loss has been shown a number that is blind to the risk the committee exists to control.

WORKED EXAMPLE

Worked example 7.4.2 — one offtaker or four, and what enhancement is worth.

- 1. Setup.** Compare Kestrel's single offtaker (annual PD 0.60 %, twelve-year cumulative 6.9671 %, exposure 53,522,460, LGD 45 %) with a hypothetical structure in which four offtakers each take 25 % of the output on identical terms, with independent defaults. Compute expected loss in each, and the probability of losing at least half of the revenue and of losing all of it. Then price a sovereign guarantee that reduces the effective annual PD to **0.20 %** for a fee of **0.35 % a year on the outstanding debt balance**, against both its expected-loss benefit and its effect on required coverage — the lenders having indicated that a guaranteed structure would be sized at **1.20 ×** rather than **1.30 ×**.
- 2. Formula.** Four-counterparty default counts follow the binomial distribution with $n = 4$ and $p = 0.069671$; losing at least half the revenue requires at least two defaults. Guarantee fee present value = $\sum (0.35 \% \times \text{opening balance in year } t) \times DF(0.06, t)$ over the amortisation schedule of Domain 3. Debt capacity as in Domain 10.
- 3. Result.**

Measure	One offtaker	Four offtakers at 25 %
Expected loss	1,678,031	1,678,031 — identical
P(no default)	93.0329 %	74.9111 %
P(exactly one default)	—	22.4399 %
P(losing ≥ 50 % of revenue)	6.9671 %	2.6489 %
P(losing all revenue)	6.9671 %	0.0024 %

Splitting the offtake reduces the probability of a revenue loss of half or more by **61.98 %** and the probability of total loss by a factor of about 2,957 — with **no change whatever in expected loss**. On the guarantee: expected loss falls from 1,678,031 to **571,726**, a reduction of **1,106,304**, against a fee whose total is 1,056,745 and whose present value at 6 % is **805,901** — an expected-loss gain of only **300,403**. But the coverage step from 1.30 × to 1.20 × raises debt capacity from 41,171,123 to **44,602,050**, a gain of **3,430,927**, or **2,625,026** net of the fee's present value. **4. Interpretation.** **Two structures with identical expected loss are not equally creditworthy, and that difference is the whole subject of concentration risk.** The four-way structure is far more likely to suffer a small loss — a 22.4 % chance of one default against a 6.97 % chance of any default at all in the single-offtaker case — and far less likely to suffer a fatal one. Since a project can absorb a quarter of its revenue disappearing for a period but not all of it, the four-way structure is materially better credit while reporting the same expected loss. **Report the loss distribution, or at minimum the probability of crossing the thresholds the structure cannot survive, and never let expected loss stand alone.** Kestrel's largest revenue risk is not the offtaker's credit quality — 0.60 % a year is respectable — it is that the offtaker is one entity, and diversification is unavailable because a single regional authority is the only buyer of the water. Where concentration cannot be diversified away it

must be **structured** against: guarantees, letters of credit, escrow, step-in rights, termination compensation that repays debt, or lower gearing.

And credit enhancement is bought for the coverage it unlocks, not the expected loss it removes. On expected-loss grounds the guarantee barely earns its fee — 300,403 of net benefit is inside the noise of the PD assumption. On coverage grounds it releases **2,625,026** of equity net of cost, because it changes the case the lender underwrites and therefore the divisor in Domain 10's sizing arithmetic. That is how experienced sponsors evaluate every mitigant: a letter of credit, a parent guarantee, an escrow account and a termination-compensation regime are all priced by asking what they do to the required ratio and the underwritten case, then comparing that with the cost of the equity they release. Expected loss is the wrong metric for the decision, though it remains the right metric for the provision.

7.4.3 Revenue stress testing and the bank case

Definition. Revenue stress testing moves the commercial drivers to levels the structure must survive and reports the outputs the decision turns on — for a financing, coverage and liquidity, not value. **Reverse stress testing** inverts the question, asking **what combination of driver movements reaches a defined failure point** — the form that produces an answer management can monitor.

WORKED EXAMPLE

Worked example 7.4.3 — Kestrel's stress matrix and its reverse.

1. **Setup.** Move tariff (price) and despatch (volume) jointly across the ranges a market adviser considers credible, and report year-one DSCR. Then find the volume required to hold the $1.20 \times$ covenant at a 5 % tariff reduction.
2. **Formula.** $CFADS = 0.75R - 0.03V - 1,896,000$ with $R = 0.50 \times \text{price factor} \times V$; $DSCR = CFADS \div 5,009,635.23$. Reverse: solve $V \times (0.375 \times \text{price factor} - 0.03) = 6,011,562 + 1,896,000$.
3. **Result.** Year-one DSCR:

Tariff \ Despatch	−20 %	−10 %	base	+10 %
+5 %	1.0156	1.1899	1.3642	1.5384
base	0.9438	1.1091	1.2743	1.4396
−5 %	0.8719	1.0282	1.1845	1.3408
−10 %	0.8001	0.9474	1.0947	1.2420

At a 5 % tariff cut, despatch must **rise 0.9906 %** — to 24,237,739 m³ — to hold $1.20 \times$. 4. **Interpretation.** Read the matrix by its boundaries, not its cells. **Six of the sixteen cells clear the $1.20 \times$ covenant, and not one of them at despatch below forecast:** the whole +10 % despatch column clears, base despatch clears only at base tariff and above, and every cell at −10 % despatch or worse fails. The covenant contour therefore runs down the right-hand edge and steps left only in the top two tariff rows — the visual statement that Kestrel has almost no joint tolerance, and none at all once volume falls. **Four cells fall below $1.00 \times$,** three of them in the −20 % despatch column, where debt service cannot be paid from operating cash at all and the debt-service reserve (2,504,818, Domain 10 KA 10.3.2) is the difference between a difficult year and a payment default. Two cells tie the matrix to the rest of the book: the base-despatch, −10 % tariff cell is **1.0947**,

exactly Domain 6's revenue-down-10 % figure, and extending the tariff row to +10 % reproduces Domain 6's **1.4540**.

The reverse stress is the more useful instrument, and the one usually missing. A 5 % tariff reduction cannot be recovered by any volume response: 0.99 % more despatch is attainable in principle, but Kestrel has no right to more despatch, because volume is the oftaker's choice — so the recovery lever does not exist. That is what a reverse stress test is for. It identifies not just the failure point but **whether the project holds the lever that would avoid it**, and a breakeven reported without asking who controls the driver is arithmetic without decision content.

Three disciplines complete the practice. **Stress drivers, not outputs** — "revenue –10 %" is two different stresses with different elasticities (KA 7.3.2). **Stress in correlated bundles**, because a demand recession arrives with a price response and a delayed indexation catch-up, and Domain 6 (KA 6.4.2) showed that one-at-a-time analysis is additive on this model and therefore says nothing about joint probability. **And report the minimum over the loan life** — this matrix is a year-one snapshot, and Domain 6's Fig 6.4.1 showed the bank-case minimum falling to 1.1851 in year 12 with no revenue stress at all, so every cell here is optimistic as a statement about the loan's worst year.

AI in this KA

Counterparty and stress work divides cleanly. **Machines should:** monitor counterparty credit signals continuously — rating actions, payment behaviour, filings, published statements — and raise exceptions, which is surveillance no human team performs consistently across a portfolio; generate and run large stress grids including the correlated bundles a workshop would never enumerate; and extract guarantee, letter-of-credit and termination-compensation terms into the structured form Toolkit 7.T.3 requires.

They must not: assign a **PD**, **LGD** or recovery assumption that becomes an input to a financing decision without a named professional adopting it, because each embeds a legal and market judgment a model states with unwarranted confidence; conclude whether facts constitute a counterparty default or trigger termination compensation, which is a matter for qualified counsel; or select the bank case. One failure mode deserves naming: asked to assess a concentrated revenue structure, a model readily computes expected loss — that is the formula in its training data — and does not volunteer that expected loss is blind to concentration, which is the entire question. **Ask for the distribution, not the expectation**, and check that the threshold used is one the structure cannot survive rather than an arbitrary confidence level.

■ KEY TERMS — KA 7.4

Term	Meaning
PD / EAD / LGD	Probability of default over a stated horizon · exposure when it occurs · proportion not recovered.
Expected loss	$PD \times EAD \times LGD$; linear in exposure, and therefore blind to concentration.
Cumulative PD	$1 - (1 - PD)^n$; the horizon matters and single-year PD understates a twelve-year exposure.
Concentration risk	The exposure created by dependence on few counterparties; visible in the loss distribution, not in expected loss.
Credit enhancement	Guarantee, letter of credit, escrow or reserve that improves the credit; priced against the coverage it unlocks.
Reverse stress test	Solving for the driver movements that reach a defined failure point, rather than testing given movements.

■ SAMPLE MCQS — KA 7.4

MCQ 7.4-A [7.4.1 · Application] Annual PD 0.60 %, exposure 53,522,460, LGD 45 %, over a twelve-year loan life. Expected loss is closest to:

- A. USD 144,511
- B. USD 1,678,031 ✓ CORRECT
- C. USD 3,728,957
- D. USD 24,085,107

Rationale: Twelve-year cumulative PD is $1 - 0.994^{12} = 6.9671\%$, so $0.069671 \times 53,522,460 \times 0.45 = 1,678,031$. A applies the single-year PD, understating the twelve-year exposure by a factor of eleven; C omits LGD, treating default as total loss; D omits PD entirely.

MCQ 7.4-B [7.4.2 · Analysis] A single offtaker taking 100 % of output is replaced by four independent offtakers taking 25 % each, with identical PD and LGD. Expected loss:

- A. falls by 75 %
- B. is unchanged, while the probability of losing at least half the revenue falls from 6.9671 % to 2.6489 % ✓ CORRECT
- C. falls to one quarter of its previous value
- D. rises, because there are four counterparties who might default

Rationale: Expected loss is linear in exposure, so splitting it changes nothing; the loss distribution changes profoundly (7.4.2). A and C confuse per-counterparty exposure with total expected loss; D confuses the probability of some default — which does rise, to 25.09 % — with expected loss.

MCQ 7.4-C [7.4.2 · Analysis] A sovereign guarantee reduces expected loss by 1,106,304 at a fee with a present value of 805,901, and would allow the lenders to size at $1.20\times$ rather than $1.30\times$, raising debt capacity from 41,171,123 to 44,602,050. The correct basis for the decision is:

- A. reject it: the expected-loss saving of 300,403 net is immaterial
- B. accept it: it releases 3,430,927 of debt capacity, or 2,625,026 net of the fee's present value, which is what credit enhancement is bought for ✓ CORRECT
- C. accept it because guarantees always improve bankability
- D. the two effects cannot be compared

Rationale: Enhancement is priced against the coverage and case it unlocks, not the provision it reduces (7.4.2). A applies the wrong metric to the decision, though it is the right metric for the provision; C is an unsupported generality; D is false — both effects are in present-value terms.

MCQ 7.4-D [7.4.3 · Analysis] A stress matrix shows that six of sixteen tariff and despatch combinations clear the $1.20\times$ covenant — none of them at despatch below forecast — and that a 5 % tariff cut requires despatch 0.99 % above forecast to remain compliant. The most valuable observation for management is:

- A. the matrix should be widened until more cells comply
- B. the project has almost no joint tolerance, and it does not hold the lever — despatch is the offtaker's choice — that would recover a tariff cut ✓ CORRECT
- C. the year-one figures understate the risk, so the matrix should be discarded
- D. the covenant should be renegotiated to $1.00\times$

Rationale: A reverse stress test must identify both the failure point and whether the project controls the driver that would avoid it (7.4.3). A is presentational dishonesty; C is half right — year-one

figures are optimistic, so the matrix should be extended to the minimum year, not discarded; D mistakes a covenant for the problem.

MCQ 7.4-E [7.4.1 · Analysis] Kestrel's offtaker exposure can be measured three defensible ways: the receivable of **2,958,904** on 90-day terms, the present value of contracted **CFADS** over the twelve loan years at 6 % (**53,522,460**), or the present value over the whole 25-year concession, which is larger again. The credit committee is deciding whether to advance 41,171,123. The exposure it should be shown is:

- A. the receivable, since that is the amount actually owed at any moment
- B. 53,522,460, because the loss event for this decision is the loss of the contracted stream over the period being lent against, not an unpaid invoice ✓ CORRECT
- C. the whole-concession figure, being the largest and therefore the most prudent
- D. all three, averaged, so that the committee neither over- nor understates

Rationale: **EAD** follows from what the loss event is, and choosing it is a judgment tied to a decision (7.4.1). A is the working-capital exposure, trivial by comparison, and quoting it is exactly how a concentration problem gets presented as a working-capital matter. C is genuinely defensible and is the right number for a different decision — the sponsors' own exposure across the concession — but selecting it here because it is the largest substitutes an instinct for prudence for the question asked, and it overstates what the lenders are relying on. D is arithmetic without meaning: three exposures answer three questions and their mean answers none.

MCQ 7.4-F [7.4.3 · Evaluation] The stress matrix clears the $1.20 \times$ covenant in six of sixteen cells and falls below $1.00 \times$ in four, and the unstressed bank case already reaches a year-twelve minimum of 1.1851 (Domain 6, Fig 6.4.1). Four requirements are proposed. Which should the committee impose first?

- A. extend the matrix to the loan's minimum year, since every cell is a year-one snapshot and therefore optimistic about the loan's worst year ✓ CORRECT
- B. widen the tariff and despatch ranges beyond the market adviser's credible bounds
- C. attach a probability to each cell so that the committee can weigh the outcomes
- D. increase the debt-service reserve from six months to twelve, because four cells cannot pay debt service from operating cash

Rationale: the matrix understates the problem before any stress is applied: coverage already falls to 1.1851 by year twelve on the unstressed bank case, so ten failing cells is a floor rather than a finding (7.4.3). D is a real mitigant applied in the wrong order — a reserve sized against a mis-stated worst year is sized against the wrong number, and the right sequence is measure, then mitigate. C is what committees usually ask for and is the more dangerous request: joint probabilities here would have to be invented, and a probability-weighted matrix built on assumed correlations implies knowledge nobody has (Domain 6, KA 6.A.1). B changes nothing, since the ranges are already the adviser's credible bounds and extending them past that only adds cells nobody will underwrite.

MCQ 7.4-G [7.4.2 · Evaluation] A credit paper records that the sole offtaker is investment grade, with an annual **PD** of 0.60 %, a twelve-year cumulative **PD** of 6.9671 % and an expected loss of 1,678,031 on exposure of 53,522,460. A single regional authority is the only buyer of the water. The soundest assessment of the paper is that it:

- A. is adequate: expected loss is the standard measure and the counterparty's grade is strong
- B. is inadequate because a 0.60 % annual **PD** is implausibly low for a sub-sovereign counterparty

- C. is incomplete: expected loss is identical whether one counterparty or four carry the same revenue, so the paper must also state the probability of losing more revenue than the structure can survive and what has been structured against it ✓ CORRECT
- D. is inadequate, and the remedy is to split the offtake among four independent payers

Rationale: expected loss is linear in exposure and therefore blind to concentration — four payers would show the same 1,678,031 while the probability of losing half or more of the revenue falls from 6.9671 % to 2.6489 % and of losing all of it to 0.0024 % (7.4.2). A lets the expectation stand alone on a concentrated base. B attacks the one parameter the paper at least sources, and misses the omission. D prescribes a remedy this market does not offer: where concentration cannot be diversified away it must be structured against — guarantees, letters of credit, escrow, step-in rights, termination compensation that repays debt, or lower gearing.

MCQ 7.4-H [7.4.1 · Comprehension] Kestrel's LGD of 45 % rests on an expectation of recovering 55 % of contracted value. What that figure embeds is:

- A. the proportion of an unpaid invoice that is written off
- B. a market judgment — that a merchant market exists to re-sell into — together with a legal one, that termination compensation, step-in rights and the security package work as drafted ✓ CORRECT
- C. a figure fixed for each counterparty class by regulation, and therefore not an assumption at all
- D. the probability that recovery efforts fail

Rationale: LGD is the proportion of exposure not recovered, and on a project the recovery depends on both a market and a set of documents, so an LGD not traced to them is a guess wearing a decimal point (7.4.1). A describes a receivable write-off, not the loss of a contracted stream. C states as universal a treatment that is institution- and jurisdiction-specific. D is PD's territory — likelihood — not the severity LGD measures.

■ SELF-CHECK — KA 7.4

1. Why does expected loss understate a concentrated exposure? — It is linear in exposure, so it is identical whether one counterparty or four carry the same total; only the loss distribution shows the difference.
2. On what basis is credit enhancement priced? — On the coverage and underwritten case it unlocks, and therefore the equity it releases — 2,625,026 net for Kestrel's guarantee — not on the expected loss it removes.
3. What must a reverse stress test establish beyond the breakeven? — Whether the project controls the driver that would avoid the failure.

— Advanced topics — Domain 7

7.A.1 The collar: a minimum revenue guarantee with revenue sharing

A **minimum revenue guarantee** (MRG) is a floor the grantor writes; **revenue sharing** is a ceiling it buys back. Together they form a **collar**, which can be structured to cost the grantor nothing in expectation while transforming bankability — making it the most efficient instrument in this domain.

Take Kestrel's Structure B distribution and add an MRG at **10,800,000** (90 % of base revenue) with **100 % revenue sharing above 13,200,000** (110 %). In the low outcome the grantor tops up by

1,200,000; in the high outcome it recovers 1,200,000; in the base outcome nothing happens. The **expected net transfer is exactly nil** and **expected CFADS is unchanged at 6,384,000**. What changes is the distribution: **CFADS** outcomes narrow from 4,728,000–8,040,000 to **5,628,000–7,140,000**, **DSCR** outcomes from 0.9438–1.6049 to **1.1234–1.4253**, and debt capacity sized on the low case at $1.30 \times$ rises from 30,491,396 to **36,295,595** — a gain of **5,804,200 for nothing in expectation**.

Three professional points. The collar is **not free to the grantor**, whose exposure has moved from an expectation to a contingency: a 25 % chance of paying 1,200,000 is a real budgetary and accounting matter in its own jurisdiction and framework, and it is why guarantees of this kind are increasingly recognised as contingent liabilities rather than treated as costless policy. It is **not free to equity** either: the shared upside is the shareholders', and 5,804,200 of extra debt is 5,804,200 of leverage risk. And **it does not fix compliance** — the collared low case at 1.1234 still breaches both the $1.20 \times$ covenant and the $1.15 \times$ lock-up, so a floor set at the lock-up level is worth far more than a floor at a round percentage of base revenue, and costs the grantor only slightly more.

7.A.2 The merchant tail and the contracted horizon

The tenor a project can support is set by its **contracted horizon**, not its asset life. Suppose Kestrel's offtake ran eight years rather than twenty-five, with output thereafter sold merchant at 70 % of the contracted tariff: merchant-year revenue is 8,400,000, **CFADS 3,684,000** and **DSCR** on the existing instalment **0.7354** — the loan cannot be paid in those years. Three structural responses, each with a computed price:

- **Shorten the tenor to the contracted horizon.** Eight years at $1.30 \times$ on contracted **CFADS**, with $AF(0.06, 8) = 6.209794$, supports **30,494,864** — 10,676,259 less than the twelve-year contracted structure, and it creates refinancing risk at year eight.
- **Keep twelve years with level service.** The weakest period governs: $3,684,000 \div 1.30 = 2,833,846$ of service, supporting only **23,758,524**. Level service against a cliff is the worst of the three.
- **Sculpt, with a higher target in the merchant years.** At $1.30 \times$ through the contracted years and $1.80 \times$ through the merchant years, sculpted capacity is **34,944,420** — the best answer, and the reason sculpting (Domain 10, KA 10.1.3) is close to mandatory where a contract cliff sits inside the tenor.

The leadership point is that the second option, which looks like the conservative one, destroys **11,185,896** of capacity by pricing every year at the worst year's rate. And all three answers depend on a merchant price forecast for years nine to twelve — a market forecast embedded in a debt structure, which is Domain 10's discipline on refinancing assumptions applied to revenue.

7.A.3 The reviewer's revenue eye

Invariants to test on any revenue model or commercial structure:

- Base-case revenue reconciles to the tariff formula applied to base-case volume, clause by clause, including every deduction, cap and multiplier.
- The capacity or availability charge covers fixed cash costs, debt service and return; the variable charge covers variable costs at contracted efficiency and no more (7.1.2).
- Expected revenue and expected **CFADS** are reported **with** the low case and the coverage each delivers; a case labelled "expected" never appears as a sizing basis (7.1.1).
- Every escalating line carries an index, a lag and an **indexed share**, and the model's effective compound rate reconciles to first-year and final-year values (7.3.1).

- Revenue and cost effective escalation rates are compared, and the margin at loan maturity and at concession end are both reported (7.3.1).
- **CFADS** elasticity is stated separately for price and for volume, with its case label and base value (7.3.2).
- Every covenant is expressed as a tolerance in each driver the business manages, and the smallest tolerance is identified (7.3.3).
- Counterparty exposure is stated as the present value of the stream at risk, on a named horizon, with cumulative rather than single-year **PD** (7.4.1).
- Revenue concentration is reported as a distribution or as the probability of crossing the thresholds the structure cannot survive — never as expected loss alone (7.4.2).
- Contracted revenue tenor is compared with loan tenor, and any uncontracted years inside the tenor are separately sized and separately priced (7.A.2).
- Stress is applied to drivers, in correlated bundles, and reported on the **minimum** period over the loan life (7.4.3).

— Industry variations — Domain 7

- **Contracted power and renewables.** Two-part tariffs and capacity payments dominate; the specific difference is **curtailment and deemed generation** — whether the offtaker pays for output it instructs the plant not to produce, a drafting question worth several points of availability. Under a contract-for-differences the project sells merchant and settles the difference against a strike: economically contracted, operationally merchant, and modelled wrongly whenever the two are conflated.
- **Merchant power and commodities.** There is no contracted case, so the **price deck is the commercial structure**: lenders size on a conservative deck, require coverage well above 1.5 ×, shorten tenors and often demand a hedge over a defined share of output. The specific difference is that the hedge is itself a counterparty exposure, so KA 7.4 applies to the mitigant as well as to the revenue.
- **Transport concessions.** Patronage risk with a ramp; the specific difference is that **the project often controls price but faces elasticity**, so a toll increase to recover volume may reduce revenue. Operating leverage is extreme — Domain 10's Case study B implies an elasticity of 1.4931 — so tolerance is thin at any coverage ratio, and ramp reserves and sculpting are standard rather than optional.
- **Water and regulated utilities.** Availability or take-or-pay with a public counterparty; the specific difference is the **regulatory reset**, a scheduled discontinuity no escalation formula describes. Covenant testing and reserve sizing must straddle resets, and the indexation architecture applies only between them.
- **Digital infrastructure.** Contracted revenue with short tenors relative to asset life; the specific difference is that **re-contracting risk replaces volume risk**, so **WARCT** against tenor is the binding metric (7.2.3), tenant concentration is usually severe, and required coverage is driven by re-letting assumptions and tenant credit rather than demand forecasts.
- **Social infrastructure PPP.** Pure availability payments from a public budget; the specific difference is that **the deduction and performance regime is the entire revenue risk**. With no demand exposure at all, diligence and management attention belong on the performance-measurement system, the multiplier, the cumulative-deduction cap and the cure regime — which KA 7.1.3 showed can move a covenant breakpoint by 1.584 points of availability.

— Case study — Domain 7: the concession that was worth less than it looked (water)

Situation. Kestrel's tariff negotiation reached indexation last, as it usually does. The offtaker's position was **80 % of the tariff indexed to CPI**, assumed at 2.5 %, with 20 % fixed for the 25-year concession. The sponsors' commercial director, uncomfortable with an unindexed slice, asked for **full indexation**; the offtaker agreed — at **CPI less 50 basis points**, presented as a fair exchange. The finance director asked for the calculation before the term sheet was initialled.

What happened. The exchange was value-destroying. Present value of revenue over 25 years at 8 %: 80 % at 2.5 % gives **152,913,886**; 100 % at 2.0 % gives **152,088,430** — the "full indexation" offer was worth **825,456 less**, and 166,192 less over the twelve loan years at 6 %. The mechanism is not obvious, and that is the point: the unindexed 20 % compounds at nothing, but the indexed 80 % compounds at the higher rate, so by year 25 the partly indexed tariff reaches 19,763,769 against the fully indexed one's 19,301,247. Minimum **DSCR** over the loan life was 1.2743 in year one under both and year-12 coverage was 1.4253 against 1.4140, so **no coverage test would have detected the loss** — a covenant-compliant structure can be materially worse than the alternative and nothing in the coverage model will say so.

The second finding was larger. Decomposing the architecture (Worked example 7.3.1) showed the year-25 margin falling from 62.50 % to **59.23 %**, and the **effective** rate gap at 35.7 basis points rather than the headline 70 — half the apparent mismatch already neutralised by the 30 % fixed portion of the O&M contract. The lever nobody had pulled was on the cost side: the O&M escalation index, negotiated separately by the technical team, ran at 3.2 % against the tariff's 2.5 % for no reason beyond the contractor having proposed it.

How it resolved. Two changes, negotiated together. The tariff moved to **90 % indexed at full CPI**, and the O&M contract was re-tendered with its escalating 70 % **matched to the tariff's index**. Present value of **EBITDA** over 25 years at 8 % rose from **93,938,399** to **99,836,527** — a gain of **5,898,128**, of which **3,102,071** came from the extra ten points of tariff indexation and **2,796,057** from index matching, the two effects being exactly additive. The year-25 margin rose to **66.01 %**, above the year-1 62.50 %, because matched indices against a partly fixed cost base produce margin expansion. The offtaker took a tighter availability regime in exchange, which KA 7.1.3 priced separately.

What the domain teaches here. Indexation is an **architecture**, not a rate, and it must be valued rather than preferred. The sponsors' instinct — more indexation is better — was wrong by 825,456 as offered, and the valuable change was on a line nobody had connected to the revenue negotiation. Two disciplines follow: compute the present value of every indexation proposal before responding to it, and negotiate revenue and cost indices **in the same room**, because the exposure is the gap between them and neither team can see it alone.

— Case study B — Domain 7: the tenant they gave a discount to (digital infrastructure)

Situation. Northwind Data Campus (a fictitious SPV) was a 200,000,000 colocation development fully pre-let to a single investment-grade anchor tenant on a ten-year lease: revenue **34,000,000**, fixed cash operating costs **12,000,000**, maintenance capex **1,500,000**, so **CFADS 20,500,000**, with cash tax nil in the early years under capital allowances. The sponsors regarded one strong tenant as

their best credit feature. The lead arranger, pricing a ten-year facility at **6.5 %** ($AF(0.065, 10) = 7.188830$), required **1.60 ×** coverage precisely because 100 % of revenue depended on one counterparty and one lease: $20,500,000 \div 1.60 = 12,812,500$ of service, supporting **92,106,887** and leaving equity of **107,893,113**, **53.95 %** of capital, against a business plan built on 40 %.

What happened. The sponsors first argued the ratio, which failed for the reason Domain 10's Case study A established — a coverage requirement is an output of the credit, not a negotiating variable in isolation. Their second response worked. They asked the anchor, whose own growth forecast had softened, to release **25 % of the capacity**, and re-let it to three independent tenants at an average **6 % below** the anchor rate. Revenue fell to **33,490,000**, down 510,000 or **1.50 %**; operating costs rose 400,000 on the additional billing and service load; **CFADS** fell to **19,590,000**, down **910,000**.

How it resolved. With four tenants and none above 75 % of revenue, the arranger reduced the requirement to **1.35 ×**: debt service of 14,511,111 supporting **104,317,914 — 12,211,027** more debt on **910,000 less CFADS**. Equity fell to **95,682,086**, from 53.95 % to **47.84 %** of capital. The arranger then imposed a condition the sponsors had not anticipated and that was entirely correct: because the three new leases ran three years against the anchor's ten, **WARCT** fell from **10.00 to 8.25 years** against a ten-year loan, so a **2,000,000 re-letting reserve** was required, reducing the net capacity gain to **10,211,027**.

What the domain teaches here. Concentration, not expected value, priced the debt. The sponsors gave up 910,000 a year of **CFADS** — **4.44 %** — and received twelve million of debt, because what the arranger charged 0.25 × of coverage for was not the level of the cash flow but the fact that all of it came from one signature (KA 7.4.2). The second lesson is the reserve: reducing concentration by adding shorter leases traded counterparty risk for **re-contracting risk**, and a lender who accepts the first while ignoring the second has not improved its position. Every diversification must be assessed on both dimensions — how many payers, and for how long — which is the **WARCT**-against-tenor test of KA 7.2.3.

— Executive perspective — Domain 7

What a project finance director cannot delegate in this domain:

- **The choice of revenue structure, priced.** The decision between an availability payment and a volume tariff is worth 10,679,727 of debt capacity on Kestrel's numbers (7.1.1). It is a capital-structure decision wearing commercial clothes, and it cannot be settled by the commercial team alone.
- **The deduction and performance regime.** Multipliers, caps, cure periods and outage allowances set the operational tolerance the whole project then lives inside — 2.91 availability points for Kestrel, of which a point and a half is the negotiated multiplier (7.1.3).
- **The indexation architecture, on both sides.** Indexed shares and indices for revenue and cost, negotiated together, with effective rates computed. Case study A's 5,898,128 of present value came from two terms nobody had connected.
- **The case that debt is sized on.** The bank case is a negotiating position, and conceding it unopposed concedes more than the coverage ratio does (7.2.1).
- **The concentration statement.** Not the counterparty's rating and not the expected loss, but the probability of losing more revenue than the structure can survive, and what has been structured against it (7.4.2).

- **The tolerance in each team's own unit.** 4.14 % on tariff, 4.50 % on despatch, 2.91 points on availability, 5.83 % on **CFADS** — the same covenant, translated into four dashboards, with the smallest one owned (7.3.3).

— Calculation exercises — Domain 7

Exercise 7.1 A capacity charge of 20,000,000 a year carries a 97 % availability guarantee and a deduction equal to the charge multiplied by the availability shortfall and by a $1.25 \times$ multiplier. Availability outturns at 94 %. Compute the deduction and the revenue received. Solution. Shortfall $0.97 - 0.94 = 0.03$; deduction $20,000,000 \times 1.25 \times 0.03 = 750,000$, which is **3.75 %** of the charge; revenue **19,250,000**. Common error: omitting the multiplier (600,000), or applying the multiplier to total unavailability of 6 % rather than to the 3 % shortfall against the guarantee (1,500,000) — the first understates exposure by a fifth, the second doubles it.

Exercise 7.2 A project earns 0.80 per unit with variable cost 0.10 per unit and fixed cash cost 4,000,000; there is no tax or working-capital movement. Volume is 18,000,000 units with probability 0.60 and 10,500,000 with probability 0.40. Debt service is 6,000,000 a year and the loan runs ten years at 7 % ($AF(0.07, 10) = 7.023582$). Compute **CFADS** and **DSCR** in each outcome, the expected values, and debt capacity at a $1.25 \times$ target sized (a) on expected **CFADS** and (b) on the low case. Solution. High: revenue 14,400,000, **CFADS** $14,400,000 - 4,000,000 - 1,800,000 = 8,600,000$, **DSCR** **1.4333**. Low: revenue 8,400,000, **CFADS** **3,350,000**, **DSCR** **0.5583**. Expected volume 15,000,000; expected **CFADS** **6,500,000**; expected **DSCR** **1.0833**. Capacity on expected **CFADS**: $6,500,000 / 1.25 \times 7.023582 = 36,522,624$; on the low case: $3,350,000 / 1.25 \times 7.023582 = 18,823,199$ — a difference of **17,699,425**. Common error: sizing on the expected case and reporting the expected **DSCR** of 1.0833 as the project's coverage; the low outcome does not pay debt service at all, and a 40 % probability of that is not a rounding matter.

Exercise 7.3 A concession's revenue is 30,000,000 with 90 % indexed at 2.2 %; its operating cost is 18,000,000 with 60 % indexed at 3.5 %. Compute the **EBITDA** margin in year 1 and year 20, and the effective compound rates. Solution. Year 1: **EBITDA** **12,000,000**, margin **40.00 %**. Year 20: revenue $30,000,000 \times (0.90 \times 1.022^{19} + 0.10) = 43,825,432$; cost $18,000,000 \times 0.60 \times 1.035^{19} + 7,200,000 = 27,963,014$; **EBITDA** **15,862,417**, margin **36.19 %** — a drift of **3.81 points**. Effective rates: revenue **2.015 %**, cost **2.346 %**. Common error: comparing the headline 2.2 % and 3.5 % and concluding a 130-basis-point exposure; the effective gap is 33.1 basis points, because both sides are only partly indexed.

Exercise 7.4 Revenue 50,000,000; variable costs are 30 % of revenue; fixed cash costs 18,000,000. Compute the degree of operating leverage, and the volume fall that takes a $1.40 \times$ base coverage ratio to a $1.25 \times$ covenant. Solution. Contribution $50,000,000 \times 0.70 = 35,000,000$; **EBITDA** **17,000,000**; **DOL** $35,000,000 / 17,000,000 = 2.0588$. Required earnings fall $1 - 1.25 / 1.40 = 10.7143 \%$; volume fall $10.7143 \% \div 2.0588 = 5.2041 \%$. Verification: volume down 5.2041 % gives **EBITDA** of **15,178,571**, which is **89.29 %** of base — and $1.40 \times 0.8929 = 1.25$. Common error: reading the coverage gap as the volume tolerance (a 10.71 % volume fall would take coverage to $1.09 \times$, well below the covenant); operating leverage means the tolerance is always smaller than the earnings tolerance.

Exercise 7.5 A single offtaker has an annual PD of 1.0 %. Exposure over a ten-year loan is 80,000,000 and LGD is 50 %. Compute the expected loss, then compute the probability of losing at least half the revenue if the same output were sold instead to **two** independent offtakers of 50 % each on identical terms. Comment. Solution. Ten-year cumulative PD $1 - 0.99^{10} = 9.5618\%$; expected loss $0.095618 \times 80,000,000 \times 0.50 = 3,824,717$. With two offtakers, losing at least half the revenue requires **at least one** default: $1 - (1 - 0.095618)^2 = 18.2093\%$, against **9.5618 %** with a single offtaker — the probability has almost **doubled**, while the probability of total loss falls from 9.5618 % to $0.095618^2 = 0.9143\%$. Comment: splitting a revenue base into parcels at or above the survival threshold does not reduce the risk of crossing it; diversification only helps when each parcel is **strictly smaller** than the loss the structure can absorb. Common error: assuming that any diversification reduces concentration risk — the four-way split of Worked example 7.4.2 reduces the probability of a $\geq 50\%$ loss to 2.6489 %, but a two-way split increases it.

— Practitioner's toolkit — Domain 7

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 7.T.1 — Revenue mechanism specification

One row per component of the payment mechanism, populated from the agreement and signed off before the model is built. Columns: component (capacity charge · variable charge · take-or-pay floor · band · deduction · bonus · merchant) · **clause reference** · the formula in full, with every rate, threshold, multiplier and cap · the units and the measurement source · the billing period and payment terms · indexation reference (cross-refer to 7.T.2) · the model line that implements it · the person who reconciled model to clause, and the date. Rule: **no revenue figure is reportable until a historical or hypothetical period has been computed from the clause text by hand and agreed with the model** (7.1.3). The deduction row carries its multiplier, its cap and its cure regime explicitly, because a summary that omits them understates exposure by a third.

Toolkit 7.T.2 — Indexation mismatch map

Domain 3's escalation register (Toolkit 3.T.3) catalogues each line's index mechanics. This artefact pairs them. One row per **cost** line: amount · indexed share · index and expected rate · **effective rate** · the revenue line that funds it · that revenue line's indexed share, index and effective rate · **the gap in basis points** · the annual and present-value exposure the gap represents over the concession, and separately over the loan life. Footer rows: total unindexed revenue exposure, total unindexed cost protection, net effective gap, and margin at loan maturity and at concession end. Rule: **negotiate on effective rates, never on headline indices**, and review the map whenever either side of a pair is re-rendered — Case study A's second finding came from an O&M re-tender nobody had connected to the tariff.

Toolkit 7.T.3 — Revenue stress and counterparty pack

Section A, **counterparty**: each payer's share of revenue · rating or internal grade with source and date · annual and horizon-cumulative PD · exposure defined as the present value of the stream at risk, on a stated horizon · LGD with its recovery assumption traced to the security and termination provisions · expected loss · enhancement in place, its cost, and **the coverage step it purchased**. Section B, **concentration**: revenue share by payer · the loss the structure can absorb · the probability of exceeding it · what has been structured against it. Section C, **stress**: the driver list with elasticities and case labels · the two-way matrix on the drivers, not on revenue · the correlated

bundles with their rationale · the **minimum** coverage over the loan life in each · the reverse stress result for every covenant, expressed as a tolerance in each driver, with a note on **who controls that driver**. Front page: the smallest tolerance, its driver, its owner, and the date it was last recomputed.

— Exam preparation — Domain 7

What is assessed. Placing a structure on the revenue-risk spectrum and stating its coverage and capacity consequence; computing revenue under two-part, banded, floored and deduction-based mechanisms; demonstrating and quantifying the gap between expected value and bankable value; computing effective escalation rates and margin drift from indexed shares; computing **DOL** and **CFADS** elasticities and converting a coverage threshold into a driver tolerance; computing expected loss with a cumulative **PD** and explaining its blindness to concentration; and pricing credit enhancement against coverage.

The calculations to do under time pressure. Revenue from a banded tariff at a given volume. Deduction from a shortfall, a multiplier and a charge. **CFADS** and **DSCR** from the domain's bridge. Expected value across a discrete distribution, and debt capacity from a low case ($\text{CFADS} \div \text{target} \times \text{AF}$). Effective compound rate from an indexed share, an index and a horizon. **DOL** as $\text{contribution} \div \text{EBITDA}$. A driver tolerance as the **CFADS** tolerance divided by that driver's elasticity. Cumulative **PD** as $1 - (1 - \text{PD})^n$, and expected loss as the product of three factors.

The traps.

- Treating expected **CFADS** or expected **DSCR** as a sizing basis (Worked example 7.1.1; Exercise 7.2) — the single most consequential error in the domain.
- Omitting the deduction multiplier, or applying it to total unavailability rather than to the shortfall against the guarantee (MCQ 7.1-B; Exercise 7.1).
- Recovering fixed costs and debt service through a purely volume-linked charge (7.1.2).
- Using the headline index instead of the effective rate on a partly indexed line (MCQ 7.3-A; Exercise 7.3) — and its mirror, comparing headline indices across revenue and cost and overstating the gap twofold (Case study A).
- Assuming more indexation is better without computing the present value (Case study A).
- Treating "revenue –10 %" as one stress when price and volume have different elasticities (7.3.2, 7.4.3).
- Quoting a **CFADS** tolerance to a team that manages volume or availability (7.3.3).
- Using a single-year **PD** for a multi-year exposure (MCQ 7.4-A), or omitting **LGD**.
- Letting expected loss stand alone on a concentrated revenue base (7.4.2; MCQ 7.4-B).
- Assuming that any diversification reduces concentration risk, when parcels at or above the survival threshold make matters worse (Exercise 7.5).
- Reporting a year-one stress matrix as though it described the loan's worst year (7.4.3).
- Sizing a tenor on asset life rather than on the contracted horizon (7.A.2).

How the domain connects. Domain 5 (KA 5.3.2) named the five components of the revenue bankability test and deferred the taxonomy here; Domain 6 built the model this domain feeds and supplied the elasticity and breakeven machinery it extends; Domain 8 escalates the cost side with the same indexation arithmetic; Domain 9 prices the equity that a weaker revenue structure makes necessary; Domain 10 divides this domain's **CFADS** by the coverage this domain's structure earns; Domain 11 places demand, price and counterparty risk in the allocation framework; Domain 12 drafts the mechanisms described here; and Domain 15 operates the covenant tests whose tolerances KA 7.3.3 computed.

— Domain 7 summary

Revenue structure, not revenue level, decides how much debt a project can carry. Kestrel's two offers — a 12,000,000 availability payment and a 0.50 per m³ volume tariff — have **identical expected CFADS of 6,384,000** and identical expected **DSCR of 1.2743**, and differ by **10,679,727 of debt capacity**, 25.94 %, because a lender underwrites the low case (**CFADS 4,728,000**, **DSCR 0.9438** — debt service unpaid) and raises the required ratio for dispersion as well. An availability structure does not remove volatility, it converts demand risk into operational risk: Kestrel breaches its 1.20 × covenant at **92.086 %** availability against a 95 % guarantee, **2.91 points** of headroom, of which about a point and a half is the negotiated 1.5 × deduction multiplier. Banded, floored and shared mechanisms are risk-transfer instruments priced in tariff form — a volume band costing 2,515,153 of present value bought 3,482,520 of capacity, and a value-neutral collar with an **MRG** at 90 % and full sharing above 110 % bought **5,804,200 for nothing in expectation** — while service-revenue structures fail on re-contracting rather than volume: at 93 % net revenue retention against a fixed cost base, Halyard Connect's run-off case supports **20,271,839**, half the 40,000,000 sought, and its **WARCT** of 3.30 years covers 47 % of the tenor. Escalation is an architecture: 80 % of Kestrel's tariff at 2.5 % against 70 % of its cost at 3.2 % produces effective rates of **2.101 %** and **2.457 %** — a 35.7-basis-point gap, half the headline — and **3.27 margin points** of drift by year 25, all of it landing after the lender has gone; the unindexed tariff slice costs 3.65 points and the fixed cost slice saves 7.72, which is why Case study A's most valuable term was in the O&M contract. Operating leverage explains why a 12 % patronage miss became Domain 10's 17.9 % cash miss — an elasticity of **1.4931** — and generalises: at identical 1.30 × coverage and an identical 1.20 × covenant, demand tolerance ranges from **6.15 % to 1.54 %** on cost structure alone. Kestrel's own tolerance is **4.14 %** on tariff, **4.50 %** on despatch (1,079,530 m³) and **5.83 %** on **CFADS**, and quoting the last to a team that manages the second overstates their room by 30 %. Counterparty quality bounds all of it: an annual **PD** of 0.60 % over twelve years is **6.9671 %** cumulative, giving an expected loss of **1,678,031** on exposure of **53,522,460** and a credit charge worth **0.0400** of **DSCR** — but expected loss is identical whether one offtaker or four carry the revenue, while the probability of losing half of it falls from **6.9671 % to 2.6489 %**, so concentration must be reported as a distribution and never as an expectation. And credit enhancement is bought for the coverage it unlocks: Kestrel's guarantee saves 300,403 of net expected loss and releases **2,625,026** of equity. Domain 8 escalates the cost side, Domain 9 prices the equity a weak revenue structure demands, and Domain 10 divides this domain's **CFADS** by the coverage this domain's structure has earned.

08

DOMAIN 8

Cost, Schedule and Contingency Integration

— Why this domain exists

Domain 6 built a model in which the balancing line was contingency, and reported it: **USD 3,645,403**, 7.59 % of the EPC price, "inside the band a lender would expect" (KA 6.2.1). It did not say where that band comes from, whether 7.59 % is generous or reckless, or what would happen if the number were wrong. Domain 5 priced a slip in the commercial operations date but only at COD, where remaining spend is zero. Neither domain touched the fact that a project under construction produces a monthly cost and schedule report — earned value, forecasts, variances — that a lender receives, reads, and acts on differently from the project controller who wrote it.

This domain closes all three gaps, and its central claim is a single sentence: **a contingency percentage is meaningless without the estimate class it was struck against and the basis it was sized on**. Everything else here is that claim worked out. A cost estimate carries an accuracy range that narrows as scope definition matures, and the contingency implied by that range at a stated confidence is computable (KA 8.1). A schedule converts a cost estimate into a spend profile, and the shape of that profile prices two things in opposite directions — capitalised interest and escalation — with a breakeven between them (KA 8.2). Contingency sized from a quantified risk register states what confidence it buys; contingency sized as a percentage of base cost does not, and is wrong in ways this domain computes exactly (KA 8.3). And when the build slips, the cost of a month is three components, not one, and its consequence lands on a coverage ratio that will be tested for the next twelve years (KA 8.4).

The professional discipline the domain teaches is the discipline of the interface. A project controller and a lender's technical adviser read the same monthly report and extract different facts from it. The controller asks what the project will cost; the lender asks whether the money still in the facility will finish it. Those are not the same question, and a finance leader who cannot translate between them is dependent on whoever can.

Learning objectives. After this domain a candidate can: separate the four cost families a financing must fund and place each in the sources-and-uses statement or the operating model; state an estimate's accuracy class and derive the contingency its range implies at a nominated confidence; explain why a fixed-price wrap changes the estimate class and therefore the defensible contingency; compute a whole-life maintenance charge and size the reserve that converts it from a covenant cliff into a distribution reduction; build a schedule-driven spend profile and compute the capitalised interest it generates using the area rule; compute the escalation the same profile generates and find the breakeven escalation rate at which the two effects cancel; size contingency from a quantified register to a stated confidence level and reconcile it against the estimate range; demonstrate in figures why a percentage-of-base contingency fails; convert an earned-value forecast into a cost to complete and run the funds sufficiency test a lender runs; price a month of construction slip as

escalation plus extra interest plus deferred revenue and compute its permanent **DSCR** consequence; and govern AI-assisted estimating, simulation and forecasting.

The master thread. Kestrel Water SPC continues. Its **USD 60,000,000** envelope is funded 70/30 — **42,000,000** senior debt at **6.0 %** over 12 years (annual instalment **5,009,635.23**) and **18,000,000** equity — against an EPC contract price of **48,000,000**, owner's costs and land of 3,600,000, capitalised development costs of 1,800,000, fees of 840,000, capitalised interest of **2,114,597** and the balancing contingency of **3,645,403** (Domain 6, KA 6.2.1). Construction runs **eight quarters** on the certified spend profile **6, 9, 13, 16, 17, 15, 13, 11 per cent**, with cumulative debt drawn reaching 42,000,000 exactly at COD. Operating **CFADS** is **6,384,000** and the base-case **DSCR 1.2743** against a 1.20× covenant, giving annual headroom of **372,438** (Domain 10, KA 10.2.1). Construction cost escalation is assumed at **3.6 % per annum** on unwrapped scope. From PML-AI: **Project Auriga**, **BAC 4,000,000**, **CPI 0.905660** and **SPI 0.923077** at the week-13 data date, with the **EAC** family **4,200,000 / 4,416,667 / 4,608,056** (PML-AI D7, KA 7.3.3) and a sanction-date risk register whose mean exposure is **278,000**, standard deviation **252,642** and P80 **490,624** (PML-AI D8, KA 8.2.4). This domain does not re-derive any of those figures. It uses them.

KNOWLEDGE AREA 8.1

Development, capital, operating and lifecycle cost; estimate classes

Topics: 8.1.1 the four cost families and where each lands · 8.1.2 estimate classes and the contingency a range implies · 8.1.3 lifecycle cost, major maintenance and the reserve that smooths it.

8.1.1 The four cost families and where each lands

Definition. A financing must fund four distinct families of cost, and each enters the structure in a different place, on a different basis, under different control.

Development cost is everything spent between concept and financial close: studies, surveys, legal and advisory fees, permit applications, land options, the sponsors' own staff time. It is spent at risk, before any facility exists, and its treatment at close is a negotiation — Kestrel capitalised 1,800,000 of it into the funding envelope (Domain 6), which means the equity that funded it is reimbursed and — subject to the accounting and tax framework that applies, which is a question for the sponsor's own auditors (Domain 2) — the amount enters the depreciable base. Development cost that is not accepted into the envelope is sunk equity, and Domain 5 (KA 5.1.2) priced it per close rather than per deal for exactly that reason.

Capital cost is the asset: the EPC contract price, owner-supplied equipment, owner's costs, land, connection charges, insurance during construction. It is what the estimate classes of 8.1.2 measure, and it is the base against which contingency percentages are quoted.

Operating cost is the recurring cash cost of running the asset — labour, energy, chemicals, routine maintenance, insurance, administration, the operator's fee. It never appears in the sources-and-uses statement; it appears as a deduction inside **CFADS**, which makes it a coverage driver rather than a funding requirement. The distinction has teeth: an error of 500,000 per year in operating cost is an error of 500,000 per year in **CFADS**, which at Kestrel's 1.20× covenant is 1.34 times the entire annual headroom of 372,438.

Lifecycle cost is the periodic, non-routine expenditure that keeps the asset capable of performing for its whole concession — membrane replacement, major overhauls, control-system refresh, and at the end handback or decommissioning. It is lumpy, it falls in specific years, and it is the family most often omitted from a first-pass model because it is invisible in year one (KA 8.1.3).

The professional point. These four families are not four lines of one budget; they are four different financial objects. Development cost is at-risk equity that may or may not be reimbursed. Capital cost is funded, drawn and capitalised. Operating cost reduces **CFADS** every period. Lifecycle cost creates a reserve obligation. A cost report that presents them as one "project cost" figure has destroyed the information a financing needs.

8.1.2 Estimate classes and the contingency a range implies

Definition. An **estimate class** records how well the scope was defined when the estimate was made, and carries with it a stated **accuracy range** — the band within which the estimate's author expects the outturn to fall. The range is not a confidence interval in the statistical sense; it is an expression of definitional maturity, and it narrows as engineering, site investigation, procurement and contracting progress. Professional estimating bodies and large owner organisations publish classification frameworks of their own; the principle is common practice, the specific bands are always organisation-specific, and the table below is the PCI illustrative ladder used throughout this book — it reproduces no other body's classification and should not be read as one.

Stage	Scope definition	Typical basis	Accuracy range	Implied contingency to the upper bound on a 48,000,000 base
A — screening	Concept only; capacity and location	Capacity-factored from analogues	−30 % / +50 %	24,000,000
B — concept	Process selected; block layout	Factored equipment costs	−20 % / +40 %	19,200,000
C — feasibility	Basic engineering; major equipment listed	Semi-detailed, some quotations	−15 % / +30 %	14,400,000
D — definition	Detailed engineering substantially complete	Quotations for most packages	−10 % / +18 %	8,640,000
E — control	Contract awarded; scope fixed	Contract prices, priced bill	−5 % / +8 %	3,840,000

Read the last column before reading anything else. **The same 48,000,000 base estimate implies a contingency of 24,000,000 or 3,840,000 depending only on how well the scope was known when it was priced** — a factor of 6.25. Any conversation about "how much contingency is normal" that has not first established the estimate class is a conversation about nothing.

WORKED EXAMPLE**Worked example 8.1.2 — is Kestrel's 7.59 % contingency defensible?**

1. **Setup.** Domain 6's balancing line gave contingency of **USD 3,645,403** on a base of **48,000,000**. Establish the percentage, identify which estimate class that percentage is a provision for, and test whether Kestrel's contracting structure justifies it.
2. **Formula.** Contingency as a percentage of base = contingency ÷ base. Implied class = the ladder row whose upper bound is nearest above that percentage. Coverage of the class band = contingency ÷ (base × upper-bound percentage).
3. **Substitution.** $3,645,403 / 48,000,000$; compare with the upper bounds 8 %, 18 %, 30 %, 40 %, 50 %; $3,645,403 / (48,000,000 \times 0.08)$.
4. **Result.** Contingency is **7.59 %** of base. That is a **Stage E** provision — it sits inside the –5 %/+8 % control-estimate band and covers **94.93 %** of it, falling **194,597** short of the full +8 % position of 3,840,000. Against a Stage C feasibility estimate the same money covers only **25.32 %** of the +30 % band; the Stage C provision would be **14,400,000**, or **3.950 times** what is funded.
5. **Interpretation.** The 7.59 % is defensible, and the reason it is defensible is **not** that 7.59 % is a normal number. It is that Kestrel let a **fixed-price, date-certain EPC contract with a full wrap** (Domain 5, KA 5.4.1) before the envelope was fixed, which converted a Stage C estimate into a Stage E position. The wrap is what makes a thin contingency honest: it transfers the base-estimate uncertainty — the quantity growth, the productivity assumption, the unpriced package — to a contractor who has accepted a price. What remains with the owner is a short list of retained risks (KA 8.3), which is why the owner's provision can be small. Reverse the contracting decision and the arithmetic reverses with it. **The same project, procured as six packages against a Stage C estimate with owner-managed interfaces, needs a provision of the order of 14,400,000 rather than 3,645,403** — and a 60,000,000 envelope does not fund it. The professional caution is therefore that the contingency line and the contracting strategy are one decision taken twice, and the two halves are usually taken by different people in different months. Where a lender sees a thin contingency and a weak wrap together, it is looking at a structure whose funding assumption has already failed; where it sees a thin contingency behind a full wrap, it is looking at a risk transfer it can price. **The breakeven question to ask of any contingency is: which estimate class does this percentage belong to, and did we buy the contract that earns it?**

Common pitfall — the contingency inside the contract price. A contractor's price contains the contractor's own contingency, which the owner cannot see and does not control. Adding an owner's contingency on top is correct — they cover different risks — but describing the total as "the project's contingency" is not, because only one of the two is available to the owner on a draw request (KA 8.4.1). Where a cost report shows a single contingency figure, ask whose it is.

8.1.3 Lifecycle cost, major maintenance and the reserve that smooths it

Definition. Lifecycle cost (also whole-life cost) is the total cost of ownership across the asset's economic life: capital cost, operating cost, periodic major maintenance, and terminal handback or decommissioning obligations. In a financing its distinctive property is timing: it falls in a few specific years, in amounts large relative to a single year's cash, which is exactly the profile a coverage covenant handles worst.

WORKED EXAMPLE**Worked example 8.1.3 — Kestrel's whole-life charge, and the year-seven cliff.**

- Setup.** Kestrel's 25-year operating life requires **membrane replacement in years 7, 14 and 21** at **USD 3,200,000** each at base-date prices, and **high-lift pump refurbishment in years 12 and 24** at **USD 1,400,000** each. Costs escalate at **3.6 %** per annum; the sponsor's appraisal rate is **8.0 %** (Domain 4). Operating **CFADS** of 6,384,000 is struck **before** major-maintenance funding; annual debt service is **5,009,635.23**. Compute the present value of the lifecycle programme, the level annual charge equivalent to it, and what happens in year seven with and without a funded maintenance reserve.
- Formula.** Nominal cost at year t = real cost $\times (1 + 0.036)^t$; present value = nominal $\div (1 + 0.08)^t$ (Domain 3, $DF(t)$); level annual charge = $PV \div AF(0.08, 25)$ (Domain 4's **EAV**); year-seven **DSCR** without a reserve = $(CFADS - \text{nominal cost}) \div \text{debt service}$ (Domain 10).
- Substitution.**

Year	Item	Real (USD)	Nominal (USD)	Present value (USD)
7	Membrane replacement	3,200,000	4,098,909	2,391,674
12	Pump refurbishment	1,400,000	2,140,154	849,885
14	Membrane replacement	3,200,000	5,250,329	1,787,533
21	Membrane replacement	3,200,000	6,725,194	1,335,999
24	Pump refurbishment	1,400,000	3,271,615	515,931
Total		12,400,000	21,486,202	6,881,021

$AF(0.08, 25) = 10.674776$; level charge = $6,881,021 / 10.674776$. 4. **Result.** Present value of the lifecycle programme **USD 6,881,021**; **level annual charge USD 644,606**, which is **10.10 %** of **CFADS**. Without a reserve, year seven's **CFADS** falls to $6,384,000 - 4,098,909 = 2,285,091$ and the **DSCR** to **0.4561**. With the charge funded into a maintenance reserve account below **CFADS** and above distributions (Domain 10, KA 10.3.3), **CFADS** and therefore the **DSCR** stay at **1.2743** in every year, and the cost lands on distributions instead. 5. **Interpretation.** A **DSCR** of 0.4561 is not a covenant breach; it is a **payment default** — the project cannot pay debt service from cash in the year it replaces its membranes, having been entirely healthy in the six years before and the six years after. That is the whole case for a maintenance reserve in one number, and it explains why lenders commonly require one on an asset with a material overhaul cycle and why they generally require the reserve to be **forward-looking**: funded against the next overhaul, not accumulated at a policy percentage. Three professional qualifications belong beside the arithmetic. **The level charge is not the reserve deposit schedule.** 644,606 per year is the economically equivalent annual cost; the actual deposit schedule must have the money in the account before year seven, which with only six years of deposits means a higher early contribution or an opening balance funded at close — and the difference is a real funding requirement that belongs in the sources and uses. **The escalation assumption is load-bearing.** At 3.6 % the year-21 membrane costs 6,725,194 against 3,200,000 today; assume 2.0 % instead and the whole-life PV falls to a materially smaller number, which is why the lifecycle escalation rate must be the same rate used for operating cost and stated once in the assumption register (Domain 6, KA 6.1). **And the reserve converts a covenant event into a distribution event.** That is the trade: 644,606 per year of distributions forgone buys the removal of a payment default. Sponsors who resist it are choosing to hold a 0.4561 **DSCR** in year seven, which no lender will accept and no board should.

Handback and decommissioning. Where a concession requires the asset to be returned in a specified condition, the handback obligation is a lifecycle cost with a legal deadline, usually secured by a dedicated reserve funded in the final years. Where the asset must instead be removed, the decommissioning provision is both an accounting matter (Domain 2, KA 2.3.4) and a cash matter, and its cash timing sits after the loan matures — which is why it reduces the tail that Domain 10's **PLCR** of 1.9431 measures without appearing in any coverage ratio the lender tests. A reviewer's habit worth forming: read the **PLCR** and then ask what the project owes at the end of the life the **PLCR** counts.

AI in this KA

Estimate benchmarking is genuinely good machine work — comparing a new estimate's unit rates, quantities and factored allowances against a library of prior estimates and outturns, and flagging lines outside the historical distribution — and so is lifecycle-schedule construction from equipment documentation into a dated, costable programme. Both are high-volume comparison tasks with verifiable outputs. What an assistant must **not** do is assign the estimate class, because the class is a statement about how well the scope is defined and a model reading the estimate cannot know what engineering has not been done. The characteristic failure is confident class inflation: an estimate presented in the format of a control estimate is classified as one, and a 30 % range is reported as an 8 % range — a misclassification worth 10,560,000 of contingency on Kestrel's base that nothing downstream will catch.

Verification is therefore three specific requirements. The class assignment carries a named human owner and a one-line justification referencing the engineering deliverables actually complete. The benchmark comparison is re-run on a held-out sample of the organisation's own outturns, with both flagged and unflagged items reviewed — a benchmark that flags nothing is not evidence of a good estimate. And the lifecycle programme is reconciled to the supplier's written maintenance schedule item by item, because a missed overhaul is invisible until the year it happens. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 8.1

Term	Meaning
Development cost	Pre-close spend at risk; capitalised into the envelope only if accepted.
Capital cost	The asset: contract price, owner's costs, land, connection, insurance in construction.
Operating cost	Recurring cash cost; a deduction inside CFADS , never a funding line.
Lifecycle (whole-life) cost	Periodic major maintenance plus handback or decommissioning.
Estimate class	The definitional maturity of an estimate, carrying a stated accuracy range.
Accuracy range	The band the estimator expects the outturn to fall in; narrows with definition.
Level annual charge	Lumpy lifecycle PV converted to a level equivalent via AF(r, n) (Domain 4's EAV).
Maintenance reserve (MRA)	Funded account that converts a lifecycle spike into a distribution reduction.

■ SAMPLE MCQS — KA 8.1

MCQ 8.1-A [8.1.2 · Application] A 48,000,000 base estimate carries a funded contingency of 3,645,403. Which statement is defensible?

- A. 7.59 % is a normal contingency, so the provision is adequate
- B. 7.59 % is a Stage E (control-estimate) provision, adequate only because a fixed-price wrap moved the estimate to that class ☒ **CORRECT**
- C. 7.59 % is adequate for any estimate class, since contingency is a policy percentage
- D. the provision is inadequate at every class, because contingency should be 10 %

Rationale: $3,645,403/48,000,000 = 7.59\%$, which sits inside the $-5/+8$ control band and covers 94.93 % of it; the same money covers 25.32 % of a Stage C $+30\%$ band. A appeals to a norm that does not exist; C is the error the whole KA exists to remove; D substitutes a different unreasoned percentage for the first one.

MCQ 8.1-B [8.1.2 · Analysis] A project is procured as six separate packages against a Stage C feasibility estimate of 48,000,000 carrying a stated accuracy range of -15% / $+30\%$, with the owner managing interfaces. The contingency implied by the estimate's own upper bound is:

- A. 3,840,000
- B. 8,640,000
- C. 14,400,000 ☒ **CORRECT**
- D. 24,000,000

Rationale: Stage C's $+30\%$ upper bound on 48,000,000 is 14,400,000. A is the Stage E provision (the answer only a full wrap earns); B is Stage D's $+18\%$; D is Stage A's $+50\%$.

MCQ 8.1-C [8.1.3 · Application] Membranes costing 3,200,000 at base-date prices are replaced in year 7; escalation is 3.6 % per annum. CFADS is 6,384,000 and debt service 5,009,635.23. With no maintenance reserve, the year-seven DSCR is closest to:

- A. 1.2743
- B. 0.4561 ☒ **CORRECT**
- C. 0.6356
- D. 1.1457

Rationale: Nominal cost $3,200,000 \times 1.036^7 = 4,098,909$; $(6,384,000 - 4,098,909)/5,009,635.23 = 0.4561$. A is the ratio with a funded reserve; C forgets to escalate (using 3,200,000, giving $3,184,000/5,009,635.23 = 0.6356$); D deducts only the level annual charge of 644,606 rather than the actual spend ($5,739,394/5,009,635.23 = 1.1457$).

MCQ 8.1-D [8.1.1 · Analysis] An operating-cost forecast understates annual cost by 500,000. Against Kestrel's $1.20\times$ covenant with annual headroom of 372,438, the consequence is:

- A. a funding shortfall in the sources-and-uses statement
- B. no consequence, since operating cost is not a funded use
- C. a covenant breach — the error is 1.34 times the entire annual headroom, and it recurs every year ☒ **CORRECT**
- D. a one-off reduction in the contingency line

Rationale: Operating cost is a deduction inside CFADS, so a 500,000 understatement removes 500,000 of CFADS annually against 372,438 of headroom ($500,000/372,438 = 1.34$). A and D put an operating error in a capital line; B confuses "not funded" with "no effect".

MCQ 8.1-E [8.1.2 · Comprehension] A sponsor asks how two estimates of the same plant, both totalling 48,000,000, can carry defensible contingencies differing by a factor of 6.25. The best explanation is:

- A. one estimator is more conservative than the other
- B. contingency provides for the range that the estimate's own definitional maturity implies, and that range narrows — on this book's illustrative ladder — from -30 %/+50 % at screening to -5 %/+8 % once scope is contracted ✓ CORRECT
- C. contingency is a policy percentage, so the difference reflects two companies' policies
- D. the two estimates must be stated at different base dates

Rationale: the class records how well scope was defined when the estimate was priced, and the provision to the upper bound on the same 48,000,000 base moves from 24,000,000 to 3,840,000 (8.1.2). A treats a structural property as a personal trait; C is the belief the whole KA exists to dislodge, since a percentage that names no class states nothing; D names a real and separate parameter (8.2.3) that governs escalation exposure rather than accuracy.

MCQ 8.1-F [8.1.3 · Evaluation] Kestrel's year-seven membrane replacement costs 4,098,909 in nominal terms, and without a reserve the year-seven DSCR is 0.4561 — a payment default. The level annual charge equivalent to the whole lifecycle programme is 644,606. The sponsors accept that a reserve is required and ask what to deposit. The soundest recommendation is:

- A. deposit the level annual charge of 644,606 from year one, since that is the economically equivalent annual cost
- B. deposit 683,152 a year over the six years before the replacement, because the account must hold 4,098,909 before year seven and the level charge is an equivalence, not a deposit plan ✓ CORRECT
- C. deposit nothing and fund the replacement from a standby facility drawn in year seven
- D. defer the replacement to year eight, when the outstanding debt balance is lower

Rationale: the whole 4,098,909 must be in the account before the money is spent, with no credit taken for interest on the balance — $4,098,909/6 = 683,151.50$ a year, taken up to **683,152** so that six deposits are not themselves short; six deposits of 644,606 total 3,867,636 and leave the account **231,273** short in the one year it is needed (8.1.3). A is the right economic measure used as a funding plan — precisely the confusion the worked example warns against. C is genuinely available and is the weaker structure: it converts a funding certainty into a drawing risk in the year the project would otherwise be at 0.4561, which is the year a lender is least willing to be relied on. D subordinates a maintenance requirement to a credit calendar and does not remove the cliff — it moves it and escalates it to 4,246,470.

MCQ 8.1-G [8.1.2 · Evaluation] A team declines the fixed-price wrap because six separate packages priced lower, and proposes retaining the funded contingency of 3,645,403 — 7.59 % of the 48,000,000 base, which covers 94.93 % of a Stage E band and 25.32 % of a Stage C one. The soundest position is that:

- A. the provision should stand: the packages priced lower, so the expected outturn is lower
- B. the provision should stand, and any difference should fall to the sponsors' cost-overrun support if it is needed
- C. declining the wrap returns the base-estimate uncertainty to the owner, so the provision must be resized on the range — 14,400,000 at the estimate's upper bound, 6,512,795 at P80 — and if the envelope cannot fund that, the envelope is wrong rather than the table ✓ CORRECT
- D. the provision should be raised to the 10 % rule, 4,800,000, as a policy compromise

Rationale: the contracting strategy and the contingency line are one decision taken twice, usually by different people in different months (8.1.2); 7.59 % is a Stage E number and only a wrap earns it. A confuses the lowest tendered price with the lowest outturn — the interfaces the packages exclude are now the owner's. B converts funded provision into a contingent commitment worth less than cash (8.3.1) and does so without resizing anything. D swaps one unreasoned percentage for another, and 4,800,000 is still a third of the range-based upper bound.

MCQ 8.1-H [8.1.1 · Comprehension] Operating cost never appears in the sources-and-uses statement. The reason is that it:

- A. is not a cost of the project, being incurred by the operator rather than the SPV
- B. is a recurring deduction inside [CFADS](#), so it reduces coverage every period rather than creating a funding requirement before revenue exists ✓ CORRECT
- C. is met from the maintenance reserve, which is funded separately
- D. is funded by equity, which is why it sits outside the facility

Rationale: the sources-and-uses statement funds what must be paid before the asset earns, while operating cost is a coverage driver — which is why a 500,000 understatement is 1.34 times the entire annual headroom and recurs every year (8.1.1). A misstates who bears it: the SPV pays the operator's fee and the costs the contract leaves with it. C confuses routine operating cost with periodic major maintenance (8.1.3). D invents a funding route for a cost that is not funded at all.

■ SELF-CHECK — KA 8.1

1. Why is "10 % contingency" not an answer? — Because contingency is only meaningful against a stated estimate class; 10 % is generous at Stage E and reckless at Stage C, and the ladder spans a factor of 6.25 on the same base.
2. What did Kestrel buy that makes 7.59 % defensible? — A fixed-price, date-certain EPC wrap, which transferred base-estimate uncertainty and moved the estimate to a Stage E position.
3. State the year-seven consequence of omitting a maintenance reserve. — [CFADS](#) 2,285,091, [DSCR](#) 0.4561 — a payment default, not merely a breach, on an otherwise healthy project.

KNOWLEDGE AREA 8.2

Schedule-driven cash flow and escalation

Topics: 8.2.1 from schedule to spend profile · 8.2.2 the shape of the S-curve and the area rule for capitalised interest · 8.2.3 escalation, base dates and the breakeven that links the two.

8.2.1 From schedule to spend profile

Definition. A **spend profile** (informally an **S-curve**) is a cost estimate distributed over time according to the schedule that will execute it. It is produced by loading cost onto activities or work packages and summing by period, and its characteristic shape — slow, then steep, then slow — arises because mobilisation and commissioning are cheap per unit time while the middle of a build is not.

The profile is the single most consequential output the schedule hands to the financing, and it is handed over in a specific direction: **the schedule owns the timing and the financing owns the consequence**. PML-AI Domain 6 builds the network, the critical path and the float that determine when work happens; this domain takes that timing as given and prices it. Three distinctions matter at

the handover. **Certified spend is not incurred cost**, because a draw request is paid against certified progress, and the certification lag shifts the funding profile relative to the cost profile. **Committed is not spent**, because a purchase order creates a commitment that will appear in a cost report long before it appears in a payment. And **the profile must be at a stated price basis** — base-date money or then-current money — because the whole of 8.2.3 depends on knowing which.

Kestrel's certified spend profile of **6, 9, 13, 16, 17, 15, 13 and 11 per cent** over eight quarters is the profile Domain 6 funded. Note what it is not: it is not a straight line, and the difference between it and a straight line is worth money.

8.2.2 The shape of the S-curve and the area rule

The result to internalise. Capitalised interest depends on the shape of the drawdown, not only on its total. Two profiles that spend the same money over the same duration produce different interest during construction, and the difference is computable in one line.

The area rule. With draws made at period end and interest accruing on the opening balance at the periodic rate r_q , on total spend S funded at gearing g :

$$IDC = r_q \times g \times S \times \sum \text{cum}(t-1)$$

where $\text{cum}(t-1)$ is the cumulative fraction of spend completed before period t . The summation is the discrete area under the cumulative drawdown curve — so **capitalised interest is proportional to the area under the S-curve**, and "shape" is precisely the thing that area measures.

WORKED EXAMPLE**Worked example 8.2.2 — three shapes, one total, three interest bills.**

1. **Setup.** USD 48,000,000 of certified spend over **eight quarters**, funded **70 %** by debt at **6.0 % per annum** (1.5 % per quarter) on the opening balance, draws at period end. For this example escalation is set to zero and interest is accrued outside the debt balance, to isolate the shape effect; Domain 6 (KA 6.2.1) runs the full circular capitalisation. Three profiles: **A**, Kestrel's S-curve (6, 9, 13, 16, 17, 15, 13, 11); **B**, front-loaded (14, 16, 16, 14, 12, 11, 9, 8); **C**, back-loaded (5, 7, 9, 12, 15, 17, 18, 17). All sum to 100 %.
2. **Formula.** The area rule above; $r_q \times g \times S = 0.015 \times 0.70 \times 48,000,000 = 504,000$ per unit of accumulated area.
3. **Substitution.** $\Sigma \text{cum}(t-1)$ for A: $0 + 6 + 15 + 28 + 44 + 61 + 76 + 89 = 319$ per cent, i.e. **3.1900**. For B: $0 + 14 + 30 + 46 + 60 + 72 + 83 + 92 = 397 \rightarrow \mathbf{3.9700}$. For C: $0 + 5 + 12 + 21 + 33 + 48 + 65 + 83 = 267 \rightarrow \mathbf{2.6700}$. Then $504,000 \times \text{area}$.
4. **Result.** **A: USD 1,607,760 · B: USD 2,000,880 · C: USD 1,345,680.** The spread between front-loaded and back-loaded is **655,200**, or **40.75 %** of the S-curve's own interest bill, on identical total spend over an identical duration.
5. **Interpretation.** 655,200 is more than the arrangement fee on this facility would move in any plausible negotiation, and it is produced by a decision nobody in the room thinks of as financial: the sequence in which the contractor plans to build. That is the first professional consequence — **the construction programme is a financing variable, and the person who sets it is usually not consulted about interest.** The second is diagnostic. Because the area rule is linear in the area, a reviewer can test any construction model in one calculation: recompute $r_q \times g \times S \times \Sigma \text{cum}(t-1)$ from the profile and compare with the model's IDC. Agreement validates the whole interest calculation; disagreement localises the defect immediately (wrong periodic rate, average rather than opening balance, draws at period start, gearing applied to the wrong base). The third is a caution against the obvious inference. It does **not** follow that back-loading is good: delaying spend delays completion unless the duration is held, and holding the duration while back-loading the money usually means accepting a steeper, riskier finish. And it costs escalation, which is 8.2.3 — where the two effects meet.

8.2.3 Escalation, base dates and the breakeven that links the two

Definitions. An estimate is stated at a **base date** — the price level at which its rates were compiled. **Escalation** is the movement in input prices between that base date and the date the money is actually spent; it is a real cost, and it is not the same as **inflation** in the general price level, which is why construction cost indices for labour, steel, cement and specialist plant move differently from consumer price indices and from each other. Escalation applies to the timing of spend, so it cannot be computed from a total: it must be computed profile-period by profile-period.

$$\text{Escalated spend} = \Sigma \text{ base spend}(t) \times (1 + e)^{(t / \text{periods per year})}$$

Under a fixed-price contract the escalation on the contracted scope is the contractor's risk — which is a large part of what a fixed price is for. The owner retains escalation on owner-retained scope, on variations priced at then-current rates, and on any scope let after the base date.

WORKED EXAMPLE**Worked example 8.2.3 — the two prices of shape, and where they cancel.**

1. **Setup.** The three profiles of 8.2.2, now with **3.6 % per annum** construction escalation on the full 48,000,000 (the unwrapped variant — the same works procured as packages, so the owner carries escalation), quarterly escalation factor $1.036^{(1/4)} = 1.00888099$. Debt draws are 70 % of escalated spend; interest as before. Compute escalated spend, IDC and the total for each profile, and find the escalation rate at which the S-curve and the back-loaded profile cost the same.
2. **Formula.** Escalated spend as above; IDC by accumulation of $\text{opening balance} \times 0.015$; total funded construction cost = escalated spend + IDC. Breakeven e^* solves $\text{total}(C, e^*) = \text{total}(A, e^*)$.
3. **Substitution and result.**

Profile	Escalated spend (USD)	Escalation over base (USD)	IDC (USD)	Total (USD)
B front-loaded	49,750,365	1,750,365	2,052,036	51,802,401
A S-curve	50,093,393	2,093,393	1,658,953	51,752,346
C back-loaded	50,324,512	2,324,512	1,391,209	51,715,720

Escalation spread B→C **574,146**; IDC spread C→B **660,827**; total spread **86,681**. Breakeven escalation between A and C: **4.1659 %**; between A and B: **4.1147 %**. 4. **Result.** At 3.6 % escalation the back-loaded profile is cheapest, but only by **36,626** against the S-curve and **86,681** against the front-loaded one — **0.17 %** of a 51.7 million spend. **Above an escalation rate of about 4.17 % the ranking reverses** and front-loading wins. 5. **Interpretation.** The near-cancellation is the most useful result in this KA, and it is not a coincidence. Deferring a dollar of spend by a period costs escalation at rate e on the whole dollar and saves interest at rate r on the geared fraction g of it, so shape is price-neutral when $e \approx g \times r$ — here $0.70 \times 6.0 \% = 4.20 \%$, against the computed 4.1659 %, the 3.4-basis-point gap being the discrete quarterly conventions. That heuristic is worth carrying: **at gearing of 70 % and a 6 % debt rate, construction escalation above roughly 4.2 % makes early spending cheaper and below it makes late spending cheaper**, and the further the actual rate is from that line, the more the programme sequence is worth arguing about. Three professional cautions. **The components are far larger than the net**, so a model that gets both wrong in the same direction produces a plausible total and two wrong lines — which is why the escalation and IDC lines are reviewed separately, never as a "construction cost" total. **The rates are not interchangeable**: using the revenue escalation assumption (2.967 % on Kestrel, Domain 6) for construction cost, or one construction index for all trades, is a silent error, and where an offtake escalates at one rate while costs escalate at another the difference compounds across the whole concession (Domain 7). **And the base date is a document, not an assumption.** An estimate whose base date nobody can name has an escalation exposure nobody can compute; the first question of any cost review is "as at what date are these rates?"

Common pitfall — escalating the total. Multiplying a 48,000,000 total by 1.036^2 for a two-year build gives 51,518,208, against the profile-correct 50,093,393 for the S-curve — an overstatement of **1,424,815**, because it escalates all the money as though every dollar were spent on the last day. The mirror error, escalating nothing because "the contract is fixed price", understates the owner's retained exposure. Both are avoided by the same discipline: escalate the profile, and state which scope is wrapped.

AI in this KA

Cost-loading a schedule and pricing every plausible sequence for escalation and interest is a deterministic search problem and proper machine work; so is index research — assembling and documenting the published construction cost indices relevant to a project's trade mix with sources and publication dates recorded. Two boundaries. **It must not select the escalation rate**, which is a forecast of input prices over a specific build in a specific market; an assistant asked for "a reasonable construction escalation assumption" supplies a plausible number with no provenance, and it then propagates into the funding envelope, the depreciable base and the delay arithmetic of KA 8.4. **And it must not re-shape the profile as an optimisation** — the area rule makes it trivially easy to cut IDC by pushing spend later, and the constraint that makes that legitimate lives in the construction logic, not in the cost model.

Verification: recompute IDC independently from the area rule and require agreement to the dollar; confirm escalation on wrapped scope is zero and on retained scope is not; re-derive one period's escalated spend by hand from the base rate and the stated base date; and require every escalation assumption to carry a named index, source and human owner in the assumption register before the model is run.

■ KEY TERMS — KA 8.2

Term	Meaning
Spend profile / S-curve	A cost estimate distributed over time by the schedule that executes it.
Certified spend	Progress certified for payment; the basis of a draw request, lagging incurred cost.
Area rule	$IDC = r_q \times g \times S \times \sum cum(t-1)$; capitalised interest is proportional to the area under the drawdown curve.
Base date	The price level at which an estimate's rates were compiled.
Escalation	Input-price movement between base date and spend date; trade-specific, not general inflation.
Shape neutrality	Profile timing is cost-neutral when escalation $\approx$ gearing $\times$ debt rate (4.20 % on Kestrel; 4.1659 % computed).

■ SAMPLE MCQS — KA 8.2

MCQ 8.2-A [8.2.2 · Application] 48,000,000 of spend over eight quarters, 70 % debt-funded at 1.5 % per quarter on opening balances. The profile's cumulative-before-period fractions sum to 3.9700. Capitalised interest is:

- A. USD 1,607,760
- B. USD 2,000,880 ✓ CORRECT
- C. USD 2,858,400
- D. USD 504,000

Rationale: $0.015 \times 0.70 \times 48,000,000 \times 3.9700 = 2,000,880$. A is the S-curve's area of 3.1900; C omits the gearing, applying interest to full spend ($0.015 \times 48,000,000 \times 3.9700 = 2,858,400$); D is the per-unit-of-area coefficient mistaken for the answer.

MCQ 8.2-B [8.2.3 · Analysis] A model escalates a 48,000,000 two-year construction estimate by multiplying it by 1.036², giving 51,518,208, where the profile-correct figure for the same S-curve is 50,093,393. The error is:

- A. 1,424,815 of understatement
- B. 1,424,815 of overstatement, because escalating a total prices every dollar as though spent on the final day ☒ **CORRECT**
- C. immaterial, since the rate is correct
- D. offset by the interest calculation

Rationale: $51,518,208 - 50,093,393 = 1,424,815$ too much; escalation must be applied period-by-period to the profile. C mistakes a correct rate for a correct method; D is wrong in direction — a higher spend also raises draws and therefore IDC.

MCQ 8.2-C [8.2.3 · Analysis] At 70 % gearing and a 6.0 % debt rate, the construction escalation rate above which front-loading spend becomes cheaper than back-loading it is closest to:

- A. 6.0 %
- B. 4.2 % ☒ **CORRECT**
- C. 3.6 %
- D. 1.8 %

Rationale: Deferral costs escalation on 100 % of spend and saves interest on the geared 70 %, so neutrality is at $e \approx g \times r = 4.20\%$ — computed as **4.1352 %** between Kestrel's front- and back-loaded profiles on the quarterly convention (8.2.3 quotes 4.1659 % for the same effect measured between the S-curve and the back-loaded profile; every pairwise breakeven sits just below $g \times r$). A ignores gearing; C is the assumed escalation rate, not the breakeven; D halves the rate for no stated reason.

MCQ 8.2-D [8.2.2 · Analysis] A reviewer wants one calculation that validates a construction model's entire capitalised-interest line. The best choice is:

- A. confirm the total spend equals the contract price
- B. recompute IDC from the area rule and require agreement to the dollar ☒ **CORRECT**
- C. confirm the closing debt balance equals the facility amount
- D. compare the IDC percentage against other projects

Rationale: The area rule reproduces IDC from the profile, rate and gearing, so agreement validates all four inputs and disagreement localises the defect. A and C are necessary but pass with a wrong interest convention; D is benchmarking, not verification.

MCQ 8.2-E [8.2.2 · Evaluation] A modeller proposes replacing Kestrel's S-curve (area 3.1900) with the back-loaded profile (area 2.6700) to cut capitalised interest by 262,080 on identical total spend over an identical duration, and asks the contractor to resequence accordingly. The soundest response is:

- A. accept: 262,080 is a real saving produced by the area rule, on the same money over the same time
- B. reject the proposal as framed: at 3.6 % escalation the back-loaded profile's escalation is 231,119 higher and its interest 267,744 lower, so the total funded construction costs differ by only 36,626 — 0.07 % of a 51.7 million spend — and the constraint that makes a sequence legitimate lives in the construction logic, not in the cost model ☒ **CORRECT**
- C. reject: once escalation is counted, back-loading always costs more than front-loading

D. accept, and extend the programme by a further quarter to reduce the area again

Rationale: escalation and interest run in opposite directions and nearly cancel near $e \approx g \times r = 4.20\%$, so at 3.6 % the whole prize is 36,626 — set against a steeper, riskier finish that no cost model prices (8.2.2, 8.2.3). A quotes the zero-escalation isolation as though it were the answer, which is the trap the isolation exists to expose. C overstates the correction: below the breakeven of about 4.17 % back-loading genuinely is cheaper, by exactly the 36,626 computed here. D compounds the error, because lowering the area by extending the duration defers commercial operations at 532,000 a month of CFADS (KA 8.4.2) — against a total interest saving of 262,080 for the entire build.

MCQ 8.2-F [8.2.3 · Evaluation] Asked for "a reasonable construction escalation assumption", an assistant returns 3.6 % per annum with no source. The modeller notes that 3.6 % is within the range of published construction indices, and that the model already carries Domain 6's 2.967 % revenue escalation. The soundest position is that:

- A. 3.6 % may be used, since it is within the range of published indices for this class of work
- B. the revenue escalation of 2.967 % should be used for both, so that the model is internally consistent
- C. no escalation rate may be relied on until it names an index, a source, a base date and a human owner in the assumption register, because the rate propagates into the funding envelope, the depreciable base and the delay arithmetic ✓ **CORRECT**
- D. one blended index should be used for all trades, since trade-level differences average out

Rationale: an assistant must not select the escalation rate, which is a forecast of input prices for a specific build in a specific market (the AI boundary in KA 8.2), and construction and revenue escalation are distinct assumptions — labour, steel, cement and specialist plant move differently from consumer prices and from each other. A accepts plausibility as provenance. B imports a revenue assumption into a cost line, which is the silent error 8.2.3 names. D discards the trade mix that makes the rate mean anything. The related discipline is that escalation is applied period-by-period to the profile: escalating the 48,000,000 total by 1.036^2 gives 51,518,208 against the profile-correct 50,093,393, an overstatement of 1,424,815.

MCQ 8.2-G [8.2.2 · Comprehension] The area rule states that $IDC = r_q \times g \times S \times \sum cum(t-1)$. What it tells a reader is that capitalised interest:

- A. depends on total spend and duration, so the shape of the drawdown is a presentational matter
- B. is proportional to the area under the cumulative drawdown curve, so two profiles spending the same money over the same duration produce different interest bills ✓ **CORRECT**
- C. is proportional to the peak debt balance reached during construction
- D. equals the average of the opening and closing balances multiplied by the rate

Rationale: the summation is the discrete area under the cumulative curve, which is precisely what "shape" measures — on Kestrel, 1,345,680 back-loaded against 2,000,880 front-loaded on identical spend and duration, a 655,200 spread and 40.75 % of the S-curve's own bill (8.2.2). A is the belief the rule refutes. C and D describe quantities the rule does not use: the same peak balance is reached on every profile that draws the full facility, and an average-of-two-balances calculation ignores the whole interior of the curve.

■ SELF-CHECK — KA 8.2

1. State the area rule and what it proves. — $IDC = r_q \times g \times S \times \sum cum(t-1)$; capitalised interest is proportional to the area under the cumulative drawdown curve, so shape has a price.

2. How much did shape alone move Kestrel's interest bill? — 655,200 between front- and back-loaded profiles, 40.75 % of the S-curve's own 1,607,760, on identical spend and duration.
3. Why is the total cost of the three profiles nearly equal at 3.6 % escalation? — Escalation and interest run in opposite directions and cancel near $e = g \times r = 4.20\%$; the two components differ by 574,146 and 660,827 while the totals differ by 86,681.

KNOWLEDGE AREA 8.3

Contingency and management reserve

Topics: 8.3.1 the reserve family in a financing, and who controls the draw · 8.3.2 sizing contingency from quantified risk · 8.3.3 why the percentage method fails, computably.

8.3.1 The reserve family in a financing, and who controls the draw

Definition. Contingency is funded provision for identified risks within the agreed scope. **Management reserve** is provision for what the register does not contain — in delivery language, unknown-unknowns and scope change. PML-AI Domain 8 (KA 8.3.2) sets out that distinction as a delivery-governance matter, with contingency controlled by the project manager under a published draw protocol and management reserve controlled by the sponsor through change control. In a financing, three things change.

Contingency becomes a funded line with an external gatekeeper. It sits in the sources-and-uses statement (Domain 6) as money the facility will lend and the equity will match, and a draw against it typically requires the lenders' technical adviser to certify both that the cost is a proper contingency item and that the remaining contingency is still adequate for the remaining risk (KA 8.4.1). The project manager's draw protocol still applies internally; it is no longer the only gate.

Management reserve mostly leaves the envelope. Lenders do not fund unknown scope, so the financing equivalent is **contingent support outside the base case**: cost-overrun undertakings, standby equity, a standby debt tranche, or sponsor several-liability support (Domain 5, KA 5.2.3). The economic difference is important — funded contingency is drawn on certification, contingent support is called on a defined trigger, and the second is worth less than the first to a lender precisely because it depends on someone's willingness and ability to pay when called.

Owner's contingency and contractor's contingency are different money. The contractor's sits inside the contract price, invisible and unavailable; the owner's is the only provision the project can actually draw (KA 8.1.2's pitfall).

WORKED EXAMPLE**Worked example 8.3.1 — sizing Kestrel's contingent support.**

1. **Setup.** Kestrel's funded contingency is **3,645,403**. The lender requires that the retained construction risk be covered to **P95** by funded contingency plus contingent equity support. The retained register's mean exposure is **2,690,000** with a standard deviation of **1,848,973** (derived in 8.3.2).
2. **Formula.** $P95 \approx \text{mean} + 1.6449 \times \sigma$ (the 95th percentile of a normal approximation); standby requirement = $P95 - \text{funded contingency}$.
3. **Substitution.** $2,690,000 + 1.6449 \times 1,848,972.69 = 2,690,000 + 3,041,375.17$; then $5,731,375 - 3,645,403$.
4. **Result.** P95 exposure **USD 5,731,375**; contingent support required **USD 2,085,972**.
5. **Interpretation.** The number to hold on to is the ratio: covering from P80 to P95 costs another 1,485,280 of committed support on a project whose whole funded contingency is 3,645,403. Tail cover is expensive, which is why it is provided as a commitment rather than as funded cash — the sponsors post an obligation, not money, and pay for it only in the futures where it is called. That is the correct structure and it carries a specific professional caution: a commitment is only as good as the entity behind it, so 2,085,972 of support from a well-rated sponsor and the same figure from a thinly capitalised project company are not the same credit, and Domain 5 (KA 5.2.3) showed the distinction between joint-and-several and several liability deciding which. **A lender's contingency question is never only "how much?"; it is "how much, funded by whom, callable on what trigger, and enforceable against what balance sheet?"**

8.3.2 Sizing contingency from quantified risk

The method. Take the register, quantify each item as probability $\times$ impact, aggregate to a mean and a variance, and read the amount at the confidence level policy requires. The machinery is PML-AI Domain 8's (KA 8.2.2 and 8.2.4) and is not re-derived here: $EMV = p \times \text{impact}$; for independent items $\text{mean} = \Sigma EMV$ and $\text{variance} = \Sigma p(1 - p) \times \text{impact}^2$; a P80 amount $\approx \text{mean} + 0.8416 \sigma$.

WORKED EXAMPLE**Worked example 8.3.2 — Kestrel's retained construction risk, and two P80s that disagree.**

1. **Setup.** Under the fixed-price wrap the owner retains six quantified items on a 48,000,000 base. Compute the mean, the standard deviation and the P80; separately, translate the Stage C accuracy range (−15 %/+30 %) into a P80 using a triangular distribution with minimum 40,800,000, mode 48,000,000 and maximum 62,400,000; then reconcile the two answers.
2. **Formula.** As above. For a triangular distribution with parameters $a < m < b$, the cumulative probability above the mode is $F(x) = 1 - (b - x)^2 / ((b - a)(b - m))$, its mean is $(a + m + b)/3$, and the P80 solves $(b - x)^2 = 0.20 (b - a)(b - m)$.
3. **Substitution and result.**

ID	Retained risk	p	Impact (USD)	EMV (USD)
C1	Ground conditions worse than surveyed (owner-retained geotechnical basis)	0.40	2,400,000	960,000
C2	Utility diversion and third-party interface scope growth	0.30	1,800,000	540,000
C3	Membrane supply price above the contract indexation formula	0.35	1,400,000	490,000
C4	Marine intake weather standby beyond the allowance	0.50	900,000	450,000
C5	Permit condition requiring additional monitoring works	0.20	2,000,000	400,000
C6	Early-completion rebate (opportunity)	0.25	(600,000)	(150,000)
Mean exposure				2,690,000

Variance = $0.40 \times 0.60 \times 2,400,000^2 + 0.30 \times 0.70 \times 1,800,000^2 + 0.35 \times 0.65 \times 1,400,000^2 + 0.50 \times 0.50 \times 900,000^2 + 0.20 \times 0.80 \times 2,000,000^2 + 0.25 \times 0.75 \times 600,000^2 = 3,418,700,000,000$; $\sigma = 1,848,973$; $P80 = 2,690,000 + 0.8416 \times 1,848,973 = 4,246,095$. Worst-case sum of threats **8,500,000** (17.71 % of base). Triangular: mean **50,400,000** (contingency 2,400,000, 5.00 %); P80 total **54,512,795**, contingency **6,512,795** (13.57 %). 4. **Result. Register P80 contingency USD 4,246,095 (8.85 % of base); range-based P80 contingency USD 6,512,795 (13.57 %).** The funded 3,645,403 sits at the **69.7th percentile** of the register and the **62.81st percentile** of the Stage C range. 5. **Interpretation.** Two defensible methods have produced answers 2,266,700 apart, and the resolution is the most valuable idea in this KA: **they are not competing estimates of the same thing.** The accuracy range measures systemic uncertainty in the base estimate — quantities, productivity, unpriced scope, the things a better-defined design would resolve. The register measures discrete risk events that either happen or do not. Adding them double-counts, because a Stage C range already contains an allowance for the sort of surprise the register enumerates; taking the lower of them under-provides. The defensible convention is to **take the higher, and then ask which of the two the contracting structure has actually eliminated.** On Kestrel the fixed-price wrap transfers the base-estimate uncertainty to the contractor, so the range-based number is the right measure of a risk the owner no longer carries, and the register-based 4,246,095 is the owner's provision. On the unwrapped variant of 8.1.2 the range governs and 6,512,795 is the floor. **The funded 3,645,403 is therefore 600,692 short of the P80 the retained register supports** — a small number with a permanent consequence: capitalise it and debt becomes 42,600,692, the instalment 5,081,284.04, the **DSCR 1.2564** and annual headroom **286,459**, down 85,979 or **23.1 %** from the 372,438 Domain 10 measured, for the whole twelve-year loan life. Two standing caveats carry over from PML-AI Domain 8 unchanged and must be stated in any paper using this arithmetic: **independence is an optimistic assumption** (C1 and C2 both concern ground and third parties, and if they are correlated the variance and the true P80 are higher), and **the normal approximation is a convenience** for a handful of Bernoulli items where a simulation over the register and the schedule is the proper instrument. Neither caveat weakens the method against the alternative in 8.3.3; both bound what may be claimed for it.

Six methods, one question — and a 3.16× spread between the answers

Crimson: the two numbers that do not state a confidence level. Blue: the provision the register supports at P80 under a fixed-price wrap

The rule of thumb buys P87.3 against the risk register and P70.4 against the estimate range — the same 4,800,000, two different promises




Fig 8.3.1 — Six answers to one question: how much contingency?

8.3.3 Why the percentage method fails, computably

The practice. Contingency is set at a policy percentage of base cost — 5 %, 10 %, 15 % — chosen by convention, precedent or negotiation. It is fast, it is universally understood, and it has two defects that can be stated as arithmetic rather than as opinion.

Defect one: it does not know what confidence it buys. Kestrel's ten-per-cent rule gives **4,800,000**. Against the retained register (mean 2,690,000, σ 1,848,973) that is $z = (4,800,000 - 2,690,000) / 1,848,973 = 1.1412$, a **P87.3** provision. Against the Stage C accuracy range it is $F(52,800,000) = 1 - (9,600,000)^2 / ((21,600,000)(14,400,000)) = 0.7037$, a **P70.4** provision. **The same 4,800,000 is a 87.3 % promise on one basis and a 70.4 % promise on the other**, and the rule cannot tell which it is making. A provision whose confidence level is unknown cannot be compared with a covenant, a support commitment or another project, which is the entire practical purpose of sizing it.

Defect two: it does not move when the risk moves. Suppose C1, the ground-conditions risk, is retired — the additional site investigation is complete, the conditions are as surveyed, the risk window has closed with no impact. The register responds immediately: mean falls to **1,730,000**, σ to **1,426,990**, and the P80 provision to **2,930,955** — a release of **1,315,141**. The percentage rule responds not at all: 10 % of base is still 4,800,000, because base cost has not changed. The organisation is now holding **1,869,045** of provision against risks that no longer exist, and that holding has a price in two stages. **While it is undrawn** it is committed capital: at a 0.60 % per annum commitment fee the excess costs **11,214** a year — small, and the reason the excess is rarely challenged. **If it is drawn**, the price becomes permanent. Funded 70/30, the excess adds **1,308,332** to senior debt, raising the annual instalment by **156,054** to 5,165,689.12, taking the **DSCR** from 1.2743 to **1.2358**, lifting the covenant cash trigger to **6,198,827** and cutting annual headroom from 372,438 to **185,173** — a fall of **187,265**, or **50.3 %**, for the whole twelve-year loan life. That is the financing translation of the slush-fund failure PML-AI Domain 8 (KA 8.3.2) warns about: **an**

unreleased provision that gets spent because it is there halves the project's covenant headroom for a decade, and the percentage method guarantees there will always be some.

The symmetric error is worse. A percentage rule that happens to under-provide is invisible in exactly the same way. Nothing in "10 % of base" reacts when a new risk is added to the register, so a project can accumulate exposure all through detailed design while its contingency line stays constant, and the first evidence anyone sees is a draw request that cannot be certified (KA 8.4.1).

What survives of the percentage method. Two legitimate uses. As a **screening figure** at Stage A or B, where no register exists and none could — a factored allowance is the honest instrument for an estimate that is itself factored. And as a **cross-check** on a register-based number: if quantified risk produces 1 % of base at Stage C, the register is incomplete, and if it produces 40 %, the project is being asked to fund a scope that is not defined. The rule of thumb is a plausibility test on the arithmetic, never a substitute for it.

AI in this KA

Monte Carlo simulation over the register and the schedule is the correct instrument that 8.3.2's normal approximation stands in for, and running it — with correlation structures, which are what make the approximation optimistic — is machine work. Correlation detection is a further genuine use: mining an organisation's own historical registers and outturns for items that have moved together is beyond manual analysis and directly improves the variance estimate. So is register hygiene — duplicates, items double-counted between register and base estimate, impacts stated in inconsistent price bases. Three things a model must not do: **set probabilities**, which are expert judgments about a specific site, contractor and market, and which if invented give the P80 a false precision a board cannot see; **choose the confidence level**, a risk-appetite decision belonging to governance (PML-AI D8, KA 8.2.4); and **reconcile the two P80s of 8.3.2**, which is a judgment about what the contract transferred and therefore a reading of a document.

Verification: recompute the mean by hand and require it to equal ΣEMV — a simulated mean that differs from the analytic mean means the model is not implementing the register; recompute one percentile with the normal approximation and require the simulation to be in the same region, a large divergence being either documented correlation or an error; and require every probability and impact to carry a named owner and a dated basis, because nothing in a simulation adds credibility its inputs do not have.

■ KEY TERMS — KA 8.3

Term	Meaning
Contingency	Funded provision for identified risks within agreed scope; drawn on certification.
Management reserve	Provision for unidentified risk and scope change; in a financing, largely replaced by contingent support.
Contingent support	Cost-overrun undertaking, standby equity or standby tranche called on a defined trigger.
Confidence level (P50 / P80 / P95)	The probability that the provision covers the aggregate outcome; a policy choice.
Owner's vs contractor's contingency	Only the owner's is drawable by the project; the contractor's is inside the price.
Percentage method	Contingency as a policy share of base cost; states no confidence and does not respond to risk retirement.
Contingency release	Reduction in the provision when a risk retires; the percentage method cannot produce one.

■ SAMPLE MCQS — KA 8.3

MCQ 8.3-A [8.3.2 · Application] A retained register has mean exposure 2,690,000 and standard deviation 1,848,973. The P80 contingency is closest to:

- A. USD 2,690,000
- B. USD 4,246,095 ✓ CORRECT
- C. USD 8,500,000
- D. USD 5,731,375

Rationale: $2,690,000 + 0.8416 \times 1,848,973 = 4,246,095$. A is the mean, which by construction is exceeded about half the time; C is the worst-case sum of threats; D is the P95 ($z = 1.6449$), a different policy choice.

MCQ 8.3-B [8.3.3 · Analysis] A 10 %-of-base contingency of 4,800,000 is a P87.3 provision against the risk register and a P70.4 provision against the estimate's accuracy range. The correct conclusion is:

- A. the rule is validated, since both figures exceed P50
- B. the rule states no confidence level, so the provision cannot be compared with a covenant, a support commitment or another project ✓ CORRECT
- C. the register must be wrong, since the two bases disagree
- D. the average of the two, P78.9, is the provision's true confidence

Rationale: The two percentiles measure different uncertainties (discrete events versus systemic estimate error), so a single percentage of base cannot express a confidence at all — which is the defect. A mistakes "above the median" for "sized"; C misreads a difference in basis as an error; D averages two probabilities that are not on the same scale.

MCQ 8.3-C [8.3.3 · Application] The largest register item (p 0.40, impact 2,400,000) retires with no impact. Register P80 falls from 4,246,095 to 2,930,955 while the 10 % rule stays at 4,800,000. If

the resulting excess is drawn and funded 70/30, the effect on annual covenant headroom of 372,438 is a fall of:

- A. nil — contingency is not carried at a cost
- B. 187,265, or 50.3 %, because 1,308,332 of extra senior debt raises the instalment by 156,054
✓ CORRECT
- C. 11,214, the commitment fee on the excess
- D. 1,869,045, the excess itself

Rationale: $4,800,000 - 2,930,955 = 1,869,045$; $\times 0.70 = 1,308,332$; $/8.383844 = 156,054$ of extra instalment; the 1.20× trigger rises to 6,198,827 and headroom falls to 185,173. A ignores that drawn contingency is debt serviced for the loan life; C is the cost while the excess is undrawn, not drawn; D confuses the provision with its coverage effect.

MCQ 8.3-D [8.3.1 · Analysis] Why do lenders treat 2,085,972 of contingent equity support as worth less than 2,085,972 of funded contingency?

- A. it is a smaller amount in present-value terms
- B. it is only drawable on certification
- C. it depends on a sponsor's willingness and ability to pay when called, which is a credit exposure rather than cash in the structure **✓ CORRECT**
- D. it cannot be documented

Rationale: Funded contingency is money the facility will lend against certification; contingent support is a commitment whose value is the obligor's credit (8.3.1, and Domain 5 KA 5.2.3 on several versus joint-and-several liability). B describes funded contingency; A confuses timing with credit; D is false.

MCQ 8.3-E [8.3.2 · Evaluation] Kestrel's retained register supports a P80 contingency of 4,246,095 (8.85 % of base) while the Stage C accuracy range supports 6,512,795 (13.57 %); the funded balancing line is 3,645,403, a P69.7 provision on the register. The works are let under a fixed-price, date-certain wrap. The soundest recommendation is:

- A. fund 6,512,795, following the convention of taking the higher of two defensible provisions
- B. size the provision at 4,246,095 on the retained register, and settle in the funding documents whether the additional 600,692 comes from debt or from equity — the range-based 6,512,795 measures base-estimate uncertainty the wrap has transferred to the contractor **✓ CORRECT**
- C. leave the funded 3,645,403 unchanged and disclose it as a P69.7 provision
- D. fund the 600,692 by capitalising it into senior debt, the coverage cost being only 23.1 % of headroom

Rationale: "take the higher" is where the reconciliation starts, not where it ends: the next question is which of the two uncertainties the contracting structure has eliminated, and a full wrap transfers base-estimate uncertainty, leaving the owner the discrete retained register (8.3.2, 8.1.2). A applies half the rule and would fund 2,266,700 against a risk the owner no longer carries. C is honest and insufficient — a named P69.7 beats an unnamed percentage but is still 600,692 short of the confidence the register supports. D is a real funding route that pre-empts the decision it should present: capitalising 600,692 takes the instalment to 5,081,284, the **DSCR** to 1.2564 and annual headroom from 372,438 to 286,459 for the whole twelve-year loan life, which is a choice about where the money lands and belongs to the sponsors before close.

MCQ 8.3-F [8.3.1 · Comprehension] A delivery manager asks where management reserve sits in a project financing. The best explanation is:

- A. it is contingency under another name, relabelled for the lenders
- B. lenders will not fund undefined scope, so its financing equivalent sits outside the base case as contingent support — a cost-overflow undertaking, standby equity or a standby tranche — called on a trigger rather than drawn on certification **✓ CORRECT**
- C. it is the contractor's own contingency inside the contract price
- D. it is the unused balance of contingency remaining at the end of the build

Rationale: contingency is funded provision for identified risks within agreed scope, drawn against certification; management reserve covers what the register does not contain, which a facility will not lend against (8.3.1). A collapses a distinction the funding structure depends on; C names a third and separate pot the owner cannot draw at all (8.1.2's pitfall); D describes a release rather than a reserve.

MCQ 8.3-G [8.3.3 · Evaluation] Kestrel's ground-conditions risk retires with no impact: the register's P80 falls from 4,246,095 to 2,930,955 while the 10 % rule stays at 4,800,000, leaving 1,869,045 of excess provision. The project director resists reducing it while construction is running, and the finance function does not press the point because the excess costs only the 11,214 a year of commitment fee. The soundest position is that:

- A. the director is right: cover should not be reduced while construction continues, and 11,214 is immaterial
- B. the excess should be released, and the release relied on as a matter of judgement at each quarterly review
- C. a recalculation of the required provision at defined milestones should be written into the finance documents, because the asymmetry is 11,214 a year undrawn against 187,265 of annual covenant headroom — 50.3 % — permanently lost if the excess is drawn **✓ CORRECT**
- D. the excess should be drawn now and held as project cash, so that it is available if needed

Rationale: released contingency is rarely given back because nobody is rewarded for handing money back, so the answer is mechanical rather than behavioural (8.3.3, 8.A.2): funded 70/30 the excess adds 1,308,332 of senior debt and 156,054 to the annual instalment, taking the DSCR to 1.2358 and headroom to 185,173 for the whole twelve-year loan life. A prices the visible cost and ignores the permanent one. B is the arrangement that has just failed. D converts an option into the exposure the release exists to avoid, and does so at once.

■ SELF-CHECK — KA 8.3

1. Why can two correct P80 contingencies differ by 2,266,700 on one project? — They measure different uncertainties: the register measures discrete events, the accuracy range measures systemic base-estimate error; take the higher, then ask which the contract transferred.
2. State the two computable defects of the percentage method. — It states no confidence level (4,800,000 is P87.3 on one basis, P70.4 on the other), and it does not respond to risk retirement: 1,869,045 of excess, costing 11,214 a year undrawn and 50.3 % of covenant headroom if drawn.
3. What does the P80-to-P95 step cost on Kestrel, and how is it provided? — 1,485,280 more of cover, provided as a 2,085,972 contingent commitment rather than funded cash, because tail cover as cash is prohibitively expensive.

KNOWLEDGE AREA 8.4

Delay impact, cost-to-complete, and the interface with project controls

Topics: 8.4.1 from earned value to cost to complete and the funds sufficiency test · 8.4.2 the cost of a month of slip during construction · 8.4.3 one data spine, two questions.

8.4.1 From earned value to cost to complete and the funds sufficiency test

Definition. Cost to complete (CTC) is the money still required to finish: $CTC = EAC - AC$ on any chosen **EAC** method. The **funds sufficiency test** — often written into a facility as an "in balance" condition — asks whether the funds remaining available, from the undrawn facility, unused contingency and uncalled equity, are at least **CTC**. It is the test a lender runs on a monthly cost report, and it is not a test a project control account produces.

WORKED EXAMPLE

Worked example 8.4.1 — what a lender does with Auriga's earned value.

- 1. Setup.** Project Auriga (PML-AI D7, KA 7.3.3) at the week-13 data date: **BAC 4,000,000**, **AC 2,120,000**, **EV 1,920,000**, **CPI 0.905660**, **SPI 0.923077**, and the three published forecasts **EAC 4,200,000** (remaining work at the budgeted rate), **4,416,667** (**BAC/CPI**) and **4,608,056** (**CPI × SPI**). Assume the delivery organisation financed it: total funding **4,300,000**, being **BAC 4,000,000** plus a funded contingency of **300,000** (7.5 % — the same order as Kestrel's 7.59 %), of which **180,000** has already been drawn. Of the sanction register (PML-AI D8, KA 8.2.2), R2 has materialised and R4 has been retired; R1 (p 0.35, impact 240,000), R3 (p 0.25, 320,000) and the R5 opportunity (p 0.30, −120,000) remain open. Run both lender tests.
- 2. Formula.** $CTC = EAC - AC$; funds available = total funding − AC; surplus/(shortfall) = available − CTC. Contingency adequacy: remaining contingency versus the P80 of the remaining register (mean = ΣEMV , variance = $\Sigma p(1 - p)impact^2$, P80 $\approx$ mean + 0.8416 σ).
- 3. Substitution.** Available = $4,300,000 - 2,120,000 = 2,180,000$. CTC by method: $4,200,000 - 2,120,000$; $4,416,667 - 2,120,000$; $4,608,056 - 2,120,000$. Remaining register mean = $84,000 + 80,000 - 36,000$; variance = $0.2275 \times 240,000^2 + 0.1875 \times 320,000^2 + 0.21 \times 120,000^2$.
- 4. Result.**

EAC method	EAC (USD)	CTC (USD)	Funds available (USD)	Surplus / (shortfall)
Remaining at budgeted rate	4,200,000	2,080,000	2,180,000	+100,000
BAC/CPI	4,416,667	2,296,667	2,180,000	(116,667)
CPI × SPI	4,608,056	2,488,056	2,180,000	(308,056)

Remaining register: mean **128,000**, σ **187,957**, **P80 286,185** against remaining contingency of **120,000** — a **166,185** shortfall on the contingency-adequacy test. 5. **Interpretation.** This is the domain's bridge, in one table. A project controller's report ends at the **EAC** column and its honest conclusion is a range: the project will cost between 4.2 and 4.6 million depending on which assumption about the remaining work holds (PML-AI D7's point, that a forecast is a statement about the future's resemblance to the past). **A lender reads the same three numbers and produces a date and an amount:** on the **BAC/CPI** forecast the project is out of balance by 116,667, so before the next drawdown the sponsor must inject 116,667 of equity or the facility does not fund. The forecast

has become a cash call. Three consequences follow for a finance leader. **The choice of EAC method is a commercial negotiation, not a technical one**, because it sets the size of the cash call: the sponsor argues for the budgeted-rate forecast (+100,000, in balance), the technical adviser for BAC/CPI or worse, and the honest position is that a CPI of 0.906 sustained over thirteen weeks is evidence about the remaining work unless something specific has changed — which someone must name. **The contingency test fails independently and earlier**. With 120,000 of contingency left against a remaining P80 exposure of 286,185, a certifier cannot honestly confirm that remaining contingency is adequate for remaining risk, and that conclusion needed no EAC at all — only the register and the draw history. A project can therefore be out of balance on the contingency test while every cost report still shows a forecast inside budget. **And the shortfall was arithmetically predictable at sanction**. The 300,000 funded was a **P53.5** provision against the sanction register (mean 278,000, σ 252,642), while the P80 was **490,624**; the actual overrun on the BAC/CPI forecast is 416,667, a **P70.8** event — comfortably inside a P80 provision and comfortably outside a P53.5 one. Nothing unlikely happened. **The project was funded to a confidence level nobody named, and then behaved normally**.

8.4.2 The cost of a month of slip during construction

The three components. A month of delay declared during construction costs three separable things: **escalation** on the scope not yet bought, because the money will be spent a month later at a month's higher prices; **extra interest** on the balance already drawn, which accrues for a month with no offsetting progress; and **deferred revenue**, because the operating period starts a month later. Domain 5 (KA 5.4.2) priced a slip at COD, where remaining spend is zero and the escalation row vanishes. During the build it does not vanish, and the relative sizes of the three rows change continuously through the programme.

WORKED EXAMPLE

Worked example 8.4.2 — Kestrel declares a three-month slip at the end of quarter six.

- Setup.** At the end of construction quarter six, cumulative debt drawn is **31,990,655** (Domain 6's funding profile). The remaining owner-retained scope — owner's costs and land of 3,600,000 spent on the same profile — stands at **922,906** at then-current prices; the EPC scope is fixed-price and date-certain, so its escalation is the contractor's risk. Escalation on retained scope is **3.6 %** per annum, giving a monthly factor of $1.036^{(1/12)} = 1.00295161$, i.e. **0.2952 %** per month. The debt rate is **6.0 %**; operating **CFADS** would be **6,384,000** per year. Delay damages are **USD 20,000 per day** (Domain 5). Compute the cost of one month, the cost of the three-month slip, the damages coverage, and the coverage consequence if the cost components are capitalised.
- Formula.** Escalation row = remaining retained scope at then-current prices $\times$ monthly escalation factor $- 1$. Interest row = debt drawn $\times$ rate $\div 12$. Revenue row = annual **CFADS** $\div 12$. Coverage consequence: new debt = 42,000,000 + capitalised cost; instalment = new debt $\div$ **AF**(0.06, 12); **DSCR** = **CFADS** $\div$ instalment; covenant trigger = instalment $\times 1.20$ (Domain 10).
- Substitution.** $922,906 \times 0.00295161$; $31,990,655 \times 0.06/12$; $6,384,000/12$; $20,000 \times 30$; $(2,724 + 159,953) \times 3$; $42,488,032 / 8.383844$.
- Result.**


Component	Per month (USD)	Share	Three months (USD)
Escalation on owner-retained scope	2,724	0.39 %	8,172
Extra interest on drawn debt	159,953	23.03 %	479,860
Deferred CFADS	532,000	76.58 %	1,596,000
Total economic cost	694,677		2,084,032
Delay damages at 20,000/day	600,000	86.37 % recovered	1,800,000
Uncovered, borne by the SPV	94,677		284,032

Capitalising the escalation and interest components (488,032) takes debt to **42,488,032**, the instalment to **5,067,846.24**, the [DSCR](#) from 1.2743 to **1.2597**, the covenant cash trigger to **6,081,415** and annual headroom to **302,585** — down **69,853**, or **18.8 %**. 5. **Interpretation.** Read the share column first. **Three quarters of the cost of a delay during construction is revenue the project will never earn, and almost none of it is escalation** — which is precisely the reverse of the intuition a cost engineer brings to the meeting, because escalation is the row a cost report shows and deferred revenue is a row it does not contain. The 0.39 % escalation share is not a general result; it is the value of the wrap, and it is measurable: on the unwrapped variant of 8.1.2 the escalation row would be **39,045** per month rather than 2,724, so the fixed-price contract is worth **36,321 per month of slip** on this row alone. The second reading is the damages calibration. At 20,000 per day the regime recovers 86.37 % of a delay declared at quarter six, but its adequacy moves through the programme: at financial close a month of slip costs **552,329** and damages of 600,000 over-recover; at COD it costs **742,000** (reconciling exactly to Domain 5's 7,000 + 17,733.33 per day) and they recover 80.86 %. **The crossing is between quarter two (580,033) and quarter three (604,156)** — after which a single flat damages rate is never again sufficient, because the interest row grows monotonically as the balance builds while the escalation row shrinks as scope is bought. A negotiator who understands that asks for a **stepped** damages rate rather than a higher flat one, which is both cheaper for the contractor to accept and better matched to the exposure. The third reading is the permanence. 488,032 of capitalised delay cost — a rounding error against a 60,000,000 envelope — removes **18.8 %** of the covenant headroom for the entire twelve-year loan life, on a project that is otherwise exactly as forecast. That is the mechanism Domain 5 named and this example generalises: **a construction event becomes an operating constraint the moment it is capitalised**, and whether it is capitalised or funded with equity is a choice about whether the slip lands on coverage or on equity return. It belongs to the sponsors before the event, in the funding documents, not to a project director in the month it happens. Finally, the deferred-revenue row deserves the caution Domain 5 attached to it: 1,596,000 of [CFADS](#) deferred is a cash fact, not a value loss of that size, because most of it is postponed rather than destroyed — the value calculation (Domain 5, KA 5.4.2) is the right instrument for a damages negotiation and the cash calculation is the right instrument for a funding one.

A month of slip costs 552,329 at close and 742,000 at COD — the same month, 34.3 % dearer

Escalation falls as the remaining scope runs out; interest rises as the balance builds. Only the deferred-revenue band is constant

Damages calibrated at 20,000 per day cover the cost until quarter three and never again — the crossing is between q2 (580,033) and q3 (604,156)



A single damages rate cannot be right for a cost that moves 34.3 % across the programme it insures

Fig 8.4.1 — The cost of a month of slip rises through the build

8.4.3 One data spine, two questions

The principle. The project controls function and the financing function should read the same numbers. They will always ask different questions of them, and the interface exists to keep the numbers common while letting the questions differ. Where two sets of numbers appear — a cost report for management and a different one for lenders — the organisation has created a reconciliation burden it will fail at exactly the moment it matters.

What each side owns.

Object	Project controls owns	The financing asks
Cost breakdown and control accounts	The structure, the coding, the hundred-per-cent rule (PML-AI D4)	Do the accounts map to the funded uses in the sources and uses?
Earned value at the data date	PV, EV, AC, CPI, SPI and their integrity	What is CTC, and is the facility in balance? (8.4.1)
The EAC family	The method and its stated assumption	Which forecast does the technical adviser certify, and what cash call follows?
Schedule and forecast COD	The network, the critical path, the float	What is the cost per month of the slip, and who bears it? (8.4.2)
Risk register	Identification, probability, impact, response	What contingency does it support at P80, and is the remainder adequate? (8.3.2)
Contingency drawn and remaining	The internal draw protocol	Can a draw be certified against the remaining risk?
Change control	The baseline and its integrity	Is this a variation under the contract, a scope change requiring consent, or a cost overrun?

The monthly reporting pack this domain endorses is therefore one document with a financing annexe: certified progress and the draw request; earned value and the three **EAC** forecasts with their assumptions named; **CTC** and the funds sufficiency position against undrawn facility, unused contingency and uncalled equity; contingency drawn to date trended against **risk retired** rather than against time (PML-AI D8, KA 8.3.2 — burning 60 % of contingency while retiring 20 % of the register is the signal); the register's current P80 and the remaining-adequacy test; forecast COD with the cost-per-month figure current at that point in the programme; and the covenant consequence of any capitalised delay or overrun cost. Every one of those lines derives from data the controls function already holds. **What the financing adds is not data collection; it is three transformations — CTC, sufficiency, and the coverage consequence — and the discipline of stating which confidence level the provisions represent.**

The governance point. The reconciliation must be scheduled, not discovered. A finance leader who first meets a **CPI** of 0.906 in a certifier's refusal to fund has lost the two months in which the problem was cheap to fix, and the relationship cost of that surprise is the one Domain 10 (KA 10.4.4) priced: a lender who learns of a problem from a compliance certificate prices the discovery into everything afterwards.

AI in this KA

The transformations of 8.4.3 are deterministic and monthly, which makes them ideal automation: **CTC** under every **EAC** method, the sufficiency test against current facility balances, the register's P80 recomputed as items retire, and the cost-per-month-of-slip figure recomputed as the drawn balance moves. Anomaly detection is a second strong use — a **CPI** that steps without an operational cause is usually a measurement change (PML-AI D7, MCQ 7.2-A), and a machine watching the series sees it before a monthly reader does. Three prohibitions. It must not **choose the EAC method**, because that choice sets the size of a cash call and is a commercial position requiring an accountable owner. It must not **certify** — whether a cost is a proper contingency item, whether a variation falls within the contract, whether remaining contingency is adequate are certifications with contractual consequences, and Domain 12's boundary applies. And it must not **write the narrative** accompanying a deteriorating forecast, because a fluent explanation of a variance is exactly what a lender must not receive without a human who can be questioned about it.

Verification: recompute $CPI = EV/AC$ and one **EAC** independently at each data date and require reconciliation to the automated pack to the dollar; test PML-AI D7's identity (KA 7.3.4) that **TCPI** to the **BAC/CPI** forecast equals the current **CPI**, as a free check on the forecast engine; confirm by hand that the register mean behind the automated P80 equals ΣEMV ; and tie the funds-sufficiency line to the facility agent's own statement of undrawn commitment, not to the model's memory of it.

■ KEY TERMS — KA 8.4

Term	Meaning
Cost to complete (CTC)	$EAC - AC$; the money still required on a stated forecast method.
Funds sufficiency / in balance	Funds available (undrawn facility + unused contingency + uncalled equity) $\geq$ CTC.
Cash call	The equity injection a sufficiency failure requires before the next drawdown.
Contingency adequacy test	Remaining contingency $\geq$ P80 of the remaining register; fails independently of EAC.
Cost per month of slip	Escalation on unbought scope + extra interest on drawn debt + deferred CFADS.
Stepped damages	Delay damages that rise through the programme to match a rising exposure.
Data spine	One set of numbers, two sets of questions; the controls-financing interface.

■ SAMPLE MCQS — KA 8.4

MCQ 8.4-A [8.4.1 · Application] BAC 4,000,000, contingency 300,000, AC 2,120,000, EAC on BAC/CPI 4,416,667. The funds sufficiency position is:

- A. a surplus of 100,000
- B. a shortfall of 116,667, requiring an injection before the next drawdown ✓ CORRECT
- C. a shortfall of 416,667
- D. in balance, since the EAC is within the total funding of 4,300,000

Rationale: Available = $4,300,000 - 2,120,000 = 2,180,000$; CTC = $4,416,667 - 2,120,000 = 2,296,667$; shortfall 116,667. A is the position on the budgeted-rate forecast; C is the overrun against BAC, not against funding; D is false — 4,416,667 exceeds 4,300,000.

MCQ 8.4-B [8.4.1 · Analysis] Remaining contingency is 120,000 and the P80 of the remaining register is 286,185. A cost report shows the forecast inside total funding. The correct reading is:

- A. no action is required, since the forecast is inside funding
- B. the contingency-adequacy test fails by 166,185 and does so independently of any EAC forecast ✓ CORRECT
- C. the register must be revised downwards to match the contingency
- D. the shortfall is 120,000

Rationale: Adequacy compares remaining provision with remaining exposure and needs only the register and the draw history; $286,185 - 120,000 = 166,185$. A misses the second test entirely; C is the corruption the test exists to prevent; D subtracts in the wrong direction.

MCQ 8.4-C [8.4.2 · Application] Debt drawn 31,990,655 at 6.0 %; remaining owner-retained scope 922,906 escalating at 3.6 % per annum; annual CFADS 6,384,000. One month of slip costs closest to:

- A. USD 532,000
- B. USD 694,677 ✓ CORRECT
- C. USD 162,677
- D. USD 730,998

Rationale: $922,906 \times (1.036^{(1/12)} - 1) = 2,724$; $31,990,655 \times 0.06/12 = 159,953$; $6,384,000/12 = 532,000$; total 694,677. A is the deferred revenue alone; C omits the revenue row; D is the unwrapped variant, where escalation applies to the whole remaining scope (39,045).

MCQ 8.4-D [8.4.2 · Analysis] Flat delay damages of 20,000 per day recover 86.37 % of the cost of a month's slip at quarter six, over-recover at financial close and recover 80.86 % at COD. The best negotiating response is:

- A. accept the rate — it recovers most of the cost
- B. seek a higher flat rate calibrated to the COD figure
- C. seek a stepped rate rising through the programme, since the exposure rises monotonically as the drawn balance builds ☒ **CORRECT**
- D. remove damages and rely on contingency

Rationale: A flat rate cannot fit a cost that moves 34.3 % across the programme; a stepped rate matches exposure and is cheaper for a contractor to accept than a flat rate set at the maximum. A ignores the tail; B over-recovers early and is resisted for that reason; D abandons the transfer altogether.

MCQ 8.4-E [8.4.1 · Evaluation] At Auriga's week-13 data date the facility is in balance by +100,000 on the budgeted-rate forecast, out of balance by 116,667 on **BAC/CPI** and by 308,056 on **CPI × SPI**; separately, remaining contingency of 120,000 stands against a remaining-register P80 of 286,185. All four courses below have been proposed. Which should the finance leader take?

- A. argue for the budgeted-rate **EAC** of 4,200,000, which leaves the facility in balance with 100,000 to spare
- B. accept **BAC/CPI**, prepare the 116,667 cash call, and treat the contingency position as a consequence of it
- C. take both tests to the sponsor now, leading with the 166,185 contingency shortfall, because that test rests on the register and the draw history alone and is therefore due whichever **EAC** is certified ☒ **CORRECT**
- D. revise the remaining register down so that the 120,000 still available is adequate

Rationale: the adequacy test needs no forecast at all and fails independently and earlier, so it is the finding that survives whatever the certifier accepts about the **EAC** — and it exposes the real defect, a project funded at sanction to a P53.5 provision nobody named (8.4.1). A is the sponsor's negotiating position and is defensible as a position, but a **CPI** of 0.906 sustained over thirteen weeks is evidence about the remaining work unless somebody can name what has changed, and it leaves the 166,185 untouched. B is the right answer to the second test first: it makes the cash call turn on a forecast method that is negotiable while the register shortfall is not. D is the corruption the adequacy test exists to prevent.

MCQ 8.4-F [8.4.2 · Evaluation] A three-month slip is declared at construction quarter six. Capitalising its escalation and interest components — 488,032 — takes debt to 42,488,032, the instalment to 5,067,846.24, the **DSCR** from 1.2743 to 1.2597 and annual headroom from 372,438 to 302,585, a fall of 18.8 % for the whole twelve-year loan life. The soundest position is that:

- A. it should be capitalised: 488,032 is a rounding error against a 60,000,000 envelope
- B. this is a choice about whether the slip lands on coverage for twelve years or on equity return now, and it belongs to the sponsors before the event, in the funding documents ☒ **CORRECT**
- C. it should be funded with equity in every case, because lenders do not permit delay costs to be capitalised

- D. the decision should be left to the project director in the month the slip is declared, when the amount is known

Rationale: a construction event becomes an operating constraint the moment it is capitalised (8.4.2, and Domain 5 KA 5.4.2). A prices the cash and ignores twelve years of coverage. C presents as universal a lender position that is a negotiated term of the funding documents. D leaves a structural choice to the person with the least room to negotiate it and the strongest reason to close it out quickly — which is how the answer gets made by default rather than chosen.

MCQ 8.4-G [8.4.3 · Comprehension] A controls function already produces earned value, the *EAC* family, the register and the contingency draw history. What the financing adds to that monthly pack is:

- A. a second set of numbers, prepared to the lenders' definitions
- B. three transformations of the same data — cost to complete, the funds sufficiency position, and the coverage consequence — plus the discipline of stating which confidence level each provision represents ✓ CORRECT
- C. an independent estimate of the cost to complete, prepared by the lenders' technical adviser
- D. the same information recast onto a different cost breakdown structure

Rationale: one data spine, two sets of questions: every line the financing annexe needs derives from data the controls function already holds (8.4.3). A is the failure the principle exists to prevent — two sets of numbers create a reconciliation burden that fails exactly when it matters. C describes a diligence activity, not what the pack adds. D is a coding exercise that answers neither question the financing asks.

■ SELF-CHECK — KA 8.4

1. What does a lender compute from an *EAC* that a controller does not? — $CTC = EAC - AC$, then funds sufficiency against undrawn facility, unused contingency and uncalled equity — producing a cash call with a date rather than a forecast range.
2. Why was Auriga's shortfall predictable at sanction? — The 300,000 funded was a P53.5 provision against a register whose P80 was 490,624; the 416,667 overrun is a P70.8 event, normal behaviour against a provision nobody had priced.
3. Which row of the slip cost is largest, and which is the wrap worth? — Deferred *CFADS* at 76.58 %; the wrap saves 36,321 per month on the escalation row (2,724 rather than 39,045).

— Advanced topics — Domain 8

8.A.1 Correlation, and why the independent P80 is the optimistic one

The aggregation of 8.3.2 assumes independence, and construction risks are systematically not independent: a single adverse ground condition drives geotechnical cost, programme, dewatering and third-party interface simultaneously; a single supply-chain event moves several package prices at once. The consequence is directional and knowable. Variance under positive correlation is $\sum \sigma_i^2 + 2 \sum_{i < j} \rho_{ij} \sigma_i \sigma_j$, so any positive ρ raises σ and therefore raises the P80, while the mean is unchanged — **correlation never changes what you expect to pay and always changes what you must provide**. On Kestrel's register, treating C1 and C2 as correlated rather than independent raises the provision without touching the 2,690,000 mean, which is why a P80 quoted without a statement about correlation should be read as a lower bound. Practically, three habits: name the common

drivers (ground, weather, a shared supplier, a single approval authority) and group the items that share them; run the simulation with a correlation matrix rather than an independence assumption; and where the matrix cannot be defended, state the independence assumption explicitly in the paper rather than letting the reader infer sophistication that is not there.

8.A.2 Contingency drawdown as a monitored curve

A funded contingency should be expected to deplete, and the useful control is not its balance but the relationship between two curves: contingency consumed and register retired. Plot both as percentages of their sanction values on the same axes and the diagnosis is immediate. Consumption tracking retirement is a healthy project spending its provision on the risks it provided for. Consumption ahead of retirement is the classic overrun signature — money going out against events that were not in the register, which means either the register was incomplete or the draws are not proper contingency items. Retirement ahead of consumption is the release case of 8.3.3, worth 1,315,141 on Kestrel when C1 closed, and it is the case organisations handle worst: released contingency is rarely given back, because nobody is rewarded for returning money. The financing answer is to write the release into the documents — a defined recalculation of the required provision at stated milestones, with the excess applied to prepayment or released to distribution. That converts a behavioural problem into a mechanical one.

8.A.3 The reviewer's cost-and-contingency eye

Testable invariants for any construction cost and contingency model:

- Every contingency percentage is accompanied by the **estimate class** of the base it is a percentage of; a percentage without a class is unreviewable (8.1.2).
- The four cost families are separately identifiable, and operating cost appears **only** inside **CFADS**, never in the sources and uses (8.1.1).
- Lifecycle cost is present, dated, escalated at the same rate as operating cost, and matched by a reserve whose deposit schedule funds the **first** overhaul before it falls due (8.1.3).
- Capitalised interest reproduces the **area rule** $r_q \times g \times S \times \sum \text{cum}(t-1)$ to the dollar; a mismatch localises the defect to rate, balance convention, draw timing or gearing (8.2.2).
- Escalation is applied **period by period to the profile**, never to a total; escalation on fixed-price wrapped scope is zero and on retained scope is not (8.2.3).
- Every escalation rate names an index, a source, a base date and a human owner, and construction and revenue escalation are distinct assumptions; contingency states a **confidence level**, the register's mean equals $\sum \text{EMV}$, and the independence assumption is stated or a correlation matrix is documented (8.2.3, 8.3.2, 8.A.1).
- Range-based and register-based provisions are both computed, the higher is taken, and the contracting structure that eliminates one of them is named (8.3.2).
- Contingency consumed is trended against **risk retired**, not against elapsed time (8.A.2).
- $\text{CTC} = \text{EAC} - \text{AC}$ on a **named EAC** method, and the funds sufficiency line ties to the facility agent's undrawn commitment, not to the model (8.4.1).
- The contingency-adequacy test is run separately from the sufficiency test, because it fails earlier and independently (8.4.1).
- Delay cost has three rows, and the interest row uses the **balance drawn at the date of the slip**, not the full facility (8.4.2).
- Any capitalised overrun or delay cost is carried through to the instalment, the **DSCR**, the covenant trigger in cash and the headroom (8.3.2, 8.4.2, Domain 10).

— Industry variations — Domain 8

- **Water and desalination.** Short, well-characterised membrane and dosing cycles make 8.1.3's arithmetic unusually reliable and the maintenance reserve unusually large as a share of CFADS — 10.10 % on Kestrel. Intake and marine works carry the ground and weather-standby risks that dominate the retained register, so the contingency negotiation is about who owns the geotechnical basis.
- **Solar and wind generation.** Capital cost is modular and heavily benchmarked, so ranges narrow earlier than in process plant and Stage D provisions are genuinely thin. The estimating battleground moves to grid connection and civil works, where one interface can carry more range than all the generating equipment; lifecycle cost turns on the timing of a few component replacements rather than their price.
- **Transport concessions.** Earthworks and structures make ground risk the largest line and quantity growth against a Stage C estimate the norm, so unwrapped procurement forces 8.3.2's range-based provision rather than the register-based one. Long construction periods magnify both the escalation exposure and the shape effect of 8.2.2.
- **Digital infrastructure.** Fit-out is phased against demand, so the profile is a sequence of S-curves and the area rule must be applied per phase. Short equipment lifecycles compress the tail and make the lifecycle charge a far larger share of operating economics than in civil assets.
- **Process industry and petrochemicals.** Estimate classes matter most here, because scope definition genuinely drives outturn and the ladder's factor of 6.25 is not theoretical. Long-lead equipment pulls escalation exposure early, pushing 8.2.3's breakeven towards front-loading; turnaround and inspection cycles drive lifecycle cost and are regulated in many jurisdictions, so their timing is less discretionary than elsewhere.
- **Social infrastructure and availability PPPs.** Capital cost is comparatively predictable and the lifecycle obligation is the commercial substance: a 25- or 30-year hard-facilities obligation with a handback condition, priced at bid and unalterable afterwards. Getting 8.1.3 wrong here is not a reserve problem; it is a bid that cannot be performed.

— Case study — Domain 8: the contingency that was a percentage (transport)

Situation. A sponsor group bid a 34-kilometre highway concession in an emerging market. The capital estimate at bid was a **Stage C** feasibility estimate of **USD 420,000,000**, carrying a stated accuracy range of **−15 % / +30 %**. The financing envelope allowed contingency at the group's standing policy of **8 % of base cost — 33,600,000** — and the works were let as **four separate packages** with the concessionaire managing interfaces, because splitting the packages had produced the lowest bid prices.

What happened. The two decisions were incompatible and the incompatibility was computable at bid. An 8 % provision is a Stage E number (8.1.2); the project had a Stage C estimate and, having declined a wrap, had retained the base-estimate uncertainty the range describes. Translating the range through a triangular distribution with minimum 357,000,000, mode 420,000,000 and maximum 546,000,000 gives a **P80 outturn of 476,986,958 — a contingency requirement of 56,986,958, or 13.57 % of base**. The funded 33,600,000 was a **P64.1** provision against the range ($F = 1 - (92,400,000)^2 / ((189,000,000)(126,000,000)) = 0.6415$). Twenty-one months into a forty-

month programme, earthworks quantities on two of the four packages exceeded the bid quantities, the interface between the earthworks and structures packages produced a sequence of compensation events that neither contractor owned, and cumulative certified cost reached **252,000,000** against an earned value of **231,000,000** — a **CPI** of **0.9167**. The **BAC/CPI** forecast was **458,181,818**, an overrun of **38,181,818** against a base of 420,000,000 and **4,581,818** more than the entire funded contingency.

How it resolved. The facility's in-balance test failed at the next certification: funds available were $453,600,000 - 252,000,000 = 201,600,000$ against a cost to complete of $458,181,818 - 252,000,000 = 206,181,818$ — a **4,581,818** shortfall, and the technical adviser could not certify a further contingency draw because, with **26,200,000** of the 33,600,000 already drawn, remaining contingency was **7,400,000** against a remaining register whose P80 exposure was assessed at **19,300,000**. Drawdown stopped. The sponsors funded the shortfall as additional equity of **20,000,000** — deliberately above the 4,581,818 minimum, because a cash call computed to the last dollar fails again on the next report — and accepted a tightened reporting regime and a lenders' quantity surveyor with access to the packages. Against an original equity of 113,400,000 on a 75/25 structure, the injection **increased the sponsors' equity base by 17.6 %** and moved gearing to **71.8/28.2**, diluting the modelled equity return correspondingly.

What the domain teaches here. The contingency was not too small by accident; it was sized by a method that could not see the estimate class or the procurement decision. Both defects of 8.3.3 are visible: the 8 % rule stated no confidence level, so nobody noticed it was a P64.1 provision against a distribution its own estimate had published, and it did not respond when the decision to split the packages transferred the base-estimate uncertainty back to the owner. The cost of the arithmetic nobody did at bid was 20,000,000 of equity — 17.6 % of the sponsors' committed capital — and the whole of it was computable from two documents the sponsors already held: the estimate's stated range and the procurement strategy. **The provision was 23,386,958 short of the P80 its own estimate implied, and the eventual call was 20,000,000.** The arithmetic was not merely available; it was approximately right.

— Case study B — Domain 8: the release nobody wanted to take (solar generation)

Situation. A 180 MW solar project reached financial close with a **Stage D** capital estimate of **USD 148,000,000**, a funded contingency of **11,100,000** (7.5 % of base) and a retained risk register of eleven items with a mean exposure of **6,240,000**, a standard deviation of **4,050,926** and a **P80 of 9,649,259**. Two items dominated: a grid-connection energisation risk (p 0.35, impact 6,000,000) and a land-title consolidation risk (p 0.25, impact 4,800,000), together carrying **3,300,000** of the mean and, on their own, **3,536,948** of standard deviation — 76.2 % of the register's total variance from two of eleven lines. The remaining nine carried a mean of 2,940,000 and a standard deviation of **1,974,842**. Contingency was drawable on certification against a **0.60 % per annum** commitment fee on the undrawn balance.

What happened. Fourteen months in, both dominant items retired cleanly: the connection agreement was energised on schedule and the final title parcels were consolidated. Recomputing the register without them gave a mean of **2,940,000**, a standard deviation of **1,974,842** and a **P80 of 4,602,027** — the P80 requirement had fallen by **5,047,232**, more than half, on a single month's news. Against 11,100,000 of contingency of which **1,800,000** had been drawn, the project was holding an undrawn commitment of **9,300,000** against a P80 requirement of 4,602,027 — an excess of **4,697,973**. Nobody proposed releasing it. The project director's position was that contingency should not be reduced while construction was still running; the sponsor's finance function did not

challenge it, because the visible cost of the excess was only the commitment fee — **28,188 a year** — which no operating budget felt.

How it resolved. The lenders' technical adviser raised it at the next quarterly review, and the facility's contingency-recalculation clause was invoked at the second construction milestone. The required provision was reset to the P80 of the live register plus a **15 % correlation uplift** — **5,292,331** — and the difference between the undrawn balance and that figure, **4,007,669**, was cancelled from the commitment. The fee saving was modest: **36,069** over the remaining eighteen months. The real prize was what cancellation made impossible. Had the excess instead been drawn — which is what available money tends to become — it would have added **2,805,368** of senior debt at 70 % gearing, and at the facility's 5.4 % over a 15-year tenor ($AF(0.054, 15) = 10.104624$) that is **277,632** of additional annual debt service for fifteen years, against a project whose entire contingency provision was 11,100,000.

What the domain teaches here. The cost of holding excess contingency while it is undrawn is trivially small, which is exactly why it is never challenged; the cost if it is drawn is permanent, and it lands on the coverage ratio rather than on any construction budget. That asymmetry — 36,069 of fee against 277,632 a year of debt service — is the whole case for a mechanical release. The 15 % correlation uplift is the honest form of 8.A.1: the release was taken, and the independence assumption was not pretended to. And the governance failure is the general one — released contingency requires a mechanism, because no individual is rewarded for handing money back. Write the recalculation into the documents at defined milestones and the release happens; leave it to judgment and the excess is carried to COD every time, and then spent.

— Executive perspective — Domain 8

What a project finance director cannot delegate in this domain:

- **The estimate class behind every contingency percentage.** Not the percentage — the class. A 7.59 % provision is prudent at Stage E and negligent at Stage C, and the director is the only person in the room who sees both the estimate and the procurement decision that sets which one applies (8.1.2).
- **The link between the contracting strategy and the contingency line.** They are one decision taken twice, usually by different people in different months. Whoever declines a wrap has just resized the contingency, and someone must say so out loud before the envelope is fixed (8.1.2, Case study A).
- **The confidence level, named.** P80 or P50 is a risk-appetite decision belonging to governance, not to an analyst and never to a model. A provision whose confidence nobody stated is a provision nobody chose — Auriga's 300,000 was P53.5, and behaving normally broke it (8.4.1).
- **The lifecycle obligation and the reserve that funds it.** The director owns the question "what does this asset owe in year seven, and is the money going to be there?" A **DSCR** of 0.4561 in one year is a payment default on an otherwise healthy project, and it is entirely a reserve design question (8.1.3).
- **The release mechanism.** Contingency held after its risk has retired costs almost nothing while it is undrawn — 11,214 a year on Kestrel, 28,188 on Case study B — which is exactly why nobody challenges it, and a great deal if it is then spent: 50.3 % of Kestrel's covenant headroom, or 277,632 a year of debt service for fifteen years in Case study B. The director's job is to have the recalculation written into the documents before anyone has to be brave (8.A.2, Case study B).

- **The interface, scheduled rather than discovered.** One data spine, two questions. A director who first meets a CPI of 0.906 in a certifier's refusal to fund has lost the months in which it was cheap, and has paid the relationship cost Domain 10 priced (8.4.3).

— Calculation exercises — Domain 8

Exercise 8.1 A Stage C estimate of **30,000,000** carries a range of **-15 % / +30 %**. Using a triangular distribution, compute the mean outturn, the P80 outturn and the contingency each implies; then state the percentile a 10 %-of-base rule buys. Solution. $a = 25,500,000$, $m = 30,000,000$, $b = 39,000,000$. Mean = $(a + m + b)/3 = 31,500,000 \rightarrow$ contingency **1,500,000 (5.00 %)**. P80 solves $(b - x)^2 = 0.20 (b - a)(b - m) = 0.20 \times 13,500,000 \times 9,000,000 = 2.43 \times 10^{13} \rightarrow b - x = 4,929,503 \rightarrow x = \mathbf{34,070,497}$, contingency **4,070,497 (13.57 %)**. The 10 % rule gives 3,000,000, i.e. $x = 33,000,000$; $F = 1 - (6,000,000)^2 / (1.215 \times 10^{14}) = 0.7037 \rightarrow \mathbf{P70.4}$. Common error: assuming the percentile depends on project size — it does not. The percentile a percentage rule buys is a function of the range alone, which is why -15/+30 always returns 13.57 % at P80 and P70.4 for a 10 % rule, whatever the base.

Exercise 8.2 **30,000,000** of spend over six quarters, **60 %** debt-funded at **8 %** per annum (2 % per quarter) on opening balances, draws at period end. Profile as planned: 10, 15, 20, 25, 18, 12 per cent. Compute capitalised interest, and the interest under the reversed profile 12, 18, 25, 20, 15, 10. Solution. $r_q \times g \times S = 0.02 \times 0.60 \times 30,000,000 = 360,000$ per unit of area. As planned, $\Sigma \text{cum}(t-1) = 0 + 10 + 25 + 45 + 70 + 88 = 238 \% \rightarrow 2.3800 \rightarrow \text{IDC } \mathbf{856,800}$. Reversed, $0 + 12 + 30 + 55 + 75 + 90 = 262 \% \rightarrow 2.6200 \rightarrow \text{IDC } \mathbf{943,200}$. Difference **86,400** on identical total spend and duration. Common error: computing interest on the closing balance, which adds one period of interest to every draw and overstates IDC by $r_q \times g \times S = 360,000$ — an error of 42 % on the correct figure, and the single commonest defect in construction models.

Exercise 8.3 A register carries p/impact pairs $0.30/1,500,000 \cdot 0.45/800,000 \cdot 0.20/2,200,000 \cdot 0.25/1,000,000$, plus an opportunity $0.20/(500,000)$, on a base estimate of 22,000,000. Compute the mean, σ and P80, and state the percentile bought by an 8 %-of-base rule. Solution. Mean = $450,000 + 360,000 + 440,000 + 250,000 - 100,000 = \mathbf{1,400,000}$. Variance = $0.21 \times 1,500,000^2 + 0.2475 \times 800,000^2 + 0.16 \times 2,200,000^2 + 0.1875 \times 1,000,000^2 + 0.16 \times 500,000^2 = 1,632,800,000,000$; $\sigma = \mathbf{1,277,811}$; P80 = $1,400,000 + 0.8416 \times 1,277,811 = \mathbf{2,475,405}$. The 8 % rule gives **1,760,000**, i.e. $z = 0.2817 \rightarrow \mathbf{P61.1}$, leaving a **715,405** shortfall against P80. Common error: omitting the opportunity from the variance. It reduces the mean by 100,000 but adds $0.20 \times 0.80 \times 500,000^2 = 40,000,000,000$ to the variance, because an opportunity is an uncertain outcome like any other — dropping it understates σ and therefore the P80.

Exercise 8.4 A project declares a one-month slip with **18,000,000** of debt drawn at **7.0 %**, **2,400,000** of owner-retained remaining scope at then-current prices escalating at **4.2 %** per annum, and annual CFADS of **4,200,000**. Delay damages are 12,000 per day (30-day month). Compute the cost of the month, the damages coverage, and the share of cost a revenue-only calibration would have missed. Solution. Monthly escalation factor $1.042^{(1/12)} = 1.00343438$, i.e. 0.3434 %; escalation row $2,400,000 \times 0.00343438 = \mathbf{8,243}$. Interest row $18,000,000 \times 0.07/12 = \mathbf{105,000}$. Revenue row $4,200,000/12 = \mathbf{350,000}$. Total **463,243**. Damages $12,000 \times 30 = 360,000 \rightarrow \mathbf{77.71 \%}$ coverage; uncovered **103,243**. A calibration on forgone revenue alone targets 350,000 and misses $(8,243 + 105,000)/463,243 = \mathbf{24.45 \%}$ of the cost. Common error: using the full facility

amount rather than the balance actually drawn at the date of the slip in the interest row — the error grows through the programme and is largest exactly where the delay exposure is largest.

Exercise 8.5 BAC 30,000,000, funded contingency 2,400,000, at the data date AC 16,800,000, EV 15,600,000, PV 16,000,000. Compute CPI, SPI, the three EAC forecasts, CTC and the funds sufficiency position on each. Solution. $CPI = 15,600,000/16,800,000 = 0.928571$; $SPI = 15,600,000/16,000,000 = 0.975000$. Available = 32,400,000 – 16,800,000 = 15,600,000. (a) $EAC = 16,800,000 + 14,400,000 = 31,200,000$, CTC 14,400,000, surplus +1,200,000. (b) $EAC = 30,000,000/0.928571 = 32,307,692$, CTC 15,507,692, surplus +92,308. (c) $EAC = 16,800,000 + 14,400,000/(0.928571 \times 0.975) = 32,705,325$, CTC 15,905,325, shortfall (305,325). Common error: reporting the (b) result as "in balance" without qualification. A surplus of 92,308 is 0.28 % of the facility — inside the rounding of a monthly report, not a margin — and on the $CPI \times SPI$ forecast the same project is 305,325 short. Sufficiency conclusions must be stated with the method that produced them.

— Practitioner's toolkit — Domain 8

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 8.T.1 — Contingency basis note (one page, per sanction and per recalculation)

One page that must exist before any contingency figure is quoted. **Base estimate**: amount, base date, price basis, preparer. **Estimate class**: stage, accuracy range, and the engineering deliverables complete that justify the class, with a named owner. **Procurement**: wrapped or unwrapped, package count, interface owner — and the explicit statement of which uncertainties the contract transfers. **Range-based provision**: distribution used, parameters, mean, P50, P80, P95. **Register-based provision**: item count, mean = ΣEMV , σ , P80, P95, independence assumption or correlation matrix. **The reconciliation**: which of the two governs and why. **The funded figure**: amount, percentage of base, and the percentile it represents on the governing basis. **Contingent support**: amount, form, trigger, obligor, enforceable against what balance sheet. **Approval**: confidence level chosen, by whom, on what date. Rule: no contingency number leaves the organisation without this page attached, and the page is reissued at every recalculation milestone.

Toolkit 8.T.2 — Construction cost model check (before any envelope is fixed)

- [] Four cost families separately identified; operating cost appears only inside CFADS.
- [] Base date stated; every escalation rate names an index, a source and a human owner.
- [] Escalation applied period-by-period to the profile; zero on wrapped scope, non-zero on retained.
- [] Construction and revenue escalation are distinct assumptions.
- [] IDC reproduces the area rule $r_q \times g \times S \times \Sigma cum(t-1)$ to the dollar.
- [] Interest convention stated (opening / average balance) and paired with the period length.
- [] Balancing line identified; it is not a round number; it is tested against 8.T.1's percentile.
- [] Lifecycle programme dated, escalated and matched by a reserve deposit schedule that funds the first overhaul before it falls due.
- [] Handback or decommissioning obligation identified, with its cash date relative to loan maturity.
- [] Sensitivity run on: escalation rate, spend profile shape, contingency drawn, and COD date.

- [] Every capitalised overrun scenario carried through to instalment, **DSCR**, covenant trigger in cash and headroom.

Toolkit 8.T.3 — Monthly construction pack, financing annexe

One annexe to the existing controls report — never a second set of numbers. Rows: certified progress and this month's draw request against the funding profile · **PV, EV, AC, CPI, SPI** at the data date · the three **EAC** forecasts with assumptions named, and the method the certifier is using · **CTC and the funds sufficiency position** against undrawn facility, unused contingency and uncalled equity, tied to the agent's statement · contingency drawn and remaining, trended **against register retired** rather than against time · the register's current P80 and the remaining-adequacy test · forecast COD and the cost per month of slip current at this point in the programme, in three rows · damages coverage at the current exposure · the **DSCR**, covenant trigger and headroom consequence of any capitalised cost · exceptions, each with a named accountable person. Front line, always: **is the facility in balance, and is the remaining contingency adequate for the remaining risk?**

— Exam preparation — Domain 8

What is assessed. The four cost families and where each enters a financing; estimate classes and the contingency a range implies at a stated confidence; why a fixed-price wrap changes the defensible contingency; whole-life cost, the level annual charge and the reserve that prevents a lifecycle payment default; the area rule and the price of shape; escalation applied to a profile, base dates and the shape-neutrality breakeven; contingency sized from a register and reconciled against a range-based provision; the two computable defects of the percentage method; contingent support and why it is worth less than funded cash; the conversion of an **EAC** into a **CTC**, a sufficiency test and a cash call; the contingency-adequacy test as a separate and earlier failure; and the three components of a month's slip, their movement through the programme, and the coverage consequence of capitalising any of them.

The calculations to do under time pressure. Contingency implied by an accuracy range at the upper bound and at P80 via a triangular distribution (8.1.2, 8.3.2, Exercise 8.1) · the percentile a percentage rule buys, on both bases (8.3.3) · present value and level annual charge of a lifecycle programme, and the year-of-overhaul **DSCR** without a reserve (8.1.3) · IDC from the area rule, and the same profile reversed (8.2.2, Exercise 8.2) · escalated spend period-by-period, and the shape-neutral escalation rate $g \times r$ (8.2.3) · register mean, variance, σ , P80 and P95, including opportunities (8.3.2, Exercise 8.3) · standby support as P95 (5,731,375) less funded contingency (8.3.1) · **CTC** and funds sufficiency on all three **EAC** methods (8.4.1, Exercise 8.5) · remaining-register P80 against remaining contingency (8.4.1) · cost per month of slip in three rows, damages coverage, and the **DSCR**/headroom consequence of capitalising it (8.4.2, Exercise 8.4).

The traps.

- Quoting a contingency percentage without the estimate class of its base — the domain's central defect (8.1.2, MCQ 8.1-A).
- Applying a Stage E provision to a Stage C estimate after declining a wrap (8.1.2, MCQ 8.1-B, Case study A).
- Putting operating cost in the sources and uses, or forgetting that an operating error recurs every year against a fixed headroom (8.1.1, MCQ 8.1-D).
- Omitting lifecycle cost, or funding it at a policy percentage rather than against the next overhaul's date (8.1.3, MCQ 8.1-C).

- Escalating a total rather than the profile — 1,424,815 of overstatement on Kestrel (8.2.3, MCQ 8.2-B).
- Computing IDC on closing rather than opening balances — a 42 % overstatement in Exercise 8.2 (8.2.2, Exercise 8.2).
- Summing worst cases, or funding the mean, and calling either a contingency (8.3.2, MCQ 8.3-A).
- Dropping opportunities from the variance while keeping them in the mean (Exercise 8.3).
- Presenting an independent P80 as conservative when correlation makes it a lower bound (8.A.1).
- Treating contingent support as equivalent to funded contingency (8.3.1, MCQ 8.3-D).
- Holding contingency after its risk has retired, and pricing it as the commitment fee (11,214 a year on Kestrel) rather than as the coverage loss if it is drawn — 50.3 % of headroom (8.3.3, MCQ 8.3-C, Case study B).
- Running the sufficiency test and not the contingency-adequacy test, which fails earlier and independently (8.4.1, MCQ 8.4-B).
- Pricing a delay on forgone revenue alone — 24.45 % of the cost missed in Exercise 8.4 — or using the full facility rather than the drawn balance in the interest row (8.4.2, MCQ 8.4-C).
- Accepting a flat damages rate against an exposure that moves 34.3 % across the programme (8.4.2, MCQ 8.4-D).
- Reporting a 0.28 %-of-facility surplus as "in balance" without naming the EAC method (Exercise 8.5).

How the domain connects. Backward: Domain 3 supplied the compounding and $AF(r, n)$ this domain escalates and annuitises with; Domain 4 supplied the EAV machinery behind the level lifecycle charge and the appraisal rate; Domain 5 supplied the EPC wrap that makes a thin contingency defensible and the at-COD delay arithmetic this domain generalises to the whole programme; Domain 6 supplied the sources-and-uses statement, the funding profile and the 3,645,403 balancing line this domain finally justifies; Domain 7 supplied the revenue escalation that must not be confused with cost escalation. Forward: Domain 9 supplies the standby tranches and concessional money that fund the contingent support of 8.3.1; Domain 10 tests every coverage consequence computed here; Domain 11 allocates the risks the register enumerates and Domain 12 documents the wrap that transfers them; Domain 13's model audit checks the area rule and the escalation basis; **Domain 14 is this domain in operation** — draw requests, cost-to-complete reports and contingency certification, month by month. Across the suite: PML-AI Domain 6 owns the schedule that produces the S-curve, PML-AI Domain 7 owns the earned value this domain transforms, and PML-AI Domain 8 owns the register and the confidence- level arithmetic. **The single most useful idea to carry between the two books is that a forecast and a funding position are different objects, and the transformation between them — CTC, sufficiency, coverage — is the finance leader's contribution to a monthly report they did not write.**

— Domain 8 summary

A contingency percentage is meaningless without the estimate class it was struck against. On a 48,000,000 base, the same estimate implies a provision of 24,000,000 at screening and 3,840,000 at control-estimate maturity — a factor of 6.25 — so Kestrel's funded **3,645,403 (7.59 %)** is defensible only because a fixed-price, date-certain EPC wrap moved a Stage C estimate to a Stage E position; procured unwrapped, the same works need of the order of **14,400,000** and a 60,000,000 envelope does not fund them. Lifecycle cost is the family most often missed: Kestrel's membrane and pump programme is worth **6,881,021** in present value, **644,606** as a level annual charge and **10.10 %** of CFADS, and without a reserve the year-seven DSCR is **0.4561** — a payment default, not a breach, on an

otherwise healthy project. The schedule prices the financing through its shape: capitalised interest obeys the area rule $IDC = r_q \times g \times S \times \Sigma \text{cum}(t-1)$, so the same 48,000,000 over the same eight quarters costs **1,345,680** back-loaded, **1,607,760** on the S-curve and **2,000,880** front-loaded — a **655,200** spread — while escalation runs the other way by **574,146**, leaving a total spread of only **86,681** and a shape-neutral escalation rate of **4.1659 %**, almost exactly the heuristic $g \times r = 4.20 \%$. Contingency sized from the retained register (mean **2,690,000**, σ **1,848,973**) supports **4,246,095** at P80, against **6,512,795** from the Stage C range at P80: two defensible numbers 2,266,700 apart, reconciled by taking the higher and naming the contract that eliminated the other. The funded amount is a **P69.7** provision and **600,692** short of the register's P80, which capitalised would take the **DSCR** to **1.2564** and headroom to **286,459**, down **23.1 %**, for twelve years. The percentage method fails in two computable ways: 10 % of base is **4,800,000**, a **P87.3** promise against the register and a **P70.4** promise against the range — the rule cannot say which — and it does not move when risk retires, leaving **1,869,045** of excess after one item closes, which costs **11,214** a year while undrawn and, if drawn, adds 1,308,332 of senior debt, takes the **DSCR** to **1.2358** and removes **50.3 %** of covenant headroom for twelve years. Finally, the bridge: a controller's **EAC** family becomes a lender's cash call. Auriga's three forecasts give costs to complete of 2,080,000, 2,296,667 and 2,488,056 against 2,180,000 available — in balance, then **116,667** short, then **308,056** short — while the contingency-adequacy test fails independently and earlier, 120,000 remaining against a remaining P80 of **286,185**; and the shortfall was predictable at sanction, because a **P53.5** provision met a **P70.8** event. A month of slip declared at quarter six costs **694,677** — 0.39 % escalation, 23.03 % interest, 76.58 % deferred revenue — rising to **742,000** at COD, so a flat damages rate of 20,000 per day covers the cost only until quarter three; capitalising three months of the cost components removes **18.8 %** of Kestrel's covenant headroom permanently. Domain 9 funds the contingent support this domain sizes; Domain 10 tests every ratio it moves; Domain 14 runs it monthly.

09

DOMAIN 9

Funding Structure and Sources of Capital

— Why this domain exists

Domain 4 discounted Kestrel's cash flows at 8.0 % because the board said 8.0 %. Domain 5 asked whether the project was bankable, Domain 6 built the model, Domains 7 and 8 filled it with revenue and cost. None of them asked the question this domain exists to answer: **where does the money come from, what does each source cost, and who decides the mix?** A hurdle rate inherited rather than derived is the largest single unexamined assumption a project finance leader can carry.

The domain's central claim is deliberately contrarian. In corporate finance, capital structure is chosen by minimising the weighted average cost of capital. **In project finance it is not.** Moving Kestrel from 60 % to 80 % gearing cuts its WACC by **20.4 basis points** while lifting the sponsors' equity return by **184.6 basis points** and destroying **0.3716** of DSCR — and the 1.20× covenant fails outright above 74.34 % gearing. The structure is chosen by the **coverage constraint**, negotiated between people whose returns move in opposite directions, and the cost of capital is the consequence of that negotiation rather than its objective. Everything here follows from that inversion: equity and shareholder instruments and what they cost (KA 9.1); the debt stack from senior to mezzanine to bonds and the blended arithmetic across it (KA 9.2); the specialist sources — Islamic finance structures, export credit, development finance — that change tenor and price in ways commercial banks cannot (KA 9.3); and the public-sector and market instruments that shift the answer again (KA 9.4).

Learning objectives. After this domain a candidate can: distinguish the forms of project equity and shareholder instruments and state what each does to coverage, tax and control; build a cost of equity from a documented premium build-up and re-lever a beta for a project's own structure; compute an after-tax cost of debt and a project WACC, and say precisely why a project WACC is not the sponsor's corporate WACC; blend a senior/mezzanine/equity stack with correct weights and tax treatment; quantify the leverage trade-off on both faces and identify the gearing at which each covenant threshold binds; describe subordinated, mezzanine and bond instruments including negative arbitrage; describe Islamic finance structures in economic terms and compare them with conventional debt on an all-in basis; compute the all-in cost of an export-credit or development-finance tranche and separate that cost effect from the debt-capacity effect of tenor; compute a grant's effect on WACC, DSCR and equity return and state the treatment choice that drives it; test sustainability-linked pricing against its own verification cost; compute and decompose a refinancing gain and price a gain-share obligation; and govern AI-assisted structuring so that no structure is recommended on an unverified cost of capital.

The master financing. Kestrel Water SPC continues from Domains 1–8 and 10. Capex is **USD 60,000,000**, funded 70/30 as **USD 42,000,000** of senior debt at **6.0 % over 12 years** (annual instalment **USD 5,009,635.23**; year-one interest **2,520,000**, principal **2,489,635**) plus **USD 18,000,000** of equity. Operating life is **25 years**. Documented CFADS is **USD 6,384,000** (6,984,000 before working-capital movements), against EBITDA of **7,500,000** and EBIT of **5,100,000**; the

resulting ratios are **DSCR 1.2743** = **LLCR 1.2743**, **PLCR 1.9431** (Domain 10, KA 10.2). Domain 4's appraisal at 8 % gave **NPV +16,179,360**, **IRR 12.19 %**, **MIRR 9.73 %**, **PI 1.270**.

Two Kestrel cash-flow streams appear in this volume and this domain keeps them apart. Domain 4's appraisal stream — net inflows of **USD 8,900,000 a year for fifteen years** — is the pre-financing screening forecast against which a **discount rate** is applied. Domain 10's documented **CFADS of 6,384,000**, held level over the 25-year life on that domain's stated illustrative convention, is the stream against which **coverage** is tested and from which **distributions** are paid. This domain applies costs of capital to the first and computes coverage and equity returns on the second, never mixing them inside one calculation; equity returns quoted on the level-**CFADS** basis are labelled as such. Their divergence is not an inconsistency to be hidden — KA 9.1.4 turns it into the domain's most useful breakeven.

The tax rate, derived rather than assumed. Every after-tax cost below depends on it, and the thread fixes it. **EBITDA 7,500,000** less **CFADS-before-working-capital 6,984,000** leaves cash tax of **516,000**; taxable profit is **EBIT 5,100,000** less interest **2,520,000** = **2,580,000**; the implied rate is $516,000 / 2,580,000 = 20.0\%$ exactly, and depreciation reconciles as **EBITDA - EBIT = 2,400,000**. Kestrel's year-one interest tax shield is $2,520,000 \times 20\% = 504,000$. A tax rate is a jurisdictional fact and an interest deduction a jurisdictional privilege: both come from the project's actual tax position (Domain 2), never from a modelling convention.

KNOWLEDGE AREA 9.1

Equity and shareholder instruments

Topics: 9.1.1 equity in a limited-recourse structure · 9.1.2 shareholder instruments · 9.1.3 the cost of equity, built up · 9.1.4 the leverage trade-off, computed on both faces.

9.1.1 Equity in a limited-recourse structure

Definition. Project equity is the capital that ranks last in the cash waterfall, absorbs the first losses, carries no contractual return, and in exchange holds the residual and the votes. In a limited-recourse structure it is also the only capital whose provider is normally expected to lose the whole of it without the transaction failing — which is why lenders size it as a risk buffer rather than as a funding source.

Three practical distinctions decide how equity behaves in a financing. **Committed versus contributed:** equity is committed at close through a subscription agreement and contributed when called, and lenders care about the enforceability of the commitment far more than its size — a commitment supported by a letter of credit from an investment-grade bank is worth more, in credit terms, than a larger promise from a thinly-capitalised sponsor. **Pro-rata versus back-ended funding:** equity drawn alongside debt in the agreed ratio, or debt drawn first with equity plugging the final gap; sponsors prefer the latter because it defers the outflow, lenders resist it because it leaves them exposed while the sponsor has nothing at risk, and where they concede it they require a standby letter of credit for the undrawn balance. **The equity bridge loan (EBL):** a construction-period facility secured on the equity commitment rather than on the project, funding the sponsor's contribution and repaid by it at commercial operations date. Because a rate of return is sensitive to timing, this is one of the cheapest available uplifts to a sponsor's headline number — and one of the least understood.

WORKED EXAMPLE**Worked example 9.1.1 — what an equity bridge is actually worth.**

1. **Setup.** For this example only, Kestrel's two-year construction period is modelled explicitly: equity of **18,000,000** at $t = 0$, operations from year 3, **CFADS 6,384,000**, senior debt service **5,009,635.23** for twelve operating years, then **CFADS** alone to the end of the 25-year operating life. An EBL is offered at **5.0 %**, interest capitalised, repaid from equity at COD.
2. **Formula.** Equity **IRR** is the rate at which the equity cash-flow stream has zero present value. The EBL's capitalised cost is $E \times ((1 + r_{\text{EBL}})^2 - 1)$.
3. **Substitution.** Without the EBL the stream is $(-18,000,000; 0; 0; 1,374,364.77 \times 12; 6,384,000 \times 13)$. The EBL's cost is $18,000,000 \times (1.05^2 - 1) = 18,000,000 \times 0.1025$; the contribution at $t = 2$ becomes $18,000,000 + 1,845,000$.
4. **Result.** Base equity **IRR 10.6696 %**. With the EBL, the sponsor injects **19,845,000** at $t = 2$ and the equity **IRR** rises to **11.6157 %** — an uplift of **94.61 basis points**, bought by paying **1,845,000** of interest.
5. **Interpretation.** The uplift is real but it is timing, not value: the project generates exactly the same cash. The governing test is a clean identity — **an equity bridge is accretive if and only if its rate is below the equity IRR it defers**, and at a rate exactly equal to that **IRR** the uplift is precisely zero; solving for the indifference rate here returns **10.6696 %**, the base equity **IRR** itself, to every decimal tested. Three cautions follow. The bridge is **debt**, and a sponsor reporting an EBL-enhanced **IRR** without disclosing it has presented a financing artefact as a project return. It is **recourse to the sponsor**, so it consumes corporate credit capacity the treasury may value above 95 basis points. And a bridge that cannot be repaid at COD — because the commitment has weakened or COD has slipped past the bridge's maturity — converts a timing benefit into a refinancing event at the worst moment in the project's life (Domain 8's delay arithmetic, in funding form).

9.1.2 Shareholder instruments

Equity is rarely a single instrument. The standard family, and what each is for:

Instrument	Economic character	Why it is used
Ordinary share capital	Residual claim, votes, no contractual return	The irreducible risk layer lenders require
Subordinated shareholder loan	Contractual interest and repayment, ranked below all third-party debt	Interest may be deductible; repayment is easier than a capital reduction
Preference shares	Fixed or participating dividend, priority over ordinary equity, usually non-voting	Sizing a passive investor's return without giving control
Sponsor support / contingent equity	An obligation to inject on a defined trigger (cost overrun, ratio breach)	Bridges lender risk without funding it at close
Deferred consideration / development-cost roll-in	Development spend credited as equity at close	Recognises promoter value without cash

The shareholder loan is the instrument that repays study, because it changes the after-tax arithmetic: part of a sponsor's contribution structured as subordinated debt can create a deductible interest expense while remaining, in ranking terms, indistinguishable from equity to third-party lenders.

WORKED EXAMPLE**Worked example 9.1.2 — the shareholder-loan shield, and the ranking that destroys it.**

1. **Setup.** Of Kestrel's 18,000,000 of equity, **6,000,000** is provided as a subordinated shareholder loan at **12.0 %**, ranked below the senior facility and serviceable only from distributions. Cash tax rate **20.0 %** (derived above). Discount the shield at the board's 8.0 % over the 25-year life.
2. **Formula.** Annual shield = interest × tax rate. $PV = \text{shield} \times AF(0.08, 25)$.
3. **Substitution.** Interest $6,000,000 \times 12.0 \% = 720,000$; shield $720,000 \times 20 \% = 144,000$; $AF(0.08, 25) = 10.674776$; $144,000 \times 10.674776$.
4. **Result.** Annual shield **144,000**; present value **USD 1,537,168** — **25.62 %** of the 6,000,000 tranche, created by a documentation choice rather than by any change in the project.
5. **Interpretation.** A quarter of the tranche's face value in present-value terms explains why shareholder loans are ubiquitous. It is also the most jurisdiction-dependent number in this domain: thin-capitalisation limits, interest-deduction caps expressed as a share of **EBITDA**, transfer-pricing constraints on the rate, and withholding tax on cross-border interest can each reduce the shield to nothing. **No shareholder-loan shield may be modelled without a written tax opinion on the specific structure.** The structural caution is sharper still: the shield exists only while the loan is genuinely subordinated. If the interest is drafted to rank **above CFADS** rather than being paid out of distributions, Kestrel's **DSCR** falls from **1.2743** to $6,384,000 / (5,009,635.23 + 720,000) = 1.1142$ — straight through the 1.20× covenant and the 1.15× lock-up — and the tax saving has bought a default. Serviced correctly, out of distributions of **1,374,364.77**, the same interest is covered **1.9088** times and the senior ratio is untouched. The instrument is safe; the ranking clause is where it becomes dangerous.

9.1.3 The cost of equity, built up

Definition. The cost of equity k_e is the return an equity provider requires for bearing the project's residual risk. It is not observed and never will be; it is **constructed**, and the professional obligation is to construct it in a way that is documented, decomposable and challengeable. The build-up form used throughout this volume:

$$k_e = r_f + \beta_e \times ERP + CRP + SP$$

$$\beta_e = \beta_a \times (1 + (1 - T) \times D/E)$$

where r_f is the risk-free rate (a long-dated government yield in the cash flows' currency), ERP the equity risk premium, β_a the asset (unlevered) beta of the project's activity, β_e the equity beta after re-levering for the project's own capital structure, CRP a country risk premium and SP a project-specific premium for single-asset concentration and illiquidity. Each term is a judgment; stating them separately is what makes the judgment reviewable.

WORKED EXAMPLE**Worked example 9.1.3 — Kestrel's cost of equity.**

1. **Setup.** Illustrative inputs, all to be replaced with the transaction's own: r_f **4.10 %** (long-dated sovereign yield in USD), ERP **6.00 %**, β_a **0.60** (contracted water utility — low systematic exposure because revenue is availability-based, per Domain 7), CRP **0.50 %**, SP **0.50 %**. Capital structure $D/E = 42,000,000 / 18,000,000$; T **20.0 %**.
2. **Formula.** As above.
3. **Substitution.** $D/E = 2.333333$; $(1 - 0.20) \times 2.333333 = 1.866667$; $\beta_e = 0.60 \times (1 + 1.866667) = 0.60 \times 2.866667$; $\beta_e \times ERP = 1.72 \times 6.00$; $k_e = 4.10 + 10.32 + 0.50 + 0.50$.
4. **Result.** β_e **1.72**; k_e **15.42 %**.
5. **Interpretation.** Read the decomposition, not the total. Of the 15.42 %, **4.10 points** is the time value of money, **10.32 points** is systematic risk amplified by leverage, and **1.00 point** is country and single-asset risk. The leverage term is the largest single component and it is **created by the financing decision** — the first hint of this domain's central claim, that the sponsors' required return is a property of the structure they chose rather than of the plant. Two disciplines follow. k_e is **not constant across structures**: re-lever it whenever gearing changes, or every comparison in KA 9.2 is invalid. And the non-beta terms are not re-levered in this convention — a modelling choice with visible consequences in 9.A.1, to be stated and applied uniformly. Sponsors also carry a **target** return, commonly a round 15 % or 16 % set by committee policy rather than by build-up; the gap between a derived 15.42 % and a policy 16 % is a negotiation to be minuted, not a discrepancy to be resolved by adjusting a beta until the two agree.

9.1.4 The leverage trade-off, computed on both faces

Gearing is the only structural lever that moves the sponsor's return and the lender's protection in opposite directions at the same time, which is why it is negotiated last and hardest. The two faces must be computed together or the conversation is not honest.

WORKED EXAMPLE**Worked example 9.1.4 — five gearings, three consequences.**

1. **Setup.** Kestrel's 60,000,000 capex funded at 60 %, 65 %, 70 %, 75 % and 80 % senior gearing; loan rate **6.0 %**, tenor **12 years**, $AF(0.06, 12) = 8.383844$; level **CFADS 6,384,000** over the 25-year life; k_e re-levered at each gearing per 9.1.3; after-tax cost of debt **4.80 %** (KA 9.2.1). Equity cash flow is **CFADS** less senior debt service for twelve years, then **CFADS** for thirteen.
2. **Formula.** $DSCR = CFADS \div (D \div AF(r, n))$ (Domain 10, KA 10.2.1); equity **IRR** from the equity stream; $WACC = g \times k_d(1 - T) + (1 - g) \times k_e$.
3. **Substitution.** At 70 %: $42,000,000 / 8.383844 = 5,009,635.23$; $6,384,000 / 5,009,635.23$; equity stream $(-18,000,000; 1,374,364.77 \times 12; 6,384,000 \times 13)$; $0.70 \times 4.80 + 0.30 \times 15.42$.
4. **Result.**


Gearing	Senior debt	Equity	Debt service	DSCR	Distributable yrs 1-12	k_e	Equity IRR	WACC
60 %	36,000,000	24,000,000	4,293,973.06	1.4867	2,090,026.94	13.02 %	11.7685 %	8.0880 %
65 %	39,000,000	21,000,000	4,651,804.15	1.3724	1,732,195.85	14.05 %	12.1206 %	8.0370 %
70 %	42,000,000	18,000,000	5,009,635.23	1.2743	1,374,364.77	15.42 %	12.5311 %	7.9860 %
75 %	45,000,000	15,000,000	5,367,466.32	1.1894	1,016,533.68	17.34 %	13.0193 %	7.9350 %
80 %	48,000,000	12,000,000	5,725,297.41	1.1151	658,702.59	20.22 %	13.6146 %	7.8840 %

1. **Interpretation.** Across twenty points of gearing the sponsors gain **184.61 basis points** of equity return, the project saves **20.40 basis points** of **WACC**, and the lenders lose **0.3716** of coverage. The ratio is the finding: **the equity return gain is 9.05 times the WACC gain**, which means gearing in a project financing is overwhelmingly a transfer to equity rather than an efficiency for the project. Priced at the margin, moving from 70 % to 75 % buys **48.82 basis points** of equity **IRR** for **8.50** points of **DSCR** — about **5.75 basis points of equity return per hundredth of coverage surrendered** — and that exchange rate, computed for the actual structure, is the only defensible basis on which to argue a gearing. Now impose Domain 10's covenants and the table stops being a menu. At **75 %** the 1.20× covenant requires **CFADS** of $5,367,466.32 \times 1.20 = 6,440,960$, which exceeds the base-case 6,384,000 — the covenant **fails on the base case, before any stress**. At **80 %** even the 1.15× lock-up requires **6,584,092** and also fails. Precisely: the 1.30× target binds at **41,171,123** of debt (**68.6185 %** gearing, Domain 10's Case A), the 1.20× covenant at **44,602,050 (74.3367 %)**, and the 1.15× lock-up at **46,541,269 (77.5688 %)**. The cost-minimising structure is unavailable and the constraint is not price, it is coverage. That is the domain's central claim, in a table.

Gearing is a transfer to equity, not an efficiency for the project

Kestrel Water SPC: level CFADS 6,384,000; senior debt at 6.0 % over 12 years; cost of equity re-levered at each gearing

The 1.30 × sizing target binds at 68.62 % gearing; above 74.34 % the 1.20 × covenant fails on base-case cash, before any stress



The structure is chosen by the coverage constraint; the cost of capital is the consequence

Fig 9.1.4 — The leverage ladder: what gearing buys and what it costs

The two cases, and where the equity return really comes from. On the level-CFADS basis the base structure's equity IRR is **12.5311 %** — below the **15.42 %** cost of equity derived in 9.1.3. That is not an arithmetic error; it is the difference between a lender's flat "bank case" and a sponsor's escalating "sponsor case", and it is where equity's return actually lives. Solving for the constant CFADS escalation that lifts the equity IRR to exactly 15.42 % gives **1.7403 %** a year: CFADS of 6,384,000 in year one becomes 6,495,101 in year two, 6,608,136 in year three, and DSCR improves from **1.2743** to **1.5407** by year twelve. The whole equity case therefore rests on **174 basis points of annual escalation** — a tariff-indexation clause, not a financial-engineering choice. State it that way in the board paper: the equity return is a contracted escalation assumption, and Domain 7's indexation drafting is the asset that produces it.

AI in this KA

Where it earns its place. Re-levering a beta across a gearing ladder, recomputing equity IRR for twenty candidate structures, and solving for the escalation breakeven above are mechanical, high-volume and error-prone by hand — exactly the work to delegate.

Where it must not go. It must not choose the premiums. ERP, β_a , CRP and SP determine k_e , they are unobservable, and a model asked to "estimate the cost of equity" returns a confident figure assembled from whatever premium conventions dominated its training data, with no disclosure of which convention, which market or which date. A cost of equity without a named, dated, owned source for each component is not an input, it is an opinion wearing decimals. Nor may it decide the gearing: that trades a lender's protection against a sponsor's return and belongs to accountable people.

Verification, concretely. Re-lever one case by hand and confirm β_e . Confirm the WACC weights sum to one and that the debt weight uses the same debt figure as the coverage test. Test the equity-bridge identity — set the bridge rate equal to the base equity IRR and confirm the uplift computes to

zero; a model reporting a gain there has a timing error. Confirm every quoted equity **IRR** names its cash-flow case. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 9.1

Term	Meaning
Committed vs contributed equity	Enforceable obligation to subscribe, versus cash actually injected.
Pro-rata / back-ended funding	Equity drawn alongside debt, versus equity plugging the final gap.
Equity bridge loan (EBL)	Construction facility against the equity commitment; accretive only below the equity IRR it defers.
Subordinated shareholder loan	Sponsor funding as ranked debt; may create a tax shield, dangerous if mis-ranked.
Contingent / sponsor support	Obligation to inject on a defined trigger rather than at close.
k_e	Cost of equity, built up as $r_f + \beta_e \times ERP + CRP + SP$.
β_a / β_e	Asset (unlevered) beta; equity beta re-levered as $\beta_a(1 + (1 - T)D/E)$.
Bank case / sponsor case	Lender's conservative cash forecast versus sponsor's escalating forecast; equity's return lives in the gap.

■ SAMPLE MCQS — KA 9.1

MCQ 9.1-A [9.1.3 · Application] With $\beta_a = 0.60$, $D/E = 42,000,000 / 18,000,000$, $T = 20\%$, $r_f = 4.10\%$, $ERP = 6.00\%$, $CRP = 0.50\%$ and $SP = 0.50\%$, the cost of equity is:

- A. 15.42 % ☒ **CORRECT**
- B. 8.70 %
- C. 17.10 %
- D. 14.42 %

Rationale: $\beta_e = 0.60 \times (1 + 0.80 \times 2.333333) = 1.72$; $k_e = 4.10 + 1.72 \times 6.00 + 0.50 + 0.50 = 15.42\%$. B uses the **unlevered** beta throughout ($4.10 + 0.60 \times 6.00 + 1.00 = 8.70$) — the error of not re-levering at all. C re-levers **without** the tax adjustment ($\beta_e = 0.60 \times 3.333333 = 2.00 \rightarrow 4.10 + 12.00 + 1.00 = 17.10$). D omits the country and single-asset premiums ($4.10 + 10.32 = 14.42$) — building the beta term correctly and then forgetting the rest of the build-up.

MCQ 9.1-B [9.1.4 · Analysis] Moving Kestrel from 70 % to 80 % gearing changes **WACC** from 7.9860 % to 7.8840 % and equity **IRR** from 12.5311 % to 13.6146 %, while **DSCR** falls from 1.2743 to 1.1151 against a 1.20× covenant. The correct conclusion is:

- A. gear to 80 % — the **WACC** is lower and **WACC** minimisation is the objective
- B. the 80 % structure is not financeable: the 1.20× covenant fails on the base case, and the 10.2 basis points of **WACC** saved are irrelevant beside a breach ☒ **CORRECT**
- C. gear to 80 % and negotiate a 1.10× covenant, since the equity gain is large
- D. the two structures are equivalent because total capital is unchanged

Rationale: At 80 % the covenant requires **CFADS** of $5,725,297.41 \times 1.20 = 6,870,357$ against 6,384,000 available — a base-case breach, so the structure does not exist to be optimised (9.1.4). A applies the

corporate-finance objective to a constrained problem; C proposes a covenant no lender sizing at 1.30× would grant and ignores that the lock-up also fails; D confuses the funding total with its risk allocation.

MCQ 9.1-C [9.1.1 · Analysis] A sponsor's equity IRR on Kestrel is 10.6696 % without an equity bridge. An EBL is offered at exactly 10.6696 %, interest capitalised over the two-year build. The effect on the reported equity IRR is:

- A. it rises, because the equity outflow is deferred
- B. it is unchanged: a bridge priced exactly at the equity IRR it defers is value-neutral ✓ CORRECT
- C. it falls, because the sponsor pays interest it would otherwise not have paid
- D. it rises by 94.61 basis points

Rationale: Deferring an outflow at exactly the rate at which that outflow discounts leaves the IRR identical — the indifference identity of 9.1.1, which the bisection confirms to the tested precision. A states the general direction of a cheap bridge but ignores its pricing; C confuses a cash cost with a rate effect, since the capitalised interest is exactly compensated by the deferral; D quotes the uplift computed at a 5.0 % bridge rate and applies it as though the bridge rate were irrelevant.

MCQ 9.1-D [9.1.2 · Analysis] A 6,000,000 shareholder loan at 12 % is drafted so that its interest ranks **above** CFADS rather than being paid from distributions. The consequence is:

- A. an additional tax shield of 144,000 a year and no other effect
- B. DSCR falls from 1.2743 to 1.1142, breaching both the 1.20× covenant and the 1.15× lock-up ✓ CORRECT
- C. the senior lenders are unaffected because the loan is subordinated in name
- D. the loan becomes senior debt for all purposes

Rationale: $6,384,000 / (5,009,635.23 + 720,000) = 1.1142$ (9.1.2). A is the shield without the ranking consequence; C mistakes a label for a waterfall position; D overstates — the ranking clause changes the coverage calculation without converting the instrument.

MCQ 9.1-E [9.1.2 · Evaluation] A sponsor's model carries the 144,000 annual tax shield on a 6,000,000 shareholder loan — 1,537,168 of present value, 25.62 % of the tranche — inside the base case that will be shown to lenders and to the investment committee. The soundest professional position is that the shield:

- A. belongs in the base case, because interest on a shareholder loan is deductible
- B. should be halved, as a prudent allowance for jurisdictional uncertainty
- C. should be excluded from the base case until a written tax opinion on this specific structure confirms deductibility, thin-capitalisation headroom and withholding treatment, and should then be disclosed as a documented upside rather than embedded in the cash flow ✓ CORRECT
- D. means the shareholder loan should be replaced with ordinary share capital

Rationale: A quarter of a tranche's face value created by a documentation choice is the most jurisdiction-dependent figure in this domain: thin-capitalisation limits, interest-deduction caps expressed as a share of EBITDA, transfer-pricing constraints on the rate and withholding tax on cross-border interest can each reduce it to nothing, so it is not an input until counsel says it is (9.1.2). A states one jurisdiction's treatment as though it were universal. B substitutes an arbitrary haircut for a determination that is obtainable and close to binary. D discards a legitimate instrument to avoid a question of evidence — and the instrument's real danger is the ranking clause, not the shield.

MCQ 9.1-F [9.1.3 · Comprehension] The build-up states r_f , $\beta_e \times ERP$, CRP and SP separately rather than quoting a single required return because:

- A. accounting standards require a disclosed decomposition of a discount rate
- B. only the risk-free rate is a judgment; the remaining terms are market data
- C. the components must be summed in that order for the total to be correct
- D. the cost of equity is constructed rather than observed, so separating the terms is what makes each judgment reviewable — and what allows the leverage term to be re-levered when gearing changes ✓ CORRECT

Rationale: k_e is not observed and never will be; stating the premiums separately is what turns an assertion into something a reviewer can challenge term by term, and the beta term is the one that must move with the structure or every structure comparison is invalid (9.1.3). A invents a reporting requirement. C confuses a sum with a sequence. B reverses the position — ERP , β_a , CRP and SP are all judgments, which is exactly why each needs a named, dated, owned source.

MCQ 9.1-G [9.1.4 · Evaluation] The sponsors argue for 75 % gearing on the exchange rate computed in 9.1.4: moving from 70 % to 75 % buys **48.82 basis points** of equity IRR for 8.50 points of $DSCR$, about **5.75 basis points of equity return per hundredth of coverage surrendered**, which they describe as the best-value structural trade available. The lenders size on a 1.30× target (41,171,123, 68.6185 % gearing, $WACC$ 8.0001 %); the 1.20× covenant binds at 44,602,050 (74.3367 % gearing, $WACC$ 7.9418 %). The soundest response is that the exchange-rate argument:

- A. is the right frame and stops applying at 74.34 %: above that gearing there is no coverage left to sell, and at 75 % the covenant fails on the base case, so the trade should be priced inside the feasible region and the recommendation made at the 68.62 % the sizing target permits ✓ CORRECT
- B. is correct and decisive — 5.75 basis points per hundredth is a favourable rate and the board should mandate 75 %
- C. is invalid, because coverage and equity return are not commensurable quantities
- D. should be resolved by mandating 74.34 %, the highest gearing the covenant permits

Rationale: At 75 % debt service of 5,367,466.32 requires $CFADS$ of **6,440,960** against 6,384,000 available — short by **56,960** before any stress — so the marginal rate is being quoted across a boundary at which the structure ceases to exist (9.1.4). B applies a valid marginal calculation outside its domain. C rejects the only honest way to argue a gearing: the exchange rate is exactly how the trade should be framed, and framing it is what reveals where it ends. D is the defensible weaker course — it satisfies the covenant arithmetically, with nil headroom, and lenders set a target above the covenant precisely so that a covenant is not a base-case condition; the constraint's price against the sponsors' proposal is **6.51 basis points** of $WACC$, which is what belongs in the paper.

■ SELF-CHECK — KA 9.1

1. When is an equity bridge accretive? — Only when its rate is below the equity IRR it defers; at equality the uplift is exactly zero.
2. Why must k_e be re-levered before any structure comparison? — Because the leverage term is the largest component of k_e (10.32 of Kestrel's 15.42 points); holding it constant across gearings compares incomparable things.
3. State Kestrel's leverage exchange rate at the margin. — About 5.75 basis points of equity IRR per 0.01 of $DSCR$ surrendered, moving from 70 % to 75 %.

KNOWLEDGE AREA 9.2

Senior, subordinated and mezzanine debt; bonds

Topics: 9.2.1 the senior tranche and the after-tax cost of debt · 9.2.2 subordination and mezzanine · 9.2.3 the blended cost of a multi-tranche stack and the project [WACC](#) · 9.2.4 the capital-markets route.

9.2.1 The senior tranche and the after-tax cost of debt

Definition. Senior debt ranks first in the cash waterfall, holds the security package, sets the covenants, and is therefore the cheapest and largest tranche in almost every project financing. Its cost to the borrower has three layers: the **base rate** (a floating reference rate, or a fixed rate achieved by swapping), the **credit margin** (basis points over base, stepping up or down with project phase and sometimes with coverage), and **fees** — arrangement, commitment on undrawn amounts, agency, and any hedging cost. The headline rate is never the cost; 9.3 makes that point quantitatively.

The after-tax cost of debt is what enters [WACC](#), because interest is (in many but not all jurisdictions) deductible:

$$k_d(\text{after tax}) = k_d \times (1 - T)$$

For Kestrel: $6.00\% \times (1 - 0.20) = 4.80\%$. The shield is worth **504,000** in year one ($2,520,000 \times 20\%$) and declines with the interest profile, which matters because a project's amortising debt front-loads the shield — a level after-tax rate is a simplification, and where tax losses, carry-forwards or interest-limitation rules bite it is a material simplification that the model must handle explicitly (Domain 6, KA 6.2).

Three properties distinguish senior project debt from corporate borrowing: it is **drawn progressively** against certified construction spend, so commitment fees and interest during construction are real costs (Domain 14); it is **covenanted on cash** rather than on accounting measures (Domain 10, KA 10.4.1); and its **tenor is bounded by the concession or offtake term**, which is why Domain 10's sizing levers include tenor but not appetite.

9.2.2 Subordination and mezzanine

Definition. Subordinated debt ranks behind senior debt in the waterfall and in enforcement, and is compensated for that position with a materially higher return. **Mezzanine** describes instruments sitting between senior debt and ordinary equity: subordinated loans, high-yield notes, payment-in-kind instruments, and hybrids with equity participation (warrants, conversion rights, or a return that steps up if the project outperforms).

Mezzanine exists because there is a gap between what senior lenders will advance and what sponsors will fund with equity, and it is priced in that gap — above senior margins, below the equity return, at a level reflecting a genuine risk of total loss with no upside beyond the coupon. Two placements matter enormously and are routinely confused. **Project-level (SPV) mezzanine** sits inside the borrowing entity, so its debt service appears in the project's own coverage calculation; senior lenders normally prohibit it or confine it to a defined basket, precisely because it consumes the [CFADS](#) their covenant measures. **HoldCo mezzanine** sits above the SPV in the sponsors' holding company and is serviced from **distributions**: invisible to the SPV's [DSCR](#), which is why sponsors prefer it, but fully exposed to the distribution lock-up of Domain 10, KA 10.4.2 — the single most under-appreciated risk in the instrument, which Case study A quantifies.

9.2.3 The blended cost of a multi-tranche stack, and the project WACC

Definition. The weighted average cost of capital is the weighted mean of each tranche's cost, weighted by its share of total capital, with debt-like tranches taken **after tax**:

$$WACC = \sum (V_i / V) \times k_i \quad \text{with } k_i = k_i(\text{pre-tax}) \times (1 - T) \text{ for deductible tranches}$$

Two rules do all the damage when broken. **Weights are market or funding values of the capital actually deployed**, not book equity or authorised capital. And **only genuinely deductible costs are tax-adjusted** — equity never is, and mezzanine may or may not be, depending on the instrument and the jurisdiction.

WORKED EXAMPLE

Worked example 9.2.3 — three structures priced, and the reconciliation of Domain 4's 8 %.

1. **Setup.** Kestrel's 60,000,000 funded three ways. **A (base):** senior 42,000,000 at 6.00 %, equity 18,000,000. **B (mezzanine displacing senior):** senior 36,000,000 at 5.70 % — the margin tightens because 9,000,000 of junior capital now sits beneath it — mezzanine 9,000,000 at 11.50 % amortising over 15 years, equity 15,000,000. **C (mezzanine displacing equity):** senior 42,000,000 at 6.00 %, mezzanine 6,000,000 at 11.50 % over 15 years, equity 12,000,000. Tax 20.0 %; mezzanine interest assumed deductible (a jurisdictional assumption, flagged); k_e re-levered at each structure per 9.1.3 with all debt-like tranches counted as debt; $AF(0.057, 12) = 8.523470$, $AF(0.115, 15) = 6.996708$.
2. **Formula.** WACC as above; DSCR per Domain 10, KA 10.2.1, computed both on senior debt service alone and on total debt service; equity IRR from the residual stream.
3. **Substitution.** B: senior service $36,000,000 / 8.523470 = 4,223,631.91$; mezzanine $9,000,000 / 6.996708 = 1,286,319.25$; k_e at D/E = $45,000,000/15,000,000 = 3.0$ gives $\beta_e = 0.60 \times (1 + 0.80 \times 3.0) = 2.04$ and $k_e = 5.10 + 2.04 \times 6.00 = 17.34$ %; `WACC = $(36 \times 4.56$
4. $9 \times 9.20 + 15 \times 17.34) / 60`.$
5. **Result.**

	A — base 70/30	B — mezz displaces senior	C — mezz displaces equity
Senior	42,000,000 @ 6.00 %	36,000,000 @ 5.70 %	42,000,000 @ 6.00 %
Mezzanine	—	9,000,000 @ 11.50 %	6,000,000 @ 11.50 %
Equity	18,000,000	15,000,000	12,000,000
k_e (re-levered)	15.42 %	17.34 %	20.22 %
Senior debt service	5,009,635.23	4,223,631.91	5,009,635.23
Mezzanine service	—	1,286,319.25	857,546.17
DSCR — senior only	1.2743	1.5115	1.2743
DSCR — total service	1.2743	1.1586	1.0881
Equity IRR	12.5311 %	12.0824 %	12.7378 %
WACC	7.9860 %	8.4510 %	8.3240 %

1. **Interpretation. Mezzanine raises the blended cost in both directions** — by 46.50 basis points in B and 33.80 in C — and the reason is structural: mezzanine's after-tax cost of **9.20 %** sits far above senior's **4.80 %**, and the equity left underneath it is more levered and therefore dearer (17.34 % and 20.22 % against 15.42 %). Anyone selling mezzanine as a route to cheaper capital is selling arithmetic that does not exist. What it actually buys depends on **which tranche it displaces**. In B it displaces senior debt and buys the senior lenders comfort — **DSCR 1.5115** against 1.2743, inside the 1.30× target Domain 10's Case A could not reach — at the price of 46.50 basis points of **WACC** and 44.87 basis points of equity return, because 11.50 % money replaced 6.00 % money. In C it displaces equity and buys the sponsors 20.67 basis points of equity **IRR**, but total coverage collapses to **1.0881**, below any covenant in the facility, so C exists only if the mezzanine sits at HoldCo level and is invisible to the SPV test. **Mezzanine is bought for coverage relief or for equity uplift, never for a lower cost of capital, and the tranche it displaces decides which.**

Now the reconciliation this volume has owed since Domain 4. Substitute Kestrel's re-levering into the **WACC** definition and the whole ladder collapses to a straight line:

$$\begin{aligned} \text{WACC}(g) &= [F + \text{ERP} \times \beta_a] - g \times [F + \text{ERP} \times \beta_a \times T - k_d(1 - T)] \\ &= 8.70 \% - 1.02 \% \times g \quad \text{with } F = r_f + \text{CRP} + \text{SP} = 5.10 \% \end{aligned}$$

Every entry in the 9.1.4 table satisfies it exactly: 8.0880 at $g = 0.60$, 7.9860 at 0.70, 7.8840 at 0.80. The slope tells the real story. Its two parts are $F - k_d(1 - T) = 5.10 - 4.80 = 0.30$ and the tax-shield term $\text{ERP} \times \beta_a \times T = 3.60 \times 0.20 = 0.72$. **Because the non-systematic part of the equity build-up (5.10 %) barely exceeds the after-tax cost of senior debt (4.80 %), leverage buys the project almost nothing** — 1.02 basis points of **WACC** per point of gearing, most of it supplied by the tax shield. The benefit of gearing accrues to equity as return, not to the project as cheaper capital.

Now evaluate the line where the project is actually financeable. Domain 10 established that a 1.30× target caps senior debt at **41,171,123 — 68.6185 %** gearing, with equity of **18,828,877**. At that gearing β_e is **1.649565**, k_e is **14.9974 %**, and

$$\text{WACC} = 8.70 \% - 1.02 \% \times 0.686185 = 8.0001 \%$$

Domain 4's given 8.0 % was exactly right — and for a reason nobody had written down. It is not a policy round number: it is the project's own weighted average cost of capital at the maximum gearing its coverage requirement permits. The board's rate and the credit committee's ratio were describing the same structure from opposite sides of the table. Two consequences. The rate is right **only for that structure**: the actual 70/30 proposal prices at **7.9860 %**, raising the appraisal NPV from 16,179,360 to **16,244,525 (+65,164)** — a harmless difference, but only because it was checked. And the cost-minimising 80 % structure prices at **7.8840 %**, so the coverage constraint costs **11.61 basis points** of WACC. That is the honest price of bankability, and it is small — the best argument available for not fighting the coverage requirement.

Mezzanine raises the blended cost in both directions

Kestrel Water SPC: 60,000,000 of capital, four candidate structures, cash tax 20.0 %, cost of equity re-levered for each

Structure C reaches the highest equity return and the lowest coverage — 1.0881 is below every covenant in the facility



The tranche a junior instrument displaces decides what it buys

Fig 9.2.3 — Four capital structures, priced

9.2.4 The capital-markets route

Definition. Instead of a bank loan, a project may issue **bonds** — notes sold to institutional investors, publicly or by private placement, with or without a rating and with or without a third-party guarantee ("wrapped"). Three axes drive the choice. **Tenor:** insurers and pension funds matching long liabilities will hold 20- to 30-year paper that few banks will, and for a long concession that is decisive (9.3.3 quantifies why tenor beats rate). **Price and rating:** rated investment-grade paper can price below bank margins and sub-investment grade well above, and the rating process imposes disclosure and a published opinion on the project's credit — valuable or unwelcome depending on circumstances. **Negative arbitrage:** bonds are normally drawn in full at close while construction spends over years, so idle proceeds earn a deposit rate far below the coupon — a real cost that progressively-drawn bank debt does not incur.

WORKED EXAMPLE**Worked example 9.2.4 — the price of drawing early.**

1. **Setup.** Kestrel's 42,000,000 raised as a bond at a 6.0 % coupon, fully drawn at close, spent evenly over a two-year construction period so the average idle balance is half the issue. Deposit rate on idle proceeds **3.0 %**. Bank alternative: progressive drawdown with a **0.60 %** commitment fee on the average undrawn balance.
2. **Formula.** Negative arbitrage = average idle balance × (coupon – deposit rate) × years.
Commitment cost = average undrawn × fee rate × years.
3. **Substitution.** $21,000,000 \times (6.0 \% - 3.0 \%) \times 2$ against $21,000,000 \times 0.60 \% \times 2$.
4. **Result.** Negative arbitrage **1,260,000**; commitment fees **252,000**; the bank route is **1,008,000** cheaper on this dimension alone. Spread over the 12-year facility, the negative arbitrage is worth **35.78 basis points** a year on the 42,000,000.
5. **Interpretation.** Thirty-six basis points is the same order as the entire **WACC** benefit of twenty points of gearing (9.2.3), which puts the drawdown mechanism in its proper place: a first-order structuring decision, not an administrative detail. It also explains the standard market answer — a **bank facility during construction, refinanced into bonds at or after completion** — capturing progressive drawdown while the spend is uncertain and long institutional tenor once the risk profile has changed. That is not a compromise but the correct sequencing, and KA 9.4.4 prices it. Two asymmetries complete the comparison. **Flexibility:** a bank syndicate of six can approve a waiver in weeks (Domain 10, KA 10.4.3), while a dispersed bondholder base cannot easily be assembled at all — making bonds a poor choice where amendments are foreseeable. **Prepayment:** bonds typically carry make-whole or spends provisions capturing the lender's lost yield, so the refinancing gain computed in 9.4.4 may simply not be available.

AI in this KA

Where it earns its place. Normalising a dozen indicative term sheets — rate, tenor, amortisation profile, fee schedule, prepayment mechanics, covenant thresholds — into one comparable table is genuinely strong machine work and the foundation of Toolkit 9.T.2, as is generating the candidate structures whose arithmetic 9.2.3 tabulates.

Where it must not go. It must not decide the tax treatment of a tranche. Whether mezzanine interest is deductible, whether a shareholder loan survives thin-capitalisation rules and whether withholding applies are questions of law in a specific jurisdiction at a specific date, and a wrong answer moves **WACC** by hundreds of basis points while looking entirely plausible. Nor may it assert a market price: an indicative margin generated by a model is not a quote, and presenting one as though it were misrepresents to whoever relies on it.

Verification, concretely. Recompute one structure's **WACC** by hand and confirm the weights sum to one. Confirm every tax adjustment traces to a written opinion rather than a default. Confirm any all-in cost was solved from the actual stream rather than assembled by adding fees to a headline rate. And test the closed form: under the re-levering convention of 9.1.3 a **WACC** ladder that is not linear in gearing contains an error.

■ KEY TERMS — KA 9.2

Term	Meaning
$k_d(\text{after tax})$	$k_d \times (1 - T)$; the debt cost that enters WACC.
WACC	$\Sigma(\text{tranche share} \times \text{tranche cost})$, debt-like tranches after tax.
Mezzanine	Capital between senior debt and ordinary equity; priced in the gap, never cheap.
SPV vs HoldCo mezzanine	Inside the borrower and visible to DSCR, versus above it and exposed to lock-up.
Negative arbitrage	Cost of holding fully drawn bond proceeds at deposit rates below the coupon.
Wrapped bond	Notes credit-enhanced by a third-party guarantor.
Make-whole / spens	Prepayment compensation that can eliminate a refinancing gain.

■ SAMPLE MCQS — KA 9.2

MCQ 9.2-A [9.2.3 · Application] A 150,000,000 project is funded with senior 80,000,000 at 5.2 %, mezzanine 20,000,000 at 10.8 % (both deductible) and equity 50,000,000 at 14.5 %; tax 30 %. The WACC is:

- A. 7.7827 % ☒ **CORRECT**
- B. 9.0467 %
- C. 8.5667 %
- D. 6.3327 %

Rationale: $(80 \times 3.64 + 20 \times 7.56 + 50 \times 14.5)/150 = 7.7827 \%$. B omits the tax shield on both debt tranches; C takes a simple average of the three costs, ignoring the weights; D tax-adjusts the **equity** cost as well, which no jurisdiction permits.

MCQ 9.2-B [9.2.3 · Analysis] Adding 9,000,000 of 11.50 % mezzanine in place of senior debt raises Kestrel's senior-only DSCR from 1.2743 to 1.5115 and its WACC from 7.9860 % to 8.4510 %. The correct reading is:

- A. the structure is superior because coverage improved
- B. the structure is inferior because WACC rose
- C. mezzanine bought 23.72 points of senior coverage for 46.50 basis points of WACC and 44.87 basis points of equity IRR; whether that is worth paying depends on whether the senior tranche is otherwise unavailable ☒ **CORRECT**
- D. WACC and DSCR cannot both be affected by one tranche

Rationale: Both faces move and the decision is the exchange rate between them (9.2.3). A and B each optimise one number in isolation — the specific error this domain exists to prevent; D is simply false, since the mezzanine changes both the weighted cost and the debt service.

MCQ 9.2-C [9.2.4 · Application] A 42,000,000 bond at a 6.0 % coupon is drawn in full at close and spent evenly over two years; idle proceeds earn 3.0 %. The negative arbitrage is:

- A. USD 2,520,000
- B. USD 1,260,000 ☒ **CORRECT**
- C. USD 630,000
- D. nil, because the proceeds are invested

Rationale: Average idle balance $21,000,000 \times 3.0\% \text{ spread} \times 2 \text{ years} = 1,260,000$. A applies the spread to the **full** 42,000,000 for two years, ignoring the drawdown profile; C covers one year only; D confuses earning a return with earning enough of one.

MCQ 9.2-D [9.2.2 · Analysis] Why do senior lenders usually prohibit mezzanine debt at SPV level while tolerating it at HoldCo level?

- A. HoldCo debt is cheaper
- B. SPV mezzanine consumes the **CFADS** their covenant measures, while HoldCo mezzanine is serviced from distributions that already rank behind every senior test ✓ **CORRECT**
- C. HoldCo debt carries no security
- D. accounting standards require it

Rationale: The placement determines whether the junior service appears in the coverage calculation (9.2.2). A is not generally true — HoldCo debt is usually dearer, being further from the cash; C is incidental; D confuses drafting practice with reporting requirements.

MCQ 9.2-E [9.2.3 · Evaluation] A board paper discounts Kestrel's cash flows at 7.8840 % — the **WACC** of the 80 % gearing structure — on the ground that it is the lowest cost of capital available to the project. The soundest position is that the appraisal should use:

- A. 7.8840 %, because minimising **WACC** is the objective of a capital-structure decision
- B. the sponsors' corporate **WACC**, since it is the sponsors' shareholders who set the hurdle
- C. the **WACC** of a structure the project can actually raise — 8.0001 % at the coverage-binding gearing — quoted together with the structure it belongs to ✓ **CORRECT**
- D. any rate between 7.8840 % and 8.0001 %, since the whole range is 11.61 basis points

Rationale: A cost of capital is a property of one specific structure, and the 80 % structure fails the 1.20× covenant on the base case, so its rate prices a financing that does not exist; the coverage constraint costs 11.61 basis points of **WACC**, and that is the honest price of bankability (9.1.4, 9.2.3). A imports the corporate-finance objective into a constrained problem. B discounts a single ring-fenced asset at a parent's blended risk. D is right about materiality and wrong about discipline: the difference is small only because someone checked it, and an unlabelled rate is reused in places where the difference is not small.

MCQ 9.2-F [9.2.4 · Evaluation] The board is attracted by a 20-year project bond at close: it matches institutional appetite to a 25-year asset and removes the refinancing question. Drawn in full at close against a two-year construction spend, the bond incurs **1,260,000** of negative arbitrage — **35.78 basis points** a year on 42,000,000, levelised over the facility — against **252,000** of commitment fees on a progressively drawn bank facility, and it would carry make-whole prepayment protection. The soundest recommendation is:

- A. issue the bond: 35.78 basis points of negative arbitrage is a modest price for twenty years of committed tenor
- B. bank facility only: bonds are inappropriate for project financings because amendments are impracticable across a dispersed holder base
- C. issue the bond and negotiate a delayed-draw structure, which removes the negative arbitrage
- D. bank facility during construction, refinanced into bonds at or after completion — capturing progressive drawdown while the spend is uncertain and institutional tenor once the risk profile has changed; and the bond's make-whole terms must be settled at that point, since they can eliminate the refinancing gain the sequencing exists to capture ✓ **CORRECT**

Rationale: The two instruments are strong in different phases, so the answer is sequencing rather than selection — and 1,008,000 of avoidable cost on this dimension alone is the same order as the entire [WACC](#) benefit of twenty points of gearing (9.2.4). A treats a first-order structuring decision as an administrative detail. C is the defensible weaker course: a delayed-draw or forward-purchase structure does address negative arbitrage, at a commitment cost of its own, and it leaves the amendment inflexibility of a bond in place through the phase in which amendments are most likely. B promotes one true asymmetry into a prohibition and forgoes the tenor that makes a long concession financeable.

■ SELF-CHECK — KA 9.2

1. State the closed form for Kestrel's [WACC](#) and what its slope means. — $WACC(g) = 8.70\% - 1.02\% \times g$; the slope is small because the non-systematic equity premium (5.10 %) barely exceeds after-tax senior debt (4.80 %), so gearing transfers return to equity rather than cheapening the project.
2. What is the project [WACC](#) at the coverage-binding gearing, and why does it matter? — **8.0001 %** at 68.6185 % gearing: it is Domain 4's given rate, derived.
3. What does mezzanine buy? — Coverage relief or equity uplift, depending on the tranche it displaces; never a lower cost of capital.

KNOWLEDGE AREA 9.3

Islamic finance concepts, export credit and development finance

Topics: 9.3.1 Islamic finance structures in economic terms · 9.3.2 export credit · 9.3.3 development finance · 9.3.4 assembling a multi-source stack.

9.3.1 Islamic finance structures in economic terms

Scope statement, and it binds. This topic describes, in economic and cash-flow terms, structures used in Islamic finance markets, because a project finance leader must be able to price them, model them and compare them. Whether any particular structure is compliant with Shariah is a determination for the relevant Shariah supervisory board, guided by the standards of bodies such as the Accounting and Auditing Organisation for Islamic Financial Institutions; **it is outside the scope of this book, and nothing here expresses, implies or substitutes for any religious or legal ruling.**

The structures share one economic feature: the financier's return arises from a transaction in an asset — a sale, a lease, a partnership, an agency — rather than from lending money at interest. The principal forms encountered in project financing:

Structure	Economic mechanics	Typical project use
Istisna'a	Commissioned manufacture or construction: the financier procures the asset to specification and takes delivery risk during the build	The construction-period facility
Ijara	Lease of a completed asset; the lessee pays rentals comprising a capital and a return element; ownership sits with the lessor	The operating-period facility
Ijara mawsufah fi al-dhimmah (forward lease)	Rentals commence on a described future asset, bridging construction to operation	The standard istisna'a-to-ijara conversion
Murabaha	Cost-plus sale with deferred payment; the mark-up is agreed and fixed at inception	Working capital, procurement of specific inputs
Wakala	Agency: the financier appoints an agent to invest funds for an expected return	Portfolio and liquidity tranches
Sukuk	Certificates representing undivided beneficial ownership in an asset, usufruct or business, with returns generated by that asset	The capital-markets tranche, often alongside a bank ijara

Three consequences a leader must handle. **The asset must exist and be identifiable**, which constrains what can be financed and makes security and title arrangements materially different from a conventional mortgage-and-charge package. **Ownership carries obligations** — a lessor's responsibility for major maintenance and insurance in an ijara is usually passed back to the lessee through a service agency agreement, and the drafting of that pass-back is where economic equivalence is achieved or lost. And **intercreditor arrangements between Islamic and conventional tranches are the hardest documentation in the deal**, because both must share security and enforcement proceeds on a genuinely equal footing without either being subordinated in substance.

WORKED EXAMPLE**Worked example 9.3.1 — comparing an ijara tranche with a conventional tranche, properly.**

1. **Setup.** Kestrel's 42,000,000 is to be raised half conventionally and half through an ijara tranche, each **21,000,000 over 12 years**. The conventional tranche carries **6.00 %** with a **1.20 %** arrangement fee deducted from proceeds. The ijara carries a **6.15 %** profit rate with a **0.60 %** structuring fee. The sponsor's question is which is dearer.
2. **Formula.** The only defensible comparison is the **all-in effective cost**: the rate r solving $\text{net proceeds} = \text{periodic payment} \times AF(r, n)$. Headline rates and fees cannot be added.
3. **Substitution.** Conventional: payment $21,000,000 / 8.383844 = 2,504,817.62$; fee $21,000,000 \times 1.20 \% = 252,000$; net proceeds **20,748,000**; solve $20,748,000 = 2,504,817.62 \times AF(r, 12)$. Ijara: $AF(0.0615, 12) = 8.315327$; rental $21,000,000 / 8.315327 = 2,525,456.84$; fee **126,000**; net proceeds **20,874,000**; solve likewise.
4. **Result.** Conventional all-in **6.2209 %**; ijara all-in **6.2604 %**. The ijara is dearer by **3.95 basis points** — not by the 15 basis points the headline rates suggest. Annual payments differ by **20,639.22**, worth **173,036** in present value at 6 % over the twelve years.
5. **Interpretation.** The headline gap of 15 basis points shrank to 4 once the lower structuring fee was counted, and that reversal is the whole lesson: **a tranche is compared on the effective rate solved from its own cash-flow stream, never on its stated rate plus its fees**. Four basis points on 21,000,000 is 173,036 of present value — real money, but small enough that it should not decide the question. What should decide it is what the arithmetic cannot show: whether the ijara tranche reaches **investors the conventional tranche cannot**, widening the pool and reducing concentration risk; whether the extra documentation and intercreditor complexity are worth **173,036**; and whether the service-agency pass-back leaves the SPV with a residual ownership obligation the model has not priced. A leader who compares only the rates decides on the wrong axis in either direction.

9.3.2 Export credit

Definition. An export credit agency (ECA) is a state-backed institution that supports its country's exporters by guaranteeing, insuring or directly lending against the purchase of that country's goods and services. The effect for a project is a tranche whose credit risk is largely sovereign rather than commercial, producing a lower margin and a longer tenor than the commercial market would offer — in exchange for three conditions. **Sourcing (content) requirements** tie support to eligible goods and services from the supporting country, usually as a minimum share of contract value; this constrains procurement, and Case study B prices what that constraint can cost. **An exposure premium** reflecting buyer-country risk and tenor is charged, commonly **capitalised into the loan**, so it does not reduce cash proceeds but increases the amount repaid — precisely the structure that makes headline-rate comparison worthless. And participating agencies operate within the **OECD Arrangement on Officially Supported Export Credits**, an inter-governmental understanding constraining minimum premium rates, maximum repayment terms, starting points and local-content treatment; its terms are revised periodically and vary by sector, so they must be checked as at the transaction date rather than assumed.

WORKED EXAMPLE**Worked example 9.3.2 — the true cost of a cheap ECA tranche.**

1. **Setup.** 15,000,000 of eligible equipment is financed by an ECA-supported tranche at **3.80 %** over **14 years**, with an exposure premium of **6.0 %** of the tranche **capitalised** into the loan. The commercial comparator is 15,000,000 at **6.00 %** over 12 years.
2. **Formula.** All-in cost is the rate solving $\text{cash proceeds} = \text{instalment} \times AF(r, n)$, where the instalment is computed on the **grossed-up** loan and the proceeds are the amount actually available to the project.
3. **Substitution.** Premium $15,000,000 \times 6.0 \% = 900,000$; loan **15,900,000**; $AF(0.038, 14) = 10.703972$; instalment $15,900,000 / 10.703972 = 1,485,429.84$; solve $15,000,000 = 1,485,429.84 \times AF(r, 14)$.
4. **Result.** All-in cost **4.6895 %** — **88.95 basis points** above the 3.80 % headline, and still **131 basis points** below the commercial alternative. Annual debt service falls from $15,000,000 / 8.383844 = 1,789,155.44$ to **1,485,429.84**, a saving of **303,725.60** a year.
5. **Interpretation.** Both halves of that result matter and they are usually conflated. The **cost** advantage is 131 basis points, which is genuine but not transformational. The **coverage** advantage is 303,726 of annual debt service released, and that is decisive: substituting the ECA tranche for 15,000,000 of Kestrel's commercial senior debt leaves total debt service of $27,000,000/8.383844 + 1,485,429.84 = 3,220,479.79 + 1,485,429.84 = \mathbf{4,705,909.63}$, so DSCR rises from **1.2743** to **1.3566** — **8.23 points**, straight through the 1.30× sizing target the all-commercial structure could not reach. The two effects have different causes — the cost advantage from the sovereign-backed margin, the coverage advantage mostly from the **two extra years of tenor** — and separating them is the discipline of 9.3.3. The cautions are procedural and expensive when missed: ECA processes run to their own timetable and can add months to financial close; documentation is agency-specific and in places non-negotiable; and the eligible-content test is verified against invoices after the fact, so a procurement change during construction can retrospectively disqualify a tranche.

9.3.3 Development finance

Definition. Development finance institutions (DFIs) — multilateral and bilateral development banks and their private-sector arms — lend and invest to advance development objectives, contributing what commercial lenders often cannot: **tenor** well beyond the bank market, **availability** through periods when commercial appetite has withdrawn, political-risk comfort that can reduce other lenders' margins, and structures such as an A/B loan in which the institution is lender of record and commercial banks take participations behind its umbrella.

The price is **conditionality**: environmental and social performance requirements — the IFC Performance Standards and the Equator Principles are the frameworks most commonly referenced by lenders in this market — together with procurement, disclosure, integrity and reporting obligations. Meeting them costs money and time, and that cost belongs in the tranche's economics rather than in an overhead line where nobody sees it.

WORKED EXAMPLE**Worked example 9.3.3 — separating the cost effect from the capacity effect.**

1. **Setup.** A DFI offers **12,000,000** at **5.25 %** over **18 years**, with a **1.00 %** front-end fee, an incremental environmental and social advisory cost of **350,000** at close, and **120,000** a year of monitoring and reporting cost through the loan life.
2. **Formula.** All-in economic cost solves $\text{net proceeds} = (\text{instalment} + \text{annual compliance cost}) \times \text{AF}(r, n)$. Debt capacity is Domain 10's $\text{max debt} = (\text{CFADS} \div \text{target DSCR}) \times \text{AF}(r, n)$, computed on the **contractual** rate and tenor.
3. **Substitution.** $\text{AF}(0.0525, 18) = 11.464588$; $\text{instalment } 12,000,000 / 11.464588 = 1,046,701.34$; $\text{net proceeds } 12,000,000 - 120,000 - 350,000 = 11,530,000$; $\text{annual outflow } 1,046,701.34 + 120,000 = 1,166,701.34$; solve for r . Capacity: $6,384,000 / 1.30 = 4,910,769.23$, then $\times 11.464588$ against $\times 8.383844$.
4. **Result.** All-in economic cost **7.2465 %** — **199.65 basis points** above the 5.25 % headline, and **125 basis points above the commercial 6.00 %**. Yet on the contractual terms, debt capacity at a 1.30× target rises from Domain 10's **41,171,123** to **56,299,948**, an uplift of **15,128,825**; and Kestrel's existing 41,171,123 of debt, repaid over 18 years at 5.25 %, would carry debt service of only **3,591,155.80** and a **DSCR** of **1.7777**.
5. **Interpretation.** This is the domain's most counter-intuitive result and it must not be collapsed into one verdict. On **cost** the DFI tranche is expensive: the headline 5.25 % is a fiction once the front-end fee, the advisory spend and 120,000 a year of monitoring are counted, and at 7.2465 % it is dearer than the commercial market. On **capacity** it is transformational: six extra years of tenor support **36.7 % more debt** at the same coverage, more than any plausible margin negotiation could deliver. **Tenor beats rate**, because coverage is the binding constraint and tenor is the lever that moves it most — Domain 10, KA 10.1.2 lists four levers, and this is the arithmetic showing which one pays. Three cautions. The compliance cost is **not** waste: it buys an environmental and social management system a well-run project would want anyway, and other lenders price the comfort it provides, so charging all of it against the DFI tranche overstates its cost. The monitoring obligation runs for the full 18 years and must be budgeted for 18 years, not three. And DFI processes are slow: putting a DFI tranche on the critical path to financial close without allowing for that creates a schedule risk Domain 8's arithmetic prices at hundreds of thousands a month.

9.3.4 Assembling a multi-source stack

Combining commercial banks, an ECA, a DFI and an Islamic tranche in one financing is ordinary in large infrastructure, and it creates a documentation problem often larger than the financing problem. Four recurring issues. **Common terms:** one common terms agreement carries the representations, covenants, events of default and the definition of **CFADS**, each facility agreement then carrying only its own commercial terms — without it, coverage is tested on different definitions by different lenders, the defect Domain 10, KA 10.1.1 warns against, multiplied by the number of tranches. **Intercreditor:** voting thresholds, instructing-group mechanics, sharing of enforcement proceeds and which decisions require unanimity; a tranche holding a blocking position it did not pay for is a structural defect visible only in a workout. **Availability and drawdown order:** tranches whose conditions precedent mature at different times cannot be drawn pro rata, and whichever is drawn first bears the most construction risk and prices accordingly. **Currency:** a tranche in a currency other than the revenue currency introduces an exposure that must be hedged or accepted, and the cheapest tranche is frequently the one that creates it — a project with local-currency

availability payments and a hard-currency ECA tranche has borrowed a devaluation risk in exchange for a margin saving. The natural hedge, borrowing in the currency of revenue, is worth paying for and its price is exactly that margin difference (Domain 3, KA 3.3.3; Domain 11, KA 11.3).

AI in this KA

Where it earns its place. Normalising heterogeneous tranche offers onto a common all-in basis is arithmetic with many steps and one method, and it is where analysts most often err under time pressure. Solving effective rates across a dozen structures, and re-solving when a fee schedule changes, should be automated — with the method (solve from the cash-flow stream) fixed in the tool rather than left to the user.

Where it must not go. It must not opine on Shariah compliance: that belongs to the relevant supervisory board and to no model. It must not assert current ECA premium rates, maximum tenors or content thresholds from memory — those come from a periodically revised inter-governmental framework, and a stale figure presented confidently is worse than no figure. And it must not draft or interpret intercreditor mechanics, where a misread voting threshold shows up only in a default.

Verification, concretely. For each tranche, confirm the all-in cost was solved from the stream and that the proceeds figure excludes capitalised premiums and deducted fees. Confirm the compliance-cost assumption runs for the full tenor. Confirm any framework constraint cited was checked against the current published text at a stated date by a named person. And keep cost and capacity in separate columns — a model reporting one number per tranche has already lost the 9.3.3 distinction.

■ KEY TERMS — KA 9.3

Term	Meaning
Istisna'a / ijara / forward lease	Commissioned-construction, lease, and described-future-asset lease structures used in Islamic finance markets.
Murabaha / wakala / sukuk	Cost-plus deferred sale; agency investment; certificates of undivided beneficial ownership.
All-in effective cost	The rate solving $\text{net proceeds} = \text{payment} \times AF(r, n)$; the only valid basis for tranche comparison.
ECA / exposure premium	State-backed export-credit support; the risk premium it charges, usually capitalised.
Content requirement	Minimum share of contract value sourced from the supporting country.
DFI conditionality	Environmental, social, procurement and reporting obligations attached to development finance.
Common terms agreement	One document carrying shared covenants and definitions across all tranches.
Natural hedge	Borrowing in the currency of revenue; its price is the margin forgone.

■ SAMPLE MCQS — KA 9.3

MCQ 9.3-A [9.3.2 · Application] A 40,000,000 tranche carries 4.10 % over 12 years with a 5.5 % exposure premium capitalised into the loan. The all-in cost on the 40,000,000 of proceeds is closest to:

A. 4.10 %

B. 5.0378 % ☒ **CORRECT**

- C. 4.5583 %
- D. 9.60 %

Rationale: Loan 42,200,000; $AF(0.041, 12) = 9.330854$; instalment 4,522,630.17; solve $40,000,000 = 4,522,630.17 \times AF(r, 12) \rightarrow 5.0378 \%$. A ignores the premium entirely; C spreads the premium straight-line over the tenor and adds it to the rate ($4.10 + 5.5/12$), which understates because it ignores that the premium is also financed; D adds the premium to the rate as though it were annual.

MCQ 9.3-B [9.3.3 · Analysis] A DFI tranche at 5.25 % over 18 years has an all-in economic cost of 7.2465 % against a commercial market at 6.00 % over 12 years. The soundest conclusion is:

- A. reject the DFI tranche — it is more expensive
- B. accept it — the headline rate is lower
- C. the cost comparison favours the commercial market by about 125 basis points, while the six extra years of tenor raise debt capacity at a 1.30× target from 41,171,123 to 56,299,948; the decision turns on whether coverage or cost is the binding constraint ✓ CORRECT
- D. the two are equivalent because tenor and rate offset

Rationale: Cost and capacity are different effects with different causes (9.3.3). A optimises cost while ignoring the constraint that actually binds; B is the headline-rate error the worked example exists to destroy; D asserts an offset without computing either side.

MCQ 9.3-C [9.3.1 · Application] A conventional tranche of 21,000,000 at 6.00 % over 12 years carries a 1.20 % fee; an ijara tranche of the same size and tenor carries a 6.15 % profit rate and a 0.60 % fee. The difference in all-in cost is closest to:

- A. 15 basis points in favour of the conventional tranche
- B. 4 basis points in favour of the conventional tranche ✓ CORRECT
- C. 60 basis points in favour of the ijara tranche
- D. nil, since the structures are economically identical

Rationale: All-in 6.2209 % against 6.2604 % — **3.95 basis points** (9.3.1). A is the headline difference before fees; C confuses the fee saving with a rate advantage; D asserts an equivalence the arithmetic disproves, small though the gap is.

MCQ 9.3-D [9.3.4 · Recall] The primary purpose of a common terms agreement in a multi-source financing is to:

- A. reduce legal fees
- B. ensure every tranche tests coverage on the same definitions and shares one covenant and default architecture ✓ CORRECT
- C. give the DFI a veto
- D. permit tranches to be drawn in any order

Rationale: One set of shared definitions and covenants prevents the same project being measured differently by different lenders (9.3.4). A is a by-product; C describes an intercreditor outcome to be negotiated, not the purpose; D is a drawdown question the agreement constrains rather than liberates.

MCQ 9.3-E [9.3.3 · Evaluation] A funding paper describes a 12,000,000 DFI tranche as "5.25 %, the cheapest money in the structure". Its all-in economic cost, once a 1.00 % front-end fee, 350,000

of advisory spend at close and 120,000 a year of monitoring across an 18-year tenor are counted, is 7.2465 %. The soundest way to report the tranche is:

- A. at 7.2465 % and, in a separate column, the capacity effect — six extra years of tenor lifting debt capacity at a 1.30× target from 41,171,123 to 56,299,948 — with a statement of which compliance costs the project would have incurred in any event ✓ **CORRECT**
- B. at 5.25 %, which is the contractual rate the facility agreement will carry
- C. as rejected, because 7.2465 % exceeds the commercial market's 6.00 %
- D. as one net figure combining the cost penalty and the capacity benefit

Rationale: Cost and capacity are different effects with different causes and belong in separate columns; charging the whole of an environmental and social management system against the tranche also overstates its cost, because a well-run project wants the system and other lenders price the comfort it provides (9.3.3). B repeats the headline the worked example exists to destroy. C optimises cost while ignoring that coverage is the binding constraint. D collapses two decisions into one number and conceals which of them is driving it.

MCQ 9.3-F [9.3.1 · Comprehension] In economic terms, an istisna'a facility differs from an ijara facility in that:

- A. istisna'a is a lease and ijara a cost-plus sale with deferred payment
- B. istisna'a finances commissioned construction, the financier procuring the asset to specification and holding delivery risk during the build, while ijara is a lease of a completed asset whose rentals comprise a capital and a return element ✓ **CORRECT**
- C. they differ only in name, both being loans at interest under another label
- D. istisna'a funds working capital and ijara funds procurement of specific inputs

Rationale: The two structures cover the two phases of a project's life, which is why the istisna'a-to-ijara conversion — commonly through a forward lease — is the standard project shape (9.3.1). A inverts them. C denies the asset-based mechanics that determine title, security and the lessor's ownership obligations, which is where economic equivalence with conventional debt is achieved or lost. D describes murabaha and wakala uses. Whether any structure is compliant with Shariah is a determination for the relevant supervisory board and is outside this book's scope.

MCQ 9.3-G [9.3.4 · Evaluation] A project whose availability payments are denominated in the host currency is offered two ways to fund the same 15,000,000: a hard-currency export-credit tranche at a materially lower margin and longer tenor, or a local-currency commercial tranche at the market margin. The structuring team recommends the export-credit tranche on the strength of its all-in cost and tenor. The soundest recommendation is:

- A. accept the recommendation: the all-in cost and the capacity effect both favour the export-credit tranche, and cost and capacity are the two tests this Knowledge Area sets
- B. accept it and rely on the local cost base as a natural hedge, since local costs fall in hard-currency terms as the currency weakens
- C. reject the export-credit tranche: a currency mismatch is unmanageable at any margin
- D. price the exposure before choosing, and on these facts take the local-currency tranche and pay the margin — unless the tariff can be exchange-rate-indexed, in which case the export-credit tranche is the better answer: borrowing in the currency of revenue is the natural hedge, and its price is exactly the margin forgone ✓ **CORRECT**

Rationale: The cheapest tranche is frequently the one that creates the exposure, and a margin saving bought with an unhedged devaluation risk is not a saving (9.3.4). A applies the right two tests to the wrong currency and recommends on cost and tenor alone. C reaches the same instruction as the key

for the wrong reason and is the closest rival: it is defensible in a market where long tenors genuinely cannot be hedged, but it forecloses the indexation remedy — Domain 11 (KA 11.3.2) shows an exchange-rate-indexed tariff share lifting the tolerable devaluation from 5.06 % to 37.17 %, which makes the tranche usable and makes the choice a priced one rather than a prohibition. B is the seductive error: local costs do provide a partial offset, and it is far too small, because debt service and hard-currency operating costs do not devalue at all — on Kestrel's numbers a **5.06 %** movement breaches the covenant even with the whole local cost base offsetting.

MCQ 9.3-H [9.3.2 · Comprehension] An export credit agency's exposure premium is described as "capitalised into the loan". In cash-flow terms that means:

- A. the premium is added to the amount borrowed, so cash proceeds are unchanged while the sum repaid rises — which is why the headline rate understates the cost and only the rate solved from proceeds against instalments measures it ✓ CORRECT
- B. the premium is deducted from the amount advanced, so proceeds fall and repayments are unchanged
- C. the premium is treated as a capital cost of the project and depreciated
- D. the premium is waived in exchange for a higher margin

Rationale: Capitalisation grosses the loan up: 15,000,000 of eligible equipment financed with a 6.0 % premium becomes a 15,900,000 loan against 15,000,000 of proceeds, and the all-in cost is **4.6895 %** against a 3.80 % headline — **88.95 basis points** the ranking would otherwise miss (9.3.2). B describes a deducted arrangement fee, which reduces proceeds instead. C is an accounting treatment, not a cash-flow mechanic, and it does not change what is repaid. D describes a different bargain altogether.

■ SELF-CHECK — KA 9.3

1. How is a tranche's cost compared, and why not by rate plus fees? — By solving the effective rate from its own cash-flow stream; fees, capitalised premiums and tenor interact and cannot be added.
2. State the two distinct effects of a longer-tenor tranche. — A cost effect (usually adverse once fees and conditionality are counted) and a capacity effect (36.7 % more debt at the same coverage, in the 9.3.3 case) — reported separately.
3. What does this book decline to determine about Islamic finance structures? — Their compliance with Shariah, which rests with the relevant supervisory board; the book describes only economics and cash flows.

KNOWLEDGE AREA 9.4

Government support, grants, sustainable finance and refinancing

Topics: 9.4.1 forms of government support · 9.4.2 grants and concessional tranches · 9.4.3 green and sustainability-linked finance · 9.4.4 refinancing.

9.4.1 Forms of government support

Definition. Government support is any intervention that improves a project's financeability without the grantor becoming an ordinary equity investor. Every form transfers value, and every form has a fiscal price — either cash now or a contingent liability later — which is why the discipline of this topic is to name the price alongside the benefit.

Form	What it does for the project	What it costs the grantor
Capital grant / viability gap funding	Reduces the amount to be financed	Cash, at the point of greatest budget pressure
Availability or capacity payment	Removes demand risk from the revenue line (Domain 7)	A long-dated committed expenditure line
Minimum revenue guarantee	Caps downside on a demand-based revenue	A contingent liability, valued as an option
Sovereign or agency guarantee of debt	Converts project credit into sovereign credit	Full contingent exposure to the debt
Concessional or subordinated public loan	Fills the gap between senior debt and equity cheaply	The margin forgone, plus subordination risk
Tax incentives, allowances, exemptions	Raises CFADS by reducing cash tax	Forgone revenue, often unbudgeted and unmeasured
Land, permits, connections in kind	Reduces development cost and timeline	Opportunity cost of the asset, rarely quantified

Two professional points cut across the table. **A guarantee is not free because no cash moves** — it is a written option whose value can be estimated, and a grantor that does not estimate it is accumulating unmeasured liabilities. And **support that improves coverage is worth more to a project than support of equal value that improves return**, because coverage is the binding constraint (9.1.4). A grantor seeking maximum financeability per unit of fiscal cost should therefore direct support at the coverage face — which is exactly what 9.4.2 quantifies.

9.4.2 Grants and concessional tranches

WORKED EXAMPLE

Worked example 9.4.2 — one grant, two structures, two entirely different projects.

- Setup.** A **6,000,000** capital grant (10 % of capex) is awarded to Kestrel. The funding plan must place it. **Case G1:** the grant **displaces equity** — senior stays at 42,000,000, equity falls to 12,000,000. **Case G2:** the grant **displaces senior debt** — senior falls to 36,000,000, equity stays at 18,000,000. In both, the grant is treated as zero-cost capital that absorbs risk alongside equity, so β_e is re-levered on debt against equity **plus grant**.
- Formula.** $WACC = \Sigma(\text{share} \times \text{cost})$ with the grant at zero cost; **DSCR** per Domain 10; equity **IRR** from the residual stream.
- Substitution.** G1: $WACC = (42 \times 4.80 + 12 \times 15.42 + 6 \times 0)/60$; **DSCR** unchanged; equity stream $(-12,000,000; 1,374,364.77 \times 12; 6,384,000 \times 13)$. G2: senior service $36,000,000 / 8.383844 = 4,293,973.06$; $\beta_e = 0.60 \times (1 + 0.80 \times 36/24) = 1.32$ so $k_e = 13.02\%$; $WACC = (36 \times 4.80 + 18 \times 13.02)/60$; equity stream $(-18,000,000; 2,090,026.94 \times 12; 6,384,000 \times 13)$.
- Result.**

	Base (no grant)	G1 — grant displaces equity	G2 — grant displaces debt
Senior debt	42,000,000	42,000,000	36,000,000
Equity	18,000,000	12,000,000	18,000,000
k_e	15.42 %	15.42 %	13.02 %
WACC	7.9860 %	6.4440 %	6.7860 %
DSCR	1.2743	1.2743	1.4867
Equity IRR	12.5311 %	16.8231 %	14.9940 %

1. **Interpretation.** The same 6,000,000 produces two different projects, and the difference is the allocation question every grant negotiation is really about. **G1 is the sponsors' case:** equity return jumps **429.20 basis points**, from 12.5311 % to 16.8231 % — clearing the 15.42 % cost of equity for the first time on the flat-CFADS basis, without a single change to the project — while lenders gain **nothing**, because DSCR is untouched at 1.2743. **G2 is the lenders' case:** coverage rises **21.24 points** to 1.4867, comfortably above the 1.30× sizing target that Domain 10's Case A could not reach, while equity gains 246.29 basis points rather than 429.20. A grantor who does not specify which face the grant is intended to strengthen has funded whichever the sponsors preferred, and the answer will be G1. The tie-break should follow the public purpose: if the objective is **financeability** — getting a project financed that otherwise could not be — the grant must reduce debt (G2), because coverage is the binding constraint; if the objective is **attracting private capital to a thin sector**, raising equity returns (G1) is defensible, and should be said out loud. **The treatment caution is as large as the allocation question.** The re-levering convention above places the grant in the risk-bearing base with equity. Treat it instead as outside that base — so D/E in G1 becomes $42/12 = 3.5$, $\beta_e = 2.28$ and $k_e = 18.78\%$ — and G1's WACC rises from 6.4440 % to **7.1160 %**, a difference of **67.20 basis points** on identical cash flows. Both treatments are defensible; only one can be used; and it must be documented before the numbers are quoted, because 67 basis points is more than the entire WACC effect of twenty points of gearing.

Concessional tranches and the grant element. Support often arrives as cheap debt rather than cash, and its subsidy content can be measured precisely. Take **12,000,000 at 2.0 % over 25 years with 7 years' grace** (interest-only, then level amortisation), against a **6.0 %** market rate. Interest during grace is $12,000,000 \times 2.0\% = 240,000$ a year; the amortising instalment is $12,000,000 / AF(0.02, 18) = 12,000,000 / 14.992031 = 800,425.23$. Discounting the whole service stream at 6.0 % gives a present value of **7,103,613**, so the **grant element** is $1 - 7,103,613/12,000,000 = 40.80\%$, and the subsidy is worth **4,896,387** in present-value terms. A concessional tranche of 12,000,000 is therefore 7.1 million of debt and 4.9 million of grant, and reporting it as 12 million of borrowing misstates both the leverage and the support received.

9.4.3 Green and sustainability-linked finance

Two mechanisms, routinely confused. A **use-of-proceeds** instrument — a green bond or green loan — commits the borrower to spend the money on defined eligible assets, with reporting and usually an external review; the pricing benefit, where it exists, comes from demand. A **sustainability-linked** instrument leaves the use of proceeds unrestricted and instead ties the **margin** to performance against key performance indicators through a ratchet, so the borrower pays less for hitting targets and more for missing them. The first constrains what the money does; the second prices what the borrower does.

Both rest on voluntary market frameworks — the principles published by international market associations for green bonds and green loans, and their sustainability-linked counterparts — together with jurisdiction-specific taxonomies and disclosure regimes that differ materially between jurisdictions and change frequently. None of them is a global standard, and treating one jurisdiction's taxonomy as universal is the characteristic error in this area.

WORKED EXAMPLE

Worked example 9.4.3 — does the ratchet pay for itself?

1. **Setup.** Kestrel's 42,000,000 senior facility is offered as a sustainability-linked loan with a **±15 basis point** margin ratchet tied to two KPIs (specific energy consumption per cubic metre produced, and a verified brine-discharge metric). Meeting both targets earns the full 15 basis point reduction. The apparatus required — metering, data assurance, annual limited-assurance verification, a second-party opinion refreshed periodically, and reporting — costs **85,000** a year. Assess over the 12-year facility at 6 %.
2. **Formula.** Annual benefit = tranche × ratchet. Compare present values using $AF(0.06, 12) = 8.383844$.
3. **Substitution.** $42,000,000 \times 0.15 \% = 63,000$ a year against 85,000 a year; $63,000 \times 8.383844$ against $85,000 \times 8.383844$.
4. **Result.** Present value of the margin saving **528,182**; present value of the compliance cost **712,627**; **net –184,445**. On margin alone the ratchet **destroys value**, even assuming both KPIs are met every year. The breakeven is a ratchet of **20.24 basis points**, or equivalently a base-margin reduction of **5.24 basis points** alongside the 15.
5. **Interpretation.** This is the number the market conversation usually omits, and stating it is not scepticism about sustainability — it is honesty about where the value comes from. A ratchet of 15 basis points on a facility of this size cannot pay for a credible verification apparatus, so **if the case for the label rests on the ratchet, there is no case**. The case rests elsewhere, and it is quantifiable: if the label genuinely widens the lender pool enough to cut the **base** margin by **10 basis points** — 42,000 a year, **352,121** in present value — the combined position turns **positive by 167,677**. That reframes the negotiation correctly: ask the arranger what the label does to the **base** margin and to the size of the club, not what the ratchet is worth. Three further cautions. The ratchet is **symmetric** in most drafting, so missing targets increases the margin, and a KPI set without headroom converts an ESG initiative into a cost. Targets must be **material and measurable** — a KPI the project would have met anyway invites the accusation of greenwashing, which is a reputational and, increasingly, a regulatory exposure. And **the verification cost is permanent** for the life of the facility, while the ratchet benefit is contingent on performance; budget them asymmetrically.

9.4.4 Refinancing

Definition. Refinancing replaces existing debt with new debt on better terms, and in project finance the opportunity is structural rather than opportunistic: construction risk, ramp-up risk and counterparty uncertainty all resolve in the first operating years, so the project that emerges is a materially better credit than the one that was financed. Better terms mean a lower margin, a longer tenor, a looser covenant package, or all three.

WORKED EXAMPLE**Worked example 9.4.4 — Kestrel's refinancing gain, decomposed.**

1. **Setup.** At the end of **year 6**, six of twelve instalments of 5,009,635.23 have been paid. The market offers **4.75 %**. Transaction costs — arrangement on the new facility plus a prepayment fee on the old — total **1.75 %** of the refinanced balance. Two structures are available: refinance the remaining **6 years**, or refinance over **12 years**, extending maturity from year 12 to year 18 within the 25-year operating life.
2. **Formula.** Outstanding balance = instalment $\times AF(r_{old}, remaining)$; new instalment = balance $\div AF(r_{new}, new\ tenor)$; the equity gain is the present value of the change in the equity cash-flow stream, discounted at the cost of equity.
3. **Substitution.** Balance $5,009,635.23 \times AF(0.06, 6) = 5,009,635.23 \times 4.917324$. Rate-only: balance $\div AF(0.0475, 6)$. Extended: balance $\div AF(0.0475, 12) = \text{balance} \div 8.989557$. Transaction cost balance $\times 1.75 \%$.
4. **Result.** Outstanding balance **24,634,001.18** (principal repaid to date **17,365,998.82**). Transaction cost **431,095.02**.

	Rate only, 6 years	Rate + extension, 12 years
New instalment	4,814,595.21	2,740,290.88
Annual saving, years 7–12	195,040.02	2,269,344.35
New DSCR	1.3260	2.3297
New LLCR	1.3260	2.3297
Tail (project life beyond maturity)	13 years	7 years
PV of equity gain at k_e 15.42 %	298,757	3,723,616
PV of equity gain at 8.00 %	470,552	2,076,800
PV of equity gain at 4.75 %	—	566,832

1. **Interpretation.** The extension appears to create **3.72 million** of equity value against 299 thousand from the rate reduction alone, and the decomposition shows why that comparison is misleading: of the 3.72 million, only **298,757** is the rate saving and **3,424,859** is the **extension**, which is not a gain at all but a **deferral** — six years of debt service moved from years 7–12 into years 13–18. Its apparent value is almost entirely an artefact of the discount rate: at 15.42 % the deferral is worth 3.42 million, at 8.00 % it is worth 1.61 million, and at the new loan rate of 4.75 % the whole package is worth only **566,832**. **A refinancing gain that shrinks by 85 % when the discount rate falls to the loan rate is a financing artefact, not value creation**, and a leader who presents the 3.72 million without the sensitivity has misled the board. What is unambiguously real: the rate saving of 195,040 a year; the coverage improvement to **2.3297**, which creates genuine covenant headroom; and the reduction of the **tail from 13 years to 7**, which is a genuine loss — **PLCR** at the refinancing date rises from 2.8917 to 3.1968 only because the new rate discounts more gently, while the contractual cushion behind the lenders has almost halved. Two further disciplines. **Costs are real and immediate:** 431,095 is paid at once against a gain earned over years, and at the rate-only structure the costs consume 59 % of the discounted benefit at 15.42 %. **Refinancing gain-share is common in concession-based structures**, requiring the grantor's consent and a defined share of the gain — at 50 % of the 15.42 % figure,

1,861,808 returns to the grantor, which changes the economics enough that the clause must be read before the refinancing is modelled, not after (Domain 12, KA 12.2).

AI in this KA

Where it earns its place. Refinancing screening across a portfolio — outstanding balances, candidate rates and tenors, opportunities ranked by gain net of costs — is repetitive arithmetic on data the organisation already holds, and it surfaces what manual review misses. Grant-element and sustainability-linked breakeven calculations are similarly mechanical.

Where it must not go. It must not conclude what a grant, subsidy or state guarantee means legally or fiscally: state-aid and subsidy-control regimes, the accounting treatment of grants and the tax character of concessional support are jurisdiction-specific and consequential. It must not generate sustainability claims or KPI narratives — statements about environmental performance carry regulatory and reputational exposure, and model-written text published as a project's own assertion is the shortest route to a greenwashing allegation. And it must not settle a refinancing recommendation, which turns on the discount-rate judgment 9.4.4 shows dominates the answer.

Verification, concretely. Recompute the outstanding balance independently — instalment $\times AF(r, \text{remaining})$ must equal the schedule's closing balance (Domain 3's check). Confirm every gain is reported at two or more discount rates, one of them the new loan rate, and net of transaction costs and any gain-share. Confirm the grant treatment used in a WACC is stated. And confirm a sustainability-linked benefit is compared against the **full-tenor** verification cost, not the first year's.

■ KEY TERMS — KA 9.4

Term	Meaning
Viability gap funding	Capital grant sized to make an otherwise unfinanceable project viable.
Minimum revenue guarantee	Grantor-provided floor under demand-based revenue; a written option.
Grant element	$1 - PV(\text{debt service at a market rate}) \div \text{face value}$; the subsidy content of concessional debt.
Use-of-proceeds instrument	Green bond or loan; proceeds restricted to eligible assets.
Sustainability-linked loan	Margin ratchet tied to KPI performance; usually symmetric.
Refinancing gain	PV of improved terms, net of costs; decomposed into rate and extension components.
Gain-share	Contractual obligation to pass a defined share of a refinancing gain to the grantor.
Tail	Project life beyond debt maturity; reduced by tenor extension.

■ SAMPLE MCQS — KA 9.4

MCQ 9.4-A [9.4.2 · Analysis] A 6,000,000 grant applied to reduce **equity** leaves DSCR at 1.2743 and lifts equity IRR from 12.5311 % to 16.8231 %; applied to reduce **debt** it lifts DSCR to 1.4867 and equity IRR to 14.9940 %. If the grantor's stated objective is to make an otherwise unfinanceable project financeable, it should:

A. apply the grant to reduce equity, maximising private-sector return

- B. apply the grant to reduce debt, because coverage is the binding constraint on financeability and 1.4867 clears the 1.30× sizing target ☒ **CORRECT**
- C. split the grant evenly, as a neutral position
- D. either — the WACC reduction is what matters

Rationale: Financeability is a coverage question (9.1.4, 9.4.2). A serves a different objective and should be stated as such; C is a decision avoided rather than made; D optimises the number that this domain shows is not binding — and WACC actually falls further under the equity-displacing case (6.4440 % against 6.7860 %), which is exactly why WACC is the wrong test here.

MCQ 9.4-B [9.4.3 · Application] A 42,000,000 facility offers a 15 basis point sustainability ratchet; the verification and reporting apparatus costs 85,000 a year; the facility runs 12 years and $AF(0.06, 12) = 8.383844$. On margin alone the arrangement is:

- A. value-positive by 528,182
- B. value-negative by 184,445 ☒ **CORRECT**
- C. value-neutral
- D. value-positive by 63,000 a year

Rationale: $63,000 \times 8.383844 = 528,182$ of benefit against $85,000 \times 8.383844 = 712,627$ of cost → **−184,445**. A counts the benefit and omits the cost; D quotes the annual benefit gross, also omitting cost; C asserts an offset that the arithmetic contradicts.

MCQ 9.4-C [9.4.4 · Analysis] A refinancing that extends maturity shows an equity gain of 3,723,616 at a 15.42 % cost of equity, 2,076,800 at 8.00 % and 566,832 at the new 4.75 % loan rate. The correct board disclosure is:

- A. a gain of 3,723,616
- B. a gain of 3,723,616, since the cost of equity is the correct discount rate for equity cash flows
- C. that most of the reported gain is deferral rather than saving — the rate component is 298,757 and the extension component 3,424,859 at 15.42 % — and that the package is worth only 566,832 discounted at the loan rate ☒ **CORRECT**
- D. no gain, since the total cash paid over the loan's life increases

Rationale: The decomposition and the rate sensitivity are the disclosure (9.4.4). A and B report a correct arithmetic result while concealing that it is an artefact of the discount rate; D swings to the opposite error, ignoring the genuine 195,040 a year of rate saving and the coverage improvement.

MCQ 9.4-D [9.4.2 · Application] A 12,000,000 concessional loan at 2.0 % over 25 years with 7 years' grace has a debt-service stream worth 7,103,613 at a 6.0 % market rate. Its grant element is:

- A. 40.80 % ☒ **CORRECT**
- B. 4.00 %
- C. 59.20 %
- D. nil — it is a loan, not a grant

Rationale: $1 - 7,103,613/12,000,000 = 40.80$ %, a subsidy worth 4,896,387 (9.4.2). B quotes the interest-rate difference as though it were the subsidy; C is the complement — the debt content, not the grant content; D confuses legal form with economic substance.

MCQ 9.4-E [9.4.3 · Evaluation] A 15 basis point sustainability ratchet on a 42,000,000 facility is worth 528,182 in present value against 712,627 of verification and reporting cost — net **−184,445** —

even assuming both key performance indicators are met every year. The soundest professional response is:

- A. take the label: 15 basis points is a saving, and the reporting would be done anyway
- B. reject sustainability-linked structures generally, since the ratchet is value-negative
- C. ask the arranger what the label does to the **base** margin and to the size of the club, because a 10 basis point base-margin reduction turns the combined position positive by 167,677 — and if the case rests on the ratchet alone there is no case ✓ CORRECT
- D. accept the ratchet and set key performance indicators the project would meet in any event, so that the reduction is certain

Rationale: A ratchet of this size cannot pay for a credible verification apparatus, so the negotiation belongs on the base margin and the lender pool, where the value actually is (9.4.3). A weighs a contingent benefit against a permanent cost and omits the cost. B generalises one arithmetic result into a policy and forgoes a benefit the same arithmetic shows is available. D is the greenwashing failure in one sentence: a target the project would have met is not a target, it carries reputational and increasingly regulatory exposure, and because the ratchet is symmetric in most drafting a KPI set chosen without headroom converts the initiative into a cost.

MCQ 9.4-F [9.4.2 · Comprehension] A finance ministry official describes a concessional loan as "part loan and part gift". Expressed in this domain's terms, that means:

- A. part of the principal will be forgiven at maturity and the remainder repaid
- B. the loan's subsidy content is the shortfall between its face value and the present value of its debt service discounted at a market rate — 40.80 % of a 12,000,000 tranche at 2.0 %, so about 7.1 million of borrowing and 4.9 million of support, with every dollar repaid ✓ CORRECT
- C. the gift is the total interest saved over the loan's life relative to a market rate, before discounting
- D. the description is loose talk: a loan repayable in full contains no grant

Rationale: The grant element is $1 - PV(\text{debt service at a market rate}) \div \text{face value}$, which measures subsidy in present-value terms without any principal being written off (9.4.2). A describes forgiveness, a different instrument. C omits discounting, which is where a seven-year grace period does most of its work. D confuses legal form with economic substance and would report 12,000,000 of borrowing where 7.1 million exists — misstating both the leverage and the support received.

MCQ 9.4-G [9.4.1 · Comprehension] A grantor with a fixed fiscal envelope can direct its support at a project either as a capital grant reducing the amount to be financed or as a minimum revenue guarantee capping the downside on a demand-based revenue line. Its stated objective is to get an otherwise unfinanceable project financed at the least fiscal cost. Restated in the terms 9.4.1 uses, the two professional points that decide the advice are that:

- A. no cash leaves the budget when a guarantee is given, so its fiscal cost is nil
- B. the choice belongs to the sponsors, since they are the party that must raise the financing
- C. a grant is always cheaper for a grantor than a contingent commitment
- D. support directed at the **coverage** face buys more financeability per unit of fiscal cost than support of equal value directed at the return face; and a guarantee is a written option whose value can be estimated, so an unvalued guarantee is an unmeasured liability rather than a free one ✓ CORRECT

Rationale: Those are 9.4.1's two cross-cutting points, and both are needed here: coverage is the binding constraint, so support aimed at the coverage face converts fiscal cost into financeability most

efficiently (9.1.4); and a guarantee is a written option whose value can be estimated, so "no cash moves" is a budgeting statement and not a cost statement. A is the error the topic exists to correct — a contingent liability is unbudgeted, not costless. C reverses it into a universal ranking: a guarantee that is never called costs nothing, and its expected cost is what has to be compared with the grant's certain one. B delegates a public-purpose judgement to the party whose interest lies in the return face — on the grant arithmetic of 9.4.2, the answer will be the structure that lifts equity IRR by 429.20 basis points and leaves DSCR untouched.

■ SELF-CHECK — KA 9.4

1. A grant of fixed size: which face should it strengthen and why? — The coverage face, if the objective is financeability, because coverage binds; the return face only if attracting equity to a thin sector is the stated objective.
2. When does a sustainability-linked ratchet pay for itself? — Only above about 20 basis points on a facility of this size, or when the label also reduces the base margin — 5.24 basis points is the breakeven addition here.
3. How must a refinancing gain be reported? — Net of costs and gain-share, decomposed into rate and extension components, at no fewer than two discount rates including the new loan rate.

— Advanced topics — Domain 9

9.A.1 Why capital-structure irrelevance fails in a project SPV

The classical result — that in frictionless markets the value of a firm is independent of how it is financed — is a useful diagnostic precisely because every one of its assumptions fails in a project financing, and naming the failures tells a leader where the value actually sits. **Taxes** are the first: the deductibility of interest supplies 0.72 of Kestrel's 1.02 WACC slope, so most of the apparent benefit of leverage is a transfer from the tax authority, contingent on a jurisdictional rule that can change. **Bankruptcy and distress costs** are the second, and in a single-asset SPV they are severe: there is no diversified balance sheet to absorb a bad year, which is why lenders demand coverage rather than accepting the theory's indifference. **Contracting frictions** are the third — covenants, lock-up, reserve accounts, cure limits — and they impose a hard boundary on the feasible set that no cost calculation can cross (9.1.4). The fourth is a modelling artefact worth confronting: the build-up of 9.1.3 re-levers only the beta term, leaving r_f , CRP and SP un-levered, which is what makes WACC linear in gearing and gives the slope its value. Re-lever the country and single-asset premiums as well and the slope changes; leave the beta un-levered and WACC rises with gearing. The convention is therefore not innocent, and the honest presentation states it, applies it uniformly, and reports how much of the conclusion depends on it.

9.A.2 Concessionality, blending, and measuring what the public sector gave

The grant-element calculation of 9.4.2 — **40.80 %** on the illustrative 12,000,000 tranche — generalises into the discipline of **blended finance**: combining concessional public capital with commercial capital so that a project unfinanceable on market terms becomes financeable. Three disciplines make it defensible. **Measure the subsidy**, using the grant element at an explicit market comparator rate, and report it as subsidy rather than as debt; a portfolio described as "5 billion of development lending" with an unstated 30 % grant element has misreported both its leverage and its fiscal cost. **Test additionality**: concessional capital that displaces commercial capital that would

have come anyway has funded a transfer, not a project. And **price the subordination separately** — public capital that ranks behind commercial debt is providing first-loss protection whose value is not captured by the interest-rate difference at all, and which should be valued as the credit enhancement it is.

9.A.3 The reviewer's funding-structure eye

Invariants to test on any funding structure or cost-of-capital model:

- Sources equal uses, at every drawdown date and in total (Domain 14's discipline, applied at close).
- **WACC** weights sum to one, and the debt weight uses the same debt figure as the coverage test.
- Every debt-like tranche is tax-adjusted and equity is not; each adjustment traces to a written opinion.
- **k_e** is re-levered for each candidate structure; no two structures share a cost of equity unless they share a gearing.
- Under the re-levering convention of 9.1.3, **WACC** is **linear in gearing**; a non-linear ladder contains an error.
- The **WACC** at the coverage-binding gearing is reported alongside the **WACC** at the proposed gearing (**8.0001 %** and **7.9860 %** for Kestrel) — the gap is the price of bankability.
- Every quoted equity **IRR** names its cash-flow case (bank case or sponsor case) and its treatment of any equity bridge.
- An equity bridge priced at exactly the equity **IRR** it defers produces **zero** uplift; a model reporting a gain there has a timing defect.
- Every tranche's cost is an **all-in effective rate solved from its own stream**, with capitalised premiums added to the loan and deducted fees excluded from proceeds.
- Compliance and monitoring costs run for the tranche's full tenor.
- The grant treatment used in **WACC** is stated; the alternative treatment's effect is disclosed (**67.20 basis points** for Kestrel).
- Every refinancing gain is net of costs and gain-share, decomposed, and reported at two or more discount rates.
- Cost effects and capacity effects are reported in separate columns and never netted.

— Industry variations — Domain 9

- **Contracted power and renewables.** Availability or fixed-price offtake supports high gearing and a deep pool of infrastructure debt funds; the distinctive feature is a large, jurisdiction-specific incentive layer (allowances, credits, feed-in mechanisms) whose value is often monetised through a specialist tranche with its own investor base and its own tax opinion. Green-labelled instruments are near-universal, so the label carries little pricing benefit and the 9.4.3 analysis matters more, not less.
- **Merchant power and commodities.** Coverage requirements of 1.5× and above compress feasible gearing, so structures lean on mezzanine and on private credit funds that will price risk banks will not; reserve-based and borrowing-base facilities re-size against periodic technical redeterminations, making debt capacity a variable rather than a term.
- **Transport concessions.** Ramp-up risk pushes structures toward long-tenor institutional debt, substantial capital grants or viability gap funding, and staged refinancing after patronage

stabilises — which is why refinancing gain-share clauses (9.4.4) are most common in this sector and why the grantor's consent regime is a financing term, not a legal footnote.

- **Water and regulated utilities.** Regulatory reset cycles cap the tenor over which revenue is contractually visible, so debt maturities are often set to reset dates and refinancing is structural. Public grant support is common and the G1/G2 allocation question of 9.4.2 is a standing negotiation with the regulator as well as the grantor.
- **Digital infrastructure.** Shorter asset lives compress tails, so lenders rely on contracted tenant credit rather than on [PLCR](#); capital arrives fast and in size from private credit and from vendor financing, and gearing is constrained by lease-term coverage rather than by concession length.
- **Social infrastructure PPPs.** Availability payments from a public counterparty support the thinnest equity in the market — gearing of 90 % is ordinary — which makes the leverage exchange rate of 9.1.4 extreme: tiny coverage movements dominate the equity return, and a lock-up is catastrophic rather than inconvenient.

— Case study — Domain 9: three ways to close 828,877 (water)

Situation. Domain 10's Case A left Kestrel with an arithmetic gap. Against base-case [CFADS](#) of 6,384,000 and a $1.30\times$ requirement, sustainable senior debt service is **4,910,769** supporting **41,171,123 — 828,877** short of the 42,000,000 requested. The bank would not move on coverage. The sponsors, whose investment committee had approved 18,000,000 of equity and no more, asked their adviser for options.

Option one: more equity. Senior 41,000,000 (debt service $41,000,000/8.383844 = 4,890,358$, [DSCR](#) **1.3054**) with equity of **19,000,000**. Distributions run at **1,493,642** a year, the equity [IRR](#) on the flat-[CFADS](#) basis is **12.3868 %**, and the structure's [WACC](#) is **8.0030 %**. This is Domain 10's answer, and it works.

Option two: mezzanine at SPV level. Senior 41,000,000, mezzanine 4,000,000 at 11.50 % over 15 years (debt service $4,000,000/6.996708 = 571,697$), equity 15,000,000. The bank rejected it in one line: total debt service becomes 5,462,056 and the project's [DSCR](#) falls to **1.1688**, below both the covenant and the lock-up. Mezzanine inside the borrower consumes the [CFADS](#) the covenant measures (9.2.2), and no amount of subordination language changes the arithmetic.

Option three: mezzanine at HoldCo level. The same 4,000,000 raised by the sponsors' holding company, serviced from **distributions**. The SPV's [DSCR](#) stays at **1.3054** because the SPV has no additional obligation; the mezzanine is covered $1,493,642/571,697 = 2.6126$ times out of distributions; and the sponsors' equity falls to 15,000,000 with an [IRR](#) of **12.4934 %** — 10.66 basis points better than option one, on 4,000,000 less cash committed. The bank consented, subject to the mezzanine having no recourse to the SPV and no security over its shares.

How it resolved, and what nearly went wrong. The sponsors took option three. Six months into operations the adviser ran the stress that should have been run first. The distribution lock-up triggers when [CFADS](#) falls below $4,890,358.20 \times 1.15 = 5,623,912$, which is **11.9061 %** below base case. Immediately above that line the mezzanine still looks serviceable: at an **11.5 %** shortfall [CFADS](#) is **5,649,840**, the SPV's [DSCR](#) is **1.1553** (a covenant breach, but payment made in full), distributions are **759,482** and HoldCo cover is **1.3285** — yet that case sits only **25,928** above the trigger. Four-tenths of a percentage point further down — a **12 %** shortfall, [CFADS](#) **5,617,920**, a further **31,920** of cash gone — the lock-up trips, the SPV retains cash it would otherwise have distributed, and **HoldCo coverage goes from 1.3285 to zero in a single step** while the senior lenders are paid on time. The mezzanine's $2.6126\times$ cover in the base case was therefore worth almost nothing in the one

scenario that mattered: it stood 2.6 times covered against a cliff **11.9 %** away, with no gradual deterioration to warn anyone. The sponsors renegotiated a 12-month HoldCo interest reserve of **571,697** and a standstill on HoldCo enforcement while an SPV lock-up subsisted, and the structure held.

What the domain teaches here. Mezzanine's placement, not its price, is its defining characteristic. HoldCo mezzanine is invisible to the SPV's coverage test and entirely dependent on the distribution it sits behind, so its true coverage is not the base-case multiple but the distance between base case and the **lock-up trigger** — for Kestrel, **11.9061 %**. Any junior instrument serviced from distributions must be stress-tested against the lock-up rather than the covenant, because the exposure is a cliff and not a slope: the number that matters is the shortfall at which the cash stops, not the multiple by which it is covered today.

— Case study B — Domain 9: the cheap money that bought expensive rolling stock (transport)

Situation. A metropolitan rail authority's concessionaire needed a **120,000,000** rolling-stock and signalling package. Supplier N, in a country with an active export credit agency, quoted **120,000,000**. Supplier S quoted **111,111,111** — **8.0 %** less, a difference of **8,888,889** — but with no ECA support available. The ECA offered **85 %** of the contract value at **3.90 %** over **14 years**, with an exposure premium of **6.5 %** capitalised. The commercial alternative for Supplier S was **85 %** at **6.30 %** over **12 years** with a **1.10 %** fee. The concessionaire's finance team recommended Supplier N: "the money is 240 basis points cheaper."

The arithmetic done properly. All-in costs first. Route N: ECA loan $120,000,000 \times 85 \% = 102,000,000$, premium **6,630,000**, financed loan **108,630,000**, instalment $108,630,000 / AF(0.039, 14) = 108,630,000 / 10.633202 = 10,216,114$; solving on the 102,000,000 of proceeds gives an all-in of **4.8656 %** — a full point above the 3.90 % headline. Route S: commercial loan **94,444,444**, fee **1,038,889**, proceeds **93,405,556**, instalment $94,444,444 / 8.247657 = 11,451,063$, all-in **6.5041 %**. So the money really is **164 basis points** cheaper, not 240.

But the money and the equipment must be decided together. Discounting each route's whole cash profile — the own-funds outflow at close plus the debt service — at the project's 8.0 % cost of capital: Route N costs **102,224,065** in present value against Route S's **104,001,662**. **Route N wins by 1,777,597** on a 120,000,000 package — **1.5 %**, and the finance team's recommendation was right, for reasons it had not calculated.

How it resolved. The team then computed the number that should have opened the analysis: the **breakeven equipment premium**, the price differential at which the two routes are indifferent. At an 8.0 % discount rate it is **9.8780 %**. The ECA route was worth paying up to about a **9.9 %** premium on the equipment, and the actual premium was **8.0 %** — a margin of **1.9 percentage points**, against a sole-source negotiation still in progress and a discount-rate assumption that moved the breakeven to **8.7179 %** at 6 % and **10.8612 %** at 10 %. The decision was live, not comfortable. Two months later the ECA re-rated the host country and raised its exposure premium from 6.5 % to **9.0 %**, lifting the financed loan to 111,180,000, the instalment to **10,455,929**, the all-in to **5.2291 %** and the route's present value to **104,201,155** — **199,494 worse** than Route S. The flip point on the exposure premium was **8.7477 %**. The concessionaire switched to Supplier S, having preserved the option by refusing to sign a sole-source commitment while the premium was un-fixed.

What the domain teaches here. A financing decision that is tied to a procurement decision is one decision, and it must be evaluated on the present value of the combined cash flows rather than on a comparison of rates. The output a leader should demand is not "which tranche is cheaper" but **the**

breakeven premium — the price differential at which the cheap money stops being worth its conditions — because that number is a negotiating position and a monitoring trigger, while a rate comparison is neither. Route N also carried a real coverage advantage worth naming: annual debt service of 10,216,114 against 11,451,063, **1,234,949** a year lower, almost entirely from two extra years of tenor (9.3.3). Had coverage been the binding constraint rather than cost, the answer would have survived the premium re-rating.

— Executive perspective — Domain 9

What a project finance director cannot delegate in this domain:

- **The hurdle rate, derived.** Not inherited, not a policy round number. The director owns the build-up — r_f , ERP, β_a , CRP, SP, tax rate, each with a named source and a date — and owns the reconciliation. Kestrel's 8.0001 % at the coverage-binding gearing was Domain 4's given 8.0 %; that agreement was luck until somebody checked it.
- **The refusal to use the group's cost of capital.** Kestrel's project WACC is **8.0001** % against the sponsor's corporate **6.544** %; discounting the project at the group rate raises its NPV from 16,179,360 to **23,447,722** — an overstatement of **7,268,362**, or **44.92** %. The gap is structural, not a rounding difference: a diversified investment-grade group carries lower gearing, cheaper debt, a lower asset beta, and neither a country premium nor a single-asset illiquidity premium. **The rate belongs to the project, not to the balance sheet that sponsors it**, and a director who allows the group rate into a project appraisal has authorised the systematic acceptance of value-destroying projects.
- **The gearing decision, on both faces.** The exchange rate — 5.75 basis points of equity return per hundredth of DSCR at the margin — and the gearing at which each covenant binds (68.62 %, 74.34 %, 77.57 %). These are the director's numbers because they trade a lender's protection against a shareholder's return, and no analyst should be asked to make that trade.
- **Where a grant lands.** The same 6,000,000 either lifts equity return 429 basis points or lifts coverage 21 points. The director states the objective **before** the allocation is negotiated, and states the treatment convention before any WACC is quoted.
- **The all-in discipline.** No tranche enters a comparison on its headline rate. The DFI tranche at 5.25 % costs 7.2465 %; the ECA tranche at 3.80 % costs 4.6895 %; the ijara's 15 basis point premium is really 4. The director enforces the method, because the method is where the errors are.
- **The honesty of a refinancing.** Report gains net of cost and gain-share, decomposed into rate and extension, at more than one discount rate — and never let a deferral be presented as value created.

— Calculation exercises — Domain 9

Exercise 9.1 A 150,000,000 project is geared 70/30. Senior debt costs 5.5 % and the tax rate is 25 %. Build the cost of equity from r_f 3.80 %, ERP 5.5 %, β_a 0.55, CRP 1.20 % and SP 0.40 %, then compute the WACC. Solution. $D/E = 105,000,000/45,000,000 = 2.333333$; $(1 - 0.25) \times 2.333333 = 1.75$; $\beta_e = 0.55 \times 2.75 = \mathbf{1.5125}$; $\beta_e \times ERP = 8.31875$; $k_e = 3.80 + 8.31875 + 1.20 + 0.40 = \mathbf{13.71875}$ %. After-tax debt $5.5 \times 0.75 = \mathbf{4.125}$ %; $WACC = 0.70 \times 4.125 + 0.30 \times 13.71875 = \mathbf{7.0031}$ %. Common error: using the pre-tax cost of debt, giving 7.9656 % — a 96 basis point

overstatement that would kill marginal projects. A second common error is failing to re-lever at all ($\beta_e = \beta_a = 0.55$), giving k_e 8.425 % and a WACC of 5.4150 % — a 159 basis point understatement, which approves projects that destroy value.

Exercise 9.2 A 100,000,000 project generates level CFADS of 14,000,000 over a 22-year life; debt costs 6.5 % over 15 years ($AF(0.065, 15) = 9.402669$). Compare 65 % and 75 % gearing on DSCR and equity IRR. Solution. At 65 %: debt 65,000,000, equity 35,000,000, debt service $65,000,000/9.402669 = 6,912,930.89$, DSCR 2.0252, distributable 7,087,069.11, equity IRR 20.7836 %. At 75 %: debt 75,000,000, equity 25,000,000, debt service 7,976,458.72, DSCR 1.7552, distributable 6,023,541.28, equity IRR 24.8151 %. Ten points of gearing buys 403.15 basis points of equity return for 0.2700 of coverage. Common error: computing the equity IRR on the whole CFADS stream rather than on CFADS less debt service, which produces the project return and makes gearing look irrelevant.

Exercise 9.3 Senior 80,000,000 at 5.2 %, mezzanine 20,000,000 at 10.8 %, equity 50,000,000 at 14.5 %; tax 30 %; both debt tranches deductible. Compute the WACC. Solution. After-tax senior $5.2 \times 0.7 = 3.64$ %; mezzanine $10.8 \times 0.7 = 7.56$ %; WACC = $(80 \times 3.64 + 20 \times 7.56 + 50 \times 14.5)/150 = (291.2 + 151.2 + 725)/150 = 7.7827$ %. Common error: tax-adjusting the equity cost as well, giving 6.3327 % — a 145 basis point understatement. Also common: a simple average of the three costs (8.5667 %), which ignores that senior debt is more than half the capital.

Exercise 9.4 A 40,000,000 tranche carries 4.10 % over 12 years with a 5.5 % exposure premium capitalised into the loan. Compute the all-in cost on the proceeds actually available. Solution. Premium 2,200,000; loan 42,200,000; $AF(0.041, 12) = 9.330854$; instalment $42,200,000/9.330854 = 4,522,630.17$; solve $40,000,000 = 4,522,630.17 \times AF(r, 12) \rightarrow 5.0378$ %, an uplift of 93.78 basis points over the headline. Common error: spreading the premium straight-line across the tenor and adding it to the rate ($4.10 + 5.5/12 = 4.5583$ %), which ignores that the premium is itself financed and repaid with a return on it.

Exercise 9.5 A 120,000,000 project has CFADS of 13,000,000 and debt at 6.2 % over 13 years ($AF(0.062, 13) = 8.750167$); tax 25 %. An 18,000,000 grant is awarded. Case (a): the grant displaces equity, leaving debt 84,000,000 and equity 18,000,000, with k_e 16.50 %. Case (b): the grant displaces debt, leaving debt 66,000,000 and equity 36,000,000, with k_e 13.50 %. Compute DSCR and WACC for each. Solution. After-tax debt $6.2 \times 0.75 = 4.65$ %. Case (a): debt service $84,000,000/8.750167 = 9,599,817.02$, DSCR 1.3542; WACC = $(84 \times 4.65 + 18 \times 16.50 + 18 \times 0)/120 = 5.7300$ %. Case (b): debt service $66,000,000/8.750167 = 7,542,713.37$, DSCR 1.7235; WACC = $(66 \times 4.65 + 36 \times 13.50)/120 = 6.6075$ %. The equity-displacing case has the lower WACC and the worse coverage — the 9.4.2 result, in a different project. Common error: omitting the grant from the denominator of the WACC weights, which inflates the debt and equity shares to sum to more than one and produces a meaningless figure.

— Practitioner's toolkit — Domain 9

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 9.T.1 — Cost-of-capital derivation record (one per project, per structure)

One page, signed. Rows: r_f — instrument, tenor, currency, quotation date, source · ERP — value, source, date, market · β_a — value, comparator set named, source of the unlevering · re-levering formula and whether non-beta premiums are re-levered · D/E used, and confirmation it matches the funding plan · CRP and SP — value and basis · resulting k_e · tax rate and the written opinion supporting deductibility, per tranche · each tranche's pre- and post-tax cost · weights and their sum · resulting $WACC$ · **the $WACC$ at the coverage-binding gearing** and the gap to the proposed structure · the sponsor's corporate $WACC$, stated for contrast, with a note that it is **not** the project rate. Rule: no appraisal in the organisation uses a discount rate without a current signed record, and the record is re-signed whenever the funding plan changes.

Toolkit 9.T.2 — Tranche comparison sheet (all-in, like-for-like)

One column per candidate tranche. Rows: amount · currency · base rate and margin, or profit rate · fee schedule (arrangement, commitment, agency, structuring) · capitalised premiums · tenor, availability period and amortisation profile · grace · prepayment mechanics and any make-whole · security and ranking · conditions precedent and expected time to satisfy · compliance and monitoring cost, for the full tenor · currency of repayment against currency of revenue · **cash proceeds actually available** · **all-in effective rate, solved from the stream** · annual debt service · $DSCR$ contribution · **debt capacity supported at the target coverage** · grant element, where concessional. Two mandatory footers: the method statement (all-in rates solved, not added) and the separation rule (cost effects and capacity effects reported in different rows, never netted).

Toolkit 9.T.3 — Capital-structure decision record

For each candidate structure, one row: tranche amounts and costs · re-levered k_e · $WACC$ · senior-only $DSCR$ · total $DSCR$ · minimum $DSCR$ over the loan life · gearing at which each covenant and the lock-up binds · equity IRR on the bank case **and** on the sponsor case, with the escalation assumption that separates them · treatment of any grant, stated · junior instruments and their placement (SPV or HoldCo), with the lock-up shortfall at which HoldCo service stops · refinancing assumption, if any, and whether a gain-share applies. Front line: **which constraint binds, at what gearing, and what the structure costs in $WACC$ to stay inside it**. The record is minuted with the decision, and the rejected structures stay in it.

— Exam preparation — Domain 9

What is assessed. Building a cost of equity from stated components with correct re-levering; computing an after-tax cost of debt and a multi-tranche $WACC$ with correct weights and tax treatment; quantifying the leverage trade-off on both faces and identifying the gearing at which a covenant binds; distinguishing a tranche's cost effect from its debt-capacity effect; computing an all-in effective cost from a stream containing fees and capitalised premiums; computing a grant's effect on $WACC$, $DSCR$ and equity return, and a concessional loan's grant element; testing sustainability-linked pricing against its verification cost; and computing and decomposing a refinancing gain.

The calculations to have automatic under time pressure. $k_d(1 - T)$. $\beta_e = \beta_a(1 + (1 - T)D/E)$ and the build-up onto it. $WACC$ as a weighted sum with the grant at zero cost and in the denominator. $DSCR = CFADS \div (D \div AF(r, n))$ and its inversion to a binding gearing ($\max \text{ debt} = CFADS/\text{target} \times AF$, then $\div \text{ capex}$). All-in cost as the rate solving $\text{proceeds} = \text{payment} \times AF(r, n)$. Grant element as $1 - PV(\text{service at market rate})/\text{face}$. Outstanding balance as $\text{instalment} \times AF(r, \text{remaining})$.

The traps.

- Using the pre-tax cost of debt in [WACC](#) — Exercise 9.1, 96 basis points.
- Tax-adjusting the cost of equity — Exercise 9.3, 145 basis points.
- Failing to re-lever [k_e](#) when comparing structures — 9.1.3, 9.2.3; every comparison in KA 9.2 is invalid without it.
- Re-levering **without** the tax adjustment — MCQ 9.1-A, distractor C.
- Omitting a grant from the [WACC](#) denominator so the weights exceed one — Exercise 9.5.
- Comparing tranches on headline rate plus fees instead of the solved all-in rate — 9.3.1, 9.3.2, Exercise 9.4.
- Treating a capitalised premium as a one-off percentage added to the rate — Exercise 9.4.
- Netting a cost effect against a capacity effect — 9.3.3, MCQ 9.3-B.
- Placing mezzanine at SPV level and expecting the senior [DSCR](#) to be unaffected — 9.2.2, Case A option two.
- Stress-testing HoldCo junior debt against the covenant instead of the lock-up — Case A, 11.9061 %.
- Reporting a refinancing extension as value created — 9.4.4, MCQ 9.4-C.
- Discounting a project at the sponsor's corporate [WACC](#) — Executive perspective, 44.92 % overstatement.
- Quoting an equity [IRR](#) without naming its cash-flow case, or without disclosing an equity bridge — 9.1.1, 9.1.4.
- Modelling a shareholder-loan tax shield without a tax opinion, or with the interest mis-ranked — 9.1.2, MCQ 9.1-D.
- Valuing a sustainability ratchet against a single year's compliance cost rather than the full tenor — 9.4.3.

How the domain connects. Domain 3 supplied $AF(r, n)$, which does almost all the arithmetic here, and Domain 4 the appraisal this domain's [WACC](#) finally justifies. Domain 7's indexation drafting supplies the 1.7403 % escalation on which the equity case rests; Domain 8's contingency and delay arithmetic sets the funding headroom. Domain 10 supplies the coverage machinery that constrains everything here and the four sizing levers this domain prices; Domain 11 allocates the risks that set [CRP](#), [SP](#) and the required coverage; Domain 12 documents the intercreditor, security and gain-share terms; Domain 13 audits the model; Domain 14 draws the tranches; and Domain 15 lives with the structure and executes the refinancing this domain sized.

— Domain 9 summary

Funding structure is where a project's economics are finally decided, and this domain's central claim is that the decision is **not** made by minimising the cost of capital. Kestrel's cost of equity, built up from a 4.10 % risk-free rate, a 6.00 % equity risk premium on an asset beta of 0.60 re-levered to **1.72**, and one point of country and single-asset premium, is **15.42 %**; its after-tax cost of debt, on the 20.0 % cash tax rate the thread's own numbers imply, is **4.80 %**; and its [WACC](#) at the proposed 70/30 structure is **7.9860 %**. The whole ladder collapses to $WACC(g) = 8.70 \% - 1.02 \% \times g$, whose slope is small precisely because the non-systematic equity premium of 5.10 % barely exceeds after-tax senior debt at 4.80 % — so across twenty points of gearing the project saves **20.40 basis points** while the sponsors gain **184.61** and the lenders lose **0.3716** of [DSCR](#). Gearing is a transfer, not an efficiency, and its exchange rate at the margin is about **5.75 basis points of equity return per 0.01 of coverage surrendered**. The constraint that decides the structure is coverage: the $1.30 \times$

sizing target binds at **68.6185 %** gearing, the 1.20× covenant fails on the base case above **74.3367 %**, and the 1.15× lock-up above **77.5688 %**. Evaluated at the coverage-binding gearing the project **WACC** is **8.0001 %** — which is Domain 4's given 8.0 %, derived at last, and right only for that structure; the sponsor's corporate **WACC** of **6.544 %** would have overstated the appraisal **NPV** by **7,268,362**, or **44.92 %**, and is never the project's rate. Within the stack, mezzanine raises the blended cost in every direction — **8.4510 %** displacing senior, **8.3240 %** displacing equity — and is bought for coverage relief (senior **DSCR 1.5115**) or equity uplift, never for cheaper capital; its **placement** decides everything, and HoldCo mezzanine covered **2.6126** times in the base case receives nothing once **CFADS** falls **11.9061 %** to the lock-up trigger. Every tranche is compared on an all-in rate solved from its own stream: the ijara's 15 basis point headline premium is really **3.95**; the ECA's 3.80 % is **4.6895 %** and releases **303,726** a year of debt service; the DFI's 5.25 % is **7.2465 %** all-in yet its six extra years of tenor lift debt capacity from **41,171,123** to **56,299,948** — because tenor, not rate, moves the binding constraint. Public support must be aimed: the same 6,000,000 grant either lifts equity return **429.20 basis points** or coverage **21.24 points**, and the treatment convention alone moves **WACC** by **67.20 basis points**; a 12,000,000 concessional loan at 2 % carries a **40.80 %** grant element. A 15 basis point sustainability ratchet worth **528,182** cannot pay for **712,627** of verification, so the case for a label must rest on the base margin and the investor pool, not on the ratchet. And a refinancing gain of **3,723,616** is **298,757** of rate saving and **3,424,859** of deferral, worth only **566,832** discounted at the loan rate and halved again by a gain-share — which is why every gain is reported net, decomposed, and at more than one rate. Domain 10 tests the coverage this domain has just priced; Domain 13 audits the model behind it; Domain 15 operates the structure and executes the refinancing.

03

PART THREE

Executing the transaction

Domains 10-13 — debt sizing and covenants, risk allocation, contracts and transaction structure, and due diligence to financial close: turning an appraised project into a funded one.



10

DOMAIN 10

Debt Sizing, Covenants and Credit Metrics

— Why this domain exists

Everything before this point valued a project. This domain decides **how much debt it can carry, and on what conditions** — which is the question that determines whether the financing exists at all. It is the lender's side of the table, and a project finance leader who cannot compute it is negotiating blind against people who can.

The logic is inverted from corporate finance and that inversion is the domain's central idea. A company borrows against its balance sheet; a project's debt is sized **from its cash flow outwards**: forecast [CFADS](#), divide by the coverage the lender requires, and the result is the debt service the project can afford — from which the debt amount follows. Debt capacity is therefore not a negotiation about appetite but an arithmetic consequence of cash flow and required coverage (KA 10.1). The coverage ratios themselves — [DSCR](#), [LLCR](#), [PLCR](#), [ICR](#) — measure different things and are routinely confused (KA 10.2). Reserve accounts and the debt-service schedule convert the arithmetic into liquidity that survives a bad year (KA 10.3). And covenants, default, cure rights and distribution lock-up are the machinery that gives lenders control before, not after, a project fails (KA 10.4).

Learning objectives. After this domain a candidate can: define [CFADS](#) and explain why its documented definition governs every ratio built on it; size debt from a [CFADS](#) forecast and a target [DSCR](#), and distinguish a base-case test from a minimum-period test; show why exchanging a lower coverage requirement for a lower cash case is not necessarily a concession, and compute the stress at which the exchange turns negative; build a sculpted debt-service schedule against an uneven [CFADS](#) profile, including the tax circularity, and derive the effective rate at which sculpted debt discounts; compute and interpret [DSCR](#), [LLCR](#), [PLCR](#) and [ICR](#), state what each sees that the others do not, and show which of them repayment structure can and cannot move; stress a coverage position against several covenants at once and identify the covenant that binds first; explain reserve accounts, size a debt-service reserve, express it as the shortfall it survives, and choose between funding it with equity, debt or a letter of credit; compute the effect of a cash sweep on the repayment profile and the loan's average life; describe covenant types, the lock-up mechanism, events of default and cure rights; size an equity cure under both of the standard drafting treatments; explain why lenders prefer cash-based to accounting-based covenants; and govern AI-assisted covenant and model analysis.

The master financing. Kestrel Water SPC continues from Domains 1–4. Its senior loan is **USD 42,000,000 at 6.0 % over 12 years** (Domain 3's schedule: annual instalment **USD 5,009,635**, year-one interest **USD 2,520,000**, year-one principal **USD 2,489,635**). Domain 2 derived its first-year [CFADS](#) of **USD 6,384,000** on the facility's documented definition — after working-capital movements. Equity at close was **USD 18,000,000**, giving 70/30 gearing. The project's operating life is **25 years**; the loan's is 12.

The CFADS relation this domain works with. Several of the calculations below need CFADS as a function rather than as a single figure, and Domains 2 and 6 have already supplied every component of one. On Kestrel's bank case — revenue R flat at 12,000,000, cash operating cost 4,500,000 of which 750,000 varies with output, depreciation 2,400,000, tax at 20 % of taxable profit, a 600,000 working-capital movement — CFADS in a period is

$$\text{CFADS} = 0.75 \times R - 3,120,000 + 0.20 \times I(t)$$

where $I(t)$ is that period's interest. At $R = 12,000,000$ and $I = 2,520,000$ it returns **6,384,000**, and with interest fixed at the year-one figure it collapses to Domain 6's one-variable form $\text{CFADS} = 0.75 R - 2,616,000$ (Domain 6, Exercise 6.4). Two consequences run through the whole domain. **A revenue shock moves CFADS by 0.75 of itself**, not by all of it, because variable cost and tax absorb a quarter of the loss — which is why headroom quoted in CFADS terms overstates the room available to a team that manages revenue. And **CFADS depends on the debt**, through the interest deduction: as the loan amortises the tax shield shrinks, cash tax rises and CFADS falls. Domain 6 (Worked example 6.4.1b) computed the consequence on this facility — CFADS declining from 6,384,000 in year one to **5,936,713** in year twelve, DSCR from **1.2743** to **1.1851**, LLCR **1.2395** rather than the level-case 1.2743. That declining profile, not the level illustration, is the case this domain sizes, sculpts and stresses against.

Kestrel's three coverage thresholds, which are used throughout and are routinely conflated: a **1.25× distribution condition** (cash may leave the structure only above it), a **1.20× financial covenant** (below it the facility is in breach), and a **1.15× lock-up trigger** (below it retained cash is blocked or applied to prepayment rather than merely undistributed). In cash they are **6,262,044**, **6,011,562** and **5,761,081** of annual CFADS. Which of them actually binds is the subject of KA 10.4.

KNOWLEDGE AREA 10.1

Debt capacity and sizing

Topics: 10.1.1 CFADS — the term everything rests on · 10.1.2 sizing from coverage · 10.1.3 sculpting and the shape of debt service.

10.1.1 CFADS — the term everything rests on

Definition. CFADS is the cash a project generates that is available to service debt, in a period, **before** debt service and after everything that must be paid first. Its construction runs:

```
Revenue collected
- cash operating costs
- cash taxes
- maintenance capex (usually; sometimes below debt service)
± movements in working capital
± movements in reserve accounts (as defined)
= CFADS
```

Every one of those lines is negotiated. Domain 2 (KA 2.3.1) demonstrated the consequence with Kestrel: CFADS of **6,984,000** before working-capital movements and **6,384,000** after, on the same year's trading. That is a DSCR of 1.39 versus 1.27 — the difference between comfort and near breach — from a definitional choice.

The professional discipline follows directly. **CFADS is whatever the finance documents say it is**, and the ratio a lender enforces is computed on their definition, not on textbook practice. The leader's obligations are to know the definition, to ensure the model implements it (Domain 13's model audit checks precisely this), and never to quote a coverage ratio without being able to state the **CFADS** definition underneath. The recurring negotiation points worth naming: whether maintenance capex sits above or below **CFADS**; whether cash taxes or accounting tax are used (Domain 2, KA 2.A.1 — cash, always, and the model must implement it); whether working capital is included; and how reserve-account movements are treated.

10.1.2 Sizing from coverage

The principle. Debt is sized so that forecast cash covers debt service by the required margin:

$$\begin{aligned} \text{Maximum debt service per period} &= \text{CFADS} \div \text{target DSCR} \\ \text{Maximum debt} &= \text{maximum debt service} \times \text{AF}(r, n) \end{aligned}$$

The second line is Domain 3's annuity factor doing the work: level debt service discounted at the loan rate over the loan tenor gives the principal it can support.

WORKED EXAMPLE

Worked example 10.1.2 — how much can Kestrel actually borrow?

- Setup.** **CFADS USD 6,384,000** per year (level, for this illustration), loan rate **6.0 %**, tenor **12 years**, lender's target **DSCR 1.30×**. The sponsors have asked for USD 42,000,000.
- Formula.** Max debt service = **CFADS/target DSCR**; max debt = max debt service × **AF(0.06, 12)**.
- Substitution.** $6,384,000 / 1.30 = 4,910,769$; $\text{AF}(0.06, 12) = 8.383844$; $4,910,769 \times 8.383844$.
- Result.** Maximum debt service **USD 4,910,769**; maximum debt **USD 41,171,123** — so the requested 42,000,000 is **USD 828,877 too much** at a 1.30× target. At 42,000,000 the actual **DSCR** is **1.2743**, below the target.
- Interpretation.** This single calculation is the centre of most financing negotiations, and notice what it does not depend on: the sponsors' preference, the project's NPV (Domain 4's +16.2m), or the asset's cost. Debt capacity is a function of **cash flow, required coverage, rate and tenor** — nothing else. That gives the leader four levers and no others: raise **CFADS** (revenue or cost), argue the coverage requirement down (usually by reducing revenue risk — Domain 7's contracted structures, Domain 11's allocation), lengthen the tenor, or lower the rate. The fifth option is to **contribute more equity**, which is what happens when the first four fail — and the 828,877 gap is exactly the additional equity Kestrel's sponsors would need to find. One thing this calculation quietly assumes deserves stating, because most sizing arguments turn on it: **it is a single-period test**. **CFADS** was taken as level and the coverage requirement was applied once, so 41,171,123 is the debt that clears 1.30× in the period tested — conventionally the first full operating year, which is why lenders call it the base-case test. A requirement that 1.30× be met in **every** period is a different and much tighter constraint, and against Kestrel's actual declining profile it produces a materially smaller answer (Worked example 10.1.3). A leader who agrees a target **DSCR** without agreeing whether it is tested on the base case or on the minimum has agreed the easy half of the term.

Debt capacity is arithmetic: CFADS 6,384,000 at 6 % — capacity falls as required coverage rises




Fig 10.1.1 — Debt capacity as a function of coverage and tenor

WORKED EXAMPLE**Worked example 10.1.2b — the coverage-for-case exchange, and the stress at which it turns against you.**

- Setup.** The most common concession offered in a sizing negotiation is a lower target **DSCR**. The most common condition attached to it is that the lower ratio be applied to the lender's own stressed case rather than to the sponsor's base case. Kestrel's lead bank offers **1.25×** in place of **1.30×**, applied to a case **5 %** below the base-case **CFADS** of 6,384,000. Rate 6 %, tenor 12 years, $AF(0.06, 12) = 8.383844$. Is that a concession, and at what stress does the answer change?
- Formula.** Capacity = $CFADS \div \text{target DSCR} \times AF(r, n)$. Two offers give the same capacity when $CFADS \times (1 - s) \div \lambda_2 = CFADS \div \lambda_1$, so the **indifference stress** is $s^* = 1 - \lambda_2/\lambda_1$ — a function of the two ratios alone, independent of **CFADS**, rate and tenor.
- Substitution.** $s^* = 1 - 1.25/1.30$. Capacity at 1.30× on base cash $6,384,000/1.30 \times 8.383844$; capacity at 1.25× on $6,384,000 \times 0.95 = 6,064,800$, that is $6,064,800/1.25 \times 8.383844$.
- Result.** Indifference stress $s^* = 3.8462 \%$, equivalent to a **CFADS** of **USD 6,138,462**. The bank's stress of 5 % exceeds it, so the offer is worth **less** than the term it replaces: **40,677,069** against **41,171,123**, a loss of **USD 494,053** of debt capacity for what was presented as a five-basis-point-of-coverage relaxation.
- Interpretation.** The general rule is worth memorising in the form the algebra gives it: **a coverage relaxation from λ_1 to λ_2 is worth exactly the stress $1 - \lambda_2/\lambda_1$, and nothing more.** Moving from 1.30× to 1.25× buys 3.8462 % of cash; moving from 1.30× to 1.20× buys **7.6923 %**. Any stressed case deeper than that leaves the sponsor worse off, and because the result is independent of rate, tenor and the absolute size of **CFADS**, it can be computed in the meeting rather than after it. Three professional points follow. First, **the two halves of the term must be negotiated together or not at all** — a sponsor who concedes the case definition on Tuesday and negotiates the ratio on Thursday has given away the only lever that matters, which is the same error Domain 15 (KA 15.3.4) identifies in refinancings negotiated on margin before sweep. Second, the rule shows what a genuine concession looks like: the bank must either hold the case and move the ratio, or move the ratio by more than the case costs — here 1.25× on a 5 % stress would need to fall to $1.30 \times 0.95 = 1.2350\times$ to be neutral. Third, the caution: this is an arithmetic equivalence, not a risk equivalence. A stressed case and a base case are different statements about the world, and a lender who insists on sizing against a stress it believes has done something a ratio adjustment cannot undo — which is why the honest response to the offer is usually to argue about the stress's evidence base (Domain 7's demand work) rather than to trade ratio points against it.

10.1.3 Sculpting and the shape of debt service

The problem with level debt service. An annuity assumes cash flow is level. Projects rarely oblige: availability payments may escalate, merchant revenue may ramp, and major maintenance may fall in specific years. Level debt service against uneven cash produces **wasted coverage** in good years and **breach risk** in weak ones.

Sculpting sets each period's debt service so that coverage is constant by design:

$$\text{Debt service in period } t = CFADS(t) \div \text{target DSCR}$$

The principal profile then follows from what is left after interest — irregular by construction, and that is the point. Sculpted debt supports **more** total debt than level debt against the same uneven cash flow, because no period is over-covered merely to protect the weakest one. The trade is complexity: an irregular repayment profile has to be documented, modelled and monitored, and a sculpted schedule computed on a forecast must be re-cut when the forecast changes (which the facility agreement provides for, or does not).

The circularity, and the rate that resolves it. Sculpting looks like a one-line rule and is not, because in any structure where interest is tax-deductible **CFADS** depends on the interest, the interest depends on the balance, and the balance depends on the debt service that **CFADS** was supposed to determine. Domain 6 (KA 6.3.1) names the three honest resolutions — charge on the opening balance, iterate to convergence, or solve algebraically — and for a sculpted schedule the algebra is available in closed form, which is much the best answer because it is deterministic. Write $\text{CFADS}(t) = A + T \times I(t)$ where A is the cash flow before the tax shield and T the tax rate, and let λ be the target coverage. Then $\text{DS}(t) = (A + T \cdot r \cdot B(t-1)) / \lambda$ and the balance rolls forward as

$$B(t) = B(t-1) \times (1 + r - T \cdot r / \lambda) - A / \lambda$$

so requiring $B(n) = 0$ gives, exactly,

$$\text{Maximum sculpted debt} = (A \div \lambda) \times \text{AF}(r^*, n) \quad \text{with the effective sculpting rate } r^* = r \times (1 - T / \lambda)$$

The tax shield therefore does not merely add cash: it **discounts the sculpted profile at a lower rate than the loan rate**, because every unit of interest returns T of tax saving into the same **CFADS** line the coverage test divides. That single expression removes the circularity, and it is the reason a sculpted structure should never be built by iterating a workbook until the closing balance looks like zero.

WORKED EXAMPLE

Worked example 10.1.3 — sculpting Kestrel's declining profile, and the three different answers to "how much can it borrow at 1.30×

- Setup.** Kestrel's bank case: $\text{CFADS}(t) = 5,880,000 + 0.20 \times I(t)$ (the relation derived in this domain's opening, with revenue flat at 12,000,000), loan rate **6.0 %**, tenor **12 years**, tax **20 %**, required coverage **1.30×**. Size the facility three ways — level service tested on the base case, level service tested on the minimum period, and sculpted service holding 1.30× in every period — and reconcile the differences.
- Formula.** Base-case level: $\text{CFADS}(1) / \lambda \times \text{AF}(r, n)$ (10.1.2). Minimum-period level: the binding period is the last, where $I = r \cdot \text{DS} / (1 + r)$ because the final payment retires the balance, so $\text{DS} = A \div (\lambda - T \cdot r / (1 + r))$ and debt = $\text{DS} \times \text{AF}(r, n)$. Sculpted: $(A / \lambda) \times \text{AF}(r^*, n)$ with $r^* = r(1 - T / \lambda)$.
- Substitution.** Base-case level: $6,384,000 / 1.30 \times 8.383844$. Minimum-period level: $5,880,000 \div (1.30 - 0.20 \times 0.06 / 1.06) = 5,880,000 / 1.28867925$, then $\times 8.383844$. Sculpted: $r^* = 0.06 \times (1 - 0.20 / 1.30) = 0.05076923$; $\text{AF}(0.05076923, 12) = 8.824924$; debt = $5,880,000 / 1.30 \times 8.824924 = 4,523,076.92 \times 8.824924$.
- Result.**

Sizing basis	Debt service	Debt supported	DSCR year 1	DSCR year 12
Level, base-case (year-one) test at 1.30×	4,910,769.23	41,171,123	1.2980	1.2087
Level, minimum-period test at 1.30×	4,562,811.13	38,253,896	1.3893	1.3000
Sculpted, 1.30× in every period	4,891,530.57 falling to 4,562,811.13	39,915,812	1.3000	1.3000

The sculpted schedule, in outline: year one interest 2,394,949, [CFADS](#) 6,358,990, debt service 4,891,531, principal 2,496,582; year six debt service 4,763,995 on principal 3,198,030; year twelve debt service 4,562,811 retiring the closing balance of 4,304,539 exactly. Total debt service **56,888,034**, of which **16,972,222** is interest. 5. **Interpretation.** Start with the number that decides the negotiation: **insisting that 1.30×** be met in every period, with level service, costs **2,917,226 of debt capacity** — 41,171,123 against 38,253,896 — and **sculpting recovers 1,661,916 of it**, or 56.97 %, without relaxing the requirement by a single basis point in any period. That is the whole commercial case for sculpting in two figures, and it is available on any declining or ramping profile. Then notice the structural identity hiding in the table: **the sculpted schedule's final payment, 4,562,811.13, is exactly the level payment that a minimum-period test would have imposed for the whole loan.** That is not a coincidence but the same equation solved twice, and it is the clearest statement of what level sizing does wrong against uneven cash — it makes every year pay what only the worst year needed to pay. Three further readings and two cautions. The **effective sculpting rate** of 5.076923 % against a 6.0 % loan rate is a real and often-missed effect: at a 30 % tax rate the same structure would discount at $0.06 \times (1 - 0.30/1.30) = 4.6154$ %, so **the value of sculpting rises with the tax rate**, which is a jurisdictional matter and must be checked with local tax advice rather than assumed (Domain 9's treatment of deductibility, and the counsel pointer there). The **sculpted year-one CFADS of 6,358,990 is lower than the base case's 6,384,000**, because a smaller loan generates less interest and therefore a smaller shield — a reviewer who sculpts against a [CFADS](#) line computed on the original debt has over-sized the facility, and this is the commonest error in sculpted models. And the sculpted profile here **declines** (4,891,531 down to 4,562,811), which is the opposite of the back-ended shape most practitioners associate with sculpting: the shape follows the cash, and Kestrel's cash falls because its tax shield amortises. The cautions are that a sculpted schedule is **computed on a forecast** — if revenue departs from 12,000,000 the profile is wrong in every remaining period, not just the current one, so the facility must say whether and how it is re-cut, and who pays for the exercise — and that an irregular profile is materially harder to hedge, because an interest-rate swap has to be written against an amortisation schedule that is no longer a standard shape (Domain 11, KA 11.3). Domain 7 (KA 7.A.2) works the same machinery against a contract cliff rather than a tax shield and reaches the same conclusion from the other direction: level service against uneven cash destroyed 11,185,896 of capacity there.




Fig 10.1.2 — Three ways to size the same project at 1

Two related shapes, and what they are really buying. A **cash sweep** applies a defined share of surplus cash above the required coverage to accelerated repayment — protecting lenders and shortening the effective tenor while reducing distributions; its mechanics and its effect on the loan's average life are worked at 10.3.3, and Domain 15 (KA 15.3.4) prices it as the cost of a consent. A **balloon or bullet** leaves principal at maturity, cutting periodic debt service and creating refinancing risk, exactly as Domain 3 (Case study B) priced it. A balloon deserves one piece of arithmetic here, because it is the structural answer to 10.1.2's shortfall: the balloon that would let 42,000,000 clear a 1.30× base-case test is $(42,000,000 - 4,910,769.23 \times 8.383844) \div 1.06^{-12} = \text{USD } 1,667,864$, only **3.97 %** of the facility. In other words the 828,877 capacity gap that Case study A closes with equity could instead be closed by deferring under four per cent of the principal to maturity — which is precisely why the next Knowledge Area asks what the coverage ratios do and do not notice when structure changes (Worked example 10.2.3).

AI in this KA

Model-building and scenario generation are legitimate machine work at this scale, and there is a specific failure mode here worth naming: an assistant asked to "size the debt" will apply the textbook **CFADS** definition rather than the facility's, and produce a defensible-looking number that the lender's own model will contradict. Verification is therefore definitional before it is arithmetical — check that the model's **CFADS** line implements the documented definition clause by clause, then recompute one period's ratio by hand. A sculpted schedule adds a second, purely arithmetical check that is worth automating: a machine-built sculpt must reproduce $(A/\lambda) \times AF(r(1 - T/\lambda), n)$ to the cent, and a solver that has merely iterated until the closing balance rounds to zero will not. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 10.1

Term	Meaning
CFADS	Cash available for debt service in a period, on the facility's documented definition.
Debt capacity	$CFADS / \text{target } DSCR \times AF(r, n)$; a function of cash, coverage, rate and tenor only.
Target $DSCR$	The coverage the lender requires; the divisor in sizing.
Sculpting	Setting each period's debt service to hold coverage constant against uneven cash.
Effective sculpting rate r^*	$r \times (1 - T/\lambda)$; the rate at which a sculpted profile discounts once the interest tax shield feeds back into CFADS.
Base-case vs minimum-period test	Coverage required in the period tested (usually year one) against coverage required in every period; on Kestrel the difference is 2,917,226 of debt.
Indifference stress s^*	$1 - \lambda_2/\lambda_1$; the cash stress at which a lower coverage requirement stops being a concession.
Cash sweep	Mandatory prepayment from a defined share of surplus cash.
Balloon / bullet	Principal deferred to maturity; lower periodic service, refinancing risk.

■ SAMPLE MCQS — KA 10.1

MCQ 10.1-A [10.1.2 · Application] CFADS is 6,384,000 per year; the lender requires a $1.30 \times DSCR$; the loan runs 12 years at 6 % ($AF = 8.383844$). Maximum debt is closest to:

- A. USD 42,000,000
- B. USD 41,171,123 ✓ CORRECT
- C. USD 53,522,460
- D. USD 36,143,689

Rationale: $6,384,000 / 1.30 = 4,910,769$; $\times 8.383844 = 41,171,123$. A is the requested amount, which the calculation rejects; C omits the coverage divisor (sizing on full CFADS, $6,384,000 \times 8.383844$); D uses a 10-year tenor ($AF = 7.360087$) instead of the 12-year tenor.

MCQ 10.1-B [10.1.1 · Analysis] Two advisers compute Kestrel's $DSCR$ as 1.39 and 1.27 from the same audited year. The most likely explanation is:

- A. one has made an arithmetic error
- B. they are applying different CFADS definitions — one before and one after working-capital movements — and only the facility's definition governs ✓ CORRECT
- C. they are using different interest rates
- D. one has used accounting profit instead of cash

Rationale: Domain 2's demonstration exactly: 6,984,000 versus 6,384,000 of CFADS on the same trading. The documented definition decides which is enforceable (10.1.1). D would produce a much larger discrepancy and is a different error.

MCQ 10.1-C [10.1.3 · Analysis] A project's cash flow ramps over its first five years. Against the same forecast, sculpted debt service compared with level debt service will:

- A. support less total debt, being more complex
- B. support more total debt, because no period is over-covered merely to protect the weakest one ✓ CORRECT

- C. support the same debt, since total cash is unchanged
- D. eliminate refinancing risk

Rationale: Level service is constrained by the weakest period; sculpting holds coverage constant and so uses the stronger periods (10.1.3). C ignores that capacity is set period by period, not in total; D confuses sculpting with tenor structure.

MCQ 10.1-D [10.1.3 · Application] CFADS before the interest tax shield is 5,880,000, the loan rate is 6.0 %, tax is 20 %, the tenor 12 years and the target coverage 1.30×. The maximum sculpted debt is closest to:

- A. USD 41,171,123
- B. USD 39,915,812 ✓ CORRECT
- C. USD 37,920,771
- D. USD 38,253,896

Rationale: $r^* = 0.06 \times (1 - 0.20/1.30) = 0.05076923$; $AF(0.05076923, 12) = 8.824924$; $5,880,000/1.30 \times 8.824924 = 39,915,812$ (10.1.3). A is the level, base-case answer on year-one CFADS of 6,384,000, which does not hold 1.30× in later periods; C ignores the tax shield's feedback and discounts at the full 6.0 % ($4,523,076.92 \times 8.383844$); D is level service sized on the minimum period, which sculpting beats by 1,661,916.

MCQ 10.1-E [10.1.2 · Evaluation] A lender offers to reduce the target DSCR from 1.30× to 1.25× provided the test is run on a case 5 % below base. The sponsor should conclude that:

- A. the offer is a concession worth 5 basis points of coverage
- B. the offer destroys 494,053 of capacity, because the indifference stress at these two ratios is only 3.8462 % ✓ CORRECT
- C. the offer is neutral, since ratio and case move in opposite directions
- D. the offer cannot be evaluated without knowing the rate and tenor

Rationale: $s^* = 1 - 1.25/1.30 = 3.8462 \%$, so a 5 % stress more than absorbs the relaxation: 40,677,069 against 41,171,123 (10.1.2b). A prices the ratio and ignores the case; C asserts an offset without testing its size; D is wrong because s^* depends only on the two ratios — rate and tenor scale both sides equally.

MCQ 10.1-F [10.1.3 · Evaluation] Sizing Kestrel at a 1.30× target gives 41,171,123 on the base-case test, 38,253,896 on the minimum-period test and 39,915,812 sculpted. An arranger asks the sponsor's adviser to confirm "the debt capacity". The soundest answer is:

- A. 41,171,123, since the base-case test is what the market conventionally applies
- B. 39,915,812, because sculpting is the technically superior structure
- C. that none of the three is "the" capacity: the figure is meaningless until the term states whether coverage is tested on the base case or in every period, and whether service is level or sculpted — so the sizing basis must be agreed before any number circulates ✓ CORRECT
- D. 38,253,896, because prudence requires the lowest of the available answers

Rationale: The three answers differ by 2,917,226 on identical cash flows, and the whole difference is definitional — it belongs in the term sheet, not in a footnote (10.1.3, Toolkit 10.T.4). A concedes the tested period without negotiating it, which is the easy half of the term. B recommends a structure before its documentation, modelling and re-cutting cost has been weighed, and before the facility has said who re-cuts a sculpted profile when the forecast moves. D mistakes conservatism for analysis

and surrenders the 1,661,916 that sculpting recovers without relaxing any period's requirement by a basis point.

MCQ 10.1-G [10.1.2 · Comprehension] A 1.30× target tested on the base case and the same 1.30× required in every period differ in that:

- A. they are the same requirement expressed in two ways
- B. the distinction matters only where cash flow is level
- C. the minimum-period test is the looser of the two, because it disregards the early years
- D. the first requires the coverage only in the period tested — conventionally the first full operating year — while the second requires it in the weakest period, so on any uneven profile the second is the tighter constraint on the same cash flow ✓ CORRECT

Rationale: One ratio, two tests; the gap between them is a property of the shape of the cash flow rather than of the ratio (10.1.2, 10.1.3). A ignores that a single-period test says nothing about the other eleven periods. C inverts the definition — the minimum-period test binds precisely because it is measured on the worst period. B reverses the condition: where cash is level the two coincide, and it is unevenness that separates them.

MCQ 10.1-H [10.1.2 · Evaluation] The sponsors have asked for 42,000,000 and the 1.30× target supports 41,171,123, leaving the **828,877** gap. Kestrel's offtake and concession both run 25 years and the facility is drawn for 12. Of the resolutions available, the one a leader should test **first** is:

- A. contribute the 828,877 as additional equity, which is the arithmetic residual and closes the gap with certainty
- B. argue the target down from 1.30× to the 1.2743 the requested amount delivers, since that is the coverage the project actually produces
- C. one additional year of tenor: at 13 years the same 1.30× target supports **43,473,483**, which clears the request with 1,473,483 to spare, and a thirteenth year is a far smaller ask of the tail than the fifteen years Case study A tried for ✓ CORRECT
- D. raise **CFADS**, which is the only lever that improves the lender's position as well as the sponsors'

Rationale: Debt capacity depends on cash, coverage, rate and tenor and on nothing else, so the question is which of the four is worth testing first — and tenor is the one bounded by the offtake and concession rather than by the sponsors' cheque, while equity is the residual that is contributed when the other levers fail (10.1.2). A is defensible and is the answer of last resort: it closes the gap by funding it, and it should be priced against a lever that might cost the sponsors nothing — which is exactly the sequence Case study A ran, where the tenor ask was made at **fifteen** years, refused against the tail lenders required, and the 828,877 was then funded as equity. That the lever failed on that transaction is not a reason to stop asking for it on this one, and it is the reason the caution below belongs with C. B asks a credit committee to abandon the margin its target exists to create, which is the request least likely to succeed and the one that damages the negotiation elsewhere. D is the defensible weaker course on the right principle: it does help both parties, and the uplift required is **128,526** a year — **2.0132 %** of **CFADS** — which has to come from a revenue or cost commitment somebody will have to make good, whereas the thirteenth year is a drafting change. The two cautions on C belong with it: the extra year must sit comfortably inside the tail lenders require, and at 42,000,000 over 13 years the year-one **DSCR** becomes **1.3456**, which is the number the committee will actually test.

■ SELF-CHECK — KA 10.1

1. Name the only four variables debt capacity depends on. — **CFADS**, target coverage, rate, tenor. (Equity contribution is the residual, not a driver.)

2. Why can two correct *DSCR* figures differ for one year? — Different *CFADS* definitions; only the facility's governs.
3. What does sculpting buy and what does it cost? — More debt against uneven cash; complexity in documentation, modelling and re-cutting.
4. State the effective rate at which sculpted debt discounts, and why it is below the loan rate. — $r(1 - T/\lambda)$; each dollar of interest returns T of tax saving into the *CFADS* the coverage test divides. On Kestrel, 5.076923 % against a 6.0 % loan.
5. When is a lower target *DSCR* not a concession? — Whenever the stress attached to it exceeds $1 - \lambda_2/\lambda_1$ — 3.8462 % for a move from 1.30× to 1.25×.
6. Which of the three sizing answers is "the" debt capacity? — None on its own: the term must say whether coverage is tested on the base case or in every period, and whether service is level or sculpted. The three answers on Kestrel are 41,171,123, 38,253,896 and 39,915,812.

KNOWLEDGE AREA 10.2

The coverage ratios

Topics: 10.2.1 *DSCR* · 10.2.2 *LLCR* and *PLCR* · 10.2.3 *ICR* and leverage · 10.2.4 reading a ratio set together.

10.2.1 *DSCR* — the period test

$$DSCR = CFADS \div \text{debt service} \quad (\text{debt service} = \text{interest} + \text{scheduled principal})$$

DSCR is a **period** measure: it asks whether this period's cash covers this period's obligations. It is the ratio lenders covenant on, test on defined dates, and lock up distributions against, because liquidity failures happen in periods, not in averages.

WORKED EXAMPLE**Worked example 10.2.1 — Kestrel's year-one position, and what breaks it.**

1. **Setup.** CFADS 6,384,000; debt service 5,009,635 (Domain 3's instalment). The facility carries a **1.20× covenant** and a **1.15× lock-up**. Compute the DSCR, the cash headroom to each threshold, and the position under a 20 % CFADS shortfall.
2. **Formula.** $DSCR = CFADS / \text{debt service}$. Threshold cash = debt service × threshold.
3. **Substitution.** $6,384,000 / 5,009,635$. Covenant cash $5,009,635 \times 1.20$; lock-up cash $\times 1.15$. Stress: $6,384,000 \times 0.80 = 5,107,200$, then $\div 5,009,635$.
4. **Result.** DSCR 1.2743. Covenant is breached below CFADS of 6,011,562; distributions lock up below 5,761,081; the project fails to cover debt service at all below 5,009,635. Under a 20 % CFADS shortfall, DSCR falls to 1.0195 — a **covenant breach**, though the project still pays.
5. **Interpretation.** The headroom is USD 372,438 of annual cash (6,384,000 – 6,011,562) — 5.8 % of CFADS. That is the sentence that belongs in a board paper, not "DSCR 1.27": it says how much cash may be lost before a covenant is breached, which is what management can actually monitor. And the stress case makes the crucial distinction between **breach and default on payment**: at 1.0195 the lenders are paid in full and the project is nonetheless in breach, with all the consequences of KA 10.4. Covenants bite long before cash runs out — by design, because that is when intervention still works.

10.2.2 LLCR and PLCR — the horizon tests

$$\begin{aligned} LLCR &= PV(\text{CFADS over the remaining loan life, discounted at the loan rate}) \div \text{debt outstanding} \\ PLCR &= PV(\text{CFADS over the remaining project life}) \div \text{debt outstanding} \end{aligned}$$

Where DSCR asks about a period, these ask about a **horizon**: is there enough total discounted cash ahead to repay what is outstanding? LLCR looks to the loan's maturity; PLCR looks to the end of the project's economic life, and therefore counts the cash that exists after the loan is due — which is why PLCR exceeds LLCR whenever the project outlives the loan.

WORKED EXAMPLE**Worked example 10.2.2 — Kestrel's three ratios, and an identity worth knowing.**

1. **Setup.** CFADS 6,384,000 per year (level), debt outstanding 42,000,000, loan rate 6 %, loan life 12 years, project life 25 years.
2. **Formula.** As above, with $AF(0.06, 12) = 8.383844$ and $AF(0.06, 25) = 12.783356$.
3. **Substitution.** $LLCR = (6,384,000 \times 8.383844)/42,000,000$; $PLCR = (6,384,000 \times 12.783356)/42,000,000$.
4. **Result.** DSCR 1.2743 · LLCR 1.2743 · PLCR 1.9431.
5. **Interpretation.** LLCR equals DSCR exactly — and that is not a coincidence but an **identity**: when CFADS is level and debt service is an annuity at the discount rate used, the two ratios must coincide, because both are the same cash divided by the same present value. A reviewer should use it as a check: level-cash models whose DSCR and LLCR differ contain an inconsistency (usually a discount rate that is not the loan rate, or a CFADS line that differs between the two calculations). Where cash is not level the ratios diverge, and the divergence is informative — LLCR above DSCR means the weak period is early and later cash is stronger. PLCR's 1.9431 says something different again: substantial value exists beyond the loan's maturity, which is what makes a **tail** and supports refinancing (Domain 15). Lenders nevertheless rely on PLCR least, because cash beyond their maturity is cash they have no contractual claim on. There is a wider version of the identity, and it is the most useful thing in this Knowledge Area. Sculpting sets $DS(t) = CFADS(t)/\lambda$, so the debt it supports is $PV(CFADS)/\lambda$, which rearranges to $\lambda = PV(CFADS) \div \text{debt}$ — **the LLCR**. In words: **the constant DSCR that sculpting can deliver at a given debt level is the LLCR of that debt level**, and the level-cash case above is simply the special case where the sculpted profile happens to be an annuity. That gives the reviewer a fast reading of any coverage pack. Where LLCR exceeds the minimum DSCR, the gap is the coverage that a sculpted profile could recover; where the two are equal, the schedule is already optimally shaped and no re-cutting will help. On Kestrel's declining bank case the LLCR at 42,000,000 is Domain 6's **1.2395** against a minimum DSCR of **1.1851** — a gap of 0.0544 of coverage lying idle in the early years. One qualification keeps this honest: the identity is exact only where CFADS is independent of the schedule. Kestrel's is not, because of the interest tax shield, so the constant coverage a sculpted 42,000,000 actually delivers is **1.2387** rather than 1.2395 — the eight-basis-point difference being the shield the smaller early balances no longer generate. A reviewer who quotes LLCR as the achievable sculpted coverage in a tax-paying structure is right to two decimal places and wrong in principle, and should say which number is which.

10.2.3 ICR and leverage

$ICR = EBIT \text{ (or EBITDA)} \div \text{interest}$ — an **accounting** coverage measure that ignores principal entirely. Domain 2 computed Kestrel's EBIT-based interest cover at 2.02× and, on EBITDA, **2.98×**. Leverage measures — debt/EBITDA, gearing — describe the balance sheet: Kestrel's 42,000,000 debt against 18,000,000 equity is **2.33:1**, the 70/30 structure of Domain 1.

Why project lenders covenant on DSCR rather than ICR: ICR can look comfortable while principal goes unpaid, and it is computed on accounting figures exposed to the classification judgments Domain 2 (Case study B) showed can flip a covenant without any change in cash. ICR appears mainly in corporate facilities and as a secondary project covenant.

WORKED EXAMPLE**Worked example 10.2.3 — three shapes of the same loan: what repayment structure can move, and what it cannot.**

- Setup.** The same 42,000,000 at 6.0 % over 12 years, against level CFADS of 6,384,000, in three repayment shapes. **A — fully amortising:** the annuity instalment of 5,009,635.23. **B — 25 % balloon:** 10,500,000 repaid at maturity, the balance amortised by level payments. **C — bullet:** interest only, with the whole 42,000,000 at maturity. EBITDA 7,500,000, EBIT 5,100,000, year-one interest 2,520,000, $AF(0.06, 12) = 8.383844$, $1.06^{-12} = 0.496969$. Compute each structure's four ratios and say what a credit committee should read from them.
- Formula.** For B, the level payment is $(\text{debt} - \text{balloon} \times DF(12)) \div AF(r, 12)$; for C it is $\text{debt} \times r$. $DSCR = CFADS \div \text{debt service}$; $LLCR = CFADS \times AF(r, 12) \div \text{debt}$; $PLCR = CFADS \times AF(r, 25) \div \text{debt}$; $ICR = EBITDA \div \text{interest}$.
- Substitution.** B: $(42,000,000 - 10,500,000 \times 0.496969) / 8.383844 = 4,387,226.43$. C: $42,000,000 \times 0.06 = 2,520,000$. LLCR and PLCR in every case: $6,384,000 \times 8.383844 / 42,000,000$ and $6,384,000 \times 12.783356 / 42,000,000$.
- Result.**

	A — amortising	B — 25 % balloon	C — bullet
Year-one debt service	5,009,635.23	4,387,226.43	2,520,000.00
DSCR	1.2743	1.4551	2.5333
LLCR	1.2743	1.2743	1.2743
PLCR	1.9431	1.9431	1.9431
ICR (on EBITDA)	2.9762	2.9762	2.9762
DSCR ÷ LLCR	1.0000	1.1419	1.9880
Payment due at maturity	5,009,635.23	14,887,226.43	44,520,000.00

- Interpretation.** Read the rows, not the columns. **DSCR almost doubles across the three structures and LLCR, PLCR and ICR do not move at all** — and nothing whatever has changed about the project, the cash it generates or the amount owed. That is the single most important caution in this Knowledge Area: **DSCR is a property of the repayment schedule as much as of the project, so a DSCR quoted without its amortisation profile is not a credit statement.** LLCR is immune because it discounts all the cash to maturity against all the debt outstanding, and is therefore blind to when principal is scheduled; ICR is immune because it never looked at principal in the first place. The diagnostic that falls out of the table is the ratio in the penultimate row. **Where debt service is a level annuity against level cash, DSCR ÷ LLCR = 1 exactly (10.2.2); any excess above 1 measures principal deferred beyond the periods being tested.** At 1.1419 it says a balloon of moderate size; at 1.9880 it says almost all of the principal sits at maturity. This is a reading, not a market metric, and it should be labelled as such in a paper — but it takes one division and it catches a structure whose comfortable coverage is manufactured rather than earned. Three consequences for practice. First, the **maturity row is the real risk statement:** structure C's DSCR of 2.5333 is arithmetically correct and professionally worthless beside a 44,520,000 payment the project must refinance, and structure B's apparently healthy 1.4551 conceals a year-twelve obligation of 14,887,226 — against which that year's DSCR, on the same 6,384,000 of cash, is **0.4288**. Second, **this is why lenders covenant on a ratio set**

rather than on DSCR alone, and why 10.A.2's discipline on stating the refinancing assumption is not optional: a balloon converts a credit question into a market question, and the market is not a party to the facility. Third, the honest converse — **balloons are not a defect**. They match debt service to a genuine cash profile (a concession whose revenue ends, an asset whose residual value is real), they are cheaper than the equity they displace, and 10.1.3's 1,667,864 balloon would have closed Kestrel's sizing gap for a deferral of 3.97 % of principal. The professional position is that a balloon must be sized against a stated refinancing plan and stress-tested, and that the **DSCR** it produces must never be reported without the maturity obligation beside it.

10.2.4 Reading a ratio set together

No single ratio is sufficient, and the four answer different questions:

Ratio	Question	Blind to
DSCR	Can this period pay?	Everything outside the period
LLCR	Is there enough cash to loan maturity?	Timing within the loan life
PLCR	Is there value beyond the loan?	The lender's lack of claim on it
ICR	Do earnings cover interest?	Principal; and exposed to accounting judgment

Kestrel's set — 1.27 / 1.27 / 1.94 / 2.98 — describes a project with adequate but unspectacular period coverage, no timing distortion, a substantial tail, and comfortable interest cover. The story a lender reads is: repayable, thin in a bad year, refinanceable. That reading, not any single number, is what credit committees actually decide on.

Where the capital structure has more than one debt tranche, the set has to be computed twice — on senior debt service alone and on total debt service — because project-level subordinated or mezzanine debt consumes the same **CFADS** the senior covenant measures. Domain 9 (KA 9.2.2 and Fig 9.2.1) works that arithmetic on Kestrel and is the reference; this domain's ratios are the senior-only case throughout.

WORKED EXAMPLE**Worked example 10.2.4 — four covenants, one stress: which one binds first?**

- Setup.** Kestrel's facility as mandated at **42,000,000** carries four financial covenants: $DSCR \geq 1.20\times$, tested annually; $LLCR \geq 1.15\times$; $\text{debt}/EBITDA \leq 6.00\times$; and $ICR \text{ on } EBITDA \geq 2.50\times$. Apply a single common stress — a fall in revenue from the base 12,000,000, with cash operating cost partly fixed as this domain's opening relation specifies — and find the fall at which each covenant is first crossed. Year-one interest 2,520,000; debt service 5,009,635.23; year-twelve **CFADS** 5,936,713 (Domain 6); the present value of **CFADS** over the loan life at the loan rate **52,060,092**; $AF(0.06, 12) = 8.383844$.
- Formula.** A revenue fall of x reduces **CFADS** by $0.75 \times 12,000,000 \times x = 9,000,000x$ and **EBITDA** by $0.9375 \times 12,000,000 \times x = 11,250,000x$; interest is unchanged. Set each covenant to equality and solve for x : $(CFADS - 9,000,000x)/DS = 1.20$; $(PV - 9,000,000x \times AF)/\text{debt} = 1.15$; $\text{debt}/(EBITDA - 11,250,000x) = 6.00$; $(EBITDA - 11,250,000x)/\text{interest} = 2.50$.
- Substitution.** $DSCR$ (year one): $(6,384,000 - 9,000,000x) = 6,011,562.28$. $DSCR$ (year twelve): $(5,936,712.85 - 9,000,000x) = 6,011,562.28$. Leverage: $7,500,000 - 11,250,000x = 42,000,000/6 = 7,000,000$. $LLCR$: $52,060,092.41 - 9,000,000x \times 8.383844 = 1.15 \times 42,000,000 = 48,300,000$. ICR : $7,500,000 - 11,250,000x = 2.50 \times 2,520,000 = 6,300,000$.
- Result.**

Covenant	Threshold in its own units	Revenue fall that breaches it	Revenue at the trigger
$DSCR \geq 1.20\times$ (year twelve)	CFADS 6,011,562	already breached, by 74,849	12,099,799 needed
$DSCR \geq 1.20\times$ (year one)	CFADS 6,011,562	4.1382 %	11,503,416
$\text{debt}/EBITDA \leq 6.00\times$	EBITDA 7,000,000	4.4444 %	11,466,667
$LLCR \geq 1.15\times$	PV(CFADS) 48,300,000	4.9833 %	11,402,010
$ICR \geq 2.50\times$	EBITDA 6,300,000	10.6667 %	10,720,000

- Interpretation.** Four results, in ascending order of usefulness. First, the operational one: **on the mandated facility the binding covenant is not merely the tightest, it is already breached** — Domain 6's year-twelve **DSCR** of 1.1851 is 74,849 of cash short of the $1.20\times$ threshold, so revenue would have to run **0.8317 % above** base for the covenant to hold in every year. That figure is the arithmetic behind the 828,877 of resizing Case study A argues for on entirely different grounds, and it is why the facility did not close at 42,000,000. Second, the ranking: **the period test binds first and by a wide margin**. The year-one **DSCR** fails at a 4.1382 % revenue fall while **ICR** survives to 10.6667 % — two and a half times as much — which is the quantitative version of 10.2.3's argument about why project lenders covenant on cash coverage. Third, and least expected, **the accounting leverage covenant binds second, at 4.4444 %**, only thirty basis points of revenue behind the **DSCR**. A treasury function monitoring **DSCR** alone would have three-tenths of a percentage point of warning before a second covenant fell, and leverage covenants are precisely the ones that move for reasons unconnected with cash — Domain 2 (Case study B) showed a classification judgment flipping an accounting covenant with no change in economics at all. Fourth, the caution that stops this from being over-read: **the ordering is a property of the thresholds, not a law of finance**. Set the **ICR** covenant at $2.90\times$ instead of $2.50\times$ and it binds first of all four, at a revenue fall of **1.7067 %**. Nothing about the project changed; the drafting did. So the professional output of this analysis is not "**DSCR** is the tight one"

but a table like the one above, recomputed for the facility actually signed, with the smallest number in the third column circled — and the sanity check that a facility whose covenants all trigger within a few tenths of a percentage point of each other has no graduated warning at all, which defeats the purpose set out in 10.4.1. Note finally that the **LLCR** covenant here is $1.15\times$ and so is the **DSCR** lock-up trigger of 10.4.2: the same number attached to two different tests on two different quantities. That coincidence is common in real facilities and a reviewer must never treat it as a link.

Which covenant binds first

Revenue fall from the 12,000,000 base that crosses each covenant on the mandated 42,000,000 facility.

The period cash test binds first; the worst period is already breached.




Fig 10.2.2 — Which covenant binds first

AI in this KA

Computing four ratios across a 25-year model is exactly what machines should do, and their outputs are dangerously plausible because the arithmetic is simple and the definitions are not. The invariants of 10.A.3 are the defence, and the **LLCR** = **DSCR** identity of 10.2.2 is the cheapest single check available on any level-cash model. Two further checks are worth building into any machine-produced coverage pack because they are one division each and they catch the errors a scanner misses: **DSCR** ÷ **LLCR**, which flags coverage manufactured by deferral rather than earned (10.2.3), and the **binding-covenant stress**, because a compliance dashboard that reports every covenant as "pass" has told the reader nothing about which one is closest to failing (10.2.4). Where an AI produces a covenant-compliance summary across a portfolio of facilities, the verification duty is to test it against the documents on a sample — because the failure will not be arithmetic, it will be a definition read from the wrong agreement.

■ KEY TERMS — KA 10.2

Term	Meaning
DSCR	$CFADS \div \text{debt service}$; the period test lenders covenant on.
LLCR	$PV \text{ of } CFADS \text{ to loan maturity} \div \text{debt outstanding}$; the loan-horizon test.
PLCR	$PV \text{ of } CFADS \text{ to end of project life} \div \text{debt outstanding}$; counts the tail.
Tail	Project life beyond loan maturity; supports refinancing.
ICR	$\text{Earnings} \div \text{interest}$; ignores principal, exposed to accounting judgment.
Headroom	Cash that can be lost before a covenant threshold is crossed.
$DSCR \div LLCR$	A reading, not a market metric: 1.0000 for a level annuity against level cash; any excess measures principal deferred beyond the periods tested (1.1419 for a 25 % balloon, 1.9880 for a bullet).
Binding covenant	The covenant crossed by the smallest common stress; identified by solving each covenant for the same stress variable, not by comparing ratio levels.

■ SAMPLE MCQS — KA 10.2

MCQ 10.2-A [10.2.1 · Application] $CFADS$ 6,384,000; debt service 5,009,635. The $DSCR$ is:

- A. 1.2743 ☒ **CORRECT**
- B. 0.7847
- C. 1.3941
- D. 2.5333

Rationale: $6,384,000/5,009,635 = 1.2743$. B inverts the ratio; C uses the pre-working-capital $CFADS$ of 6,984,000 (Domain 2's other definition); D divides by interest only.

MCQ 10.2-B [10.2.1 · Analysis] With a 1.20× covenant and $DSCR$ at 1.2743 on $CFADS$ of 6,384,000, the most useful figure for a board is:

- A. the $DSCR$ of 1.2743
- B. the annual cash headroom of USD 372,438 — 5.8 % of $CFADS$ — before the covenant is breached ☒ **CORRECT**
- C. the debt outstanding of 42,000,000
- D. the loan's remaining tenor

Rationale: Headroom states what may be lost before consequence, which management can monitor (10.2.1). The ratio alone does not convey magnitude, and C and D are facts, not exposures.

MCQ 10.2-C [10.2.2 · Analysis] A model with level $CFADS$ and annuity debt service reports $DSCR$ 1.27 and $LLCR$ 1.41. The soundest conclusion is:

- A. the project has a strong tail
- B. there is an inconsistency: with level cash and annuity service at the loan rate the two must be equal ☒ **CORRECT**
- C. the $LLCR$ is correct and the $DSCR$ is stale
- D. this is normal and requires no investigation

Rationale: The identity of 10.2.2 makes divergence a defect indicator — typically a discount rate that is not the loan rate, or differing $CFADS$ lines. A describes $PLCR$, not $LLCR$.

MCQ 10.2-D [10.2.3 · Analysis] Why do project lenders covenant primarily on **DSCR** rather than **ICR**?

- A. **ICR** is harder to compute
- B. **ICR** ignores principal repayment and rests on accounting figures exposed to classification judgment ☒ **CORRECT**
- C. **ICR** is only used for equity investors
- D. **DSCR** is required by accounting standards

Rationale: **ICR** can look healthy while principal is unpaid, and Domain 2 showed accounting classification flipping a profit-based covenant with no cash change. D confuses covenant drafting with accounting requirements.

MCQ 10.2-E [10.2.3 · Analysis] A 42,000,000 facility is restructured from a full amortisation to a 25 % balloon. Against level **CFADS** of 6,384,000 the **DSCR** rises from 1.2743 to 1.4551. The **LLCR** will:

- A. rise in the same proportion
- B. be unchanged at 1.2743, because it discounts all the cash to maturity against all the debt outstanding and is blind to when principal is scheduled ☒ **CORRECT**
- C. fall, because more debt is outstanding for longer
- D. become undefined, since there is no level instalment

Rationale: $\text{LLCR} = 6,384,000 \times 8.383844 / 42,000,000 = 1.2743$ on any repayment profile (10.2.3). A confuses the period test with the horizon test; C describes the interest cost, which **LLCR** does not measure; D confuses **LLCR** with **DSCR**, which does need a periodic debt-service figure.

MCQ 10.2-F [10.2.4 · Evaluation] A facility carries **DSCR** $\geq 1.20\times$ (breached by a 4.1382 % revenue fall), **debt/EBITDA** $\leq 6.00\times$ (4.4444 %), **LLCR** $\geq 1.15\times$ (4.9833 %) and **ICR** $\geq 2.50\times$ (10.6667 %). The most useful conclusion for the treasury function is:

- A. the **ICR** covenant is redundant and should be removed
- B. **DSCR** binds first, so monitoring **DSCR** is sufficient
- C. **DSCR** binds first but **debt/EBITDA** follows only 0.31 percentage points of revenue behind it, so both must be monitored — and the ordering would reverse if **ICR** were drafted at $2.90\times$ ☒ **CORRECT**
- D. the covenants are inconsistent and one of them must be wrong

Rationale: The gap between the first and second triggers is what determines whether monitoring one covenant is enough, and the ordering is a drafting outcome — at $2.90\times$ the **ICR** binds at 1.7067 % (10.2.4). A treats a loose covenant as a useless one; B ignores the 0.31-point gap; D mistakes different thresholds for an inconsistency.

MCQ 10.2-G [10.2.3 · Evaluation] A sponsor's credit paper reports a **DSCR** of 1.4551 on a 25 % balloon structure, against 1.2743 fully amortising, as evidence of a stronger credit. The soundest professional position is:

- A. the coverage is deferred rather than earned — $\text{DSCR} \div \text{LLCR}$ is 1.1419 and the year-twelve obligation is 14,887,226, against which that year's coverage on the same cash is 0.4288 — so the balloon is defensible only if it is sized against a stated refinancing plan, stress-tested, and reported with the maturity obligation beside the ratio ☒ **CORRECT**
- B. the paper is right: **DSCR** is the covenanted ratio, and 1.4551 is more comfortable than 1.2743
- C. balloons should not be used, because they convert a credit question into a market question
- D. the two structures are equivalent, since **LLCR**, **PLCR** and **ICR** are identical in both

Rationale: Nothing about the project, the cash it generates or the amount owed has changed, so a higher period ratio is information about the schedule and not about the credit (10.2.3). B reports an arithmetically correct figure that misdescribes the risk. C is the opposite failure of judgment: a balloon matched to a genuine cash profile is cheaper than the equity it displaces, and 10.1.3's 1,667,864 balloon would have closed Kestrel's sizing gap for a deferral of 3.97 % of principal. D uses the horizon ratios' immunity to conclude that nothing differs, when the thing that differs — 14,887,226 falling due on one date — is the entire exposure.

MCQ 10.2-H [10.2.2 · Comprehension] **PLCR** exceeds **LLCR** whenever a project outlives its loan because:

- A. **PLCR** discounts the same cash flow at a lower rate
- B. **PLCR** discounts **CFADS** to the end of the project's economic life while **LLCR** stops at loan maturity, so **PLCR** counts the tail — cash the lenders have no contractual claim on, which is why they rely on it least ✓ CORRECT
- C. **PLCR** is computed on **EBITDA** and **LLCR** on **CFADS**
- D. **PLCR** adds the asset's residual value to its numerator

Rationale: The two ratios differ only in the horizon of the numerator, and the extra cash is exactly the cash beyond the lenders' claim (10.2.2). A invents a rate difference; both discount at the loan rate. C confuses **PLCR** with **ICR**, which is the accounting measure. D adds a terminal value that neither ratio contains.

■ SELF-CHECK — KA 10.2

- When must **LLCR** equal **DSCR**? — Level **CFADS** with annuity debt service discounted at the loan rate; divergence signals an inconsistency.
- Why do lenders rely least on **PLCR**? — It counts cash beyond their maturity, on which they have no contractual claim.
- State Kestrel's headroom to covenant in cash terms. — USD 372,438 per year, 5.8 % of **CFADS**.
- Which ratios does repayment structure move, and which does it not? — It moves **DSCR** only; **LLCR**, **PLCR** and **ICR** are unchanged across full amortisation, balloon and bullet on the same debt and cash.
- What does the gap between **LLCR** and the minimum **DSCR** tell you? — Approximately the coverage a sculpted profile could recover — 0.0544 of coverage on Kestrel's bank case — exactly where cash is independent of the schedule, and to within eight basis points where a tax shield is present.
- How is the binding covenant identified? — By solving every covenant for the same stress variable and comparing the stresses, never by comparing ratio levels or headroom in the ratios' own units.

KNOWLEDGE AREA 10.3

Reserve accounts and the debt-service schedule

Topics: 10.3.1 the reserve family · 10.3.2 sizing a debt-service reserve · 10.3.3 the schedule and the waterfall's top.

10.3.1 The reserve family

Coverage ratios measure adequacy on a forecast; reserves provide liquidity when reality departs from it. The standard family:

Reserve	Purpose	Typical sizing
Debt service reserve (DSRA)	Bridge a short cash shortfall so scheduled service is paid	3–12 months of debt service
Maintenance reserve (MRA)	Fund lumpy major maintenance without a cash spike	Forward-looking schedule of major overhauls
Insurance / proceeds account	Hold claim proceeds for application per the documents	Event-driven
Distribution / lock-up account	Hold cash that fails a distribution test	Event-driven (KA 10.4)

A reserve is not a covenant substitute: it buys **time**, which converts a liquidity failure into a negotiation. Its cost is that funded cash is not distributed — which is precisely why sponsors argue for smaller reserves and lenders for larger ones, and why the negotiation is really about how long the lenders want before they must act.

Maintenance-reserve sizing is worked in full elsewhere and is not repeated here: Domain 8 (Worked example 8.1.3) prices Kestrel's lifecycle programme at a present value of **6,881,021**, derives the economically equivalent level charge of **644,606** a year, and shows that without a reserve the membrane-replacement year's **DSCR** collapses to **0.4561** — a payment default, not a covenant breach. Three points from that arithmetic belong in a coverage discussion. The level charge is **not** the deposit schedule: the money must be in the account before the first overhaul falls due, which usually means either a higher early contribution or an opening balance funded at close, and that difference is a real requirement in the sources and uses (Domain 14). Whether the charge sits **above or below CFADS** is a definitional negotiation of exactly the kind 10.1.1 warns about, and it decides whether the reserve protects the coverage ratio or merely the payment. And a reserve converts a covenant event into a **distribution** event, which is the trade in one sentence: the 600,000 a year Kestrel actually charges is **77.5 %** of its base-case dividend (Domain 15, KA 15.2.2).

10.3.2 Sizing a debt-service reserve

WORKED EXAMPLE

Worked example 10.3.2 — how much time does Kestrel's DSRA buy?

1. **Setup.** Annual debt service **USD 5,009,635**. The facility requires a **six-month DSRA**. **CFADS** is 6,384,000 in the base case. How much must be funded, and what shortfall does it absorb?
2. **Formula.** $DSRA = \text{debt service} \times \text{months}/12$. Absorbable shortfall = $DSRA \div \text{debt service}$, as a fraction of a period's obligation.
3. **Substitution.** $5,009,635 \times 6/12$.
4. **Result.** DSRA **USD 2,504,818**. It covers **half** of one year's debt service — meaning the project can absorb a **CFADS** collapse to as low as **2,504,818** (39 % of base case) in a single year and still pay in full.
5. **Interpretation.** Express the reserve as the shortfall it survives, not as a number of months: six months of debt service sounds procedural, while "we can lose 61 % of one year's cash and still pay" is a risk statement a board can weigh. Note what it does not do — it does not prevent the **covenant breach** (**DSCR** would be far below 1.20 in that year), so the reserve buys payment continuity and time to negotiate, not compliance. That distinction is the practical content of KA 10.4. The same arithmetic gives the reserve negotiation a price, which is what turns "three months or six?" from a preference into a decision. Tolerance to a **CFADS** shortfall with m months funded is $1 - DS \times (1 - m/12) \div CFADS$, so on Kestrel it runs **21.5283 %** with no reserve, **41.1462 %** at three months and **60.7641 %** at six. Because the expression is linear in m , **each additional month buys exactly 6.5393 percentage points of cash tolerance and costs 417,470 of funded cash** — that is **63,840 of cash per percentage point of tolerance**, and it is the figure to put beside a lender's request for a twelfth month. Two cautions on over-applying it. The tolerance is a **single-year** measure: a reserve drawn in one year must be replenished before distributions resume (10.3.3), so a two-year shortfall of half the size is a far worse event than a one-year shortfall of the whole, and the linear rule says nothing about it. And the tolerance is only meaningful against the **project's own downside case**: six months is the market convention and twelve is common through a ramp-up, but the month count worth paying for is the one whose tolerance covers the stress the sponsor and the lender have already agreed is plausible (Domain 11's allocation work, Domain 7's demand cases).

WORKED EXAMPLE**Worked example 10.3.2b — funding the reserve: equity, debt or a letter of credit.**

1. **Setup.** Kestrel must have **2,504,818** in its DSRA at first drawdown. Three routes are on offer. **Equity:** the sponsors fund it in cash at close; the account earns a deposit rate of **3.00 %** (Domain 15, KA 15.4) against a cost of equity of **15.42 %** (Domain 9, KA 9.1.3). **Debt:** the facility is increased by the same amount, at 6.0 % with tax relief at 20 %. **Letter of credit:** an acceptable bank issues an LC in favour of the security trustee for an annual fee, and no cash is funded at all. Price each route and identify the breakeven LC fee.
2. **Formula.** Equity carry = reserve $\times$ (cost of equity – deposit rate). After-tax debt cost = reserve $\times r \times (1 - T)$. LC cost = reserve $\times$ fee rate. Breakeven fee = the rate at which the LC cost equals the route it displaces. For the debt route, the coverage consequence is that the reserve consumes capacity: capex funding available = debt capacity – reserve.
3. **Substitution.** Equity: $2,504,817.62 \times (0.1542 - 0.0300)$. Debt: $2,504,817.62 \times 0.06 \times 0.80$. LC at a market rate of 1.25 %: $2,504,817.62 \times 0.0125$. Capacity: $41,171,123 - 2,504,818$.
4. **Result. Equity carry USD 311,098 a year. After-tax debt cost USD 120,231 a year** — but the 2,504,818 comes out of the 41,171,123 the project can borrow at 1.30 $\times$, leaving only **38,666,305** for capex and widening the equity requirement against the funding plan's 42,000,000 of senior debt from 828,877 to **USD 3,333,695. LC at 1.25 %: USD 31,310 a year**, saving **279,788** a year against the equity route — **USD 2,108,505** of present value at 8 % over the loan life. The **breakeven LC fee is 12.42 %** a year.
5. **Interpretation.** The breakeven fee is the result that decides the question, and its size is the point: **letter-of-credit pricing is not remotely close to 12.42 %**, so wherever the facility permits it, an LC-backed reserve is the sponsor's answer and the negotiation is about the LC's terms rather than its price. The debt route looks cheapest per dollar and is the trap: **it does not avoid the equity requirement, it relocates and enlarges it**, because a reserve funded from a coverage-constrained facility displaces capex debt one for one — 2,504,818 of reserve costs 2,504,818 of capex borrowing and therefore 2,504,818 of additional equity, on top of the 828,877 that Case study A already had to find. That is a general result for any structure sized on coverage rather than on cost: **inside a binding coverage constraint every use of debt competes with every other use at par**, which is why sources and uses must be agreed before reserve levels are (Domain 14, KA 14.1). Three qualifications keep the LC answer honest. An LC **substitutes bank credit risk for cash**, so the lenders will require an issuer of specified standing and a replacement obligation if it is downgraded — the sponsor has therefore bought a cheaper reserve and sold a contingent obligation to refinance it at the worst possible moment. An LC **consumes the sponsor's own credit lines**, an opportunity cost that appears nowhere in the fee and can be larger than it for a sponsor with limited headroom. And whether the LC is a demand instrument or a documentary one, when it may be drawn, how long it must run and what happens on expiry are **enforceability-sensitive drafting matters that differ by jurisdiction and by issuing bank** — a point for qualified counsel, not for a model. The reviewer's check across all three routes is the same: the reserve must appear in the **uses** of funds as well as in the operating cash flow, which is exactly the class-one model-audit finding Domain 13 (Worked example 13.2.3, finding F-03) prices at 2,504,818 of unfunded requirement.

10.3.3 The schedule and the waterfall's top

The **debt-service schedule** is Domain 3's amortisation table with a purpose: it fixes the obligations each coverage test is measured against. Kestrel's year one — interest 2,520,000, principal 2,489,635,

total 5,009,635 — is the denominator of the **DSCR**, and its accuracy is therefore load-bearing for covenant compliance.

The schedule sits inside the **cash waterfall** (built fully in Domain 15), whose ordering is the whole security architecture in miniature: operating costs, then taxes, then **senior debt service**, then reserve top-ups, then subordinated debt, then — only if every test passes — distributions to equity. Two consequences follow for a leader. **Equity is paid last, and only by permission** — which is the economic meaning of subordination. And **the reserve top-up sits above distributions**, so a depleted reserve is refilled before shareholders see anything; a sponsor forecasting distributions without modelling reserve replenishment has forecast cash that is contractually unavailable. The magnitude is easy to underestimate. Kestrel's base-case cash available for distribution is 774,364.77 a year (Domain 15, KA 15.2.3), so a DSRA drawn by **2,009,635** — the gap in the bad year of MCQ 10.3-B — takes **2.5952 years** of the entire dividend to replace. One year of shortfall therefore buys roughly two and a half years of distribution drought, before any covenant or lock-up test has been applied at all; Domain 15 (KA 15.2.4) prices what a drought of that length does to an equity return.

WORKED EXAMPLE

Worked example 10.3.3 — a cash sweep, and the average life the lender is really buying.

1. **Setup.** Kestrel's facility as signed: 42,000,000 at 6.0 %, level instalment 5,009,635.23 over 12 years, [CFADS](#) 6,384,000, maintenance-reserve charge 600,000, so cash available for distribution is **774,364.77** a year (Domain 15, KA 15.2.3). The lenders require a **50 % cash sweep**: half of the cash that would otherwise be distributed is applied to mandatory prepayment, in addition to the scheduled instalment. Compute when the loan retires, the reduction in the loan's **weighted average life**, the interest saved, and what the sweep costs equity in timing.
2. **Formula.** Sweep per period = 50 % × distributable cash. Each period the balance rolls forward as $B(t) = B(t-1) \times (1 + r) - \text{instalment} - \text{sweep}$, with the final payment truncated to the balance outstanding. Weighted average life = $\sum t \times \text{principal}(t) \div \sum \text{principal}(t)$, in years. Interest = total paid – principal.
3. **Substitution.** Sweep $774,364.77/2 = 387,182.39$; total annual application $5,009,635.23 + 387,182.39 = 5,396,817.62$. Roll the balance forward from 42,000,000 until it is extinguished; compute the two average lives from the two principal profiles.
4. **Result.** The loan **retires in year 11**, with a final payment of **4,326,132.35** in place of the scheduled 5,009,635.23. **Weighted average life falls from 7.1887 years to 6.4660 years**, a reduction of **0.7227 years**. Total interest falls from **18,115,622.76** to **16,294,308.50** — a saving of **USD 1,821,314**. Equity pays **387,182.39** a year for ten years, **3,871,824** in total, and gets back **683,502.88** more than base in year eleven plus the whole of year twelve's avoided debt service of **5,009,635.23**; discounted at Domain 4's 8 % the timing costs equity **USD 315,488** of present value.
5. **Interpretation.** The lender's benefit is best stated as the **average life**, not the maturity date, and this is why: the facility's stated tenor is unchanged at twelve years, the maturity is unchanged until the year the loan happens to extinguish, but the weighted average time the lenders' money is at risk falls by **0.7227 years — 10.05 % of the exposure period**. Average life is the measure a credit committee prices margin against and a treasury desk uses to set the swap notional profile, and a sweep is best described to both as an average-life reduction rather than as "prepayment protection". The **1,821,314 of interest saved is a benefit to equity, not to the lenders** — they lose it — which explains why sweeps are conceded in exchange for something else (a covenant reset, a longer tenor, a lower margin) rather than granted, and why Domain 15 (KA 15.3.4) treats a sweep as part of the price of consent and computes its breakeven share at 40.3334 % in that context. Note carefully what the equity arithmetic does and does not say. The present-value cost of **315,488** is modest against a 3,871,824 nominal diversion, because prepaying 6 % debt while discounting equity cash at 8 % is close to value-neutral in isolation; the real cost to a sponsor is not present value but **leverage and flexibility** — a swept structure de-gears faster, so the equity return falls even where present value barely moves, and cash committed to a sweep is cash unavailable for anything else in the year it arises. Three cautions. The result above assumes distributable cash is **level**; on Kestrel's actual declining profile the sweep shrinks year by year with the tax shield, so a model that applies a constant sweep has overstated the prepayment in every later period. A sweep interacts with the **coverage tests**, because the scheduled instalment is unchanged while the balance falls faster, so the [DSCR](#) improves through the loan life and the facility becomes progressively less likely to breach — a real second-order benefit that sponsors rarely claim in negotiation. And the drafting matters more than the percentage: whether the sweep is taken **before or after** reserve top-ups, whether it is computed on distributable cash or on cash above a coverage threshold, and

whether it is applied in order of maturity or pro rata, will change the answer above by more than moving the share from 50 % to 60 % would.

AI in this KA

Reserve and prepayment mechanics are arithmetically simple and structurally fiddly, which is exactly the profile on which a machine is useful and a machine's answer is dangerous. **Where it earns its place:** rebuilding a sweep or a sculpted profile across many periods and many scenarios, so that the average-life and retirement-year consequences of a proposed sweep share can be tabulated in minutes rather than days; reconciling reserve required-balance schedules against the facility's own tables period by period; and flagging periods in which a reserve top-up, a sweep and a distribution test compete for the same cash — the class of interaction that hand-built waterfalls get wrong. **Where it must not go:** it must not decide the **order** of the waterfall, because that order is a contractual reading and every mechanical answer downstream depends on it; it must not choose the reserve's funding route, which turns on a credit judgment about an LC issuer and on tax advice that is jurisdiction-specific (10.3.2b); and it must not assume the market convention where the document is silent — a silent document is a question for counsel, not a default. **Verification, concretely:** recompute one period of the waterfall by hand against the clause, including the top-up and the distribution test, and confirm that the reserve appears in the **uses** of funds as well as in the operating cash flow. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 10.3

Term	Meaning
DSRA	Debt service reserve; buys payment continuity and time, not compliance.
MRA	Maintenance reserve; smooths lumpy major maintenance (sized in Domain 8, KA 8.1.3).
Reserve tolerance	$1 - DS \times (1 - m/12) \div CFADS$; the single-year CFADS shortfall a reserve of m months survives — 6.5393 points per month on Kestrel, at 417,470 of funded cash each.
LC-backed reserve	A reserve satisfied by a letter of credit rather than cash; cheapest for the sponsor, and a substitution of bank credit risk for cash.
Weighted average life	$\sum t \times \text{principal}(t) \div \sum \text{principal}(t)$; the measure a sweep actually shortens (7.1887 → 6.4660 years on Kestrel).
Debt-service schedule	The obligation profile that coverage tests are measured against.
Cash waterfall	The contractual priority order for applying project cash.
Subordination	Junior claims paid only after senior tests pass.

■ SAMPLE MCQS — KA 10.3

MCQ 10.3-A [10.3.2 · Application] Annual debt service is 5,009,635 and the facility requires a six-month DSRA. The amount to be funded is:

- A. USD 5,009,635
- B. USD 2,504,818 ✓ CORRECT
- C. USD 1,252,409
- D. USD 417,470

Rationale: $5,009,635 \times 6/12 = 2,504,818$. A is twelve months; C is three; D is one month.

MCQ 10.3-B [10.3.2 · Analysis] In a year when CFADS falls to 3,000,000 against debt service of 5,009,635, a fully funded six-month DSRA means:

- A. no covenant breach occurs, since the reserve covers the gap
- B. scheduled debt service is paid in full from cash plus reserve, but the DSCR covenant is still breached ✓ **CORRECT**
- C. the lenders must accelerate the loan
- D. distributions may continue, since payment was made

Rationale: The reserve preserves payment (gap 2,009,635, within the 2,504,818 reserve) but the ratio is computed on CFADS, so the covenant fails (10.3.2). D is wrong because a breach triggers lock-up (KA 10.4), and C overstates the automatic consequence.

MCQ 10.3-C [10.3.3 · Recall] In the cash waterfall, reserve-account top-ups rank:

- A. below distributions to equity
- B. above distributions to equity ✓ **CORRECT**
- C. above senior debt service
- D. at the same level as operating costs

Rationale: Reserves are replenished before equity is paid (10.3.3); senior service ranks above the top-up, and operating costs above both.

MCQ 10.3-D [10.3.2 · Evaluation] A sponsor must satisfy a 2,504,818 DSRA. Cash funding costs the spread between a 15.42 % cost of equity and a 3.00 % deposit rate; an LC is available at 1.25 %. The strongest professional conclusion is:

- A. fund it from the senior facility, since after-tax debt at 4.80 % is the cheapest source
- B. use the LC: the breakeven fee is 12.42 % a year, so 1.25 % saves 279,788 a year, and the residual questions are the issuer's standing and the LC's drafting ✓ **CORRECT**
- C. fund it in cash, because lenders will not accept an LC
- D. the routes are economically equivalent because the reserve is returned at maturity

Rationale: Breakeven fee = $0.1542 - 0.0300 = 12.42\%$; at 1.25 % the LC costs 31,310 against an equity carry of 311,098 (10.3.2b). A is the trap: inside a binding coverage constraint the debt route displaces capex borrowing one for one and enlarges the equity requirement to 3,333,695. C asserts a market position that is simply untrue where the facility permits an LC. D confuses the return of principal with the cost of carrying it for twelve years.

MCQ 10.3-E [10.3.3 · Application] A 42,000,000 loan at 6.0 % with a 5,009,635.23 level instalment over 12 years is subjected to a 50 % sweep of 774,364.77 of annual distributable cash. The metric that best states what the lenders have gained is:

- A. the tenor, which is unchanged at 12 years
- B. the reduction in weighted average life from 7.1887 to 6.4660 years — 0.7227 years, or 10.05 % of the exposure period ✓ **CORRECT**
- C. the 1,821,314 of interest saved
- D. the retirement in year 11 rather than year 12

Rationale: Average life is the measure of exposure that margin is priced against and swap notional are set from (10.3.3). A is true and uninformative; C is a benefit to equity — the lenders forgo that interest; D is a single date rather than the exposure profile, and it moves with the cash case.

MCQ 10.3-F [10.3.3 · Evaluation] Lenders ask for a 50 % cash sweep. The sponsor's treasury recommends conceding it, on the ground that the present-value cost to equity is only 315,488 at 8 % against a 3,871,824 nominal diversion. The soundest position is:

- A. concede it: 315,488 is immaterial beside the 1,821,314 of interest the sweep saves the lenders
- B. concede it and present the 0.7227-year reduction in weighted average life as a benefit shared with the lenders
- C. refuse any sweep, since diverting distributable cash always destroys equity value
- D. concede it only in exchange for something, and only on drafting settled first: the present-value figure understates the cost because a swept structure de-gears faster, so the equity return falls even where present value barely moves **✓ CORRECT**

Rationale: Prepaying 6 % debt while discounting equity cash at 8 % is close to value-neutral in present value, which is precisely why present value is the wrong test here; the real costs are leverage, flexibility and cash unavailable in the year it arises — and whether the sweep is taken before or after reserve top-ups will move the answer by more than raising the share from 50 % to 60 % would (10.3.3). A misattributes the interest saving, which accrues to equity: the lenders forgo it. C denies a trade routinely worth making against a covenant reset, a longer tenor or a lower margin. B gives away the consideration the concession should have bought — the shorter average life is the lenders' benefit, not a mutual one.

MCQ 10.3-G [10.3.2 · Comprehension] A newly appointed director is told that a debt service reserve "protects the covenant". Restated correctly, what the reserve does is:

- A. buy time — it keeps scheduled debt service being paid through a short cash shortfall, converting a liquidity failure into a negotiation, while the coverage ratio, computed on CFADS, fails regardless **✓ CORRECT**
- B. raise CFADS in the year it is drawn, because the cash reaches the lenders
- C. reduce the required coverage ratio in proportion to the months funded
- D. stand in place of a covenant, which is why facilities carrying a reserve covenant looser ratios

Rationale: A reserve is a liquidity instrument and a covenant is a cash-flow test, so a fully funded six-month reserve preserves payment and does not prevent breach — Kestrel can absorb a collapse of CFADS to 2,504,818, some 39 % of base case, and still pay in full while the ratio is far below 1.20 (10.3.2). B is the error the definition of CFADS excludes: it counts cash the project found rather than cash it generated. C and D assert relationships between reserves and ratios that no facility creates — the month count is negotiated for how long lenders want before they must act.

MCQ 10.3-H [10.3.2 · Evaluation] In final negotiation the lenders ask for a **twelfth** month of debt service reserve in place of six. Each month buys **6.5393 percentage points** of single-year cash tolerance and costs **417,470** of funded cash — **63,840** per percentage point — and the facility permits an LC-backed reserve at a market fee of 1.25 % against a breakeven of 12.42 %. The soundest response is:

- A. refuse: six months is the market convention and twelve is excessive for an operating asset
- B. accept the twelve months and fund them from the senior facility, since after-tax debt at 4.80 % is the cheapest source
- C. accept the twelve months and satisfy them with a letter of credit: the quantity question is worth arguing only if cash must be funded, and at 1.25 % against a 12.42 % breakeven the incremental 2,504,818 of cover costs 31,310 a year rather than 311,098 **✓ CORRECT**
- D. offer nine months as a midpoint, which buys 80.3821 % of tolerance

Rationale: Twelve months takes single-year tolerance from **60.7641 %** to **100 %** — 39.2359 points for a further 2,504,818 — and the instrument, not the month count, is what determines whether that is expensive (10.3.2, 10.3.2b). A defends a convention against a request whose price the sponsor can make trivial. B is the trap the worked example exists to expose: inside a binding coverage constraint every use of debt competes with every other at par, so the reserve displaces capex borrowing one for one and enlarges the equity requirement. D is the defensible weaker course — a genuine midpoint, correctly computed, which spends negotiating capital on a quantity that has stopped mattering once the instrument question is settled, and buys back a month the lenders may value more than the sponsor gives up.

■ SELF-CHECK — KA 10.3

1. What does a DSRA actually buy? — Payment continuity and time to negotiate; not covenant compliance.
2. How should a reserve be expressed to a board? — As the shortfall it survives, not as a number of months.
3. Why must distribution forecasts model reserve replenishment? — Top-ups rank above equity, so unreplenished reserves make forecast distributions contractually unavailable; on Kestrel a 2,009,635 drawdown takes 2.5952 years of the whole dividend to replace.
4. What does each extra month of DSRA buy, and at what price? — 6.5393 percentage points of single-year cash tolerance, for 417,470 of funded cash: 63,840 per percentage point.
5. Why is funding a reserve from the senior facility rarely the cheap option it looks? — Inside a binding coverage constraint it displaces capex debt one for one, so it relocates and enlarges the equity requirement rather than avoiding it.
6. State what a cash sweep gives the lender and what it takes from equity. — A shorter weighted average life (0.7227 years on Kestrel); cash diverted in the years it arises, and faster de-gearing — the present-value cost, 315,488 at 8 %, understates the return effect.

KNOWLEDGE AREA 10.4

Covenants, default and cure

Topics: 10.4.1 covenant types · 10.4.2 distribution lock-up · 10.4.3 events of default and cure rights · 10.4.4 living with covenants.

10.4.1 Covenant types

Financial covenants are tested ratios — **DSR** (historic, forward-looking, or both), **LLCR**, sometimes leverage or **ICR** — measured on defined dates with defined inputs. **Information covenants** require reporting: management accounts, compliance certificates, model updates, budgets. **Positive covenants** require action (maintain insurance, comply with law, operate to standard). **Negative covenants** prohibit action without consent (no additional debt, no asset disposals, no material contract amendments, no change of control).

The design intent runs through all four: **give lenders visibility and control while the project is still fixable**. A covenant set that only bites at payment failure is worthless, because by then the options have gone (Domain 1's irreversibility point, in credit form).

Two mechanical distinctions matter in practice. **Historic versus forward-looking tests:** a backward test measures what happened; a forward test (often required for distributions) measures the projection, which introduces the question of whose projection and on what assumptions. **Cash-based versus accounting-based:** as Domain 2 established, cash-based tests are indifferent to classification judgments that can flip an accounting covenant with no change in economics — which is why project facilities lean on [DSCR](#).

WORKED EXAMPLE

Worked example 10.4.1 — historic against forward-looking, on the same facility.

- Setup.** Kestrel's facility tests $\text{DSCR} \geq 1.20\times$ annually on two bases: a **historic** test on the twelve months just ended and a **forward-looking** test on the twelve months about to begin, both computed on the same documented [CFADS](#) definition and the same debt service of 5,009,635.23. On the bank case [CFADS](#) declines from 6,384,000 to 5,936,713 over the loan (Domain 6), so the year-by-year figures around the end of the loan are: year 10 **6,040,690**, year 11 **5,990,216**, year 12 **5,936,713**. Which test breaches first, and by how much time?
- Formula.** At the test date ending year t : historic $\text{DSCR} = \text{CFADS}(t)/\text{DS}$; forward $\text{DSCR} = \text{CFADS}(t+1)/\text{DS}$. Threshold in cash = $1.20 \times 5,009,635.23 = 6,011,562$.
- Substitution.** End of year 10: historic $6,040,690/5,009,635.23$, forward $5,990,216/5,009,635.23$. End of year 11: historic $5,990,216/5,009,635.23$, forward $5,936,713/5,009,635.23$.
- Result.**

Test date	Historic DSCR	Historic result	Forward DSCR	Forward result
End of year 9	1.2153	pass	1.2058	pass
End of year 10	1.2058	pass	1.1957	breach
End of year 11	1.1957	breach	1.1851	breach
End of year 12	1.1851	breach	—	—

The forward test breaches **one full test date earlier** than the historic test.

- Interpretation.** The result generalises into a rule worth carrying: **on a declining cash profile the forward-looking test binds; on a rising profile the historic test binds; and which of them is "the tighter covenant" is therefore a property of the project's cash shape, not of the drafting.** Kestrel's profile declines because its interest tax shield amortises, so its forward test is the operative covenant and its historic test is decorative — while on Domain 6's sponsor case, where coverage rises from 1.2743 to 1.5940, the reverse is true and the historic test is the only one that could ever fail. A sponsor who negotiated hard on the forward test's assumptions without noticing which way its own cash slopes has negotiated the wrong clause. Three practical consequences. **The year the forward test buys is the whole point of it:** at the end of year ten the project is compliant on everything that has happened and in breach on what is about to happen, which is exactly the moment at which a cure, a waiver or an operational fix is still cheap — the design intent of this Knowledge Area, made arithmetic. **A facility with both tests effectively has the earlier of the two as its covenant**, so compliance certificates must report both, and a certificate that reports only the historic figure states compliance in the very period the facility fails. And **a forward test is a test on a forecast**, which raises the questions 10.A.1 sets out — whose model, on what assumptions, reviewed by whom — with real consequence here: the difference between breaching at the end of year ten and the end of year eleven is decided by

a number nobody can observe yet. That is why forward tests are normally accompanied by a defined basis of preparation and, often, by the lenders' technical adviser's assumptions prevailing on specified inputs.

10.4.2 Distribution lock-up

The **lock-up** is the mechanism that makes covenants effective without triggering default: if a distribution test fails, cash that would have gone to equity is trapped — held in a blocked account, applied to prepayment, or simply retained. Kestrel's structure has a **1.20× covenant** and a **1.15× lock-up trigger**, and the sequencing is deliberate: cash is retained before a breach becomes an event of default, so the lenders' exposure reduces while the project stabilises.

The economics for a sponsor are severe and often underappreciated: distributions deferred are equity returns deferred, and because equity returns are the residual (Domain 1's leverage arithmetic), a lock-up hits the equity IRR far harder than the ratio shortfall suggests. This is why lock-up thresholds are negotiated as hard as the covenant itself, and why a sponsor's model must show the distribution profile **after** lock-up tests, not before.

Three thresholds, not two. Kestrel's graduated set is the standard shape and was stated in cash at the head of this domain ($1.25\times \cdot 1.20\times \cdot 1.15\times$, or $6,262,044 \cdot 6,011,562 \cdot 5,761,081$ of annual CFADS). The distinction sponsors miss is between the first and the third. Failing the distribution condition means this period's cash waits, and is usually released when the test is next passed. Falling through the lock-up trigger means the cash stops being the sponsor's at all.

WORKED EXAMPLE

Worked example 10.4.2 — where the lock-up should sit, and which threshold actually bites.

- Setup.** Kestrel's mandated 42,000,000 facility, tested against Domain 6's bank case in which CFADS declines from 6,384,000 to 5,936,713 over the loan's twelve years. Debt service 5,009,635.23; maintenance-reserve charge 600,000, so cash available for distribution in year t is $CFADS(t) - 5,009,635.23 - 600,000$. Test three candidate thresholds — the 1.25 × distribution condition as drafted, the 1.20 × covenant, and the 1.15 × lock-up trigger — and report which years fail each, how much cash is affected and what it is worth.
- Formula.** Threshold in cash = threshold × debt service. A year is caught when $CFADS(t)$ falls below it. Cash affected = Σ distributable cash in the caught years; its value to equity = the same sum discounted at Domain 4's 8 % appraisal rate.
- Substitution.** Cash thresholds $5,009,635.23 \times 1.25 / 1.20 / 1.15$. Compare each year's $CFADS(t)$ against them; sum and discount the distributable cash of the caught years.
- Result.**

Threshold	Cash trigger	Years caught	Cash affected	Present value at 8 %
Distribution condition 1.25×	6,262,044	years 5-12 (eight of twelve)	USD 3,956,574	USD 2,165,274
Financial covenant 1.20×	6,011,562	years 11-12	707,658	—
Lock-up trigger 1.15×	5,761,081	none	nil	nil

The eight caught years are **57.61 %** of the 6,867,502 of distributable cash the loan period generates. The minimum **CFADS** over the loan is 5,936,713, which never reaches the $1.15 \times$ trigger.

1. **Interpretation.** The headline is uncomfortable and entirely typical: **on its own bank case the threshold that traps most of Kestrel's dividend is the one nobody negotiated.** The $1.15 \times$ lock-up trigger — argued over, documented, cited in every summary of the structure — never engages at all, because the project's coverage never falls that far. The $1.20 \times$ covenant catches two years. The $1.25 \times$ distribution condition catches **eight**, and 3,956,574 of cash with a present value of 2,165,274 against total equity of 18,000,000. A sponsor who modelled the covenant, or even the covenant and the lock-up, and reported a twelve-year dividend stream to its board has overstated distributable equity cash by more than half. Three professional consequences. First, **the distribution condition is the operative constraint in most healthy projects and the lock-up trigger is the operative constraint in sick ones** — they are not alternatives and they are not redundant, and a negotiation that spends its capital on the second while conceding the first has optimised for a state of the world the project is unlikely to reach. Second, **the graduated design is doing exactly what 10.4.1 says it should:** the thresholds engage in order, cash is retained long before breach, and by the time the covenant is crossed in year eleven the structure has already accumulated retained cash from seven earlier years. That is the mechanism working, not failing — the failure is in the sponsor's forecast, not in the drafting. Third, the caution about generalising this result: it is computed on a flat-revenue case whose coverage declines only because the interest tax shield amortises, which is a slow and entirely predictable slope. Put a revenue stress on top and the caught years extend earlier; put Domain 6's escalating sponsor case underneath and coverage rises to 1.5940 and **no** threshold is ever touched. So the output that belongs in a board paper is not a number but a **table of caught years per case**, and the discipline is to run the distribution profile through the tests on the lender's case, not the sponsor's. Domain 15 (KA 15.2.2 and 15.2.4) then prices what those trapped years do to an equity return, and shows the block account funding a later reserve shortfall out of the very cash the sponsor resented losing.

10.4.3 Events of default and cure rights

An **event of default** is a defined breach that entitles lenders to remedies — typically acceleration (all sums due), enforcement of security, or step-in. In practice lenders rarely accelerate a fundamentally sound project: enforcement destroys value and leaves them owning an asset. The realistic path is renegotiation from a much stronger position, which is why the consequences of default are usually commercial before they are legal.

Cure rights are the sponsors' contractual ability to fix a breach — most commonly an **equity cure**, injecting cash treated as **CFADS** (or applied to prepayment) so the ratio is restored. Facilities limit them: a maximum number of cures over the loan life, a maximum in consecutive periods, and rules on whether cure cash counts in the ratio or reduces debt. The negotiation matters because cure rights convert a technical breach into a funding decision the sponsor controls, and that is a meaningful option in a downside — Domain 8's optionality, in financing form.

WORKED EXAMPLE**Worked example 10.4.3 — the same breach, two drafting treatments, two cheques.**

- Setup.** Kestrel's mandated 42,000,000 facility breaches its $1.20 \times$ covenant in years eleven and twelve of the bank case: **CFADS** of **5,990,216** and **5,936,713** against a threshold of **6,011,562** (Domain 6 quantified the two shortfalls at 21,347 and 74,849). The sponsors hold unused cure rights. The facility could treat cure cash in either of the two standard ways: **(a)** the injected amount is **deemed to be CFADS** for the tested period, or **(b)** it is **applied to prepayment** and the tested debt service is reduced by the amount prepaid. Debt service 5,009,635.23; closing balance after year eleven 4,726,071; prepayments applied in reverse order of maturity as the facility provides. Size the cure under each treatment.
- Formula.** Treatment (a): $C = \lambda \times DS - CFADS$. Treatment (b): $P = DS - CFADS/\lambda$. Since $P = (\lambda \cdot DS - CFADS)/\lambda$, the two are related exactly by $P = C \div \lambda$ — the prepayment cure is the **CFADS** cure divided by the covenant level, because it works on the denominator, which the ratio itself levers. Under (b) the prepayment also reduces the following period's balance, interest and final payment, so the year-twelve requirement must be recomputed.
- Substitution.** Year 11, (a): $1.20 \times 5,009,635.23 - 5,990,215.54$. Year 11, (b): $5,009,635.23 - 5,990,215.54/1.20$. Then the year-twelve knock-on: balance $4,726,071 - 17,789 = 4,708,282$; new interest $\times 0.06$; new final payment $\times 1.06$; new **CFADS**(12) = $5,880,000 + 0.20 \times$ new interest; then $P_{12} = DS_{12} - CFADS(12)/1.20$.
- Result** (money to whole units).

	Treatment (a) — deemed CFADS	Treatment (b) — applied to prepayment
Year 11 cure	21,347	17,789
Year 12 debt service after the year-11 cure	5,009,635	4,990,779
Year 12 DSCR before curing	1.1851	1.1895
Year 12 cure	74,849	43,696
Total cash injected	USD 96,196	USD 61,485

Treatment (b) costs **34,711 less** — **36.08 % less** — for exactly the same compliance outcome. 5. **Interpretation.** The identity is the transferable result: **a prepayment cure is the deemed- CFADS cure divided by the covenant level, so treatment (b) always costs $1 - 1/\lambda$ less in the period cured** — 16.6667 % at a $1.20 \times$ covenant, 23.0769 % at $1.30 \times$, so the drafting is worth more the tighter the covenant. The rest of the saving here, and the larger part of it, comes from the second-order effect the table makes visible: **prepayment permanently reduces the debt, so it cures the current period and improves every later one.** The year-eleven cure lifts the year-twelve **DSCR** from 1.1851 to 1.1895 unaided, cutting the second cure from 74,849 to 43,696. On a declining coverage profile that compounding is worth having; on a single isolated breach it is worth nothing, which is why the identity, not the total, is the thing to remember. Four cautions belong with this arithmetic. **Lenders do not concede treatment (b) lightly**, because deemed **CFADS** leaves their exposure unchanged while prepayment reduces it — which is exactly why they prefer it, and why the negotiation is often about both limbs (cash in, and where it goes). **A cure computed to the last cent breaches again on any further slippage:** treatment (a) restores the year-twelve ratio to precisely 1.2000, so a single dollar of adverse variance re-breaches, which is why Case study B's sponsors deliberately injected 3,700,000 against a bare minimum of 3,550,000. **Cures are limited**

and consumed: a maximum number over the loan life, a maximum in consecutive periods, and rules on whether the cash counts once or permanently, so the cheapest cure is not always the right one — Domain 6 records the auditor rejecting an otherwise trivial 96,196 of curing on the ground that a structure designed to need a cure has consumed an option it should be holding in reserve. And **whether an injection is equity, subordinated debt or a shareholder loan changes its tax, accounting and insolvency treatment**, which is jurisdiction-specific and a matter for counsel and tax advice rather than for the model.

Waivers and amendments are the ordinary resolution of a breach: lenders consent, usually for a fee, often with tightened terms. Domain 15 handles the restructuring end of this spectrum.

10.4.4 Living with covenants

The leadership content of this domain is not the arithmetic but the operating posture it implies:

- **Know which covenant binds first.** Kestrel's binds at [CFADS 6,011,562](#) — 5.8 % below base case. That number, not the ratio, is the operational trigger, and it should sit on the management dashboard.
- **Forecast the tests, do not just report them.** A covenant tested next quarter on a forecast that is already visibly deteriorating is a conversation to have with lenders now, from a position of candour, rather than in three months from a position of breach.
- **Never surprise a lender.** The single most valuable asset in a covenant negotiation is a track record of early, accurate disclosure; a lender who learns of a problem from a compliance certificate will price that discovery into everything afterwards. (Domain 1's honesty asymmetry, applied to credit relationships.)
- **Model every threshold, not just the covenant — and expect the distribution condition to be the one that bites.** Sponsors are hurt by trapped cash long before default, and boards are routinely surprised by a distribution profile nobody tested; on Kestrel's own bank case the threshold that got the negotiating attention never engages at all (10.4.2).
- **Know which test basis binds, historic or forward.** It is decided by the slope of the project's cash, not by the drafting: a declining profile breaches the forward test a full test date before the historic one (10.4.1), which is the year in which a cure or an operational fix is still cheap. Report both figures on every compliance certificate.

AI in this KA

Covenant extraction and monitoring is a genuinely strong application: pulling defined terms, test dates and thresholds out of long agreements, and tracking actuals against them across a portfolio. Two boundaries. **Definitions are where models fail** — a covenant summary is only as good as its reading of the definitions clause, and that reading must be verified against the document before anyone relies on it (Domain 1's document-against-summary check). And **legal consequence is not decision support**: whether a set of facts constitutes an event of default, and what remedies follow, is a question for qualified counsel. Use AI to ensure no test is missed; never to conclude what a breach means.

■ KEY TERMS — KA 10.4

Term	Meaning
Financial / information / positive / negative covenant	Tested ratios · reporting · required acts · prohibited acts.
Historic vs forward-looking test	Measured on what happened vs on projection; which binds follows the slope of the cash profile, not the drafting.
Distribution condition	The coverage level above which cash may leave the structure at all (1.25× on Kestrel); usually the operative constraint in a healthy project.
Distribution lock-up	Trapping equity cash when a test fails, short of default; on Kestrel the 1.15× trigger, operative only in a sick project.
Event of default	Defined breach entitling lenders to remedies including acceleration.
Equity cure	Sponsor cash injected to restore a ratio; limited by the facility.
Cure identity $P = C \div \lambda$	A prepayment cure costs $1 - 1/\lambda$ less than a deemed-CFADS cure of the same breach — 16.6667 % at a 1.20× covenant — and also reduces later periods' debt service.
Waiver / amendment	Consented departure from terms, usually for a fee and tighter conditions.

■ SAMPLE MCQS — KA 10.4

MCQ 10.4-A [10.4.2 · Analysis] A facility has a 1.20× DSCR covenant and a 1.15× lock-up trigger. Why is the lock-up set below the covenant?

- A. it is a drafting convention with no economic effect
- B. so that cash is trapped only after a breach has occurred
- C. so that cash begins to be retained as coverage deteriorates, reducing exposure before a breach becomes an event of default ✓ CORRECT
- D. because lock-up and covenant tests use different CFADS definitions

Rationale: Graduated triggers act early while the project is fixable (10.4.2). B misreads the ordering; a lock-up below the covenant level means it engages as the ratio falls through it.

MCQ 10.4-B [10.4.3 · Application] A DSCR covenant is breached and the sponsors have an unused equity cure. The realistic sequence is:

- A. lenders accelerate and enforce security
- B. sponsors decide whether to inject cure cash; failing that, waiver or amendment negotiations follow, with acceleration a remedy of last resort ✓ CORRECT
- C. the breach is disregarded if payment was made
- D. the loan converts automatically to equity

Rationale: Acceleration destroys value for lenders too, so cure, waiver and amendment are the normal path (10.4.3). C ignores that breach and payment failure are distinct (10.2.1).

MCQ 10.4-C [10.4.4 · Analysis] Which figure best belongs on a management dashboard for covenant management?

- A. the current DSCR
- B. the CFADS level at which the binding covenant fails — 6,011,562, or 5.8 % below base case

✓ CORRECT

- C. the debt outstanding
- D. the loan's maturity date

Rationale: The operational trigger is the cash level, which management can influence and monitor (10.4.4). The ratio alone conveys no magnitude of headroom.

MCQ 10.4-D [10.4.3 · Application] A DSCR covenant of 1.20× is breached with CFADS of 5,990,216 against debt service of 5,009,635.23. Under the two standard treatments the cure required is:

- A. 21,346.73 whether the cash is deemed CFADS or applied to prepayment
- B. 21,346.73 if deemed CFADS; 17,788.94 if applied to prepayment, since the prepayment reduces the denominator and $P = C \div \lambda$ ✓ **CORRECT**
- C. 21,346.73 if deemed CFADS; 25,616.08 if applied to prepayment
- D. the breach cannot be cured with cash, only waived

Rationale: $C = 1.20 \times 5,009,635.23 - 5,990,215.54 = 21,346.73$, and $P = 5,009,635.23 - 5,990,215.54/1.20 = 17,788.94 = C/1.20$ (10.4.3). A ignores that the two treatments act on different sides of the ratio; C multiplies by the covenant instead of dividing — a nameable sign error that makes the prepayment route look dearer; D confuses a cure right with a waiver.

MCQ 10.4-E [10.4.2 · Evaluation] A facility has a 1.25× distribution condition, a 1.20× covenant and a 1.15× lock-up trigger. On the lenders' bank case the project's DSCR runs from 1.2743 down to 1.1851. The sponsor's negotiating priority should be:

- A. the 1.15× lock-up trigger, since it has the most severe consequence
- B. the 1.25× distribution condition, which catches eight of the twelve years and 3,956,574 of dividend, while the 1.15× trigger is never reached on this case ✓ **CORRECT**
- C. the 1.20× covenant, since breach is the event that matters
- D. all three equally, since they are tested on the same ratio

Rationale: The threshold that binds on the case being tested is the one worth negotiating capital on; here the lock-up trigger never engages (10.4.2). A optimises for a state the project does not reach on this case; C is the two-year problem rather than the eight-year one; D ignores that the same ratio crosses three different levels at three different times.

MCQ 10.4-F [10.4.1 · Evaluation] A facility tests DSCR on both a historic and a forward-looking basis. At the end of year ten the historic test passes at 1.2058 and the forward test fails at 1.1957. The compliance certificate reports the historic figure only. The soundest professional position is:

- A. the certificate is adequate: the historic figure is the only one that can be observed
- B. a facility with both tests effectively has the earlier of the two as its covenant, so a certificate reporting only the historic figure certifies compliance in the very period the facility fails; both figures must be reported, on an agreed basis of preparation for the forward test ✓ **CORRECT**
- C. only the forward figure should be reported, since the forward test is the tighter covenant on any project
- D. the forward test should be resisted altogether, because it tests a forecast nobody can observe

Rationale: On a declining coverage profile the forward test breaches a full test date earlier, and that test date is exactly when a cure, a waiver or an operational fix is still cheap — the design intent of the covenant set, made arithmetic (10.4.1). A treats observability as the criterion for disclosure. C overgeneralises: which basis binds follows the slope of the project's cash, and on Domain 6's rising sponsor case the historic test is the only one that could ever fail. D discards the year of warning the

forward test buys; the answer to a test on a forecast is a defined basis of preparation with stated prevailing assumptions, not removal of the test.

MCQ 10.4-G [10.4.3 · Evaluation] Kestrel's mandated 42,000,000 facility breaches its 1.20× covenant in years eleven and twelve of the bank case. Curing both breaches costs **96,196** if the cash is deemed to be **CFADS** and **61,485** if it is applied to prepayment. Counsel proposes spending the remaining negotiating capital on securing the prepayment treatment. The better judgement is:

- A. agree: 34,711 is a 36.08 % saving, and $P = C \div \lambda$ makes the drafting worth more the tighter the covenant
- B. disagree: cure rights are unlimited in number, so their cost is immaterial
- C. disagree: cure cash is always deemed to be **CFADS**, so there is nothing to negotiate
- D. the drafting point is real and minor: a facility whose **base case** needs a cure has consumed an option that should be held for a downside, so the capital belongs on the sizing — the year-twelve shortfall of 74,849 is the 828,877 resizing question in another form ✓ CORRECT

Rationale: The cure arithmetic is correct and answers the smaller question, while the facility is being sized to breach on its own base case — which is a capacity problem the cure conceals, and the ground on which Domain 6's model auditor rejected an otherwise trivial 96,196 of curing (10.4.3, 10.1.2). A is the defensible weaker course: the identity and the saving are both real, and both are small beside a structure that starts in breach. C asserts a single treatment where the domain describes two standard ones, and the negotiation is ordinarily about both limbs — cash in, and where it goes. B is false: cures are limited in number and in consecutive periods, and each one consumed is unavailable later.

MCQ 10.4-H [10.4.2 · Comprehension] A sponsor's board is told that the facility has "a 1.20× covenant and a 1.15× lock-up, so there are two levels to watch". The 1.25× distribution condition is not mentioned. The clearest statement of what the three thresholds do is:

- A. the distribution condition decides whether this period's cash may leave the structure at all, the covenant decides whether the facility is in breach, and the lock-up decides whether retained cash stops being the sponsor's — three different consequences at three different levels ✓ CORRECT
- B. the three are alternative drafting formulations of the same test, and only the lowest binds
- C. the distribution condition and the lock-up trigger are the same mechanism, one expressed as a ratio and the other as a cash figure
- D. the covenant is the operative constraint and the other two are consequences of breaching it

Rationale: The thresholds engage in order and do different things, which is what makes the design graduated: on Kestrel they sit at 6,262,044, 6,011,562 and 5,761,081 of annual **CFADS** (10.4.2). B denies the sequencing the structure depends on. C conflates two mechanisms whose difference is the whole point — failing the distribution condition delays this period's cash, while falling through the lock-up trigger stops the cash being the sponsor's. D reverses the order of engagement: cash is retained long before a breach becomes an event of default, and on Kestrel's own bank case the distribution condition catches eight of twelve years while the lock-up trigger never engages at all.

■ SELF-CHECK — KA 10.4

1. What does a lock-up achieve that a covenant alone does not? — It retains cash as coverage deteriorates, short of default, reducing exposure while the project is still fixable.
2. Why do lenders rarely accelerate a sound project? — Enforcement destroys value and leaves them owning the asset; renegotiation from strength is better.

3. What is the most valuable asset in a covenant negotiation? — A track record of early, accurate disclosure.
4. Distinguish the distribution condition from the lock-up trigger. — The first decides whether this period's cash may leave; the second decides whether the cash remains the sponsor's at all. On Kestrel, 1.25× and 1.15×.
5. Which test basis breaches first on a declining coverage profile, and what does that buy? — The forward-looking test, one test date earlier — the period in which a cure or an operational fix is still available.
6. State the cure identity and what it is worth. — $P = C \div \lambda$: a prepayment cure costs $1 - 1/\lambda$ less than a deemed-CFADS cure — 16.6667 % at 1.20× — and reduces later periods' debt service as well.

— Advanced topics — Domain 10

10.A.1 Forward-looking tests and whose forecast counts

A forward **DSCR** test measures a projection, which raises three questions the documents must answer: whose model, on what assumptions, and reviewed by whom. Facilities typically require the borrower's model updated to an agreed basis, sometimes with the lenders' technical adviser's assumptions prevailing on specified inputs. The practical consequence is that **assumption control becomes a covenant matter** — a sponsor who cannot defend an assumption cannot pass a forward test on it — and it is why Domain 13's model audit and Domain 6's model governance are contractual, not merely prudent. Worked example 10.4.1 gives that abstraction a price on Kestrel: the difference between breaching at the end of year ten and the end of year eleven turns entirely on a projected **CFADS** figure that nobody can yet observe, and the whole of the forward test's early-warning value — its one test date of notice — is bought with that unobservable number. Three drafting features are what make the trade acceptable rather than arbitrary, and a leader should look for all three: a **defined basis of preparation** (which case, which conventions, which vintage of assumptions); a **change protocol** stating who may alter an assumption between tests and on what evidence; and a **tie-break** naming whose assumption prevails on specified inputs, usually the lenders' technical adviser's on availability and degradation. A forward test without those three is not a covenant but an invitation to argue at the worst possible moment.

10.A.2 Refinancing, tails and mini-perms

Kestrel's **PLCR** of 1.9431 against an **LLCR** of 1.2743 quantifies its **tail** — the 13 years of project life beyond loan maturity. Tails are what make refinancing possible, and structures deliberately exploit them: a **mini-perm** (a short facility priced and documented in the expectation of refinancing, sometimes with punitive step-up margins if it is not) trades cheap early money for refinancing risk, which is Domain 3's Case study B arithmetic at facility scale. The leader's discipline is to state the refinancing assumption explicitly and stress it, because a plan that requires a functioning credit market at a specific date has embedded a market forecast in a financing structure.

10.A.3 The reviewer's coverage eye

Invariants to test on any coverage model: **CFADS** reconciles line-by-line to the facility's definition; the same **CFADS** line feeds **DSCR**, **LLCR** and lock-up tests; **LLCR equals DSCR where cash is level and service is an annuity at the loan rate** (10.2.2); $PLCR \geq LLCR$ whenever a tail exists; debt service

equals interest plus scheduled principal and ties to the amortisation schedule; the schedule's closing balance is zero at maturity and total principal equals the loan (Domain 3's checks); cash tax, not accounting tax, feeds **CFADS**; reserve movements are treated as the documents specify; every covenant has a modelled test date; and the model's minimum **DSCR** over the loan life is reported, not merely the average — because covenants are tested in periods, and an average conceals the one that breaches.

Six further invariants earned by this domain's worked examples, each cheap to test:

- **$DSCR \div LLCR = 1.0000$ for a level annuity against level cash**, and any excess measures principal deferred beyond the periods tested (1.1419 for a 25 % balloon, 1.9880 for a bullet). A coverage pack reporting a strong **DSCR** and a flat **LLCR** is reporting structure, not performance (10.2.3).
- **A sculpted schedule discounts at $r(1 - T/\lambda)$, not at r** . A sculpted model built by iterating until the closing balance looks like zero should reproduce $(A/\lambda) \times AF(r(1 - T/\lambda), n)$ to the cent; if it does not, the circularity has not converged (10.1.3).
- **A sculpted profile's final payment equals the level payment a minimum-period test would have imposed** — 4,562,811.13 on Kestrel. Two independent calculations that must agree.
- **CFADS used for sculpting must be the CFADS of the resized debt**, not of the original request: Kestrel's sculpted year-one **CFADS** is 6,358,990, not 6,384,000, because a smaller balance generates a smaller tax shield.
- **The binding covenant is found by solving every covenant for one common stress**, never by comparing headroom in each covenant's own units — and the answer changes with the thresholds, not with the project (10.2.4).
- **Every reserve appears in the uses of funds as well as in the operating cash flow**, whatever its funding route (10.3.2b; Domain 13, finding F-03).

— Industry variations — Domain 10

- **Contracted power and availability PPPs**. Revenue certainty supports the lowest coverage requirements (often 1.15–1.25× base case), long tenors and high gearing; **DSCR** is tested against a tightly defined **CFADS**.
- **Merchant power and commodities**. Coverage requirements rise sharply (1.5× and above), tenors shorten, and lenders size on stressed rather than base-case cash — often on a bank case using conservative price decks.
- **Transport concessions**. Patronage risk produces ramp-up profiles that make sculpting close to mandatory, and lenders commonly require larger reserves through the ramp.
- **Water and regulated utilities**. Regulatory reset cycles create step-changes in cash, so covenant testing and reserve sizing must straddle resets rather than assume continuity.
- **Digital infrastructure**. Shorter asset lives compress tails, so **PLCR** provides less comfort and structures rely more on contracted tenant credit and refinancing at a defined point.
- **Mining and resources**. The project life that **PLCR** measures is bounded by the **reserve**, not by the asset, so the tail is a physical quantity subject to its own technical dispute; coverage requirements are set well above infrastructure levels, sculpting follows the mine plan rather than a tax shield, and cash sweeps are close to universal because the lenders' objective is to be repaid out of the highest-grade years rather than across the life.

— Case study — Domain 10: the 828,877 that changed the structure (water)

Situation. Kestrel's sponsors sought USD 42,000,000 of senior debt against a base-case **CFADS** of 6,384,000. The lead bank's credit committee required a **1.30×** base-case **DSCR**.

The arithmetic. At 1.30×, sustainable debt service is 4,910,769, supporting $4,910,769 \times AF(0.06, 12) = 41,171,123$ — **828,877 short** of the request. At 42,000,000 the **DSCR** is 1.2743 and the **LLCR**, on level cash, is identically 1.2743.

The four levers, worked. Raise **CFADS**: the sponsors first proposed adding back the 600,000 working-capital movement to reach 6,984,000 and a 1.39× ratio — rejected, because the facility's own definition was struck after working capital (Domain 2's point, now with a price attached). Reduce required coverage: the bank agreed **1.25×** in exchange for a longer offtake term and a tightened lock-up at 1.15×, which on base-case cash lifts capacity to $6,384,000 / 1.25 \times 8.383844 = 42,817,968$ — apparently enough. But the bank sizes on its own **stressed case**, and at a **CFADS** 5 % lower (6,064,800) the same 1.25× supports only **40,677,069**, which is less than the 1.30× base-case answer. The concession was therefore worth less than it appeared, and this is the recurring trap in coverage negotiations: **a lower ratio applied to a lower cash case is not a concession**. Lengthen tenor: 15 years was unavailable against a 25-year concession with a required tail. Lower the rate: not negotiable in the market of the day.

The outcome. The facility closed at the sized maximum: **41,171,123** of senior debt — debt service $41,171,123 / 8.383844 = 4,910,769$, a base-case **DSCR** of exactly **1.30000**, which is what a credit committee documents when it has set a requirement and means it — with the residual **828,877 funded as additional equity**, a six-month **DSRA** (2,504,818), sculpted service against the declining coverage profile, and a 1.15× lock-up. Equity rose from 18,000,000 to **18,828,877**, gearing from 70/30 to **68.62/31.38** (debt/equity **2.1866:1**), and the sponsors' modelled **IRR** fell by roughly 40 basis points — the true price of the coverage requirement, paid in equity rather than argued away. Note that the 828,877 is not a new number: it is precisely the gap Worked example 10.1.2 computed at the top of this domain, which is the point. **The sizing arithmetic did not describe the negotiation; it determined its outcome**, and every hour spent arguing about the amount was spent arguing with a division. Domain 6 models this structure and Domain 15 operates it, both on the same 41,171,123.

What the domain teaches here. Debt capacity is arithmetic, and the negotiation is about its four inputs — not about the number itself. Every attempt to move the answer without moving an input (redefining **CFADS**, quoting a more flattering ratio) fails at the first competent review, and the attempt costs credibility that the later, genuine negotiation needs.

— Case study B — Domain 10: paid in full and in breach (transport)

Situation. A toll-road SPV entered its third operating year with patronage **12 % below forecast**. Because most of a road's operating cost is fixed, **CFADS** fell further than revenue: from a base-case 24,000,000 to **19,700,000**, a fall of **17.9 %** — the operating-leverage effect a sponsor should model rather than discover. Against debt service of 18,600,000 that is a **DSCR** of **1.0591**, versus a **1.25×** **covenant** and a **1.15×** **lock-up**. The **DSRA** (six months, 9,300,000) was fully funded and untouched.

What happened. Debt service was paid in full and on time, from operating cash alone. The project was nonetheless in breach of covenant from the first test date, distributions locked up automatically at the 1.15× trigger, and the sponsors — who had modelled distributions against the covenant rather than the lock-up — had budgeted dividends that were contractually unavailable. The board's initial

position, that "the lenders are being paid, so there is no problem", was precisely wrong and cost two months of credibility before the finance director corrected it internally.

How it resolved. The sponsors injected an equity cure of **3,700,000**, lifting cure-adjusted **CFADS** to 23,400,000 and the ratio to **1.2581×** — back above the covenant, and deliberately above the bare minimum of $18,600,000 \times 1.25 = 19,700,000 = \mathbf{3,550,000}$, because a cure computed to the last dollar breaches again on any further slippage. They used one of their two permitted cures, and agreed an amended covenant profile stepping from 1.15× to 1.25× over three years in exchange for a fee, a cash sweep of 50 % of surplus above 1.30×, and monthly rather than quarterly reporting. Patronage recovered to within 6 % of forecast by year five and the sweep retired debt ahead of schedule.

What the domain teaches here. Breach and payment failure are different events, and the covenant is designed to bite first — while cure, waiver and amendment are all still available. The sponsors' avoidable error was modelling the covenant and not the lock-up, which is the specific discipline of KA 10.4.2.

— Executive perspective — Domain 10

What a project finance director cannot delegate in this domain:

- **The **CFADS** definition.** Read it in the document, clause by clause, and confirm the model implements it. Every ratio the project will be judged on is built on that one term (Case study A).
- **The binding trigger in cash.** Not the ratio — the **CFADS** level at which the first covenant fails (6,011,562 for Kestrel, 5.8 % below base case), on the dashboard, owned.
- **The distribution profile after lock-up tests.** Boards are surprised by trapped cash, and the surprise is always avoidable (Case study B).
- **The minimum, not the average.** Minimum **DSCR** across the loan life is the covenant-relevant number; averages conceal the period that breaches.
- **Whether the coverage target is a base-case or an every-period test.** It is the single largest unstated term in a sizing negotiation: on Kestrel the two readings of the same $1.30 \times$ differ by **2,917,226** of debt, and sculpting recovers 1,661,916 of the difference without conceding a basis point (10.1.3).
- **What structure is being asked to do for the ratios.** A balloon or a bullet moves **DSCR** and moves nothing else; if coverage improved without the project changing, the improvement is deferral and the maturity obligation belongs in the same sentence (10.2.3).
- **The reserve's funding route.** Equity, debt or a letter of credit is a decision with a computable answer — 311,098 a year, a 2,504,818 displacement of capex borrowing, or a fee against a 12.42 % breakeven — and it is decided far too often by whoever drafted the term sheet (10.3.2b).
- **The refinancing assumption.** If the structure needs a market at a date, say so explicitly and stress it (10.A.2).
- **The relationship.** Early, accurate disclosure is the asset that determines the terms of every future waiver — and it is built before it is needed.

— Calculation exercises — Domain 10

Exercise 10.1 **CFADS** 9,200,000; target **DSCR** 1.35×; loan 10 years at 7 %. Compute maximum debt service and maximum debt. Solution. Max debt service $9,200,000/1.35 = \mathbf{6,814,815}$; **AF**(0.07, 10)

= 7.023582; max debt $6,814,815 \times 7.023582 = \text{USD } 47,864,408$. Common error: sizing on full CFADS ($9,200,000 \times 7.023582 = 64,616,950$), which omits the coverage requirement entirely.

Exercise 10.2 Debt outstanding 47,864,408; CFADS 9,200,000 level; loan life 10 years at 7 %; project life 20 years. Compute LLCR and PLCR, and verify the DSCR identity. Solution. $\text{LLCR} = (9,200,000 \times 7.023582) / 47,864,408 = 1.3500$; $\text{AF}(0.07, 20) = 10.594014$, $\text{PLCR} = (9,200,000 \times 10.594014) / 47,864,408 = 2.0363$. $\text{DSCR} = 9,200,000 / 6,814,815 = 1.35$ — equal to LLCR, as the identity requires with level cash and annuity service. Common error: discounting CFADS at the project's equity discount rate rather than the loan rate, which breaks the identity and the comparability.

Exercise 10.3 A facility has debt service of 6,814,815, a 1.20× covenant and a 1.10× lock-up. State the CFADS levels at which each triggers, and the headroom from a base case of 9,200,000. Solution. Covenant at $6,814,815 \times 1.20 = 8,177,778$; lock-up at $\times 1.10 = 7,496,297$. Headroom to covenant $9,200,000 - 8,177,778 = 1,022,222$, or 11.1 % of base-case CFADS. Common error: quoting headroom in ratio points (0.15×), which conveys no magnitude.

Exercise 10.4 CFADS falls 25 % from 9,200,000. Compute the DSCR against debt service of 6,814,815 and state whether the 1.20× covenant holds and whether payment is made. Solution. CFADS 6,900,000; $\text{DSCR} = 6,900,000 / 6,814,815 = 1.0125$. The covenant is **breached** ($1.0125 < 1.20$) but **scheduled debt service is still paid** from cash alone ($6,900,000 > 6,814,815$) — the distinction of KA 10.2.1. Common error: treating breach and payment default as the same event.

Exercise 10.5 A project generates CFADS of 8,400,000 a year before the interest tax shield, borrows at 7.0 % over 10 years, pays tax at 25 %, and must hold 1.35× coverage in every period. Compute the effective sculpting rate and the maximum sculpted debt, and state the error made by a modeller who discounts the sculpted profile at the loan rate. Solution. $r^* = 0.07 \times (1 - 0.25/1.35) = 5.703704\%$; $\text{AF}(0.05703704, 10) = 7.464519$; the sizing basis is $A/\lambda = 8,400,000/1.35 = 6,222,222$, and maximum sculpted debt $6,222,222 \times 7.464519 = \text{USD } 46,445,895$. Actual debt service falls with the shrinking shield, from $(8,400,000 + 0.25 \times 0.07 \times 46,445,895) / 1.35 = 6,824,299$ in the first period to 6,298,528 in the tenth — A/λ is the annuity-equivalent basis, not the first payment. Discounting at the full 7.0 % gives $\text{AF}(0.07, 10) = 7.023582$ and 43,702,285 — an **understatement of 2,743,609**, because it ignores the tax saving that each dollar of interest returns to the same CFADS line the coverage test divides. Common error: solving the circularity by iterating a workbook until the closing balance "looks like" zero; the closed form is deterministic and should tie to the cent.

Exercise 10.6 A 40,000,000 facility runs 10 years at 6.5 % against level CFADS of 7,000,000. Compare full amortisation with a 30 % balloon: compute the level payment, DSCR, LLCR, the $\text{DSCR} \div \text{LLCR}$ reading, and the year-ten obligation with that year's coverage. Solution. $\text{AF}(0.065, 10) = 7.188830$; $1.065^{-10} = 0.532726$. **Full amortisation:** payment $40,000,000 / 7.188830 = 5,564,188$, $\text{DSCR } 1.2580$, $\text{LLCR } 7,000,000 \times 7.188830 / 40,000,000 = 1.2580$ — equal, as the level-cash identity requires, so $\text{DSCR} \div \text{LLCR} = 1.0000$. **30 % balloon (12,000,000):** payment $(40,000,000 - 12,000,000 \times 0.532726) / 7.188830 = 4,674,931$, $\text{DSCR } 1.4973$, $\text{LLCR unchanged at } 1.2580$, $\text{DSCR} \div \text{LLCR} = 1.1902$. Year-ten obligation $4,674,931 + 12,000,000 = 16,674,931$, against which that year's coverage is 0.4198. Common error: reporting the balloon structure's 1.4973 as an improvement in credit quality; nothing about the project changed and 1.1902 is the measure of the deferral that produced it.

Exercise 10.7 A facility carries $DSCR \geq 1.20\times$, ICR on $EBITDA \geq 3.00\times$ and $debt/EBITDA \leq 5.50\times$. Base case: revenue **20,000,000**, $EBITDA$ **9,000,000** (of which cash cost 10 % of revenue is variable), depreciation 3,000,000, interest 2,600,000, tax 25 %, debt **40,000,000**, debt service **6,500,000**. Identify the covenant that binds first under a common revenue stress. Solution. $CFADS = 9,000,000 - 0.25 \times (9,000,000 - 3,000,000 - 2,600,000) = 8,150,000$, so $DSCR = 1.2538$. A revenue fall of x reduces $EBITDA$ by $0.9 \times 20,000,000x = 18,000,000x$ and $CFADS$ by $0.75 \times 18,000,000x = 13,500,000x$. $DSCR: (8,150,000 - 13,500,000x) = 7,800,000 \rightarrow 2.5926\%$. $ICR: 9,000,000 - 18,000,000x = 7,800,000 \rightarrow 6.6667\%$. Leverage: $9,000,000 - 18,000,000x = 40,000,000/5.5 = 7,272,727 \rightarrow 9.5960\%$. **DSCR binds first, at a 2.5926 % revenue fall** — less than half the next covenant's tolerance. Common error: ranking the covenants by headroom in their own units (0.0538 of $DSCR$, 0.4615 of ICR , 1.0556 of leverage), which are not comparable quantities; only a common stress variable ranks them.

Exercise 10.8 A $1.25\times$ $DSCR$ covenant is breached: $CFADS$ **7,600,000** against debt service **6,500,000**. Size the equity cure under each drafting treatment and state the identity that links them. Solution. Deemed $CFADS: 1.25 \times 6,500,000 - 7,600,000 = 525,000$. Applied to prepayment: $6,500,000 - 7,600,000/1.25 = 420,000$. The prepayment cure is $C \div \lambda$, so it costs $1 - 1/1.25 = 20.0000\%$ less — **105,000** on these figures — and it also reduces later periods' debt service. Common error: multiplying by the covenant instead of dividing (656,250), which makes the prepayment route look dearer and reverses the negotiating position.

Exercise 10.9 Debt service is **6,500,000** a year and base-case $CFADS$ **8,150,000**. Compute the single-year shortfall tolerance with no reserve, with three months and with six months; state what each month buys; and find the breakeven letter-of-credit fee for a three-month reserve where the cost of equity is **14.0 %** and the reserve account earns **2.5 %**. Solution. Tolerance = $1 - DS \times (1 - m/12) \div CFADS$: **20.2454 %** with no reserve, **40.1840 %** at three months (1,625,000 funded), **60.1227 %** at six. Each month buys **6.6462** percentage points for **541,667** of funded cash. Breakeven LC fee = $14.0 - 2.5 = 11.50\%$ a year; the equity carry on a three-month reserve is $1,625,000 \times 0.115 = 186,875$ a year, against **16,250** for an LC at 1.0 % — a saving of **170,625** a year. Common error: comparing the LC fee with the reserve's principal rather than with the carry on it, which makes cash funding look free.

— Practitioner's toolkit — Domain 10

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 10.T.1 — $CFADS$ definition reconciliation

Column 1: each line of the facility's $CFADS$ definition, with its clause reference. Column 2: the model line implementing it. Column 3: included/excluded and on what basis (cash or accrued; above or below $CFADS$). Column 4: the person who confirmed the match, and the date. Rule: no coverage ratio is reportable until every definition line has a confirmed model line (Domain 2's defined-terms sheet, made specific to $CFADS$).

Toolkit 10.T.2 — Covenant dashboard (per facility, per test date)

Per covenant: test name and clause · test date and frequency · historic or forward-looking · threshold · current/forecast value · **the $CFADS$ level at which it triggers** · cash headroom in currency and as a percentage of base case · lock-up threshold and its own trigger level · reserve balances against

required levels · cures used and remaining · reporting obligations due. Front line: **which covenant binds first, and by how much cash.**

Toolkit 10.T.3 — Coverage model check (before any ratio is quoted)

- [] **CFADS** reconciles to the documented definition (10.T.1 complete).
- [] The same **CFADS** line feeds **DSCR**, **LLCR** and every distribution test.
- [] **LLCR** = **DSCR** where cash is level and service is an annuity at the loan rate.
- [] **PLCR** ≥ **LLCR** wherever a tail exists.
- [] Debt service = interest + scheduled principal, tied to the amortisation schedule.
- [] Schedule closes at zero; Σ principal = loan drawn.
- [] Cash tax, not accounting tax, in **CFADS**.
- [] **Minimum DSCR** over the loan life reported alongside the average.
- [] Every covenant has a modelled test date; **distribution condition and lock-up trigger modelled as well as the covenant**, and both test bases (historic and forward) reported.
- [] **DSCR** ÷ **LLCR** computed; any excess over 1.0000 explained by the amortisation profile, and the maturity obligation stated beside the ratio.
- [] Sculpted schedules reproduce $(A/\lambda) \times AF(r(1 - T/\lambda), n)$ to the cent, and the **CFADS** line used is the resized structure's, not the original request's.
- [] Weighted average life reported for the base profile and for every sweep case.
- [] Every reserve appears in the **uses** of funds, with its funding route (equity, debt or LC) and that route's annual cost stated.
- [] The binding covenant identified by solving all covenants for one common stress.
- [] AI-produced covenant summaries sampled against the documents; verifier named.

Toolkit 10.T.4 — Sizing-basis statement (one page, agreed before any capacity number circulates)

Nine lines, each with a named owner and a document reference. **1 — CFADS definition** and its clause. **2 — the case:** base, bank or sponsor, with its revenue and escalation assumptions. **3 — the test:** base-case (single-period) or minimum-across-all-periods, and which period is expected to bind. **4 — the target coverage**, and whether it is a sizing target, a covenant, or both. **5 — the service profile:** level, sculpted or structured, and if sculpted, the target λ , the effective rate $r(1 - T/\lambda)$ and the re-cut provision. **6 — deferred principal:** balloon or bullet amount, the maturity obligation in cash, and the stated refinancing plan. **7 — reserves:** each reserve, its required balance, its funding route and that route's annual cost. **8 — prepayment:** sweep share, its base, its priority in the waterfall, and the average life before and after. **9 — the thresholds:** distribution condition, covenant and lock-up trigger, each in ratio and in **CFADS**, with the years each catches on the agreed case. Rule: a debt-capacity figure quoted without lines 1 to 5 agreed is an opinion, not a number — and the three answers of Worked example 10.1.3 are what happens when it is quoted anyway.

— Exam preparation — Domain 10

The traps. Sizing debt on full **CFADS** without the coverage divisor (Exercise 10.1) · quoting a **DSCR** without its **CFADS** definition (10.1.1) · treating covenant breach and payment default as the same event (Exercise 10.4, Case study B) · discounting **CFADS** at an equity rate in **LLCR** (Exercise 10.2) · reporting average rather than minimum **DSCR** · modelling the covenant but not the lock-up (10.4.2) ·

assuming a DSRA prevents breach (MCQ 10.3-B) · using accounting rather than cash tax in **CFADS** · inverting **DSCR** · relying on **PLCR** as a lender comfort · quoting a debt capacity without saying whether the coverage test is base-case or every-period (10.1.3) · discounting a sculpted profile at the loan rate instead of at $r(1 - T/\lambda)$ (Exercise 10.5) · sculpting against the **CFADS** of the original request rather than of the resized structure (10.1.3) · treating a lower target **DSCR** attached to a deeper stressed case as a concession without computing $1 - \lambda_2/\lambda_1$ (10.1.2b) · reading a balloon's improved **DSCR** as improved credit quality when **LLCR** has not moved (10.2.3) · ranking covenants by headroom in their own units instead of by a common stress (10.2.4) · comparing a letter-of-credit fee with a reserve's principal rather than with the carry on it (Exercise 10.9) · funding a reserve from a coverage-constrained facility and believing the equity requirement has been avoided (10.3.2b) · multiplying rather than dividing by the covenant when sizing a prepayment cure (Exercise 10.8) · reporting the tenor rather than the weighted average life as what a sweep delivers (10.3.3).

Reflection questions.

1. For your facility: state the **CFADS** definition from memory, then check it against the document. How close were you, and what would the difference have done to your reported ratio?
2. At what **CFADS** level does your first covenant fail, and is that number on anyone's dashboard?
3. Does your distribution forecast pass the lock-up tests, or only the covenant tests?
4. Is your coverage target tested on the base case or in every period, and can you say which document settles it? What would the other reading do to your facility size?
5. Which of your facility's thresholds actually catches a year on the lenders' own case — and is it the one your team spent its negotiating capital on?
6. If your schedule carries deferred principal, what is the obligation at maturity in cash, and what is that year's coverage against it?

— Domain 10 summary

Project debt is sized from cash flow outwards, and the arithmetic admits only four inputs: **CFADS**, required coverage, rate and tenor. Kestrel's request for 42,000,000 against level **CFADS** of 6,384,000 supports only **41,171,123** at a 1.30× target — an 828,877 gap closed by equity, because every attempt to close it by redefining **CFADS** fails at the first competent review. **CFADS** itself is a **defined term** whose documented construction governs every ratio built on it, as Domain 2 proved by moving Kestrel's **DSCR** from 1.39 to 1.27 with one working-capital treatment. The ratios answer different questions: **DSCR** tests a period (1.2743, with covenant headroom of **372,438** of annual cash — the number that belongs on a dashboard); **LLCR** tests the loan horizon and, with level cash and annuity service, is **identically equal to DSCR** — an invariant that catches model inconsistency; **PLCR** (1.9431) counts the tail that makes refinancing possible but that lenders have no claim on; and **ICR** covers interest while ignoring principal and inheriting accounting judgment. Reserves buy payment continuity and time rather than compliance — Kestrel's six-month DSRA of **2,504,818** survives a collapse to 39 % of base-case cash while the covenant still breaches — and they rank above distributions in the waterfall. Covenants exist to give lenders control while the project is fixable, with lock-up trapping cash short of default, cure rights giving sponsors a funding option, and waiver or amendment as the ordinary resolution; breach and payment failure are different events, and confusing them is the error Case study B cost two months of credibility.

Four results deepen that summary and are the domain's own contribution. **A coverage target is meaningless until it says which periods it applies to.** Kestrel's 1.30 × supports 41,171,123 as a base-case test and only **38,253,896** as an every-period test against the declining bank case — a difference of **2,917,226** — and **sculpting recovers 1,661,916 of it at 39,915,812**, holding 1.30 ×

in every year, because the sculpted profile discounts at the effective rate $r(1 - T/\lambda) = 5.076923\%$ rather than at the 6.0 % loan rate. The sculpted schedule's final payment, 4,562,811.13, is precisely the level payment a minimum-period test would have imposed throughout — which is the clearest statement of what level sizing does wrong against uneven cash. **Structure moves DSCR and moves nothing else.** The same 42,000,000 against the same cash reports 1.2743 fully amortising, **1.4551** with a 25 % balloon and **2.5333** as a bullet, while **LLCR**, **PLCR** and **ICR** do not move at all; the **DSCR ÷ LLCR** reading ($1.0000 \cdot 1.1419 \cdot 1.9880$) measures the deferral, and the balloon structure's year-twelve coverage against its 14,887,226 obligation is **0.4288**. **The covenant that binds is found by stress, not by inspection.** On the mandated facility a revenue fall of **4.1382 %** breaches the year-one **DSCR**, **4.4444 %** the leverage covenant, **4.9833 %** the **LLCR** and **10.6667 %** the **ICR** — while the year-twelve **DSCR** is already breached by **74,849** before any stress at all, and an **ICR** drafted at $2.90 \times$ instead of $2.50 \times$ would bind first of the four at **1.7067 %**. **And the threshold that traps cash is rarely the one that was negotiated:** Kestrel's $1.25 \times$ distribution condition catches **eight of twelve years** and **3,956,574** of dividend — 57.61 % of the loan period's distributable cash, worth 2,165,274 at 8 % — while the $1.15 \times$ lock-up trigger never engages. Alongside these, three pieces of practical arithmetic: each month of DSRA buys **6.5393** percentage points of single-year cash tolerance for 417,470 of funded cash; the reserve's funding route is a real decision with a **12.42 %** breakeven letter-of-credit fee and a debt route that relocates rather than avoids the equity requirement; and a 50 % cash sweep shortens the loan's weighted average life from **7.1887 to 6.4660 years**, which is what the lender is buying, at a present-value cost to equity of 315,488. Finally, the cure identity $P = C \div \lambda$: the same breach costs 96,196 cured as deemed **CFADS** and **61,485** cured by prepayment, because prepayment works on the denominator and improves every later period as well.

Domain 11 allocates the risks these ratios are stressed against; Domain 13 audits the model that computes them; Domain 15 operates the waterfall and handles the restructuring end.

11

DOMAIN 11

Risk Identification and Allocation

— Why this domain exists

Domain 10 established what a project's cash flow can carry and on what conditions. It stress-tested that cash flow without ever asking the prior question: **who bears each of the things that could reduce it, and what did that allocation cost?** Domains 5 to 9 named the risks; Domain 10 measured the consequence of them materialising. Neither decided the allocation, and the allocation is where most of a project financing's value is created or quietly destroyed.

The domain's central claim is that **risk allocation is a price, not a preference**. Practitioners talk as though risk were transferred by assertion — "the contractor takes ground risk", "the offtaker takes volume risk" — but no counterparty absorbs an exposure for nothing. It charges, and its charge is its own expected cost plus a loading for capital, uncertainty and margin. The value of a transfer is therefore the transferor's expected cost minus the price paid, and that difference can be negative. It is reliably negative in one identifiable circumstance: when the party being asked to take the risk can neither influence its probability nor its consequence. Such a party prices its ignorance, and a project that buys the transfer anyway pays more than the risk costs — sometimes enough to break its own coverage. The five items of Kestrel's construction register that were offered to the contractor and declined would have cost **USD 4,620,000** in premium against an owner's expected cost of **USD 2,840,000**, and buying them at 70/30 gearing would have pushed the project's year-one **DSCR** to **1.1832** — below its own covenant, before the plant produced a litre of water.

The domain then works outwards through the four risk families. Construction and completion risk is where the pricing test is sharpest, because counterparty and price are both explicit (KA 11.1). Market and operating risk is allocated through indexation and pass-through formulae rather than liability clauses, and a **mismatch** between the index on revenue and the driver of cost is a slow covenant breach nobody tests for (KA 11.2). The financial and event risks are where the arithmetic is most tractable and most often left undone: 74 basis points of reference rate, a 5.06 % devaluation and a 21-day outage each sit between Kestrel and a breach, all three computable in advance (KA 11.3). And the modern families — environmental and social, technology, cybersecurity, AI model risk — are where the register is newest, thinnest and most aggressively re-cut by lenders (KA 11.4).

Learning objectives. After this domain a candidate can: build a risk register at the level of granularity an allocation decision requires; state the two legitimate grounds for transferring a risk and distinguish them from bargaining power; compute the net value of a transfer as expected cost less loaded premium, and the breakeven premium and breakeven loading at which a transfer stops paying; demonstrate arithmetically why transferring an uncontrollable risk destroys value even at a zero margin; translate an input-cost pass-through share into a coverage tolerance multiplier; detect and quantify an indexation mismatch between revenue escalation and cost drivers; compute unhedged, partially hedged and fully hedged debt service and the **DSCR** range each produces; derive the minimum hedge ratio that survives a specified rate shock; quantify the coverage consequence of a currency mismatch and compute the exchange-rate-indexed revenue share that neutralises debt

service; test an insurance waiting period against covenant headroom in days; aggregate a risk register to a mean, a standard deviation and a percentile on the PML-AI Domain 8 method, explain why a lender re-cuts it and what correlation does to it; convert a register into a debt-capacity number; and govern AI use in risk identification while treating AI itself as a register line.

The master thread. Kestrel Water SPC continues. Capital cost **USD 60,000,000** funded **70/30** as **USD 42,000,000** of senior debt at **6.0 % over 12 years** — annual instalment **USD 5,009,635.23**, year-one interest **2,520,000**, year-one principal **2,489,635.23**, $AF(0.06, 12) = 8.383844$ (Domain 3) — plus **USD 18,000,000** of equity. Operating life 25 years; documented first-year **CFADS USD 6,384,000** (6,984,000 before working-capital movements) on revenue of 12,000,000 and cash operating costs of 4,500,000. Coverage at close (Domain 10): **DSCR 1.2743** = **LLCR 1.2743**, **PLCR 1.9431**, covenant cash trigger **6,011,562.28**, lock-up trigger **5,761,080.51**, annual headroom **372,437.72**. Domain 8 provisioned against a retained construction register with a mean of **2,690,000** and a P80 of **4,246,095**. This domain supplies the fact those chapters took as given: **where that retained register came from**, and what the allocation that produced it cost.

KNOWLEDGE AREA 11.1

Construction and completion risk

Topics: 11.1.1 the register at allocation granularity · 11.1.2 the two grounds for transfer · 11.1.3 pricing the transfer · 11.1.4 completion risk and the residue.

11.1.1 The register at allocation granularity

Definition. A **risk register** for financing purposes is a list of identified events, each with a probability, a monetary impact, an owner and — the line most registers omit — **the mechanism by which that ownership is effected**. Registers written for project-management purposes stop at the owner's name; a financing register must name the clause, the guarantee, the reserve or the insurance policy that makes the ownership real, because an unmechanised allocation is an intention, not a transfer.

Granularity is the practical craft. A register line reading "construction risk — contractor" is useless for allocation because construction risk is not one thing: it decomposes into workmanship and plant performance, programme and productivity, procurement and logistics, ground conditions, third-party interfaces, input prices and permit conditions, and those seven items belong to different parties on different grounds. The test of adequate granularity is operational: **a register is granular enough when every line could in principle be allocated separately**. Aggregating two risks with different natural owners into one line guarantees that one of them is mis-allocated, and the mis-allocation is invisible because the line has only one owner column.

Two consequences follow. Identification must run through the **cash-flow model**, not around it: a risk that cannot be expressed as a change to a modelled line — revenue, an operating cost, capex, a timing — cannot be quantified, priced or allocated on any basis but instinct. And identification must be **adversarial**, because a sponsor's register supports a case while a lender's supports a doubt, so the sponsor's is systematically the shorter of the two. A leader who has not written the lender's register before the lender does (Domain 13) will negotiate from a document already discredited.

11.1.2 The two grounds for transfer

The principle. There are exactly two defensible reasons to move a risk from one party to another, and one common indefensible one.

Control. The transferee can change the probability or the impact. A contractor can supervise welding, sequence a programme and expedite a supplier; when it holds the consequence, it does those things better. Transfer on control grounds creates value because it **changes the underlying distribution**, not merely who observes it.

Capacity. The transferee cannot change the distribution but has a lower cost of bearing it — because it is diversified across many such exposures (an insurer), because the exposure is small relative to its balance sheet (a state offtaker facing a devaluation that would destroy an SPV), or because it can hedge in a market the transferor cannot access. Transfer on capacity grounds creates value without touching the distribution, by moving the exposure to a cheaper holder of it.

Bargaining power is the indefensible ground. A party with a weak negotiating position can be made to accept a risk it neither controls nor can cheaply bear. The transfer looks free because it is not priced in the agreement, but it is priced somewhere: in a claims strategy, in a contingency the counterparty holds privately, in a bid that fails at the diligence stage, or — most expensively — in a counterparty that fails when the risk crystallises and hands the exposure back at the worst possible moment (11.3.3). **A risk allocated to a party that can neither control nor absorb it has not been transferred; it has been hidden.**

11.1.3 Pricing the transfer

The arrangement. Nothing new is needed beyond **EMV** (PML-AI Domain 8, KA 8.2.2: **EMV** = probability × impact), arranged three ways:

Expected cost if retained	= EMV(transferor's own p and impact)
Loaded premium the transferee wants	= EMV(transferee's own p and impact) × (1 + loading)
Net value of transfer	= expected cost if retained – loaded premium
Breakeven premium	= expected cost if retained
Breakeven loading	= (transferor's EMV ÷ transferee's EMV) – 1

The **breakeven loading** is the number that carries the professional insight, because it separates the two grounds for transfer arithmetically. Where the transferee controls the risk, its own **EMV** is much lower than the transferor's, so the breakeven loading is large and a generous margin still leaves value on the table. Where it does not control the risk, its **EMV** equals or exceeds the transferor's, the breakeven loading is zero or negative, and **no negotiation over margin can rescue the transfer.**

WORKED EXAMPLE

Worked example 11.1.3 — Kestrel's construction register, priced item by item.

- Setup.** Before award, Kestrel's sponsors hold eight quantified construction threats plus one opportunity. The preferred bidder is asked to price each item into a fixed-price wrap. It quotes each on **its own** probability and impact estimates, with a **40 % loading** for capital, uncertainty and margin (a stated assumption, not a market constant: the loading reflects the transferee's cost of capital and its own uncertainty, and is itself negotiable). Determine which items should transfer.
- Formula.** As above, per item, then aggregated by decision.
- Substitution and result.**

ID	Item	Owner p	Owner impact	Owner EMV	Bidder p	Bidder impact	Bidder EMV	Premium ×1.40	Net value
A1	Workmanship, plant defects, performance shortfall	0.30	6,000,000	1,800,000	0.12	4,000,000	480,000	672,000	+1,128,000
A2	Construction programme and labour productivity	0.35	5,200,000	1,820,000	0.20	3,400,000	680,000	952,000	+868,000
A3	Equipment procurement and logistics	0.25	3,200,000	800,000	0.15	2,400,000	360,000	504,000	+296,000
A4	Ground conditions beyond the disclosed geotechnical baseline	0.40	2,400,000	960,000	0.45	2,900,000	1,305,000	1,827,000	(867,000)
A5	Utility diversion and third-party interface scope growth	0.30	1,800,000	540,000	0.31	2,000,000	620,000	868,000	(328,000)
A6	Membrane supply price above the contract indexation formula	0.35	1,400,000	490,000	0.35	1,500,000	525,000	735,000	(245,000)
A7	Marine intake weather standby beyond the allowance	0.50	900,000	450,000	0.50	900,000	450,000	630,000	(180,000)
A8	Permit condition requiring additional monitoring works	0.20	2,000,000	400,000	0.20	2,000,000	400,000	560,000	(160,000)
A9	Early-completion rebate (opportunity, retained)	0.25	(600,000)	(150,000)	—	—	—	—	—

A1-A3 transfer: owner EMV 4,420,000 against premiums of **2,128,000** — value created **+2,292,000**. **A4-A8 do not:** owner EMV 2,840,000 against premiums of **4,620,000** — value destroyed **(1,780,000)**. **4. Result.** The wrap is drawn round A1-A3 for a priced risk premium of **USD 2,128,000** inside the 48,000,000 EPC price (an un-risked scope of **45,872,000** plus that premium). The retained residue is **2,840,000 – 150,000 = USD 2,690,000** — precisely the register Domain 8 sized contingency against. Gross expected cost of the risk position falls from **7,110,000** wholly

retained to **4,818,000** after allocation. 5. **Interpretation.** Four things in that table are worth more than the arithmetic that produced them. **The premium is not the cost; the net is.** Every dollar of the 2,128,000 premium bought 2.0771 dollars of expected-cost reduction, and an organisation that judges a wrap by its price rather than by its net value will reject the transfers that pay for themselves twice over. **Where control exists, price barely matters.** The breakeven loading on A1–A3 is **190.79 %** — the bidder could charge nearly three times its own expected cost and the transfer would still create value, because the transfer changes the distribution: 6,000,000 of impact at 0.30 becomes 4,000,000 at 0.12 when the party doing the welding carries the consequence. **Where control does not exist, no price works.** The breakeven loading on A4–A8 is **–13.94 %**: the bidder would have to accept the bundle at 86.06 % of its own expected cost before the transfer merely broke even. Stripping the margin out entirely still destroys **460,000**, because the bidder's own expected cost on those items (3,300,000) exceeds the owner's (2,840,000) — it must assume the worst about a ground investigation it did not commission, a utility corridor it does not own and a permit condition it cannot influence. **And the asymmetry has a shape.** A4 is the extreme case and the most instructive: the owner commissioned the geotechnical survey, holds the data and set the baseline, so the owner is the better-informed party. Transferring a risk to the less-informed party converts an information advantage into a price disadvantage. The standing professional caution is that the arithmetic depends entirely on the honesty of the two **EMV** columns: a sponsor who understates its own retained probabilities will "prove" that every transfer destroys value, and a bidder who overstates its own will justify any premium. **The register's probabilities are the negotiation**, which is why they must be evidenced (Domain 8's estimate basis, PML-AI Domain 8's elicitation discipline) before they are argued.

Allocation is a price, not a preference — three transfers create 2,292,000, five destroy 1,780,000

Contractor prices its own expected cost at a 40 % loading. Blue: it controls the risk. Crimson: it does not

The crimson five destroy 460,000 even at a zero margin: the contractor's own expected cost, 3,300,000, exceeds the owner's 2,840,000

The blue three still create value at a premium 190.79 % above the contractor's expected cost — control is what pays




Fig 11.1.1 — The allocation price test

11.1.4 Completion risk and the residue

Definition. Completion risk is the risk that the project does not reach commercial operation on time, on budget, or to the performance the financing was sized against. It is the one construction risk that cannot be wholly transferred, because its consequences fall on parties the EPC contract does not reach: the lenders lose their repayment source, and the equity loses its return.

Three residues survive even a well-priced wrap, and Domain 5 measured each of them, so they are cited rather than re-derived. **Timing residue:** a slip costs 24,733.33 per day in extra interest and forgone [CFADS](#), against delay damages of 20,000 per day capped at day 240 — so damages recover 80.86 % of the cost and nothing at all beyond the cap (Domain 5, KA 5.4.2). **Performance residue:** completion at 97 % of guaranteed output requires a buy-down that restores lenders' coverage, not merely compensation for lost revenue (Domain 5, KA 5.4.3). **Credit residue:** the whole wrap is worth the contractor's balance sheet, priced in 11.3.3.

The professional discipline is to state the residue in the same units as the covenant. Kestrel's retained register mean of 2,690,000, spread across the two-year construction period, is not a coverage number; **capitalised into debt it becomes one**. Domain 8 demonstrated the mechanism precisely: the 600,692 by which the funded contingency fell short of the register P80, capitalised, moved the [DSCR](#) from 1.2743 to 1.2564 and cut annual headroom by 23.1 % for the whole twelve-year loan life. That is the sentence a construction risk register should end with: not "the exposure is 2.69 million" but "the exposure, if funded by debt, costs us this much covenant headroom for twelve years."

AI in this KA

Risk identification is one of the strongest genuine applications of language models in project finance, and one of the most dangerous places to accept an output unedited. **Where it earns its place:** extracting risk allocation from a long contract suite into a matrix of item, clause, mechanism and cap; cross-checking a sponsor's register against the risk taxonomies implied by comparable transactions and the lender's diligence scopes, and reporting what is missing — the omission is the failure mode registers have, and a machine that has read a thousand registers is good at noticing an absent line; and normalising register wording so that two advisers' items can be compared at all. **Where it must not go:** the probability and impact columns. Those are elicited judgments with an evidentiary basis, and a model asked to supply them will produce plausible central values with no basis, which then propagate through [EMV](#), the P80, the contingency and the debt sizing. A model may challenge a probability ("this is inconsistent with the ground investigation extent you described"); it may not supply one. **Verification, concretely:** for an extracted allocation matrix, sample at least ten lines back to the clause text and confirm the cap and the mechanism, because the recurring error is a correct owner attached to a wrong cap; for a machine-suggested register addition, require that it be expressed as a change to a named model line before it is accepted, which filters the plausible-but-unquantifiable; and never let a model perform the arithmetic of 11.1.3 without an independent recomputation, since a single transposed probability flips a transfer decision. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 11.1

Term	Meaning
Risk register (financing)	Identified events with probability, impact, owner and mechanism ; granular enough for each line to be allocated separately.
Grounds for transfer	Control (changes the distribution) and capacity (cheaper holder); bargaining power is neither.
Loaded premium	Transferee's own EMV $\times (1 + \text{loading})$ — what the transfer actually costs.
Net value of transfer	Transferor's EMV — loaded premium; negative means retain.
Breakeven loading	$(\text{transferor EMV} \div \text{transferee EMV}) - 1$; negative means no price works.
Retained residue	The register left after allocation — the thing contingency and reserves are sized against.
Completion risk	Risk of not reaching commercial operation on time, on budget or to guaranteed performance; never wholly transferable.

■ SAMPLE MCQS — KA 11.1

MCQ 11.1-A [11.1.3 · Application] An owner's EMV on an item is 960,000. The contractor assesses the same item at p 0.45 and impact 2,900,000 and applies a 40 % loading. The net value of transferring is:

- A. +573,000
- B. -345,000
- C. -867,000 ☒ **CORRECT**
- D. -1,827,000

Rationale: Premium = $0.45 \times 2,900,000 \times 1.40 = 1,827,000$; net = $960,000 - 1,827,000 = -867,000$. B is the net at a **zero** loading ($960,000 - 1,305,000$) and understates the destruction; D is the premium alone, ignoring the retained cost avoided; A compares the owner's gross **impact** (2,400,000) with the premium, omitting probability from the retained side.

MCQ 11.1-B [11.1.3 · Analysis] A bundle of items has an owner EMV of 2,840,000 and a contractor EMV of 3,300,000. The correct conclusion is:

- A. transfer if the loading can be negotiated below 40 %
- B. transfer, because the contractor is better placed to manage construction
- C. do not transfer: the breakeven loading is -13.94 %, so even at a zero margin the transfer destroys 460,000 ☒ **CORRECT**
- D. transfer, and recover the premium through the contingency

Rationale: The transferee's own expected cost exceeds the transferor's, so the loading is not the problem — the distribution is (11.1.3). A treats a structural result as a pricing negotiation; B asserts control where the items are ground, interface, index and permit risks the contractor does not control; D funds a value destruction twice.

MCQ 11.1-C [11.1.2 · Analysis] An SPV with weak negotiating position accepts a risk it neither controls nor can absorb. The most accurate description of what has happened is:

- A. an efficient transfer, since the price was zero

- B. the risk has not been transferred but hidden — it will reappear as a claim, a private contingency, a failed bid or a counterparty default ✓ CORRECT
- C. a transfer on capacity grounds
- D. a transfer on control grounds

Rationale: Neither ground applies, and an unpriced allocation is not a costless one (11.1.2). C and D name grounds that are absent by the stem's own terms.

MCQ 11.1-D [11.1.3 · Evaluation] The allocation arithmetic shows the five uncontrollable items destroying 1,780,000 of value at a 40 % loading. A colleague proposes reducing the owner's retained probabilities so that the full wrap can be recommended to the board on price grounds. The soundest professional position is:

- A. adjust them: the register is a negotiating instrument and the full wrap has strategic value
- B. adopt the bidder's probabilities throughout, since the bidder is the party pricing the risk
- C. hold the retained probabilities to their evidence base and negotiate item by item on that evidence, because the register's probabilities are the negotiation and an input adjusted to reach a conclusion has inverted the analysis ✓ CORRECT
- D. abandon the arithmetic, since probabilities are subjective and cannot support a decision

Rationale: The whole result rests on the honesty of the two EMV columns: a sponsor who understates its retained probabilities will "prove" that every transfer destroys value, and a bidder who overstates its own will justify any premium (11.1.3). A produces a recommendation the lender's diligence will reverse, at the cost of the register's credibility everywhere else. B imports the less-informed party's assumptions about a ground investigation the owner commissioned, which is how an information advantage becomes a price disadvantage. D discards a rule that is transparent and challengeable in favour of instinct, which is neither.

MCQ 11.1-E [11.1.3 · Analysis] The preferred bidder declines to price Kestrel's register items separately and offers a single wrap covering all eight threats for a premium of **6,748,000** — the sum of the 2,128,000 it quoted on A1-A3 and the 4,620,000 it quoted on A4-A8. Retaining the whole register has an expected cost of 7,110,000; transferring A1-A3 alone and retaining the rest costs 4,818,000. The recommendation is:

- A. accept the bundle: at an expected cost of **6,598,000** it beats full retention by **512,000**, and a single wrap removes every argument about which item a loss belongs to
- B. accept the bundle and negotiate the 40 % loading down, since the loading is where the value destruction sits
- C. refuse all transfer: the bidder's own expected cost on A4-A8 exceeds the owner's, so no wrap creates value
- D. refuse the bundle and require the items to be priced line by line — A1-A3 transferred and A4-A8 retained costs 4,818,000, which is **1,780,000** better than the bundle ✓ CORRECT

Rationale: The bundle genuinely beats full retention, which is exactly what makes A the trap — it is defensible on its own comparison and leaves 1,780,000 on the table, because it buys five items the bidder cannot influence at the same time as three it can (11.1.3). C generalises the A4-A8 result across the register and forgoes the 2,292,000 the control-based transfers create. B misplaces the defect: stripping the loading out entirely still destroys 460,000 on A4-A8, because the bidder's own expected cost there (3,300,000) exceeds the owner's (2,840,000). The negotiating point that follows from D is that unbundling is itself the ask — a bidder that will not price line by line is charging for the items it would rather not discuss.

MCQ 11.1-F [11.1.2 · Comprehension] An insurer accepts a risk it cannot influence in any way. Expressed in this domain's terms, that transfer rests on:

- A. capacity: the insurer cannot change the distribution but holds it more cheaply, being diversified across many such exposures — so value is created by moving the exposure to a cheaper holder rather than by improving it ✓ CORRECT
- B. control, since the insurer's loss-prevention requirements change the project's behaviour
- C. bargaining power, since the project has no alternative
- D. no recognised ground, which is why insurance is a cost rather than a transfer

Rationale: The two defensible grounds are control, which changes the underlying distribution, and capacity, which changes only who holds it; diversification is the classic capacity case (11.1.2). B describes a real secondary effect and names the wrong ground — the insurer's requirements do not put it in charge of the welding. C describes the indefensible ground and does not apply: the insurer is a willing party pricing an exposure it can bear. D denies a transfer that the pricing test of 11.1.3 values in the ordinary way, as expected cost retained less loaded premium.

■ SELF-CHECK — KA 11.1

1. State the test for adequate register granularity. — Every line could in principle be allocated separately; if two risks in one line have different natural owners, one is mis-allocated invisibly.
2. Why does the breakeven loading separate the two grounds for transfer? — Control lowers the transferee's EMV below the transferor's, making the breakeven loading large; without control it is zero or negative, and no margin negotiation helps.
3. State Kestrel's allocation outcome in one line. — 2,128,000 of premium bought 4,420,000 of expected-cost reduction (net +2,292,000); 4,620,000 of offered premium against 2,840,000 of retained EMV was declined; the residue is 2,690,000.

KNOWLEDGE AREA 11.2

Market risks and operations

Topics: 11.2.1 why market risk resists transfer · 11.2.2 pass-through as a coverage multiplier · 11.2.3 the indexation mismatch · 11.2.4 operating risk and the O&M interface.

11.2.1 Why market risk resists transfer

Demand, price and supply risks are the hardest to allocate because **no party to the transaction controls them**. The pricing test of 11.1.3 therefore predicts what practice confirms: transfers of market risk are either expensive or illusory. Domain 7 built the machinery — contracted versus merchant structures, tariff architecture, minimum revenue guarantees, offtaker credit — and this KA adds only the allocation view of it, which reduces to three findings.

Transfer to the offtaker is a capacity transfer, not a control transfer. An availability-based structure moves volume risk to a payer that is diversified or sovereign-adjacent where the SPV is neither, and it is bought with a lower tariff — Domain 7 priced that trade at 10,679,727 of debt capacity relative to a volume tariff.

Transfer to a guarantor is a capacity transfer with a credit tail. A minimum revenue guarantee is worth the guarantor's balance sheet in the state of the world where it is called — by construction,

the state in which the guarantor's other exposures are also stressed. Domain 7 valued Kestrel's guarantee at 2,625,026 of released equity; the discipline is to value it for the coverage it unlocks and then discount it for that correlation.

Transfer to the contractor or operator is usually a mis-allocation. Asking an O&M contractor to carry input-price risk it cannot hedge produces exactly the A6 result of 11.1.3: a premium above the retained cost, because a counterparty that can only insure itself by assuming the worst case prices the worst case.

11.2.2 Pass-through as a coverage multiplier

Definition. A **pass-through** is a contractual term under which a defined movement in a defined input cost is recovered in revenue, in whole or in a stated share. Its financial effect is not to remove the exposure but to **divide** it, and the arithmetic of that division is more powerful than practitioners expect.

If an input has a base annual cost C and a share ϕ of its price movement is passed through, the residual cash effect of a 1 % rise in that input's price is $C \times 0.01 \times (1 - \phi)$. Because covenant tolerance is fixed headroom divided by residual exposure per unit, **the tolerance is multiplied by $1/(1 - \phi)$.**

WORKED EXAMPLE**Worked example 11.2.2 — what a 70 % power pass-through is worth to Kestrel.**

1. **Setup.** Of Kestrel's 4,500,000 of cash operating costs, **1,800,000 is electricity** — the dominant input in reverse-osmosis desalination. The water-purchase agreement passes through **70 %** of movements in the reference power tariff. Annual covenant headroom is **372,437.72** (Domain 10). Compute the tolerance to a power-price rise with and without the pass-through, and the position after a 25 % rise.
2. **Formula.** Residual per 1 % rise = $1,800,000 \times 0.01 \times (1 - \phi)$; tolerance = headroom ÷ residual per 1 %; multiplier = $1/(1 - \phi)$.
3. **Substitution.** With $\phi = 0$: $1,800,000 \times 0.01 = 18,000$; $372,437.72 / 18,000$. With $\phi = 0.70$: $1,800,000 \times 0.01 \times 0.30 = 5,400$; $372,437.72 / 5,400$. At a 25 % rise: residual $1,800,000 \times 0.25 \times 0.30 = 135,000$.
4. **Result.** Unprotected, the covenant fails on a **20.6910 %** power-price rise. With 70 % pass-through it fails on a **68.9699 %** rise — a tolerance multiplier of **3.3333×**. A 25 % rise costs **135,000** of **CFADS**, leaving 6,249,000 and a **DSCR** of **1.2474**; unprotected the same rise costs 450,000, leaving 5,934,000 and a **DSCR** of **1.1845** — a breach.
5. **Interpretation.** The teachable content is the leverage. Negotiating the pass-through share from zero to 70 % triples the project's tolerance to its single largest cost driver, and the marginal value of each increment is increasing: moving from 0 to 50 % doubles tolerance, but moving from 70 % to 85 % doubles it again from a much higher base. The professional consequence is that a pass-through share is a **coverage term, not a commercial detail**, and it belongs in the same negotiating tranche as the covenant level. Two cautions bound the result. First, a pass-through is only as good as its **reference index and its reset frequency**: a share of 70 % reset annually leaves eleven months of exposure inside each year, and a share indexed to a published tariff the plant does not actually pay leaves a basis risk that no share removes. Second, the tolerance figures assume the rise is permanent and everything else holds; combined with any other adverse movement the tolerances share the same 372,437.72 of headroom and are **not additive** — which is the single most common misuse of a sensitivity table (Domain 7, KA 7.4.3 built the joint matrix for exactly this reason).

11.2.3 The indexation mismatch

Definition. An **indexation mismatch** exists when the index that escalates revenue is not the driver that escalates cost. It is the most under-detected structural risk in project finance because it is invisible at close — year one is unaffected by construction — and because it does not appear in any single-year sensitivity. It appears as a **trend in coverage**, and a model that reports only the base-case minimum **DSCR** over the loan life will report it, while a model that reports the year-one ratio will not.

WORKED EXAMPLE**Worked example 11.2.3 — Kestrel's CPI revenue against power-driven cost.**

- Setup.** Domain 7 established that **80 % of Kestrel's tariff is indexed to a consumer price index**, assumed at 2.5 % a year. On the cost side, 2,700,000 of operating cost tracks that same index, but the **1,800,000 of power escalates at 8.0 %** on the sponsors' own forecast. Cash tax (516,000) and the working-capital movement (600,000) are held constant, a simplifying assumption stated so the mismatch is isolated. Trace **CFADS** and **DSCR** across the loan life against the 1.20× covenant.
- Formula.** Revenue(t) = $12,000,000 \times (1 + 0.80 \times 0.025)^{(t-1)}$; CPI cost(t) = $2,700,000 \times 1.025^{(t-1)}$; power(t) = $1,800,000 \times 1.08^{(t-1)}$; CFADS(t) = revenue – CPI cost – power – 1,116,000.
- Substitution and result.**

Year	Revenue	CPI-linked cost	Power	CFADS	DSCR
1	12,000,000	2,700,000	1,800,000	6,384,000	1.2743
3	12,484,800	2,836,688	2,099,520	6,432,593	1.2840
5	12,989,186	2,980,295	2,448,880	6,444,011	1.2863
8	13,784,228	3,209,452	3,084,884	6,373,893	1.2723
10	14,341,111	3,371,930	3,598,208	6,254,972	1.2486
12	14,920,492	3,542,634	4,196,950	6,064,908	1.2106
15	15,833,745	3,815,029	5,286,949	5,615,767	1.1210

Coverage **improves** to year five, then deteriorates continuously. The first covenant breach falls in **year 13** — one year after the loan matures. The **breakeven power escalation** that would put year twelve exactly on the covenant is **8.1241 %**. **4. Result.** The structure survives its own indexation mismatch across the loan life, but by **12.41 basis points of assumed power escalation** and with **85.68 %** of its covenant headroom consumed: year-twelve headroom is **53,345.25** against 372,437.72 at close. **5. Interpretation.** This is the most important arithmetic in the KA and the least likely to be found in a base-case pack. **Coverage improving early conceals a deteriorating structure.** For the first five years the 2 % effective revenue escalation outruns a power cost that is still small in absolute terms; by year twelve power has grown from 1,800,000 to 4,196,950 while the same input escalated at CPI would have reached only 2,361,756 — a wedge of **1,835,194** a year, which is 4.93 times the entire original headroom. **The structure is not robust; it is lucky.** A power forecast of 8.1241 % rather than 8.0 % breaches in year twelve, and no one in the transaction would claim twelve basis points of precision on a twelve-year commodity forecast. That is the honest characterisation to put in front of a credit committee, and it points to three interventions, each priceable: raise the power pass-through share (11.2.2 shows the leverage), index part of the tariff to the power reference rather than to CPI, or size a reserve that funds the late-life wedge. **And the diagnostic is cheap.** Any level-escalation model can be tested in one line: compute the revenue-weighted escalation rate and the cost-weighted escalation rate, and if the cost rate is higher the structure has a mismatch whose only question is when it bites. Kestrel's are 2.00 % and 4.70 % respectively — a 270-basis-point gap that a single-year sensitivity cannot see. The standing caution is that the arithmetic is only as good as the differential forecast: the level of power prices matters far less here than the **spread** between power escalation and the revenue index, and a model that stresses both at the same rate will show no exposure at all while destroying none of it.

11.2.4 Operating risk and the O&M interface

Operating risk allocation is a smaller-scale replay of 11.1.3 with one structural difference: the O&M contractor is a **long-lived counterparty with a thin balance sheet relative to the exposure**, so transfers to it are capped early and often. The practical allocation set is: availability and performance to the operator, within a liability cap and against a fee at risk; input volumes to the operator, which controls consumption; input **prices** to the offtaker or retained, since nobody in the structure controls them (11.2.2); major maintenance to a reserve rather than to a party (Domain 10's MRA); lifecycle replacement to whichever party the handback standard makes accountable.

The interface that produces the most disputes is the boundary between **availability** and **force majeure**, because it decides whether a lost month is the operator's liability or nobody's. Domain 7 computed the coverage sensitivity that makes this boundary financially material: Kestrel breaches its 1.20× covenant at **92.086 %** availability against a 95 % guarantee, so 2.9 percentage points of availability separate compliance from breach, and the definition of what counts as an excusable outage is worth more than the damages rate attached to it.

AI in this KA

Where it earns its place: monitoring. Pass-through and indexation terms are formulae with published inputs, and an automated monthly recomputation of the escalation wedge (cost-weighted escalation less revenue-weighted escalation, and the projected year of covenant breach at current observed rates) is exactly the sort of persistent arithmetic that humans stop doing after financial close. Anomaly detection on input consumption against a plant model is similarly strong, and it is where a model earns operational trust before it is trusted with anything consequential. **Where it must not go:** forecasting the differential. The whole exposure in 11.2.3 turns on the spread between power escalation and a consumer price index over twelve years, and a model trained on recent history will extrapolate a regime rather than a relationship. Use scenarios owned by named people, not a machine point forecast, and note that a plausible-looking generated forecast is more dangerous than an obviously crude one because it survives review. **Verification, concretely:** require any automated escalation monitor to reproduce the year-one figures of the closing model exactly before its later years are believed — Kestrel's 6,384,000 and 1.2743 are the check — and require that any machine-produced sensitivity table state whether its cases are independent or joint, because non-additive tolerances presented additively is the error the tool will not flag.

■ KEY TERMS — KA 11.2

Term	Meaning
Pass-through share ϕ	Contractual share of an input-price movement recovered in revenue; multiplies coverage tolerance by $1/(1 - \phi)$.
Basis risk (pass-through)	Exposure remaining because the reference index differs from the price actually paid.
Indexation mismatch	Revenue index differs from the driver of cost escalation; appears as a trend in coverage, not in a single-year sensitivity.
Escalation wedge	Cumulative cash difference between a cost escalating at its own driver and the same cost escalating at the revenue index.
Fee at risk	The portion of an operator's fee forfeited on performance failure — its economic stake in the allocation.
Excusable outage	An unavailability event that does not count against the availability guarantee; the availability/force-majeure boundary.

■ SAMPLE MCQS — KA 11.2

MCQ 11.2-A [11.2.2 · Application] An input costs 1,800,000 a year; 70 % of its price movement passes through to revenue; covenant headroom is 372,437.72. The input-price rise that breaches the covenant is closest to:

- A. 20.7 %
- B. 69.0 % ✓ CORRECT
- C. 29.5 %
- D. 100.0 %

Rationale: Residual per 1 % = $1,800,000 \times 0.01 \times 0.30 = 5,400$; $372,437.72 / 5,400 = 68.97$ %. A ignores the pass-through (the $\phi = 0$ answer); C uses the **passed-through** share 0.70 in place of the retained share 0.30 ($372,437.72 / 12,600 = 29.56$ %) — the commonest sign error here; D assumes only a doubling of the input can breach, which no calculation supports.

MCQ 11.2-B [11.2.3 · Analysis] A project's DSCR is 1.2743 in year one, rises to 1.2863 in year five and falls to 1.2106 in year twelve. The soundest reading is:

- A. the structure is robust — coverage never breaches
- B. an indexation mismatch is consuming headroom; 85.7 % of it is gone by year twelve and the breach falls just outside the loan life ✓ CORRECT
- C. the model contains an error, since coverage cannot both rise and fall
- D. the improvement to year five shows revenue growth exceeding costs

Rationale: The shape is diagnostic of a cost driver escalating faster than the revenue index (11.2.3). A reads compliance as robustness and ignores that twelve basis points of forecast separate the two; C mistakes a normal profile for a defect; D is true only for the first five years and misses the trend.

MCQ 11.2-C [11.2.1 · Analysis] Why is asking an O&M contractor to bear input-price risk usually a mis-allocation?

- A. O&M contractors are not creditworthy
- B. it neither controls the price nor can hedge it, so it prices the worst case and the premium exceeds the retained expected cost ✓ CORRECT
- C. input prices are always passed through by law
- D. the risk is immaterial

Rationale: This is the 11.1.3 result applied to operations — neither ground for transfer is present. A is a separate (and secondary) objection; C asserts a universal legal position that does not exist; D is contradicted by 11.2.2's arithmetic.

MCQ 11.2-D [11.2.3 · Evaluation] Asked by a credit committee to test escalation, a model adds a percentage point to both the consumer price index and the power escalation rate, and reports that year-twelve DSCR rises from 1.2106 to 1.3088. The soundest reading is:

- A. the structure is insensitive to escalation: both drivers were stressed and coverage improved
- B. the model contains an error, since escalation must reduce coverage
- C. the test is not evidence — the exposure is the differential, which widens only from 2.70 to 2.90 percentage points under this stress while every escalating line simply grows, so the case must be re-run on the spread between the cost driver and the revenue index ✓ CORRECT
- D. the test is adequate once a volume stress is added alongside it

Rationale: Kestrel's revenue-weighted escalation of 2.00 % against a cost-weighted 4.70 % is the exposure; a stress that lifts both leaves that gap almost unchanged and makes the reported ratio look better, so it invites the opposite of the correct conclusion (11.2.3). A accepts a favourable output without asking what was varied — the level of power prices matters far less here than the spread. B mistakes a modelling artefact for an arithmetic defect. D adds a second variable without repairing the first, and the joint table it implies would still test the wrong thing.

MCQ 11.2-E [11.2.2 · Comprehension] A pass-through of 70 % of movements in an input price differs from a fixed-price supply contract for the same input in that the pass-through:

- A. removes the exposure entirely, as the fixed price does
- B. has no effect on coverage, since the cost is incurred either way
- C. removes the exposure while a fixed price merely defers it
- D. divides the exposure rather than removing it — the project keeps 30 % of every movement, and what it keeps also depends on the reference index and the reset frequency — whereas a fixed price replaces the price exposure with the supplier's willingness and ability to hold the price

✓ **CORRECT**

Rationale: A pass-through divides an exposure and multiplies coverage tolerance by $1/(1 - \phi)$; it eliminates nothing, and a share indexed to a published tariff the plant does not actually pay leaves basis risk inside the protected portion (11.2.2). A and C misstate what each instrument does — and a fixed price substitutes a counterparty credit question for a market one. B ignores that the retained residual falls straight through to CFADS, which is the quantity the covenant divides.

MCQ 11.2-F [11.2.4 · Evaluation] Kestrel's O&M agreement carries a 95 % availability guarantee with damages attached, and the project breaches its 1.20× covenant at **92.086 %** availability — so 2.9 percentage points of availability separate compliance from breach. With one negotiating session left on the O&M agreement, the finance leader should spend it on:

- A. the definition of an excusable outage — the availability/force-majeure boundary decides whether a lost month counts against the guarantee at all, and it is worth more than the rate attached to it because force majeure suspends performance obligations and never suspends debt service
- B. the damages rate for missed availability, which is the operator's financial incentive to perform
- C. the liability cap, which is scaled to the fee and therefore too small whatever the rate
- D. the fee at risk, which gives the operator a running stake rather than a terminal liability

✓ **CORRECT**

Rationale: With 2.9 points of availability between compliance and breach, the question that decides the covenant is which lost days are counted, not what is paid for the days that are — and an outage reclassified as excusable lands squarely on coverage with no recovery at all (11.2.4, 11.3.4). B funds the consequence rather than preventing it, and an operator's damages are capped on its fee in any case. C and D are both sound and both weaker: the cap is genuinely too small — a 30-day outage costs 742,000 against a half-fee cap of 600,000 — and fee at risk is genuinely the better incentive design, but each allocates money after the event, while the boundary definition determines whether there is a claim to make. The wider lesson is the one 11.3.4 states: insurance waiting periods, cure periods and availability carve-outs are calibrated in time while covenants are calibrated in cash, and somebody has to perform the translation. What counts as force majeure, and what relief it confers on which obligation, is a drafting and governing-law question in every contract — the structural asymmetry relied on here is that the facility agreement grants no equivalent relief; confirm the contractual position with qualified counsel before a coverage case is built on it.

■ SELF-CHECK — KA 11.2

1. State the pass-through multiplier and Kestrel's two tolerances. — Tolerance is multiplied by $1/(1 - \phi)$; 20.6910 % unprotected, 68.9699 % at $\phi = 0.70$, a $3.3333\times$ multiplier.
2. What single test detects an indexation mismatch? — Compare the revenue-weighted escalation rate with the cost-weighted rate (2.00 % against 4.70 % for Kestrel); a higher cost rate means the only open question is when it bites.
3. Why are separate tolerance percentages not additive? — They all consume the same 372,437.72 of headroom; joint movements require a joint matrix.

KNOWLEDGE AREA 11.3

Counterparty, political, currency, interest-rate and force-majeure risk

Topics: 11.3.1 interest-rate exposure and the hedge ratio · 11.3.2 currency mismatch · 11.3.3 the counterparty risk inside the allocation · 11.3.4 political, regulatory and force majeure.

11.3.1 Interest-rate exposure and the hedge ratio

The structure. Kestrel's senior facility is priced as a floating reference rate plus a **200 basis point margin**. At close the reference stood at **4.00 %**, giving the 6.00 % all-in rate Domains 3 and 10 used. The amortisation schedule fixes **principal** — year-one principal is 2,489,635.23 — so only the interest leg floats, and debt service in any period is **principal + outstanding × all-in rate**. An interest-rate swap is available that fixes the reference at **4.20 %**, above the spot rate because the curve slopes upward; the all-in fixed cost is therefore **6.20 %**.

WORKED EXAMPLE

Worked example 11.3.1 — what an unhedged Kestrel is actually exposed to.

1. **Setup.** Debt 42,000,000; year-one principal 2,489,635.23; CFADS 6,384,000; covenant 1.20×, lock-up 1.15×. Compute year-one DSCR across a ± 200 basis point range in the reference rate, unhedged, 75 % hedged and fully hedged; find the rate at which each threshold is crossed; and find the minimum hedge ratio that survives a 200 basis point shock.
2. **Formula.** Blended rate = $\text{swap all-in} \times h + \text{floating all-in} \times (1 - h)$; debt service = $2,489,635.23 + 42,000,000 \times \text{blended rate}$; DSCR = $6,384,000 \div \text{debt service}$. Breakeven rate: $((\text{CFADS} \div \text{target DSCR}) - \text{principal}) \div \text{debt}$. Minimum hedge ratio: $(\text{shocked rate} - \text{breakeven rate}) \div (\text{shocked rate} - \text{swap rate})$.
3. **Substitution and result.**

Reference shift	All-in rate	Interest	Debt service	DSCR unhedged	DSCR at h = 75 %	DSCR at h = 100 %
–200 bp	4.00 %	1,680,000	4,169,635.23	1.5311	1.3129	1.2533
–100 bp	5.00 %	2,100,000	4,589,635.23	1.3910	1.2851	1.2533
base	6.00 %	2,520,000	5,009,635.23	1.2743	1.2585	1.2533
+50 bp	6.50 %	2,730,000	5,219,635.23	1.2231	1.2456	1.2533
+100 bp	7.00 %	2,940,000	5,429,635.23	1.1758	1.2330	1.2533
+200 bp	8.00 %	3,360,000	5,849,635.23	1.0914	1.2085	1.2533

Unhedged breakeven rates: **6.7390 % (+73.9 bp)** for the 1.20× covenant, **7.2897 % (+129.0 bp)** for the 1.15× lock-up, **9.2723 % (+327.2 bp)** before scheduled debt service cannot be paid at all. Full hedge: interest 2,604,000, debt service 5,093,635.23, **DSCR 1.2533** at any reference rate, at a year-one cash cost of **84,000**. Minimum hedge ratio surviving +200 bp at the covenant: **70.0576 %**.

4. **Result.** Unhedged, **74 basis points** of reference rate stand between this project and a covenant breach. The swap costs **0.0210 of DSCR** and removes **0.4397 of DSCR range** — 20.92 units of range eliminated per unit of coverage given up.

5. **Interpretation.** Three professional conclusions, in order of how often they are missed. **Interest-rate exposure is a covenant exposure long before it is a payment exposure.** The distance to a breach is 73.9 basis points; the distance to a payment failure is 327.2. A treasury discussion framed around "can we afford the interest?" is answering the wrong question by a factor of four and a half, and the right question — at what reference rate does our first covenant fail? — has a single computable answer that belongs on the same dashboard as Domain 10's 6,011,562.28 cash trigger. **The hedge is bought with coverage, and the exchange rate is extraordinarily favourable.** Giving up 0.0210 of ratio to remove 0.4397 of range is not a close call, and the reason it is nonetheless argued is that the 84,000 is certain and visible while the range is contingent and invisible. That asymmetry of salience, not the economics, is what produces under-hedged project financings. **And the right answer is a ratio, not a binary.** A 75 % hedge leaves 10,500,000 floating, holds the covenant at +200 bp with **1.2085**, and costs only **63,000** a year — three-quarters of the full hedge cost for the protection that matters, while retaining a quarter of the benefit of falling rates. The **70.0576 %** minimum is why facilities covenant a hedging ratio rather than a full hedge: below it the structure fails the lenders' own rate stress, and above it the incremental protection is bought at a diminishing rate. Two cautions belong with the arithmetic. A swap is not free of risk — it introduces **mark-to-market exposure** (a break cost on prepayment or refinancing, which can be large when rates have fallen) and a **hedge counterparty** whose own credit is now inside the structure (11.3.3). And the figures above are year one; the exposure declines with the outstanding balance, so a hedge profile should amortise with the loan rather than sit flat, or the project will be over-hedged in its later years and paying for protection it no longer needs.

A swap costs 0.0210 of coverage and removes 0.4397 of range — 20.92 units of range per unit given up

Principal is fixed by the schedule at 2,489,635.23; only interest floats. Swap rate 4.20 % + 200 bp margin = 6.20 % all-in

70.06 % is the minimum hedge ratio that survives a 200 bp shock — which is why lenders covenant a ratio, not a full hedge




Fig 11.3.1 — Coverage against the reference rate, at three hedge ratios

11.3.2 Currency mismatch

Definition. A **currency mismatch** exists when a project's revenue and its debt service are denominated in different currencies. It is the most destructive of the financial risks because, unlike an interest-rate movement, a devaluation is **unbounded and correlated with everything else that goes wrong in a host economy** — and because it cannot be hedged for a twelve-year tenor in most markets at any price a project can pay.

Kestrel's water-purchase agreement is denominated in USD, which is why Domains 2 to 10 could treat its revenue as a USD figure. That term was not free, and this KA prices the alternative the offtaker pressed for: a tariff denominated wholly in the host currency (HC), with the USD debt unchanged.

WORKED EXAMPLE**Worked example 11.3.2 — the tariff term that was worth more than the tariff.**

- Setup.** Assume the exchange rate at close is **HC 4.00 = USD 1** (an illustrative rate for a fictitious currency; no real currency or jurisdiction is implied). Under the **HC-tariff** variant, revenue is **HC 48,000,000**; of the 4,500,000 of cash operating costs, **1,350,000 is USD-denominated** (imported membranes, chemicals, specialist spares) and the balance of 3,150,000 is local (**HC 12,600,000**); cash tax **HC 2,064,000** and the working-capital movement **HC 2,400,000** are local. Debt service remains **USD 5,009,635.23**. Compute the coverage consequence of devaluation and the exchange-rate-indexed revenue share that protects it.
- Formula.** $CFADS \text{ in USD} = (HC \text{ revenue} - HC \text{ costs} - HC \text{ tax} - HC \text{ working capital}) \div x - USD \text{ costs}$, where x is **HC per USD**. Breakeven x for a target ratio: $local \text{ numerator} \div (target \times debt \text{ service} + USD \text{ costs})$. Debt-service-matching indexed share = $(debt \text{ service} + USD \text{ operating costs}) \div revenue$.
- Substitution.** Local numerator = $48,000,000 - 12,600,000 - 2,064,000 - 2,400,000 = HC \text{ } 30,936,000$. At $x = 4.00$: $30,936,000 / 4.00 - 1,350,000 = 6,384,000$ — the master thread reproduced, which is the check that the decomposition is right.
- Result.**

HC per USD	Devaluation	CFADS (USD)	DSCR
4.000000	—	6,384,000	1.2743
4.202369	+5.06 %	6,011,562	1.2000 — covenant
4.350394	+8.76 %	5,761,081	1.1500 — lock-up
4.400000	+10.00 %	5,680,909	1.1340
4.864430	+21.61 %	5,009,635	1.0000 — cannot pay
5.000000	+25.00 %	4,837,200	0.9656

The **debt-service-matching indexed share** is $6,359,635.23 / 12,000,000 = 52.997 \%$. The **minimum indexed share** that holds the covenant through a 25 % devaluation is **48.9318 %**. At the matching 52.997 % share, a 25 % devaluation leaves **CFADS** of **6,109,128** and a **DSCR** of **1.2195**, and the covenant survives devaluation up to **+37.17 %**. 5. **Interpretation.** The headline is stark enough to be worth stating plainly: **a 5.06 % currency movement breaches this project's covenant, and a 21.61 % movement stops it paying its debt.** For comparison, the interest-rate exposure of 11.3.1 required 73.9 basis points — a rare event in a quiet market — while a 5 % currency move is a routine month in many host economies. Unhedged currency mismatch is therefore not one risk among many; on these numbers it is the **binding** exposure, larger than rates, availability (Domain 7's 2.9 availability points) and input prices combined. **Note also what the arithmetic quietly reveals about "natural hedges".** Local costs do fall in USD terms as the currency weakens, which is why the exposure is 30,936,000 of local numerator rather than the full 48,000,000 of revenue — but the offset is far too small, because debt service (5,009,635.23) and USD operating costs (1,350,000) are **52.997 %** of base-case revenue and do not devalue at all. A project whose costs are mostly local and whose debt is entirely foreign has a natural hedge on the wrong side of the balance sheet. **The remedy is indexation, and it has a number.** Indexing 52.997 % of the tariff to the exchange rate — exactly the share that funds USD outflows — is the structurally clean ask, and it lifts the tolerable devaluation from 5.06 % to 37.17 %. The covenant-preserving minimum against a specified 25 % stress is 48.93 %, only 4.07 points lower, which is a useful negotiating fact: the clean structural ask is

barely more expensive than the minimum defensible one, so there is little to be gained by conceding to a partial share. **And two limits must be stated honestly.** Indexation protects **debt service, not equity return**: full **DSCR** neutrality is impossible while any local surplus exists, because that surplus keeps shrinking in USD terms — at the 52.997 % share a 25 % devaluation still costs 274,872 of **CFADS**. And indexation is a **transfer to the offtaker**, so the pricing test of 11.1.3 applies: the offtaker does not control the exchange rate, so the transfer must be justified on **capacity** grounds — a public or utility payer with local-currency revenue and sovereign-adjacent standing bears a devaluation that would destroy the SPV — and it will be paid for in the tariff. That is a legitimate, well-grounded transfer; the illegitimate version is a sponsor accepting an unindexed **HC** tariff because the offtaker insisted, which is 11.1.2's bargaining-power allocation with a five-per-cent trigger attached.

11.3.3 The counterparty risk inside the allocation

The principle. Every risk successfully transferred becomes a **credit exposure** to the party that took it. The allocation table of 11.1.3 removed 4,420,000 of expected cost from Kestrel's balance sheet and replaced it with a claim on the EPC contractor — and that claim is worth the contractor's willingness and ability to pay.

The arithmetic that matters is conditional, not unconditional. Take the transferred bundle at 4,420,000 of avoided expected cost, an assumed recovery of 30 % on the contractor's obligations, and a two-year probability of default of 1.5 % for a contractor of the assumed standing. Expected credit loss on the transfer is $0.015 \times 0.70 \times 4,420,000 = 46,410$ — 12.46 % of annual covenant headroom, and easy to dismiss. But the unconditional probability is the wrong one. **The contractor most likely to default is the one that has already incurred the losses it was allocated**, so the relevant figure is the probability of default conditional on a claim of the size the allocation contemplates. At a conditional probability of 12 %, expected credit loss becomes $0.12 \times 0.70 \times 4,420,000 = 371,280$ — **99.69 %** of the entire annual covenant headroom of 372,437.72.

What matters is not the coincidence of the two magnitudes but the **eightfold difference between the two calculations**, and the fact that the conditional one is almost never done. Risk transfer converts a diversifiable operational exposure into a concentrated, correlated credit exposure, and the correlation is structural: the state of the world in which the guarantee is needed is the state in which the guarantor is weakest. Three consequences follow. **Test the guarantor, not the guarantee** — Domain 5's distinction between joint and several liability, and the standing of the entity behind a commitment, decides what a cap is worth. **Require the credit support to sit above the operating entity**, so that a trading counterparty's promise becomes a claim on a balance sheet or a bank. And **count the counterparties**: after allocation Kestrel's coverage depends on the EPC contractor, the operator, the offtaker (Domain 7 priced its credit at 0.0400 of **DSCR**, 53.7 % of its total expected-loss exposure), the hedge counterparty of 11.3.1, the insurers of 11.3.4 and the sponsors behind Domain 5's 24,000,000 of committed capital. Six credit dependencies are six ways to lose the protection the project paid for, and a **counterparty concentration schedule** — exposure, mechanism, cap, credit standing, correlation of the call with that standing — makes them visible (11.T.2).

11.3.4 Political, regulatory and force-majeure risk

Political and regulatory risk covers expropriation, currency inconvertibility and transfer restriction, breach of undertaking by a state counterparty, and adverse change in law, tax or regulated tariff. Its allocation is unusual in that the natural transferee is often not a commercial party at all: political risk insurance and the guarantee products of export credit agencies and multilateral development institutions exist precisely because private parties cannot bear these exposures (Domain 9 covers the instruments; the allocation view here is that they are **capacity transfers**, and the pricing test applies unchanged). Change-in-law risk is the one commonly split rather than

allocated: discriminatory change (aimed at the project or its sector) to the state, general change to the project, is a widely used convention — but conventions are not law, and the line between the two categories is where the disputes live.

Force majeure is the allocation of last resort: it allocates a risk to **nobody**, suspending obligations rather than shifting cost. That structure is right for genuinely uncontrollable, uninsurable events, and it has a specific financial consequence that projects consistently under-model: relief from performance obligations does not relieve **debt service**. The lenders' schedule continues, so a force-majeure event that suspends the operator's availability obligation lands squarely on coverage.

WORKED EXAMPLE

Worked example 11.3.4 — the insurance waiting period nobody checks against the covenant.

- Setup.** Kestrel carries business-interruption cover with a **60-day waiting period** — the insurer indemnifies lost margin only for the portion of an outage beyond 60 days. Daily CFADS is $6,384,000/360 = 17,733.33$ (Domain 5's 30/360 basis). Covenant headroom is 372,437.72. Determine the maximum outage the covenant survives, and the effect of outages of 21, 30 and 60 days.
- Formula.** Uninsured days = $\min(\text{outage days}, \text{waiting period})$; lost CFADS = uninsured days $\times$ daily CFADS; maximum survivable days = headroom $\div$ daily CFADS.
- Substitution.** $372,437.72 / 17,733.33$; then CFADS – days $\times 17,733.33$, divided by 5,009,635.23.
- Result.**

Outage	Uninsured days	Lost CFADS	CFADS	DSCR
21 days	21	372,400	6,011,600	1.2000 — exactly at covenant
30 days	30	532,000	5,852,000	1.1681 — breach
60 days	60	1,064,000	5,320,000	1.0620 — breach, below lock-up
90 days	60 (capped by the waiting period)	1,064,000	5,320,000	1.0620

The maximum survivable outage is **21.0021 days**, so the maximum tolerable waiting period is **21 days**. 5. **Interpretation.** The insurance programme and the finance documents were negotiated by different teams against different units, and the result is a structural gap nobody owns: **the waiting period is 60 days and the covenant survives 21**. Any outage longer than three weeks breaches, and the insurance — which is doing its job perfectly — pays nothing until the covenant has already failed by a wide margin. The insight generalises beyond insurance: **deductibles, waiting periods, cure periods, grace periods, notice periods and reporting lags are all calibrated in time, while covenants are calibrated in cash, and the translation between the two is almost never performed**. Three responses are available and should be priced against one another: buy down the waiting period towards 21 days (the cheapest fix if the market offers it); size the debt-service reserve to bridge the gap — Domain 10's six-month DSRA of 2,504,818 comfortably funds the 1,064,000 maximum uninsured loss, so payment continuity is not at issue and only compliance is; or negotiate a covenant carve-out for insured events within the waiting period, which is the cleanest answer and the one most often overlooked because it must be asked for before close. Note finally the shape of the exposure: it is **capped** at 1,064,000 by the waiting period itself, so this is a high-probability, bounded exposure — the opposite profile from the currency mismatch of 11.3.2 — and it should be managed with a reserve or a carve-out rather than with capital.

AI in this KA

Where it earns its place: the translation layer. Every number in this KA is a mechanical consequence of terms written in documents — a margin, a waiting period, a hedging covenant, an indexation formula — and the failure mode is that the translation is done once at close and never again. A monitored model that recomputes, every month, the reference rate at which the covenant fails, the exchange rate at which it fails, the outage length at which it fails and the hedge ratio in force against the ratio covenanted is high-value automation with a low error surface, because each output is a closed-form calculation against a stated document term. Extraction of hedging covenants, waiting periods and caps from a document suite is the same strong application named in 11.1.

Where it must not go: rate, currency and event forecasting. A model asked what the reference rate or the exchange rate will be in year seven will answer, and the answer will carry no information; the governed use is to compute the **breakeven** — the level at which something breaks — because a breakeven is a fact about the structure rather than a prediction about the world. Equally, the question of whether a set of facts constitutes force majeure, or a discriminatory change in law, is a legal determination for qualified counsel and not a model output. **Verification, concretely:** require each monitored breakeven to be reproducible by hand from the closing model on one period — the check values are 6.7390 %, HC 4.202369 and 21 days — and re-verify after any amendment, because the recurring failure is a monitor that keeps computing correctly against superseded terms.

■ KEY TERMS — KA 11.3

Term	Meaning
Hedge ratio	Share of floating debt fixed by swap or cap; lenders covenant a minimum rather than a full hedge.
Breakeven rate / breakeven exchange rate	The level at which a named covenant fails; a fact about the structure, not a forecast.
Mark-to-market (swap)	The break cost of terminating a hedge early — an exposure a swap creates rather than removes.
Currency mismatch	Revenue and debt service in different currencies; unbounded and correlated with host-economy stress.
Exchange-rate-indexed share	The portion of tariff linked to the exchange rate; the debt-service-matching share funds USD outflows.
Conditional probability of default	Default probability given a claim of the size the allocation contemplates — the relevant figure for transferred risk.
Waiting period / deductible	Time or amount an insured bears before indemnity; must be tested against covenant headroom in days.
Force majeure	Allocation to nobody: obligations suspend, debt service does not.

■ SAMPLE MCQS — KA 11.3

MCQ 11.3-A [11.3.1 · Application] Debt 42,000,000; fixed year-one principal 2,489,635.23; CFADS 6,384,000; covenant 1.20×. The all-in interest rate at which the covenant fails is closest to:

- A. 6.00 %
- B. 6.74 % ☒ **CORRECT**
- C. 8.00 %
- D. 9.27 %

Rationale: Maximum debt service = $6,384,000/1.20 = 5,320,000$; maximum interest = $2,830,364.77$; $\div 42,000,000 = 6.7390\%$. A is the rate at close; C is a +200 bp shock, at which the ratio is already 1.0914; D is the rate at which debt service cannot be paid at all — a different and much later threshold.

MCQ 11.3-B [11.3.1 · Analysis] A swap moves year-one DSCR from 1.2743 to 1.2533 and replaces a 1.0914–1.5311 range with a single value. The correct characterisation is:

- A. the swap is uneconomic, since coverage falls
- B. 0.0210 of coverage is given up to remove 0.4397 of coverage range — 20.92 units of range per unit surrendered ☒ **CORRECT**
- C. the swap eliminates all interest-rate exposure and creates no new exposure
- D. the swap is unnecessary because the project can pay debt service up to 9.27 %

Rationale: The trade is certainty for a small, certain cost (11.3.1). A counts the cost and not the benefit; C ignores mark-to-market and hedge-counterparty exposure; D confuses the payment threshold with the covenant threshold.

MCQ 11.3-C [11.3.2 · Application] Local numerator HC 30,936,000, USD operating costs 1,350,000, debt service 5,009,635.23, rate at close HC 4.00 = USD 1, covenant 1.20x. The devaluation at which the covenant fails is closest to:

- A. 5.1 % ☒ **CORRECT**
- B. 15.9 %
- C. 21.6 %
- D. 25.0 %

Rationale: Covenant CFADS = $5,009,635.23 \times 1.20 = 6,011,562.28$; $x = 30,936,000 \div (6,011,562.28 + 1,350,000) = 4.202369$, i.e. +5.06 %. B divides CFADS by the covenant instead of multiplying debt service by it — the commonest covenant-trigger error; C is the point at which the DSCR reaches 1.00; D is the illustrative stress case, at which the ratio is already 0.9656.

MCQ 11.3-D [11.3.4 · Analysis] Business-interruption cover has a 60-day waiting period; daily CFADS is 17,733.33 and covenant headroom is 372,437.72. The most useful statement for the finance committee is:

- A. the cover is adequate, since the maximum uninsured loss of 1,064,000 is within the DSRA
- B. the covenant survives 21 days of outage while the waiting period is 60 — so any outage beyond three weeks breaches, and a carve-out or a bought-down waiting period is required ☒ **CORRECT**
- C. the waiting period should be extended to reduce premium
- D. force majeure relief will suspend debt service during the outage

Rationale: The gap between a time-calibrated insurance term and a cash-calibrated covenant is the finding (11.3.4). A is true about payment and silent about compliance — the distinction of Domain 10, KA 10.2.1; C widens the gap; D is false, since force majeure suspends performance obligations and not debt service.

MCQ 11.3-E [11.3.2 · Evaluation] The offtaker will accept a host-currency tariff with 40 % of it indexed to the exchange rate. The debt-service-matching share is 52.997 % and the covenant-preserving minimum against a 25 % devaluation is 48.9318 %. The bid team argues that partial indexation is better than none. The soundest position is:

- A. accept 40 %: partial protection is better than none, and the offtaker has moved once already

- B. refuse any host-currency tariff, since a twelve-year currency mismatch cannot be managed
- C. hold for a share at or above 48.9318 %: at 40 % the covenant fails on a **14.54 %** devaluation and a 25 % devaluation leaves a **DSCR** of **1.1572**, while the clean structural ask of 52.997 % sits only 4.07 points above the minimum defensible one ✓ CORRECT
- D. accept 40 % and hedge the residual exposure in the swap market

Rationale: The tolerable devaluation runs 5.06 % unindexed, 14.54 % at a 40 % share and 37.17 % at the matching share, and because the matching share is barely more expensive than the minimum there is little to be gained by conceding to a partial one (11.3.2). A treats any movement as progress without testing it against the covenant. B forgoes a transfer that is well grounded on **capacity** — a payer with local-currency revenue and sovereign-adjacent standing bears a devaluation that would destroy the SPV — and it will be paid for in the tariff. D assumes a market that does not exist for a twelve-year tenor in most host economies at any price a project can pay.

MCQ 11.3-F [11.3.1 · Comprehension] Saying "the covenant fails at an all-in rate of 6.7390 %" is a different kind of statement from forecasting the reference rate because a breakeven:

- A. is a more accurate forecast, being derived from the schedule rather than from the market
- B. is the same statement expressed in different units
- C. rests on no assumptions at all
- D. is a fact about the structure — the level at which a named test fails, given the schedule, the **CFADS** definition and the covenant — while a forecast is a claim about the world ✓ CORRECT

Rationale: This is why the governed use of a model here is to compute breakevens rather than to predict rates: a breakeven can be monitored against a document, whereas a prediction can only be owned (11.3.1). A collapses the two categories into one. C overstates — the 6.7390 % still depends on the **CFADS** figure and the fixed-principal schedule it is computed from, which is why it must be recomputed after any amendment. B ignores that one statement is conditional and the other predictive.

MCQ 11.3-G [11.3.1 · Evaluation] Treasury proposes to leave Kestrel's floating facility unhedged, on the ground that scheduled debt service can be paid up to an all-in rate of **9.2723 %** and the reference rate stands at 4.00 %. A full hedge fixes coverage at **1.2533** at a year-one cash cost of **84,000**; a 75 % hedge holds **1.2085** at +200 basis points for **63,000**; and the minimum hedge ratio surviving that shock at the covenant is **70.0576 %**. The recommendation should be:

- A. hedge at not less than 70.06 %, and in practice at 75 %: the exposure that binds is the covenant at **+73.9 basis points**, not payment at +327.2, and 0.0210 of coverage buys the removal of 0.4397 of coverage range — 20.92 units of range per unit surrendered ✓ CORRECT
- B. leave it unhedged: **327 basis points** of reference-rate headroom to payment failure is ample, and the 84,000 is a certain cost against a contingent exposure
- C. hedge fully: a single covenanted coverage figure at any reference rate is the only defensible position for a project financing
- D. leave it unhedged and rely on the debt service reserve, which covers a rate shock as readily as a cash shortfall

Rationale: Interest-rate exposure is a covenant exposure long before it is a payment exposure, and treasury has answered the question four and a half times too generously (11.3.1). B is the under-hedging error in its usual form — the certain 84,000 is visible and the contingent range is not. C is the defensible weaker course and a common covenanted outcome: it does remove the whole range, and it pays 84,000 rather than 63,000, forgoes every benefit of falling rates, and enlarges the mark-

to-market break cost that a later refinancing must pay. D misreads what a reserve does: it buys payment continuity and time, not compliance, and the breach at +73.9 basis points happens with the reserve fully funded. Two disciplines belong with A — the hedge profile should amortise with the outstanding balance rather than sit flat, and the hedge counterparty's own credit is now inside the structure.

■ SELF-CHECK — KA 11.3

1. State Kestrel's three unhedged interest-rate breakevens. — Covenant at 6.7390 % (+73.9 bp), lock-up at 7.2897 % (+129.0 bp), payment failure at 9.2723 % (+327.2 bp).
2. Why is the unconditional probability of default the wrong input for transferred risk? — The counterparty most likely to default is the one that has already incurred the allocated loss; Kestrel's expected credit loss moves from 46,410 to 371,280 on that correction.
3. State the maximum tolerable insurance waiting period for Kestrel and why. — 21 days: covenant headroom of 372,437.72 divided by daily [CFADS](#) of 17,733.33.

KNOWLEDGE AREA 11.4

Environmental and social, technology, cybersecurity and AI model risk

Topics: 11.4.1 the operating-phase register · 11.4.2 why a lender re-cuts it · 11.4.3 AI model risk as a register line · 11.4.4 from register to debt capacity.

11.4.1 The operating-phase register

The construction register of KA 11.1 has a counterparty and therefore a price. The operating register usually has neither: there is no single party to whom environmental compliance, technology underperformance, a cyber intrusion or a model error can be transferred, so these risks are managed, insured in part, reserved against, and otherwise **retained**. That makes their quantification more important, not less, because retained risk is the only kind that shows up directly in coverage.

Definitions worth fixing. **Environmental and social risk** is the risk of loss from non-compliance with environmental consents, from social-licence failure, or from the conditions attached to lender environmental and social standards — which are contractual obligations in a project financing, not aspirations, and whose breach is an event of default in many facilities. **Technology risk** is the risk that plant performs below its warranted characteristics over life rather than at completion: degradation faster than warranted, consumables consumed faster than modelled, obsolescence of a control system. **Cybersecurity risk**, in an industrial project, is primarily an **availability** risk on the operational-technology network rather than a data risk, and it is therefore a [CFADS](#) risk with the same shape as any other outage (11.3.4's arithmetic applies). **Model risk** is, on the shared registry's definition, the risk of loss from decisions based on flawed, misused or misunderstood models — financial or AI.

WORKED EXAMPLE**Worked example 11.4.1 — Kestrel's operating register, aggregated on the Domain 8 method.**

1. **Setup.** Six retained operating-phase items, each quantified once over the loan life. The aggregation machinery is PML-AI Domain 8's (KA 8.2.2 and 8.2.4) and is not re-derived: $EMV = p \times \text{impact}$; for independent items $\text{mean} = \Sigma EMV$ and $\text{variance} = \Sigma p(1 - p) \times \text{impact}^2$; a $P80 \approx \text{mean} + 0.8416\sigma$.
2. **Formula.** As above; then the same aggregation with a uniform pairwise correlation ρ , for which $\text{variance} = (1 - \rho)\Sigma \sigma_i^2 + \rho(\Sigma \sigma_i)^2$.
3. **Substitution and result.**

ID	Retained operating risk	p	Impact (USD)	EMV (USD)
O1	Discharge-consent breach requiring plant modification	0.15	3,200,000	480,000
O2	Community objection interrupting intake maintenance access	0.10	1,500,000	150,000
O3	Membrane flux decline faster than warranted (technology)	0.20	2,600,000	520,000
O4	Cyber intrusion on the control network: outage plus remediation	0.12	4,500,000	540,000
O5	AI dosing-optimisation model error producing off-spec output	0.25	900,000	225,000
O6	Asset-model drift causing deferred-maintenance catch-up	0.30	700,000	210,000
Mean exposure				2,125,000

Variance (independent) **4,982,875,000,000**; σ **2,232,235**; **P80 4,003,649**. At $\rho = 0.30$, σ rises to **3,227,338** and the **P80 to 4,841,128** — an uplift of **837,478**, or **20.92 %**. 4. **Result.** The register's mean is **USD 2,125,000** and its P80 **USD 4,003,649** on an independence assumption that raises it to **USD 4,841,128** once a modest correlation is admitted. 5. **Interpretation.** Two observations do most of the work. **The modern risk classes dominate the register.** Cyber (540,000) and the two model-risk lines (435,000 combined) contribute 975,000 of the 2,125,000 mean — 45.9 % — and the cyber item, with the largest single impact, contributes the largest share of the variance and therefore of the tail. A register written five years earlier would have carried none of these lines, and a project whose register still does not is not less exposed, merely less informed. **The independence assumption is expensive.** The 837,478 uplift at $\rho = 0.30$ is more than twice Kestrel's entire annual covenant headroom, and correlation here is not hypothetical: O1 and O2 are both consequences of the same community and regulatory environment, and O5 and O6 are both consequences of the same data pipeline and the same modelling culture. Where items share a cause, independence is a choice to under-provide, and the choice should be stated in the paper rather than embedded in the arithmetic. PML-AI Domain 8's two standing cautions carry over unchanged: the normal approximation is a convenience for a handful of Bernoulli items, and a simulation over the register is the proper instrument where the answer is decision-critical.

11.4.2 Why a lender re-cuts the register

A lender does not accept a sponsor's register, and the reason is structural rather than adversarial: **the two parties have different loss functions.** Equity holds the upside and the downside, so its rational provision is near the middle of the distribution. A lender holds a fixed claim: it captures none of the upside, so every dollar of distribution above its expectation is irrelevant to it while every dollar

of shortfall is loss. A rational lender therefore prices the **tail**, not the mean, and it does so by re-cutting the register's inputs rather than by arguing about the output.

WORKED EXAMPLE

Worked example 11.4.2 — the same register, on the lender's basis.

1. **Setup.** The lender's technical and E&S advisers re-cut the register of 11.4.1: probabilities at **1.5×** the sponsor's (the upper end of the plausible range rather than the central estimate), impacts at **1.4×** (a P80 within each item's own impact range rather than its mode), and a uniform pairwise correlation of **0.30** in place of independence. These multipliers are illustrative of the direction and order of magnitude advisers apply; the actual re-cut is item-specific and evidenced.
2. **Formula.** As 11.4.1, on the re-cut inputs.
3. **Result.** Lender EMVs: O1 1,008,000 · O2 315,000 · O3 1,092,000 · O4 1,134,000 · O5 472,500 · O6 441,000. **Lender mean 4,462,500; σ 5,253,726; lender P80 8,884,036.**
4. **Interpretation.** The single most useful comparison in this KA: **the lender's expected case (4,462,500) exceeds the sponsor's 80th percentile (4,003,649) by 458,851 — a ratio of 1.1146 — and the lender's P80 is 4.1807 times the sponsor's mean.** A sponsor who arrives at a credit committee expecting to negotiate a percentile has misread the disagreement: the parties are not arguing about confidence levels, they are working from different input sets, and the only productive negotiation is **item by item on the evidence** — this probability, on this ground investigation; this impact, on this remediation quotation. Two further consequences deserve stating. **The gap is a financeable quantity, not a debating point:** it will be closed by a reserve, a sponsor commitment, a contingent equity undertaking or less debt, and the sponsor's choice among those is a real commercial decision (Domain 8's distinction between funded cash and a posted commitment applies directly). And **the re-cut is where AI-assisted analysis is most tempting and least appropriate:** a model asked to "produce the bank case" will multiply, which is precisely the intellectually empty version of the exercise the arithmetic above is designed to expose. Multipliers illustrate; evidence decides.

11.4.3 AI model risk as a register line

Definition. In a project financing, **AI model risk** is the risk of loss arising from a decision taken, or an action executed, on the output of a machine-learning model — whether because the model was wrong, because it was used outside the conditions it was validated for, or because its output was misunderstood by the person who acted on it. Kestrel's register carries two such lines: **O5**, an optimisation model that sets chemical dosing and can drive output off specification, and **O6**, an asset model whose drift defers maintenance that later has to be caught up.

Three properties distinguish AI model risk from the other register lines. **The impact distribution is fat-tailed relative to the probability:** most model errors are small and self-correcting, but a model with authority over a physical process can produce a large excursion quickly, and a single $p \times$ impact pair compresses that shape. **It is correlated with everything the model touches,** so one model feeding dosing, energy optimisation and maintenance planning creates a common cause across three otherwise independent register lines — a concrete reason the $p = 0.30$ case of 11.4.1 is the honest one. And **its probability is a function of governance rather than of nature:** unlike a membrane's degradation rate, p here is set by whether validation, monitoring, drift detection, human approval and rollback exist. That last property makes it the one register line whose probability the

project can genuinely change — which by 11.1.2's logic makes the project its own best holder of the risk, and controls worth more than transfer.

For allocation purposes the practical settlement is: the **vendor** takes defect and availability risk on the software within a liability cap that will be small relative to the exposure; the **operator** takes the risk of using the model outside its validated envelope, backed by procedure and training; and the **project retains the consequence**, provisions for it in the register, and manages it with the control set Domain 16 specifies. Two negotiating points are worth naming because they are so often missed: the right to the **model's validation evidence and monitoring outputs** (without which the project cannot demonstrate its own p), and the right to **operate without the model** — a documented manual fallback, which converts a dependency into a preference and is the cheapest single mitigation available.

11.4.4 From register to debt capacity

A register is not a document; it is a **debt-capacity input**. The translation is short: convert the register's present-value exposure into an annual equivalent over the loan life using the loan-rate annuity factor, deduct it from **CFADS**, and read the coverage.

WORKED EXAMPLE

Worked example 11.4.4 — what Kestrel's register does to its coverage and its debt.

- Setup.** $AF(0.06, 12) = 8.383844$; **CFADS** 6,384,000; debt service 5,009,635.23; covenant $1.20\times$. Test the five register measures of 11.4.1 and 11.4.2.
- Formula.** Annual equivalent = PV exposure $\div AF(0.06, 12)$; stressed **CFADS** = 6,384,000 – annual equivalent; **DSCR** = stressed **CFADS** $\div$ 5,009,635.23. Covenant-preserving maximum PV exposure = headroom $\times AF(0.06, 12)$.
- Result.**

Register measure	PV exposure	Annual equivalent	Stressed CFADS	DSCR
Sponsor mean	2,125,000	253,464	6,130,536	1.2237 — holds
Sponsor P80, independent	4,003,649	477,543	5,906,457	1.1790 — breach
Sponsor P80, $p = 0.30$	4,841,128	577,435	5,806,565	1.1591 — breach, near lock-up
Lender mean	4,462,500	532,274	5,851,726	1.1681 — breach
Lender P80	8,884,036	1,059,661	5,324,339	1.0628 — breach

The **covenant-preserving maximum PV exposure** is $372,437.72 \times 8.383844 = \text{USD } 3,122,460$. On the lender's P80 the sustainable debt at $1.20\times$ falls to $(5,324,339/1.20) \times 8.383844 = \text{USD } 37,198,687 - 4,801,313$ less than the 42,000,000 drawn. 4. **Interpretation.** This table is the domain's closing argument. **Kestrel's covenant survives its own operating risk register only at the mean.** At its own P80 — the confidence level its own contingency policy uses for construction (Domain 8) — the covenant fails, and it fails on every one of the lender's measures. The number to carry away is the **3,122,460 covenant-preserving ceiling**: that, and not a percentage of capex or an industry norm, is how much present-value operating risk this structure can absorb, and it is directly comparable with the register's own 4,003,649. The gap of 881,189 is the honest size of the

problem, and it has exactly the same four resolutions as any coverage shortfall (Domain 10, KA 10.1.2): more cash, lower required coverage, longer tenor, or less debt — with the fifth, more equity, as the residual. **The lender's arithmetic is the same arithmetic.** Its re-cut register removes 4,801,313 of debt capacity, which is why a diligence process that appears to be about risk management is in fact a negotiation about the debt quantum, and why a sponsor who cannot reproduce the calculation above will not understand what it is conceding. Two cautions bound the method. The **annuity-equivalent conversion is a simplification**: register events are lumpy and dated, and a proper treatment models each in the year it is assumed to fall, which will produce a worse minimum **DSCR** than the levelised figure shown here because coverage is tested in periods. And the **register and the estimate range must not be added** — Domain 8's demonstration on the construction side applies unchanged to operations.

AI in this KA

Where it earns its place: three specific, high-value uses. Extracting environmental and social obligations from consents and lender standards into a monitored obligation register, which is document work at a volume humans do badly. Anomaly detection on operational-technology telemetry, where a model that flags a deviation for a human to investigate is doing what machines are for. And **register completeness challenge** — asking what a comparable project's register contains that this one does not, which is where the model's breadth is a genuine advantage over an individual's experience. **Where it must not go:** into the probability and impact columns (11.1's rule, and here it bites harder because there is no counterparty pricing the risk to provide an external check); into autonomous action on a physical process without a human approval step and a tested rollback; and into producing the bank case by multiplication (11.4.2). **Verification, concretely:** treat every model in the operating envelope as a register line with a named owner, a validation date, a monitored drift metric and a documented manual fallback — a model without those four attributes is an unquantified register line, which is the definition of an unmanaged risk. Recompute the register's mean by hand and require it to equal ΣEMV before any percentile is quoted. And require any automated register aggregation to state its correlation assumption explicitly on the face of its output, because independence is the assumption tools default to and the assumption that is worth 837,478 here. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 11.4

Term	Meaning
Environmental and social risk	Loss from consent breach, social-licence failure or breach of lender E&S standards — contractual, not aspirational.
Technology risk	Under-performance over life (degradation, consumption, obsolescence) rather than at completion.
Cybersecurity risk (project)	Primarily an availability risk on the operational-technology network; a CFADS risk.
AI model risk	Loss from decisions or actions taken on model output — wrong model, wrong envelope, or misunderstood output.
Bank case	The lender's re-cut of the register: higher probabilities, higher impacts, correlation admitted.
Correlation uplift	The increase in a percentile from admitting $\rho > 0$; 837,478 at $\rho = 0.30$ on Kestrel's register.
Covenant-preserving exposure ceiling	Headroom $\times AF(r, n)$ — the present-value risk a structure can absorb (3,122,460 for Kestrel).

■ SAMPLE MCQS — KA 11.4

MCQ 11.4-A [[11.4.1 · Application](#)] A register of independent items has a mean of 2,125,000 and a variance of 4,982,875,000,000. Its P80 is closest to:

- A. 2,125,000
- B. 4,003,649 ✓ CORRECT
- C. 4,357,235
- D. 4,841,128

Rationale: $\sigma = 2,232,235$; $P80 = 2,125,000 + 0.8416 \times 2,232,235 = 4,003,649$. A is the mean, which is exceeded roughly half the time; C applies a 1.0- σ (P84) factor instead of 0.8416; D is the P80 once a 0.30 correlation is admitted — right method, different stated assumption.

MCQ 11.4-B [[11.4.2 · Analysis](#)] A sponsor's register P80 is 4,003,649 and its lender's re-cut mean is 4,462,500. The correct inference is:

- A. the lender is applying a higher confidence level than the sponsor
- B. the parties are working from different input sets, not different percentiles — the lender's expected case already exceeds the sponsor's 80th ✓ CORRECT
- C. the sponsor's arithmetic is wrong
- D. the difference is immaterial at 458,851

Rationale: The lender re-cuts probabilities, impacts and correlation; the disagreement is evidential and must be negotiated item by item (11.4.2). A misdiagnoses the disagreement as a percentile choice; D ignores that 458,851 exceeds the whole annual covenant headroom of 372,437.72.

MCQ 11.4-C [[11.4.4 · Application](#)] Annual covenant headroom is 372,437.72 and $AF(0.06, 12)$ is 8.383844. The present-value operating-risk exposure the structure can absorb before its covenant fails is:

- A. USD 372,438
- B. USD 3,122,460 ✓ CORRECT

- C. USD 4,003,649
- D. USD 44,423

Rationale: $\text{Headroom} \times \text{AF}(0.06, 12) = 3,122,460$ — the present value of losing that much cash every year of the loan life. A is the annual figure, not its present value; C is the register's own P80, which is the exposure being tested against the ceiling, not the ceiling; D divides (44,423) rather than multiplies by the annuity factor.

MCQ 11.4-D [11.4.3 · Analysis] Which property makes AI model risk different in kind from membrane degradation risk?

- A. its impact is always larger
- B. its probability is a function of governance — validation, monitoring, approval and rollback — so the project can genuinely change it ☒ **CORRECT**
- C. it can be transferred to the software vendor in full
- D. it is uninsurable

Rationale: 11.4.3: p is set by the control set rather than by nature, which by 11.1.2's logic makes the project the right holder and controls worth more than transfer. A is unsupported; C is false — vendor liability caps are small relative to the exposure; D overstates a market position.

MCQ 11.4-E [11.4.2 · Evaluation] A sponsor prepares "the bank case" by multiplying its own register probabilities by 1.5 and its impacts by 1.4 and admitting a 0.30 correlation, reproducing the order of magnitude the lender's advisers apply. The soundest professional position is:

- A. the case is adequate, since it reproduces the multipliers the lender's advisers use
- B. adopt the lender's P80 of 8,884,036 as the sponsor's base case, to remove the argument
- C. present only the sponsor's own mean, since the lender will produce its own case regardless
- D. multipliers illustrate direction and order of magnitude only: the re-cut must be item-specific and evidenced, because the disagreement is evidential and will be settled line by line — this probability on this ground investigation, this impact on this remediation quotation

☒ **CORRECT**

Rationale: A bank case produced by multiplication is the intellectually empty version of the exercise: it concedes the arithmetic without contesting a single input, and multipliers illustrate while evidence decides (11.4.2). A mistakes agreement on a multiplier for agreement on evidence. C arrives at a credit committee unable to reproduce the calculation that will set the debt quantum — the lender's re-cut removes 4,801,313 of capacity. B over-concedes: adopting a tail as a central case mis-sizes contingency, reserves and distributions, when the gap between the two cases is a financeable quantity to be closed by a reserve, a sponsor commitment or less debt.

MCQ 11.4-F [11.4.4 · Evaluation] Kestrel's operating register has a mean of **2,125,000** and a P80 of **4,003,649** on an independence assumption, against a covenant-preserving exposure ceiling of **3,122,460**. The team proposes to provision the mean, on the ground that it is the expected case. The soundest position is:

- A. agree: the mean is the unbiased estimate, and the P80 is a construction-side convention that does not belong in an operating provision
- B. the **881,189** gap between the register's own P80 and the ceiling is the size of the problem, and it is closed by one of the four coverage levers or by equity — with the correlation assumption stated on the face of the output, since admitting $\rho = 0.30$ raises the P80 by a further **837,478**

☒ **CORRECT**

- C. adopt the lender's P80 of 8,884,036 and resize the facility to 37,198,687

- D. the two figures are not comparable, since the register is a present value and the ceiling an annual headroom figure

Rationale: Both quantities are present values — the ceiling is $\text{headroom} \times \text{AF}(0.06, 12)$ precisely so that the comparison can be made — so the gap is a financeable quantity rather than a choice of percentile (11.4.4). A selects the measure that makes the problem disappear, against the project's own contingency policy on the construction side and against a covenant that is a fixed claim rather than an expectation. C is defensible and over-conservative: the lender's re-cut is a negotiating position to be argued item by item on the evidence (11.4.2), and adopting it unexamined surrenders 4,801,313 of debt capacity before the argument has been had. D is simply wrong about the units, and it is the reason the comparison is so often not performed.

MCQ 11.4-G [11.4.3 · Comprehension] A board asks why the operating register carries a **model risk** line at all, given that every forecast in the model is already uncertain and that the cyber line covers the control network. Restated in the terms this KA uses, model risk is:

- A. the risk that a model contains a coding error
- B. the risk of loss from decisions or actions taken on the output of a model — because the model was flawed, because it was used outside the conditions it was validated for, or because its output was misunderstood by whoever acted on it ✓ CORRECT
- C. the risk that a model's forecast differs from the outcome, which is inherent in any forecast
- D. the risk that a model or its training data is compromised by an intruder

Rationale: The definition turns on the decision taken and covers three distinct failures — a wrong model, a sound model used in the wrong envelope, and a correct output misread (11.4.3). A is one cause of the first failure only. C describes forecast uncertainty, which is a property of the future rather than a defect of the model, and treating the two as the same makes the register line unmanageable — part of why p here is a function of governance rather than of nature. D is cybersecurity risk, which this domain treats primarily as an availability exposure on the operational-technology network.

■ SELF-CHECK — KA 11.4

1. State Kestrel's register on four bases. — Sponsor mean 2,125,000; sponsor P80 independent 4,003,649; sponsor P80 at $p = 0.30$ 4,841,128; lender P80 8,884,036.
2. What is the covenant-preserving exposure ceiling and how is it computed? — $3,122,460 = \text{annual headroom } 372,437.72 \times \text{AF}(0.06, 12)$ 8.383844.
3. Why is a lender's mean higher than a sponsor's P80? — Different loss functions produce different input sets: a fixed claim prices the tail, so probabilities, impacts and correlation are all re-cut upwards.

— Advanced topics — Domain 11

11.A.1 Bargaining power, priced

The illegitimate ground for transfer (11.1.2) can be quantified, and doing so is the fastest way to stop an organisation using it. When a party is compelled to accept a risk it neither controls nor can absorb, one of four things happens and each has a cost the transferor eventually pays. It prices the risk **privately**, and the premium is paid unseen — the A4 case, where 1,827,000 sits inside a lump sum against 960,000 of retained expected cost. It **adopts a claims strategy**, converting a priced

allocation into an unpriced dispute costing legal spend, management time and programme. It **withdraws from the bid**, reducing competitive tension — the most expensive outcome and the hardest to attribute. Or it **accepts, fails and hands the risk back** at the conditional default probabilities of 11.3.3, the 371,280 case. Hence one question in every negotiation: if this counterparty cannot influence this outcome, what is it charging us, and where is that charge?

11.A.2 Correlation, and the two places it hides

Correlation enters a risk position twice, and practitioners usually model neither. **Within the register**, admitting $\rho = 0.30$ on Kestrel's operating items raises σ from 2,232,235 to 3,227,338 and the P80 by **837,478** — 20.92 %, and more than twice the annual covenant headroom. **Between the register and the counterparties**, the correlation is between the call on a protection and the condition of the party providing it: the eightfold move from 46,410 to 371,280 in 11.3.3 is this second correlation priced. The two compound in the state of the world that matters, and the structural implication is the one to carry: **a risk position is not the sum of its lines**, and every mitigation that depends on a counterparty is weakest exactly when it is needed. The practical mitigations are diversification of counterparties, credit support that sits above the trading entity, and funded reserves in place of commitments where the correlation is highest — each of which is a real cost, honestly incurred, rather than an assumption quietly avoided.

11.A.3 The reviewer's allocation eye

Invariants to test on any risk allocation and its arithmetic. Every register line names a **mechanism** (clause, guarantee, insurance, reserve), not merely an owner. Every transferred line names the **counterparty, the cap and the credit standing behind it**, and the sum of caps is compared with the sum of transferred exposures. Every transfer has a **priced net value**: transferor **EMV** less loaded premium, with the breakeven loading stated; any transfer of a risk the transferee cannot control or cheaply bear is flagged. The register's mean equals **ΣEMV** , and its correlation assumption is stated on the face of the output. Register and estimate-range provisions are **not added** (Domain 8). Every exposure is expressed in the **covenant's units**: the **CFADS** it consumes, and the basis points, percentage, days or exchange-rate move that consumes the headroom. Time-calibrated terms (waiting periods, deductibles, grace and cure periods) are **tested against headroom in days**. The hedge ratio in force is compared with the ratio covenanted, and the hedge profile amortises with the loan. Interest-rate, currency and input-price tolerances are reported as **non-additive** unless a joint matrix is provided. The **PLCR/tail** is not used to justify retaining an exposure the lenders have no claim on. And the register is reconciled to the **debt quantum**: the covenant-preserving exposure ceiling ($\text{headroom} \times AF(r, n)$) is stated alongside the register's own percentile, because a register that exceeds the ceiling has already re-sized the debt whether or not anyone has said so.

— Industry variations — Domain 11

- **Water and desalination (Kestrel's sector).** Allocation turns on the availability/force-majeure boundary and on input-cost pass-through, because power is the dominant operating cost; ground and marine-interface risks are typically retained by the owner, which commissions the investigations, and E&S risk concentrates on discharge consents.
 - **Contracted power and availability PPPs.** The cleanest allocation set in the market: volume to the payer, availability to the operator, fuel or input price passed through by formula. The residual risks are therefore financial — rate, currency, refinancing — which is why hedging covenants are tightest in this sector.
-

- **Merchant power and commodities.** Market risk cannot be allocated at all, only hedged for a fraction of the tenor. Lenders respond with higher required coverage and stressed price decks rather than with allocation, and the register's price lines dominate its mean.
- **Transport concessions.** Patronage risk is the defining exposure and is genuinely uncontrollable by any party, which is why minimum revenue guarantees, availability structures and traffic-band mechanisms exist; ramp-up correlation makes the independence assumption of 11.4.1 least defensible here.
- **Digital infrastructure.** Technology obsolescence and cybersecurity move from the tail to the centre of the register, tenant credit substitutes for offtaker credit, and power price and availability become the dominant operating exposures; short asset lives compress the tail that would otherwise absorb a late-life register.
- **Mining and heavy industry.** Environmental and social risk carries the largest single impacts — closure, rehabilitation, community and permitting — and is least transferable, so the allocation question becomes one of funded provision, bonding and completion support rather than of contractual ownership.

— Case study — Domain 11: the wrap that could not be afforded (water / desalination)

Situation. Two weeks before Kestrel's EPC award, the preferred bidder offered to convert its partial wrap into a **full wrap**, taking the five items the pricing exercise of 11.1.3 had left with the owner — ground conditions beyond the disclosed baseline, utility diversion and third-party interfaces, membrane price above the contract index, marine weather standby, and permit-driven monitoring works. The price was an additional **USD 4,620,000** on the EPC contract, taking it from 48,000,000 to **52,620,000**. Two of the three sponsors were in favour: the wrap removed 2,840,000 of retained expected cost and, in the words of the meeting, "made the project a single-point-of- responsibility financing".

What happened. The finance director ran the arithmetic of 11.1.3 and then carried it one step further, into coverage. On expectations the transfer destroyed **1,780,000** of value, and it destroyed **460,000** even if the bidder's 40 % loading were negotiated to zero, because the bidder's own expected cost on the bundle (3,300,000) exceeded the owner's (2,840,000) — it had priced a geotechnical baseline it had not set, a utility corridor it did not control and a permit condition it could not influence. The breakeven loading was **-13.94 %**. But the decisive number was the financing consequence. Capital cost rises to **64,620,000**. Held at 70/30 gearing, senior debt becomes **45,234,000**, the annual instalment $45,234,000/8.383844 = 5,395,377.11$, and the year-one **DSCR** falls from 1.2743 to **1.1832** — below the facility's own 1.20× covenant at financial close and only **0.0332** above its 1.15× lock-up threshold. (The figure is generous: it ignores the additional interest during construction the larger facility would accrue.) Funded with equity instead, the project is financeable but equity rises from 18,000,000 to **22,620,000**, gearing moves from 70.0/30.0 to **65.0/35.0 (D/E 1.8568)**, and the same distributable cash stream is spread over **25.67 %** more equity.

How it resolved. The wrap was declined and the partial allocation of 11.1.3 was executed: A1-A3 transferred for **2,128,000** of priced risk premium inside the 48,000,000 price, A4-A8 retained, leaving the **2,690,000** register that Domain 8 provisioned against. Two of the five retained items were then attacked on their own terms rather than by transfer: the owner extended the geotechnical investigation before award (reducing its own A4 probability and, more importantly, narrowing the baseline the bidder had been pricing blind), and the utility diversion scope was fixed by a tripartite

interface agreement with the utility before contract signature — an allocation to the party that actually controlled the corridor, which is 11.1.2's control ground applied to the right counterparty rather than the convenient one.

What the domain teaches here. A wrap is not a good or a bad thing; it is a price, and the price is comparable with a number the project already knows. Kestrel's full wrap cost **1,780,000** of expected value and **0.0911 of DSCR** — more coverage than its entire 372,437.72 of annual headroom represents — and the sponsors who favoured it were not being imprudent, they were reasoning about responsibility rather than about arithmetic. **Single-point responsibility is worth paying for only where the single point can actually influence the outcome.** And the resolution shows the third option that allocation debates routinely omit: where transfer destroys value, the answer is often not to retain the risk passively but to **reduce it at source**, or to allocate it to a party outside the EPC relationship who genuinely controls it.

— Case study B — Domain 11: the currency the model held constant (transport / aviation)

Situation. Larkspur Regional Airport Concession Company (a fictitious concessionaire) financed a terminal expansion with **USD 180,000,000** of senior debt at **6.5 % over 14 years** — $AF(0.065, 14) = 9.013842$, annual instalment **USD 19,969,286.50** — against a 20-year concession. Revenue of **USD 60,000,000** equivalent came entirely from regulated charges denominated in the host currency. Cash operating costs of **24,200,000** split **17,600,000 local** and **6,600,000 USD-linked** (imported spares, systems maintenance and expatriate technical services); cash tax of 4,000,000 was local. Base-case **CFADS** was **31,800,000**, a **DSCR** of **1.5924** against a **1.30× covenant** and a 1.20× lock-up — a structure everyone involved described as comfortable. The financial model held the exchange rate constant across all fourteen years, and the sensitivity pack contained traffic, tariff, opex and interest-rate cases but no currency case.

What happened. In the concession's fourth operating year the host currency depreciated such that the cost of a dollar rose **30 %**. Traffic was on forecast; the airport was operating exactly as planned. **CFADS** in USD fell to **22,938,462** — revenue down to 46,153,846, partly offset by local operating costs falling to 13,538,462 and tax to 3,076,923 — and the **DSCR** fell to **1.1487**, breaching both the covenant and the lock-up while debt service continued to be paid in full. The retrospective arithmetic was unforgiving: the covenant had a breakeven at a devaluation of only **17.94 %**, and payment failure at **44.53 %**. Neither number had ever been computed. The natural hedge everyone had relied on — "our costs are local too" — was worth exactly the 21,600,000 of local costs and tax against 60,000,000 of local revenue, leaving a local numerator of **38,400,000** exposed against 6,600,000 of USD costs and 19,969,286.50 of USD debt service that did not move at all.

How it resolved. The lenders waived the breach for four quarters against a fee, a distribution lock-up that was in any case automatic, and a binding obligation on the concessionaire to seek an exchange-rate indexation amendment from the concession grantor. The amendment obtained indexed **40 %** of regulated charges to the exchange rate. At that share, a 30 % devaluation leaves **CFADS** of **28,476,923** and a **DSCR** of **1.4260**; a 60 % devaluation — the lenders' stress case — leaves **26,400,000** and **1.3220**, still above the covenant; and the covenant breakeven moves from a 17.94 % devaluation to **68.22 %**, a **3.804-fold** improvement in tolerance. The 40 % share was chosen, deliberately, above the **38.04 %** minimum that survives the 60 % stress, so that the structure was not calibrated to the last basis point of its own stress case. The grantor accepted the indexation because the analysis demonstrated the alternative: a concessionaire in default on a strategic asset, at a moment when the state's own capacity to intervene was weakest.

What the domain teaches here. Three things. **A model that holds a variable constant has made a forecast, not an assumption** — and the variable held constant in this financing was the largest single exposure in it. **A natural hedge must be measured, not asserted:** Larkspur's was real but covered only 36 % of its local revenue, and the untouched USD debt service was 33.3 % of base-case revenue. And **the remedy is a number, obtainable before it is needed.** The 40 % indexed share, the 38.04 % minimum, the 17.94 % and 68.22 % breakevens are all computable at close from the closing model in an afternoon; obtained at close they cost a tariff negotiation, and obtained in year four they cost a waiver fee, a locked-up distribution and a year of reporting under breach.

— Executive perspective — Domain 11

What a project finance director cannot delegate in this domain:

- **The price of every allocation.** Not who owns each risk but what the ownership cost: transferor [EMV](#) less loaded premium, with the breakeven loading stated. A transfer nobody has priced is a transfer nobody has evaluated (11.1.3, Case study A).
- **The refusal to use bargaining power as a ground for transfer.** Where a counterparty can neither control nor cheaply bear a risk, the director's job is to say so in the room, because the charge for that transfer is real and will be paid somewhere less visible (11.A.1).
- **The four breakevens.** The reference rate (6.7390 %), the exchange rate ([HC 4.202369](#), +5.06 %), the outage length (21 days) and the input-price rise (68.9699 %) at which the first covenant fails. These are facts about the structure, computable at close, and they belong on one page beside Domain 10's 6,011,562.28 cash trigger.
- **The hedging and indexation policy.** The hedge ratio, its amortisation profile, the pass-through shares and the exchange-rate-indexed share are coverage terms, not treasury detail, and the director owns the decision that trades 0.0210 of ratio for 0.4397 of range.
- **The counterparty concentration after allocation.** Six credit dependencies are six ways to lose the protection the project paid for, and the relevant default probability is the conditional one (11.3.3).
- **The register's correlation and confidence assumptions, stated in the open.** Independence is worth 837,478 of understatement on Kestrel's register, and the covenant-preserving ceiling of 3,122,460 is the number against which any register must be read (11.4.4).

— Calculation exercises — Domain 11

Exercise 11.1 Three risks. X1: owner [p](#) 0.25, impact 4,000,000; transferee [p](#) 0.10, impact 3,000,000. X2: owner [p](#) 0.40, impact 1,500,000; transferee [p](#) 0.40, impact 1,600,000. X3: owner [p](#) 0.30, impact 2,000,000; transferee [p](#) 0.15, impact 1,800,000. Loading 35 %. Compute each net value of transfer, each breakeven loading, and the bundle decision. Solution. X1: own [EMV](#) **1,000,000**, transferee [EMV](#) 300,000, premium 405,000, net **+595,000**, breakeven loading **233.33 %**. X2: own 600,000, transferee 640,000, premium 864,000, net **(264,000)**, breakeven loading **-6.25 %** — no price works. X3: own 600,000, transferee 270,000, premium 364,500, net **+235,500**, breakeven loading **122.22 %**. Transfer X1 and X3 for 769,500 of premium against 1,600,000 of retained expected cost (net **+830,500**); retain X2. Common error: applying the

loading to the transferor's **EMV** rather than the transferee's, which inflates every premium and rejects transfers that create value.

Exercise 11.2 Debt 120,000,000; fixed period principal 6,000,000; **CFADS** 17,500,000; covenant 1.25×. The facility floats at an all-in 5.50 %; a swap fixes the all-in rate at 5.75 %. Compute the **DSCR** at 5.50 % and at a 150 basis point shock, the breakeven all-in rate, and the minimum hedge ratio that survives the shock. Solution. At 5.50 %: interest 6,600,000, debt service 12,600,000, **DSCR 1.3889**. At 7.00 %: interest 8,400,000, debt service 14,400,000, **DSCR 1.2153** — breach. Breakeven: maximum debt service $17,500,000/1.25 = 14,000,000$; maximum interest 8,000,000; $\div 120,000,000 = 6.6667\%$ (+116.7 bp). Minimum hedge ratio $(0.07 - 0.066667)/(0.07 - 0.0575) = 26.6667\%$. Fully swapped: debt service 12,900,000, **DSCR 1.3566**, at a cost of **300,000** a period. Common error: computing the breakeven on total debt service rather than netting the fixed principal first, which understates the tolerable rate and over-buys the hedge.

Exercise 11.3 A project earns 30,000,000 of revenue, 75 % in local currency and 25 % in USD; its operating costs are 11,000,000, 60 % local; debt service is 12,400,000 in USD; the covenant is 1.30×. Compute base **CFADS** and **DSCR**, the position after 20 % and 35 % devaluations, and the covenant breakeven. Solution. Local numerator $30,000,000 \times 0.75 - 11,000,000 \times 0.60 = 15,900,000$; USD numerator $30,000,000 \times 0.25 - 11,000,000 \times 0.40 = 3,100,000$; base **CFADS 19,000,000**, **DSCR 1.5323**. At +20 %: $15,900,000/1.20 + 3,100,000 = 16,350,000$, **DSCR 1.3185** — holds. At +35 %: **14,877,778**, **DSCR 1.1998** — breach. Breakeven: covenant **CFADS** $12,400,000 \times 1.30 = 16,120,000$; devaluation multiple $15,900,000/(16,120,000 - 3,100,000) = 1.2212$, i.e. **+22.12 %**. Common error: applying the devaluation to gross revenue and ignoring that local costs devalue too, which overstates the exposure — here by treating 22,500,000 rather than 15,900,000 as exposed.

Exercise 11.4 Four independent register items: (p 0.20, 2,500,000), (0.10, 4,000,000), (0.30, 1,200,000), (0.15, 2,000,000). Compute the mean, σ and P80; recompute the P80 at $p = 0.30$; and state the covenant-preserving exposure ceiling for a project with 900,000 of annual headroom and $AF(0.06, 10) = 7.360087$. Solution. Mean $500,000 + 400,000 + 360,000 + 300,000 = 1,560,000$. Variance $0.16 \times 2,500,000^2 + 0.09 \times 4,000,000^2 + 0.21 \times 1,200,000^2 + 0.1275 \times 2,000,000^2 = 3,252,400,000,000$; σ **1,803,441**; P80 $1,560,000 + 0.8416 \times 1,803,441 = 3,077,776$. With $p = 0.30$: the item standard deviations are $1,000,000 \cdot 1,200,000 \cdot 549,909 \cdot 714,143$, so $\Sigma\sigma_i = 3,464,052$ and variance $0.7 \times 3,252,400,000,000 + 0.3 \times 3,464,052^2 = 5,876,576,724,325$, giving σ **2,424,165** and P80 **3,600,177** — an uplift of **522,401**. Ceiling $900,000 \times AF(0.06, 10) = 900,000 \times 7.360087 = 6,624,078$, comfortably above the correlated P80. Common error: summing the σ_i rather than the variances for the independent case, which produces 3,464,052 in place of 1,803,441 and nearly doubles the provision.

Exercise 11.5 A project has **CFADS** of 9,600,000, debt service of 7,100,000 and a 1.20× covenant. Its business-interruption cover carries a 45-day waiting period; use a 30/360 basis. Compute annual headroom, the maximum survivable outage, and the **DSCR** after outages of 45, 30 and 15 days. State the maximum tolerable waiting period. Solution. Covenant trigger $7,100,000 \times 1.20 = 8,520,000$; headroom **1,080,000**. Daily **CFADS** $9,600,000/360 = 26,666.67$; maximum survivable outage $1,080,000/26,666.67 = 40.50$ days. At 45 days uninsured: **CFADS** 8,400,000, **DSCR 1.1831** — breach. At 30 days: 8,800,000, **1.2394**. At 15 days: 9,200,000, **1.2958**. Maximum tolerable waiting period **40 days** (40.50 rounded down to a whole day), so the 45-day period leaves a **4.5-day gap** to be closed by a carve-out, a buy-down or a reserve. Common error: computing headroom as **CFADS**

÷ covenant rather than debt service × covenant — the error that turns a 5 % currency tolerance into a 16 % one in MCQ 11.3-C.

— Practitioner's toolkit — Domain 11

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 11.T.1 — Risk allocation price sheet (one row per register line)

Columns: ID · risk statement · phase · **our p and impact, with the evidence reference** · our EMV · proposed transferee · **their p and impact as priced** · their EMV · loading applied · loaded premium · **net value of transfer** · **breakeven premium** · **breakeven loading** · ground for transfer (control / capacity / neither) · mechanism (clause, guarantee, insurance, reserve) · liability cap · credit standing behind the cap · decision and decision owner. Rules: a line with "neither" in the grounds column may not be transferred without a written reason from the decision owner; a negative breakeven loading is a stop, not a negotiation; and the sheet totals must reconcile to the retained register the contingency provision is sized against.

Toolkit 11.T.2 — The breakeven page (one side of paper, per facility)

Every material exposure, expressed in the covenant's own units. Rows: covenant and lock-up **cash triggers** and the annual headroom (Domain 10) · the **reference rate** at which the covenant fails, the hedge ratio in force and the ratio covenanted, and the hedge profile against the amortisation profile · the **exchange rate** at which the covenant fails, the exchange-rate-indexed revenue share in force and the debt-service-matching share · the **input-price rise** at which the covenant fails, per material input, with its pass-through share and reset frequency · the **availability or volume** level at which it fails (Domain 7) · the **outage length in days** at which it fails, beside every insurance waiting period and deductible, every grace period and every cure period · the **counterparty concentration schedule**: exposure, mechanism, cap, credit standing, and the correlation of the call with that standing. A footer states, in bold, which single exposure is nearest its breakeven — and the answer is rarely the one the risk register ranks first.

Toolkit 11.T.3 — Register aggregation and re-cut worksheet

Three panels. **Sponsor case**: items with p, impact, evidence reference, EMV, σ_i ; mean = $\sum EMV$ (hand-checked); variance and σ ; the required percentile; and the **correlation assumption stated on the face of the output** with the uplift it suppresses. **Bank case**: the same items with re-cut p and impact, each change carrying its evidential basis — not a multiplier — plus the correlation assumption; the resulting mean and percentile; and the gap to the sponsor case, item by item. **Coverage translation**: annual equivalent of each measure over the loan life at $AF(r, n)$, the stressed CFADS and DSCR, the **covenant-preserving exposure ceiling** (headroom × $AF(r, n)$), and the debt quantum each measure supports at the covenant ratio. A model register in the operating envelope appears in the item list with an owner, a validation date, a monitored drift metric and a documented manual fallback, or it is recorded as unquantified.

— Exam preparation — Domain 11

What is assessed. The pricing of allocation rather than its description: net value of transfer, breakeven premium, breakeven loading, and the identification of transfers that destroy value

regardless of margin. The translation of every risk into coverage units — basis points, exchange-rate moves, days, input-price percentages — and the level at which a named covenant fails. Hedge-ratio arithmetic, including the minimum ratio surviving a stated shock. Currency-mismatch decomposition and the indexed share that funds foreign outflows. Register aggregation on the PML-AI Domain 8 method, the effect of correlation, why a lender's inputs differ from a sponsor's, and the conversion of a register into a debt-capacity number.

The calculations to do under time pressure. Net value of transfer and breakeven loading for a three-item bundle. Debt service and **DSCR** at a shocked floating rate with fixed principal, and the breakeven all-in rate. Minimum hedge ratio for a stated shock and covenant. **CFADS** and **DSCR** after a devaluation, and the covenant-breakeven exchange rate. Register mean, σ and P80, independent and correlated. Covenant-preserving exposure ceiling. Maximum survivable outage in days against a waiting period. Pass-through tolerance and its $1/(1 - \phi)$ multiplier.

The traps. Computing a covenant trigger as **CFADS** ÷ ratio rather than debt service × ratio, which turns Kestrel's 5.06 % currency tolerance into 15.9 % (MCQ 11.3-C, Exercise 11.5) · applying the loading to the transferor's **EMV** instead of the transferee's (Exercise 11.1) · treating a negative breakeven loading as a pricing negotiation (MCQ 11.1-B) · computing an interest-rate breakeven on total debt service without netting fixed principal first (Exercise 11.2) · confusing the covenant threshold with the payment threshold — 73.9 bp against 327.2 bp (MCQ 11.3-A) · applying a devaluation to gross revenue and ignoring that local costs devalue too (Exercise 11.3) · summing standard deviations instead of variances (Exercise 11.4) · presenting single-variable tolerances as additive when they share one pool of headroom (11.2.2) · adding a register provision to an estimate-range provision (Domain 8, KA 8.3.2) · using an unconditional default probability for transferred risk (11.3.3) · reporting a year-one ratio for a structure with an indexation mismatch (11.2.3) · and quoting a P80 without stating the correlation assumption underneath it (11.4.1).

How the domain connects. Domain 5 identified the bankability conditions each of these risks threatens; Domain 7 built the revenue and credit machinery this domain allocates; Domain 8 supplied the **EMV** and confidence method and provisioned against the residue this domain derives; Domain 10 supplied the coverage units every exposure is expressed in. Forward, Domain 12 documents the allocations priced here — and a clause that does not implement a priced allocation is the defect that domain exists to catch; Domain 13's diligence streams are where the lender's re-cut register is actually produced; Domain 14 monitors the construction risks A1–A8 as they crystallise or expire; and Domain 15 lives with whatever was retained, including the indexation wedge that only appears in the loan's later years.

— Domain 11 summary

Risk allocation is a price, not a preference, and the price is computable. The net value of a transfer is the transferor's expected cost less the transferee's loaded premium, and it is reliably negative where the transferee can neither control the risk nor cheaply bear it: Kestrel's five declined items carried an owner's **EMV** of **2,840,000** against a premium of **4,620,000**, and destroyed **460,000** even at a zero margin because the bidder's own expected cost (**3,300,000**) exceeded the owner's — a breakeven loading of **−13.94 %**, against **+190.79 %** on the three items the bidder genuinely controlled. Those three transferred for **2,128,000** of premium against **4,420,000** of retained expected cost — **2.0771** dollars of expected-cost reduction per dollar of premium — leaving the **2,690,000** register Domain 8 provisions against. Buying the full wrap would have raised capex to **64,620,000** and, at 70/30, pushed the year-one **DSCR** to **1.1832**, below the project's own covenant. Market risk is allocated by formula rather than by clause: a **70 %** power pass-through multiplies Kestrel's tolerance to its largest cost driver by **3.3333×**, from a **20.6910 %** to a **68.9699 %** price rise, while an indexation mismatch

— revenue escalating at an effective **2.00 %** against costs at **4.70 %** — consumes **85.68 %** of the covenant headroom by year twelve and breaches in year thirteen, surviving the loan life by **12.41 basis points** of assumed power escalation. The financial exposures are the most tractable and the most neglected: unhedged, **73.9 basis points** of reference rate stand between Kestrel and a covenant breach against **327.2** to a payment failure, and a swap trades **0.0210** of coverage for **0.4397** of coverage range with **70.0576 %** the minimum hedge ratio that survives a 200 basis point shock; an unindexed host-currency tariff would breach the covenant on a **5.06 %** devaluation and stop payment at **21.61 %**, against a debt-service-matching indexed share of **52.997 %** that lifts tolerance to **37.17 %**; every transferred risk becomes a credit exposure whose relevant default probability is conditional, moving Kestrel's expected credit loss from **46,410** to **371,280**; and a **60-day** insurance waiting period sits against a covenant that survives **21 days** of outage. The operating register — where environmental and social, technology, cybersecurity and AI model risk now sit — has a mean of **2,125,000** and a P80 of **4,003,649**, rising **837,478** once a 0.30 correlation is admitted, against a lender's re-cut **mean** of **4,462,500** that already exceeds the sponsor's P80 and a lender P80 of **8,884,036**. Read through the coverage machinery, Kestrel's covenant survives its register only at the mean: the covenant-preserving ceiling is $372,437.72 \times 8.383844 = 3,122,460$ of present-value exposure, and the lender's P80 removes **4,801,313** of debt capacity. That is the domain's whole argument in one number — a risk register is not a document, it is a debt-capacity input — and it is the argument Domain 12 must now write into contracts.

12

DOMAIN 12

Contracts and Transaction Structure

— Why this domain exists

Domain 11 established that risk allocation is a price and computed what Kestrel's transfers were worth. It stopped one step short of the thing that actually binds anyone: **the document**. An allocation that has been priced but not written is an intention; an allocation that has been written badly is a liability the model does not show. This domain is where the arithmetic of Domains 5 to 11 becomes contractual language, and where the leader discovers whether the protections the financial model assumed are the protections the contracts deliver.

The domain's central claim is that **a contract's commercial value is not its promise but the size, quality and reach of the money standing behind it**. Practitioners read contracts for their obligations — the contractor shall achieve the guaranteed output, the offtaker shall take the water. Lenders read them for their limits: the liquidated-damages rate, the cap on that rate, the aggregate cap above it, the exclusion of consequential loss, the identity and balance sheet of the guarantor, the expiry date of the bond, and what the termination clause pays. Those limits are numbers, they are computable before signature, and they routinely fail to cover the loss they were drafted against. Kestrel's contract stack looks orthodox — delay damages of USD 20,000 per day capped at 10 % of the EPC price, performance damages capped at another 10 %, an aggregate liability cap of 20 % — and yet a 300-day delay combined with a 5 % output shortfall produces exposure of **USD 12,255,674** against nominal cover of **USD 9,600,000** and risk-adjusted cover of **USD 8,160,000**. The uncovered residue of **2,655,674** is 14.75 % of the entire equity cheque, and it was knowable at signature from four numbers on two pages.

The domain works through the stack in the order a transaction is assembled. The construction and operating contracts are where damages, caps and buy-downs are calibrated — or mis-calibrated against a loss that is computable to the day (KA 12.1). The revenue contracts are where the project's cash flow is manufactured, and where the single most under-tested number in project finance lives: the **contracted volume floor**, which for Kestrel must be **95.8892 %** of capacity to hold its own covenant, not the 90 % the commercial team negotiated (KA 12.2). The guarantees, direct agreements and security package convert promises into recoveries, and their worth is the guarantor's credit quality multiplied by the cap, not the cap (KA 12.3). And claims and change are where the allocation is tested in anger, on an arithmetic most organisations never do: on Kestrel's disputed claim, fighting costs a present value of **1,347,115** against a disputed sum of **1,520,000**, so the rational settlement ceiling is **84.68 %** of the claim and the disputed sum would have to exceed **6,901,234** before litigation beat settlement (KA 12.4).

Learning objectives. After this domain a candidate can: read an EPC, O&M, offtake, concession and guarantee package as a set of computable financial limits rather than a set of promises; calibrate a delay liquidated-damages rate against daily carrying cost plus forgone **CFADS**, and identify the day on which the cap binds; compute the uncovered residue of a delay beyond the cap and express it as a share of contract value, equity and project **NPV**; build a cap stack and show where sub-caps exhaust

an aggregate cap; calibrate performance liquidated damages on a value basis and distinguish that figure from the coverage-restoring buy-down and from the bare covenant-restoring prepayment, quantifying the gap between all three; explain why the clause governing the application of damages proceeds can leave equity short even when the amount is right; derive the minimum contracted volume that holds a stated **DSCR** covenant and explain why it exceeds the commercially negotiated floor; test a termination-compensation formula against the debt-outstanding profile and against unreturned equity; compute risk-adjusted cover from instrument face amounts and guarantor credit quality, and the equivalent face amount of a conditional guarantee against an unconditional bond; assess the commercial value of a claim including time impact and the cost of the dispute itself; compute a settlement ceiling, the saving from settling and the disputed sum at which litigation becomes rational; and govern AI use in contract review while never delegating a legal conclusion to it.

The master thread. Kestrel Water SPC continues. Capital cost **USD 60,000,000** funded **70/30** as **USD 42,000,000** of senior debt at **6.0 % over 12 years** — annual instalment **USD 5,009,635.23**, year-one interest **2,520,000**, year-one principal **2,489,635.23**, $AF(0.06, 12) = 8.383844$ (Domain 3) — plus **USD 18,000,000** of equity. Operating life 25 years; documented **CFADS 6,384,000** (6,984,000 before working-capital movements); **EBITDA 7,500,000**, **EBIT 5,100,000**; appraisal at 8 % gives **NPV +16,179,360**, **IRR 12.19 %**, **MIRR 9.73 %**, **PI 1.270**; year-one **DSCR 1.2743 = LLCR**, **PLCR 1.9431**, with a **1.20×** covenant (cash trigger **6,011,562**, headroom **372,438**) and a **1.15×** lock-up (cash trigger **5,761,081**). Its contracts are a fixed-price, date-certain EPC wrap at **48,000,000** (Domains 5, 6 and 8), delay damages of **20,000 per day** capped at **10 %** of that price, and a 25-year water offtake coterminous with the 25-year concession. This domain adds the rest of the stack — the performance-damages regime, the aggregate cap, the security package and the claims machinery — and computes what each is worth.

KNOWLEDGE AREA 12.1

EPC and O&M

Topics: 12.1.1 the construction contract as a set of financial limits · 12.1.2 delay damages, caps and the uncovered residue · 12.1.3 performance damages, buy-down and the three make-good numbers · 12.1.4 O&M contracts and the liability asymmetry.

12.1.1 The construction contract as a set of financial limits

Definition. An **EPC contract** is a single agreement under which one contractor engineers, procures and constructs the whole works for a fixed lump-sum price, by a date certain, to defined performance — the **wrap** whose bankability role Domain 5 (KA 5.4.1) established and whose premium Domain 11 (KA 11.1.3) priced. Its obligations are familiar. Its **financial limits** are what a financier reads, and they are these six numbers:

Limit	What it is	Kestrel
Contract price	The fixed sum, with defined change mechanics	48,000,000
Delay damages rate	Payable per day of delay beyond the date certain	20,000 / day
Delay damages cap	Maximum recoverable for delay, whatever its length	10 % = 4,800,000
Performance damages cap	Maximum recoverable for output or efficiency shortfall	10 % = 4,800,000
Aggregate liability cap	Maximum total contractual liability, all heads	20 % = 9,600,000
Performance security	Instruments callable against the above (KA 12.3)	bond 10 % + parent guarantee

Three properties of that table decide whether the financing works. First, **the rate and the cap are independent decisions**: a well-calibrated rate under a low cap protects only the early days of a delay. Second, **the caps interact**, and the aggregate cap is the real limit — Kestrel's two 10 % sub-caps sum to exactly the 20 % aggregate, so any third head of claim (defect rectification after the sub-caps are exhausted, a third-party indemnity that is not carved out) has no room left in the stack. Third, **the exclusion of consequential or indirect loss** removes from recovery precisely the losses a project company actually suffers — forgone revenue, financing cost, loss of profit — which is why liquidated damages exist at all: they are the agreed, recoverable substitute for a loss the contract has excluded.

Whether a particular damages provision is enforceable as agreed compensation, whether it is vulnerable to challenge as a penalty, how "consequential loss" is construed, and whether an aggregate cap survives particular breaches are all **jurisdiction-specific questions of law and drafting**. This domain computes the commercial arithmetic those provisions are meant to deliver; it does not opine on their effect. Refer each such question to qualified counsel in the governing jurisdiction, and require counsel's confirmation before the model relies on a recovery.

12.1.2 Delay damages, caps and the uncovered residue

Definition. Delay liquidated damages are a pre-agreed sum per unit of time by which the contractor misses the date certain. Their commercial purpose is to reimburse the project company for the cost of lateness, and their correct calibration basis is therefore the **daily economic cost of delay**: the carrying cost of debt already drawn plus the **CFADS** the project would have earned. Domain 5 (KA 5.4.2) computed Kestrel's: **7,000 per day** of interest on the fully drawn 42,000,000 at 6.0 % on a 30/360 basis, plus **17,733.33 per day** of forgone **CFADS**, giving **24,733.33 per day**. A rate of 20,000 recovers **80.86 %** of that; a rate calibrated on forgone revenue alone would recover **71.70 %**, omitting the most certain component of the loss, because interest accrues whether or not the plant would have run well.

What Domain 5 did not do — and what a financier must do before signature — is compute the whole cap stack against a combined stress, because delay and underperformance are correlated (a contractor in schedule trouble commissions in a hurry) and the caps are shared.

WORKED EXAMPLE**Worked example 12.1.2 — Kestrel's cap stack against a 300-day delay and a 5 % shortfall.**

1. **Setup.** The contract stack of 12.1.1. The stress: commissioning is **300 days** late and the plant completes at **95 %** of guaranteed output. Daily economic cost of delay **24,733.33** (Domain 5, KA 5.4.2, 30/360). The value of the output shortfall is computed in 12.1.3 below as **4,835,673.53**. Compute the total exposure, the recovery the caps permit, and the residue.
2. **Formula.** Delay exposure = daily economic cost × days. Delay recovery = min(rate × days, delay cap). Performance recovery = min(value of shortfall, performance cap). Total recovery is further limited by the aggregate cap. Residue = exposure – recovery.
3. **Substitution.** Delay: $24,733.33 \times 300$; recovery $\min(20,000 \times 300, 4,800,000)$. Performance: $\min(4,835,673.53, 4,800,000)$. Aggregate: $\min(4,800,000 + 4,800,000, 9,600,000)$.
4. **Result.**

Head	Exposure	Contractual recovery	Uncovered
Delay, 300 days	7,420,000.00	4,800,000.00 (capped at day 240)	2,620,000.00
Output shortfall, 5 %	4,835,673.53	4,800,000.00 (capped)	35,673.53
Total	12,255,673.53	9,600,000.00 (= the aggregate cap, exactly)	2,655,673.53

The uncovered residue is **5.53 %** of the EPC price, **14.75 %** of the equity contribution and **16.41 %** of Domain 4's entire project NPV of 16,179,360. 5. **Interpretation.** Four things in that table are decision-grade and none of them requires a model. **The cap, not the rate, is where the structure breaks.** Damages of 20,000 per day recover 80.86 % of the daily cost for 240 days and **nothing at all** thereafter; the 300-day case leaves 2,620,000 uncovered and Domain 5's 360-day case leaves 4,104,000. The negotiating priority is therefore not the rate — sponsors habitually spend their leverage there — but the **cap-binding day**, which is the cap divided by the rate and which the sponsor should compare with the credible worst-case delay from the schedule risk analysis. A cap that binds before the P80 delay is a cap that does not cover the risk it was bought for. **The aggregate cap is not an additional protection.** Two 10 % sub-caps summing to a 20 % aggregate means the aggregate binds only when a third head arises, and then it binds at zero: after a full delay and a full performance claim, a defect the contractor refuses to rectify is uncompensated. Structures that intend the aggregate to be meaningful set it above the sum of the sub-caps, or ring-fence specific heads outside it. **The residue is an equity number, and it belongs in the equity case.** 2,655,674 is 14.75 % of the 18,000,000 cheque; a sponsor that has not stated that figure to its investment committee has not described the transaction. **And the contractor's incentive changes at the cap.** Once cumulative damages reach 4,800,000 the contractor's marginal cost of a further day of delay is zero, which converts a financial deterrent into a pure commercial negotiation exactly when the project can least afford one — the reason sophisticated structures pair a cap with a **termination-for-delay right** at a defined long-stop date, so that something other than money still bites.

A cap is a promise; a recovery is a cap multiplied by the credit behind it

Kestrel: 48,000,000 EPC price · delay damages 20,000/day capped at 10 %, binding at day 240 · performance damages capped at 10 %

The two 10 % sub-caps exhaust the 20 % aggregate cap exactly — a third head of claim recovers nothing

One dollar of on-demand bank cover is worth 1.4286 dollars of parent guarantee at a 0.70 assessment:

the face amount equivalent to the 4,800,000 bond is 6,857,143




Fig 12.1.1 — The cap stack against the loss it was drafted for

12.1.3 Performance damages, buy-down and the three make-good numbers

Definition. Performance liquidated damages compensate for a plant that completes but underperforms — output, efficiency, availability or consumption below guarantee. Where the shortfall is permanent they are commonly structured as a **buy-down**: a lump sum, usually applied to prepay debt, calibrated so that the financing survives a smaller plant. The question nobody asks early enough is calibrated to restore what — because there are three defensible answers and they differ by an order of magnitude.

Kestrel's cash flow is linear in output, which makes the arithmetic clean. With revenue of 12,000,000 at full output, cash operating costs of 4,500,000 of which **85 % is fixed** (3,825,000), depreciation 2,400,000, year-one interest 2,520,000, cash tax at 20 % and a working-capital movement of 600,000 (Domain 5, KA 5.4.3 established this cost structure and the **1.510× operating leverage** it produces), **CFADS** as a function of output share x is:

$$CFADS(x) = 9,060,000 \cdot x - 2,676,000$$

so **each percentage point of output is worth 90,600 of annual CFADS**. At $x = 1$ the line reproduces the documented 6,384,000; at 0.97 it reproduces Domain 5's 6,112,200.

WORKED EXAMPLE**Worked example 12.1.3 — what should a 5 % output shortfall be worth?**

- Setup.** Kestrel completes at **95 %** of guaranteed output, permanently. **EBITDA** falls to **6,933,750** and **CFADS** to **5,931,000** — an annual shortfall of **453,000**. Remaining operating life 25 years; the sponsors' appraisal rate is Domain 4's **8 %**; the performance damages cap is **4,800,000**. Compute the value of the shortfall, the damages rate it implies, the shortfall the cap can cover, and the two rival make-good figures.
- Formula.** Value of the shortfall = annual **CFADS** shortfall $\times AF(0.08, 25)$. Damages rate per point = $90,600 \times AF(0.08, 25)$. Coverage-restoring buy-down = debt $\times (\text{CFADS shortfall} \div \text{base CFADS})$, first-order as in Domain 5, KA 5.4.3. Covenant-restoring prepayment: reduce debt until $\text{CFADS}(\text{new}) \div (\text{debt} \div AF(0.06, 12)) = 1.20$.
- Substitution.** $AF(0.08, 25) = 10.674776$; $453,000 \times 10.674776$; $90,600 \times 10.674776$; $42,000,000 \times 453,000/6,384,000$; $5,931,000/1.20 = 4,942,500$, then $\times 8.383844$.
- Result.**

Basis	What it restores	Amount
Bare covenant	DSCR back to the 1.20 covenant, nothing more	562,851.03 (debt to 41,437,148.97)
Sized coverage	DSCR back to the 1.2743 the debt was sized on	2,980,263.16 (debt to 39,019,736.84)
Value	The present value of 25 years of lost CFADS	4,835,673.53

The value basis implies a damages rate of **967,134.71 per percentage point** of shortfall, and the **4,800,000 cap therefore covers a shortfall of 4.9631 %** and not one basis point more. For reference, the covenant itself fails at a shortfall of **4.1108 %** (the point at which 90,600 per point exhausts the 372,438 of headroom): at 5 % the **DSCR** is **1.1839**, breaching the 1.20 covenant by **80,562** of cash. 5. **Interpretation.** The spread between 562,851 and 4,835,674 is **8.591×**, and every party at the table has a favourite end of it. **Lenders are satisfied by the smallest number**, because their interest ends at the covenant — which is why a facility agreement that merely requires "performance damages sufficient to restore the covenant" protects the banks and abandons the equity. **Sponsors need the largest**, because their loss is 25 years of cash, not 12 years of coverage. **The sized-coverage basis, at 2,980,263, is the negotiated middle** and the one most commonly drafted, which means the standard market outcome quietly transfers 1,855,410 of value loss from the contractor to the equity. A sponsor that understands this asks for the value basis and settles for the sized basis knowing what it conceded; a sponsor that does not, discovers the gap in operations.

The application clause matters as much as the amount, and this is the subtler and more expensive point. Suppose the full 4,800,000 is received and, as facility agreements usually require, applied to **mandatory prepayment**. Debt falls to 37,200,000, the instalment falls to **4,437,105.46** — a relief of **572,529.77** per year — and the **DSCR** rises to **1.3367**, better than the position the debt was sized on. Distributions actually rise, from 1,374,365 to **1,493,895**. And yet equity is still worse off: the relief runs for the loan's remaining 12 years and is worth $572,529.77 \times AF(0.08, 12) = 7.536078 \rightarrow$ **4,314,628.99**, while the loss runs for 25 years and is worth 4,835,673.53. The residual gap is **521,044.53**. Paying a 25-year loss with a 12-year debt prepayment under-compensates by construction, however generous the headline. The remedies are to direct part of the proceeds to a distribution account or a maintenance reserve rather than wholly to prepayment, or to size the damages on the value basis in the first place — a drafting choice worth half a million dollars that costs nothing to make at signature and cannot be made afterwards.

The caution: this arithmetic assumes the shortfall is permanent, the cost structure holds and the 8 % rate is the right measure of the sponsors' loss. Where the shortfall can be engineered out, the honest comparison is the rectification cost against the damages; where the offtake pays for availability rather than output, the loss runs through the deduction regime instead (KA 12.2) and this calculation must be rebuilt on that basis.

12.1.4 O&M contracts and the liability asymmetry

Definition. An **operation and maintenance agreement** engages an operator to run the asset to defined standards for a fee, usually with a fixed element, a variable element and a performance regime of bonuses and deductions. Structurally it is the mirror of the EPC contract, and it carries one systematic defect a financier must look for: **the liability asymmetry**.

The asymmetry is arithmetic. An O&M contractor's annual fee on a project like Kestrel might be 1,200,000 — roughly 27 % of the 4,500,000 cash operating cost, the rest being power, chemicals and insurance. Its liability cap is customarily expressed as a share of that fee: one year's fee, or 50 % of it, is common. But the loss an operator can cause is a revenue loss, measured on the same daily basis as a construction delay. A **30-day** unplanned outage costs Kestrel $24,733.33 \times 30 = 742,000$, which already exceeds a cap set at 50 % of the fee (600,000) by **142,000**; a **60-day** outage costs **1,484,000**, leaving **884,000** uncovered against that cap and **284,000** uncovered even against a full-year-fee cap of 1,200,000. The consequence is that **operating risk is only nominally transferred**: the O&M agreement buys competence, mobilisation and a set of key performance indicators, not indemnity. Lenders know this, which is why they price operating risk in the coverage ratio and the maintenance reserve (Domain 10, KA 10.3.1) rather than relying on the O&M contract, and why an availability guarantee from a thinly capitalised operator adds less bankability than sponsors expect.

Three structural responses are worth naming. A **parent guarantee or performance bond** from the operator's group raises the recoverable amount to something comparable with the loss (KA 12.3). A **deduction regime that bites on the fee before the cap** — availability-linked fee at risk — gives the operator a running incentive rather than a terminal liability. And a **step-in and replacement right**, with a pre-qualified substitute operator and a transition plan, is often worth more than any cap: the value at stake is continuity of revenue, and the fastest route to continuity is a new operator, not a claim against the old one. Where the O&M contractor is an affiliate of the sponsor — very common — the conflict must be disclosed and the agreement tested on arm's-length terms, because a lender is being asked to accept a related-party contract as a bankability item (Domain 1, KA 1.3.2).

AI in this KA

Where it earns its place. Extracting the six financial limits of 12.1.1 from a 400-page contract and its schedules, across a portfolio, is exactly the work machines should do: rate, cap, cap-binding day, aggregate cap, exclusions, security instruments and their expiry dates, assembled into a structured table with clause references. So is the consistency check between that table and the financial model — an assistant that reads both and flags "the model recovers 6,000,000 of delay damages; the contract caps them at 4,800,000" has earned its licence fee in one line. And so is generating the stress grid: exposure and residue across a matrix of delay days and output shortfalls, which is 400 arithmetic cells nobody computes by hand.

Where it must not go. It must not conclude whether a damages provision is enforceable, whether a cap survives a particular breach, what "consequential loss" excludes in a given jurisdiction, or whether a set of facts triggers a termination right. Those are legal conclusions, they are jurisdiction-specific, and they belong to qualified counsel; a model's confident answer on any of them is a liability dressed as a summary. Nor should it draft the damages number: the calibration of 12.1.3 rests on a judgment about whose loss is being restored, which is a commercial decision with a named owner.

Verification, concretely. Sample the extracted limits back to the clause on at least five items per contract, including every cap, and record the human verifier and date. Recompute one cap-binding day and one residue by hand. Confirm that the exclusions list in the extraction matches the contract's own list word for word rather than a normalised paraphrase — the normalising is where the error enters. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 12.1

Term	Meaning
EPC wrap	Single-contractor fixed-price, date-certain, turnkey responsibility for the whole works.
Delay liquidated damages	Pre-agreed sum per unit of time of late completion; calibrated on carrying cost plus forgone CFADS .
Cap-binding day	Delay cap ÷ daily damages rate; the day after which further delay is uncompensated.
Cap stack	The interacting set of sub-caps and the aggregate cap; the aggregate is the real limit.
Performance liquidated damages / buy-down	Payment for permanent underperformance, usually applied to prepay debt.
Uncovered residue	Exposure less contractual recovery; an equity number, and a disclosure item.
Liability asymmetry (O&M)	Operator liability capped on fee while the loss it can cause is revenue-scaled.

■ SAMPLE MCQS — KA 12.1

MCQ 12.1-A [\[12.1.2 · Application\]](#) Delay damages are 20,000 per day, capped at 10 % of a 48,000,000 EPC price, against a daily economic cost of delay of 24,733.33. For a 300-day delay the amount borne by the project company is:

- A. USD 1,420,000
- B. USD 2,620,000 ✓ CORRECT
- C. USD 1,484,000
- D. nil — the damages regime covers it

Rationale: Economic cost $24,733.33 \times 300 = 7,420,000$; recovery is capped at 4,800,000 (the cap binds at day 240), so 2,620,000 is uncovered. A applies the 4,733.33 per day uncovered rate to 300 days and ignores that the cap stops recovery entirely after day 240. C is the 60-day interface figure of 12.2.4. D assumes a cap covers any delay.

MCQ 12.1-B [\[12.1.2 · Analysis\]](#) An EPC contract has a 10 % delay-damages sub-cap, a 10 % performance sub-cap and a 20 % aggregate liability cap. The correct reading is:

- A. total recoverable liability is 40 % of the contract price
- B. the aggregate cap adds protection above the sub-caps
- C. the two sub-caps can exhaust the aggregate cap exactly, leaving no room for any third head of claim ✓ CORRECT
- D. the aggregate cap applies only to indemnities

Rationale: $10\% + 10\% = 20\%$, so once both sub-caps are drawn the aggregate is fully consumed and a later defect or indemnity claim recovers nothing (12.1.1, 12.1.2). A double-counts; B is the common misreading the arithmetic disproves; D asserts a carve-out the structure does not contain.

MCQ 12.1-C [12.1.3 · Application] Kestrel's CFADS falls by 453,000 per year for 25 years on a 5 % output shortfall; the appraisal rate is 8 % ($AF(0.08, 25) = 10.674776$); debt is 42,000,000 against base CFADS of 6,384,000 and an instalment of 5,009,635.23. Which figure is the **value-basis** performance damages amount?

- A. USD 562,851 — the prepayment that restores the 1.20 covenant
- B. USD 2,980,263 — the buy-down that restores the sized 1.2743 DSCR
- C. USD 4,835,674 ☒ **CORRECT**
- D. USD 453,000 — one year of lost CFADS

Rationale: $453,000 \times 10.674776 = 4,835,673.53$. A restores only the covenant, B only the sized coverage — both are lender-facing measures, not the sponsors' loss; D omits discounting and the remaining 24 years.

MCQ 12.1-D [12.1.3 · Analysis] A 4,800,000 performance damages receipt is applied wholly to mandatory prepayment, cutting debt to 37,200,000 and the instalment to 4,437,105, and lifting the DSCR to 1.3367. The soundest conclusion is:

- A. equity has been over-compensated, since the DSCR now exceeds the sized 1.2743
- B. equity remains short by about 521,000, because a 25-year loss has been compensated with 12 years of debt-service relief ☒ **CORRECT**
- C. equity is exactly compensated, since the amount equals the cap
- D. the prepayment is irrelevant to equity

Rationale: Relief of $572,529.77 \times AF(0.08, 12) = 7.536078$ is 4,314,629 against a loss of 4,835,674 — a residual gap of 521,045 (12.1.3). A confuses a coverage ratio with value; C confuses the cap with the loss; D ignores that prepayment raises distributions.

MCQ 12.1-E [12.1.2 · Evaluation] Kestrel's delay damages run at 20,000 per day under a 4,800,000 cap. With limited negotiating capital left before signature, the soundest priority is to:

- A. press for a higher daily rate, since a higher rate raises recovery on every day of delay
- B. press for the 20 % aggregate cap to be raised, since the aggregate is the real limit and a higher aggregate extends delay recovery
- C. compare the cap-binding day — $4,800,000 \div 20,000$, day 240 — with the credible worst-case delay from the schedule risk analysis, and pair the cap with a termination-for-delay right at a long-stop date, because beyond the cap the contractor's marginal cost of a further day is zero ☒ **CORRECT**
- D. accept the regime, since a 10 % delay cap under a 20 % aggregate is conventional

Rationale: The rate governs recovery only to the cap-binding day, after which further delay is wholly uncompensated — 2,620,000 on a 300-day slip — so a cap that binds before the P80 delay does not cover the risk it was bought for (12.1.2). A spends leverage where sponsors habitually spend it and where it buys least. B is a true point misapplied: the aggregate binds only when a third head of claim arises, and raising it extends the delay sub-cap by not one day. D substitutes market convention for the project's own schedule evidence, which is the only thing that can calibrate a cap.

MCQ 12.1-F [12.1.4 · Comprehension] The "liability asymmetry" in an O&M agreement means that:

- A. the operator's bonuses exceed the deductions it can suffer

- B. the cap binds the project company but not the operator
- C. the operator's liability outlasts its appointment
- D. the operator's liability cap is scaled to its fee while the loss its failure causes is scaled to the project's revenue, so the two are measured on different bases and the cap is smaller than the loss by construction ✓ CORRECT

Rationale: A cap expressed as one year's fee, or half of it, stands against an outage cost measured on the same daily basis as a construction delay, so a 30-day outage already exceeds a half-fee cap (12.1.4). That is why lenders price operating risk in the coverage ratio and the maintenance reserve rather than relying on the O&M contract. A describes an incentive regime, not a cap. C describes a survival period. B misstates whom the cap protects.

MCQ 12.1-G [12.1.3 · Evaluation] Kestrel's negotiator proposes to accept performance damages on the sized-coverage basis, **2,980,263**, describing it as the market standard. The value of the sponsors' loss on a permanent 5 % output shortfall is **4,835,674**; the bare covenant-restoring figure is **562,851**; the performance sub-cap is 4,800,000. The recommendation to the investment committee should be:

- A. ask for the value basis and, if the sized basis is conceded, direct part of the proceeds away from mandatory prepayment — because the sized basis gives up **1,855,410** of value loss, and even the full 4,800,000 applied wholly to prepayment under-compensates equity by **521,045** ✓ CORRECT
- B. accept 2,980,263: it restores the 1.2743 the debt was sized on, which is the standard the financing was built to
- C. accept 562,851: the covenant is the only contractual test, so anything above it is a windfall
- D. insist on 4,835,674, which the sub-cap makes deliverable

Rationale: The three bases restore three different things, and only the value basis restores the sponsors' loss, so the ask and the fallback should each be stated with what it concedes (12.1.3). B is the defensible weaker course — it is the common drafting and the coverage argument supports it — and it transfers 1,855,410 of value loss to equity without saying so. C adopts the lenders' interest as the equity case, an understatement of $8.591\times$. D overstates what is available: 4,835,674 exceeds the 4,800,000 sub-cap, so the value basis requires the cap to move as well as the calibration, and asking for the number without the cap is asking for 4,800,000. The application point in A is the one that costs nothing at signature and cannot be made afterwards: a 25-year loss compensated with 12 years of debt-service relief is short by construction, however generous the headline.

■ SELF-CHECK — KA 12.1

1. Which negotiating variable matters more, the damages rate or the cap, and why? — The cap: the rate governs recovery only up to the cap-binding day (day 240 for Kestrel), after which further delay is wholly uncompensated.
2. Name the three make-good bases for a permanent output shortfall and Kestrel's figures. — Bare covenant 562,851; sized coverage 2,980,263; value 4,835,674 — a spread of $8.591\times$.
3. Why does an O&M liability cap rarely transfer operating risk? — It is scaled to the fee while the loss it can cause is scaled to revenue; the practical protections are guarantees, fee at risk and a step-in replacement right.

KNOWLEDGE AREA 12.2
Offtake, concession, supply and interface agreements

Topics: 12.2.1 the four load-bearing terms of a revenue contract · 12.2.2 the contracted volume floor is a financing parameter · 12.2.3 concession termination compensation · 12.2.4 supply, interface and the hole between packages.

12.2.1 The four load-bearing terms of a revenue contract

Definition. The **offtake agreement** (a power purchase agreement, water purchase agreement, capacity or availability agreement, or a concession's tariff regime) is the contract that manufactures the project's cash flow. Domain 7 built its economics; this domain reads it as a document, and four of its terms carry the entire financing:

The volume or availability commitment. Whether the offtaker must pay for output it does not take (**take-or-pay**) or only for output delivered (**take-and-pay**), and at what level. This is the term of 12.2.2, and it is systematically under-tested.

The price and its indexation. The tariff, its escalation formula and the pass-through of input costs. Domain 11 (KA 11.2.3) demonstrated the cost of an **indexation mismatch** — a revenue index that does not track the cost driver it is meant to fund — and that analysis is not repeated here; the contractual point is that the mismatch is created by the words in the escalation schedule, so the schedule must be read against the operating cost build-up line by line, not accepted as "CPI-linked".

The deduction and abatement regime. What reduces payment: unavailability, quality failures, delivery-point failures, metering disputes. A deduction regime is a liability cap in reverse — uncapped, running annually, and biting on revenue before any of the project's own protections engage. The single most useful test is to compute the **maximum annual deduction** the regime permits and compare it with the covenant headroom: for Kestrel, a deduction exceeding 372,438 in any year breaches the 1.20 covenant regardless of how well the plant ran in every other respect.

Termination and compensation. What is paid, by whom, on whose default (12.2.3). For a lender this is the most important clause in the document, because it is the only one that speaks to the recovery of principal.

12.2.2 The contracted volume floor is a financing parameter

The claim. Commercial teams negotiate the take-or-pay level as a commercial matter — how much volume will the offtaker commit to, how much flexibility does it need. It is not a commercial matter. **The minimum contracted volume is determined by the covenant**, and it is computable from the cash-flow line and the debt service before anyone sits down.

WORKED EXAMPLE**Worked example 12.2.2 — what floor does Kestrel's covenant actually require?**

- Setup.** $CFADS(x) = 9,060,000x - 2,676,000$ from 12.1.3, where x is the share of guaranteed output taken and paid for. Debt service **5,009,635.23**; covenant **1.20x**; lock-up **1.15x**. The commercial team has agreed a take-or-pay floor of **90 %** of capacity. Find the **DSCR** at that floor, the floor the covenant requires, the floor the lock-up requires, and the floors at which coverage and cash reach unity and zero.
- Formula.** $DSCR(x) = CFADS(x) \div \text{debt service}$. Inverting for a target ratio k : $x = (k \times 5,009,635.23 + 2,676,000) \div 9,060,000$.
- Substitution.** At $x = 0.90$: $(8,154,000 - 2,676,000)/5,009,635.23$. For $k = 1.20$: $(6,011,562.28 + 2,676,000)/9,060,000$. Similarly for 1.15, 1.00 and $CFADS = 0$.
- Result.**

Contracted floor	CFADS	DSCR	Status
100.0000 %	6,384,000	1.2743	The sized case
95.8892 %	6,011,562	1.2000	Covenant exactly met
95.0000 %	5,931,000	1.1839	Covenant breached
93.1245 %	5,761,080	1.1500	Lock-up trigger
90.0000 %	5,478,000	1.0935	Breach and lock-up; debt still paid
84.8304 %	5,009,635	1.0000	Cash exactly equals debt service
29.5364 %	0	—	CFADS exhausted

5. Interpretation. The negotiated 90 % floor does not support the project's own covenant,

and the gap is not marginal: 90 % delivers 1.0935 against a 1.20 requirement, a breach and an

automatic distribution lock-up from the first test date, on a plant performing exactly to

specification and an offtaker performing exactly to contract. The floor the financing needs is

95.8892 % — which, expressed the way it must be expressed to a commercial negotiator, means

the offtaker's flexibility is worth **4.11 percentage points of capacity, not ten.**

The reason the intuition fails is **operating leverage compounded by fixed debt service**. Because 85 % of cash operating cost is fixed, a 10 % volume reduction cuts **CFADS** by 14.19 % (906,000 on 6,384,000), and because debt service does not move at all, the whole reduction lands on the ratio. The general form is worth carrying: **DSCR** is linear in contracted volume with a slope of $90,600 \div 5,009,635.23 = 0.0181$ of ratio per percentage point, so **each point of contracted volume conceded costs 0.0181 of coverage** — and the 372,438 of headroom buys 4.11 points and no more.

Three professional consequences. **The floor is a financing deliverable, not a commercial preference**, and it should be issued to the commercial team as a constraint with its derivation attached, before negotiation, in the same way a lender issues a target DSCR. **A lower floor has a price, and the price is computable**: if the offtaker will only commit to 90 %, the project needs either more equity (reducing debt service until 90 % clears 1.20 — debt of $5,478,000/1.20 \times 8.383844 = 38,272,248$, so 3,727,752 of additional equity), or a compensating floor price, or a volume-shortfall payment that is economically take-or-pay under another name. **And the two thresholds must both be mapped onto volume**: the covenant fails at 95.8892 % and the lock-up engages 2.76 points of volume lower, at 93.1245 %, so between those two floors the project is in breach — with all the consequences of Domain 10, KA 10.4 — while distributions are not yet automatically trapped. A sponsor who models only the lock-up will therefore believe it has more contractual room than it has, which is the mirror image of the error Domain 10's Case study B punished.

The caution: this arithmetic is year-one, on a level CFADS assumption, and it takes the cost structure as fixed. A ramping or seasonal offtake requires the same test **period by period** against the sculpted debt-service profile (Domain 10, KA 10.1.3), and the binding period — almost always the first full year or the year of a major maintenance outage — is the one the floor must clear.

The contracted volume floor is a financing parameter, not a commercial preference

CFADS(x) = 9,060,000x – 2,676,000 against fixed debt service of 5,009,635.23 — each point of volume is worth 0.0181 of coverage

85 % of cash operating cost is fixed, so a 10 % volume cut removes 14.19 % of CFADS and debt service does not move at all




Fig 12.2.1 — The contracted volume floor a covenant requires

12.2.3 Concession termination compensation

Definition. A **concession agreement** grants the project company the right to build, operate and charge for an asset for a defined term, subject to obligations and reversion. Its **compensation-on-termination** provisions state what the grantor pays if the arrangement ends early, and they are conventionally graded by cause: grantor default or voluntary termination (most generous, typically debt plus equity plus a return); force majeure or extended unavailability of the asset (intermediate, often debt-focused); and project-company default (least generous, sometimes a market-value or debt-haircut formula).

The financier's test is arithmetic and takes ten minutes. **Compare the compensation formula, at each year of the term, with the debt outstanding on that date.** Kestrel's 12-year amortisation gives:

End of year	Interest	Principal	Debt outstanding
1	2,520,000.00	2,489,635.23	39,510,364.77
3	2,212,281.09	2,797,354.14	34,073,997.28
5	1,866,528.11	3,143,107.12	27,965,694.77
8	1,266,144.36	3,743,490.87	17,358,915.21
12	283,564.26	4,726,070.97	0

Two consequences follow. First, **a formula that pays a percentage of debt outstanding fails worst early**: an 85 %-of-debt formula on project-company default leaves a gap of **5,926,555** at the end of year 1 and **4,194,854** at the end of year 5 — and the early years are precisely when default risk is highest, so the haircut bites exactly when it is most likely to be needed. Lenders respond by requiring compensation at least equal to senior debt outstanding plus breakage in the grantor-default and force-majeure cases, and by treating the project-company default case as a real exposure to be sized rather than a theoretical one.

Second, **a formula that covers debt in full makes the lenders whole and leaves equity at zero**, and this is the single most important number in a concession for an equity investor. If Kestrel's concession terminated for force majeure at the end of year 5 on a debt-outstanding formula, the lenders recover 27,965,695 and the sponsors recover nothing against 18,000,000 contributed less the **6,871,824** of nominal distributions received in five years (1,374,365 per year) — an unreturned **11,128,176**. That figure, not the elegance of the clause, is what an investment committee needs, and it is why sponsors negotiate hardest on the definition of equity base, whether a return is payable on it, and the treatment of subordinated debt.

Whether a compensation formula is enforceable as drafted, how it interacts with statutory compensation or public-procurement rules, whether the grantor's payment obligation ranks ahead of other public liabilities, and what happens on the grantor's own insolvency are **matters of local law and public policy that vary fundamentally between jurisdictions**. They must be confirmed by qualified local counsel before the model treats a termination sum as a recovery.

12.2.4 Supply, interface and the hole between packages

Definition. Supply agreements secure inputs — fuel, feedstock, chemicals, grid connection, raw water — on terms whose volume, price, indexation and interruption provisions mirror the offtake in reverse. **Interface agreements** allocate responsibility where two or more contractors, utilities or authorities must physically or programmatically connect. The financier's interest in both is the same: **an input failure or an interface failure produces a revenue loss that the offtake's deduction regime charges to the project company, and the question is who reimburses it.**

Where the works are delivered under a single EPC wrap, interface risk sits inside the wrap; where they are split, it sits nowhere. That is not rhetoric but arithmetic. Had Kestrel's 48,000,000 been split into an 8,000,000 marine intake package and a 40,000,000 process plant package, a 60-day delay caused by the intake being handed over late to a specification the process contractor disputed would cost the project company $24,733.33 \times 60 = 1,484,000$ — **3.092 %** of the combined contract price — with **no recovery against either contractor**, because each would demonstrate that it performed its

own scope and each would claim an extension of time and prolongation cost for the other's delay. The wrap premium Domain 11 (KA 11.1.3) priced is, in part, the price of not owning that hole.

Splitting packages is nevertheless often right — it can be cheaper, it can be the only route to a specialist scope, and Domain 11 established that buying a transfer is not automatically value creating. What is never right is splitting them **without an interface regime**. The minimum package: a single **interface matrix** identifying every physical, programme, data and documentation handover with a named owner and a date; **back-to-back completion obligations** so that one contractor's milestone is defined by the other's readiness; **cross-liability or knock-for-knock provisions** stating who pays whom when a handover slips; an **interface manager** with authority inside the project company; and **a single float owner**, because unallocated float is the commonest cause of concurrent claims (Domain 8, KA 8.4). Case study B below prices exactly this omission on a digital-infrastructure project at **5,302,717**.

AI in this KA

Where it earns its place. Reading a long tariff and deduction schedule and reconstructing the payment formula as an auditable calculation is high-value machine work, and so is the reverse check: does the model's revenue line reproduce the contract's formula on a sample of historical or test-case months? Extracting every termination and compensation provision from a concession and tabulating it by cause, with the payment basis and the clause reference, turns a week of associate time into an afternoon of review. And the volume-floor computation of 12.2.2 should be automated across every revenue contract in a portfolio, because it is mechanical and nobody does it.

Where it must not go. It must not decide whether a deduction is contractually due in a disputed month, whether a force-majeure definition captures a particular event, or whether a termination notice is valid. Those are contract-interpretation questions with legal consequences and named counsel. Nor should it be trusted to normalise a bespoke tariff formula into a standard shape: the variations between formulae are where the money is, and a tidy summary is precisely the wrong output.

Verification, concretely. Re-derive the payment for two contract months by hand from the clause and compare with the extraction. Confirm that the extracted deduction regime's worst annual case has been computed and compared with covenant headroom. Sample every termination row back to its clause, and record counsel's confirmation that the compensation basis is enforceable as modelled before the recovery appears in a lender case.

■ KEY TERMS — KA 12.2

Term	Meaning
Take-or-pay / take-and-pay	Offtaker pays for contracted volume whether taken, or only for volume delivered.
Contracted volume floor	The minimum committed volume; a financing parameter set by the covenant, not a commercial preference.
Deduction / abatement regime	Contractual reductions in payment for unavailability or quality failure; an uncapped, annually recurring exposure.
Compensation on termination	What the grantor or offtaker pays on early termination, graded by cause.
Interface agreement	Allocation of responsibility at handovers between separately contracted packages.
Interface hole	Loss caused by a handover failure that neither contractor is liable for.

■ SAMPLE MCQS — KA 12.2

MCQ 12.2-A [12.2.2 · Application] $CFADS(x) = 9,060,000x - 2,676,000$; debt service is 5,009,635.23; the covenant is $1.20\times$. The minimum contracted volume that holds the covenant is:

- A. 90.0000 %
- B. 84.8304 %
- C. 95.8892 % ☒ **CORRECT**
- D. 100.0000 %

Rationale: $(1.20 \times 5,009,635.23 + 2,676,000)/9,060,000 = 0.958892$. A is the commercially negotiated floor, which delivers only 1.0935; B is the volume at which $DSCR = 1.00$, i.e. cash merely equals debt service; D is the sized case, which the covenant does not require.

MCQ 12.2-B [12.2.2 · Analysis] Why does a 10 % reduction in contracted volume cut $DSCR$ by far more than 10 %?

- A. because the covenant is tested on revenue, not $CFADS$
- B. because 85 % of cash operating cost is fixed, so $CFADS$ falls 14.19 %, and debt service does not fall at all ☒ **CORRECT**
- C. because interest rates rise with lower volume
- D. because the tariff falls with volume

Rationale: Operating leverage compounded by a fixed denominator: 906,000 of $CFADS$ lost on 6,384,000 is 14.19 %, and all of it lands on the ratio (12.2.2, and the $1.510\times$ leverage of Domain 5, KA 5.4.3). A misstates the test basis; C and D invent mechanisms.

MCQ 12.2-C [12.2.3 · Analysis] A concession pays 85 % of senior debt outstanding on project-company default. Kestrel's debt outstanding is 39,510,365 at the end of year 1 and 27,965,695 at the end of year 5. The most important observation is:

- A. the formula is adequate, since 85 % is a high recovery
- B. the shortfall is largest early — 5,926,555 at the end of year 1 — precisely when default risk is highest ☒ **CORRECT**
- C. the shortfall is largest late, as the debt amortises
- D. the formula protects equity but not lenders

Rationale: 15 % of a declining balance is largest at the start (12.2.3). C inverts the profile; D reverses the ranking — a debt-based formula protects lenders first and leaves equity at zero.

MCQ 12.2-D [12.2.4 · Application] Two packages are let without an interface regime; a 60-day handover dispute delays completion. The daily economic cost of delay is 24,733.33. The project company's most likely position is:

- A. it recovers 1,484,000 from the contractor whose scope was late
- B. it bears 1,484,000, recovers nothing, and faces prolongation claims from both contractors ☒ **CORRECT**
- C. it recovers from its insurers under a delay-in-start-up policy in all cases
- D. it suffers no loss, because the offtake date moves with the works

Rationale: Each contractor shows performance of its own scope and claims for the other's delay (12.2.4). A assumes an allocation the documents do not make; C assumes cover that depends entirely on policy wording and a triggering insured peril; D assumes an offtake flexibility that date-certain revenue contracts do not grant.

MCQ 12.2-E [12.2.2 · Evaluation] The commercial team has agreed a take-or-pay floor of 90 % of capacity — a DSCR of 1.0935 against a 1.20× covenant that requires 95.8892 % — and asks the finance lead to sign it off so the bid can go in. The soundest professional response is:

- A. sign it off: 90 % is a strong commercial outcome and a covenant can be reset at close
- B. decline the transaction, since any floor below 100 % is unbankable
- C. decline to treat the floor as a commercial term, restate it as a financing constraint with its derivation attached, and price the alternatives — 3,727,752 of additional equity, a compensating floor price, or a volume-shortfall payment that is take-or-pay under another name ☒ **CORRECT**
- D. sign it off and rely on the 1.15× lock-up trigger, which sits at 93.1245 % of capacity

Rationale: The floor is a financing deliverable computable before anyone sits down: each point of contracted volume is worth 0.0181 of coverage, so 372,438 of headroom buys 4.11 points and not ten (12.2.2). A concedes a breach and an automatic distribution lock-up from the first test date, on a plant performing exactly to specification and an offtaker performing exactly to contract. B is the opposite failure of judgment — the covenant requires 95.8892 %, not the sized case. D is self-defeating as well as misdirected: 90 % sits below the lock-up floor too, and a covenant breach is an event of default whether or not cash is trapped.

MCQ 12.2-F [12.2.1 · Evaluation] A draft water purchase agreement has been reviewed by the commercial team, which reports the tariff, its indexation and the take-or-pay level as agreed and the deduction and abatement schedule as "operational detail for the O&M team". The financier's first intervention should be to:

- A. accept the division of labour: deductions are operational, and the O&M team is closer to the metering and quality regime than the finance function
- B. re-open the indexation schedule instead, since an indexation mismatch is the larger structural risk
- C. require the deduction regime to be capped at the covenant headroom figure, since anything larger is unbankable
- D. compute the maximum annual deduction the regime permits and compare it with covenant headroom — a deduction regime is a liability cap in reverse, uncapped and running annually, and on Kestrel a deduction exceeding **372,438** in any year breaches the 1.20× covenant however well the plant performed in every other respect ☒ **CORRECT**

Rationale: Of the four load-bearing terms of a revenue contract, the deduction regime is the one with no ceiling and the one that bites on revenue before any of the project's own protections engage, so its worst annual case is a financing number and not an operating one (12.2.1). A hands the covenant to a team that is not measured on it. C is the defensible weaker course and the right thing to ask for second: a cap on aggregate annual deductions is a legitimate negotiating position, and it is not achievable at the headroom figure in most markets, so computing the exposure has to come first. B names a genuine and larger risk that Domain 11 (KA 11.2.3) prices — and the indexation schedule is reported as agreed, while the deduction schedule has not been read by anyone with a covenant to protect.

MCQ 12.2-G [12.2.3 · Comprehension] A grantor's adviser describes a compensation-on-termination formula measured on senior debt outstanding as one that "makes everybody whole". The accurate restatement is:

- A. it makes the lenders whole and pays equity nothing — it is a lender-recovery formula, and any return of, or return on, the equity base has to be provided for separately ☒ **CORRECT**
- B. it makes everybody whole, since equity ranks behind the debt and is paid from the same sum

- C. it makes equity whole and leaves the lenders exposed for their breakage costs
- D. it makes nobody whole, because debt outstanding is always less than the amount originally advanced

Rationale: The formula is measured on the debt and stops there: on a force-majeure termination at the end of year five Kestrel's lenders recover 27,965,695 and the sponsors' unreturned **11,128,176** is lost (12.2.3). That is why sponsors negotiate the definition of the equity base, whether a return accrues on it, and the treatment of subordinated debt. B assumes a residual the formula does not create. C reverses the ranking. D confuses amortisation with impairment — the sum tracks what is owed on the date, which is exactly what a lender needs. Whether any such formula is enforceable as drafted, and how it interacts with local public-procurement and insolvency rules, is a matter for qualified local counsel.

■ SELF-CHECK — KA 12.2

1. What sets the minimum take-or-pay level? — The covenant: $x = (k \times \text{debt service} + 2,676,000) \div 9,060,000$; for Kestrel's $1.20\times$ that is 95.8892 %, against a negotiated 90 %.
2. What does one point of contracted volume cost in coverage? — 0.0181 of DSCR ($90,600 \div 5,009,635.23$), so 372,438 of headroom buys 4.11 points.
3. What does a debt-outstanding termination formula give equity? — Nothing: at the end of year 5 the lenders take 27,965,695 and the sponsors' unreturned 11,128,176 is lost.

KNOWLEDGE AREA 12.3

Guarantees, direct agreements and the security package

Topics: 12.3.1 the instrument family · 12.3.2 guarantee sufficiency: cap times credit quality · 12.3.3 direct agreements and step-in · 12.3.4 what the security package is actually worth.

12.3.1 The instrument family

Definition. The **security package** is the set of instruments and rights that convert contractual promises into recoveries. It has two halves that are routinely confused. The **credit-support instruments** stand behind counterparties' obligations to the project company; the **lenders' security** stands behind the project company's obligations to the lenders.

Instrument	Who provides it	What it does	Commercial character
On-demand bond / standby letter of credit	A bank, on the counterparty's account	Pays on a compliant demand, without proof of breach	Bank credit; near-certain payment; costs a fee
Conditional (surety) bond	A surety or insurer	Pays on proof of default and loss	Slower, defensible, cheaper
Parent company guarantee	The counterparty's group parent	Extends the obligation to a bigger balance sheet	Worth the parent's credit, no more sheet
Retention / retention bond	Withheld from payments, or bonded	Funds defect rectification	Self-funding; releases on milestones
Sponsor support: equity commitment, cost overrun undertaking	The sponsors	Funds the SPV's own shortfalls	Domain 5, KA 5.2.3
Lenders' security: share pledge, asset security, assignment of contracts and insurances, accounts control	The SPV and its shareholders	Enables enforcement and step-in	Domain 13 perfects it

The instruments differ along three axes a financier must price separately: **how much** (face amount), **how certain** (the obligor's credit and the conditions on payment) and **how long** (expiry against the exposure it covers). The third is the most frequently missed: a performance bond that expires at provisional completion does not cover the defects-liability period, and a guarantee that expires on a fixed date rather than on discharge of the underlying obligation is a gap in the stack with a date on it.

The legal effectiveness of each instrument — the conditions for a compliant demand, whether a guarantee is primary or secondary, the effect of amendments to the underlying contract on the guarantor's liability, the perfection and priority of security interests, and their treatment in the obligor's insolvency — is **wholly jurisdiction-specific and must be confirmed by qualified counsel**. Nothing in the arithmetic below survives an instrument that cannot be called.

12.3.2 Guarantee sufficiency: cap times credit quality

The principle. A cap is a promise; a **recovery** is a cap multiplied by the probability that the obligor pays it in full when called. The financier's question is therefore never "what is the cap?" but "**what is the risk-adjusted cover, and how does it compare with the exposure?**"

WORKED EXAMPLE**Worked example 12.3.2 — is Kestrel's security package sufficient?**

1. **Setup.** The exposure of 12.1.2: **12,255,673.53** in the combined 300-day, 5 %-shortfall stress. The nominal cover is the **9,600,000** aggregate cap. It is supported by an **on-demand bond of 4,800,000** (10 % of the EPC price) from an investment-grade bank, treated as payable with effective certainty, and a **parent company guarantee** up to the aggregate cap from a group parent whose probability of paying in full when called is assessed at **0.70** — an illustrative assumption standing for a mid-quality unrated corporate obligor, to be replaced in practice by the credit team's own assessment. Compute the risk-adjusted cover, the residue, and the parent-guarantee face amount that would be equivalent to the bond.
2. **Formula.** Risk-adjusted cover = $\Sigma(\text{instrument face} \times \text{probability of payment})$, applying instruments in order of certainty and counting the guarantee only for the increment above the bond. Equivalent face = certain amount $\div$ probability of payment.
3. **Substitution.** $4,800,000 \times 1.00 + (9,600,000 - 4,800,000) \times 0.70$; $12,255,673.53 - 8,160,000$; $4,800,000 \div 0.70$.
4. **Result.**

Layer	Face	Quality	Risk-adjusted
On-demand bond	4,800,000.00	1.00	4,800,000.00
Parent guarantee, incremental	4,800,000.00	0.70	3,360,000.00
Total cover	9,600,000.00		8,160,000.00

The credit haircut is **1,440,000**, or **15.00 %** of the nominal cap. Against the exposure, the uncovered residue rises from **2,655,674** nominal to **4,095,674** risk-adjusted — **22.75 %** of the 18,000,000 equity contribution. The parent guarantee face amount equivalent to the 4,800,000 bond is **6,857,143**, a multiple of **1.4286×**. 5. **Interpretation.** The **1.4286×** **equivalence** is the sentence to carry out of this KA: at a 0.70 assessment, **one dollar of unconditional bank cover is worth 1.4286 dollars of parent guarantee**, so a negotiator offered "a parent guarantee instead of the bond" is being offered a discount unless the face amount rises by at least 42.86 %. That converts an argument about instrument preference into a priced trade, which is the only form in which such arguments get settled honestly. The bond's cost makes the trade concrete: at 1.2 % per annum over a three-year construction period the 4,800,000 bond costs **172,800**, or 3.60 % of its face — which the contractor prices into the contract sum, and which is cheap against 1,440,000 of credit haircut.

Three further disciplines. **Assess the guarantor, not the counterparty.** The contracting entity in a large EPC is frequently a special-purpose or thinly capitalised subsidiary, so the whole credit question is the parent's, and the assessment must be documented, dated and owned by the credit function — not asserted in a bankability memorandum. **Test expiry against exposure**, instrument by instrument: Kestrel's delay exposure runs to the long-stop date, its performance exposure to the completion tests, and its defects exposure to the end of the defects-liability period, and any instrument expiring earlier leaves a dated hole. **And never net cover against exposure without stating both.** The residue of 4,095,674 is the number that belongs in the board paper and in the equity case; the temptation to report "fully covered up to the cap" is the reporting failure this KA exists to prevent.

The caution: probabilities of payment are judgments, they are correlated with the very events that trigger a call (a contractor group in distress is both more likely to fail and less likely to pay), and a

single-point 0.70 conceals that correlation. The professional treatment is a range, a named owner for the assessment, and a structural response — an unconditional instrument — rather than a more confident number.

12.3.3 Direct agreements and step-in

Definition. A **direct agreement** is a tripartite contract among the project company, a key counterparty (the offtaker, grantor, EPC contractor or operator) and the lenders' security agent. Its function is to make the project's contracts survive the project company's own default. Its standard content: the counterparty acknowledges the assignment of the contract as security; it agrees to give the lenders **notice** of any project-company default and a **cure period** longer than the project company's own; and it agrees that the lenders (or a transferee they nominate) may **step in** and assume the contract, curing arrears, rather than have it terminated.

The commercial logic is Domain 10's, in contractual form. Enforcement that destroys the revenue contracts destroys the asset's value, leaving lenders with a plant and no offtake. Step-in converts a liquidation into a substitution: the same asset, the same contracts, a new equity owner. For the sponsors, the same instrument is the mechanism by which they can lose the project without the project failing — which is precisely the discipline it is intended to impose.

Two practical points a leader should test. **Cure periods must be operationally achievable:** a 30-day cure that requires a lenders' committee decision, an intercreditor vote and a funding call is not 30 days of cure, and Domain 10's forward-looking test discipline applies here too — the question is whether the machinery can move at the speed the clause assumes. **And step-in without a willing transferee is a right, not a remedy:** its value depends on there being an operator or sponsor able to take the asset on the terms available, which is a market question to be answered before close, not a legal question to be answered after default.

12.3.4 What the security package is actually worth

The valuation discipline for the whole package follows from 12.3.2 and takes one page:

- **Face amounts**, listed by instrument, with the exposure each is intended to cover.
- **Credit quality** of each obligor, assessed and dated, with the risk-adjusted amount.
- **Conditionality:** on-demand, conditional, or dependent on establishing breach and loss — the practical difference between money in 10 days and money in 2 years.
- **Expiry**, against the exposure period, with every gap dated.
- **Reach:** which entity in the counterparty group is actually bound, and whether the guarantee survives amendment of the underlying contract.
- **Residue:** exposure less risk-adjusted cover, stated in currency and as a share of equity.

The last line is the one that changes decisions. A package described as "10 % bond plus parent guarantee to the cap" sounds complete; the same package described as "8,160,000 of risk-adjusted cover against 12,255,674 of stress exposure, leaving 22.75 % of the equity cheque exposed" invites the questions that improve it — a larger bond, a bank guarantee in place of the parent, an uncapped indemnity for defined heads, or a smaller stress accepted with eyes open.

AI in this KA

Where it earns its place. Instrument registers are structured data trapped in unstructured documents: obligor, face amount, currency, trigger, conditions, expiry, governing law, notice address. Extracting them across a portfolio and reconciling them against the exposures they are supposed to

cover — flagging every instrument that expires before its exposure ends — is machine work with an immediate and measurable payoff. Monitoring is better still: an assistant that watches expiry dates and rating actions against a live register does a job humans do badly.

Where it must not go. It must not assess credit quality as if it were a computation; the 0.70 of 12.3.2 is a judgment with an owner. It must not opine on whether a demand would be compliant, whether a guarantee has been discharged by an amendment, or whether security is perfected — all jurisdiction-specific legal questions for counsel. And it must not be allowed to net cover against exposure in a summary, because that is exactly the reporting failure 12.3.4 warns against.

Verification, concretely. Sample every face amount and expiry date back to the instrument. Require the credit function to sign the quality assessment used in any risk-adjusted number, with a date and a range. Recompute one equivalence figure by hand. And confirm counsel's sign-off that each instrument is callable as modelled before any recovery appears in a lender or equity case.

■ KEY TERMS — KA 12.3

Term	Meaning
On-demand bond	Bank instrument payable on a compliant demand without proof of breach; near-certain, fee-bearing.
Parent company guarantee	Group parent's assumption of a subsidiary's obligation; worth the parent's credit.
Risk-adjusted cover	$\Sigma(\text{face} \times \text{probability of payment})$; the number to compare with exposure.
Equivalent face amount	Certain cover $\div$ probability of payment; $1.4286\times$ at a 0.70 assessment.
Direct agreement	Tripartite notice, cure and step-in rights making contracts survive SPV default.
Step-in	Lenders or their nominee assuming a contract instead of allowing termination.
Instrument expiry gap	The dated hole where an instrument expires before the exposure it covers.

■ SAMPLE MCQS — KA 12.3

MCQ 12.3-A [12.3.2 · Application] Cover comprises a 4,800,000 on-demand bank bond (payment effectively certain) and a parent guarantee taking total nominal cover to 9,600,000, the parent assessed at a 0.70 probability of paying in full. Risk-adjusted cover is:

- A. USD 9,600,000
- B. USD 8,160,000 ✓ CORRECT
- C. USD 6,720,000
- D. USD 3,360,000

Rationale: $4,800,000 + 4,800,000 \times 0.70 = 8,160,000$. A ignores credit quality; C applies 0.70 to the whole 9,600,000, haircutting the bank bond as well; D counts only the guarantee increment.

MCQ 12.3-B [12.3.2 · Analysis] A contractor offers to replace a 4,800,000 on-demand bond with a parent guarantee, the parent assessed at 0.70. The face amount that leaves the project company no worse off is:

- A. USD 4,800,000
- B. USD 3,360,000
- C. USD 6,857,143 ✓ CORRECT

D. any amount, since a guarantee from a large group is stronger than a bond

Rationale: $4,800,000 \div 0.70 = 6,857,142.86$, a 1.4286× multiple (12.3.2). A treats unequal certainty as equal; B applies the haircut in the wrong direction; D confuses balance-sheet size with payment certainty and ignores conditionality and timing.

MCQ 12.3-C [12.3.3 · Recall] The primary commercial purpose of a direct agreement is to:

- A. increase the liability cap of the counterparty
- B. give lenders notice, an extended cure period and the right to step in, so the project's contracts survive the project company's default ✓ CORRECT
- C. transfer the offtake obligation to the lenders
- D. provide additional security over the asset

Rationale: Direct agreements preserve the contract, not the cap (12.3.3). C misstates step-in, which is a right to assume the contract, usually through a nominated transferee; D describes asset security, a separate instrument.

MCQ 12.3-D [12.3.2 · Evaluation] A bankability memorandum states that Kestrel's EPC exposure is "fully covered up to the aggregate cap of 9,600,000". Risk-adjusted cover, on a 0.70 assessment of the parent guarantor, is 8,160,000 against a stress exposure of 12,255,674. The soundest reporting position is:

- A. report exposure and risk-adjusted cover side by side, with the residue stated in currency and as a share of equity — 4,095,674, or 22.75 % of the 18,000,000 cheque — and the 0.70 recorded as a dated range owned by the credit function ✓ CORRECT
- B. the memorandum is right: 9,600,000 is the contractual cover, and a credit assessment is not contractual
- C. report the nominal residue of 2,655,674 only, since a probability of payment is speculative
- D. raise the assumed probability to 0.85 to reflect the size of the parent's balance sheet

Rationale: Netting cover against exposure without stating both is the reporting failure this Knowledge Area exists to prevent, and it is the residue that invites the questions which improve the package — a larger bond, a bank guarantee in place of the parent, an uncapped indemnity for defined heads, or a smaller stress accepted with eyes open (12.3.2, 12.3.4). B treats a promise as a recovery. C discards the credit dimension altogether, when even the single-point 0.70 already understates the problem by concealing that distress and non-payment are correlated. D answers a correlated exposure with a more confident number rather than a structural response: at 0.70 one dollar of unconditional bank cover is worth 1.4286 dollars of parent guarantee, so the remedy is an unconditional instrument or a larger face amount, not a kinder assumption.

MCQ 12.3-E [12.3.2 · Analysis] The contractor offers to replace the 4,800,000 on-demand bank bond with a parent company guarantee of **5,500,000**, pointing out that the face amount is 700,000 higher and that the bond's fee of **172,800** over the construction period is priced into the contract sum in any event. The credit function assesses the parent at a 0.70 probability of paying in full. The response should be:

- A. accept: a larger face amount from a substantial group is better cover than a bank instrument, and the fee saving is real money
- B. accept, provided the guarantee is drafted in on-demand form
- C. reject as offered: at 0.70 the guarantee is worth **3,850,000**, which is **950,000** less than the bond, and the equivalent face is 6,857,143 — accept at that face or keep the bond

✓ CORRECT

D. reject: a parent company guarantee is never acceptable in place of bank cover

Rationale: Cover is face amount multiplied by the probability of payment, so the comparison is 3,850,000 against 4,800,000 and the fee saving is less than a fifth of the 950,000 being given up (12.3.2). B is the defensible weaker answer and the instructive one: demand form addresses **conditionality and timing** — money in ten days rather than two years — and leaves the obligor's **credit** exactly where it was, so a 5,500,000 on-demand parent guarantee is still worth 3,850,000. A confuses balance-sheet size with payment certainty. D states a rule the arithmetic does not support: the guarantee is acceptable at 6,857,143 or above, which is what converts an argument about instrument preference into a priced trade. Whether an instrument is callable as modelled, and the effect of amendments to the underlying contract on a guarantor's liability, are questions for qualified counsel in the governing jurisdiction.

MCQ 12.3-F [12.3.1 · Comprehension] A performance bond and a parent company guarantee of the same face amount differ in the way a financier prices them because:

- A. they differ only in cost, the bond carrying a fee and the guarantee none
- B. a guarantee covers the defects-liability period and a bond does not
- C. a bond is security over the asset while a guarantee is a contractual promise
- D. an instrument is priced on three separate attributes — how much (face amount), how certain (the obligor's credit and the conditions on payment) and how long (expiry against the exposure it covers) — and the two instruments are alike only on the first ✓ CORRECT

Rationale: Face amount, certainty and duration are three independent questions, and the third is the most frequently missed: a bond expiring at provisional completion does not reach the defects-liability period, and a guarantee expiring on a fixed date rather than on discharge of the underlying obligation is a gap in the stack with a date on it (12.3.1). A reduces three attributes to one — and the fee is the price of the certainty, not an extra. C confuses credit support with the lenders' own asset security. B asserts as a rule what is a drafting question in each instrument.

■ SELF-CHECK — KA 12.3

1. State the sufficiency test in one line. — Risk-adjusted cover, $\Sigma(\text{face} \times \text{probability of payment})$, against the stress exposure; Kestrel's is 8,160,000 against 12,255,674.
2. What is a 0.70 guarantee worth against an on-demand bond? — 0.70 of its face, so the equivalent face is $1.4286 \times$ the bond — 6,857,143 for a 4,800,000 bond.
3. Which instrument attribute is most often missed? — Expiry: an instrument that expires before its exposure ends is a dated hole in the stack.

KNOWLEDGE AREA 12.4

Risk allocation, claims and change

Topics: 12.4.1 the allocation matrix as a document map · 12.4.2 change and variation mechanics · 12.4.3 the commercial arithmetic of a claim · 12.4.4 dispute pathways and the cost of the process.

12.4.1 The allocation matrix as a document map

Definition. A **risk allocation matrix** in this domain is not the register Domain 11 priced; it is the map from each priced allocation to **the clause that effects it, the instrument that backs it and**

the amount recoverable under it. One row per risk, four columns beyond the risk name: the party bearing it, the document and clause, the financial limit, and the instrument standing behind that limit. The matrix's value is that it makes two failures visible that no register shows.

The orphan risk — priced as transferred in the register, but no clause transfers it. This is the commonest defect in a transaction that has moved fast, and it is created by exactly the sequence this book describes: a risk workshop allocates, a model prices the allocation, and the drafting does not follow. Domain 11's Kestrel case is instructive in reverse — five items were offered to the contractor and declined, so the register correctly shows them retained; a matrix that showed them transferred, with no clause reference, would be a 2,690,000 error hiding in a spreadsheet.

The doubly covered risk — two documents allocate the same risk to different parties, or the same cap is committed twice. Cross-liability between an EPC contract and an interface agreement is the classic case, and the aggregate-cap arithmetic of 12.1.1 is the other: a matrix that shows delay, performance and defects each backed by "the aggregate cap" has shown the reader that the cap is committed three times over.

The matrix is also the instrument of the **reviewer's discipline** of 12.A.3, and it is the artefact Domain 13's legal diligence stream produces and Domain 14's change control maintains. Adding a row is how a change order enters the financing record.

12.4.2 Change and variation mechanics

Definition. A **variation** (or change order) is an instructed alteration to scope, quality, sequence or timing, with a defined mechanism for valuing it and for adjusting time. A **compensation event** (or relief event, or excusable delay) is an occurrence for which the contract grants the contractor time, money, or both, without breach by either party.

The finance leader's interest is narrow and important: **change mechanics decide who funds the change and whether the funding exists.** Four terms carry that question.

The valuation rule. Whether variations are valued at contract rates, at agreed lump sums, on a cost-plus basis or by a defined dispute route. A cost-plus default is an open cheque against a fixed funding envelope; contract rates are only protective if the schedule of rates is complete.

The time consequence. Whether an extension of time carries prolongation cost, and at what rate. A pre-agreed daily prolongation rate removes the largest single area of claim quantification argument, and it should be negotiated at the same time as the delay damages rate, on the same evidence. Kestrel's regime is asymmetric in a way sponsors should notice: **the contractor's liability for delay is 20,000 per day, and the project company's exposure to prolongation on an owner-caused delay is a separately negotiated number** — on Kestrel's claim (12.4.3) it is 12,500 per day of site overhead before disruption and additional plant are added, which is why it should be pre-agreed on evidence rather than left to be proved after the event.

The funding link. Whether the variation is funded from contingency, from the sponsors' cost overrun undertaking, or from a further drawing — and whether the facility agreement permits it. Domain 14 (KA 14.3) operates this link at drawdown; the contractual point here is that a change mechanism that produces obligations the funding documents cannot fund is a structural defect, not an administrative one.

The threshold and approval architecture. Which changes the project company may agree alone, which require lender consent (usually any change to a material contract, per Domain 10's negative covenants), and which require the oftaker's or grantor's consent. Serial small changes below a consent threshold are how a fixed-price contract stops being fixed, which is why cumulative as well as individual thresholds belong in the drafting.

12.4.3 The commercial arithmetic of a claim

Definition. A **claim** is an assertion of entitlement to time, money or both under the contract. Its commercial value to either party is not the sum claimed. It is the **expected recovery, net of the cost of obtaining it, discounted for the time it takes** — and because disputes are slow and expensive, that arithmetic frequently inverts the negotiating intuition.

WORKED EXAMPLE

Worked example 12.4.3 — Kestrel's contractor claims 90 days and 1,870,000.

1. **Setup.** The contractor claims a **90-day** extension of time and prolongation cost, arising from a late owner-supplied approval that the contract treats as a compensation event. Quantum: site overhead **12,500 per day** for 90 days (**1,125,000**), disruption and lost productivity **480,000**, additional preliminaries and plant **265,000** — **1,870,000** in total. The project company's own assessment, on its expert's analysis, is **55 days** and **1,050,000**. Delay damages are 20,000 per day. If the matter goes to arbitration: each side's legal and expert costs **620,000**, internal management time **180,000**, an award expected in **26 months**, and assessed outcome probabilities of **0.35** that the contractor's full case succeeds, **0.25** of a split at the midpoint and **0.40** that the project company's assessment is upheld. Discount at Domain 4's **8 %**; costs are incurred evenly, so treat them as falling at the **13-month** midpoint. Each party bears its own costs (cost-shifting rules vary by jurisdiction and by arbitral rules — a matter for counsel, and one that changes this arithmetic materially).
2. **Formula.** Time impact = extension days × delay damages rate (the damages the project company forgoes by granting the extension). Disputed sum = quantum gap + time-impact gap. Expected award = $\Sigma(\text{probability} \times \text{outcome})$. Present value of fighting = expected award ÷ $(1.08)^{2.1667}$ + costs ÷ $(1.08)^{1.0833}$. Settlement ceiling = present value of fighting – negotiation cost. Breakeven disputed sum: solve $k \cdot D + \text{PV}(\text{costs}) = 0.5D + \text{negotiation cost}$, where $k = (0.35 + 0.25/2) \div (1.08)^{2.1667}$.
3. **Substitution.** Time impact $90 \times 20,000 = 1,800,000$; owner's economic cost of the 90 days $24,733.33 \times 90 = 2,226,000$. Gaps: $1,870,000 - 1,050,000 = 820,000$ of money and $35 \times 20,000 = 700,000$ of forgone damages, so $D = 1,520,000$. Expected award $0.35 \times 1,520,000 + 0.25 \times 760,000 = 722,000$. Discount factors $(1.08)^{2.1667} = 1.181458$ and $(1.08)^{1.0833} = 1.086949$.
4. **Result.**

Item	Amount
Contractor's quantum claimed	1,870,000.00
Value of the extension of time to the contractor (forgone delay damages)	1,800,000.00
Project company's own economic cost of the 90 days	2,226,000.00
Total exposure of the event to the project company	4,096,000.00
Disputed sum after the owner's assessment	1,520,000.00
Expected award	722,000.00
Present value of the expected award (26 months)	611,109.54
Present value of own costs (13 months)	736,005.26
Present value of fighting	1,347,114.80
Settling at the midpoint (760,000 + 60,000 of negotiation cost)	820,000.00
Saving from settling at the midpoint	527,114.80
Settlement ceiling (indifference point)	1,287,114.80 = 84.68 % of the disputed sum
Disputed sum at which fighting becomes rational	6,901,234.43
5. Interpretation. **The time impact is the bigger prize, and it is usually argued about least.** The contractor's money claim is 1,870,000; the extension of time is worth 1,800,000 to it in delay damages it will not pay, and the two are close to equal. Meanwhile the project company's own economic cost of the 90 days — 2,226,000 — exceeds both. The negotiation is therefore not about 1,870,000; the event is worth 4,096,000 to the project company, and any settlement discussion that treats the extension of time as a procedural concession has given away the largest number on the page.	

Fighting is expensive in a way the win probability conceals. A 0.40 chance of complete victory sounds like a strong position. It is: the expected award is only 722,000 against a disputed 1,520,000. And yet the present value of fighting is **1,347,115**, because own costs of 800,000 are certain and immediate while the award is contingent and 26 months away. The settlement ceiling is therefore **84.68 % of the disputed sum** — meaning the project company should rationally settle at anything up to 1,287,115 of a 1,520,000 dispute, and settling at the midpoint saves **527,115**. Practitioners who "never pay more than their assessment" are choosing to spend 527,115 to defend a principle, which is a legitimate choice only if it is made explicitly and for a stated reason — precedent across a portfolio of similar claims is the usual one, and it should be quantified as such.

The threshold generalises, and it is the number to carry. On these cost and probability assumptions, fighting only beats settling at the midpoint once the disputed sum exceeds **6,901,234** — roughly 4.5 times the disputed sum in front of them, and 14.4 % of the EPC price. That single figure explains the observed behaviour of the market better than any principle: small and medium

claims settle because the process costs more than the gap, and only large ones are litigated. An organisation that computes its own threshold once, from its own cost base and its own historical outcome distribution, converts claims handling from temperament into policy.

The cautions are three and they are not decoration. The probabilities are judgments and should be elicited from the party's own legal advisers as a documented range, not asserted; the arithmetic is only as good as they are. Cost recovery — whether the loser pays some or all of the winner's costs — varies fundamentally by jurisdiction and by the applicable arbitral rules, and it can move this calculation by more than the disputed sum; it is a question for qualified counsel and must be answered before the threshold is relied upon. And the model omits every non-financial consequence: management distraction, the effect on a continuing working relationship, the disclosure obligation to lenders under the information covenants, and the precedent set for the remaining claims on the same project. Those belong beside the number, not inside it.

12.4.4 Dispute pathways and the cost of the process

Definition. Contracts specify an escalating sequence for resolving disagreement — typically engineer's or employer's determination, then senior executive negotiation, then mediation or a dispute board, then arbitration or litigation, with interim binding decisions in some standard forms. Each step has a cost, a duration and a probability of resolving the matter, and 12.4.3's arithmetic applies at every one.

The finance leader's contribution is to **price the pathway before it is used**. Three questions do most of the work. How long is the whole ladder? A pathway whose steps sum to 30 months has built a 30-month funding and covenant problem into every serious disagreement, and Domain 10's information covenants will require disclosure at month one. Is there an interim binding mechanism? A dispute board or interim determination that keeps cash moving while the merits are argued is worth a great deal to a project company whose covenants are tested quarterly; a pathway whose first binding outcome is a final award is not. And who funds the process? Legal and expert cost is an operating outflow the base case does not contain, and on Kestrel's arithmetic 800,000 of it is **2.148 times** the project's entire annual covenant headroom of 372,438 — a dispute budget large enough to breach the covenant on its own.

Two standing cautions. **A claim disclosed late is a covenant problem and a relationship problem at the same time** — Domain 10, KA 10.4.4's honesty asymmetry applies with full force, because a lender who learns of a 4,096,000 exposure from a compliance certificate will price the discovery into every future waiver. **And settlement is a financing event.** A settlement that changes the contract price, the completion date, the performance guarantees or the security package touches the negative covenants and the conditions precedent, so lender consent is usually required and should be sought early, not presented as a *fait accompli*.

The selection of forum, seat, governing law, arbitral rules, enforceability of awards and the availability of interim relief are **jurisdiction-specific matters with material commercial consequences**, and they are decided at drafting. They must be settled by qualified counsel; the financial contribution is to state what each option costs in time and money so that the legal choice is made with the commercial arithmetic in view.

AI in this KA

Where it earns its place. Claims work is document-intensive and that is where machines are strongest: assembling a chronology from correspondence, programmes and site records; identifying which notices were served within contractual time bars and which were not; mapping each claimed head to the clause relied on; and computing the 12.4.3 grid across a range of probability and cost

assumptions so that the sensitivity of the settlement ceiling is visible rather than assumed. Maintaining the allocation matrix of 12.4.1 as changes are executed is another natural fit.

Where it must not go. It must not assess the merits of a claim, opine on whether a time bar has been missed with the consequence the contract states, characterise concurrent delay, or draft a settlement position. Those are legal and expert judgments; a claim consultant's and counsel's work is not a summarisation task. Nor should the probability distribution in 12.4.3 come from a model: it must come from named advisers, on the record, as a range.

Verification, concretely. Test the chronology against the primary documents on a sample of at least ten events, including every alleged notice. Recompute the expected award and one discount factor by hand. Require the probability assumptions to be attributed to a named adviser with a date. And require counsel's confirmation of the cost-shifting and limitation position before the settlement ceiling is used in a negotiation mandate.

■ KEY TERMS — KA 12.4

Term	Meaning
Allocation matrix	Risk → bearing party → clause → financial limit → instrument; reveals orphan and doubly covered risks.
Variation / compensation event	Instructed change; or an occurrence granting time and/or money without breach.
Prolongation cost	Time-related cost of delay, ideally at a pre-agreed daily rate.
Time impact of a claim	Extension days × delay damages rate — the damages forgone by granting time.
Settlement ceiling	Present value of fighting less negotiation cost; the rational maximum to settle at.
Breakeven disputed sum	The dispute size above which litigating beats settling at the midpoint.

■ SAMPLE MCQS — KA 12.4

MCQ 12.4-A [12.4.3 · Application] A contractor claims 90 days and 1,870,000; delay damages are 20,000 per day; the project company's daily economic cost of delay is 24,733.33. The total exposure of the event to the project company is closest to:

- A. USD 1,870,000
- B. USD 3,670,000
- C. USD 4,096,000 ✓ CORRECT
- D. USD 2,226,000

Rationale: Quantum 1,870,000 + own economic cost $24,733.33 \times 90 = 2,226,000$ gives 4,096,000 (12.4.3). A counts only the money claim; B adds the forgone damages of 1,800,000 to the quantum but omits the project company's own cost; D counts only the economic cost.

MCQ 12.4-B [12.4.3 · Analysis] The disputed sum is 1,520,000; the present value of the expected award is 611,110 and of own costs 736,005. The rational settlement ceiling, allowing 60,000 of negotiation cost, is:

- A. USD 760,000 — the midpoint
- B. USD 1,287,115 ✓ CORRECT
- C. USD 611,110
- D. USD 1,520,000 — the full claim

Rationale: Fighting costs a present value of 1,347,115; deducting the 60,000 that settling itself costs gives an indifference point of 1,287,115, or 84.68 % of the disputed sum (12.4.3). A is one possible settlement, not the ceiling; C omits own costs, which are the larger component; D assumes no defence has value.

MCQ 12.4-C [12.4.3 · Analysis] Why does a 0.40 probability of complete victory still leave a settlement ceiling at 84.68 % of the disputed sum?

- A. because the expected award is larger than the disputed sum
- B. because own costs are certain and immediate while the award is contingent and 26 months away ☒ **CORRECT**
- C. because the discount rate is too high
- D. because liquidated damages are excluded from the calculation

Rationale: PV of own costs (736,005) exceeds the PV of the expected award (611,110); certainty and timing dominate probability (12.4.3). A is arithmetically false; C confuses a parameter with the mechanism; D is untrue — the forgone damages are the largest part of the disputed sum.

MCQ 12.4-D [12.4.1 · Analysis] A risk register shows five construction risks as transferred; the allocation matrix shows no clause reference for any of them. The correct conclusion is:

- A. the matrix is incomplete but the allocation stands
- B. these are orphan risks: priced as transferred, retained in fact, and the register overstates protection ☒ **CORRECT**
- C. the risks are doubly covered
- D. the contractor's aggregate cap covers them

Rationale: An allocation without a clause is not an allocation (12.4.1); the register and the model are both wrong until the drafting follows. C is the opposite defect; D assumes a cap can cover a liability the contract never created.

MCQ 12.4-E [12.4.3 · Evaluation] A claims policy states that the organisation "never settles above its own assessment" — 1,050,000 on a disputed sum of 1,520,000, where the present value of fighting is 1,347,115 and the settlement ceiling 84.68 % of the disputed sum. The soundest professional position is:

- A. keep the policy: paying more than the merits justify rewards an inflated claim
- B. keep it only as a stated and quantified choice — it costs 527,115 against a midpoint settlement — and confirm the cost-shifting position with counsel first, because it can move the arithmetic by more than the disputed sum ☒ **CORRECT**
- C. settle at the ceiling of 1,287,115, since the arithmetic identifies the rational price
- D. arbitrate: a 0.40 probability that the project company's own assessment is upheld is a strong position

Rationale: Own costs of 800,000 are certain and immediate while the award is contingent and 26 months away, so the process rather than the merits dominates the answer; holding to the assessment is a legitimate choice — usually for precedent across a portfolio of similar claims — provided its price is computed and stated (12.4.3). A defends a principle without pricing it. C mistakes an indifference point for an opening position: the ceiling is a maximum, and settling at the midpoint saves 527,115. D reads a probability as a position — on these assumptions fighting beats a midpoint settlement only once the disputed sum exceeds 6,901,234.

MCQ 12.4-F [12.4.1 · Comprehension] A risk allocation matrix differs from the priced risk register in that:

- A. it is the same document at a coarser level of aggregation
- B. the register records each risk's probability, impact and owner, while the matrix maps each allocation to the clause that effects it, the financial limit and the instrument standing behind that limit — which is why only the matrix reveals an orphan or a doubly covered risk

✓ **CORRECT**

- C. the register is the legal document and the matrix the commercial one
- D. the matrix replaces the register once the contracts are signed

Rationale: An allocation with no clause is an intention, and one cap committed to three heads of claim is one cap and not three; both defects are invisible in a register whose only allocation column is an owner's name (12.4.1). A misses that the matrix adds columns the register does not have. C reverses the character of both documents. D discards the quantification the register carries and its continuing role in sizing contingency and reserves.

MCQ 12.4-G [12.4.2 · Evaluation] Kestrel's EPC contract fixes the contractor's delay liability at **20,000 per day** and leaves the project company's exposure to prolongation on an owner-caused delay to be proved after the event; on the claim of 12.4.3 it is asserted at **12,500 per day** of site overhead before disruption and additional plant. Variations are valued on a cost-plus basis where the schedule of rates is silent, and changes below a consent threshold need no lender approval. With the change mechanics still open, the priority is to:

- A. pre-agree the daily prolongation rate on the same evidence as the delay damages rate, and add a cumulative consent threshold alongside the individual one — the asymmetry is **7,500 per day** of quantification argument, and serial changes below a threshold are how a fixed-price contract stops being fixed ✓ **CORRECT**
- B. reduce the contractor's daily damages rate to 12,500, so that the regime is symmetrical
- C. remove the cost-plus fallback and require all variations to be valued at contract rates
- D. accept the mechanics: prolongation is proved on actual cost, which is the fairest measure available

Rationale: Change mechanics decide who funds a change and whether the funding exists, and a pre-agreed prolongation rate removes the largest single area of claim-quantification argument — which is why it belongs beside the delay damages rate and on the same evidence (12.4.2). B achieves symmetry by weakening the project's own recovery, which is the wrong direction from a rate that already recovers only 80.86 % of the daily economic cost of delay. C is the defensible weaker course and only protective if the schedule of rates is complete: where it is not, contract rates simply relocate the argument, so the ask is a complete schedule with a defined route for genuinely new work. D mistakes a measurement principle for a mechanism — proving actual cost after the event is precisely the exercise the pre-agreed rate exists to avoid, and it is conducted while the covenant is being tested. Whether a pre-agreed daily rate survives challenge as a penalty, and how a consent threshold interacts with the facility's negative covenants, are governing-law questions for qualified counsel; the commercial task is to price the asymmetry and ask for the term.

■ SELF-CHECK — KA 12.4

1. What is the largest number in a typical extension-of-time negotiation? — Usually the time impact: 90 days at 20,000 is 1,800,000 of forgone damages, against a 1,870,000 money claim and the project company's own 2,226,000 of economic cost.

2. State the settlement ceiling rule. — Settle at up to the present value of fighting less the cost of settling: 1,287,115 on a disputed 1,520,000, saving 527,115 against a midpoint settlement.
3. Why do most claims settle? — Because process cost and delay dominate: on these assumptions a dispute must exceed 6,901,234 before litigating beats settling at the midpoint.

— Advanced topics — Domain 12

12.A.1 What sits outside the cap

An aggregate liability cap is routinely read as the maximum a counterparty can owe. It is not. Contracts customarily carve out defined heads from the cap — abandonment, fraud or wilful misconduct, breach of confidentiality or intellectual property, third-party death and personal injury, environmental indemnities, and sometimes the proceeds of insurance — and the carve-outs are where unbounded exposure lives, in both directions. Two consequences for a finance leader.

On the recovery side, an uncapped indemnity is worth only the obligor's balance sheet, so a carve-out that looks like unlimited protection is limited in practice by exactly the credit arithmetic of 12.3.2 — and unlike the capped heads, it has no instrument sized against it. **On the liability side**, the project company's own uncapped indemnities are the exposures most likely to exceed its equity, and they are the ones sponsors most often fail to model because they sit outside every number in the contract summary. The discipline is to list the carve-outs explicitly in the allocation matrix with the word "uncapped" in the limit column, so that they cannot be read as absent, and to test the largest of them against the insurance programme rather than the cap.

The scope, validity and effect of any carve-out — and whether a cap is displaced entirely by particular conduct — are questions of the governing law and the drafting, and they vary fundamentally between jurisdictions. Qualified counsel must confirm them; the commercial task is to ensure that each one appears in the matrix with an owner and a sizing.

12.A.2 Termination compensation against the amortisation profile

12.2.3 compared a compensation formula with the debt-outstanding profile at points in time. The advanced form is to plot both across the whole term, because the **shape** of the gap is what determines whether the structure is robust. Three shapes recur. A **debt-outstanding formula** tracks the amortisation exactly and produces no gap by construction — the lenders' preferred outcome, and the one that leaves equity at zero (11,128,176 unreturned at the end of year 5 for Kestrel). A **fixed-schedule formula** — a depreciated capital value, or a table agreed at signature — diverges from an annuity amortisation because principal repayment accelerates while straight-line depreciation does not, so the gap opens or closes depending on the tenor relationship. And a **percentage-of-debt formula** produces a gap proportional to the outstanding balance, therefore **largest in the earliest years** — 5,926,555 at the end of Kestrel's year 1 against 4,194,854 at the end of year 5 on an 85 % formula — which is the worst possible profile, because early-life default risk is the highest and the tail of the loan is the part a refinancing would have addressed anyway.

Two refinements matter in a real negotiation. **Hedge breakage** is a real cost that debt-outstanding formulae frequently exclude: a fixed-to-floating swap terminated at an unfavourable point produces a payment that is neither principal nor interest, and if the compensation clause does not name it, the lenders are not whole even under a "full debt" formula. **And the reference date matters**: compensation computed at the termination date, at the date of a valuation, or at the date of payment can differ by a full period's interest and by any accrued default interest, all of which should be

specified rather than left to construction. Both are drafting points with a computable price, and both are for counsel to render enforceable and for the finance leader to size.

12.A.3 The reviewer's contract eye

The invariants to test on any contract stack before a financing relies on it:

- **Every risk shown as transferred has a clause reference**, and every clause reference resolves to language that actually transfers it (no orphan risks — 12.4.1).
- **Delay damages are calibrated on carrying cost plus forgone CFADS**, not revenue alone, and the calibration basis is documented (Kestrel: 24,733.33 per day, not 17,733.33 — 12.1.2).
- **The cap-binding day is computed and compared with the schedule risk analysis' credible worst-case delay** (Kestrel: day 240).
- **Sub-caps are summed against the aggregate cap**, and the aggregate exceeds the sum wherever it is intended to add protection (Kestrel's do not — 12.1.1).
- **Performance damages state which loss they restore** — bare covenant, sized coverage or value — and the model uses the same basis the contract does (562,851 / 2,980,263 / 4,835,674 — 12.1.3).
- **The application of damages proceeds is tested for tenor mismatch**: a multi-decade loss paid by a shorter-dated debt prepayment under-compensates (521,045 — 12.1.3).
- **The contracted volume floor clears the covenant**, computed as $x = (k \times \text{debt service} + \text{intercept}) \div \text{slope}$, in the binding period, not on an annual average (95.8892 % against a negotiated 90 % — 12.2.2).
- **The maximum annual deduction under the revenue contract is computed and compared with covenant headroom** (372,438 for Kestrel — 12.2.1).
- **Termination compensation is plotted against debt outstanding across the term**, and hedge breakage is named in the formula (12.A.2).
- **Every instrument's face amount is multiplied by an owned credit assessment**, and every expiry date is tested against the exposure period it covers (8,160,000 against 9,600,000 nominal — 12.3.2).
- **Uncovered residue is reported in currency and as a share of equity**, never netted silently (2,655,674 nominal, 4,095,674 risk-adjusted, 14.75 % and 22.75 % of equity — 12.1.2, 12.3.2).
- **Carve-outs from the cap are listed as uncapped**, sized, and tested against insurance (12.A.1).
- **Every recovery the model relies on carries counsel's confirmation** that the instrument is callable and the provision enforceable in the governing jurisdiction.

— Industry variations — Domain 12

- **Contracted power and availability PPPs**. The document set is the most standardised, and the binding constraint is usually the **availability and deduction regime** rather than volume: the test of 12.2.1 — maximum annual deduction against covenant headroom — replaces the volume floor of 12.2.2, and performance damages attach to heat rate or capacity rather than output.
- **Transport concessions**. Patronage risk is rarely contracted away, so there is no volume floor to compute; the load-bearing clauses instead are **compensation on termination** (12.2.3, because the grantor's covenant is the credit) and the **change-in-law and competing-infrastructure protections**, whose absence is a revenue risk no cap covers.

- **Water and desalination.** The Kestrel case: take-or-pay water purchase, output and consumption guarantees, and a heavy dependence on a single input contract (power) whose interruption provisions must mirror the offtake's force-majeure relief exactly, or a gap opens between the cost the project incurs and the revenue it may abate.
- **Digital infrastructure.** Multi-package delivery is normal — shell, mechanical and electrical fit-out, network — so **interface architecture is the dominant contractual question** (12.2.4 and Case study B), tenant contracts are shorter than the debt so termination and renewal provisions carry the refinancing case, and service-level agreements rather than output guarantees define performance.
- **Oil, gas and process industries.** Performance guarantees are multi-dimensional (throughput, yield, specification, consumption), so the buy-down arithmetic of 12.1.3 must be run per guarantee and aggregated, and licensor and process-technology agreements add a party whose liability is characteristically capped very low relative to the loss it can cause.
- **Social infrastructure and accommodation PPPs.** Payment is availability-based with detailed performance deductions and a defined **hand-back regime**: condition surveys, a hand-back reserve and rectification obligations at the end of the concession, which is a contractual exposure that falls after the loan has been repaid and is therefore invisible in every coverage ratio.

— Case study — Domain 12: the cap that covered 4.96 per cent (water / desalination)

Situation. Ten weeks before financial close, Kestrel's lenders' legal adviser circulated a contract-limits table of the kind set out in 12.1.1. It showed the six numbers: a 48,000,000 fixed price, delay damages of 20,000 per day capped at 10 %, performance damages capped at 10 %, an aggregate cap of 20 %, and security comprising a 10 % on-demand bond and a parent guarantee to the aggregate cap. The sponsors' commercial team regarded the stack as market standard and the technical adviser had confirmed the plant design. Nobody had multiplied anything.

What happened. The financial adviser ran three computations in an afternoon. **The cap-binding day:** $4,800,000 \div 20,000 = \text{day } 240$, against a schedule risk analysis whose P80 delay was 210 days and whose P95 was 320 — so the cap covered the P80 case and failed the P95 one, leaving **2,620,000** uncovered at 300 days and **4,104,000** at 360 (Domain 5, KA 5.4.2 computed the 360-day figure). **The performance cap's reach:** on the value basis of 12.1.3, one percentage point of permanent output shortfall is worth $90,600 \times AF(0.08, 25) = 967,134.71$, so the 4,800,000 cap covers a shortfall of **4.9631 %** — while the 1.20 covenant fails at a shortfall of **4.1108 %**. The regime was adequate by a margin of 0.85 percentage points, which nobody had designed and nobody had checked. **And the aggregate cap:** $10 \% + 10 \% = 20 \%$, so the two sub-caps consumed the aggregate exactly and a defects claim after both would recover nothing.

The combined stress — 300 days late at 95 % output — produced exposure of **12,255,673.53** against nominal cover of **9,600,000**, a residue of **2,655,673.53**. Applying the credit arithmetic of 12.3.2, with the bond at full value and the parent guarantee assessed by the lenders' credit function at 0.70, risk-adjusted cover was **8,160,000** and the residue **4,095,673.53** — **22.75 %** of the 18,000,000 equity contribution, and **16.41 %** of Domain 4's project NPV of 16,179,360 on the nominal measure.

How it resolved. Four changes were negotiated, each cheap because the arithmetic was explicit. The **aggregate cap moved from 20 % to 30 %** (14,400,000), so the sub-caps no longer exhausted it and a defects head had 4,800,000 of room. The **on-demand bond rose from 10 % to 15 %** (7,200,000), converting 2,400,000 of parent-guarantee cover at 0.70 into bank cover at full value and

lifting risk-adjusted cover by 720,000; the contractor priced the additional bonding at about 1.2 % per annum over three years — some 86,400 on the incremental 2,400,000 — and added it to the contract sum, which the sponsors accepted as the cheapest credit enhancement available. **A termination-for-delay right at a 300-day long-stop** was added, so that the contractor's incentive did not fall to zero at the cap. And **the performance damages were re-based on the value measure** at 967,135 per percentage point, with the facility agreement amended to direct 60 % of any receipt to prepayment and 40 % to a blocked distribution account — the drafting response to the 521,044.53 tenor mismatch of 12.1.3, which cost nothing and removed a permanent equity leak.

What the domain teaches here. Every one of those four defects was visible from numbers already in the documents; none required a model, a negotiation or a new adviser. The failure was not analytical but procedural: no one had been given the job of multiplying the contract's limits against the project's stresses. That job — the six-number table, the cap-binding day, the coverage reach of each cap, and cover multiplied by credit quality — is the whole of this domain's professional content, and it takes an afternoon.

— Case study B — Domain 12: the interface nobody owned (digital infrastructure)

Situation. A 24 MW hyperscale data centre in a competitive market was let as two packages to save cost and time: **shell and core at 62,000,000** and **mechanical, electrical and network fit-out at 48,000,000**, a combined **110,000,000**. The single-wrap alternative had been offered by the shell contractor at a **3.5 %** premium — **3,850,000** — and declined, correctly on Domain 11's reasoning: the shell contractor could not price the fit-out interfaces it did not control, and its loading reflected that ignorance. What the project company did not do was replace the wrap with an interface regime. There was no interface matrix, no back-to-back completion definition, no cross-liability provision, no interface manager and no single owner of programme float. Financing was **77,000,000** of senior debt at **6.5 %** against forecast operating **CFADS** of **14,600,000**.

What happened. The fit-out contractor's containment and cable-tray installation required structural penetrations at coordinates the shell contractor built to an earlier revision of the model. Each party demonstrated compliance with its own contract documents. The dispute over which revision governed the handover took eleven weeks to resolve commercially, and the practical completion date moved **74 days**.

The arithmetic was unforgiving. Daily carrying cost on the drawn debt was $77,000,000 \times 0.065 \div 360 = 13,902.78$; forgone **CFADS** was $14,600,000 \div 360 = 40,555.56$; the daily economic cost of delay was therefore **54,458.33** and the 74 days cost **4,029,916.67**. On top of that, **both** contractors claimed extensions of time and prolongation — at 9,800 and 7,400 per day respectively, **1,272,800** in total — and both were entitled to something, because neither was in breach of its own scope. Total cost to the project company: **5,302,716.67**, or **4.821 %** of the combined contract price, with **no delay damages recoverable from anyone**.

How it resolved. The claims were settled at a discount on the 12.4.3 arithmetic — both were below the project company's own litigation threshold, and settling promptly was worth more than either defence. The interface responsibility was retrofitted mid-project: an interface manager with authority over both contracts, a matrix of 340 handovers with named owners and dates, a single model revision under change control, and back-to-back milestone definitions for the remaining handovers. The retrofit cost about **640,000** and no comparable event recurred.

What the domain teaches here. The declined wrap was not the error, and the arithmetic proves it: the wrap premium of 3,850,000 was certain, the interface loss of 5,302,717 was not, so buying the

wrap would only have paid if the probability of an event of this size exceeded $3,850,000 \div 5,302,717 = 72.60\%$ — which no one could have argued. The error was to treat "do not buy the wrap" as a complete decision. The interface regime that would have prevented the event cost **640,000**, a breakeven probability of only **12.07%**, and it was the obviously correct purchase on any plausible view of the risk. **Declining a transfer creates a management obligation**, and this domain's contribution is to name the instrument that discharges it — an interface matrix with owners, dates, back-to-back completion definitions, cross-liability and one owner of float — and to price it against the exposure it removes.

— Executive perspective — Domain 12

What a project finance director cannot delegate in this domain:

- **The six numbers.** Contract price, damages rate, delay cap, performance cap, aggregate cap and security. Read them off the documents personally, multiply them, and know the cap-binding day (Kestrel: day 240) and the shortfall each cap reaches (4.9631 %) before signature.
- **The calibration basis of every damages provision.** Whether damages restore the covenant, the sized coverage or the value of the loss — 562,851, 2,980,263 or 4,835,674 for the same 5 % shortfall. Whoever chooses that basis chooses who bears the loss, and it is a sponsor decision, not a drafting detail.
- **The contracted volume floor.** Issue it to the commercial team as a financing constraint with its derivation attached, before negotiation: 95.8892 % for Kestrel's 1.20× covenant, not the 90 % a commercial team will otherwise agree.
- **Cover multiplied by credit quality, and the residue.** 8,160,000 against 12,255,674 of stress exposure leaves 22.75 % of the equity cheque exposed. That number belongs in the investment committee paper in those words; "covered up to the cap" does not.
- **The claims threshold, computed once.** Know the settlement ceiling rule and the disputed sum above which the organisation litigates (6,901,234 on Kestrel's assumptions). Claims policy set in advance beats claims temperament in the moment, and it removes a systematic value leak.
- **The boundary with counsel, in both directions.** Never let a financial model rely on a recovery counsel has not confirmed is available in the governing jurisdiction; and never let a legal negotiation trade a limit whose financial consequence has not been computed. The director owns the interface between the two, and it is the only place in the transaction where both errors are visible at once.

— Calculation exercises — Domain 12

Exercise 12.1 A project has 96,000,000 of debt drawn at 7.2 %, forecast operating **CFADS** of 15,300,000 per year, and an EPC price of 120,000,000. Delay damages are 45,000 per day, capped at 8 % of the price; 30/360 applies. Compute the daily economic cost of delay, the share of it the damages recover, the cap-binding day, and the amount uncovered on a 300-day delay.

Solution. Daily interest $96,000,000 \times 0.072/360 = 19,200$; daily forgone **CFADS** $15,300,000/360 = 42,500$; daily economic cost **61,700**. Damages recover $45,000/61,700 = 72.93\%$. Cap $120,000,000 \times 0.08 = 9,600,000$, binding at $9,600,000/45,000 = \text{day } 213.33$. At 300 days the economic cost is $61,700 \times 300 = 18,510,000$ against a capped recovery of 9,600,000, leaving **8,910,000** uncovered — 7.425 % of the contract price. Common error: calibrating on forgone **CFADS** alone, which would set the

rate at 42,500 and recover only **68.88 %** of the daily cost, omitting the carrying cost of drawn debt — the most certain component, because it accrues whether or not the plant would have performed.

Exercise 12.2 The same project's performance damages are capped at 8 % of the 120,000,000 price. Each percentage point of permanent output shortfall reduces annual **CFADS** by 210,000. The remaining operating life is 20 years and the sponsors' appraisal rate is 8 %. On a value basis, what output shortfall does the cap actually cover?

Solution. $AF(0.08, 20) = 9.818147$; the value of one percentage point is $210,000 \times 9.818147 = 2,061,810.87$. The cap of **9,600,000** therefore covers $9,600,000/2,061,810.87 = 4.6561$ % of output and no more. Common error: dividing the cap by the annual **CFADS** shortfall ($9,600,000/210,000 = 45.7$ "points"), which values a permanent loss as though it lasted one year and overstates the cap's reach roughly tenfold.

Exercise 12.3 The same project is funded with 96,000,000 of senior debt at 7.2 % over 15 years. Its **CFADS** as a function of the share x of contracted output taken is $CFADS(x) = 16,800,000x - 3,072,000$. The covenant is **1.25 $\times$** . Compute the instalment, the **DSCR** at full contracted volume, and the minimum contracted volume floor the covenant requires.

Solution. $AF(0.072, 15) = 8.993967$; instalment $96,000,000/8.993967 = 10,673,821.69$. At $x = 1$, **CFADS** = **13,728,000** and **DSCR** = **1.2861**. The covenant requires $CFADS \geq 1.25 \times 10,673,821.69 = 13,342,277.11$, so $x = (13,342,277.11 + 3,072,000)/16,800,000 = 97.7040$ %. Common error: concluding that because the sized **DSCR** of 1.2861 comfortably exceeds the 1.25 covenant, a 90 % volume floor is safe — at 90 % the **DSCR** is **1.1287**, a breach. Thin headroom converts almost any volume concession into a covenant problem, and the floor must be computed, not inferred from the base-case ratio.

Exercise 12.4 Stress exposure on a contract is 14,200,000. Cover comprises a 6,000,000 on-demand bank bond (payment treated as certain) and a parent company guarantee taking nominal cover to 12,000,000, the parent assessed at a 0.65 probability of paying in full when called. Compute risk-adjusted cover, the uncovered residue on both measures, and the parent-guarantee face amount equivalent to the bond.

Solution. Risk-adjusted cover $6,000,000 + (12,000,000 - 6,000,000) \times 0.65 = 9,900,000$. Uncovered: **2,200,000** on the nominal measure, **4,300,000** risk-adjusted — nearly double. Equivalent face for the bond $6,000,000/0.65 = 9,230,769.23$, a 1.5385 $\times$ multiple. Common error: applying the credit haircut to the whole 12,000,000 (giving 7,800,000), which wrongly discounts the bank bond; the haircut applies only to the layer the weaker obligor supports.

Exercise 12.5 A disputed sum is 2,400,000. Assessed outcomes: 0.30 that the claimant's full case succeeds, 0.30 of a split at the midpoint, 0.40 that it fails. Own legal, expert and management costs are 700,000, incurred at a 14-month midpoint; an award is expected at 30 months; the discount rate is 8 %; settling costs 50,000 of negotiation effort. Compute the present value of fighting, the saving from settling at the midpoint, the settlement ceiling, and the disputed sum above which fighting becomes rational.

Solution. Expected award $0.30 \times 2,400,000 + 0.30 \times 1,200,000 = 1,080,000$. Discount factors $(1.08)^{2.5} = 1.212158$ and $(1.08)^{(14/12)} = 1.093942$. Present value of the award $1,080,000/1.212158 = 890,972.64$; of costs $700,000/1.093942 = 639,887.55$; present value of fighting **1,530,860.19**. Settling at the midpoint costs $1,200,000 + 50,000 = 1,250,000$, so settling saves **280,860.19**. The settlement ceiling is $1,530,860.19 - 50,000 = 1,480,860.19$, or **61.70 %** of the disputed sum. With k

$= (0.30 + 0.15)/1.212158 = 0.371239$, fighting beats settling at the midpoint only above $(639,887.55 - 50,000)/(0.5 - 0.371239) = 4,581,245.18$. Common error: comparing the expected award of 1,080,000 with the midpoint settlement of 1,200,000 and concluding that fighting is cheaper — which ignores both own costs, the larger term, and the 30-month delay before any recovery.

— Practitioner's toolkit — Domain 12

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 12.T.1 — The contract limits and calibration sheet (one per contract)

One page, filled before the contract is signed and re-filled at every amendment. Rows: contract price and change mechanics · damages rate, with the daily economic cost it was calibrated against and the share it recovers · delay cap, and **the cap-binding day** · the credible worst-case delay from the schedule risk analysis, beside it · performance damages rate and cap, with **the shortfall percentage the cap reaches** on the stated basis · the basis itself (bare covenant / sized coverage / value) named and owned · aggregate cap, with the **sum of the sub-caps** beside it · the carve-outs from the cap, each marked "uncapped" and sized · the exclusion of consequential loss, quoted · the combined stress exposure and the residue in currency and as a share of equity. Rule: no contract goes to signature until the residue line is filled and initialled by the accountable sponsor executive.

Toolkit 12.T.2 — Security package sufficiency register (one per transaction)

One row per instrument: instrument type · obligor, and which entity in the group is actually bound · face amount and currency · conditionality (on demand / conditional / requires proof of loss) · credit assessment, with the assessor's name and date · **risk-adjusted amount** · the exposure it covers and that exposure's end date · **the instrument's expiry, and the gap in days if it is earlier** · counsel's confirmation that it is callable as modelled, with date. Footer lines: total face, total risk-adjusted, stress exposure, **residue in currency and as a percentage of equity**. Rule: no lender or equity case reports cover without the risk-adjusted total beside the face total.

Toolkit 12.T.3 — Claim assessment and settlement-zone worksheet (one per claim)

Header: claim reference, event, notice served and whether within the contractual time bar (fact, with the date), clause relied on. Section 1 — **quantum**: each head claimed, the party's own assessment, and the gap. Section 2 — **time**: days claimed, days assessed, and the gap valued at the delay damages rate; plus the party's own economic cost of the days at issue. Section 3 — **process**: own legal, expert and management cost, its timing midpoint, expected date of a binding outcome, outcome probabilities attributed to a named adviser as a range and dated, and the applicable cost-shifting position confirmed by counsel. Section 4 — **arithmetic**: present value of the expected award, present value of own costs, present value of fighting, the settlement ceiling, the saving against a midpoint settlement, and the organisation's standing breakeven disputed sum. Section 5 — **non-financial**: relationship, precedent across open claims, lender disclosure obligation and date, and any consent required for a settlement that touches a material contract. Rule: the mandate given to a negotiator states the ceiling, not the aspiration.

— Exam preparation — Domain 12

What is assessed. Reading a contract stack as a set of computable limits; calibrating and testing liquidated damages against the loss they cover; the interaction of sub-caps and aggregate caps; the three make-good bases for underperformance and the consequences of choosing among them; deriving a contracted volume floor from a covenant; testing termination compensation against the debt-outstanding profile; converting instrument face amounts into risk-adjusted cover and computing equivalence between instruments of different certainty; the commercial valuation of a claim including time impact and process cost; and the governance boundary between commercial arithmetic and legal conclusion.

The calculations to do under time pressure. Daily economic cost of delay = drawn debt $\times$ rate $\div$ day-count basis + annual CFADS $\div$ basis. Cap-binding day = cap $\div$ daily rate. Uncovered residue = daily cost $\times$ days – min(rate $\times$ days, cap). Value of a permanent shortfall = annual CFADS shortfall $\times$ $AF(r, n)$, and the shortfall a cap reaches = cap $\div$ value per point. Coverage-restoring buy-down = debt $\times$ (CFADS shortfall $\div$ base CFADS). Contracted volume floor = (target ratio $\times$ debt service + intercept) $\div$ slope. Risk-adjusted cover = $\Sigma(\text{face} \times \text{probability of payment})$, and equivalent face = certain cover $\div$ probability. Expected award = $\Sigma(\text{probability} \times \text{outcome})$, discounted to today; settlement ceiling = present value of fighting – cost of settling.

The traps.

- Negotiating the damages **rate** and ignoring the **cap-binding day** — the cap is where the structure breaks (12.1.2, Exercise 12.1).
- Calibrating delay damages on forgone revenue alone, omitting carrying cost — 71.70 % coverage for Kestrel, 68.88 % in Exercise 12.1 (12.1.2).
- Reading an aggregate cap as protection above sub-caps that already exhaust it (12.1.1, MCQ 12.1-B).
- Valuing a permanent output shortfall as one year's loss rather than $\times AF(r, n)$ (Exercise 12.2).
- Confusing the three make-good bases and quoting a lender-facing number as the sponsors' loss — 562,851 / 2,980,263 / 4,835,674 (12.1.3, MCQ 12.1-C).
- Assuming that damages of the right **amount** compensate, regardless of how their proceeds are **applied** — the 521,045 tenor mismatch (12.1.3, MCQ 12.1-D).
- Treating the contracted volume floor as a commercial preference rather than deriving it from the covenant — 95.8892 % against 90 % (12.2.2, MCQ 12.2-A, Exercise 12.3).
- Inferring that a comfortable base-case DSCR makes a volume concession safe (Exercise 12.3).
- Reading a percentage-of-debt termination formula as adequate without plotting it against the amortisation profile, where the gap is largest early (12.2.3, 12.A.2, MCQ 12.2-C).
- Splitting packages without an interface regime, and assuming a loss will be recoverable from one of the contractors (12.2.4, MCQ 12.2-D, Case study B).
- Reporting cap face amounts as cover, without multiplying by credit quality — 9,600,000 against 8,160,000 (12.3.2, MCQ 12.3-A, Exercise 12.4).
- Accepting a parent guarantee for a bond at equal face value — the equivalence is 1.4286 $\times$ at 0.70 (12.3.2, MCQ 12.3-B).
- Ignoring instrument expiry against the exposure period (12.3.1, 12.3.4).
- Treating an extension of time as a procedural concession rather than the largest number in the negotiation — 1,800,000 of forgone damages (12.4.3, MCQ 12.4-A).
- Comparing an expected award with a settlement figure while ignoring own costs and the delay to recovery (12.4.3, MCQ 12.4-C, Exercise 12.5).

- Recording a risk as transferred in the register with no clause reference — the orphan risk (12.4.1, MCQ 12.4-D).
- Allowing an AI-produced contract summary, or any summary, to substitute for counsel on enforceability, and letting a model rely on a recovery counsel has not confirmed (every KA).

How the domain connects. Domain 5 established the bankability role of the EPC wrap and computed the cost of a COD slip; Domain 8 sized the contingency that a fixed-price wrap made defensible; Domain 10 supplied the coverage machinery every limit in this domain is tested against, and the covenant and lock-up triggers those tests read; Domain 11 priced the allocations this domain documents and quantified the register residue that no clause covers. Forward: Domain 13's legal, insurance and tax diligence streams verify this stack and its conditions precedent, and its model audit checks that the model's recoveries match the caps; Domain 14 operates the change and certification machinery of KA 12.4 at drawdown; Domain 15 lives with the deduction regimes, guarantees and termination provisions in operation, and reaches for them in restructuring; and Domain 16 governs the AI-assisted contract review that every KA here has bounded.

— Domain 12 summary

Contracts are where Domain 11's priced allocations become enforceable limits, and those limits are numbers that can be multiplied before signature. Kestrel's stack — a 48,000,000 fixed price, delay damages of 20,000 per day against a daily economic cost of 24,733.33, a 10 % delay cap binding at **day 240**, a 10 % performance cap, a 20 % aggregate cap that the two sub-caps **exhaust exactly**, a 10 % on-demand bond and a parent guarantee — produces, against a 300-day delay and a 5 % output shortfall, exposure of **12,255,674** against nominal cover of **9,600,000** and risk-adjusted cover of **8,160,000**: a residue of **2,655,674** nominal and **4,095,674** credit-adjusted, being 14.75 % and **22.75 %** of the 18,000,000 equity cheque and 16.41 % of Domain 4's NPV of 16,179,360. Performance damages must state which loss they restore, because the same 5 % shortfall is worth **562,851** on a bare-covenant basis, **2,980,263** on the sized-coverage basis and **4,835,673.53** on the value basis — a spread of **8.591×** — and the 10 % cap reaches a shortfall of only **4.9631 %** against a covenant that fails at **4.1108 %**; even a correctly sized receipt under-compensates by **521,045** when a 25-year loss is paid by a 12-year debt prepayment, so the application clause is worth as much as the amount. On the revenue side the contracted volume floor is a **financing parameter**, not a commercial preference: Kestrel's 1.20× covenant requires **95.8892 %** of guaranteed output where the commercial team agreed 90 % (a DSCR of **1.0935**), each point of volume being worth 0.0181 of coverage; and a termination formula paying a percentage of debt outstanding fails worst early — **5,926,555** short at the end of year 1 on an 85 % formula — while a formula that covers debt in full leaves equity's **11,128,176** of unreturned capital at zero. Guarantees are worth cap × credit quality, making one dollar of on-demand bank cover equal to **1.4286** dollars of parent guarantee at a 0.70 assessment, and instrument expiry against exposure is the gap most often missed. Claims are valued on expected recovery net of process cost and time: on a disputed **1,520,000**, fighting costs a present value of **1,347,115**, the settlement ceiling is **1,287,115** — **84.68 %** of the claim — settling at the midpoint saves **527,115**, and the disputed sum must exceed **6,901,234** before litigation is rational, which is why an organisation should compute that threshold once and make it policy. Case study B prices the other half of Domain 11's lesson: declining a **3,850,000** wrap premium was defensible at a **72.60 %** breakeven probability, but failing to buy the **640,000** interface regime that would have prevented a **5,302,717** loss at a **12.07 %** breakeven was not — **declining a transfer creates a management obligation**. Throughout, the commercial arithmetic is the finance leader's and the legal conclusion is counsel's: no model may rely on a recovery that qualified counsel has not confirmed is available in the governing jurisdiction. Domain 13 verifies this stack in diligence and at

financial close; Domain 14 runs its change machinery through construction; Domain 15 lives inside its deduction, guarantee and termination regimes in operation.

13

DOMAIN 13

Due Diligence and Financial Close

— Why this domain exists

Domains 10 to 12 sized the debt, allocated the risk and drafted the contracts — all on the assumption that the facts are as represented. Nothing so far has tested that assumption, and nothing so far has turned an agreed set of terms into a funded facility. Both jobs belong here. **Due diligence** is the organised purchase of information about a project before irrevocable commitment; **financial close** is the moment at which every condition has been satisfied, every document signed and the first drawdown is available. Between them sits the most compressed and most expensive period in a project financing, and the period in which the largest number of avoidable errors are made — not because practitioners do not know what to check, but because they treat checking as a procedural obligation rather than as an investment with a computable return.

The domain's central claim is that **diligence and close are economic decisions under a deadline, and both are governed by the price of elapsed time rather than the price of advice**. Three consequences follow, one per Knowledge Area and one across them. A diligence stream is worth running when the loss it can avoid exceeds what it costs, and because fees are small beside the cost of delay, the decisive variable is whether the stream sits inside a parallel envelope or on the critical path (KA 13.1). A model audit produces findings whose value lies entirely in their **class** — whether a finding changes a conclusion — so a finding count is not a measure of anything (KA 13.2). Conditions precedent form a **conjunction with a critical path**, which means the close date is the expected maximum of several chains and not the expected duration of the longest one, a distinction that is invisible in every close timetable drawn as a single bar (KA 13.3). And syndication converts the closed transaction into held positions, with a fee architecture and a market-flex mechanism whose value routinely exceeds the fee that sponsors spend their negotiating capital on (KA 13.4).

Learning objectives. After this domain a candidate can: name the seven standard diligence streams and state what each is uniquely able to find; price a diligence stream as an information purchase and compute its breakeven detection rate; demonstrate why running the same streams in parallel rather than in series can be the difference between creating and destroying value; classify model-audit findings by whether they change a conclusion, a reported output or nothing, and compute the debt-capacity consequence of each class; explain why a finding count and a "findings closed" percentage are misleading control metrics; build a conditions-precedent register as a dependency network with float, compute the expected close date as the expected maximum of its chains, and identify the chain whose de-risking is worth most; build an itemised close-cost budget, express it as a share of debt raised, reconcile it to the sources-and-uses statement and compute the effective cost of debt it implies; explain the underwriting, club and best-efforts syndication routes and compute the fee split, the arranger's yield differential and the cost of a failed sell-down; quantify market flex and test it against the coverage covenant; and govern AI use across data-room review, model scanning,

condition tracking and investor allocation without letting a machine conclude anything that a named professional must own.

The master transaction. Kestrel Water SPC reaches the diligence phase of its financing. The mandate is for **USD 42,000,000** of senior debt at **6.0 % over 12 years** against a **USD 60,000,000** envelope funded 70/30 (Domain 6, KA 6.2.1), with an annual instalment of **USD 5,009,635.23**, first-year interest of **2,520,000** and principal of **2,489,635** (Domain 3). Documented first-year **CFADS** is **USD 6,384,000** (Domain 2), giving **DSCR 1.2743** and, on level cash, an identical **LLCR**; **PLCR** is **1.9431** (Domain 10). The concession's expiry is fixed, so every day between mandate and close destroys one day of operating life: Domain 5 (KA 5.4.2) priced that at **USD 17,733.33 per day** of forgone **CFADS** on a 30/360 basis, which this domain uses as **USD 124,133.33 per calendar week** — the single number that governs almost every decision in it. Seven diligence streams will be commissioned for **USD 1,500,000** of fees; the full close-cost budget will come to **USD 2,709,000**; the model audit will return **34 findings**; and the conditions-precedent register will resolve into five chains whose base close date is 20 weeks away.

KNOWLEDGE AREA 13.1

The diligence streams

Topics: 13.1.1 what diligence is for · 13.1.2 the seven streams and what each uniquely sees · 13.1.3 diligence as an information purchase · 13.1.4 the parallel envelope · 13.1.5 the data room and the diligence trail.

13.1.1 What diligence is for

Definition. Due diligence is the systematic, evidenced examination of a project's technical, financial, legal, tax, insurance, environmental, social and market characteristics, undertaken before commitment, by parties who will state their findings in writing and be identifiable for them.

Three properties distinguish it from ordinary analysis, and each has a practical consequence. **It is adversarial in structure and cooperative in conduct** — the lenders' advisers are paid to find what the sponsor's team has missed or has an interest in not seeing, while everyone depends on the sponsor's cooperation to find anything at all; a diligence process that becomes genuinely adversarial in conduct simply stops producing information. **It is evidenced rather than concluded** — a diligence report's value is its trail from an assertion to a document, which is why "the technical adviser is comfortable" is not a diligence output and a numbered finding against a specific drawing revision is. And **it is time-boxed by a commercial deadline**, which is the property that makes it an economic problem rather than a research problem: unlimited diligence is available at a price nobody will pay, so the real question is always which checks, in what order, inside how long.

What diligence cannot do. It cannot transfer risk. A report identifies a ground condition; it does not pay for it (Domain 11's allocation does, and Domain 12's contract writes it down). It cannot make an unbankable project bankable (Domain 5). And it does not discharge the accountability of the person relying on it — the liability caps of 13.A.1 make that arithmetically obvious. Diligence buys **information**, and information is valuable only if a decision changes as a result. The disciplined test to apply to any proposed piece of work is therefore: what decision would a different answer change, and what is that decision worth? A stream that cannot answer that question is being commissioned for comfort, and comfort is the most expensive thing in a close timetable.

13.1.2 The seven streams and what each uniquely sees

The market has converged on seven streams. The useful way to hold them is not by discipline but by **the class of error each is uniquely able to detect** — because that is what makes them non-substitutable.

Stream	Core question	The error only this stream finds
Technical	Will the asset do what the model assumes, for as long as it assumes?	Design, capacity, availability, degradation and lifecycle-cost assumptions that no financial reviewer can challenge
Financial	Does the model implement the documents, and do the historical accounts support the forecast?	Definitional and structural defects in the model (KA 13.2)
Legal	Is the security package enforceable, are the contracts as summarised, is title good?	Enforceability, perfection and consent gaps behind a correct-looking contract summary
Tax	What cash tax will this structure actually pay, in this jurisdiction, on this timetable?	Withholding, thin capitalisation, loss-relief limits, indirect tax on construction
Insurance	Is the programme in place, and does it match the loss the documents assume is insured?	Exclusions, deductibles, sub-limits and the gap between a broker's slip and a lender's endorsement requirement
Environmental and social	What obligations, liabilities and stakeholder exposures attach to the site and the works?	Legacy contamination, resettlement, biodiversity and consent-condition obligations that survive close
Market	Will the revenue exist at the price and volume the model assumes?	Demand, price and competitive assumptions — the largest single source of realised project failure

Two structural points about the set. **The streams overlap at exactly the places where projects fail**, and the overlaps must be managed rather than eliminated: the technical adviser's availability assumption is the financial model's revenue driver and the offtake contract's liquidated-damages trigger, so three streams touch one number and the risk is that each assumes another owns it. The countermeasure is a **cross-stream interface list** — a short register naming every assumption that more than one adviser touches, with a single named owner (Toolkit 13.T.1). And **the streams are not equally reliable**. Technical, legal and tax diligence examine facts that exist; market diligence examines a forecast that does not, which is why a market consultant's report is evidence about a method rather than evidence about the future, and why Domain 7's stress-testing discipline is the proper use of it.

13.1.3 Diligence as an information purchase

The shape of the arithmetic is PML-AI's gate economics (PML-AI KA 3.3.1), reapplied to a diligence stream. A stream costs a fee and, if it sits on the critical path, elapsed time; in return it converts some probability of a costly post-close discovery into a cheap pre-close correction.

$$\begin{aligned}
 \text{Expected cost without the stream} &= p \times C \\
 \text{Expected cost with the stream} &= \text{fee} + (\text{weeks on the critical path} \times \text{cost of delay}) \\
 &\quad + p \times [d \times F + (1 - d) \times C] \\
 \text{Net value} &= \text{the difference}
 \end{aligned}$$

where p is the probability that a material issue of this stream's class exists, d the probability the stream detects it, C the cost if it reaches close undetected and F the cost of correcting it pre-close. Rearranging for the detection rate at which the stream just breaks even gives the single most useful expression in this Knowledge Area:

$$\text{Breakeven detection rate } d^* = (\text{fee} + \text{priced elapsed time}) \div [p \times (C - F)]$$

Read it in words: **the breakeven detection rate is the diligence spend divided by the expected avoidable loss.** Everything about the economics of diligence follows from the fact that the numerator contains elapsed time.

WORKED EXAMPLE

Worked example 13.1.3 — Kestrel's seven streams, priced.

- Setup.** Illustrative parameters an organisation must estimate from its own transaction record; the arithmetic, not the parameters, is transferable. Kestrel commissions seven streams with the fees and durations below. p , C and F are the sponsor's own estimates from comparable closings; C for the financial stream is Domain 6's independently derived **2,691,071** for a material model error reaching close (KA 6.4.3), which anchors the scale of the others. Detection is assumed at $d = 0.80$ for every stream. Cost of delay **124,133.33 per week**.

Stream	Fee	Weeks	p	C	F	$p \times C$	$p \times (C - F)$
Technical	260,000	8	0.30	6,200,000	400,000	1,860,000.00	1,740,000.00
Financial	180,000	5	0.35	2,691,071	60,000	941,874.85	920,874.85
Legal	420,000	10	0.25	9,000,000	250,000	2,250,000.00	2,187,500.00
Tax	150,000	6	0.20	4,800,000	300,000	960,000.00	900,000.00
Insurance	60,000	4	0.15	1,400,000	120,000	210,000.00	192,000.00
Environmental and social	240,000	12	0.22	7,500,000	900,000	1,650,000.00	1,452,000.00
Market	190,000	9	0.28	5,600,000	500,000	1,568,000.00	1,428,000.00
Total	1,500,000	54				9,439,874.85	

- Formula.** As above, per stream and in aggregate. The aggregate residual expected cost is $\sum p \times [d \times F + (1 - d) \times C]$. Elapsed time is priced **once for the envelope** when streams run in parallel and **once per stream** when they run in series.
- Substitution.** Aggregate $\sum p \times C = 9,439,874.85$. Residual $\sum p \times [0.80 \times F + 0.20 \times C] = 2,383,574.97$. Parallel envelope $12 \times 124,133.33 = 1,489,600$. Serial sequencing $54 \times 124,133.33 = 6,703,200$.
- Result. Parallel:** expected cost $1,500,000 + 1,489,600 + 2,383,574.97 = 5,373,174.97$; net value **+USD 4,066,699.88**. **Serial:** expected cost $1,500,000 + 6,703,200 + 2,383,574.97 = 10,586,774.97$; net value **-USD 1,146,900.12**. The difference is **5,213,600**, exactly **42 weeks** $\times 124,133.33$.
- Interpretation.** The same seven reviews, the same seven fees, the same detection rates — worth **+4,066,700** run inside a twelve-week envelope and **-1,146,900** run one after another. Not one hour of diligence differs between the two readings; **the entire 5,213,600 is scheduling**. That is

the domain's headline result and it reframes the standard argument: a sponsor negotiating adviser fees is negotiating over 1,500,000 while the sequencing decision is worth three and a half times as much, and a lender insisting on serial sequencing "so each stream can rely on the last" is destroying value it cannot see because its own cost of delay is zero. The per-stream breakeven detection rates make the point sharper still. Inside the envelope, where only the fee is charged, the highest breakeven of the seven is **insurance at 31.25 %** and the lowest is **market at 13.31 %** — every stream pays comfortably, because a competent adviser detects far more than a third of the issues in their own discipline. Sequenced serially, the same streams need **72.02 %** (technical), **75.95 %** (legal), **86.95 %** (financial), **91.54 %** (market) and **99.42 %** (tax) — that last figure being a review that must be effectively infallible to be worth holding — while **environmental and social (119.12 %)** and **insurance (289.86 %)** cannot pay at any detection rate, because their elapsed time alone exceeds the loss they could avoid. Three cautions belong with this result. First, **d** is the least defensible parameter in the set and nobody has measured it on a sample of one project; the sensitivity of the answer to it is the reason the breakevens, not the net values, are the output a leader should carry. Second, **c** has a long right tail that expected value averages away — a legal finding can be existential rather than expensive — so a stream may be worth running below its breakeven precisely because the distribution is not symmetric. Third, several streams are **conditions precedent** rather than choices (KA 13.3): the model audit and the lenders' legal and technical reviews will be run whatever the arithmetic says, and the arithmetic's job is then to argue about **timing and scope**, which is exactly the conclusion Domain 6 reached about the audit alone.

Diligence is bought with time, not money: the same seven streams are worth +4,066,700 in parallel and –1,146,900 in series

Blue — the stream sits inside a common twelve-week envelope, so only its 1,500,000 of fees is charged against it

Crimson — the stream is sequenced serially, so it also carries its own elapsed weeks at 124,133.33 each

Insurance and environmental-and-social review cannot pay in series at any detection rate: the delay alone exceeds the loss avoided




Fig 13.1.1 — The breakeven detection rate of each diligence stream, in parallel and in series

13.1.4 The parallel envelope

If elapsed time dominates the economics, then **designing the envelope is the diligence manager's principal task**, and it is a scheduling problem with four levers.

Genuine parallelism. Most streams do not depend on each other's outputs and can be commissioned on the same day. The dependencies that do exist are few and specific: the model audit needs a frozen model, the insurance adviser needs the technical report's loss scenarios, the tax adviser needs the final structure chart. Everything else is convention.

Staged deliverables instead of a single report. A stream that reports once, at week twelve, is a stream whose findings cannot be acted on inside the envelope. A stream that issues a red-flag memorandum at week three, a draft at week eight and a final report at week twelve produces the same information and gives the transaction nine weeks to respond. This is the single highest-return change available in most close processes and it costs nothing.

Scope discipline. The envelope's length is set by the longest stream — here environmental and social at twelve weeks. Shortening that stream shortens the envelope; shortening any other shortens nothing. Compression effort spent off the binding stream is spent for no return, which is the same lesson KA 13.3 draws about conditions.

Honest reliance boundaries. Parallelism creates the risk that two advisers assume different values for the same input, so each stream's report must state the inputs it took from another stream and their version. Without that, parallel diligence produces a set of internally consistent reports that are mutually inconsistent — the failure mode Domain 6's input-provenance rule exists to prevent, appearing at transaction level.

The residual honest point: parallelism has a cost of its own. Running seven streams at once requires management bandwidth the sponsor may not have, and a red-flag finding at week three against six streams already in flight produces expensive rework. The right conclusion is not "always parallel" but "**parallel by default, sequenced only where a dependency is real and priced when it is**" — and the price is 124,133.33 a week.

13.1.5 The data room and the diligence trail

A **data room** is the controlled repository through which the sponsor discloses documents to advisers and lenders, and its quality is a leading indicator of everything else: a project whose data room is complete, indexed and version-controlled is a project whose sponsor has the discipline the finance documents will require for the next twelve years. Three disciplines earn their place. **A disclosure index that is itself a document** — numbered, dated, listing what was disclosed and when — because it later determines what a lender was told, which matters if a representation is challenged. **Version control with supersession marked, not deleted** — a superseded traffic forecast left in the room without a supersession note is the exact failure Domain 6 (Case study B) priced, and a superseded forecast removed is worse, because the trail disappears. And **a question-and-answer log**, because the answers are representations in substance whether or not they are representations in form.

The **diligence trail** is what remains after close: reports, the disclosure index, the Q-and-A log, the finding registers and their close-out evidence. It is not archive material — it is the evidence base for the first covenant dispute, the first warranty claim, the first refinancing and the first sale, and Case study B shows what its absence costs.

AI in this KA

Where it earns its place. Data-room triage is now genuinely strong machine work and it attacks exactly the constraint that matters: elapsed time. Three uses are robust. **Completeness checking** — reconciling the data-room index against a required-document list and reporting what is absent, which is a set operation humans perform badly at scale. **Extraction into a comparable register** — pulling parties, dates, tenors, defined terms, termination triggers, caps, indexation formulae and governing

law out of several hundred documents into the structured table Domain 5 (KA 5.3) and Domain 12 (KA 12.4.1) both depend on. And **inconsistency flagging** across documents: the same defined term with two definitions, a date that differs between the offtake and the concession, a capacity figure that differs between the technical report and the model.

Where it must not go. It must not produce a conclusion in any stream. Whether security is perfected, whether withholding applies, whether a consent condition survives close, whether an exclusion defeats an insured loss — each is a professional opinion in a named jurisdiction with a named accountable author, and a plausible machine answer to any of them is more dangerous than no answer, because it will be relied on without a liability position behind it. It must not be presented as diligence to a lender: a machine extraction is an input to a stream, never the stream. And it must not be used to shorten the envelope by removing a stream — the 13.1.3 arithmetic shows machine pre-checks are additive to review, the same conclusion Domain 6 reached about model scanning (KA 6.4.4).

Verification, concretely. Sample the extraction: for a stated sample size — twenty documents or ten per cent, whichever is larger — reconcile every extracted field to the source document and record the error rate, by field type, in the diligence file. Never accept an extraction whose error rate has not been measured on this transaction's own documents, because extraction accuracy varies by document quality and this project's documents are the only relevant population. Every flagged inconsistency is confirmed by a human before it enters a finding register. And the estimated parameters in the stream economics — *p*, *d*, *C* — are recorded with their basis, because a machine-assisted process that changes *d* without measuring it has changed the answer without evidence. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 13.1

Term	Meaning
Due diligence	Evidenced pre-commitment examination of a project, reported in writing by identifiable authors.
Diligence stream	One discipline's review — technical, financial, legal, tax, insurance, E&S, market.
Breakeven detection rate <i>d</i>*	$(\text{fee} + \text{priced elapsed time}) \div [p \times (C - F)]$; the diligence spend divided by the expected avoidable loss.
Parallel envelope	The period inside which streams run concurrently, so elapsed time is priced once, not per stream.
Red-flag memorandum	An early partial deliverable that lets findings be acted on inside the envelope.
Cross-stream interface list	Register of assumptions touched by more than one adviser, each with a single named owner.
Data room / disclosure index	The controlled disclosure repository and the numbered, dated record of what was disclosed.

■ SAMPLE MCQS — KA 13.1

MCQ 13.1-A [13.1.3 · Application] A diligence stream costs a 260,000 fee, *p* = 0.30, *C* = 6,200,000 and *F* = 400,000. Run inside a parallel envelope so that it adds no elapsed time, its breakeven detection rate is:

A. 13.98 %

B. 14.94 % ✓ CORRECT

- C. 4.19 %
- D. 72.02 %

Rationale: $260,000 / [0.30 \times (6,200,000 - 400,000)] = 260,000/1,740,000 = 14.94 \%$. A divides by $p \times C$ and omits the pre-close correction cost F , overstating the avoidable loss and so understating the breakeven; C divides the fee by C alone and ignores p ; D is the same stream's breakeven when sequenced serially with eight weeks of delay priced in.

MCQ 13.1-B [13.1.4 · Analysis] Seven diligence streams with 1,500,000 of fees and durations totalling 54 weeks are worth **+4,066,700** in a twelve-week parallel envelope and **-1,146,900** sequenced serially, at a cost of delay of 124,133.33 a week. The correct reading is:

- A. the streams are marginal and some should be dropped
- B. the entire 5,213,600 difference is the 42 weeks of sequencing, so the sequencing decision matters roughly three and a half times more than the fee negotiation ✓ CORRECT
- C. the fees are too high and should be reduced by 5,213,600
- D. serial sequencing is preferable because each stream can rely on the last

Rationale: $42 \times 124,133.33 = 5,213,600$ and the fees, probabilities and detection rates are identical in both readings (13.1.3). A misreads a scheduling result as a scope result; C is arithmetically impossible against 1,500,000 of fees; D describes a real but rare dependency that 13.1.4 requires to be priced rather than assumed.

MCQ 13.1-C [13.1.3 · Evaluation] On the parameters above, insurance diligence sequenced serially has a breakeven detection rate of 289.86 %. The professional conclusion is:

- A. insurance diligence should be abandoned
- B. the insurance adviser is overpriced
- C. insurance diligence must sit inside the envelope, where its breakeven is 31.25 % — the finding is about sequencing, not about the stream ✓ CORRECT
- D. the calculation is invalid because a probability cannot exceed one

Rationale: A breakeven above 100 % says the configuration cannot pay, not that the review is worthless; inside the envelope the same stream breaks even at 31.25 % (13.1.3). B is wrong because the 60,000 fee is the smallest of the seven — 496,533.33 of delay is what makes it impossible. D mistakes an impossible-configuration signal for an arithmetic error.

MCQ 13.1-D [13.1.2 · Analysis] Three parties rely on the same plant availability figure: the technical adviser who derives it, the financial model that earns revenue on it and the offtake agreement that pays damages against it. The specific diligence control for this is:

- A. asking each adviser to confirm they are comfortable
- B. a cross-stream interface list naming every multi-adviser assumption with one named owner and one version ✓ CORRECT
- C. running the streams serially so each can rely on the previous report
- D. relying on the model audit to catch any inconsistency

Rationale: The overlap is where projects fail, and the countermeasure is single ownership of the shared assumption (13.1.2). A produces no evidence; C costs 124,133.33 a week for a control a register achieves free; D is out of scope — the audit tests the model against documents, not whether two advisers assumed the same thing.

MCQ 13.1-E [13.1.4 · Analysis] Kestrel's diligence envelope is twelve weeks, set by the environmental and social stream; the next-longest streams are legal at ten weeks and market at nine.

Delay costs 124,133.33 a week. The environmental and social consultant offers to compress its stream to nine weeks for a 200,000 acceleration fee. The sponsor should:

- A. accept — three weeks at 124,133.33 is 372,399.99 against a 200,000 fee, a clear gain
- B. accept, but recognise that the envelope then falls only to ten weeks on the legal stream, so the acceleration buys two weeks (248,266.66) for 200,000 — a thin 48,266.66, and worth pairing with legal compression before the fee is agreed ✓ CORRECT
- C. decline — 200,000 exceeds the 150,000 that a ten per cent reduction across the whole 1,500,000 fee book would save
- D. decline — compression off the binding stream returns nothing

Rationale: The envelope is the maximum of the stream durations, so compressing the binding stream returns weeks only until the second-longest stream becomes binding: $\max(8, 5, 10, 6, 4, 9, 9) = 10$, giving $2 \times 124,133.33 = 248,266.66$ and a net **48,266.66**, not the 372,399.99 A assumes by crediting all three weeks. C compares an acceleration purchase against a fee negotiation as though the two were alternatives when both are available, and prefers the smaller saving. D applies 13.1.4's rule to the wrong stream — environmental and social is the binding stream; the rule bites on the legal ceiling, which is why the recommendation is conditional rather than negative.

MCQ 13.1-F [13.1.1 · Comprehension] Which restatement most closely captures the test 13.1.1 sets before any diligence stream is commissioned?

- A. every discipline should be reviewed to a comparable depth, so that the file is complete
- B. a stream is worth commissioning when a different answer would change a decision, and that decision is worth more than the stream costs ✓ CORRECT
- C. a stream is worth commissioning when the adviser will accept liability for its conclusions
- D. a stream is worth commissioning when the lenders require it as a condition precedent

Rationale: Diligence buys information, and information has value only where a decision turns on it (13.1.1). A is the comfort purchase the topic warns against — uniform depth is a filing standard, not a value test; C confuses reliance with information value, and 13.A.1 shows the cap covers a small fraction of the exposure in any case; D is a real procurement fact for several streams, but 13.1.3 notes the arithmetic then argues about timing and scope rather than about whether to run the stream.

MCQ 13.1-G [13.1.5 · Evaluation] During diligence a demand study commissioned early in development is superseded by a second study with a lower central case. The sponsor's development team proposes removing the first study from the data room, on the ground that no party relies on it and its presence will only raise questions the second study has already answered. Counsel takes a different view: leave it in the room, marked, but keep it off the numbered disclosure index, since indexing a forecast nobody stands behind is an invitation to rely on it. The soundest professional position is that the first study:

- A. should be removed — a superseded document is not a disclosure, and a central case nobody stands behind is a liability in a room and nothing else
- B. should stay, marked superseded with a date and a note, and appear on the numbered disclosure index — because the index is what later determines what the lenders were told, and a document available in the room but absent from the index is the one combination that can be neither relied on nor disproved ✓ CORRECT
- C. should stay unmarked, since both studies carry dates and a reader can see which is later
- D. should stay, marked superseded, but off the index as counsel proposes, so that the record shows the second study as the only disclosed forecast

Rationale: Two of 13.1.5's three disciplines meet here: version control with supersession **marked** rather than deleted, and a disclosure index that is itself a document. **D** is the serious competitor and it is the position counsel actually takes — it keeps the document and shortens the record — but disclosure is a matter of what the lenders had, not of what the index chose to name: a document sitting in the room is disclosed whichever list it appears on, so leaving it off buys nothing and costs the ability to show what was disclosed and when, which is the one thing the index exists to do. The reliance concern **D** is answering is what the supersession note is for. **A** has real commercial force — a superseded central case does get read, and the second study did answer it — but it treats an evidentiary problem as a presentational one, and removal is the worse of the two failures because what disappears is the evidence base for the first covenant dispute, warranty claim and refinancing. **C** leaves two live-looking central cases and no record of which was relied on, which is the failure Domain 6 (Case study B) priced.

■ SELF-CHECK — KA 13.1

1. State the breakeven detection rate in words. — The diligence spend divided by the expected avoidable loss, $p \times (C - F)$; elapsed time is part of the spend.
2. Why does shortening the tax stream not shorten the envelope? — The envelope is set by the longest stream (environmental and social, twelve weeks); compression off the binding stream returns nothing.
3. What does diligence buy, and what does it not? — Information, and only where a decision would change; it never transfers risk and never discharges the reliant party's accountability.

KNOWLEDGE AREA 13.2

Model audit

Topics: 13.2.1 scope and what the audit is not · 13.2.2 findings by class · 13.2.3 the class-one findings priced · 13.2.4 closing findings out.

13.2.1 Scope and what the audit is not

Domain 6 (KA 6.4.3) defined the model audit, established the governance apparatus that makes it possible and **priced it** — finding that its elapsed time rather than its fee decides whether it pays, that its breakeven error rate falls from 20.10 % to 8.05 % when it moves early, and that a weak audit is worse than none below a 48.81 % detection rate. That arithmetic is not repeated here. What Domain 13 adds is the transaction-side treatment: what the audit's scope must cover, how its output must be read, and what happens to a financing when a finding lands.

The four scope layers, in the order a competent auditor works through them and in the reverse order of how often they are the problem. **Arithmetic** — do the formulae compute what they claim? This is the layer everybody expects and the layer that almost never contains the expensive error. **Structure** — do the mechanics work under stress: does the waterfall behave when a tier fails, does the tax computation behave when losses exhaust, does the schedule close at zero? **Documents** — does the model implement the finance documents: the **CFADS** definition clause by clause, the covenant test dates, the reserve mechanics, the interest convention, the distribution tests? And **assumptions and provenance** — is each input traced to a source document of the correct version, and are the conventions internally consistent (Domain 3's timing and day-count discipline, Domain 6's convention list)?

What the audit is not. It is not a valuation opinion, and it is not an endorsement of the assumptions: an auditor confirms that a tariff escalation of 2.5 % is implemented correctly and sourced to clause 14.3, not that 2.5 % is right. It is not a substitute for the technical, market or tax streams — it tests whether the model implements what those streams concluded. It is not a sponsor deliverable; it is a lenders' control, and a sponsor who treats it as a compliance exercise has misunderstood who is buying. And, critically, **it is not a warranty**: its liability position is capped and its reliance is addressed (13.A.1), so a signed audit report reduces the probability of an error and does not transfer the cost of one.

13.2.2 Findings by class, not totalled

A model audit reports findings. The universal reporting failure — in transaction status reports, in credit papers and in sponsor board packs alike — is to **total them**. "Thirty-four findings, of which thirty-one closed" is a sentence with no information content, because the findings are not commensurable. The remedy is a **class scheme applied before any count is quoted**, and the classes must be defined by consequence, not by the auditor's sense of importance:

Class	Definition	What it changes	Who must see it
Class 1 — fundamental	Changes a financing conclusion : debt capacity, a covenant outcome, the funding plan's sufficiency, or a distribution test	The transaction	Credit committee and sponsor board, individually and by name
Class 2 — material	Changes a reported output beyond the agreed materiality threshold, without changing a conclusion	The reported numbers	Deal team, listed individually with quantified effect
Class 3 — presentational or procedural	Changes no number: labelling, formatting, unused rows, documentation, print ranges, non-output hardcoding	Nothing	Reported in aggregate only

The class scheme requires a stated materiality threshold, and it should be expressed in the metric the transaction is judged on rather than in currency. Kestrel's was set at **0.01× of DSCR** — roughly 50,000 of annual **CFADS** at its debt-service level — which is the kind of threshold a credit committee can reason about, unlike "USD 100,000" whose significance depends on which line it lands in.

Kestrel's 34 findings resolved as 3 Class 1, 7 Class 2 and 24 Class 3. Three consequences that generalise:

- **Class 3 is 70.6 % of the count and 0 % of the impact.** Any metric driven by count is therefore driven by the class that does not matter, which is why "31 of 34 closed" — **91.2 %** — is a progress figure that can be true while every finding that changes the transaction remains open. The honest metric is **class-weighted**: three of three Class 1 findings open is 0 % of the impact closed, whatever the count says.
- **The seven Class 2 findings netted to +18,000 of year-one CFADS** — they very nearly cancelled. That is a coincidence and must never be reported as a control: each was wrong, each was corrected, and the netting tells the reader nothing except that this particular set of errors happened to point in opposing directions. A model whose Class 2 findings net to zero is not a model with no Class 2 findings.
- **Only Class 1 findings are re-audited.** Correcting a fundamental finding changes dependent lines, so the corrected model must be re-run against the audit's own test set and the golden answers re-verified (Domain 6's regression discipline). Class 2 corrections are checked; Class 3

corrections are accepted on the modeller's confirmation. Treating all three the same is how a close timetable loses two weeks to formatting.

13.2.3 The class-one findings priced

WORKED EXAMPLE

Worked example 13.2.3 — what three findings did to Kestrel's financing.

- Setup.** The model audit of Kestrel's financing model returns three Class 1 findings. **F-01, definitional:** the facility defines **CFADS** after the annual maintenance-reserve top-up of **260,000**; the model struck it after debt service instead, so reported **CFADS** of 6,384,000 overstates the defined figure. **F-02, convention:** the debt-service schedule was built as an **annuity due** (payments in advance) rather than in arrears as the facility provides — Domain 3 (KA 3.2.1) named this the commonest annuity mistake; here it is inside a financing model. **F-03, funding plan:** the six-month DSRA of **2,504,818** (Domain 10, KA 10.3.2) appears as an operating-period cash outflow but not in the uses of funds, so the funding plan does not fund it. The lender's requirement is a base-case **DSCR** of **1.30×**; $AF(0.06, 12) = 8.383844$.
- Formula.** Corrected **CFADS** = reported — the misplaced line. $DSCR = CFADS \div \text{debt service}$. AF for an annuity due = $AF(r, n) \times (1 + r)$. Debt capacity = $CFADS \div \text{target DSCR} \times AF(r, n)$ (Domain 10, KA 10.1.2).
- Substitution.** F-01: $6,384,000 - 260,000$, then $\div 5,009,635.23$. F-02: $AF_due = 8.383844 \times 1.06 = 8.886875$; instalment $42,000,000 \div 8.886875$; then $6,384,000 \div \text{that instalment}$. Capacity: $6,124,000 \div 1.30 = 4,710,769.23, \times 8.383844$.
- Result.**

Finding	The error's effect on what was reported	The corrected figure
F-02 convention	Instalment 4,726,071 — understated by 283,564 ; DSCR reported as 1.3508 , apparently clearing the 1.30× requirement	Instalment 5,009,635.23 ; DSCR 1.2743
F-01 definition	CFADS overstated by 260,000	CFADS 6,124,000 ; DSCR 1.2224
F-01 + F-02 together	Reported DSCR 1.2958 on the wrong instalment	Debt capacity at 1.30× USD 39,494,354 against 42,000,000 mandated — a resize of USD 2,505,646
F-03 funding plan	Uses of funds understated by 2,504,818	The DSRA must be funded, from debt, equity or first operating cash

- Interpretation.** Take F-02 first, because it is the finding that should frighten a reader. A single timing convention — payments in advance instead of in arrears — understated the instalment by **283,564**, which flattered the **DSCR** from 1.2743 to **1.3508** and made the model report a project that comfortably cleared a 1.30× requirement it in fact fails. Nothing about the model looked wrong: the schedule closed at zero, total principal equalled the loan and every check block was green, because an annuity due is a perfectly valid amortisation of 42,000,000 — just not the one the facility documents. **This is the characteristic shape of an expensive model error: internally consistent, arithmetically correct and wrong against the document**, which is precisely why the audit's document layer matters more than its arithmetic layer and why a machine scanner would not have found it (Domain 6, KA 6.4.4). Second, note the **direction of the combination**. F-01 and F-02 both flatter the ratio, so they compound rather than offset: together

they take the reported 1.3508 down to a true 1.2224, and the debt the project can actually carry at the lender's requirement falls from Domain 10's **41,171,123** on uncorrected **CFADS** to **39,494,354** — a resize of **2,505,646** that must be funded as equity or not funded at all. Third, **F-03 is the finding that would have caused an event, not an argument**. A **DSCR** shortfall is negotiated; a funding plan that does not fund a mandatory reserve produces a failed condition at first drawdown or a covenant breach in the first operating year, and it is the class of error that reaches close most often, because sources-and- uses statements are reviewed for arithmetic (they always balance) rather than for completeness. Finally, the **professional caution about ordering**: had the auditor reported "34 findings, 3 fundamental" without quantifying them, the credit committee would have received a status update rather than a decision paper. The quantification — 2,505,646 of resize and 2,504,818 of unfunded reserve, on a mandate of 42,000,000 — is what converts an audit into a transaction event, and producing it is the sponsor's job as much as the auditor's.

13.2.4 Closing findings out

A finding is closed when the model has been corrected, the correction has been verified by the auditor, and the **dependent consequences have been followed through**. The third limb is where close processes fail, because a Class 1 correction propagates: correcting F-01 changes **CFADS**, which changes every coverage ratio, the sculpting profile if there is one, the distribution forecast, the lock-up test dates and the equity return. A finding closed in the model and not in the credit paper, the term sheet and the base case is not closed.

The disciplines that make close-out real: **one register, owned by one named person**, with each finding's class, quantified effect, correction, verifier and date; **a re-run of the golden-answer set after every Class 1 correction**, with any changed figure explained before it is accepted; **a final auditor's letter that lists the findings and their disposition** rather than issuing a clean opinion that conceals what was found; and **a stated position on anything not closed** — because findings are sometimes accepted rather than corrected, and an accepted finding with a written rationale is professional whereas an accepted finding recorded as "closed" is not.

AI in this KA

Where it earns its place. Domain 6 (KA 6.4.4) covered workbook scanning, version diffing, adversarial test generation and documentation drafting, and priced a pre-check at 8,000 with a 55 % detection rate. The transaction-side addition here is narrower and genuinely useful: **mapping the finance documents' defined terms onto model lines**, producing a candidate reconciliation of every **CFADS** definition limb to the cell that implements it. That is the input to Toolkit 13.T.2 and it attacks the layer where the expensive errors live.

Where it must not go. It must not assign the class. Classification is a judgment about whether a financing conclusion changes — it requires knowing the lender's requirement, the covenant level and what the credit committee approved — and a machine that grades findings by severity will grade by textual signal, systematically under-rating the quiet definitional finding that resizes the debt. It must not draft the auditor's letter or the certificate of satisfaction. And it must not be credited with detection it did not achieve: F-02 above is a document-conformance error in a structurally valid schedule, exactly the class scanners miss.

Verification, concretely. Every machine-proposed definition-to-line mapping is confirmed against the clause by a named person, with the clause reference recorded. The golden-answer set is re-run after every accepted correction, machine-assisted or not. And the finding register records, per finding, whether it was found by machine, by the auditor or by the sponsor's own review — which is the only way an organisation ever learns what its **d** actually is.

■ KEY TERMS — KA 13.2

Term	Meaning
Model audit	Independent review of a model against the transaction documents, its own logic and its arithmetic (Domain 6, KA 6.4.3).
Scope layers	Arithmetic · structure · documents · assumptions and provenance; the expensive errors sit in the last two.
Class 1 / 2 / 3 finding	Changes a financing conclusion · changes a reported output beyond materiality · changes no number.
Materiality threshold	The stated size below which a difference is not a finding; best expressed in the transaction's own metric ($0.01 \times$ of <i>DSCR</i>).
Class-weighted closure	Progress measured by impact closed, not findings closed.
Finding close-out	Corrected, verified, and every dependent consequence followed through into papers and the base case.

■ SAMPLE MCQS — KA 13.2

MCQ 13.2-A [13.2.3 · Application] A model builds the debt-service schedule as an annuity due rather than in arrears. On 42,000,000 at 6 % over 12 years (*AF* = 8.383844) with *CFADS* of 6,384,000, the reported *DSCR* and the truth are:

- A. reported 1.2743, true 1.3508
- B. reported 1.3508, true 1.2743 ☒ **CORRECT**
- C. reported and true both 1.2743 — the convention does not affect the ratio
- D. reported 1.2224, true 1.2743

Rationale: $AF_due = 8.383844 \times 1.06 = 8.886875$, instalment $42,000,000/8.886875 = 4,726,071$ and $6,384,000/4,726,071 = 1.3508$; the correct in-arrears instalment of 5,009,635.23 gives 1.2743. A reverses the direction — an annuity due has a smaller instalment, so it flatters the ratio; C denies that the denominator moved by 283,564; D is the *DSCR* after the separate *CFADS*-definition finding, on the correct instalment.

MCQ 13.2-B [13.2.2 · Evaluation] A model audit returns 34 findings — 3 Class 1, 7 Class 2, 24 Class 3 — and the status report says "31 of 34 closed, 91.2 %". The correct challenge is:

- A. the count is wrong
- B. the 91.2 % is driven by the 24 Class 3 findings, which are 70.6 % of the count and none of the impact; if the three open findings are the Class 1 findings, 0 % of the impact is closed ☒ **CORRECT**
- C. Class 3 findings should not be reported at all
- D. the audit should be re-run

Rationale: Findings are not commensurable, so a count-based metric measures the class that changes nothing (13.2.2). A is not the defect; C loses the aggregate record that shows model hygiene; D confuses a reporting failure with an audit failure.

MCQ 13.2-C [13.2.3 · Application] After correcting *CFADS* to 6,124,000, debt capacity at a $1.30 \times$ requirement over 12 years at 6 % (*AF* = 8.383844) is closest to:

- A. USD 41,171,123

- B. USD 39,494,354 ☒ **CORRECT**
- C. USD 42,000,000
- D. USD 51,342,661

Rationale: $6,124,000/1.30 = 4,710,769.23, \times 8.383844 = 39,494,354$. A is Domain 10's capacity on the uncorrected 6,384,000; C is the mandated amount, which the calculation rejects by 2,505,646; D omits the coverage divisor entirely ($6,124,000 \times 8.383844$).

MCQ 13.2-D [13.2.1 · Analysis] Which audit scope layer would have caught a model that implements a valid amortisation the finance documents do not provide for?

- A. arithmetic — the formulae are checked
- B. structure — the schedule closes at zero
- C. documents — the model is tested against what the facility actually says ☒ **CORRECT**
- D. assumptions and provenance — the inputs are traced

Rationale: An annuity due computes correctly and closes at zero, so layers A and B both pass (13.2.3); only conformance to the document detects it. D would trace the rate and tenor, both of which are right.

MCQ 13.2-E [13.2.3 · Analysis] Two Class 1 findings are almost identical in size: the definitional and convention findings together resize the facility by **2,505,646**, and the funding plan omits the **2,504,818** debt-service reserve — a difference of 828. The credit paper can lead with one. Which is the more decisive finding, and why?

- A. the resize, because 2,505,646 is the larger number
- B. the unfunded reserve, because a coverage shortfall is negotiated between the parties whereas a funding plan that does not fund a mandatory reserve produces a failed condition at first drawdown or a first-year breach ☒ **CORRECT**
- C. neither, because at 828 apart they very nearly cancel
- D. the resize, because CFADS is the model's most important line

Rationale: Class 1 findings are ranked by the kind of consequence they create, not by magnitude: one changes a negotiating position, the other creates an event the documents will treat as a failure (13.2.3). A ranks by size where the two sizes are indistinguishable anyway. C is the netting fallacy 13.2.2 forbids, applied more crudely still — these findings do not offset, they are simply similar in scale, and one of them is not a cash amount at all. D substitutes a slogan for the consequence test.

MCQ 13.2-F [13.2.2 · Comprehension] A colleague new to model audit asks why the auditor will not report a single "findings closed" percentage. The best short explanation is:

- A. the auditor prefers not to be measured on a number it does not control
- B. the three classes are not commensurable, so one percentage adds findings that change the transaction to findings that change nothing; progress has to be measured by impact closed ☒ **CORRECT**
- C. the percentage is never final, because new findings keep arriving until the model is frozen
- D. the percentage understates progress, because Class 3 findings are the quickest to close

Rationale: The objection is to combining unlike things, and the remedy is class-weighted closure (13.2.2). A imputes a motive where there is a measurement defect; C describes a practical nuisance that would apply equally to a class-weighted metric; D inverts the direction — Class 3 findings being quick and numerous is exactly what makes a count overstate progress, as "31 of 34, 91.2 %" does.

MCQ 13.2-G [13.2.4 · Evaluation] A finding moves year-one CFADS by **180,000** — **0.0359×** of DSCR, against the stated materiality threshold of $0.01\times$, about **50,096** of annual CFADS — and the sponsor disputes it, arguing the auditor has misread the clause. The auditor does not agree. The deal team proposes recording it as "closed — no adjustment required", so that the register shows nothing outstanding at close. The soundest treatment is to record it:

- A. as closed, since no adjustment was made and nothing further is to be done
- B. as **accepted** rather than corrected, with its quantified effect, the written rationale, the name of the person accepting it, and its disposition listed on the auditor's final letter ✓ **CORRECT**
- C. as withdrawn, because a finding the auditor cannot substantiate against the sponsor's reading of the clause is not a finding
- D. as escalated to the credit committee, which alone can accept a finding the parties cannot resolve

Rationale: Findings are sometimes accepted rather than corrected, and an accepted finding with a written rationale is professional whereas the same finding recorded as "closed" is not (13.2.4). A produces a register that misdescribes the position to every later reader — the defect Case study B shows costs money two years afterwards. C lets the party whose reading is disputed close the item. D is the right route for a Class 1 finding, but this one changes no conclusion — DSCR after it is **1.2384**, still clear of the 1.20 covenant, so it is Class 2 — and routing it upwards substitutes a governance step for the record the register exists to hold.

■ SELF-CHECK — KA 13.2

1. Why is a finding count uninformative? — Findings are not commensurable; Class 3 dominates the count and contributes nothing to impact.
2. Which audit layer holds the expensive errors, and why? — Documents and assumptions: a model can be arithmetically perfect and structurally sound while implementing something the facility does not provide for.
3. When is a Class 1 finding closed? — When corrected, verified by the auditor, and followed through into every dependent output, paper and base case.

KNOWLEDGE AREA 13.3

Conditions precedent and documentation

Topics: 13.3.1 the condition set and its categories · 13.3.2 the conjunction with a critical path · 13.3.3 float, criticality risk and where to spend · 13.3.4 the close-cost budget and sources and uses · 13.3.5 waivers, long-stop dates and post-close undertakings.

13.3.1 The condition set and its categories

Definition. A **condition precedent** is a requirement that must be satisfied — and evidenced to the lenders' satisfaction — before an obligation arises, most importantly before first drawdown. Domain 5 (KA 5.A.2) established that the bankability conditions become the CP schedule, that CPs are ordered by dependency rather than importance, that sponsor CPs behave differently from third-party CPs, and that a waived CP is not a satisfied CP. This Knowledge Area computes what that schedule costs.

The condition set divides into five practical groups, and the division matters because each group fails differently. **Corporate and authority** conditions — board and shareholder resolutions, constitutional documents, powers of attorney, authorised-signatory evidence — are within the sponsor group's control, fail through inattention rather than uncertainty, and are therefore forgivable in timetable terms. **Documentary** conditions — executed finance, security, project and direct agreements, and the legal opinions that support them — fail through negotiation, and their duration is a function of how many parties must agree. **Third-party** conditions — permits, licences, land instruments, offtaker and grantor consents, letters of credit from banks that are not the lenders — are outside the group's control and are the standard source of close slippage. **Adviser and process** conditions — the diligence reports of KA 13.1, the model audit of KA 13.2, final credit approvals — have durations the transaction can influence but not compress at will. And **financial** conditions — equity funded or committed on acceptable terms, accounts opened, insurance placed and endorsed, fees paid, the base-case model agreed and locked — are the ones most often discovered late, because they look administrative.

The professional discipline that this Knowledge Area exists to install: **a CP schedule is a dependency network, and it must be built and read as one.** A close timetable drawn as a single bar labelled "conditions precedent — 20 weeks" contains no information about what will actually make the project late.

13.3.2 The conjunction with a critical path

Close occurs when **every** condition is satisfied. That is a conjunction, and conjunctions of uncertain durations behave in a way that timetables systematically misrepresent: the close date is the **maximum** of the chains' realised durations, and the expected maximum is greater than the maximum of the expectations. The gap is not a rounding error; it is often the whole of the contingency a transaction should have carried and did not.

WORKED EXAMPLE

Worked example 13.3.2 — when will Kestrel actually close?

1. **Setup.** Kestrel's 40-odd conditions resolve into five dependency chains. Each chain's base duration is the sum of its links; each carries an independent risk of a single slip, estimated from the sponsor's own record of comparable closings. Cost of delay **124,133.33 per week.**

Chain	Contents	Base duration	Slip probability	Slip if it occurs
A	Board and shareholder resolutions → shareholders' agreement amendment → equity commitments and credit support	9 weeks	0.20	3 weeks
B	Land instrument registration → construction permit → abstraction licence	18 weeks	0.35	6 weeks
C	Diligence reports (12-week envelope) → model audit → final credit approvals	20 weeks	0.30	4 weeks
D	Finance documents agreed → security documents and perfection → legal opinions	17 weeks	0.25	5 weeks
E	Insurance adviser's report → placement and lender endorsements	7 weeks	0.15	2 weeks

1. **Formula.** Base close = $\max(\text{base durations})$. Each chain's expected duration = $\text{base} + \text{probability} \times \text{slip}$. The close date = $\max$ over chains of the realised duration; $E[\text{close}] = \sum \text{over all 32 outcomes of } (\text{probability} \times \text{maximum duration})$. Cost of slippage = $(E[\text{close}] - \text{base close}) \times \text{cost of delay}$.
2. **Substitution.** Base close = **20 weeks** (chain C). Expected durations: A 9.60, B 20.10, C 21.20, D 18.25, E 7.30. Chains A and E can never bind, since even their slipped durations (12 and 9 weeks) fall short of 20; the maximum is therefore decided by B, C and D over eight outcomes.
3. **Result.** $E[\text{close}] = 22.4075$ weeks against a **max of expectations of 21.2000**. The close-date distribution is **20 weeks with probability 34.125 %**, **22 weeks with 11.375 %** and **24 weeks with 54.500 %**. Expected slip **2.4075 weeks**, costing $2.4075 \times 124,133.33 = \text{USD } 298,851$. Chain C's own expected slip of 1.2 weeks costs **USD 148,960**, so the **conjunction premium is USD 149,891** — the expected cost of delay is **2.0062**× the cost of the critical chain's own expected slip.
4. **Interpretation.** Three results, in ascending order of usefulness. The first is the one that changes behaviour: **the probability that this transaction closes on its own stated date is 34.125 %** — and every individual chain owner can truthfully report that their chain is more likely than not to hold its date. That is the arithmetic behind the observation that project financings are almost never early and usually late, and it is not pessimism, incompetence or optimism bias; it is what a conjunction does. The second is the pricing consequence: **the expected cost of the CP schedule is just over double the cost of the critical chain's expected slip**, because any of three near-critical chains can become the binding one. A transaction that provisions for delay by looking at the critical path provisions for roughly half its exposure, and 149,891 is what that omission is worth here. The third is the reporting consequence: the distribution is **bimodal** — 34.1 % at 20 weeks, 54.5 % at 24 weeks, and almost nothing in between — because a slip, if it happens, is a discrete four- to six-week event rather than a smooth drift. The right output for a board is therefore not "expected close 22.4 weeks" but **"one chance in three of 20 weeks, and better than one chance in two of 24"**, which is a sentence people can plan against. The honest caveats are two: the slips are modelled as independent, and they are not — a slow grantor delays the permit chain and the consent inside the documentary chain together, which makes the true $E[\text{close}]$ later than 22.4075 and the probability of the base date lower than 34.125 %; and single-slip modelling understates the right tail, since a permit that slips six weeks can slip twelve. Both errors point the same way, which is the useful thing to know about them.

The close date is the expected maximum of the chains, not the expected duration of the critical one

Five chains, each individually likely to hold its date — and only a 34.125 % chance that the close holds its own

Expected slip 2.4075 wk = 298,851; chain C's own expected slip is 1.2 wk = 148,960. The conjunction premium is 149,891

Chain B carries the largest risk weight (2.10) and is not the critical path: de-risking it to p 0.10 is worth 76,031.67




Fig 13.3.1 — Kestrel's conditions-precedent conjunction

13.3.3 Float, criticality risk and where to spend

The chart above contains the management answer, and it is counter-intuitive. **Float is real and computable:** chain A has 11 weeks of it and a 3-week slip, so its slip is absorbed entirely and costs nothing; chain E has 13 weeks of float against a 2-week slip and likewise cannot delay close. Effort spent accelerating either returns zero, however loudly the sponsor's corporate secretariat is being chased.

Criticality risk, not criticality, ranks the work. Weighting each chain by **slip probability × slip size** gives **B 2.10, D 1.25, C 1.20, A 0.60** and **E 0.30** — and adjusting for float removes A and E entirely. The nominal critical path is chain C. The chain most likely to become critical is **B**, the permit and land chain, which sits two weeks inside the base date and carries the largest slip risk in the register.

WORKED EXAMPLE**Worked example 13.3.3 — what is it worth to de-risk a chain that is not critical?**

1. **Setup.** The sponsor can put a dedicated permitting team, local counsel and a pre-agreed submission protocol behind chain B, and estimates this reduces its slip probability from **0.35 to 0.10**. Nothing else changes. Cost of delay 124,133.33 per week.
2. **Formula.** Recompute $E[\text{close}]$ over the same outcome set with chain B's probability changed; the value of the intervention is the reduction in expected slip cost.
3. **Substitution.** $E[\text{close}]$ with $p_B = 0.10$, then $(E[\text{close}] - 20) \times 124,133.33$, compared with the base 298,851.
4. **Result.** $E[\text{close}]$ falls from **22.4075** to **21.7950 weeks**; expected slip cost falls from **298,851** to **USD 222,819.33**; the intervention is worth **USD 76,031.67**. The probability of closing on the base 20-week date rises from **34.125 %** to **47.250 %**, and the probability of the 24-week outcome falls from **54.500 %** to **37.000 %**.
5. **Interpretation.** The highest-value acceleration available on this transaction is on a chain that is **not** the critical path, and no critical-path analysis would have found it — which is the practical case for modelling the conjunction rather than the longest bar. Two further readings. The 76,031.67 is a **budget**, and it is the number the sponsor should compare a permitting adviser's fee against; below it the intervention pays, above it, it does not, and that is a far more useful procurement position than "permits are important". And the shift in the distribution is worth more to a board than the shift in the mean: moving the probability of the base date from roughly one in three to roughly one in two changes what can honestly be told to an offtaker, a contractor holding a price and an equity committee with a quarter-end. The caution is that reducing p_B to 0.10 is itself an estimate, and the honest way to present the result is as a sensitivity — if the intervention halves the risk it is worth about 38,000, if it removes two-thirds of it, about 76,000 — rather than as a single figure implying a precision the parameters do not support.

13.3.4 The close-cost budget and sources and uses

Close costs are the transaction's own price, and they are routinely provided for by a rule of thumb in the financial model — a percentage of the facility labelled "fees" — which is where the error enters. The discipline is a **line-itemised close-cost budget, reconciled to the sources-and-uses statement**, and it separates naturally into what is payable to lenders and what is not.

WORKED EXAMPLE**Worked example 13.3.4 — Kestrel's close-cost budget, and the hole it found.**

1. **Setup.** The diligence fees of KA 13.1 plus the financing, sponsor-side and perfection costs. Domain 6's funding envelope (KA 6.2.1) provided **840,000** for "arrangement and financing fees" at 2.0 % of the facility and **1,800,000** for capitalised development costs, both funded at close.
2. **Formula.** Total close costs = Σ line items. Share of debt raised = total $\div$ debt. Reconciliation = the envelope's provision – the itemised total.
3. **Substitution and result.**

Close-cost item	USD
Lenders' technical adviser	260,000
Lenders' legal counsel	420,000
Model auditor	180,000
Insurance adviser	60,000
Environmental and social consultant	240,000
Market adviser	190,000
Tax adviser	150,000
Diligence subtotal (KA 13.1)	1,500,000
Arrangement fee, 1.20 % of 42,000,000	504,000
Agency and account-bank set-up	40,000
Sponsor's legal counsel	380,000
Sponsor's financial adviser, success fee 0.45 %	189,000
Security perfection, registration and notarial costs	96,000
Total close costs	2,709,000

Total close costs are **6.45 % of debt raised** and **4.515 %** of the 60,000,000 envelope. Only **544,000** — the arrangement and agency fees — is payable to the lenders; **2,165,000** goes to third parties and the sponsor's own advisers. Against the envelope's provision of $840,000 + 1,800,000 = 2,640,000$, the budget is **69,000 short**: the fee line has **296,000 spare** (2.0 % of the facility against 544,000 of actual lender fees) while the development-cost line is **365,000 short** of the 2,165,000 it must carry.

4. Interpretation. Start with the number nobody expects: **6.45 % of debt raised**. That is not an error and it is not extravagance — it is what it costs to project-finance a 60,000,000 asset, and it is the strongest quantitative argument in this domain for why small projects are aggregated, standardised or financed on balance sheet instead. Split the total into a **fixed component** — the seven adviser fees, the sponsor's counsel, agency set-up and perfection, **2,016,000**, which barely varies with deal size — and a **proportional component** of **1.65 %** (the 1.20 % arrangement fee plus the 0.45 % success fee). Close cost as a share of debt is then $2,016,000 \div D + 1.65 \%$, which is **6.45 %** at 42,000,000, **2.994 %** at 150,000,000 and **2.130 %** at 420,000,000. A facility must reach about **USD 149,333,333** before total close costs fall below **3.0 %** of debt raised — an upper bound on the scale economy, since the fixed component does grow with complexity, but the shape is right and the implication is real. Second, the **reconciliation is the finding**. A 2.0 % "financing fees" line implicitly assumed transaction costs were the arranger's fee; they are 20 % of it. The 69,000 shortfall is small in itself and must be absorbed by the balancing contingency line, taking it from Domain 6's **3,645,403** to **3,576,403**, or from 7.59 % to **7.45 %** of the EPC price — still inside the band a lender would expect, so no financing consequence follows here. But the mechanism is the one that hurts on larger transactions, and there is a second-order effect the model must pick up: a cost moved from a spend-profile line to a close-funded line carries interest for the whole construction period rather than part of it, so the reallocation also adds capitalised interest, which the same balancing line must absorb. That is why a close-cost budget belongs **inside** the model rather than beside it. Third, the **effective cost of debt**. Netting the 544,000 of lender fees from proceeds against the unchanged instalment of 5,009,635.23 gives an all-in rate of **6.2386 %** on the facility; netting the whole 2,709,000 gives **7.2376 %** — **123.8 basis points** above the 6.00 % headline. Both figures are

correct and they answer different questions, which is exactly the discipline Domain 9 (KA 9.3.1) established for comparing tranches: **6.2386 % is the cost of the lender's money and 7.2376 % is the cost of raising it**, and only costs that differ between the routes being compared belong in a route comparison. Quoting the second as though the lender charged it is as misleading as quoting the headline 6.00 % as though closing were free.

13.3.5 Waivers, long-stop dates and post-close undertakings

Three instruments handle a condition that will not be satisfied in time, and all three are priced decisions rather than administrative fixes.

A **waiver** is the lenders' agreement to close without a condition, usually for a fee and often with a compensating term. Domain 5's rule stands — a waived CP is not a satisfied CP — and the professional requirement is that every waiver carries **a deadline, a named owner, evidence requirements and a stated consequence of non-satisfaction**. Case study B shows the same instrument used well and badly on one transaction.

A **long-stop date** (or availability-period expiry) is the date after which commitments lapse if close has not occurred. Its economic content is that it converts slippage into a **cliff**: up to the long-stop, delay costs the cost of delay; past it, the transaction needs re-approval, and re-approval prices at today's market rather than the market of the mandate. A leader should know the distance between [E\[close\]](#) and the long-stop in the same terms as the coverage headroom of Domain 10 — as a number of weeks, on the dashboard. Kestrel's [E\[close\]](#) of 22.4075 weeks against a 32-week long-stop leaves **9.5925 weeks** of margin, and the 24-week outcome that carries 54.5 % probability leaves 8.

A **post-close undertaking** converts a condition into a covenant: the obligation survives close with a deadline and, on breach, the consequences of Domain 10's covenant regime. This is the right answer for conditions that are genuinely mechanical and merely slow — a registration awaiting a registry, a final certificate awaiting an inspector — and the wrong answer for anything whose outcome is uncertain, because it converts a diligence question into a default risk.

AI in this KA

Where it earns its place. CP registers are long, repetitive and derived from documents, which makes three uses strong. **Extraction** of the condition list from the facility agreement's schedule into a register with clause references — the version-controlled starting point most transactions build by hand. **Dependency and duration tracking** — maintaining the register as evidence arrives, flagging conditions whose evidence is stale or whose owner has not reported, and recomputing the conjunction arithmetic of 13.3.2 whenever a duration estimate moves, which is the only way that arithmetic stays current inside a live close. And **evidence completeness checks** against each condition's stated documentary requirement.

Where it must not go. It must not determine that a condition is satisfied. Satisfaction is a determination the lenders make, on advice, against a documentary standard, and a machine's view that a condition "appears satisfied" has no standing and considerable capacity to mislead a transaction into a certificate it cannot support. It must not draft or sign the certificate of satisfaction. It must not decide whether a condition is waivable, or what a waiver should cost — that is a negotiation informed by counsel. And it must not generate the slip probabilities: [p](#) and the slip sizes come from an organisation's own closing record, and a plausible machine estimate would put a fabricated number at the centre of the close timetable.

Verification, concretely. The extracted register is reconciled clause by clause against the schedule by a named person before it is used, because a missing condition is invisible in a register that looks complete. Every satisfaction determination is recorded with the human who made it and the evidence

relied on. The conjunction arithmetic is recomputed and reviewed at each milestone, and the estimated slip parameters are recorded with their basis and their source transaction count — so that the register carries, in the open, how much evidence sits behind its own forecast.

■ KEY TERMS — KA 13.3

Term	Meaning
Condition precedent (CP)	Requirement satisfied and evidenced before an obligation arises, principally first drawdown.
CP chain	A dependency sequence of conditions; its duration is the sum of its links.
Conjunction premium	The excess of the expected close slip cost over the cost of the critical chain's own expected slip.
Float	Weeks by which a chain may over-run before it affects close; absorbs slip at no cost.
Criticality risk	$\text{slip probability} \times \text{slip size}$, net of float; ranks where acceleration is worth buying.
Close-cost budget	Line-itemised transaction cost, reconciled to sources and uses; fixed component plus a proportional fee rate.
Long-stop date	Date after which commitments lapse; converts slippage into re-approval at today's market.
Post-close undertaking	A condition converted into a dated covenant surviving close.

■ SAMPLE MCQS — KA 13.3

MCQ 13.3-A [13.3.2 · Analysis] Five CP chains have expected durations of 9.60, 20.10, 21.20, 18.25 and 7.30 weeks against a 20-week base close. The expected close date is:

- A. 21.2000 weeks — the longest chain's expected duration
- B. 22.4075 weeks — the expected maximum of the chains ✓ CORRECT
- C. 20.0000 weeks — the base close, since each chain is more likely than not to hold its date
- D. 76.4500 weeks — the sum of the chains

Rationale: Close is a conjunction, so the date is the expected maximum, which exceeds the maximum of the expectations (13.3.2). A takes the maximum of the expectations, the standard error; C mistakes each chain's individual likelihood for the joint one — the probability of the base date is 34.125 %; D adds chains that run in parallel.

MCQ 13.3-B [13.3.3 · Evaluation] Chain B (18 weeks, slip 6 weeks at probability 0.35) is not the critical path; chain C (20 weeks, slip 4 at 0.30) is. Reducing chain B's slip probability to 0.10 moves E[close] from 22.4075 to 21.7950 weeks at a cost of delay of 124,133.33 a week. The intervention is worth:

- A. nothing — chain B is not on the critical path
- B. USD 76,031.67, and it is the highest-value acceleration available ✓ CORRECT
- C. USD 744,800 — six weeks of delay avoided
- D. USD 298,851 — the whole expected slip cost

Rationale: $(22.4075 - 21.7950) \times 124,133.33 = 76,031.67$ (13.3.3). A is the critical-path fallacy the conjunction exists to correct; C prices the full slip as if it were certain and unavoidable; D is the total expected slip cost, which the intervention reduces but does not eliminate.

MCQ 13.3-C [13.3.4 · Application] Close costs total 2,709,000 on a 42,000,000 facility funding a 60,000,000 envelope, of which 544,000 is payable to lenders. Close costs as a share of debt raised are:

- A. 4.515 %
- B. 6.45 % ☒ **CORRECT**
- C. 1.295 %
- D. 2.00 %

Rationale: $2,709,000/42,000,000 = 6.45\%$. A divides by the 60,000,000 envelope rather than the debt; C counts only the fees payable to lenders; D is the model's original rule-of-thumb provision, which the itemised budget shows to be 20 % of the true figure.

MCQ 13.3-D [13.3.4 · Analysis] With a fixed close-cost component of 2,016,000 and a proportional component of 1.65 % of debt, the facility size at which total close costs fall to 3.0 % of debt raised is closest to:

- A. USD 67,200,000
- B. USD 149,333,333 ☒ **CORRECT**
- C. USD 122,181,818
- D. USD 90,300,000

Rationale: $2,016,000/(0.030 - 0.0165) = 2,016,000/0.0135 = 149,333,333$. A divides the fixed component by 3.0 % and ignores the proportional component; C divides by 0.0165; D applies 3.0 % to the wrong base.

MCQ 13.3-E [13.3.5 · Recall] A condition converted into a post-close undertaking is appropriately handled that way when:

- A. its outcome is uncertain and diligence could not resolve it
- B. it is mechanical and merely slow, so the only open question is timing ☒ **CORRECT**
- C. the sponsor does not wish to disclose it
- D. the lenders have waived it without a deadline

Rationale: Post-close undertakings convert timing risk into a dated covenant; they convert outcome risk into default risk, which is why A is the case for not closing rather than for an undertaking (13.3.5). D describes the defect Case study B prices.

MCQ 13.3-F [13.3.4 · Evaluation] Kestrel's headline rate is 6.00 %; netting the 544,000 of lender fees from proceeds gives an all-in **6.2386 %**, and netting the whole 2,709,000 close-cost budget gives **7.2376 %**. The sponsor is choosing between this bank facility and a bond alternative that would require substantially the same diligence, sponsor-side legal and perfection costs. Which rate belongs in that comparison?

- A. 6.00 %, because the other two include amounts that are not interest
- B. 6.2386 %, because only costs that differ between the routes discriminate between them, and the diligence and sponsor-side costs are common to both ☒ **CORRECT**
- C. 7.2376 %, because it is the full cost of raising the money and the more conservative figure to put to a board
- D. all three, because each is correct and answers a different question

Rationale: A route comparison is decided by the costs that differ, which is Domain 9's rule (KA 9.3.1) applied to close costs: the lender-payable 544,000 differs between a bank and a bond route, the 2,165,000 of adviser and perfection cost largely does not (13.3.4). C is defensible and commonly

seen, but conservatism is not a selection rule — loading both routes with the same 2,165,000 changes the level and not the ranking, while inviting the reader to treat a sunk common cost as a reason to prefer one lender over another. A is wrong because a fee paid to the lender for its money is part of the price of that money. D is true as a general statement and evades the question asked, which is a decision.

MCQ 13.3-G [13.3.2 · Evaluation] Kestrel's conjunction gives a base close of **20 weeks**, E[close] of **22.4075 weeks**, and a close-date distribution of **34.125 %** at 20 weeks, **11.375 %** at 22 and **54.500 %** at 24. The EPC contractor is holding a price and the grantor is sequencing its own approvals; both have asked for the close date. The soundest thing to tell them is:

- A. 20 weeks — the base date every chain owner is committed to, because publishing a later date is how a later date is achieved
- B. the distribution — roughly one chance in three of 20 weeks and better than one in two of 24 — because a single date is a forecast the transaction knows to be 34 % likely, the counterparties' own decisions turn on which outcome they should plan for, and the modelled independence of the chains makes even that distribution optimistic ✓ CORRECT
- C. 22.4075 weeks, the expected value, because it is the unbiased single figure and a single figure is what was asked for
- D. 24 weeks, the most likely single outcome, because under-promising protects the transaction and the parties relying on it

Rationale: The distribution is bimodal — **88.625 %** of the probability sits at 20 or 24 weeks and almost none near the mean — so C is arithmetically respectable and describes an outcome that will almost certainly not occur. A states as a plan a date known to be 34.125 % likely. D is defensible as a commitment and conceals a one-in-three chance of being four weeks early, which is exactly what a contractor holding a price and a grantor sequencing approvals need to know; it also presents as near certain a figure whose own basis — independent chains, one slip each — understates the right tail (13.3.2).

MCQ 13.3-H [13.3.1 · Comprehension] Which restatement best captures why a close timetable treats **third-party** conditions differently from **corporate and authority** conditions?

- A. third-party conditions are more numerous, so they consume more of the timetable
- B. the two groups differ in who controls satisfaction: corporate conditions sit inside the sponsor group and fail through inattention, so effort recovers them, whereas third-party conditions sit with permitting authorities, offtakers and grantors and can be influenced but not compressed at will ✓ CORRECT
- C. third-party conditions matter more to the lenders, so they are evidenced to a higher standard
- D. corporate conditions may be waived by the lenders whereas third-party conditions may not

Rationale: The five groups are distinguished by **how each fails**, and the corporate/third-party distinction is one of control rather than of importance or of evidentiary standard (13.3.1) — which is why third-party conditions are the standard source of close slippage, and why chain B, the permit and land chain, carries the largest slip risk in Kestrel's register. A may be true of a given transaction and is not the reason. C confuses a condition's ownership with its evidence requirement. D invents a rule: waiver is a lenders' decision available in principle to any condition, and a waived CP is not a satisfied CP whichever group it came from.

■ SELF-CHECK — KA 13.3

1. Why is the expected close date later than the longest chain's expected duration? — Close is a conjunction: the expected maximum exceeds the maximum of the expectations, here by 1.2075 weeks and 149,891.
2. How is acceleration effort ranked? — By criticality risk (slip probability $\times$ slip size) net of float, not by position on the critical path.
3. What two questions does the effective cost of debt answer differently? — What the lender's money costs (6.2386 % on lender fees alone) and what raising it costs (7.2376 % on the full close-cost budget).

KNOWLEDGE AREA 13.4

Syndication and financial close

Topics: 13.4.1 the three routes to a syndicate · 13.4.2 the fee architecture and the arranger's yield · 13.4.3 the failed sell-down · 13.4.4 market flex · 13.4.5 signing, close and funds flow.

13.4.1 The three routes to a syndicate

Definition. Syndication is the process by which the arranging bank or banks distribute a facility to other lenders, so that no single institution holds a position larger than its appetite or its limits allow. Three routes, distinguished entirely by **who carries the risk that the market does not turn up**:

- **Underwritten.** One or more banks commit the full amount and then sell down. The borrower has certainty of funds from the mandate; the arranger carries the distribution risk and charges for it (13.4.3 prices what that risk costs when it goes wrong).
- **Best-efforts.** The arranger undertakes to use reasonable efforts to raise the amount but does not commit it. Cheaper, and the borrower carries the risk that the book does not fill — which in a project financing means the risk that close does not happen at all, after the whole close-cost budget has been spent.
- **Club.** A small group of banks, assembled before documentation, each committing its final hold directly. No distribution risk, no underwriting fee, and — the point most often missed — no arranger with an economic interest in flexing terms, because nobody has a position to sell.

The choice is a trade between **certainty of funds**, **cost** and **flexibility**, and the sponsor's decision variable is usually the first. A transaction with a long-stop date, a contractor holding a price and a grantor's timetable cannot tolerate a book that does not fill, and will pay underwriting economics for certainty. A repeat sponsor with relationship banks and no hard deadline will club the deal and keep the fee. Kestrel's 42,000,000 sits at the size where either works, and this Knowledge Area follows it as an underwritten facility because that is the structure whose arithmetic must be understood.

13.4.2 The fee architecture and the arranger's yield

Fees in a syndicated facility are not one number. The standard architecture, and the reason for each part:

Fee	Paid to	Purpose
Praecipium (arrangement fee proper)	The arranger, exclusively	Structuring, documentation and underwriting risk; not shared with participants
Participation (pool) fee	Every lender pro rata on final allocations	Compensation for committing capital
Underwriting fee	The underwriter(s)	Explicit price of the commitment where separated from the praecipium
Commitment fee	Every lender, periodically	The undrawn balance's carrying cost (Domain 9, KA 9.2.4)
Agency fee	The facility and security agents	Ongoing administration; annual, not a close cost

WORKED EXAMPLE**Worked example 13.4.2 — who earns what on Kestrel's syndication.**

- Setup.** A total arrangement fee of **1.20 %** on 42,000,000, of which **0.25 %** is praecipium retained by the arranger and the balance is a participation pool paid pro rata on final allocations. The arranger's target final hold is **15,000,000**; two participants take **13,500,000** each.
- Formula.** Total fee = facility $\times$ 1.20 %. Praecipium = facility $\times$ 0.25 %. Pool = total – praecipium, paid at $\text{pool} \div \text{facility}$ on each lender's allocation. Fee yield = fee earned $\div$ final hold.
- Substitution.** $42,000,000 \times 1.20 \% = 504,000$; $\times 0.25 \% = 105,000$; pool 399,000, a rate of **0.95 %**. Arranger $105,000 + 0.95 \% \times 15,000,000$; each participant $0.95 \% \times 13,500,000$.
- Result.** Arranger **USD 247,500**, a fee yield of **1.650 %** on its 15,000,000 hold. Each participant **USD 128,250**, a yield of **0.950 %**. Total $247,500 + 2 \times 128,250 = 504,000$ ✓. The arranger earns **70.0 basis points** more per dollar held than the banks it sold to.
- Interpretation.** The 70 basis points is the price of two things participants do not do: structure and document the transaction, and stand behind the amount before anyone else has agreed to it. Reading it as a margin is the mistake — it is a **risk premium on distribution**, and 13.4.3 shows how quickly it is consumed. Three practical consequences for a sponsor. The fee split is **not the sponsor's business but it is the sponsor's information**: a praecipium that is a large share of the total tells you the arranger is being paid mostly for underwriting, which in turn tells you how it will behave if the book is slow — it will reach for flex. The **allocation policy is negotiable**, and a sponsor with a view on which lenders it wants in its syndicate for the next twelve years (Domain 10's waiver arithmetic: a tight syndicate consents in weeks) should express that view before the book opens, not when allocations are announced. And **fee yield, not fee, is how a lender sees the transaction**: a participant asked to take 13,500,000 at 0.950 % is comparing that yield against every other asset on its desk, which is why fees rise in a busy market even when margins do not move.

13.4.3 The failed sell-down

WORKED EXAMPLE

Worked example 13.4.3 — what an underwriter loses when the market does not turn up.

1. **Setup.** The arranger underwrites 42,000,000 with a target final hold of **15,000,000**, intending to place 27,000,000. The market takes only **20,000,000**. The arranger's internal charge for holding a project-loan position above its target hold is **90 basis points a year** over the facility's 12-year life. $AF(0.06, 12) = 8.383844$.
2. **Formula.** Residual hold = facility – amount placed. Excess = residual – target hold. Present value of the carry = excess × charge × $AF(r, n)$. Breakeven excess = the praecipium ÷ (charge × AF).
3. **Substitution.** Residual $42,000,000 - 20,000,000 = 22,000,000$; excess $22,000,000 - 15,000,000 = 7,000,000$; carry $7,000,000 \times 0.0090 \times 8.383844$.
4. **Result.** Excess hold **7,000,000**; present value of the carry **USD 528,182.17** against total fees earned of 247,500 — a **net loss of USD 280,682.17** on a transaction the arranger won, documented and closed successfully. The excess hold that exactly consumes the **praecipium** is **USD 1,391,565**, or **3.31 %** of the facility; the excess that consumes the arranger's **entire fee** is **USD 3,280,118**.
5. **Interpretation.** An underwriter can lose money on a deal that closes, and the loss threshold is startlingly low: a **3.31 % over-hold wipes out the whole underwriting premium**. That single figure explains most of the behaviour a sponsor encounters in a syndication and should be read as intelligence rather than as bad faith. It explains why arrangers insist on **market flex** (13.4.4) — flex is the instrument that lets them re-price to fill the book rather than carry the position. It explains why they **soft-sound the market before committing**, and why a sponsor who restricts pre-mandate sounding pays for that restriction in the underwriting fee. It explains why arrangers prefer **clubs in difficult markets**, where the economics of underwriting simply do not work. And it explains why an arranger's own hold level is worth watching: a bank that has just over-held on three transactions is a bank whose appetite for the fourth is about limits, not about the project. The professional caution for a sponsor is not to over-read the arithmetic — the 90 basis points is an internal capital charge, not a cash cost, and a bank may be entirely content to hold a good project-finance asset at scale. But when it is not, this is the arithmetic behind its position, and a sponsor negotiating flex without knowing it is negotiating blind against someone who does.

13.4.4 Market flex

Definition. Market flex is the arranger's contractual right, granted in the mandate or commitment letter, to change specified terms — most commonly to increase the margin or fees, and sometimes to shorten tenor, alter amortisation or reallocate between tranches — to the extent necessary to achieve a successful syndication. It is normally capped, sometimes ordered (fees before margin), and occasionally subject to a reverse flex that returns the benefit to the borrower if the book is oversubscribed.

WORKED EXAMPLE**Worked example 13.4.4 — what flex is worth, and what it costs.**

1. **Setup.** Kestrel's mandate grants flex of up to **50 basis points** on the margin. Facility 42,000,000, 12 years, base rate 6.00 %, $AF(0.06, 12) = 8.383844$, CFADS 6,384,000, DSCR covenant **1.20×**.
2. **Formula.** Present value of the flex, from the lenders' side, = facility $\times$ flex $\times AF(r, n)$. Its effect on the borrower = the new instalment $facility \div AF(r_flexed, n)$ and the resulting DSCR. The flex the covenant survives solves $CFADS \div 1.20 = facility \div AF(r^*, n)$ for r^* .
3. **Substitution.** PV of flex $42,000,000 \times 0.0050 \times 8.383844$. Flexed: $AF(0.065, 12) = 8.158725$; instalment $42,000,000 \div 8.158725$; DSCR = $6,384,000 \div$ that. Ceiling: $6,384,000 \div 1.20 = 5,320,000$; AF required $42,000,000 \div 5,320,000 = 7.894737$; solve for r^* .
4. **Result.** The 50 basis points of flex is worth **USD 1,760,607** in present value — **3.4933×** the entire 504,000 arrangement fee. Exercised in full, the instalment rises by **138,228** to **5,147,862.98** and the base-case DSCR falls from **1.2743** to **1.2401**. The 1.20× covenant survives up to a rate of **7.1138 %**, a flex ceiling of **111.4 basis points**, so the contractual 50 points consumes **44.9 %** of the available headroom.
5. **Interpretation. Flex is the most valuable term in the mandate letter, and it is almost never the term sponsors negotiate hardest.** At 3.49 times the arrangement fee, a sponsor who trades 10 basis points of flex for a 25 basis-point fee reduction has given away roughly 352,000 of present value to save 105,000 — and will describe the outcome as a fee win. The second reading is the covenant one, and it is the reason flex belongs in the financial model before the mandate is signed: **flex is a coverage event in disguise.** The fully-flexed DSCR of 1.2401 still clears the 1.20 covenant, so this transaction survives its own flex — but it does so with 44.9 % of its rate headroom consumed and nothing left for the interest-rate exposure Domain 11 (KA 11.3) priced separately, which is why the two must be stressed together rather than in sequence. The disciplined position a sponsor should hold: agree flex, **cap it at a level the model demonstrates the covenant survives with margin**, insist on ordering so fees flex before margin (a fee is a one-off, a margin is 8.38 years of annuity factor), require a **reverse flex** so that a strong book benefits the borrower, and require the arranger to evidence market conditions before exercising. What a sponsor must not do is treat flex as boilerplate, or model the base case only. And the honest note on the other side: an arranger without flex, facing the 13.4.3 arithmetic, will either not underwrite or will price the underwriting as though flex had already been exercised — so a sponsor who wins the flex negotiation outright may simply have moved the cost into the fee.

13.4.5 Signing, close and funds flow

The final mechanics, in the order they occur, and the specific way each is got wrong.

Signing is not close. Documents are executed; conditions may still be outstanding. The gap between the two is where the long-stop date lives, and a transaction that announces "financial close" on signing has misdescribed its own position — to its board, and sometimes to a market.

Satisfaction and certification. Each condition is evidenced to the agent, who confirms satisfaction against the documentary standard. The document to insist on is a **numbered certificate of satisfaction cross-referring to each condition and the evidence delivered**, because it is the record that determines, later, what was and was not satisfied. Waived and deferred conditions appear on it as such, never as satisfied (13.3.5).

The funds flow. A single statement showing every payment at close: sources by lender and by sponsor, uses by payee, net movements per account, and the day's timing. Kestrel's day-one requirement was **2,640,000** — fees and capitalised development costs, funded 70/30 as **1,848,000** of debt and **792,000** of equity (Domain 6, KA 6.2.1) — which is precisely the figure KA 13.3.4 showed must actually carry **2,709,000**. **The funds flow is where a close-cost budget error becomes visible, and it becomes visible on the day it is too late to fix.** The disciplines: reconcile the funds flow to the close-cost budget line by line before close, not on the day; confirm account signatories and payment instructions through a verified channel; and have the agent, not the sponsor's finance team, own the statement.

Equity first, or pro rata. Whether equity funds ahead of debt, alongside it or behind an equity-support instrument is a structuring decision with real consequences for the sponsor's exposure and the lenders' comfort (Domain 9, KA 9.1) — and whatever the answer, it must be the same in the documents, the model and the funds flow. **Conditions subsequent and the first drawdown.** Availability usually begins at close, but the first drawdown has its own conditions: the drawdown notice, the certification of spend, the confirmation that no default has occurred. Domain 14 takes the transaction from here.

AI in this KA

Where it earns its place. Three uses. **Term-sheet and commitment-letter normalisation** across several banks into one comparable table, which Domain 9 (KA 9.2) established and which extends naturally to flex provisions, fee structures and conditions — a genuinely tedious comparison that machines do well and humans do inconsistently. **Investor and allocation analysis:** which institutions have taken comparable paper in this sector, tenor and jurisdiction, assembled from disclosed transaction records, as a starting list for the book. And **funds-flow reconciliation:** matching a close-cost budget line by line to a funds-flow statement and reporting the differences, which is exactly the check that 13.4.5 says is done too late.

Where it must not go. It must not state market appetite or price as though it were a quote — an indicative margin generated from historical transactions is a research output, and presenting one to a sponsor as market feedback misrepresents to whoever relies on it. It must not draft or approve the certificate of satisfaction, the funds flow or any payment instruction: close-day payment instructions are the single highest-value fraud target in a project financing, and no automated channel should originate or alter one. And it must not be used to decide allocations, which are a relationship judgment with consequences over the facility's whole life.

Verification, concretely. Every normalised term-sheet field is checked against the source letter by a named person before the comparison is used, because a mis-normalised flex cap is worth 1,760,607 here. Payment instructions are verified out of band, by voice, against a previously-confirmed record — an operational control that no model output substitutes for. And the funds-flow reconciliation is signed by the agent and the sponsor's finance director, whatever produced the first draft.

■ KEY TERMS — KA 13.4

Term	Meaning
Underwritten / best-efforts / club	Arranger commits and sells down · uses reasonable efforts only · pre-assembled group each taking its final hold.
Praecipium	The arranger's exclusive share of the arrangement fee; the price of structuring and underwriting.
Participation (pool) fee	Fee paid pro rata on final allocations to every lender.
Final hold	The position a lender intends to retain after syndication.
Market flex	Contractual right to change specified terms to achieve syndication; capped, often ordered, sometimes reversible.
Signing vs financial close	Execution of documents vs satisfaction of all conditions and availability of funds.
Certificate of satisfaction	Numbered record of each condition, its evidence and its disposition, including waivers.
Funds flow	The statement of every payment at close, reconciled to the close-cost budget.

■ SAMPLE MCQS — KA 13.4

MCQ 13.4-A [13.4.2 · Application] A 42,000,000 facility carries a 1.20 % arrangement fee, of which 0.25 % is praecipium; the balance is a pool paid pro rata on allocations. The arranger's final hold is 15,000,000. It earns:

- A. USD 180,000
- B. USD 247,500 ✓ CORRECT
- C. USD 105,000
- D. USD 504,000

Rationale: $105,000 + 0.95 \% \times 15,000,000 = 247,500$, a yield of 1.650 % against participants' 0.950 %. A applies the full 1.20 % to the hold and omits the praecipium's exclusivity; C is the praecipium alone; D is the whole fee, most of which is paid away to participants.

MCQ 13.4-B [13.4.3 · Evaluation] An arranger underwrites 42,000,000 with a 15,000,000 target hold, places 20,000,000, and charges itself 90 basis points a year on the excess over 12 years ($AF = 8.383844$). Against fees of 247,500 the outcome is:

- A. a profit of 184,500
- B. a loss of USD 280,682.17 — the 528,182.17 carry on a 7,000,000 excess exceeds the whole fee ✓ CORRECT
- C. a loss of 508,500, since the entire residual hold is charged
- D. break-even

Rationale: $7,000,000 \times 0.0090 \times 8.383844 = 528,182.17$; $247,500 - 528,182.17 = -280,682.17$ (13.4.3). A charges the carry for one year only (63,000); C charges the full 22,000,000 residual rather than the excess over target hold.

MCQ 13.4-C [13.4.4 · Application] Fifty basis points of market flex on a 42,000,000 facility over 12 years at 6 % ($AF = 8.383844$) is worth, in present value:

- A. USD 210,000
- B. USD 1,760,607 ✓ CORRECT

- C. USD 2,520,000
- D. USD 504,000

Rationale: $42,000,000 \times 0.0050 \times 8.383844 = 1,760,607$, some 3.49 times the arrangement fee. A is one year of the flex, undiscounted; C sums twelve years without discounting; D is the arrangement fee the sponsor negotiates instead.

MCQ 13.4-D [13.4.4 · Analysis] With CFADS of 6,384,000, a 42,000,000 facility over 12 years and a 1.20× DSCR covenant, the margin increase the covenant just survives is:

- A. 50.0 basis points
- B. 111.4 basis points ✓ CORRECT
- C. 25.0 basis points
- D. unlimited, since the covenant is tested on CFADS

Rationale: Maximum instalment $6,384,000/1.20 = 5,320,000$, requiring $AF = 7.894737$, which solves at 7.1138 % — 111.4 basis points above 6.00 %. A is the contractual flex cap, which consumes 44.9 % of that headroom; D forgets that debt service is the denominator and rises with the rate.

MCQ 13.4-E [13.4.5 · Recall] A transaction has executed all its documents but two third-party consents remain outstanding. Its correct description is:

- A. financially closed
- B. signed, not closed — close occurs when every condition is satisfied and funds are available ✓ CORRECT
- C. closed subject to conditions subsequent
- D. in default

Rationale: Signing and close are distinct, and the gap is where the long-stop date operates (13.4.5). C misuses a term for post-close obligations; D confuses an unsatisfied condition with a breach of an existing obligation.

MCQ 13.4-F [13.4.4 · Evaluation] The arranger offers to cut the arrangement fee from 1.20 % to 0.95 % of the 42,000,000 facility — a certain saving of 105,000 — in exchange for lifting the market-flex cap from 50 to 60 basis points. Twelve years, $AF(0.06, 12) = 8.383844$; the 1.20× covenant survives a rate rise of 111.38 basis points. The recommendation is:

- A. accept — 105,000 is certain, and flex may never be exercised at all
- B. reject — the extra ten basis points of flex is worth 352,121.45 in present value, 3.3535 times the fee saved, and it takes the cap from 44.89 % to 53.87 % of the covenant headroom ✓ CORRECT
- C. reject — flex should not be granted at all, since it prices the sponsor's protection away
- D. accept, provided the fee reduction is credited in cash at close rather than netted from proceeds

Rationale: $42,000,000 \times 0.0010 \times 8.383844 = 352,121.45$ against 105,000, so the trade would have to be exercised with probability below $105,000 \div 352,121.45 = 29.82\%$ to break even — and 13.4.3 shows the arranger exercises precisely when the book is slow, which is the state in which the sponsor can least afford the coverage loss (13.4.4). A is the defensible version of the argument and is the one sponsors actually make; it fails because it prices a contingent claim at zero and ignores the 111.38 basis points of headroom being consumed. C is not available — an arranger without flex will either decline to underwrite or price the underwriting as if flex were already exercised. D negotiates the mechanics of the wrong side of the trade.

MCQ 13.4-G [13.4.1 · Evaluation] Kestrel has a long-stop date, an EPC contractor holding a price and a grantor's fixed timetable. An arranger offers a **best-efforts** mandate at a materially lower fee than the underwritten alternative, observing that books for contracted water projects of this size rarely fail to fill. The itemised close-cost budget is **2,709,000** — **6.45 %** of debt raised — of which only **544,000** is payable to lenders. The soundest recommendation is to:

- A. accept best-efforts, because the fee saving is certain while the risk it transfers has a low probability
- B. reject best-efforts here: what it transfers to the borrower is the risk that close does not happen at all after the whole 2,709,000 has been spent, of which **2,165,000** is irrecoverable third-party and sponsor-side cost, and certainty of funds against a fixed timetable is what underwriting economics buy ✓ CORRECT
- C. accept best-efforts and manage the exposure by bringing the long-stop date forward
- D. club the facility instead, since a club carries no distribution risk and no underwriting fee, and no arranger then has an economic interest in flexing terms

Rationale: The three routes differ in **who carries the risk that the market does not turn up**, and a transaction with a hard timetable is buying certainty (13.4.1). A prices a contingent claim at its probability and ignores its size: the budget at risk is **5.375 times** the 504,000 arrangement fee, and it is spent before the book is known to fill. C tightens the very constraint the sponsor is trying to satisfy. D is the genuine alternative and the right answer for a repeat sponsor with relationship banks and no hard date; it fails here because a club must be assembled before documentation and each bank commits only its own final hold, so it does not deliver certainty of funds against a fixed date — and the flex point, though correct, is a benefit the sponsor cannot collect if the group does not assemble in time.

MCQ 13.4-H [13.4.2 · Comprehension] In a syndicated facility the **praecipium** is retained exclusively by the arranger while the **participation fee** is paid pro rata on final allocations. Which statement best explains the difference?

- A. the split is a market convention with no economic content, which is why it is not disclosed to borrowers
- B. the two fees pay for different things: the praecipium prices structuring, documentation and standing behind the whole amount before any other lender had agreed to lend, while the pool prices the capital each lender ultimately commits ✓ CORRECT
- C. the praecipium compensates the arranger for the margin it forgoes by selling part of its position down
- D. the praecipium is the arranger's own pro-rata share of the pool, computed on its final hold

Rationale: The praecipium prices work and risk only the arranger bears; the pool prices committed capital, which every lender provides — which is why the arranger's yield on its 15,000,000 hold is **1.650 %** against participants' **0.950 %**, a differential of **70.0 basis points** (13.4.2). A denies the economics and misstates practice: the total fee is disclosed, and the split is information a sponsor should ask for, because a large praecipium signals an arranger paid mostly for underwriting and therefore one that will reach for flex. C describes something that does not happen — a lender selling down transfers the margin with the position. D is the pool fee itself, which the arranger receives **in addition** to the praecipium.

■ SELF-CHECK — KA 13.4

1. What does the arranger's 70 basis-point yield differential pay for? — Structuring, documentation and distribution risk — the risk 13.4.3 shows a 3.31 % over-hold consumes entirely.

2. Why is flex worth more than the arrangement fee? — A margin is an annuity over the facility's life: 50 basis points is 1,760,607 of present value against a 504,000 one-off fee.
3. What is the one thing a funds flow must be reconciled to, and when? — The line-itemised close-cost budget, before close — not on the day, when the 2,640,000 provision meets a 2,709,000 requirement.

— Advanced topics — Domain 13

13.A.1 Reliance, duty of care and the arithmetic of a liability cap

A diligence report is only useful to a party that can rely on it, and reliance is a legal arrangement rather than a natural consequence of reading. Three mechanisms carry it. **Addressing** — a report addressed to the sponsor gives lenders nothing; the standard remedy is a report addressed to the lenders and the agent, or a **reliance letter** extending a duty of care to named additional parties, usually for a fee and usually on the original engagement's terms. **Assignment and transferability**, which matters for syndication: a report on which only the original syndicate may rely constrains sell-down, and a secondary purchaser two years later needs a re-addressed report or its own. And **the liability cap**, which is where the arithmetic bites.

Advisers' engagement terms almost universally cap liability, commonly at a multiple of fees. Take Kestrel's technical stream: a fee of **260,000** and a cap at **three times fees** gives **780,000** against a **C** of **6,200,000** — the cap covers **12.58 %** of the exposure the stream exists to address. Across all seven streams, caps of three times fees total **4,500,000** against an aggregate expected exposure of **9,439,874.85**, or **47.67 %** — and that comparison flatters the position, because it sets the sum of maximum recoveries against the sum of expected losses, and because recovery requires proving negligence, not merely showing the finding was missed.

The conclusion is the one 13.1.1 stated and this arithmetic proves: **diligence buys information, not indemnity**. Two professional consequences follow. Negotiating a cap upwards is worth doing and is not a risk-transfer strategy — moving Kestrel's technical cap from three to five times fees adds 520,000 of theoretical recovery against a 6,200,000 exposure. And **the reliance package is a diligence deliverable in its own right**, to be listed on the CP schedule with the reports themselves; a transaction that discovers at syndication that its reports cannot be re-addressed has found a condition it cannot satisfy.

13.A.2 Vendor diligence, reliance and the price of time

A **vendor due diligence** report is commissioned by a seller and made available to bidders, typically with reliance extended for a fee. It is the standard mechanism in secondary infrastructure sales and increasingly in primary financings where a sponsor pre-packages diligence to compress a lender's timetable. The question it poses is exact: is it better to rely on someone else's diligence quickly, or to run your own slowly?

WORKED EXAMPLE**Worked example 13.A.2 — own diligence or reliance?**

1. **Setup.** A buyer faces an aggregate probability $p = 0.65$ that at least one material issue exists, with $C = 9,000,000$ if it reaches completion undetected and $F = 600,000$ to resolve it beforehand. **Own diligence:** 1,500,000 of fees, **12 weeks**, detection $d = 0.90$. **Reliance on vendor diligence:** a 240,000 reliance fee, **3 weeks** of confirmatory work, detection $d = 0.50$ — lower because the scope was the seller's, the questions were the seller's and the report's cap is shared across every relying party.
2. **Formula.** Expected cost = fee + weeks $\times$ cost of delay + $p \times [d \times F + (1 - d) \times C]$. The breakeven cost of delay is the weekly figure at which the two routes cost the same.
3. **Substitution.** Own residual $0.65 \times (0.90 \times 600,000 + 0.10 \times 9,000,000) = 936,000$; reliance residual $0.65 \times (0.50 \times 600,000 + 0.50 \times 9,000,000) = 3,120,000$. Breakeven cost of delay $[(1,500,000 + 936,000) - (240,000 + 3,120,000)] \div (3 - 12)$.
4. **Result.** At **zero** cost of delay, own diligence is better by **USD 924,000**: the 1,260,000 of fees saved does not cover the 2,184,000 of detection lost. The **breakeven cost of delay is USD 102,666.67 per week**. At Kestrel's actual **124,133.33**, reliance wins: total expected cost **3,732,400** against **3,925,600**, an advantage of **USD 193,200**.
5. **Interpretation.** The decision has no general answer and one general rule: **it is decided by the price of time, and the breakeven is computable**. An organisation that always runs its own diligence is implicitly asserting a low cost of delay; one that always relies is asserting a high one; neither has done the arithmetic. Three cautions, all about the parameters rather than the sums. The **0.50 detection rate is the weakest number here** and it is doing most of the work — it should be estimated from the vendor report's actual scope against the buyer's own question list, not assumed. The reliance route's **liability position is systematically worse** (13.A.1): a cap shared among relying parties may be worth a fraction of its face amount, which the expected-value arithmetic does not see at all. And in a **competitive process** the cost of delay is not 124,133.33 a week but the entire value of the opportunity, in which case reliance wins by a margin no amount of detection can overturn — which is why vendor diligence exists, and why a seller's decision to commission it is a decision about the sale price.

13.A.3 The reviewer's closing eye

Invariants to test on any diligence and close package. **Every diligence stream has a stated p , d , C and F with a recorded basis**, and its breakeven detection rate is on the page (13.1.3). **The envelope is drawn and the binding stream identified**, with the elapsed cost priced once, not per stream — and any serial dependency justified in writing at 124,133.33 a week (13.1.4). **Every assumption touched by more than one adviser has one named owner and one version** (13.1.2). **The model audit's findings are classified before they are counted**, with a stated materiality threshold in the transaction's own metric, and no progress metric is quoted that is not class-weighted (13.2.2). **Every Class 1 finding is quantified in DSCR and debt-capacity terms**, and its correction is followed through into the credit paper, the term sheet and the base case (13.2.3, 13.2.4). **The CP register is a dependency network, not a list**, with a duration, an owner, an evidence requirement and a verifier per condition; float is computed per chain; and the close date is stated as the expected maximum with its distribution, not as a single date (13.3.2). **Acceleration effort is ranked by criticality risk net of float**, and the value of de-risking the highest-weighted chain is computed before any fee is paid for it (13.3.3). **The close-cost budget is line-itemised, split into fixed and proportional components, expressed as a share of debt raised, and**

reconciled to sources and uses and to the funds flow — before close (13.3.4, 13.4.5). **The effective cost of debt is quoted twice**, on lender fees and on total close costs, with the question each answers stated (13.3.4). **Every waived or deferred condition carries a deadline, an owner, an evidence requirement and a consequence**, and appears as waived on the certificate of satisfaction (13.3.5). **Market flex is capped at a level the model demonstrates the coverage covenant survives with margin**, stressed jointly with interest-rate exposure, and its present value is stated beside the arrangement fee (13.4.4). **Reliance and transferability are on the CP schedule**, and every liability cap is expressed as a percentage of the exposure it addresses (13.A.1). And **every AI-assisted extraction has a measured error rate on this transaction's own documents**, with the sample size stated and a named human verifier (13.1, 13.2, 13.3, 13.4).

— Industry variations — Domain 13

- **Contracted power and renewables.** Diligence is standardised and comparatively fast: technology is proven, the offtake is a known form, and the binding stream is usually grid connection and land consents rather than technical review. Model audits are routine, findings are typically Class 2 and below, and the close timetable is dominated by permit chains — so the conjunction arithmetic of 13.3.2 matters more than the stream economics of 13.1.3.
 - **Merchant power, commodities and industrial.** Market diligence dominates and cannot be compressed: the report is about a method for forecasting prices, so the diligence question is the consultant's methodology and the stress cases it supports rather than its central case. Syndication is harder, flex is wider, and lenders size on stressed cases, which makes the fully-flexed coverage test of 13.4.4 the binding constraint at mandate stage.
 - **Transport concessions.** Traffic and revenue diligence is the single largest stream and often the longest, so it sets the envelope; grantor-side conditions add a chain nobody in the sponsor group controls; and the documentary chain lengthens because concession, direct agreement and finance documents must be negotiated three-cornered. Expect a lower probability of the base close date than 34 % and provision accordingly.
 - **Water and regulated utilities.** Environmental and social diligence is frequently the binding stream — abstraction, discharge, biodiversity and community consents — as it is for Kestrel, and regulatory reset cycles put a tariff-determination date into the CP schedule that no amount of effort moves. Legacy contamination on brownfield sites is the characteristic Class 1 E&S finding.
 - **Digital infrastructure.** Diligence is tenant-credit and power-availability work as much as technical work; asset lives are short so lifecycle and technology-obsolescence assumptions carry unusual weight; and close timetables are compressed by tenant commitment dates, which raises the cost of delay and therefore favours reliance and vendor diligence (13.A.2). Case study B is drawn from this sector.
 - **Social infrastructure and availability PPPs.** Documentation is closest to standardised, which compresses the documentary chain and shifts the binding constraint onto public-sector approval chains with fixed committee calendars — the governance-latency arithmetic of PML-AI (KA 3.3) applied to a close timetable. Diligence fees as a share of a small facility are the highest of any sector, making the scale arithmetic of 13.3.4 decisive: these are the transactions that are aggregated or standardised or do not get financed.
-

— Case study — Domain 13: the audit that resized the debt (water / desalination)

Situation. Kestrel Water SPC entered diligence with a mandate for 42,000,000 of senior debt at 6.0 % over 12 years against a 60,000,000 envelope, a reported base-case **DSCR** of **1.3508** and a credit committee requiring **1.30×**. Seven diligence streams were commissioned for 1,500,000 of fees. The sponsor's first close plan sequenced them, on the arranger's preference that each stream should be able to rely on the last.

What happened. The sequencing decision was challenged with the 13.1.3 arithmetic: the same seven streams, the same fees and the same detection rates were worth **+4,066,699.88** inside a twelve-week envelope and **−1,146,900.12** run serially, the 5,213,600 difference being 42 weeks at 124,133.33. Two dependencies were real — the model audit needed a frozen model and the insurance adviser needed the technical loss scenarios — and both were accommodated inside the envelope with staged deliverables. The envelope was set at twelve weeks by the environmental and social stream and the close date at 20 weeks, and the conjunction arithmetic put the probability of holding it at **34.125 %**, with an expected close of **22.4075 weeks** and an expected slip cost of **298,851** against chain C's own **148,960**. The sponsor funded a dedicated permitting effort on chain B — which was not the critical path — reducing its slip probability from 0.35 to 0.10, worth **76,031.67** and lifting the probability of the base date to **47.250 %**.

The model audit returned **34 findings: 3 Class 1, 7 Class 2, 24 Class 3**. Two of the three fundamental findings compounded. The debt-service schedule had been built as an **annuity due**, understating the instalment by **283,564** and flattering the **DSCR** from 1.2743 to the reported 1.3508 — a model that was arithmetically correct, closed at zero, and did not implement the facility. The **CFADS** definition placed the **260,000** maintenance-reserve top-up above **CFADS**; the model placed it below, so true **CFADS** was **6,124,000** and the true **DSCR** **1.2224**. Debt capacity at the committee's **1.30×** was therefore $6,124,000 \div 1.30 \times 8.383844 = 39,494,354$, against Domain 10's 41,171,123 on the uncorrected figure and the 42,000,000 mandated — a resize of **2,505,646**. The third finding was worse in kind if not in size: the six-month DSRA of **2,504,818** appeared as an operating outflow but not in the uses of funds, so the funding plan did not fund a mandatory reserve.

Separately, the itemised close-cost budget came to **2,709,000** — **6.45 %** of debt raised, of which only **544,000** was payable to lenders — against the model's provision of 2,640,000, a **69,000** shortfall absorbed by the contingency line (3,645,403 to **3,576,403**, 7.59 % to **7.45 %** of the EPC price).

How it resolved. The facility closed at **USD 39,494,354** of senior debt — an instalment of **4,710,769.23** and a base-case **DSCR** of exactly **1.3000** on corrected **CFADS** — with equity rising from 18,000,000 to **20,505,646**, gearing moving from 70/30 to **65.82/34.18** and debt-to-equity from 2.33:1 to **1.926:1**. The DSRA was funded from equity at commercial operations rather than from the construction envelope. Close costs fell by **41,343** on the smaller proportional base, to **2,667,657** — which, on the smaller facility, is **6.7545 %** of debt raised against the original 6.4500 %, because the fixed 2,016,000 does not shrink when the debt does. The base case was re-run and the golden-answer set re-verified before the credit paper was finalised.

What the domain teaches here. Three things, in order of how often they are got wrong. **The expensive model error is a document error, not an arithmetic error** — an annuity due is a valid amortisation and would have passed every check block, every scanner and every reasonable review that did not read the facility. **Diligence value is destroyed by sequencing, not by fees** — the 5,213,600 that separated the two close plans was more than three times the entire diligence budget and would never have appeared in a fee negotiation. And **the numbers that matter are the ones that change a conclusion**: three of thirty-four findings resized the debt by 2,505,646 and exposed

an unfunded 2,504,818, while the other thirty-one, closed and reported as 91.2 % progress, changed nothing at all.

— Case study B — Domain 13: the same waiver, used well and badly (digital infrastructure)

Situation. A 180,000,000 facility for a colocation data centre reached its long-stop date with two conditions unsatisfied. **CP-14** was the registration of a land instrument, complete in substance and awaiting a registry whose published processing time was 210 days. **CP-22** was a third-party interface consent from the operator of an adjacent utility corridor, which had been requested, acknowledged and not progressed. The anchor tenant's commitment expired in eleven weeks and the sponsor's cost of a day's delay to close, in forgone contracted revenue against a fixed lease term, was **240,000**.

What happened. Both conditions were waived into post-close undertakings at the same meeting, on the same paper, for the same fee. **CP-14 was waived well.** It carried a 90-day deadline, a named owner in the sponsor's legal team, a documentary standard (the registered instrument, certified), and a consequence: a **25 basis-point margin step-up** until satisfaction. Registration in fact took the registry's full 210 days, so the undertaking ran **120 days late**. The cost was the waiver fee of **0.25 % of 180,000,000 = 450,000** plus the step-up of $180,000,000 \times 0.0025 \times 120/360 = 150,000$, a total of **600,000**. The counterfactual — waiting to close until registration completed — was **210 days × 240,000 = 50,400,000**. **The waiver was worth 49,800,000**, and it was the correct decision by a margin of eighty-three to one.

CP-22 was waived badly. Because it was mechanical in the sponsor's view and small in the lenders', it was recorded as waived with no deadline, no consequence and no owner — a single line in the certificate of satisfaction reading "waived". It fell out of every register within a month. Twenty-six months later, on a refinancing, the incoming lenders' legal diligence found the corridor consent outstanding and treated it as a title and access defect. Curing it — a negotiated easement, a survey, and a payment to the corridor operator now negotiating with a counterparty that had no alternative — cost **3,400,000**, **5.667 times** the entire cost of the CP-14 waiver, and delayed the refinancing by a quarter.

How it resolved. The sponsor's post-mortem changed one artefact rather than one policy: the certificate of satisfaction was rebuilt so that no condition could be marked waived without a deadline, an owner, an evidence standard and a consequence, and the waived-condition register became a standing item on the same monthly report as the covenant dashboard (Domain 10, Toolkit 10.T.2) — so that a waived condition was reported in the same place as a covenant until it was satisfied.

What the domain teaches here. The instrument was not the problem. **A waiver is a priced decision and here it was overwhelmingly right** — 600,000 against 50,400,000 — and a project finance leader who refuses to waive on principle will destroy far more value than one who waives carelessly. What distinguished the two conditions was entirely the **discipline attached to the waiver**: deadline, owner, evidence standard, consequence. Domain 5's rule that a waived CP is not a satisfied CP is not an accounting nicety; it is the difference between 600,000 and 4,000,000, and the interval over which the difference emerges is two years, which is why nobody is present to learn the lesson at the time.

— Executive perspective — Domain 13

What a project finance director cannot delegate in this domain:

- **The sequencing decision.** Whether diligence runs in parallel or in series is worth **5,213,600** on Kestrel — three and a half times the entire diligence budget — and it will be decided by advisers' scheduling preferences unless the director decides it. Own the envelope, name the binding stream, and require every serial dependency to be justified at 124,133.33 a week.
- **The CFADS definition and the model's conformance to it.** Domain 10 made this a standing obligation; here it acquires a price. Two document-conformance findings moved Kestrel's reported **DSCR** from 1.3508 to a true 1.2224 and its debt capacity by 2,505,646, and neither was an arithmetic error. Read the definition, then read the model line that implements it.
- **The finding classification, before any count is reported.** The director's question on receiving a model audit is never "how many findings?" but "which findings change a conclusion, and by how much?" A 91.2 % closure metric with three Class 1 findings open is a report that must be sent back.
- **The close date as a distribution.** One chance in three of the stated date, and better than one in two of four weeks later, is what a board, an offtaker and a contractor holding a price need to be told. A single-date close timetable is a forecast the director knows to be 34 % likely and has chosen to present as a plan.
- **The close-cost budget and the funds flow, reconciled before close.** 6.45 % of debt raised is the real number, only 20 % of it is the lender's, and a 69,000 hole between a rule-of-thumb provision and an itemised budget becomes visible on the day it cannot be fixed.
- **The flex cap, tested against the covenant.** Fifty basis points of flex is worth 1,760,607 — 3.49 times the arrangement fee the director's team is negotiating — and consumes 44.9 % of the rate headroom the coverage covenant allows. Flex is signed at mandate stage, months before anyone models it; the director is the only person who can insist that the order be reversed.

— Calculation exercises — Domain 13

Exercise 13.1 A diligence stream costs a **320,000** fee and takes **7 weeks**. The probability of a material issue in its class is **0.25**, the cost if it reaches close is **7,400,000** and pre-close correction costs **380,000**. The cost of delay is **96,000 per week** and detection is estimated at **0.75**. Compute the breakeven detection rate inside a parallel envelope and on the critical path, and the net value in each case. Solution. Expected avoidable loss $0.25 \times (7,400,000 - 380,000) = 1,755,000$. Inside the envelope $d^* = 320,000/1,755,000 = 18.23\%$; on the critical path the priced delay is $7 \times 96,000 = 672,000$, so $d^* = 992,000/1,755,000 = 56.52\%$. Net value: without the stream $0.25 \times 7,400,000 = 1,850,000$; with it inside the envelope $320,000 + 0.25 \times (0.75 \times 380,000 + 0.25 \times 7,400,000) = 320,000 + 533,750 = 853,750$, so net value **+996,250**; on the critical path add the 672,000, giving net value **+324,250**. Common error: computing d^* as $\text{fee} \div (p \times C) = 17.30\%$, which ignores that a detected issue still costs **F** to fix and so overstates the loss the stream can avoid.

Exercise 13.2 Three CP chains: **A** 16 weeks, slip 4 weeks at probability 0.30; **B** 14 weeks, slip 5 at 0.40; **C** 11 weeks, slip 6 at 0.25. Cost of delay **80,000 per week**. Compute the base close, the

expected close, the probability of the base date, and the conjunction premium. Solution. Base close **16 weeks** (chain A). Realised durations: A 16 or 20, B 14 or 19, C 11 or

1. Over the eight outcomes: $E[\text{close}] = 18.1450$ weeks, with probabilities **31.50 %** at 16, **10.50 %** at 17, **28.00 %** at 19 and **30.00 %** at 20. Expected slip **2.1450 weeks**, costing **171,600**. Chain A's own expected slip is $0.30 \times 4 = 1.2$ weeks, costing **96,000**, so the conjunction premium is **75,600**. Note that the max of expectations is **17.200** weeks, well inside the expected maximum. Common error: taking the longest chain's expected duration (17.200 weeks) as the expected close, which understates the slip by 0.945 weeks and the cost by 75,600 — precisely the premium the conjunction creates.

Exercise 13.3 A transaction's close costs comprise a fixed component of **1,650,000** and a proportional component of **1.85 %** of debt raised. Debt is **55,000,000**. Compute total close costs and their share of debt, and the facility size at which they would fall to 2.5 % of debt. Solution. Total $1,650,000 + 0.0185 \times 55,000,000 = 1,650,000 + 1,017,500 = 2,667,500$, which is **4.850 %** of debt raised. Setting $1,650,000/D + 0.0185 = 0.025$ gives $D = 1,650,000/0.0065 = \text{USD } 253,846,153.85$. Common error: solving $1,650,000/D = 0.025$ and reporting 66,000,000, which forgets that the proportional component consumes 1.85 of the 2.5 percentage points before the fixed component is spread at all.

Exercise 13.4 A model audit on a **36,000,000** facility at **6.5 %** over **14 years** finds that a **320,000** annual line included in **CFADS** is excluded by the facility's definition. Reported **CFADS** is **5,600,000**; the covenant is **1.25×**. Compute the reported and corrected **DSCR**, the debt capacity at 1.25× on corrected **CFADS**, and classify the finding. Solution. $AF(0.065, 14) = 9.013842$; instalment $36,000,000/9.013842 = 3,993,857.30$. Reported **DSCR** $5,600,000/3,993,857.30 = 1.4022$; corrected **CFADS** **5,280,000** gives **1.3220**. Debt capacity $5,280,000/1.25 \times 9.013842 = 38,074,470.00$, which **exceeds** the 36,000,000 drawn by **2,074,470**. The finding therefore moves a reported output well beyond any sensible materiality threshold but changes **no conclusion**: the covenant still holds and the debt is still supportable. It is a **Class 2** finding, not Class 1. Common error: classifying by the size of the movement (0.08 of **DSCR**, 320,000 of **CFADS**) rather than by whether a conclusion changes — the distinction on which KA 13.2.2 rests.

Exercise 13.5 A **96,000,000** facility carries a **1.35 %** arrangement fee of which **0.30 %** is praecipium; the balance is a pool paid pro rata on final allocations. The arranger's target hold is **30,000,000** and three participants take **22,000,000** each. Compute the fee split and yields. Then: the market takes only **54,000,000** and the arranger charges itself **85 basis points** a year on the excess over target hold for the facility's **14 years** at 6.5 % ($AF = 9.013842$). Compute the outcome. Solution. Total fee $96,000,000 \times 1.35 \% = 1,296,000$; praecipium **288,000**; pool **1,008,000**, a rate of **1.0500 %**. Arranger $288,000 + 1.05 \% \times 30,000,000 = 603,000$, a yield of **2.010 %**; each participant **231,000**, a yield of **1.050 %**; total $603,000 + 3 \times 231,000 = 1,296,000$ ✓. On the failed sell-down the arranger holds $96,000,000 - 54,000,000 = 42,000,000$, an excess of **12,000,000**; the carry is $12,000,000 \times 0.0085 \times 9.013842 = 919,411.92$, against fees of 603,000 — a **net loss of 316,411.92**. The excess hold that exactly consumes the praecipium is $288,000/(0.0085 \times 9.013842) = 3,758,924.52$, **3.92 %** of the facility. Common error: charging the carry on the whole 42,000,000 residual rather than on the excess over the target hold — the arranger always intended to hold 30,000,000 and earns a fee for doing so.

— Practitioner's toolkit — Domain 13

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 13.T.1 — Diligence stream economics and interface sheet (one per transaction)

Part A, one row per stream: stream · adviser and named partner · fee · duration in weeks · inside the envelope or on the critical path (and if the latter, the justification and its weekly price) · **p, d, C, F** with the basis of each estimate and the number of comparable transactions behind it · **breakeven detection rate** · net value · deliverable schedule (red-flag date, draft date, final date) · addressee and reliance position · liability cap, and the cap as a percentage of **C**. **Part B, the cross-stream interface list:** every assumption touched by more than one adviser — availability, capacity, degradation, price, volume, tariff indexation, insured loss, tax rate, construction programme — with its single named owner, its value, its version and the streams that consume it. **Front line:** the envelope length, the binding stream, and the aggregate net value in parallel against in series.

Toolkit 13.T.2 — Model-audit finding register (one per model version)

Per finding: number · date raised · raised by (auditor / sponsor review / machine scan) · scope layer (arithmetic / structure / documents / assumptions) · description · **class 1, 2 or 3 against the stated materiality threshold** · quantified effect on **CFADS**, **DSCR**, minimum **DSCR**, debt capacity and the funding plan · correction made · dependent outputs updated (credit paper, term sheet, base case, sources and uses) · re-run of the golden-answer set (date and result) · verifier and date · disposition if accepted rather than corrected, with the written rationale. **Header block, mandatory before any count is quoted:** materiality threshold; counts by class; **class-weighted closure**; and the list of open Class 1 findings with their quantified effect. A finding count without this header block is not a reportable metric.

Toolkit 13.T.3 — Close register: conditions, costs and funds flow (one per transaction)

Part A, conditions: condition · clause reference · category (corporate / documentary / third-party / adviser / financial) · chain and predecessor · duration estimate · owner · evidence requirement · evidence received and verified by whom · status (open / satisfied / waived / deferred) · for waivers and deferrals: deadline, consequence and owner. Computed per chain: base duration, float, slip probability, slip size, **criticality risk net of float**. Computed for the transaction: base close, **E[close] and its distribution**, expected slip cost, the conjunction premium, weeks of margin to the long-stop, and the value of de-risking the highest-weighted chain. **Part B, costs:** every close-cost line by payee, split into fixed and proportional components, with the total as a share of debt raised and of the envelope; the reconciliation to the model's provision and to sources and uses; and the effective cost of debt on lender fees and on total close costs. **Part C, funds flow:** every payment at close by payee and account, reconciled line by line to Part B, with the reconciliation signed by the agent and the finance director **before** close day, and payment instructions verified out of band.

— Exam preparation — Domain 13

What is assessed. The economics of an information purchase and the breakeven detection rate; the difference between parallel and serial diligence and how to price it; the seven streams and the error class each uniquely detects; the model audit's four scope layers and its three finding classes, with the

debt-capacity consequence of a Class 1 finding computed; conditions precedent as a dependency network — float, criticality risk, the expected maximum and the conjunction premium; the close-cost budget, its fixed and proportional decomposition, its share of debt raised and its reconciliation to sources and uses and to the funds flow; the three syndication routes, the fee architecture, the arranger's yield differential and the cost of a failed sell-down; market flex and its coverage-covenant ceiling; waivers, long-stop dates and post-close undertakings; and the governance of AI across all four Knowledge Areas.

The calculations to do under time pressure. A breakeven detection rate from fee, delay, p , C and F (13.1.3). A stream's net value inside and outside the envelope (Exercise 13.1). A $DSCR$ and debt capacity from a corrected $CFADS$ at a target coverage (13.2.3, Exercise 13.4). An annuity-due instalment and the ratio it flatters (13.2.3). The expected maximum of three or four chains, with the probability of the base date (13.3.2, Exercise 13.2). Close costs as a share of debt, and the deal size at which a target share is reached (13.3.4, Exercise 13.3). A syndication fee split and the arranger's yield (13.4.2, Exercise 13.5). A carry cost on an excess hold, and the excess that consumes the praecipium (13.4.3). The present value of flex, and the margin at which a coverage covenant fails (13.4.4).

The traps. Computing d^* as $\text{fee} \div (p \times C)$ and omitting the pre-close correction cost (Exercise 13.1) · pricing elapsed time once per stream when the streams run in parallel, or once for the envelope when they do not (13.1.3) · treating a stream's breakeven above 100 % as an arithmetic error rather than as evidence that the configuration cannot pay (MCQ 13.1-C) · quoting a finding count or a "findings closed" percentage as progress (13.2.2, MCQ 13.2-B) · classifying a finding by the size of the movement rather than by whether a conclusion changes (Exercise 13.4) · assuming an annuity due and an annuity in arrears give the same debt service — they differ by 283,564 here, and in the flattering direction (13.2.3, MCQ 13.2-A) · taking the longest chain's expected duration as the expected close (13.3.2, Exercise 13.2, MCQ 13.3-A) · spending acceleration effort on a chain with float (13.3.3, MCQ 13.3-B) · dividing close costs by the capital envelope rather than by debt raised (13.3.4, MCQ 13.3-C) · omitting the proportional component when solving for the deal size at a target close-cost share (Exercise 13.3, MCQ 13.3-D) · quoting the all-in cost of raising debt as though the lender charged it (13.3.4) · applying the full arrangement fee to the arranger's hold and ignoring the praecipium's exclusivity (MCQ 13.4-A) · charging an underwriter's carry on its residual hold rather than on the excess over target (Exercise 13.5, MCQ 13.4-B) · pricing flex as one year or as an undiscounted sum instead of an annuity (MCQ 13.4-C) · describing a signed transaction as closed (MCQ 13.4-E) · recording a waiver without a deadline, owner, evidence standard and consequence (Case study B).

How the domain connects. Domain 5's condition register becomes this domain's CP schedule and its close-cost provision; Domain 6's model and model-audit economics become KA 13.2's finding classes; Domain 9's tranche structures and effective-rate discipline become KA 13.4's syndication and close-cost arithmetic; Domain 10's $CFADS$, coverage ratios and covenant thresholds are what every Class 1 finding is measured in and what market flex is tested against; Domain 11's risk allocation and Domain 12's contracts are what the legal, technical and insurance streams verify. Forward, Domain 14 begins at the first drawdown this domain makes available and monitors the conditions this domain waived or deferred; Domain 15 operates the covenant regime the diligence file will be argued over; and Domain 16 systematises the AI controls each Knowledge Area here specified.

— Domain 13 summary

Diligence and close are economic decisions under a deadline, and elapsed time — **124,133.33 per week** for Kestrel — governs both. A diligence stream is worth running when the loss it avoids

exceeds what it costs, and the breakeven detection rate $d^* = (\text{fee} + \text{priced elapsed time}) \div [p \times (C - F)]$ states the condition compactly: the diligence spend divided by the expected avoidable loss. Kestrel's seven streams, 1,500,000 of fees and 54 weeks of duration, are worth **+4,066,699.88** inside a twelve-week parallel envelope and **-1,146,900.12** run serially, the **5,213,600** difference being 42 weeks of scheduling and nothing else; inside the envelope no stream needs better than a **31.25 %** detection rate to pay, while in series five need **72.02 %** to **99.42 %** and two — environmental and social at **119.12 %**, insurance at **289.86 %** — cannot pay at any detection rate. Model audits are read by **class, never by count**: Kestrel's 34 findings resolved as 3 Class 1, 7 Class 2 and 24 Class 3, so the 24 that changed nothing were **70.6 %** of the count and the reported **91.2 %** closure could be true with every consequential finding open. Two document-conformance findings — an annuity-due schedule understating the instalment by **283,564** and a misplaced 260,000 reserve line — moved the reported **DSCR** from **1.3508** to a true **1.2224** and debt capacity at 1.30× to **39,494,354**, a resize of **2,505,646**, while a third left the **2,504,818** DSRA unfunded; none of the three was an arithmetic error, which is why the audit's document layer matters more than its formulae. Conditions precedent are a conjunction with a critical path, so the close date is the expected **maximum** of the chains: Kestrel's five chains give **E[close] 22.4075 weeks** against a base of 20 and a critical chain whose own expected duration is 21.2000, a **34.125 %** probability of holding the stated date, an expected slip cost of **298,851** against the critical chain's **148,960**, and a **conjunction premium of 149,891** — and the highest-value intervention, worth **76,031.67**, is on chain B, which is not the critical path. Close costs of **2,709,000** are **6.45 %** of debt raised, only 544,000 of it payable to lenders, decomposing into a **2,016,000** fixed component and **1.65 %** proportional — so a facility must reach about **149,333,333** before close costs fall below 3.0 % of debt — and the budget reconciles to a model provision 69,000 short, implying an effective cost of debt of **6.2386 %** on lender fees and **7.2376 %** on the whole cost of raising it. Syndication pays the arranger **247,500** on a 15,000,000 hold, a **1.650 %** yield against participants' **0.950 %**, and a **3.31 %** over-hold consumes that entire premium — which is why market flex, worth **1,760,607** or **3.4933×** the arrangement fee and consuming **44.9 %** of the coverage covenant's **111.4 basis points** of rate headroom, is the term that should be negotiated hardest and almost never is. Throughout, AI shortens the envelope by extracting, reconciling and tracking, and is permitted to conclude nothing: not a legal, tax or environmental opinion, not a finding's class, not a condition's satisfaction, not a market price, and never a payment instruction. Domain 14 takes the first drawdown this domain made available.

04

PART FOUR

Operating and the future

Domains 14–16 — operations and asset management, refinancing and portfolio value, and the future of project finance: the life after close.



14

DOMAIN 14

Construction Monitoring and Drawdown

— Why this domain exists

Domain 13 closed the transaction. Every domain before it answered a question about a project that did not yet exist: is it worth building, can it carry debt, who bears which risk, what do the documents say. This domain answers the first question about a project that does exist and is being built with other people's money, and it is a narrower and harder question than any of them: **on the evidence available this month, may the next tranche of funds be released?**

That question is not "is the project going well?" and it is not "what will it finally cost?" It is a test with a binary answer, run against a defined evidence pack, on a defined date, by a person who signs. The whole apparatus of construction monitoring exists because limited-recourse debt is advanced **before** the asset that secures it exists, so the lender's only protection between financial close and commercial operations is the discipline with which each release of funds is conditioned on certified progress and on a demonstration that the remaining money still finishes the job. Everything in this domain follows from that single structural fact.

The domain's central claim is that **the construction-phase tests are not a finance version of project controls; they are a different discipline reading the same data spine, and the differences are systematic, nameable and computable**. A project controls forecast produces a range and a narrative (PML-AI Domain 7's [EAC](#) family). A lender's cost-to-complete produces one number, a date and, when it fails, a cash call — and it is built on a **commitment** basis, not a performance-extrapolation basis, so on a fixed-price contract the two can diverge by millions while both are correct on their own terms. Reconciling them, line by line, is the single most valuable professional skill this domain teaches, and Toolkit 14.T.2 exists to make it routine.

Learning objectives. After this domain a candidate can: restate a sources-and-uses statement at a data date into drawn, committed and available columns and explain why the identity is a construction, not a check; build a draw request from certified value through retention and advance recovery to a net funding requirement and its pro-rata debt and equity shares; compute the capitalised interest consequence of a funding order (pro rata, equity-first, debt-first) and state whose interest each order serves; compute a lender's cost-to-complete on a commitment basis and reconcile it, line by line, to a [BAC/CPI](#) or bottom-up [EAC](#) from the same data spine; explain why a blended [CPI](#) misattributes an overrun across fixed-price and owner-retained scope; run a funds sufficiency test and identify the double-count that makes most of them pass wrongly; compute a contingency coverage ratio on the remainder and defend the choice of denominator; value the same month's work on milestone, measured and cost-incurred certification bases and quantify the debt advanced against work not in place; compute the marginal [DSCR](#) of a variation and the debt share at which it becomes coverage-dilutive; distinguish the **funded** cost of a month of delay from its **economic** cost and show that one liquidated-damages rate can over-recover the first while under-recovering the second; compute the [DSCR](#) at a calendar-fixed first repayment date under a late commercial operations date, with its covenant, payment and reserve breakevens; compute a buy-down that restores a stated

coverage level; and govern AI-assisted certification, cost-report and covenant analysis under the family's verification rule.

The master construction. Kestrel Water SPC is being built. Domain 6 (KA 6.2.1) fixed the funding: a **USD 60,000,000** envelope, **USD 42,000,000** senior debt at **6.0 %** and **USD 18,000,000** equity, funded **70/30** against certified spend over **eight construction quarters** on a profile of **6, 9, 13, 16, 17, 15, 13 and 11 per cent**; uses of EPC price **48,000,000**, owner's costs and land **3,600,000**, capitalised development **1,800,000**, arrangement and financing fees **840,000**, a balancing contingency of **3,645,403** and capitalised interest of **2,114,597**. The certified-spend base is therefore **55,245,403**, and cumulative debt drawn reaches **31,990,655** by the end of quarter six. Domain 12 (KA 12.1.1) fixed the contract limits: delay damages **20,000 per day** capped at **4,800,000** (day 240), performance damages capped at **4,800,000**, aggregate liability **9,600,000**. Domain 10 fixed the operating regime: annual debt service **USD 5,009,635.23**, base **CFADS 6,384,000**, **DSCR 1.2743**, a **1.20×** covenant biting at **CFADS** of **6,011,562** (annual headroom **372,438**), a **1.15×** lock-up and a six-month debt service reserve of **2,504,818**. This domain takes that structure to the site and runs it, quarter by quarter, to the completion tests.

KNOWLEDGE AREA 14.1

Sources and uses, draw requests and conditions

Topics: 14.1.1 the sources-and-uses statement as a control document · 14.1.2 the draw request · 14.1.3 funding order, and who pays for it.

14.1.1 The sources-and-uses statement as a control document

Definition. A **restated sources-and-uses statement** is the financial-close statement re-expressed at a data date into three columns — **drawn to date**, **remaining to be funded**, and **available commitment** — so that the identity that held at close (sources = uses) can be tested prospectively rather than merely admired retrospectively.

Domain 6 established that sources equal uses is an identity, not a check: a model can always be made to satisfy it, and what makes it informative is knowing which line balances. In construction monitoring the same point returns with teeth. **The close statement is a plan; the restated statement is a test.** At close, the balancing line was contingency. At a data date the balancing line is whatever the sponsors will inject when the columns do not reconcile, and its size is the number this whole knowledge area exists to compute.

Three columns, and one rule for each. **Drawn to date** is a fact, reconciled to the facility agent's records and the SPV's bank statements, not to the model. **Remaining to be funded** is a forecast, and the whole of KA 14.2 is about how it is built. **Available commitment** is a contractual quantity — undrawn debt plus uncalled equity — and it carries the trap that catches most first drafts: **the undrawn commitment already includes the undrawn contingency**. Contingency is not a separate source of money; it is a use funded by the same 70/30 commitment as every other use. Adding "remaining contingency" to "undrawn debt plus uncalled equity" double-counts it, and the error flatters the in-balance test by exactly the contingency balance — which is precisely the period when the test most needs to be honest.

WORKED EXAMPLE**Worked example 14.1.1 — Kestrel's restated statement at the quarter-five data date.**

- Setup.** Five construction quarters are complete. On Domain 6's profile the planned cumulative certified spend is $55,245,403 \times 0.61 = 33,699,696$, funded by cumulative debt of **25,917,751** and equity of **11,107,608**, with capitalised interest of **685,663** accrued to date (quarterly amounts 27,720, 62,816, 115,682, 192,307 and 287,138) and **1,428,934** planned for quarters six to eight. Actual certified spend is higher: the owner-retained scope has cost **4,200,000** against a budget value of work done of **2,520,000**, and **465,403** of variations have been certified — so actual cumulative certified spend is **33,945,403**, or **245,707** above plan, drawn in quarter five. Restate the statement and test the balance.
- Formula.** Additional draw = actual – planned certified spend, split 70/30. Available commitment = $(42,000,000 - \text{cumulative debt}) + (18,000,000 - \text{cumulative equity})$. Additional interest = additional debt draw $\times 0.015 \times$ remaining quarters. Balance = available – remaining uses.
- Substitution.** $245,707 \times 0.70 = 171,995$; $245,707 \times 0.30 = 73,712$; $(42,000,000 - 26,089,746) + (18,000,000 - 11,181,320)$; $171,995 \times 0.015 \times 3 = 7,740$; remaining base-scope spend $55,245,403 \times 0.39 - 245,707 = 21,300,000$.
- Result.**

Restated statement at the quarter-five data date	Drawn (USD)	Remaining (USD)	Total (USD)
Fees and capitalised development	2,640,000	—	2,640,000
EPC contract price	29,280,000	18,720,000	48,000,000
Owner-retained scope, at budget	2,520,000	1,080,000	3,600,000
Owner-scope overrun and certified variations, from contingency	2,145,403	1,500,000	3,645,403
Interest during construction	685,663	1,436,674	2,122,337
Total uses	37,271,066	22,736,674	60,007,740
Senior debt	26,089,746	15,910,254	42,000,000
Equity	11,181,320	6,818,680	18,000,000
Total sources / available commitment	37,271,066	22,728,934	60,000,000

Remaining uses **22,736,674** against available commitment **22,728,934** — the project is **out of balance by USD 7,740** on the plan's own assumptions. 5. **Interpretation.** Read the 7,740 first, because it is the whole discipline in miniature. Nothing has gone wrong that the plan did not contain: 245,707 of contingency was drawn three quarters earlier than the model assumed it would be, and $171,995 \times 0.015 \times 3$ is the interest that early draw costs. **Drawing contingency early is not free, and the price is computable to the dollar.** A facility whose availability is measured to the last dollar of commitment is therefore out of balance the moment any use is accelerated, which is why prudent structures either fund a small unallocated headroom above the modelled envelope or provide expressly that the sponsor tops up timing differences — and why the sponsor should know which of those two the documents say before the first draw, not during the fifth. The second reading is the composition of the remaining column. **Only 18,720,000 of the 22,736,674 is a fixed contractual commitment**; 1,080,000 is a budget for owner-retained work whose demonstrated cost efficiency is

0.60 (KA 14.2), 1,500,000 is contingency against risks not yet run, and 1,436,674 is interest that depends on the draw profile of everything above it. Three of the four lines are forecasts, and the in-balance test is only as strong as the weakest of them. Third, notice what the identity does not tell you. The columns reconcile within 7,740 while — as KA 14.2 will show — the lender's own cost-to-complete on the same data date is **1,927,740** short. **A sources-and-uses statement built from the model balances by construction; a sources-and-uses statement built from the commitments does not, and the gap between them is the report.**

14.1.2 The draw request

Definition. A **draw request** (or drawdown notice, or advance request) is the borrower's certified application for the release of funds, and it is a composite document: an arithmetic claim (this much money, split this way), an evidential claim (this work is in place, certified by this person), and a representational claim (the conditions to drawing are satisfied and the project remains in balance). Lenders decline draws far more often on the third limb than on the first.

The arithmetic runs in one direction and each step has a reason:

```
Gross certified value of work executed in the period
- retention withheld
- recovery of the advance payment
+ owner-retained costs incurred and evidenced
+ fees, taxes and premiums due in the period
+ interest and commitment fees accrued
= period funding requirement
  × gearing                → senior debt draw
  × (1 - gearing)          → equity draw (or equity contribution certificate)
```

The **conditions to each drawing** are a shorter and more consequential list than the conditions precedent to first drawing (Domain 13, KA 13.3): no default or potential default continuing; the representations repeated and still true; the certificate of the independent engineer or lender's technical adviser attached; insurances in force and premiums paid; the project **in balance**; and the drawing within the availability period and within the commitment. Two of these are judgments rather than facts — "no potential default" and "in balance" — and they are where a monitoring relationship is actually conducted.

WORKED EXAMPLE**Worked example 14.1.2 — the quarter-five draw, built line by line.**

1. **Setup.** Quarter five on Domain 6's profile: planned certified spend $55,245,403 \times 0.17 = 9,391,718$; interest accrued on the opening debt balance of 19,142,551 at 1.5 % is **287,138**. The additional certified contingency spend of **245,707** identified in 14.1.1 falls in this quarter. Gearing 70/30. Compute the request and the resulting balances.
2. **Formula.** Requirement = certified spend + accrued interest; debt draw = $0.70 \times$ requirement; equity draw = $0.30 \times$ requirement.
3. **Substitution.** Carrying the three lines unrounded, $9,391,718.47 + 245,707.08 + 287,138.27 = 9,924,563.82$; $\times 0.70$; $\times 0.30$.
4. **Result.** Period funding requirement **USD 9,924,564**; senior debt draw **6,947,195**; equity draw **2,977,369**. Closing cumulative debt **26,089,746** (62.12 % of commitment) and equity **11,181,320** (62.12 % of commitment); undrawn commitment **22,728,934**.
5. **Interpretation.** Three things in that line are worth a leader's attention. **The interest line is a draw.** 287,138 of the request is money the project is borrowing in order to pay interest on money it has already borrowed, which is exactly what capitalised interest means and exactly why Domain 8's area rule matters: the interest row grows with the drawn balance, so it is largest in the quarters when the certified-spend row is already falling. In quarter eight Kestrel's interest row is 560,308 against a spend row of 6,076,994 — **8.44 %** of the period requirement, against **0.83 %** in quarter one. A sponsor budgeting equity calls from a construction spend curve alone will under-call late in the programme, every time. **The equity draw is a call, and calls have lead times.** 2,977,369 has to arrive from shareholders whose own approval processes (PML-AI Domain 3's governance latency) may run to weeks; a draw request that reveals the call is a draw request submitted too late. The professional practice is a rolling twelve-week funding forecast issued to shareholders, reconciled to the draw schedule, so that no call is news. **And the pro-rata split is a contractual mechanic, not an accounting one.** Each draw carries its own 70/30 split, which is why the cumulative percentages move in lockstep — 62.12 % of both commitments drawn — and why any departure from that lockstep is either a documented funding order (14.1.3) or an error worth finding immediately.

14.1.3 Funding order, and who pays for it

Definition. The **funding order** is the contractual rule determining, for each period's requirement, how much comes from debt and how much from equity. Three orders are standard: **pro rata**, in which every draw carries the gearing ratio; **equity-first**, in which the sponsors' whole commitment is exhausted before any debt is drawn; and **debt-first** (sometimes "debt-first with an equity backstop"), in which the facility is drawn to its limit before equity is called. The choice is usually settled in a single sub-clause of the facility agreement and is routinely treated as boilerplate. It is not: it moves capitalised interest, credit exposure and the sponsor's return, in different directions, by amounts that dwarf most of what is negotiated around it.

WORKED EXAMPLE**Worked example 14.1.3 — the same project under three funding orders.**

1. **Setup.** Kestrel's certified-spend base **55,245,403** on the eight-quarter profile, fees and development of **2,640,000** funded at close, interest at **1.5 %** per quarter on the opening debt balance, draws treated as made at period end. Scope and contingency are held identical across the three orders so that only the sequencing changes. Compute total capitalised interest, the resulting funding requirement, and the sponsor's share of funds in the ground at each draw date.
2. **Formula.** For each period: $\text{interest} = \text{opening debt balance} \times 0.015$; $\text{requirement} = \text{certified spend} + \text{interest}$; the split follows the order; $\text{total uses} = 2,640,000 + 55,245,403 + \Sigma \text{interest}$.
3. **Substitution.** Pro rata: $\text{debt draw} = 0.70 \times \text{requirement}$ throughout. Equity-first: $\text{equity draw} = \min(\text{requirement}, 18,000,000 - \text{equity drawn})$, the balance from debt. Debt-first: $\text{debt draw} = \min(\text{requirement}, 42,000,000 - \text{debt drawn})$, the balance from equity.
4. **Result.**

Funding order	Capitalised interest (USD)	Total uses (USD)	Debt drawn (USD)	Equity drawn (USD)	D/E
Equity first	1,338,006	59,223,409	41,223,409	18,000,000	2.2902
Pro rata 70/30	2,114,597	60,000,000	42,000,000	18,000,000	2.3333
Debt first	2,804,070	60,689,473	42,000,000	18,689,473	2.2473

Equity-first saves **776,591** of capitalised interest against pro rata (**36.73 %**); debt-first costs **689,473** more (**32.61 %**). The spread from best to worst is **USD 1,466,064**, or **2.4434 %** of the envelope. Under debt-first no sponsor cash is in the ground until quarter six, and at the quarter-five data date the lender's exposure is **37,323,907** against **25,917,751** pro rata — a difference of **11,406,157** — with **zero** equity contributed against **11,107,608**.

5. **Interpretation.** Start with the size of the number, because it settles a question of priorities. Kestrel's total drawn-balance exposure over the build is $2,114,597 / 0.015 = 140,973,150$ quarter-dollars, so a ten-basis-point movement in the margin is worth $140,973,150 \times 0.001/4 = 35,243$ across the whole construction period. The funding-order spread of 1,466,064 is **41.6 times** that. Financings are routinely negotiated for weeks over the margin and settle the funding order by accepting the lender's draft, which is an allocation of professional attention almost exactly inverted. **Second, the three orders serve three different interests and the arithmetic says so.** Equity-first is cheapest for the project and safest for the lender, because it puts sponsor money in first — which is why lenders draft it and why sponsors resist it. Debt-first is dearest for the project and worst for the lender, and the sponsor still prefers it: discounting each order's equity draws at Domain 4's 8 % (a quarterly 1.9427 %), pro rata has a present value of **16,476,605** and debt-first **16,293,592**, so deferring the cheque is worth **183,013** of present value to the sponsor even though it costs the project 689,473 of capitalised interest, which the sponsor then funds as additional equity. **A sponsor arguing for debt-first is buying 183,013 of present value for 689,473 of nominal cost, and both statements are true.** Whether that is rational depends on the sponsor's own cost of capital, which is exactly the conversation the clause deserves and rarely gets. **Third, at a fixed envelope the saving reappears as protection.** Hold the 60,000,000 envelope and re-solve for the balancing contingency under equity-first, and contingency rises from 3,645,403 to **4,388,050** — **9.14 %** of the EPC price against 7.59 %, an extra **742,647** of funded protection bought with a sequencing clause and no additional money. That is the

version of this calculation to take to a credit committee, because it converts an interest saving into the currency the committee actually cares about. **The professional caution:** none of this survives contact with a project that stops. Equity-first maximises the sponsor's irrecoverable exposure if the works are abandoned early, and a sponsor with a weak balance sheet may simply be unable to fund it — which is why the honest framing is not "equity-first is best" but "the funding order allocates construction-phase risk and cost between three parties, and the allocation must be priced before it is signed."




Fig 14.1.1 — Funding order: who is exposed, and what the interest costs

AI in this KA

Where it earns its place. Draw-request assembly is repetitive, document-heavy and deadline-driven, which is exactly where machine assistance pays: extracting certified quantities and values from a certifier's schedules into the draw template; reconciling the requested amount against the facility agent's drawn-to-date records and flagging every discrepancy; checking that each condition to drawing has a corresponding, in-date piece of evidence in the pack (insurance certificates, the technical adviser's certificate, the compliance certificate) and listing what is missing; and maintaining the rolling funding forecast so that no equity call is news. Recomputing the whole funding table under an alternative funding order — the arithmetic of 14.1.3 — is likewise machine work, and it is work almost nobody does by hand, which is precisely why the clause goes unnegotiated.

Where it must not go. Nothing in this knowledge area may generate a **representation**. The "no default continuing" and "in balance" statements in a draw request are certifications by named officers with consequences attached, and a model that concludes them has produced a draft for a human to verify and sign, never a signature. Nor should an assistant be permitted to reconcile a discrepancy it finds between the requested amount and the agent's records; its job is to surface the difference, because the reconciliation is where an error becomes either a correction or a misstatement.

Verification, concretely. Recompute one period's requirement by hand from the certifier's gross value — retention — advance recovery + owner costs + accrued interest, and require agreement to the dollar. Independently recompute accrued interest from the opening balance and the day-count basis (Domain 8's area rule reproduces the whole IDC line from the profile, the rate and the gearing, and disagreement is a defect not a rounding difference). Confirm that cumulative debt and equity percentages are equal under pro-rata funding, and that any divergence traces to a documented funding order. Tie drawn-to-date to the agent's statement, not to the model. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 14.1

Term	Meaning
Restated sources and uses	The close statement re-expressed at a data date into drawn, remaining and available columns; a test rather than an identity.
Available commitment	Undrawn debt + uncalled equity. Already includes undrawn contingency — adding contingency again double-counts.
Draw request	The certified application for funds: an arithmetic, an evidential and a representational claim.
Conditions to each drawing	The per-draw conditions: no default, representations repeated, certificates attached, insurances in force, in balance, within availability and commitment.
Funding order	Pro rata, equity-first or debt-first; allocates capitalised interest, credit exposure and sponsor return.
Equity contribution certificate	Evidence that the equity share of a draw has been provided, conditioning the debt share.

■ SAMPLE MCQS — KA 14.1

MCQ 14.1-A [14.1.1 · Application] At a data date, undrawn senior debt is 15,910,254 and uncalled equity is 6,818,680; remaining unallocated contingency is 1,500,000. Available commitment for the in-balance test is:

- A. USD 24,228,934
- B. USD 22,728,934 ✓ CORRECT
- C. USD 15,910,254
- D. USD 21,228,934

Rationale: Available commitment is $15,910,254 + 6,818,680 = 22,728,934$. A adds the 1,500,000 of contingency, which is a **use** funded by that same commitment — the double-count of 14.1.1, and it flatters the test by exactly the contingency balance. C counts only debt and ignores the equity commitment. D deducts the contingency instead of ignoring it, an error in the opposite direction.

MCQ 14.1-B [14.1.3 · Analysis] On identical scope and contingency, Kestrel's capitalised interest is 1,338,006 under equity-first funding and 2,804,070 under debt-first. The soundest reading is:

- A. debt-first is a modelling error, since total funding is fixed at 60,000,000
- B. the 1,466,064 spread is a real cost of the sequencing clause; equity-first is cheapest for the project and safest for the lender, while debt-first defers the sponsor's cheque and is worth 183,013 of present value to the sponsor ✓ CORRECT
- C. the orders are economically equivalent because the sponsor funds the difference either way
- D. the difference is capitalised, so it has no effect on the project's economics

Rationale: The sequencing changes the drawn balance on which interest accrues, so it changes total uses (59,223,409 / 60,000,000 / 60,689,473) — the arithmetic of 14.1.3. A misreads a fixed envelope as a fixed requirement. C ignores that the sponsor's present value improves while the project's nominal cost worsens. D is the commonest form of the error: capitalised interest enters the depreciable base and the coverage arithmetic and is therefore paid, with interest, over the loan life.

MCQ 14.1-C [14.1.2 · Application] Kestrel's quarter-eight draw carries certified spend of 6,076,994 and accrued interest of 560,308. As a share of the period requirement, the interest line is closest to:

- A. 0.83 %
- B. 8.44 % ✓ CORRECT
- C. 9.22 %
- D. 3.52 %

Rationale: $560,308 / (6,076,994 + 560,308) = 8.44 \%$. A is the quarter-one share, the point being that the interest row grows as the spend row falls. C divides interest by certified **spend** rather than by the period requirement, the commonest slip. D is total capitalised interest as a share of the 60,000,000 envelope (Domain 6), a different denominator entirely.

MCQ 14.1-D [14.1.2 · Recall] Which condition to a drawing is a judgment rather than a verifiable fact?

- A. the drawing is within the availability period
- B. the requested amount is within the undrawn commitment
- C. no potential event of default is continuing, and the project remains in balance ✓ CORRECT
- D. the technical adviser's certificate is attached

Rationale: A, B and D are checkable against a calendar, a ledger and a document schedule. C requires a forecast of remaining cost and a view on what constitutes a potential default — which is why those two limbs are where the monitoring relationship is conducted (14.1.2).

MCQ 14.1-E [14.1.3 · Evaluation] The facility agreement's funding-order sub-clause is still open. Equity-first capitalises **1,338,006** of interest against **2,114,597** pro rata and **2,804,070** debt-first; at a fixed 60,000,000 envelope, equity-first re-solves the balancing contingency from 3,645,403 to **4,388,050**. Deferring the equity cheque is worth **183,013** of present value to the sponsor at 8 %. What should the transaction lead recommend to the sponsor's board?

- A. debt-first — it is worth 183,013 of present value to the shareholders, which is the only party the board represents
- B. equity-first — it converts the 776,591 of interest saving into 742,647 of additional funded contingency, 9.14 % of the EPC price against 7.59 %, provided the sponsor can carry the larger irrecoverable exposure if the works are abandoned early ✓ CORRECT
- C. pro rata — it is neutral between the parties and is what the lender's draft provides
- D. debt-first — capitalised interest is not a cash cost during construction, so the order is presentational

Rationale: At a fixed envelope the sequencing buys funded protection with no additional money, which is the form of the argument a credit committee and a board can both act on (14.1.3) — and the condition attached to it is the real one, because equity-first maximises the sponsor's exposure to an abandoned works. A is defensible and is what sponsors argue — the 183,013 is a genuine present-value gain to the shareholders at the board's own 8 %, and it is already net of the extra 689,473 the sponsor must fund. It is weaker for two reasons the recommendation has to state. It prices only the

timing of the sponsor's own cheque and puts nothing at all against the 742,647 of funded protection the same decision forgoes, whose value shows up precisely in the state where the works overrun. And its ground is wrong: a sponsor board that signs a funding order is also fixing the project's irrecoverable exposure and the lender's, so shareholder present value is the decisive interest only once the protection question has been answered. C accepts a settlement in place of an analysis. D is false: capitalised interest is drawn, enters the debt balance and is repaid with interest over the loan life.

MCQ 14.1-F [14.1.1 · Comprehension] Which statement best restates why the restated sources-and-uses statement is a **test** where the financial-close statement is only an **identity**?

- A. the close statement was reviewed by the model auditor and the restated one is not
- B. at close one line is solved so that the columns agree, whereas at a data date the two columns are built from independent sources — the agent's records, certified progress and a commitment schedule — so a gap between them carries information ✓ CORRECT
- C. the restated statement replaces forecasts with actual costs
- D. the restated statement adds remaining contingency as a source, which the close statement omits

Rationale: An identity can always be satisfied by choosing the balancing line; a test can fail because nothing is free to move (14.1.1). C is only partly true and misleads on the important part — three of the four lines in Kestrel's remaining column are still forecasts. D describes the double-count 14.1.1 exists to forbid: contingency is a use funded by the same commitment.

MCQ 14.1-G [14.1.2 · Evaluation] The quarter-five draw request must repeat the representation that the project is **in balance**. The certified cost report supporting it shows the columns reconciling; the finance team's own rolling funding forecast, issued internally the same week, shows a prospective shortfall of **1,927,740** on a commitment basis. The soundest course is to:

- A. sign the request on the certified cost report, because a representation is made on certified information and a forecast is not certified
- B. not sign the in-balance representation on a basis the team knows to be superseded: disclose the forecast position to the agent, name the cure and the party funding it, and submit the request with the cure — because the cure is dated by the next draw and not by the reporting date ✓ CORRECT
- C. sign the request now and disclose the forecast position in next month's report, when the cost report will have caught up with it
- D. withhold the draw request altogether until the cost report has been reissued on the forecast basis

Rationale: "In balance" and "no potential default" are the two limbs of a draw request that are judgments rather than facts, and both are certifications by named officers with consequences attached (14.1.2); a certification cannot rest on a basis its signer knows to be out of date. A treats a representation as a document-assembly step. C is the commonest course and puts the misstatement and the delay together — the shortfall surfaces a month later, having consumed part of the time available to raise the money (14.2.3). D avoids the misstatement by converting a disclosure problem into a schedule problem at 415,000 a month of funded cost and 947,000 of economic cost (14.4.1); the shortfall is **4.6452 months** of that funded cost, so the delay route can consume the whole amount in a quarter and a half without curing any of it.

■ SELF-CHECK — KA 14.1

1. Why is a restated sources-and-uses statement a test where the close statement is an identity? — At close one line balances by construction; at a data date the columns are built from independent sources (the agent's records, certified progress, a commitment schedule), so a gap is information rather than a plug.
2. State the double-count that flatters most in-balance tests. — Adding remaining contingency to undrawn debt plus uncalled equity; contingency is a use funded by that same commitment.
3. Who benefits from each funding order? — Equity-first: the project (lowest capitalised interest, 1,338,006) and the lender (sponsor money in first). Debt-first: the sponsor's present value (+183,013) at the project's cost (+689,473). Pro rata: neither, which is why it is the common settlement.

KNOWLEDGE AREA 14.2

Cost-to-complete and contingency draw

Topics: 14.2.1 the lender's cost-to-complete, and the reconciliation to [EAC](#) · 14.2.2 contingency draw and coverage on the remainder · 14.2.3 the in-balance condition and the cash call.

14.2.1 The lender's cost-to-complete, and the reconciliation to [EAC](#)

Definition. A **lender's cost-to-complete** is the money still required to reach the commercial operations date, built on a **commitment** basis: remaining contractual entitlement under signed contracts, plus approved variations not yet certified, plus the assessed exposure on notified but unagreed claims, plus a bottom-up re-estimate of owner-retained scope, plus the financing costs — interest, fees, premiums — that will accrue between the data date and completion. It is not $EAC - AC$, and the difference is not an error in either number.

Domain 8 (KA 8.4.1) established the bridge in principle: a project controller's report ends at an [EAC](#) column and an honest range; a lender reads the same figures and produces a date and an amount. PML-AI Domain 7 (KA 7.3.3) supplies the [EAC](#) family — remaining work at the budgeted rate, BAC/CPI , the $CPI \times SPI$ variant, and bottom-up re-estimation. This topic supplies the missing piece: **why the two disciplines diverge systematically on a fixed-price contract, and how to reconcile them line by line so that the divergence becomes evidence instead of an argument.**

The structural reason is the wrap. Under a fixed lump-sum contract certified against milestones, the amount certified is the amount budgeted for the milestone, so on the EPC scope [EV](#) and [AC](#) are identically equal and **[CPI](#) on that scope is 1.000 by construction**. Cost variance on the largest single line of the project is therefore structurally invisible to earned value; the risk shows up instead as schedule, as claims, and as contractor solvency. Meanwhile the owner-retained scope — land, permits, the owner's engineering team, utility diversions, the items no contractor would price — is where the SPV bears cost risk directly, and it is small enough to be overlooked and volatile enough to be dangerous.

WORKED EXAMPLE**Worked example 14.2.1 — Kestrel's two cost-to-completes at the quarter-five data date, and the bridge between them.**

- 1. Setup.** The construction control accounts carry **BAC 51,600,000** (EPC 48,000,000 plus owner-retained 3,600,000; contingency and financing sit outside the control accounts). At the data date the EPC scope is **61 %** certified, so **EV = AC = 29,280,000** on that scope. The owner-retained scope is **70 %** physically complete — **EV 2,520,000** — at an actual cost of **4,200,000**, a scope **CPI** of **0.6000**. Off the control accounts: **465,403** of variations already certified, **840,000** of variations approved but not yet certified, and notified but unagreed contractor claims whose assessed exposure the technical adviser and the SPV's quantity surveyor put at **1,260,000**. A bottom-up re-estimate of the remaining owner-retained scope comes back at **2,400,000**. Remaining capitalised interest to completion is **1,436,674** (14.1.1). Compute both cost-to-completes and reconcile them.
- 2. Formula.** EVM side: $CPI = EV/AC$; $EAC(a) = AC + (BAC - EV)$; $EAC(b) = BAC/CPI$; $EAC(d) = AC + \text{bottom-up ETC}$; $CTC = EAC - AC$. Lender side: $CTC = \text{remaining committed contract value} + \text{approved variations} + \text{assessed claim exposure} + \text{bottom-up owner scope} + \text{remaining financing costs}$.
- 3. Substitution.** $CPI = 31,800,000/33,480,000$; $EAC(b) = 51,600,000 \times 33,480,000/31,800,000$; $EAC(d) = 48,000,000 + 4,200,000 + 2,400,000$; lender side $18,720,000 + 840,000 + 1,260,000 + 2,400,000 + 1,436,674$.
- 4. Result.** **CPI 0.949821** blended, **1.0000** on EPC scope, **0.6000** on owner-retained scope.

Forecast	EAC (USD)	CTC = EAC - AC (USD)
(a) remaining work at the budgeted rate	53,280,000	19,800,000
(b) BAC/CPI	54,326,038	20,846,038
(d) bottom-up re-estimate	54,600,000	21,120,000

The reconciliation to the lender's number:

Bridge from the bottom-up CTC	USD
$CTC(d) = \text{remaining EPC } 18,720,000 + \text{remaining owner scope } 2,400,000$	21,120,000
+ approved variations, outside BAC	840,000
+ assessed exposure on notified claims, outside BAC	1,260,000
+ remaining interest during construction, outside BAC	1,436,674
= lender's cost-to-complete	24,656,674

Against available commitment of **22,728,934**, the project is **out of balance by USD 1,927,740**. 5. **Interpretation.** Four readings, in order of professional value. **The bridge is the whole lesson: the two numbers differ by items each discipline is structurally blind to.** Earned value does not see capitalised interest (it is not work), it does not see approved variations until they are baselined, and it does not see claim exposure at all — 3,536,674 of the lender's number is invisible to the cost report, which is 14.34 % of it. Conversely the lender's number does not see cost-performance trend on the fixed-price scope, because there is none to see. Neither number is wrong; a report that presents one without the other is. **Second, the blended CPI gets close to the right total for**

entirely the wrong reasons, and that is worse than being wrong. EAC(b)'s uplift over BAC is 2,726,038, which sits plausibly between the 2,400,000 overrun implied by the owner-scope CPI and the 3,000,000 implied by the bottom-up. But of that uplift $48,000,000 \times (1/0.949821 - 1) = 2,535,849$ is attributed to a fixed-price scope that cannot overrun, and only **190,189** to the scope that is actually overrunning by 2,400,000 to 3,000,000. A reviewer who checks the total passes it; a reviewer who checks the composition finds that the forecast is right by coincidence and will stop being right the moment the mix changes. **Disaggregate before extrapolating: a CPI blended across scopes with different cost-risk ownership is an average of a constant and a variable, and it forecasts neither. Third, the CPI × SPI method has no honest home here.** It requires an SPI, and a milestone-certified fixed-price scope produces a lumpy, contractually-defined value curve that does not support one; the schedule question must be answered from the programme and the independent engineer's assessment (KA 14.4), not from an index. **Fourth, the 1,927,740 is a cash call, and its date is the next draw.** The forecast has stopped being a forecast. The commercial consequence is that **the choice of basis is a negotiation, not a technique** — the sponsor will argue that claims assessed at 1,260,000 are worth far less and that the bottom-up re-estimate is pessimistic, and both arguments may be right; what cannot survive is a report that omits the lines rather than arguing about them.

14.2.2 Contingency draw and coverage on the remainder

Definition. Contingency coverage on the remainder is the ratio of unallocated contingency still available to the assessed cost of everything it must still cover:

$$\text{Contingency coverage} = \frac{\text{remaining unallocated contingency}}{\div (\text{known committed claims on contingency} + \text{P80 of the open risk register})}$$

Domain 8 (KA 8.3) sized contingency at sanction and warned that the confidence level chosen is usually unnamed. This topic runs the same test during construction, where the denominator has two parts that behave completely differently, and where the standard health check is worthless.

The standard health check is the **draw rate**: contingency drawn as a percentage of contingency funded, compared with percentage progress. Kestrel at the quarter-five data date has drawn $(4,200,000 - 2,520,000) \div 465,403 = 2,145,403$ of its 3,645,403, or **58.85 %**, against **61.00 %** certified progress. That looks not merely acceptable but slightly better than proportionate, and it is the number most monthly reports lead with. It is meaningless. **Contingency is not consumed pro rata to progress, because risk is not distributed pro rata to progress** — some risks retire early (ground conditions), some cluster at the end (commissioning, performance testing, permit conditions), and a draw rate that tracks progress is a coincidence, not evidence. The only test that means anything is coverage on what remains.

WORKED EXAMPLE**Worked example 14.2.2 — Kestrel's contingency, tested twice.**

- Setup.** Contingency funded at close **3,645,403**. The sanction risk register carried six items: ground conditions at the intake structure (p 0.30, 2,600,000), a brine-outfall permit condition variation (0.25, 1,200,000), membrane supply escalation or substitution (0.35, 900,000), commissioning re-test and extended supervision (0.35, 700,000), an owner-supplied power-connection delay (0.30, 600,000) and interface and utility diversions in owner-retained scope (0.40, 800,000). By the quarter-five data date the ground-conditions and interface risks have **materialised** (they are the owner-scope overrun and the certified variations), the membrane risk has been **retired**, and four items remain open — with the claims risk restated as "notified claims settle above the assessed exposure" (p 0.40, 900,000). Known committed claims on contingency are the 840,000 of approved variations, the 1,260,000 of assessed claim exposure and the **1,320,000** by which the bottom-up owner-scope re-estimate of 2,400,000 exceeds the 1,080,000 of remaining budget. Compute coverage at close and at the data date.
- Formula.** Register mean = $\Sigma EMV = \Sigma p \times impact$; variance = $\Sigma p(1 - p) \times impact^2$; P80 $\approx$ mean + 0.8416 σ (the normal approximation of Domain 8, KA 8.3). Coverage = remaining contingency $\div$ denominator.
- Substitution.** At close: mean 780,000 + 300,000 + 315,000 + 245,000 + 180,000 + 320,000; variance $0.21 \times 2,600,000^2 + 0.1875 \times 1,200,000^2 + 0.2275 \times 900,000^2 + 0.2275 \times 700,000^2 + 0.21 \times 600,000^2 + 0.24 \times 800,000^2$. At the data date: mean 360,000 + 300,000 + 245,000 + 180,000; denominator 3,420,000 + P80.
- Result.**

Test	Contingency available (USD)	Denominator (USD)	Coverage
At financial close, against the sanction register P80	3,645,403	3,392,416	1.0746
At the data date, open risk only, on the mean	1,500,000	1,085,000	1.3825
At the data date, open risk only, at P80	1,500,000	1,764,289	0.8502
At the data date, known claims + open risk at P80	1,500,000	5,184,289	0.2893

Sanction register: mean **2,140,000**, σ **1,488,136**, P80 **3,392,416** — so the funded contingency of 3,645,403 sat at $z = 1.0116$, about the **P84** of that register. Open register at the data date: mean **1,085,000**, σ **807,140**, P80 **1,764,289**. The shortfall on the honest test is **3,684,289**. 5. **Interpretation.** The ratio a certifier reports depends entirely on what is admitted to the denominator, and the four answers span 1.38 to 0.29 on identical facts. That is not a technical quibble; it is the reason contingency certification must be a defined procedure rather than a judgment. The 1.3825 version — remaining contingency against the mean of open risk — is the one that appears most often in practice, because it is the easiest to compute and the most comfortable to sign; it fails because contingency exists precisely to cover the tail, and covering the mean is by construction a coin-flip. The 0.8502 version is defensible arithmetic and still wrong here, because it excludes 3,420,000 of claims on contingency that are not risks at all — they are approved, assessed or re-estimated amounts. **The honest denominator adds what is already known to what might still happen.** At 0.2893 the correct professional conclusion is not "coverage is thin" but

"contingency has been fully committed and the project requires additional funding" — which is the in-balance conclusion of 14.2.1 arrived at by a completely independent route, and the agreement between the two is a check worth running deliberately. **Second, the collapse from 1.0746 to 0.2893 happened without a single surprise.** Every item that materialised was on the sanction register at sanction, with a probability and an impact; ground conditions at an intake structure ran at p 0.30 and it happened. Nothing unlikely occurred. What went wrong was the confidence level: 3,645,403 was a P84 provision against the whole register, and once the two largest items materialised the remainder was funded at a level nobody had named — Domain 8's point, now with a date attached. **Third, and most practically: the draw-rate check must be struck from the report.** 58.85 % drawn at 61 % progress is the sentence that let two quarters pass without a funding conversation. Replace it with the coverage ratio, its denominator itemised, and the shortfall in currency.

14.2.3 The in-balance condition and the cash call

Definition. The **in-balance condition** is a term of the facility requiring that, at each drawdown and at each reporting date, the funds available be at least the cost to complete on the basis the documents specify. Failure is a condition failure, not a default: the consequence is that **the facility does not fund** until the position is cured. Curing is a funding event, and the documents will name its permitted forms.

Four cures, in descending order of how much they cost a sponsor. **Additional equity** — the base case, and the one every other cure is measured against. **Cost-overflow support** (Domain 5, KA 5.2.3): a pre-agreed, capped sponsor undertaking to fund overruns, which converts a negotiation into a drawing on a facility the sponsor has already granted. A **standby or contingent facility**: committed debt available only on the in-balance test, which is cheaper than equity for the sponsor and priced accordingly by lenders, and which raises gearing exactly when the project can least support it. And **reallocation** — moving a funded but unspent line (usually a residual owner's-cost or fee allocation) to the deficient line, which requires lender consent and is the cure that most often turns out on inspection to be a re-labelling of contingency that has already been committed.

Two mechanical points a leader must own. **The order of the tests matters.** A project can be in balance on the model and out of balance on the commitments (14.1.1 against 14.2.1); it can pass the in-balance test and fail the contingency-adequacy test, or the reverse. Facilities that condition drawing on one test and reporting on another produce exactly the gap Case study A exploits. And **the cure is dated by the next draw, not by the reporting date.** A cost report issued in the month after a data date has already consumed part of the time available to raise money; the practical consequence is that the sponsor's treasury must be told about a prospective shortfall from the forecast, not from the report — which is what the rolling funding forecast of 14.1.2 is for.

AI in this KA

Where it earns its place. Three tasks, all high-volume and all currently done badly. **Claims and variation registers**: extracting notified claims from correspondence, matching each to a contractual head, a quantum claimed and an assessed exposure, and keeping the register reconciled to the cost report — the register is usually maintained in three incompatible places, and a machine that reconciles them earns its keep in a month. **Disaggregated CPI reporting**: computing performance indices separately for fixed-price and owner-retained scope and flagging any report that blends them, which is the defect of 14.2.1 and is trivially detectable. **Register roll-forward**: tracking which sanction-register items have materialised, retired or been restated, and recomputing the coverage ratio on the remainder at every data date with the denominator itemised.

Where it must not go. An assessed claim exposure is a **legal and commercial judgment** about entitlement under a specific contract in a specific jurisdiction, and it must not be produced by a model. The same applies to the certification that contingency remaining is adequate for risk remaining: that is a signed opinion, and the arithmetic supporting it is an input to the opinion, not a substitute for it. Nor may an assistant select the denominator — the choice between 1,085,000, 1,764,289 and 5,184,289 is the whole content of the test, and a tool that picks the flattering one because it was the last one prompted for has industrialised the failure this topic exists to prevent.

Verification, concretely. Recompute the register mean and P80 by hand for two items and confirm the aggregation; require that the denominator be printed with its components, never as a single figure. Reconcile the in-balance shortfall against the contingency shortfall — the two routes should tell a consistent story, and Kestrel's do (1,927,740 of in-balance shortfall against contingency committed 1,920,000 beyond its balance, plus the 7,740 of early-draw interest). Require the bridge of 14.2.1 to be presented explicitly whenever an **EAC** and a lender's cost-to-complete appear in the same pack, with every bridge line attributed to the discipline that is blind to it.

■ KEY TERMS — KA 14.2

Term	Meaning
Lender's cost-to-complete	Money to completion on a commitment basis: remaining contract value + approved variations + assessed claim exposure + bottom-up owner scope + remaining financing costs.
In-balance condition	Facility term requiring available funds $\geq$ cost to complete; failure stops funding rather than causing default.
Assessed claim exposure	The SPV's and adviser's judgment of the probable settled cost of notified but unagreed claims.
Blended CPI artefact	A performance index averaged across fixed-price and owner-retained scope; misattributes an overrun and forecasts neither scope.
Contingency coverage on the remainder	Unallocated contingency $\div$ (known committed claims + P80 of the open register).
Draw-rate check	Contingency drawn as a share of contingency funded, against progress; coincidental, and to be struck from reports.
Cost-overrun support	A capped sponsor undertaking to fund overruns, converting a negotiation into a drawing.

■ SAMPLE MCQS — KA 14.2

MCQ 14.2-A [14.2.1 · Application] At a data date the remaining committed EPC value is 18,720,000, approved but uncertified variations are 840,000, assessed claim exposure is 1,260,000, the bottom-up remaining owner-retained scope is 2,400,000 and remaining capitalised interest is 1,436,674. The lender's cost-to-complete is:

- A. USD 21,120,000
- B. USD 24,656,674 ☒ **CORRECT**
- C. USD 23,220,000
- D. USD 20,846,038

Rationale: All five lines sum to 24,656,674. A is the bottom-up **CTC(d)**, which omits the three lines earned value cannot see. C omits remaining capitalised interest — the single most commonly dropped line, because it is not work. D is **CTC** on the **BAC/CPI** method, a different basis entirely.

MCQ 14.2-B [14.2.1 · Analysis] A project's blended **CPI** is 0.949821 across a fixed-price EPC scope of 48,000,000 (certified against milestones) and owner-retained scope of 3,600,000 running at a scope **CPI** of 0.60. Applying **BAC/CPI** to the blended index:

- A. is correct, since **BAC/CPI** is the standard persistence forecast
- B. attributes 2,535,849 of uplift to a scope that cannot overrun and only 190,189 to the scope that is overrunning, so the total is right only by coincidence ☒ **CORRECT**
- C. understates the forecast, because fixed-price scope carries the greater risk
- D. is invalid because **CPI** cannot be computed on a milestone-certified contract

Rationale: The composition of the 2,726,038 uplift is the defect (14.2.1). A treats a method as valid irrespective of the scope mix it is applied to. C inverts the risk ownership under a wrap. D overstates: **CPI** on that scope is computable and equals 1.000 by construction — which is exactly why blending destroys the signal.

MCQ 14.2-C [14.2.2 · Analysis] Remaining unallocated contingency is 1,500,000. Known committed claims on contingency total 3,420,000 and the open risk register has a mean of 1,085,000 and a P80 of 1,764,289. The defensible coverage ratio on the remainder is:

- A. 1.3825
- B. 0.8502
- C. 0.2893 ☒ **CORRECT**
- D. 0.4386

Rationale: $1,500,000 / (3,420,000 + 1,764,289) = 0.2893$. A tests contingency against the mean of open risk only — covering the mean is a coin-flip and it also ignores the 3,420,000 already committed. B is the P80 test on open risk only, which is defensible arithmetic on the wrong denominator. D divides by the 3,420,000 of known committed claims alone ($1,500,000/3,420,000$), omitting the open register entirely.

MCQ 14.2-D [14.2.2 · Analysis] A monthly report states that 58.85 % of contingency has been drawn at 61.00 % certified progress and concludes that contingency consumption is "in line". The correct professional response is:

- A. accept it; the draw rate is below progress, so consumption is favourable
- B. reject the inference — contingency is not consumed pro rata to progress, and the only meaningful test is coverage on the remainder ☒ **CORRECT**
- C. accept it if the draw rate has tracked progress for three consecutive periods
- D. recompute the draw rate on physical rather than certified progress

Rationale: The draw rate is coincidental because risk is not uniformly distributed through a programme (14.2.2); here the honest coverage on the remainder is 0.2893. C makes a trend out of a coincidence. D refines a measure that should not be relied on at all.

MCQ 14.2-E [14.2.2 · Evaluation] A certifier reports contingency coverage on the remainder of **0.2893** — 1,500,000 against 3,420,000 of known committed claims plus a 1,764,289 P80 on the open register — and concludes: "coverage is thin; we recommend monthly monitoring of the contingency position." Should that conclusion be accepted?

- A. yes — 0.2893 is thin, and closer monitoring is the proportionate response to a thin ratio
- B. no — a ratio below one means contingency is already fully committed and 3,684,289 short, so the finding is a funding requirement, corroborated by the independently derived 1,927,740 in-balance shortfall; monitoring a known deficit does not fund it ☒ **CORRECT**

C. no — the 3,420,000 of known claims does not belong in the denominator, and on open risk alone coverage is 0.8502

D. yes, provided the ratio is recomputed at every data date with its denominator itemised

Rationale: $1,500,000 - 5,184,289 = -3,684,289$: the number does not describe a margin that is narrow, it describes protection that has run out, and the in-balance route reaches the same conclusion from different inputs (14.2.1, 14.2.2). A and D are the defensible-sounding responses and both fail for the same reason — they answer a funding event with a reporting action. C is the argument the sponsor will make and 14.2.2 disposes of it: approved variations, assessed claim exposure and a bottom-up re-estimate are not risks that might happen, they are claims that have.

MCQ 14.2-F [14.2.1 · Comprehension] A project controller's cost report and the lender's monitor produce cost-to-complete figures differing by 3,536,674 on identical underlying data. The explanation a board should be given is:

- A. one of the two contains an error, and reconciliation will identify which
- B. each discipline is structurally blind to items the other counts — earned value cannot see capitalised interest, approved but unbaselined variations or claim exposure, while a commitment basis cannot see cost-performance trend on scope that is fixed-price

✓ **CORRECT**

- C. the monitor has applied a more conservative contingency allowance
- D. the difference is the unallocated contingency balance

Rationale: $840,000 + 1,260,000 + 1,436,674 = 3,536,674$, or 14.34 % of the lender's number, and every line of it is outside the control accounts by construction rather than by anyone's error (14.2.1). A is the instinct the bridge exists to correct. C invents a judgment difference where the difference is one of scope. D names a line that appears in neither cost-to-complete.

MCQ 14.2-G [14.2.1 · Evaluation] The lender's cost-to-complete of **24,656,674** exceeds available commitment of **22,728,934** by **1,927,740**. The sponsor disputes two lines: the **1,260,000** of assessed exposure on notified but unagreed claims ("worth far less, and unagreed in any case") and the **2,400,000** bottom-up re-estimate of remaining owner-retained scope ("pessimistic"). Both arguments may have merit. The soundest treatment in the monitoring report is to:

- A. adopt the sponsor's figures, since the SPV knows its own contracts and its own scope better than the monitor does
 - B. hold both lines at the assessor's figures, name the assessor, and record the sponsor's case and its basis beside them — because the disagreement is about the quantum of an exposure rather than about whether it exists, and a report that omits a line instead of arguing about it cannot be relied on by anyone
- ✓ **CORRECT**
- C. exclude the claim exposure until the claims are agreed, since an unagreed claim is not yet a liability, and hold the owner-scope line
 - D. publish two cost-to-completes, the monitor's and the sponsor's, and let the lenders choose between them

Rationale: The choice of basis is a negotiation rather than a technique, and both sponsor arguments may be right — what cannot survive is a report that drops the lines rather than stating them with their basis and their assessor (14.2.1). C is the accrual instinct, and it is arithmetically insufficient as well: removing the 1,260,000 closes **65.36 %** of the gap and still leaves the project **667,740** out of balance. A hands the assessment to the party that will fund the cure. D looks even-handed and evades the purpose of a monitoring report, which is a number a drawing can be conditioned on; two numbers and no recommendation is the same omission as one number with a line missing.

■ SELF-CHECK — KA 14.2

1. Name the three lines a lender's cost-to-complete contains that an **EAC** cannot see. — Approved variations not yet baselined, assessed claim exposure, and remaining capitalised interest and fees: 3,536,674 of Kestrel's 24,656,674.
2. Why is **CPI** on a milestone-certified fixed-price scope identically 1.000, and what follows? — Certified value equals budgeted milestone value, so $EV = AC$; cost risk on that scope shows up as schedule, claims and contractor solvency, and blending the index with owner-retained scope destroys the only real signal.
3. State Kestrel's contingency coverage on the remainder and its denominator. — 0.2893: 1,500,000 against 3,420,000 of known committed claims plus a 1,764,289 P80 on the open register.

KNOWLEDGE AREA 14.3

Progress certification and change control

Topics: 14.3.1 certification bases, and what each one funds · 14.3.2 advance payment, retention and the cash chain · 14.3.3 change control and the marginal coverage of a variation.

14.3.1 Certification bases, and what each one funds

Definition. Progress certification is the independent determination of the value of work executed in a period, and it is the hinge of the whole drawdown mechanic: it converts physical progress into a payment entitlement and a funding requirement. Three bases are in general use and they are not interchangeable. **Milestone certification** values only milestones actually achieved, each with a defined pre-agreed value — binary, lumpy, and the only basis that ties directly to a contractual entitlement. **Measured or percentage-of-completion certification (PoC)** values work in place on measured quantities or an assessed completion percentage of each activity — smoother, and requiring judgment. **Cost-incurred certification** values what the contractor has spent, including materials procured but not yet delivered to site — smoothest of all, and the basis on which the SPV's money leaves the country.

Who certifies matters as much as how. In a limited-recourse financing the certifier is usually an **independent engineer** or the **lender's technical adviser**, appointed under a deed the SPV cannot vary alone, and the certificate is a condition to each drawing. The certifier's independence is the structural protection; the certification basis is the structural exposure.

WORKED EXAMPLE**Worked example 14.3.1 — one quarter's work, valued three ways.**

- Setup.** In construction quarter six, Kestrel's EPC contractor executes work whose scheduled milestone value for the quarter is **7,200,000**. Milestones actually achieved total **5,760,000**; one further milestone worth **1,440,000** is assessed by the independent engineer as **92 %** physically complete but not achieved. The contractor has additionally procured **690,000** of membrane racks, paid for and stored at the vendor's works, not delivered. Retention is **5 %** of certified value. Gearing 70/30, quarterly interest 1.5 %, two quarters remain. Value the quarter on each basis and quantify the exposure the choice creates.
- Formula.** Milestone basis = Σ achieved milestone values. Measured basis = Σ achieved + PoC $\times$ value of the incomplete milestone. Cost-incurred basis = measured + off-site materials. Net for payment = certified $\times$ (1 – retention). Debt advanced = net $\times$ gearing. Over-certification = (cost-incurred – milestone) $\times$ (1 – retention).
- Substitution.** 5,760,000; 5,760,000 + 0.92 $\times$ 1,440,000 = 7,084,800; 7,084,800 + 690,000 = 7,774,800; each $\times$ 0.95; each $\times$ 0.70.
- Result.**

Basis	Certified value (USD)	Net of 5 % retention (USD)	Senior debt advanced (USD)
Milestone	5,760,000	5,472,000	3,830,400
Measured (PoC)	7,084,800	6,730,560	4,711,392
Cost-incurred	7,774,800	7,386,060	5,170,242

The spread on the same quarter's work is **2,014,800** of certified value — **34.98 %** of the milestone figure. Relative to the milestone basis, the cost-incurred basis releases **1,914,060** net, of which **1,339,842** is senior debt, and accelerates that requirement by up to two quarters at a cost of $1,339,842 \times 0.015 \times 2 = 40,195$ of additional capitalised interest.

5. Interpretation. The certification basis is a credit decision disguised as an accounting convention, and its magnitude is a third of a quarter's draw. Start with what each basis buys. Milestone certification is the most conservative and the only one whose numbers are contractual: 92 % of a milestone is worth exactly nothing, which is harsh on a contractor's cash flow and perfectly aligned with the lender's security, because an unachieved milestone is an unfinished thing. Measured certification is fairer to the contractor and introduces judgment — the 92 % is an opinion, and opinions drift upward under schedule pressure. Cost-incurred certification funds the contractor's balance sheet, and it is the basis on which lenders lose money. **The 1,339,842 of senior debt advanced against work not in place is 27.91 % of the 4,800,000 performance bond**, and it is unsecured in substance unless three things are true: the SPV holds a **vesting certificate** or equivalent transferring title in the off-site materials; the materials are **identified and segregated** at the vendor's works; and they are **insured in the SPV's name** against loss and against the vendor's insolvency. Absent any one of those, the money has bought a claim in someone else's liquidation — which is precisely what Case study B costs. **Second, the basis must be stated once and held.** Drift is the real risk: a project that begins on milestones and slides toward cost-incurred as the contractor tightens is not making a series of small accommodations, it is progressively converting secured lending into unsecured lending, one certificate at a time, and nobody signs the decision. The controls are simple and worth insisting on: the basis is defined in the facility and the certifier's deed; any off-site materials certification is separately identified, capped as a percentage of the contract price, and conditioned on vesting, segregation and insurance; and the cumulative off-site balance is a reported line. **Third,**

note the small number. The 40,195 of extra capitalised interest is real but trivial beside the 1,339,842 of exposure — which is the right lesson about certification: it is not a cost question, it is a security question, and pricing it as a cost question is how it gets conceded.

14.3.2 Advance payment, retention and the cash chain

Definitions. An **advance payment** (or mobilisation payment) is a sum paid to the contractor at or shortly after contract signature, secured by an **advance payment bond** and recovered by deduction from subsequent certifications. **Retention** is a percentage withheld from each certification, usually capped as a percentage of the contract price, released in tranches at completion and at the end of the defects liability period. Both are timing mechanisms, and both have a price a project finance leader must be able to state.

WORKED EXAMPLE

Worked example 14.3.2 — what Kestrel's payment terms cost in capitalised interest.

- 1. Setup.** The base case is Domain 6's funding profile with certified spend paid as it arises. The alternative applies the actual contract terms: an advance payment of **10 %** of the 48,000,000 EPC price — **4,800,000** — paid at financial close and recovered pro rata against each certification, and retention of **5 %** of each EPC certification capped at **2.5 %** of the contract price, being **1,200,000**, released half at the commercial operations date and half twelve months later. Interest at 1.5 % per quarter on opening drawn balances, gearing 70/30. Compute the effect of each term and of both together on capitalised interest.
- 2. Formula.** Re-run the quarterly funding model with the period requirement adjusted: $\text{requirement} = \text{certified spend} - \text{advance recovery} - \text{retention withheld} + \text{accrued interest}$, with the advance added to the close-date requirement. Compare total capitalised interest.
- 3. Substitution.** Close requirement $2,640,000 + 4,800,000$; quarterly recovery $4,800,000 \times \text{profile percentage}$; retention $\min(0.05 \times \text{EPC certified}, \text{remaining cap})$.
- 4. Result.**

Payment terms	Capitalised interest (USD)	Change vs base (USD)
Base: certified spend paid as it arises	2,114,597	—
Advance payment only (4,800,000 at close)	2,369,194	+254,597
Retention only (1,200,000 withheld to completion)	2,052,008	−62,589
Both terms, as contracted	2,306,605	+192,008

The advance costs **254,597** of capitalised interest — **5.30 %** of the advance itself, and **0.53 %** of the EPC contract price. Retention saves **62,589**, one quarter of what the advance costs. 5. **Interpretation.** An advance payment is a loan from the project to the contractor, and **254,597 is its price**. That reframing is the whole content of the topic, and it changes the negotiation. The SPV borrows at 6.0 % to fund the advance; the contractor, whose alternative is to finance its own mobilisation, borrows at whatever its own credit commands — typically more. If the contractor's marginal cost of funds exceeds the project's, the advance is genuinely value-creating for the transaction as a whole, and the correct professional position is therefore not "refuse the advance" but **"price it"**: a contractor unwilling to reduce the contract price by at least 254,597 — 0.53 % — in exchange for a 4,800,000 advance is being lent money for nothing. That is a computation the contractor can check and argue about honestly, which is what makes it a negotiating position rather than a posture. **Second, retention is worth far less than sponsors assume, in both directions.**

62,589 of interest saving over a two-year build is immaterial; retention's value is entirely as security for defect rectification, and it should be argued on that basis, against the alternative of a retention bond, which releases the cash to the contractor and substitutes a bank's credit for the withholding. **Third, and much the most dangerous: the second retention tranche falls after the commercial operations date.** Kestrel's 600,000 becomes payable twelve months after completion, which is inside the first operating year and outside any plausible availability period. If it is paid from operating cash, **CFADS** falls to $6,384,000 - 600,000 = 5,784,000$ and the **DSCR** at the first test falls to **1.1546 — below the 1.20 covenant**. Domain 10 measured Kestrel's annual headroom at **372,438**; a 600,000 retention release exceeds it by **227,562**. So a payment term agreed by a commercial team, in a contract, two years earlier, breaches a financial covenant. The remedies are all structural and all cheap if taken early: extend availability to cover retention releases, fund the releases into a dedicated retention account at completion, take a retention bond so no cash is withheld or released, or define **CFADS** to exclude construction-contract retention releases. What is not cheap is discovering the interaction in the first operating year, which is where it is normally discovered.

14.3.3 Change control and the marginal coverage of a variation

Definition. A **variation** (change order) alters the scope, price or time of a construction contract. In a corporate setting a variation has two numbers, cost and time. In a limited-recourse financing it has **four**: the price, the time, the **funding source** (which pocket pays — the contractor's, contingency, additional debt, additional equity), and the **coverage consequence** (what the variation does to the ratios the project is judged on). The third and fourth are the ones change-control procedures usually omit, and they are the ones that cannot be fixed later.

The test that connects them is the **marginal coverage of a variation**: whether the incremental **CFADS** a variation generates supports the incremental debt service its funding creates.

$$\text{Marginal DSCR} = \Delta \text{CFADS} \div \Delta \text{debt service}, \quad \text{where } \Delta \text{debt service} = \text{debt-funded cost} \div \text{AF}(r, n)$$

$$\text{Maximum coverage-neutral debt funding} = (\Delta \text{CFADS} \div \text{target DSCR}) \times \text{AF}(r, n)$$

WORKED EXAMPLE**Worked example 14.3.3 — the variation that creates value and destroys coverage.**

1. **Setup.** Kestrel's operator proposes an additional membrane train: capital cost **1,850,000**, adding **240,000** per year of **CFADS** for the project's remaining 25-year operating life. The loan runs 12 years at 6.0 % ($AF(0.06, 12) = 8.383844$); the board's appraisal rate is 8.0 % ($AF(0.08, 25) = 10.674776$); base **DSCR** is 1.2743 and the covenant is 1.20×. Assess the variation on value and on coverage, and determine how it should be funded.
2. **Formula.** $NPV = \Delta CFADS \times AF(0.08, 25) - \text{cost}$; $PI = PV/\text{cost}$; $\Delta \text{debt service} = \text{debt-funded amount} \div AF(0.06, 12)$; $\text{marginal DSCR} = \Delta CFADS \div \Delta \text{debt service}$; maximum coverage-neutral debt funding as above.
3. **Substitution.** $240,000 \times 10.674776 = 2,561,946$; $- 1,850,000$; $1,850,000 / 8.383844 = 220,663$; $240,000 / 220,663$; $(240,000 / 1.274303) \times 8.383844$.
4. **Result.** **NPV +USD 711,946** and **PI 1.3848** — comfortably value-accretive on Domain 4's tests. Funded **entirely by debt**, incremental debt service is **220,663** and the **marginal DSCR is 1.0876** — below the 1.20 covenant and far below the 1.2743 base. Funded **70/30** like every other use, the debt share is 1,295,000, incremental debt service **154,464** and the marginal **DSCR 1.5538** — accretive. The maximum debt funding that holds base coverage constant is $(240,000/1.274303) \times 8.383844 = \text{USD } 1,578,947$, being **85.35 %** of the cost; the residual **271,053** must come from equity or contingency. To be coverage-neutral at full debt funding the variation would need **281,200** per year of **CFADS**, **41,200** more than it delivers.
5. **Interpretation.** **A variation can be value-accretive and coverage-dilutive at the same time, and the funding decision follows the coverage test, not the NPV.** That is the sentence to carry out of this topic. The reason the two tests disagree is structural: **NPV** discounts 25 years of incremental cash at 8 %, while **DSCR** compares one year of incremental cash against debt service compressed into 12 years at 6 %. A long-lived, modestly-returning addition therefore looks good on value and thin on coverage, every time — and the ratio that binds is the one in the facility agreement. **The general rule is worth memorising in the form that makes it usable:** a variation is coverage-neutral if its debt-funded share does not exceed $\Delta CFADS/\text{target DSCR} \times AF(r, n)$ — here 85.35 % of cost — so at Kestrel's 70 % gearing the variation is comfortably accretive and at 100 % debt funding it is not. **Most variations are silently funded at 100 % from whatever is undrawn, which is the funding order nobody chose.** Third, the aggregate effect is small and therefore easy to wave through: fully debt-funded, this variation moves the blended **DSCR** from 1.2743 to **1.2665**, the covenant cash trigger from 6,011,562 to **6,276,357** and annual headroom from 372,438 to **347,643** — a loss of **24,795** of headroom, 6.66 % of it. One variation is nothing. Eight are a covenant. **The control that works is a threshold in the change-control procedure:** every variation above a stated value carries a computed marginal **DSCR** and a named funding source before approval, and the cumulative headroom consumed by approved variations is a reported line — the financing analogue of PML-AI Domain 4's baseline-drift test. **The professional caution:** the 240,000 of incremental **CFADS** is a forecast produced by the party proposing the variation, and a marginal **DSCR** of 1.0876 is inside the error bar of most operating forecasts. Where the coverage test is close, the honest conclusion is that the variation should not be debt-funded at all.

AI in this KA

Where it earns its place. Certification packs are large, repetitive and structured, which makes them good machine territory: cross-checking claimed quantities against the measurement schedule

and the previous certificate; detecting **certification drift** by tracking, period by period, the share of certified value attributable to achieved milestones, assessed percentages and off-site materials — a trend no monthly report currently shows and which a machine can produce for nothing; verifying that every off-site materials certification has a matching vesting certificate, segregation confirmation and insurance endorsement, and listing the exceptions; and computing the four numbers of a variation (price, time, funding source, marginal **DSCR**) at the point the variation is logged, so that the coverage consequence exists before the approval rather than after it.

Where it must not go. A **certification is a professional opinion with liability attached** and must not be generated, and an assessed percentage of completion must not be inferred from photographs or progress narrative and presented as a measurement. Entitlement questions — whether a claimed variation is a variation at all, whether the contractor bears the cost, whether a delay is excusable — are contractual and jurisdictional and belong to the certifier and to counsel.

Verification, concretely. Recompute one certificate end to end from measured quantities to net payment, including advance recovery and retention, and require agreement to the dollar; confirm the retention cap has not been exceeded cumulatively. Reconcile cumulative certified value to cumulative milestone value and separately identify the off-site balance. For every variation above the threshold, recompute Δ debt service and the marginal **DSCR** by hand and check the funding source recorded matches the funding actually drawn. Require that any tool computing a marginal **DSCR** print the $AF(r, n)$ it used and the target ratio it compared against — those two inputs carry the answer.

■ KEY TERMS — KA 14.3

Term	Meaning
Milestone certification	Value of milestones actually achieved; binary, lumpy, tied to contractual entitlement.
Measured / PoC certification	Value of work in place on measured quantities or assessed completion; requires judgment.
Cost-incurred certification	Value of contractor spend including off-site materials; funds the contractor's balance sheet.
Vesting certificate	Instrument transferring title in off-site materials to the SPV; with segregation and insurance, the condition of any off-site certification.
Certification drift	Progressive migration from milestone toward cost-incurred certification; converts secured lending into unsecured lending without a decision.
Advance payment / bond	Pre-mobilisation payment recovered from certifications, secured by a bond; a loan from the project to the contractor.
Retention / retention bond	Percentage withheld from certifications, capped and released in tranches; a bond substitutes bank credit for the withholding.
Marginal DSCR of a variation	$\Delta CFADS \div \Delta \text{debt service}$; coverage-neutral debt funding = $(\Delta CFADS / \text{target DSCR}) \times AF(r, n)$.

■ SAMPLE MCQS — KA 14.3

MCQ 14.3-A [14.3.1 · Application] A quarter's work comprises achieved milestones of 5,760,000 and one milestone worth 1,440,000 assessed at 92 % complete; the contractor has also procured 690,000 of off-site materials. Retention is 5 %. The senior debt advanced at 70 % gearing under a cost-incurred basis exceeds that under a milestone basis by:

A. USD 2,014,800

- B. USD 1,914,060
- C. USD 1,339,842 ✓ CORRECT
- D. USD 690,000

Rationale: $(7,774,800 - 5,760,000) \times 0.95 \times 0.70 = 1,339,842$. A is the gross certified spread, before retention and before the gearing split. B applies retention but not gearing. D counts only the off-site materials and omits the 92 % milestone.

MCQ 14.3-B [14.3.2 · Analysis] Kestrel's second retention tranche of 600,000 falls due twelve months after the commercial operations date and is paid from operating cash. The consequence is:

- A. none; retention is part of the EPC price already funded
- B. **CFADS** falls to 5,784,000 and the **DSCR** to 1.1546, breaching the 1.20 covenant, because the release exceeds the 372,438 of annual headroom by 227,562 ✓ CORRECT
- C. the **DSCR** is unaffected, since retention is a balance-sheet movement
- D. the release is deducted from debt service, so coverage improves

Rationale: The release is a cash outflow in an operating period, and coverage is computed on cash (Domain 10). A confuses being funded with being available — the availability period has ended. C misstates a cash payment as an accrual. D reverses the direction of the effect.

MCQ 14.3-C [14.3.3 · Application] A variation costs 1,850,000 and adds 240,000 a year of **CFADS**. The loan factor is $AF(0.06, 12) = 8.383844$ and base **DSCR** is 1.2743. The maximum debt-funded amount that leaves base coverage unchanged is closest to:

- A. USD 1,850,000
- B. USD 1,578,947 ✓ CORRECT
- C. USD 1,295,000
- D. USD 2,012,123

Rationale: $(240,000/1.274303) \times 8.383844 = 1,578,947$, being 85.35 % of the cost. A is full debt funding, which yields a marginal **DSCR** of 1.0876. C is the 70 % pro-rata debt share — inside the limit but not the limit. D applies **AF** to the full **ACFADS** without the coverage divisor, the sizing error of Domain 10, Exercise 10.1.

MCQ 14.3-D [14.3.3 · Analysis] A variation has an **NPV** of +711,946 at the board's 8 % rate and a marginal **DSCR** of 1.0876 against a 1.20× covenant if fully debt-funded. The correct conclusion is:

- A. approve and fund from the facility; a positive **NPV** is decisive
- B. reject; a marginal **DSCR** below the covenant disqualifies the variation
- C. approve, but cap debt funding at the coverage-neutral 1,578,947 and fund the residual 271,053 from equity or contingency ✓ CORRECT
- D. approve and renegotiate the covenant

Rationale: Value and coverage answer different questions and both bind; the funding mix is the lever that satisfies both (14.3.3). A ignores the covenant. B discards 711,946 of value that a funding decision can capture. D proposes to renegotiate a covenant over 271,053, which no lender would price kindly.

MCQ 14.3-E [14.3.1 · Evaluation] The contractor asks for **690,000** of membrane racks, paid for and stored at the vendor's works, to be certified on a cost-incurred basis. The SPV's finance team

supports the request, noting that the only consequence is a small amount of additional capitalised interest. Reviewing the request, what should be challenged first?

- A. the additional capitalised interest, which the contractor rather than the SPV should bear
- B. whether vesting of title in the SPV, identification and segregation at the vendor's works, and insurance in the SPV's name are all in place — the certification advances 458,850 of senior debt against goods in a third party's possession, which is a security question, not a cost question ✓ CORRECT
- C. the independent engineer's 92 % assessment of the incomplete milestone, since an assessed percentage is an opinion that drifts upward under schedule pressure
- D. nothing — the materials are paid for, identifiable and represent real value to the project

Rationale: $690,000 \times 0.95 \times 0.70 = 458,850$ of debt advanced against work not in place, and absent vesting, segregation and insurance the money has bought a claim in someone else's liquidation (14.3.1). A is the finance team's own framing and is the specific error the topic names: pricing a security question as a cost question is how certification drift gets conceded, one certificate at a time. C raises a real and separate concern about the measured basis, but it is not what this request changes. D confuses the vendor's title with the SPV's. Whether a given vesting arrangement in fact defeats the vendor's insolvency, and what has to be filed or registered for it to do so, is a question of the law governing the goods and the contract on which this book states no jurisdiction's position; the reviewer's job is to require the question be put to counsel before the certificate is signed, not to answer it (14.3.1).

MCQ 14.3-F [14.3.2 · Evaluation] The contractor requests the contracted **10 %** advance payment — **4,800,000** on the 48,000,000 price, secured by an advance payment bond — and declines any reduction in the contract price. Re-running the funding model shows the advance costs **254,597** of capitalised interest: **5.30 %** of the advance and **0.53 %** of the EPC price. The SPV's finance lead proposes refusing the advance. The soundest position is to:

- A. refuse — an advance payment is a loan from the project to the contractor, and a project financing exists to fund the works rather than the contractor's balance sheet
- B. treat the 254,597 as the price of the advance and negotiate against it: where the contractor's own cost of funds exceeds the project's the advance creates value for the transaction as a whole, so the defensible outcomes are a price reduction of at least 0.53 %, a smaller advance, or an accepted and recorded cost — not a refusal on principle ✓ CORRECT
- C. accept — the advance payment bond covers the amount advanced, so the SPV carries neither cost nor exposure
- D. accept, and recover the 254,597 from the delay-damages account if the contractor completes late

Rationale: An advance is a priced loan, and pricing it converts a posture into a position the contractor can check and argue about honestly (14.3.2). A is the reflex and forgoes a genuine joint gain wherever the contractor's marginal cost of funds is the higher of the two. C confuses a bond, which secures **recovery** if the advance is not earned, with the **carrying cost** of having advanced it — the 254,597 is incurred whether or not the bond is ever called, and it is **4.068 times** the 62,589 that retention saves in the other direction. D applies damages calibrated to delay against a cost caused by a payment term, and helps itself to a cap Domain 12 reserves for a different head.

MCQ 14.3-G [14.3.1 · Comprehension] Setting the amounts aside, which statement best explains why **milestone** certification is the basis most closely aligned with the lenders' security?

- A. it produces the smallest certified figure, so the least money leaves the account

- B. a milestone has either been achieved or has not, so certified value corresponds to a completed thing the security attaches to; a measured percentage is an opinion, and cost incurred may be goods in a third party's possession ✓ CORRECT
- C. it is the only basis an independent engineer is professionally qualified to certify
- D. it removes the need for retention, since nothing is certified until it is complete

Rationale: The three bases differ in **what they measure** — an achieved contractual event, an assessed percentage, and the contractor's spend — and only the first is binary and contractually defined, which is why 92 % of a milestone is worth exactly nothing and why that harshness is the alignment (14.3.1). A states a consequence rather than the reason, and a smaller figure is not by itself a virtue. C is false: certifiers apply all three, and the measured basis is the standard one on long linear works. D confuses the certification basis with retention, which secures defect rectification and is withheld on any basis.

■ SELF-CHECK — KA 14.3

1. State the three conditions that make off-site materials certification defensible. — Vesting of title in the SPV, identification and segregation at the vendor's works, and insurance in the SPV's name including against vendor insolvency.
2. What does Kestrel's 10 % advance payment cost, and what is the negotiating consequence? — 254,597 of capitalised interest, 5.30 % of the advance and 0.53 % of the EPC price; the advance should be priced, not simply refused or granted.
3. Give the coverage-neutral funding rule for a variation. — Debt funding must not exceed $\Delta CFADS / \text{target } DSCR \times AF(r, n)$ — for Kestrel's train, 1,578,947, or 85.35 % of cost.

KNOWLEDGE AREA 14.4

Schedule delay, lender reporting and completion tests

Topics: 14.4.1 the funded cost of a month of slip · 14.4.2 coverage at a calendar-fixed first repayment date · 14.4.3 lender reporting and the completion tests.

14.4.1 The funded cost of a month of slip

Definition. The **funded cost of delay** is the cash the project must raise, per unit of time of slip, to keep paying while it is not yet earning. It is a strict subset of the **economic cost of delay**, which adds the cash the project would have earned. The distinction sounds pedantic and is worth millions: **the drawdown and in-balance tests see only the funded cost, and the liquidated damages that under-recover the economic cost can substantially over-recover the funded one.**

Domain 5 (KA 5.4.2) priced a slip at the commercial operations date at **24,733.33 per day** — 7,000 of interest on a fully drawn 42,000,000 plus 17,733.33 of forgone **CFADS**, on a 30/360 basis — and Domain 8 (KA 8.4.2) priced a slip declared during construction, where escalation on unbought scope appears and forgone revenue is deferred rather than lost. This topic completes the family by splitting the same event along a different axis: **not economic against contractual, but funded against forgone.**

WORKED EXAMPLE**Worked example 14.4.1 — a month of extension at Kestrel's commercial operations date.**

- 1. Setup.** At the scheduled commercial operations date the facility is fully drawn at **42,000,000** at **6.0 %**. Prolongation costs the SPV bears directly: extended owner's team and site supervision **138,000** per month, extended construction all-risks and delay-in-start-up premium **46,000**, and independent engineer, facility agent and technical adviser monitoring fees **21,000**. Operating **CFADS** would have been **6,384,000** per year. Delay damages are **20,000 per day**, capped at **4,800,000** (Domain 12). The availability period runs to **six months** beyond the scheduled commercial operations date. Compute the funded and economic costs per month, the recovery each enjoys, and the exposure the mismatch creates.
- 2. Formula.** Funded cost = interest on drawn debt + prolongation costs = $42,000,000 \times 0.06/12 + 138,000 + 46,000 + 21,000$. Forgone **CFADS** = $6,384,000/12$. Full economic cost = funded cost + forgone **CFADS**. Recovery = damages ÷ cost. Months covered = damages cap ÷ monthly cost.
- 3. Substitution.** $210,000 + 138,000 + 46,000 + 21,000$; $6,384,000/12 = 532,000$; $415,000 + 532,000$; $600,000/415,000$; $600,000/947,000$; $4,800,000/415,000$; $4,800,000/947,000$.
- 4. Result.**

Per month of slip at the commercial operations date	USD	Damages recovery
Interest on drawn debt (42,000,000 at 6.0 %)	210,000	
Extended owner's team and site supervision	138,000	
Extended all-risks and delay-in-start-up premium	46,000	
Independent engineer, agent and adviser fees	21,000	
Funded cost of delay	415,000	144.58 %
Forgone CFADS (6,384,000 ÷ 12)	532,000	
Full economic cost of delay	947,000	63.36 %
Domain 5's basis (interest + forgone CFADS only)	742,000	80.86 %
Delay damages at 20,000 per day (30 days)	600,000	

Damages of 4,800,000 cover **11.5663 months** of funded cost but only **5.0686 months** of full economic cost. Over an eight-month slip — the day the cap binds — the funded cost is **3,320,000** against damages of 4,800,000, a **surplus of 1,480,000**, while the full economic cost is **7,576,000**, leaving **2,776,000** uncovered. The availability period funds only $6 \times 415,000 = 2,490,000$ of extension cost. **5. Interpretation. One damages rate, three coverage percentages — 144.58 %, 80.86 % and 63.36 % — and which one you quote depends entirely on which cost basis you are defending.** That is the professional content, and it explains a pattern practitioners see and misdiagnose: a delayed project whose drawdown tests keep passing while equity value is being destroyed. The in-balance test measures funds against cost-to-complete, and forgone revenue is in neither column; a delay that over-recovers the funded cost therefore leaves the facility comfortable and the sponsor poorer, month after month, with no covenant to notice it. **The report must carry both numbers or it is not a report.** Second, note the two constraints that bind before the damages cap does, because they are the ones sponsors miss. **The availability period binds at six months,**

not eleven and a half: beyond month six the facility no longer funds the extension and the sponsor pays 415,000 a month in cash even though damages will eventually reimburse it — a **timing** exposure of up to $(11.5663 - 6) \times 415,000 =$ about **2,310,000** that is invisible in a coverage table. And **damages are recovered later than the cost is incurred**, often much later and sometimes only after adjudication, so the sponsor is financing the contractor's breach in the meantime. Third, the composition is instructive: **prolongation costs the SPV bears directly — 205,000 a month — are 49.4 % of the funded cost and are entirely absent from Domain 5's calibration basis.** A damages rate calibrated on interest plus forgone **CFADS** alone therefore understates the loss by those 205,000, and the correct calibration statement is that Kestrel's full monthly cost is 947,000, or **31,566.67 per day** — against which 20,000 recovers 63.36 %, not the 80.86 % Domain 5's narrower basis suggests. Both figures are honest; the negotiation should use the wider one, and say so.

14.4.2 Coverage at a calendar-fixed first repayment date

The mechanic. Facility agreements set repayment dates. Some set them by reference to the **actual** commercial operations date; many set them by **calendar date**, fixed at financial close with a cushion for expected slip. A calendar-fixed first repayment date has a consequence that almost no construction report models: **a slip does not postpone the first instalment, it shortens the operating period that funds it.** With m months of slip, the first annual test sees $(12 - m)/12$ of a year's **CFADS** against a full year's debt service.

WORKED EXAMPLE

Worked example 14.4.2 — Kestrel's commercial operations date slips four months.

- Setup.** Debt service **USD 5,009,635.23** falls due twelve months after the scheduled commercial operations date, by calendar date. Annual operating **CFADS 6,384,000**, accruing evenly from the actual commercial operations date. The covenant is **1.20×**; the six-month debt service reserve holds **2,504,818**. Delay damages of **20,000 per day** are recoverable, capped at 4,800,000. Compute the **DSCR** at the first test for a four-month slip, the reserve consumption, and the slip at which each threshold is crossed.
- Formula.** $\text{CFADS at first test} = 6,384,000 \times (12 - m)/12$; $\text{DSCR} = \text{CFADS} \div 5,009,635.23$. Breakevens solve $6,384,000 \times (12 - m)/12 = k$ for k equal to the covenant cash trigger ($1.20 \times$ debt service), to debt service, and to debt service less the reserve.
- Substitution.** $6,384,000 \times 8/12 = 4,256,000$; $\div 5,009,635.23$. Covenant: $12 \times (1 - 6,011,562.28/6,384,000)$. Payment: $12 \times (1 - 5,009,635.23/6,384,000)$. With reserve: $12 \times (1 - (5,009,635.23 - 2,504,817.62)/6,384,000)$.
- Result.**

Slip (months)	CFADS at first test (USD)	DSCR	Shortfall vs debt service (USD)	Share of DSRA consumed
0	6,384,000	1.2743	—	—
1	5,852,000	1.1681	—	—
2	5,320,000	1.0620	—	—
3	4,788,000	0.9558	221,635	8.85 %
4	4,256,000	0.8496	753,635	30.09 %
6	3,192,000	0.6372	1,817,635	72.57 %
8	2,128,000	0.4248	2,881,635	115.04 %

Breakevens: the **1.20× covenant is breached beyond 0.7001 months — 21.00 days**; the project can no longer pay debt service from operating cash beyond **2.5834 months (77.50 days)**; and it can no longer pay from cash plus a fully funded reserve beyond **7.2917 months (218.75 days)**. If delay damages are creditable to CFADS, a four-month slip yields $20,000 \times 120 = 2,400,000$ of damages, lifting CFADS to **6,656,000** and the DSCR to **1.3286 — 0.4791 higher**, and above the undelayed base case. 5. **Interpretation. Three weeks of slip breaches the covenant.** That is the result, and it is the single most under-modelled number in construction-phase finance. Nothing has gone wrong with the project: the plant works, the tariff is contracted, CFADS is running exactly at forecast on an annualised basis, and the covenant fails at the first test because the test period contains less operating time than the obligation period. Sponsors discover this at the first compliance certificate, which is the worst possible moment, and the discovery is unforced. **Second, whether delay damages count in CFADS is worth 0.4791 of coverage — more than the entire distance from the base case to the covenant.** Domain 10 established that CFADS is a defined term and that its documented construction governs every ratio built on it; this is that principle at its most valuable. Damages at 20,000 a day are 600,000 a month against forgone CFADS of 532,000, so they **over-compensate** the coverage effect of delay, and the sign of the delay's impact on the first test flips on a definitional clause. A leader who negotiates one thing in the CFADS definition should negotiate this. Note the tail carefully, though: once the damages cap binds at eight months the damages line stops growing while the CFADS line keeps shrinking, so the damages-credited coverage peaks at **1.3829** and then falls, crossing 1.20 at **9.7226 months** and 1.00 at **11.6059** — the cap converts a comfortable position into a cliff. **Third, the reserve is smaller protection than it looks.** A six-month debt service reserve does not survive six months of slip; it survives **7.2917 months** only because operating cash covers most of the obligation, and it is consumed 30.09 % by a four-month slip that also breaches the covenant and must then be replenished ahead of any distribution (Domain 10, KA 10.3.3). **Fourth, the fixes are all structural and all cheap at signing.** Set the first repayment date by reference to the actual commercial operations date with a long-stop; or annualise the first test on a look-forward basis; or size the reserve on the delay scenario rather than on a convention of six months; or provide expressly that delay damages and delay-in-start-up insurance proceeds are CFADS. Each is a drafting point worth more than the margin. **The professional caution:** none of these fixes should be pursued quietly as a technical amendment. A lender asked to move a repayment date late in a delayed project reads the request as news about the project, which is why the structure is negotiated before the delay and the disclosure discipline of Domain 10, KA 10.4.4 applies from the first month of slip.

Coverage at a calendar-fixed first repayment date

Kestrel: CFADS 6,384,000 a year, debt service 5,009,635.23, DSRA 2,504,818, damages 20,000 a day capped at 4,800,000




Fig 14.4.1 — Coverage at a calendar-fixed first repayment date

14.4.3 Lender reporting and the completion tests

The reporting obligation. Construction-phase information covenants are heavier than operating ones because the security does not yet exist. The standard pack, monthly or quarterly: certified progress against the programme, with the certifier's own commentary; cost incurred against the sources and uses, restated per 14.1.1; the cost-to-complete and the in-balance statement (14.2.1); the contingency position with coverage on the remainder (14.2.2); the variation and claims registers with movements; the schedule position, critical path and forecast commercial operations date; health, safety and environmental performance and any reportable incident; insurance status and claims; and the compliance certificate signed by named officers. Two disciplines make the pack useful rather than ceremonial: **the same numbers reconcile across sections** — the contingency balance in the contingency section equals the contingency line in the restated sources and uses, and a pack in which they differ has told the lender something the sponsor did not intend — and **the forecast commercial operations date is stated as a single date with a stated confidence, not as "on programme"**, because "on programme" is the phrase that precedes every delay notification.

The completion sequence. Completion is not one event, and conflating its stages is the commonest drafting and reporting error of the phase. **Mechanical completion** confirms the plant is built and can be safely energised. **Commissioning and reliability testing** demonstrates that it runs. **Performance testing** demonstrates that it runs to guarantee — output, quality, efficiency, consumption. **Provisional acceptance or the commercial operations date** is the contractual moment from which revenue accrues and, in the financing, the moment the construction facility converts to term debt, the operating covenant regime begins, the completion guarantees and cost-overrun support fall away, the first retention tranche is released and the debt service reserve must be funded. **Final acceptance** follows the defects liability period and releases the second retention tranche. The financing attaches consequences to each, and the sponsor who has read only the EPC contract's definitions will be surprised by the facility's.

Conditional and partial completion. Plants routinely complete late, or on time with a punch list, or on time at less than guaranteed output. The first is KA 14.4.1 and 14.4.2. The second is managed by valuing the punch list and withholding, which is arithmetic. The third is the interesting case, because a permanent output shortfall is a permanent **CFADS** shortfall and therefore a permanent coverage problem, remedied by **performance liquidated damages** or a **buy-down** — a lump sum, usually applied to prepay debt, calibrated so that the financing survives a smaller plant (Domain 12, KA 12.1.3).

WORKED EXAMPLE

Worked example 14.4.3 — the buy-down that restores which coverage?

- Setup.** Kestrel completes on time but the performance test settles at an operating **CFADS** of **5,900,000** rather than 6,384,000. Debt outstanding at completion **42,000,000**, $AF(0.06, 12) = 8.383844$, covenant **1.20×**, base **DSCR 1.2743**, performance damages cap **4,800,000**. Compute the coverage as completed and the buy-down that restores (i) the covenant and (ii) the coverage the lenders originally priced.
- Formula.** $DSCR = CFADS \div (debt \div AF)$. Supportable debt at a target ratio = $(CFADS \div target) \times AF$. Buy-down = $42,000,000 - \text{supportable debt}$.
- Substitution.** $5,900,000 / (42,000,000 / 8.383844); (5,900,000 / 1.20) \times 8.383844; (5,900,000 / 1.274303) \times 8.383844$.
- Result.** As completed the **DSCR** is **1.1777** — the **covenant is breached from the first test**. Restoring the 1.20× covenant requires debt of **41,220,566**, a buy-down of **779,434**. Restoring the 1.2743 base coverage requires debt of **38,815,789**, a buy-down of **3,184,211**. Both sit inside the 4,800,000 performance cap; the full cap would take debt to 37,200,000 and coverage to **1.3297**.
- Interpretation.** The buy-down that restores the covenant is a quarter of the buy-down that restores the coverage the lenders priced, and the difference — **2,404,777** — is settled by drafting, not by negotiation after the test. That is the transferable lesson. A buy-down formula expressed as "the amount required to restore the **DSCR** to the covenant level" is worth 779,434 here; one expressed as "to restore the base-case **DSCR** in the financial model at close" is worth 3,184,211; and the two clauses look almost identical to a reader who is not computing them. The sponsor should also see what the difference costs it: at 41,220,566 of debt the project sits exactly on its covenant with zero headroom, so the first bad operating year breaches — a position no sponsor should accept in exchange for keeping 2,404,777 of contractor money that would otherwise have deleveraged the project. **Second, note that the buy-down is a prepayment, not compensation.** It repairs coverage by shrinking debt, so it repairs the lender's position directly and the sponsor's only through the coverage headroom it restores; the equity return still falls, because the plant is permanently smaller. **Third, the cap is the binding question again.** Here both buy-downs fit inside 4,800,000, but a 10 % shortfall rather than a 7.6 % one would not, and the residue would sit on equity exactly as Domain 12 computed for the delay head. The professional sequence at a failed performance test is therefore: compute the permanent **CFADS** effect; compute both buy-downs; read the clause to see which one you are entitled to; check it against the cap and against the aggregate cap after any delay claim; and only then open the negotiation.

AI in this KA

Where it earns its place. The construction report pack is a reconciliation problem, and machines reconcile. Cross-checking that every figure appearing in two sections of the pack agrees, and listing

the exceptions, is the single highest-value automation available in this knowledge area, and it catches the defect that most embarrasses sponsors. Beyond that: recomputing the coverage-at-first-repayment table (14.4.2) at every data date from the current forecast commercial operations date, so that the covenant breakeven in days of slip is a live number rather than an annual discovery; maintaining the delay-cost ledger with funded and economic columns and the cumulative damages position against the cap and its binding day; and drafting the narrative sections of the pack from the underlying registers, which reduces the drift between what the numbers say and what the commentary says.

Where it must not go. A **forecast commercial operations date** is a schedule opinion belonging to the certifier and the delivery organisation, and a model that produces one from trend data has produced an input to that opinion, not a substitute for it. Whether a delay is excusable, whether an extension of time is due, whether a completion test has been passed, and what remedies a failed test entitles anyone to are contractual determinations for the certifier and counsel. And no machine output may constitute the compliance certificate: that is signed.

Verification, concretely. Recompute the **DSCR** at the first repayment date by hand for the current forecast slip and confirm the covenant breakeven in days; require that any tool reporting it state whether delay damages have been treated as **CFADS** and cite the definition clause relied on. Recompute the monthly funded and economic costs of delay independently and confirm the damages recovery percentages against both. For a buy-down, recompute the supportable debt at both target ratios and check which the clause specifies. Tie the cumulative damages position to the cap and its binding day, and confirm nothing in the pack assumes recovery beyond it.

■ KEY TERMS — KA 14.4

Term	Meaning
Funded cost of delay	Cash the project must raise per period of slip: interest on drawn debt plus prolongation costs. Excludes forgone CFADS .
Economic cost of delay	Funded cost plus forgone CFADS ; the correct calibration basis for delay damages.
Availability period	The window in which the facility may be drawn; often binds on a delay long before the damages cap does.
Calendar-fixed repayment date	A first instalment set by date rather than by actual completion; a slip shortens the operating period that funds it.
Mechanical completion / commissioning / performance test / commercial operations date / final acceptance	The completion sequence; the financing attaches distinct consequences to each.
Buy-down	A lump sum, usually applied to prepay debt, calibrated so the financing survives a permanently smaller plant.

■ SAMPLE MCQS — KA 14.4

MCQ 14.4-A [14.4.2 · Application] Kestrel's first instalment of 5,009,635.23 falls on a fixed calendar date twelve months after the scheduled commercial operations date. **CFADS** accrues evenly from actual completion at 6,384,000 a year. If completion slips four months, the **DSCR** at the first test is:

A. 1.2743

- B. 0.8496 ☒ **CORRECT**
- C. 1.1681
- D. 0.4248

Rationale: $6,384,000 \times 8/12 = 4,256,000$; $\div 5,009,635.23 = 0.8496$. A assumes the test date moves with completion. C is a one-month slip. D is an eight-month slip.

MCQ 14.4-B [14.4.2 · Analysis] With a 1.20× covenant, debt service of 5,009,635.23 and CFADS of 6,384,000 a year accruing from actual completion, the slip at which the first covenant test fails is closest to:

- A. six months
- B. three weeks ☒ **CORRECT**
- C. two months
- D. it cannot fail, since annualised CFADS is unchanged

Rationale: $12 \times (1 - 6,011,562.28/6,384,000) = 0.7001$ months, 21.00 days. A and C overstate the tolerance by an order of magnitude. D is the error the calculation exists to kill: the covenant is tested on the period, not on an annualised run rate.

MCQ 14.4-C [14.4.1 · Analysis] Kestrel's funded cost of a month of slip at completion is 415,000 and its full economic cost 947,000; delay damages are 600,000 a month. The most useful observation for a board is:

- A. damages recover 80.86 % of the cost of delay
- B. damages over-recover the funded cost by 44.58 % while recovering only 63.36 % of the economic cost, so the drawdown tests keep passing while equity value is destroyed ☒ **CORRECT**
- C. damages fully cover the delay, so no action is required
- D. the delay is cost-neutral because damages exceed the funded cost

Rationale: The two bases give 144.58 % and 63.36 % recovery, and only the second is a statement about value (14.4.1). A quotes Domain 5's narrower basis, which omits the 205,000 of monthly prolongation cost. C and D mistake a passing funding test for an absence of loss.

MCQ 14.4-D [14.4.3 · Application] A performance test settles CFADS at 5,900,000 against debt of 42,000,000, $AF(0.06, 12) = 8.383844$. The buy-down required to restore the base-case DSCR of 1.2743 is closest to:

- A. USD 779,434
- B. USD 3,184,211 ☒ **CORRECT**
- C. USD 4,800,000
- D. nil, since 1.1777 exceeds 1.00

Rationale: $42,000,000 - (5,900,000/1.274303) \times 8.383844 = 3,184,211$. A restores only the 1.20× covenant, leaving zero headroom. C is the performance damages cap, not the calibrated amount. D confuses paying debt service with satisfying a covenant (Domain 10, KA 10.2.1).

MCQ 14.4-E [14.4.2 · Evaluation] The term sheet provides a calendar-fixed first repayment date. On Kestrel's figures the 1.20× covenant fails beyond **0.7001 months** of slip, and the delivery team

regards a slip of up to four months as a live risk. Four amendments are available and the sponsor can press for one. Which should be pressed first?

- A. size the debt service reserve on the four-month slip scenario rather than on the six-month convention
- B. set the first repayment date by reference to the actual commercial operations date, with a long-stop — it removes the mismatch between the test period and the obligation period instead of funding its consequences ✓ CORRECT
- C. rely on delay damages being creditable to **CFADS**, which at a four-month slip is worth 0.4791 of coverage and turns a breach into a 1.3286 ratio
- D. accept the calendar-fixed date and request a covenant waiver if the slip occurs

Rationale: The defect is that the first test period contains less operating time than the obligation it is tested against, and only B removes it (14.4.2). A is defensible and cheap, but a reserve pays an instalment — it does not raise **CFADS**, so the covenant still fails at 0.7001 months and the reserve must then be replenished ahead of any distribution. C is genuinely valuable and worth negotiating alongside B, but it is a protection that expires: once the 4,800,000 cap binds at eight months the damages line stops growing while **CFADS** keeps shrinking, so the damages-credited ratio peaks at 1.3829 and re-crosses 1.20 at 9.7226 months. D is the worst available course — a waiver requested inside a delayed project is read as news about the project.

MCQ 14.4-F [14.4.1 · Evaluation] The works are a month late at the commercial operations date. The contractor's negotiator argues that the contracted **20,000 a day** — **600,000** a month — is generous, because it recovers **144.58 %** of the **415,000** the project must actually raise while it is not yet earning. The soundest response is to:

- A. accept the point — a damages rate that over-recovers the cash the project must raise is by definition adequate, and the drawdown and in-balance tests confirm it
- B. reject the framing: the funded cost excludes the **532,000** a month of forgone **CFADS**, so against the full economic cost of **947,000** the same rate recovers **63.36 %** — the signature of a project whose funding tests keep passing while equity value drains, which is the loss a damages rate exists to compensate ✓ CORRECT
- C. reject the rate on the ground that a recovery above 100 % shows the sum to be a penalty rather than a genuine pre-estimate of loss
- D. quote **80.86 %**, the recovery on interest plus forgone **CFADS**, as the neutral middle figure between the two positions

Rationale: One rate produces three recovery percentages, and the choice of basis is the whole argument: the economic cost is the correct calibration basis, while the drawdown and in-balance tests see only the funded one, which is why a delayed project can pass every test while destroying value (14.4.1). A mistakes a passing funding test for an absence of loss. C imports a legal conclusion the arithmetic cannot support — whether and how a contractual damages provision is enforceable is a question of the law governing the particular contract, on which this book states no jurisdiction's position, and a recovery above 100 % of one cost basis says nothing about the character of the sum. D is honest arithmetic on Domain 5's narrower basis and understates the monthly loss by the **205,000** of prolongation cost the SPV bears directly — **49.4 %** of the funded cost — so it is a figure to disclose, not the figure to negotiate on.

MCQ 14.4-G [14.4.3 · Comprehension] Which statement best describes what a **buy-down** does and does not do when a plant completes on time at less than guaranteed output?

- A. it compensates equity for the output permanently lost, restoring the return the sponsors priced

B. it is a lump sum, usually applied to prepay debt and calibrated so the financing survives a permanently smaller plant — repairing the lenders' coverage directly and equity's only through the headroom it restores; the equity return still falls, because the plant is smaller

✓ **CORRECT**

C. it is a reserve the contractor funds against the possibility of future underperformance

D. it replaces the delay-damages head once the commercial operations date has passed

Rationale: A buy-down is a **prepayment**, not compensation: it shrinks the debt so that a smaller **CFADS** still supports it, which is why the drafting question — restore the covenant level, or restore the base-case coverage — is worth the difference between the two amounts (14.4.3). A is the misreading that makes a buy-down look like a settlement of equity's claim. C describes a reserve, which is funded before an event rather than paid after a failed test. D confuses two heads of damages, each with its own sub-cap under one aggregate cap (Domain 12, KA 12.1.2).

■ SELF-CHECK — KA 14.4

1. Distinguish the funded and economic costs of a month of Kestrel's delay, with figures. — Funded 415,000 (interest 210,000 plus 205,000 of prolongation); economic 947,000, adding 532,000 of forgone **CFADS**. Damages of 600,000 recover 144.58 % and 63.36 % respectively.
2. Why does a three-week slip breach a 1.20× covenant on an otherwise perfect project? — A calendar-fixed first repayment date shortens the operating period funding a full year's debt service; $12 \times (1 - 6,011,562/6,384,000) = 0.7001$ months.
3. What is the drafting difference between the two buy-downs, in money? — 2,404,777: restoring the 1.20× covenant costs 779,434, restoring the 1.2743 base coverage costs 3,184,211.

— Advanced topics — Domain 14

14.A.1 The availability period, long-stop dates and the commitment that lapses

An **availability period** is the window in which a facility may be drawn; a **long-stop date** is the date by which completion must occur before defined consequences follow. Both are dates set at close against a programme that has not yet started, and both are routinely set with a cushion calibrated to optimism. The construction-phase consequence is asymmetric and often misunderstood: **an expired availability period does not accelerate the loan, it simply stops funding** — the undrawn commitment lapses and every remaining use becomes an equity obligation. For Kestrel, a six-month cushion funds $6 \times 415,000 = 2,490,000$ of extension cost against delay damages that would cover **11.5663 months**, so the binding constraint on a delay is the availability period and not the damages cap, and the exposure is a **timing** exposure of roughly 2,310,000 rather than a loss. Three practices follow. Model the availability period against the P80 completion date, not the programme date. Check that the availability period covers every use that falls after completion — Kestrel's second retention tranche of 600,000 falls twelve months after the commercial operations date and is outside any plausible window (KA 14.3.2). And treat an availability-period extension as a pre-agreed mechanic where possible, because a request made during a delay is priced as news.

14.A.2 Certifying value while liability is disputed

The hardest recurring problem in construction monitoring is that certification and entitlement move on different clocks. Work is in place, the SPV disputes that the contractor is entitled to be paid for it,

and the draw request must nonetheless state a number. Three conventions are in use and each has a cost. **Certify and reserve:** the certifier values the work and the certificate records the dispute, so cash moves and the argument continues — which protects the programme and funds a position the SPV may later have to recover. **Withhold and escalate:** nothing is certified, which protects the money and stops the site, converting a commercial dispute into a schedule loss at 415,000 a month of funded cost and 947,000 of economic cost. **Certify into escrow:** the funds are drawn and held, which costs the interest and preserves both positions — the compromise, and the one that requires the facility to permit a drawing into an account the SPV does not control. The finance leader's contribution here is not legal but arithmetical: **price the three options before the meeting**, because the ordinary failure mode is to withhold on principle for two months and discover that principle cost 1,894,000 of economic value against a claim worth 1,260,000.

14.A.3 The reviewer's drawdown eye

Invariants to test on any construction monitoring pack. Drawn-to-date ties to the facility agent's records, not to the model. Cumulative debt and equity percentages of commitment are equal under pro-rata funding, and any divergence traces to a documented funding order. Available commitment is undrawn debt plus uncalled equity and **excludes** contingency, which is a use. The restated sources-and-uses columns reconcile, and any imbalance is explained in cash terms rather than absorbed. Capitalised interest to date reproduces Domain 8's area rule from the profile, the rate and the gearing, to the dollar; interest is computed on opening, not closing, balances. **CPI** is reported **separately** for fixed-price and owner-retained scope, and equals 1.000 on milestone-certified fixed-price scope; no blended index feeds a **BAC/CPI** forecast. The lender's cost-to-complete contains remaining committed value, approved variations, assessed claim exposure, a bottom-up owner-scope estimate **and** remaining financing costs, and reconciles to the **EAC**-based **CTC** through an explicit bridge. Contingency coverage on the remainder is reported with its denominator itemised, and the in-balance shortfall and the contingency shortfall tell a consistent story. Certified value reconciles to milestone value with the off-site materials balance separately identified, and every off-site amount has vesting, segregation and insurance. Retention held has not exceeded its cap, and each release tranche has a funding source that is not operating cash. Every variation above the threshold carries a marginal **DSCR** and a funding source, and cumulative headroom consumed by variations is reported. The delay ledger shows funded **and** economic costs and the cumulative damages position against the cap and its binding day. And the **DSCR** at the first repayment date is computed from the current forecast completion date, with the covenant breakeven stated in days and the treatment of delay damages in **CFADS** cited to a clause.

— Industry variations — Domain 14

- **Water and desalination.** Long commissioning and reliability-test periods mean the gap between mechanical completion and the commercial operations date is months rather than weeks, so the calendar-fixed repayment-date problem of KA 14.4.2 is at its sharpest; permit conditions (discharge, brine outfall) generate owner-retained variations late in the programme, exactly where contingency coverage on the remainder is thinnest.
- **Solar and wind, contracted power.** Modular construction gives smooth, measurable progress and short commissioning, so certification is comparatively easy — but equipment is procured early and in bulk, which makes **off-site materials certification** the dominant exposure and vesting the dominant control. Grid-connection dates are owner-retained risk and are the usual cause of a commercial operations date slip the EPC contractor does not pay for.

- **Transport concessions.** Long linear works, extensive land and utility interfaces, and measured rather than milestone certification, so PoC judgment dominates and the certifier's independence is the whole control. Variations are numerous and small, which is precisely the regime in which cumulative headroom consumption (KA 14.3.3) escapes notice.
- **Digital infrastructure — data centres.** Very long lead times on electrical and cooling equipment, so advance payments and off-site certification are structural rather than exceptional, and the vesting question of Case study B is a first-order credit issue. Phased handover means the completion sequence is repeated per hall, and the facility must define whether revenue from an early phase is CFADS before overall completion.
- **Oil, gas and process plant.** Performance testing is elaborate and multi-parameter (throughput, yield, energy consumption, emissions), so partial completion and buy-down arithmetic (KA 14.4.3) is a normal rather than exceptional outcome, and the interaction of delay and performance sub-caps under an aggregate cap (Domain 12, KA 12.1.2) is tested in practice.
- **Social infrastructure PPPs — availability-based.** Payment begins on availability rather than output, so a delay is pure revenue deferral with no volume dimension; the sharp edge is that unitary-charge deductions begin immediately at service commencement, so a project that completes late and commissions imperfectly is penalised twice, and the contingency held for the commissioning period must cover both.

— Case study — Domain 14: the quarter-five draw that did not fund (water / desalination)

Situation. Kestrel Water SPC reached the end of construction quarter five with certified progress at **61 %**, cumulative certified spend of **33,945,403**, and a monthly report whose headline was that contingency was **58.85 % drawn against 61.00 % progress** — "consumption proportionate, no funding issue arising". The same report showed a blended CPI of **0.949821** and a BAC/CPI forecast of **54,326,038** against a BAC of 51,600,000, described as "a 2.7 million forecast overrun within the funded contingency of 3,645,403". Two quarters had passed on that reading. The quarter-five draw request was submitted for **9,924,564**.

What happened. The lenders' technical adviser declined to certify. Three findings, each independently sufficient. **The CPI was blended across scopes with different cost-risk ownership.** Of the 2,726,038 of uplift in the BAC/CPI forecast, **2,535,849** was attributed to a fixed lump-sum EPC scope certified against milestones — where CPI is 1.000 by construction and cannot overrun — and only **190,189** to the owner-retained scope, which was running at a scope CPI of **0.6000** and had already consumed **1,680,000** of contingency. Disaggregated, the bottom-up remaining owner-retained estimate was **2,400,000** against a remaining budget of 1,080,000. **The cost-to-complete omitted three lines earned value cannot see.** On a commitment basis it was $18,720,000 + 840,000 + 1,260,000 + 2,400,000 + 1,436,674 = 24,656,674$ against available commitment of $15,910,254 + 6,818,680 = 22,728,934$ — out of balance by **1,927,740**. **And the contingency test failed independently.** Known committed claims on contingency were **3,420,000** (840,000 of approved variations, 1,260,000 of assessed claim exposure, 1,320,000 of bottom-up owner-scope uplift) against remaining contingency of **1,500,000**; adding the open register's P80 of **1,764,289** gave coverage of **0.2893**. The report's 58.85 % draw-rate check had been a coincidence throughout: risk had never been distributed pro rata to progress, and the two largest sanction-register items — ground conditions at the intake and owner-retained interface diversions — had both materialised, leaving the remainder funded at a confidence level nobody had computed. The original 3,645,403 had been a **P84** provision against the whole register; what remained was a P-nothing.

How it resolved. The sponsors injected **1,927,740** of additional equity as a condition to the quarter-five drawing, taking equity to **19,927,740** and total funding to **61,927,740**. Because senior debt was unchanged at 42,000,000, **every coverage ratio was untouched** — **DSCR** stayed at 1.2743 — and the whole overrun landed on equity: gearing moved from 70.0/30.0 to **67.82/32.18 (D/E 2.1076)**, the equity cheque rose **10.71 %**, and Domain 4's project **NPV** of +16,179,360 fell to **+14,251,620** on the same operating forecasts. The monitoring regime was rewritten with three changes and no new money: disaggregated **CPI** reporting by scope with the blended figure banned; a contingency coverage ratio on the remainder replacing the draw-rate check, with the denominator itemised at every data date; and the in-balance test computed on the commitment basis at every draw and every reporting date, reconciled against the contingency shortfall as a cross-check.

What the domain teaches here. Two independent tests reached the same conclusion — 1,927,740 of in-balance shortfall against 1,920,000 of contingency committed beyond its balance, plus the 7,740 of interest on an early draw — and the monthly report contained neither. What it contained instead were two numbers that looked reassuring and were arithmetically empty: a draw rate compared with progress, and a blended **CPI** that happened to produce a plausible total by attributing 93 % of an overrun to the one scope incapable of overrunning. The lesson is not that the sponsors were negligent; it is that **the reassuring figures are the default outputs of an ordinary cost report, and the tests that matter have to be specified, itemised and demanded.** That is the entire purpose of Toolkit 14.T.2.

— Case study B — Domain 14: the switchgear that was never ours (digital infrastructure)

Situation. A data-centre SPV financed a first phase at an envelope of **420,000,000 — 294,000,000** senior debt and **126,000,000** equity — with a funded contingency of 12,600,000. Lead times on medium-voltage switchgear and generators ran to fourteen months, and the electrical subcontractor's cash flow could not carry them. With the general contractor's support, the certification basis was allowed to drift: over five months the independent engineer certified **38,400,000** of off-site equipment at the vendors' works. Vesting certificates, segregation confirmations and insurance endorsements in the SPV's name were obtained for 22,000,000 of it. For **16,400,000 — 3.90 %** of the envelope — they were not; the paperwork was described in the monthly report as "in progress with the vendors".

What happened. The electrical subcontractor entered insolvency proceedings sixteen months into a twenty-two-month programme. The vested equipment was traced and released. Of the 16,400,000 that had been certified without vesting, segregation or insurance, the administrator treated the equipment as the subcontractor's asset; **4,100,000** was ultimately recovered through negotiated release of identifiable items, a **25 %** recovery. The loss was **12,300,000**. Of the certified amount, **11,480,000** had been advanced as senior debt at 70 % gearing, and it had been outstanding for fourteen months at 5.5 %, adding **736,633** of capitalised interest carried on an asset that did not exist. Total cost **13,036,633 — 10.35 %** of the equity cheque. Against remaining contingency of **5,600,000** the in-balance test failed by **6,700,000**, which the sponsors funded as equity; gearing moved to **68.90/31.10**. The plant completed five months late, by which point the delay damages cap had bound and the availability period had been extended once, for a fee.

How it resolved. The immediate remedy was procedural and should have been in place from the first draw: certification of off-site materials was capped at a stated percentage of the contract price; each certification was conditioned on a vesting certificate, a segregation confirmation from an independent inspector and an insurance endorsement naming the SPV, delivered before the certificate rather than promised after it; and the cumulative off-site balance became a reported line

with an ageing analysis. The certification-basis mix — achieved milestones, assessed percentages, off-site materials — was reported every month thereafter, which made drift visible within one period instead of five.

What the domain teaches here. Certification drift is never decided; it accumulates. No single certificate was unreasonable, every one had a commercial justification, and the cumulative effect was to convert 11,480,000 of secured lending into an unsecured claim in a third party's insolvency — a decision no committee took and no minute records. The arithmetic that would have stopped it is trivial and was never run: **16,400,000 certified without vesting was 3.90 % of the envelope and 130.16 % of the whole 12,600,000 of contingency funded at close**, and its exposure was fully computable on the day of each certificate. Compare Kestrel: the exposure there was measured on the same basis at 1,339,842 in a single quarter, or 27.91 % of the performance bond. The control is not sophistication; it is a reported line and a condition that must exist before, not after, the money moves.

— Executive perspective — Domain 14

What a project finance director cannot delegate in this domain:

- **The certification basis, and the off-site balance.** Which basis the facility specifies, whether the mix has drifted, and how much has been certified against work not in place — with vesting, segregation and insurance confirmed before the money moves, never promised after it (Case study B, where the answer was 16,400,000 and cost 13,036,633).
- **The in-balance test on the commitment basis, at every draw.** Not the model's balance, which reconciles by construction, but the commitment number: Kestrel's 24,656,674 against 22,728,934, and the double-count that would have hidden it by adding contingency to available funds.
- **The contingency coverage on the remainder, with its denominator itemised.** 0.2893, not the 1.3825 that appears when only the mean of open risk is counted, and never the draw-rate check that let two quarters pass.
- **The funding order.** A single sub-clause worth 1,466,064 of capitalised interest and 11,406,157 of mid-build credit exposure — 41.6 times the ten-basis-point margin the same team spent three weeks negotiating.
- **The date the first instalment falls due, and what counts as CFADS when it does.** A calendar-fixed date breaches a 1.20× covenant on **three weeks** of slip, and whether delay damages are CFADS is worth **0.4791** of coverage at that test. Both are drafting decisions taken before there is a delay.
- **The two costs of delay, stated together.** 415,000 funded and 947,000 economic a month, with the damages recovering 144.58 % of the first and 63.36 % of the second — because a project whose drawdown tests keep passing while equity value drains is the failure mode this domain exists to make visible.

— Calculation exercises — Domain 14

Exercise 14.1 A project has a total funding envelope of 180,000,000, of which 96,000,000 has been drawn. At the data date the remaining committed contract value is 74,000,000; approved variations not yet certified are 3,200,000; assessed exposure on notified claims is 2,600,000;

remaining owner's costs are 4,100,000; and remaining capitalised interest and fees are 2,900,000. Remaining unallocated contingency is 5,000,000. Run the in-balance test. Solution. Available commitment = $180,000,000 - 96,000,000 = 84,000,000$. Cost-to-complete = $74,000,000 + 3,200,000 + 2,600,000 + 4,100,000 + 2,900,000 = 86,800,000$. The project is **out of balance by 2,800,000**, which must be cured before the next drawing. Common error: adding the 5,000,000 of remaining contingency to available funds, giving 89,000,000 and a comfortable surplus of 2,200,000 — contingency is a **use** funded by the same undrawn commitment, so the addition double-counts it and reverses the answer.

Exercise 14.2 A four-quarter construction programme spends 20,000,000 per quarter, funded 75/25 at 8.0 % per annum, interest accruing at 2.0 % per quarter on the opening drawn debt balance with draws at period end. Compute total capitalised interest under pro-rata funding and under equity-first funding. Solution. Pro rata: interest accrues from quarter two on a growing 75 %-geared balance, giving **1,818,068** and total uses of 81,818,068 (debt 61,363,551, equity 20,454,517). Equity-first: the 20,000,000 equity commitment funds the whole of quarter one, so debt is first drawn in quarter two and first accrues interest in quarter three, giving **1,208,000** and total uses of 81,208,000. The saving is **610,068**, or **33.56 %**. Common error: computing interest on closing rather than opening balances, which charges a full period of interest to every draw and overstates capitalised interest — Domain 8's Exercise 8.2 measured that error at 42 % on a comparable profile.

Exercise 14.3 An EPC contract has a price of 90,000,000, an advance payment of 15 % recovered pro rata against certified value, and retention of 10 % of each certification capped at 5 % of the contract price. Cumulative certified value before this month is 36,000,000; this month's certified value is 7,200,000. Compute this month's net payment and the cumulative retention held. Solution. Advance = $13,500,000$; recovery this month = $0.15 \times 7,200,000 = 1,080,000$. Retention cap = $0.05 \times 90,000,000 = 4,500,000$; held before = $0.10 \times 36,000,000 = 3,600,000$, so the cap permits a further 900,000 and this month's 10 % of 7,200,000 = **720,000** fits. Net payment = $7,200,000 - 1,080,000 - 720,000 = 5,400,000$; cumulative retention held **4,320,000**. Common error: applying retention to the amount net of advance recovery — $0.10 \times (7,200,000 - 1,080,000) = 612,000$, giving a net payment of 5,508,000 and **over-paying by 108,000**. Retention is withheld from gross certified value; advance recovery is a separate deduction.

Exercise 14.4 A variation costs 6,200,000 and will add 600,000 a year of CFADS. The loan runs 15 years at 6.5 % and the target DSCR is 1.25×. Compute the maximum coverage-neutral debt funding, the equity or contingency required, and the marginal DSCR if the variation were fully debt-funded. Solution. $AF(0.065, 15) = 9.402669$. Maximum debt funding = $(600,000/1.25) \times 9.402669 = 4,513,281$, being **72.79 %** of the cost; the residual **1,686,719** must come from equity or contingency. Fully debt-funded, incremental debt service = $6,200,000/9.402669 = 659,387$ and the marginal DSCR = $600,000/659,387 = 0.9099$ — the variation would not even service the debt raised to build it. Common error: sizing on the full ACFADS without the coverage divisor ($600,000 \times 9.402669 = 5,641,601$), which is the Domain 10 sizing error transplanted into change control and would leave the project 1,128,320 over-levered on this variation alone.

Exercise 14.5 A facility has annual debt service of 11,200,000 falling due on a calendar-fixed date twelve months after scheduled completion, a 1.15× covenant, a six-month debt service reserve of 5,600,000, and operating CFADS of 14,400,000 a year accruing evenly from actual completion. Completion slips three months. Compute the DSCR at the first test, the reserve consumption, and the three breakeven slips. Solution. CFADS at the first test = $14,400,000 \times 9/12 = 10,800,000$; DSCR

$= 10,800,000/11,200,000 = 0.9643$. Shortfall **400,000**, being **7.14 %** of the reserve. Breakevens: covenant cash trigger $= 1.15 \times 11,200,000 = 12,880,000$, so the covenant fails beyond $12 \times (1 - 12,880,000/14,400,000) = 1.2667$ months; operating cash ceases to cover debt service beyond $12 \times (1 - 11,200,000/14,400,000) = 2.6667$ months; cash plus a fully funded reserve ceases to cover it beyond $12 \times (1 - 5,600,000/14,400,000) = 7.3333$ months. Common error: computing the **DSCR** on annualised **CFADS** of 14,400,000 (giving 1.2857 and a comfortable pass) — the covenant is tested on the period's cash, not on a run rate, which is the whole content of KA 14.4.2.

— Practitioner's toolkit — Domain 14

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 14.T.1 — Draw request pack and certification control sheet

Part A, the arithmetic, one row per line with a source reference: gross certified value this period, split into value of milestones achieved, value of assessed percentage completion, and value of off-site materials; less retention this period, with cumulative retention against its cap; less advance recovery this period, with cumulative recovery against the advance; plus owner-retained costs incurred and evidenced; plus fees, taxes and premiums; plus interest and commitment fees accrued, computed on **opening** balances with the day-count basis stated; equals the period funding requirement, split by the documented funding order into the debt draw and the equity draw. **Part B, the conditions**, one row per condition to drawing with the evidence reference, its expiry date, and the named person who confirmed it — no default or potential default, representations repeated, certifier's certificate, insurances in force and premiums paid, in balance, within the availability period, within the commitment. **Part C, the certification-mix trend**: the three components of Part A's gross certified value as percentages, this period and cumulatively, with the off-site balance aged. **Rules**: the off-site line is nil unless vesting, segregation and insurance are all in place for the amount certified; the certification mix is reported whether or not anyone asks; and cumulative drawn is tied to the facility agent's statement, never to the model.

Toolkit 14.T.2 — Restated sources and uses, the in-balance test, and the EAC bridge

Sheet 1, restated statement: every use in three columns — drawn to date, remaining to be funded, total — against sources in the same three columns, with available commitment stated as undrawn debt plus uncalled equity and a printed warning that contingency is **not** added. Any imbalance is explained in cash terms with its cause named. **Sheet 2, lender's cost-to-complete**: remaining committed contract value; approved variations not yet certified; assessed exposure on notified claims, with the assessor named; bottom-up re-estimate of owner-retained scope; remaining capitalised interest, fees, premiums and taxes to the forecast commercial operations date; total; available commitment; surplus or shortfall. **Sheet 3, the bridge**: the **EAC**-based **CTC** from the delivery organisation's cost report on each published method, then one line per reconciling item — each labelled with the discipline that is blind to it — arriving at the lender's number. **Sheet 4, disaggregated performance**: **EV**, **AC** and **CPI** separately for fixed-price and owner-retained scope, with the blended index shown only to be marked "not to be used for forecasting". **Rule**: no cost report is issued, and no draw request signed, without Sheets 2 and 3 complete.

Toolkit 14.T.3 — Contingency coverage and change-control register

Contingency section: funded amount; drawn to date, itemised by cause with the register item each draw retires; remaining unallocated. **Denominator, itemised**: approved variations not yet certified;

assessed claim exposure; bottom-up re-estimate above budget on owner-retained scope; then the open risk register with **p**, impact, **EMV**, and the computed mean, σ and P80. **Coverage on the remainder**, computed as remaining $\div$ (known committed + P80), with the two partial ratios (against the mean, and against open risk only) shown beside it and labelled as insufficient tests. **Shortfall in currency. Change-control section**, one row per variation above the threshold: price; time effect; funding source, named; **ACFADS** claimed and by whom; **Δ debt service** at the debt-funded share; **marginal DSCR**; coverage-neutral maximum debt funding; headroom consumed; cumulative headroom consumed by all approved variations against the base-case headroom. **Rule**: the draw-rate check — contingency drawn against progress — does not appear on this form; and no variation is approved without a funding source and a marginal **DSCR**.

— Exam preparation — Domain 14

What is assessed. The restated sources-and-uses statement and the in-balance test on a commitment basis; the composition of a draw request from gross certified value to the debt and equity draws; the funding-order comparison and its capitalised-interest, exposure and present-value consequences; the lender's cost-to-complete and its line-by-line reconciliation to an **EAC**-based **CTC**; why a blended **CPI** misattributes an overrun where one scope is fixed-price and milestone-certified; the contingency coverage ratio on the remainder and the defensible choice of denominator; the three certification bases and the exposure created by off-site certification without vesting; advance payment and retention arithmetic, including the retention release that falls in the first operating year; the marginal **DSCR** of a variation and the coverage-neutral debt share; the funded versus economic cost of a month of slip and the three damages-recovery percentages; the **DSCR** at a calendar-fixed first repayment date with its covenant, payment and reserve breakevens; and the buy-down that restores a stated coverage level.

The calculations to do under time pressure. Available commitment and the in-balance result from a five- or six-line cost-to-complete. A period funding requirement and its 70/30 split, with accrued interest on the opening balance. Certified value on three bases, net of retention, times gearing. Net payment after advance recovery and retention, with the cap tested. **Δ debt service** = $\text{cost} \div \text{AF}(r, n)$ and the marginal **DSCR**; and the coverage-neutral maximum, $(\text{ACFADS}/\text{target}) \times \text{AF}(r, n)$. $\text{CFADS} \times (12 - m)/12 \div \text{debt service}$, and the three breakeven slips by inverting it. Supportable debt at a target ratio, and the buy-down as the difference from outstanding debt.

The traps. Adding remaining contingency to available commitment (Exercise 14.1, MCQ 14.1-A) · omitting remaining capitalised interest from a cost-to-complete because it is not work (MCQ 14.2-A) · applying **BAC/CPI** to a blended index across fixed-price and owner-retained scope (14.2.1, MCQ 14.2-B, Case study A) · reading the contingency draw rate against progress as evidence of health (14.2.2, MCQ 14.2-D) · testing contingency against the mean of open risk rather than the P80 plus known commitments (MCQ 14.2-C) · computing capitalised interest on closing rather than opening balances (Exercise 14.2, imported from Domain 8) · certifying off-site materials without vesting, segregation and insurance (14.3.1, Case study B) · applying retention to the amount net of advance recovery (Exercise 14.3) · assuming a retention release falling after completion is already funded because it is inside the contract price (14.3.2, MCQ 14.3-B) · sizing a debt-funded variation on full **ACFADS** without the coverage divisor (Exercise 14.4, MCQ 14.3-C) · treating an **NPV**-positive variation as automatically fundable by debt (14.3.3, MCQ 14.3-D) · quoting one damages-recovery percentage without naming the cost basis (14.4.1, MCQ 14.4-C) · computing the first-test **DSCR** on annualised rather than period **CFADS** (Exercise 14.5, MCQ 14.4-B) · assuming a slip postpones a calendar-fixed repayment date (MCQ 14.4-A) · and confusing the buy-down that restores a covenant with the one that restores base coverage (14.4.3, MCQ 14.4-D).

How the domain connects. Domain 6 built the construction funding model this domain operates; Domain 8 supplied the capitalised-interest area rule, the escalation treatment and the economic cost of a slip during construction; Domain 5 priced a slip at the commercial operations date and established cost-overflow support; Domain 12 fixed the contract limits — damages rates, caps, bonds and guarantees — that this domain draws against; Domain 10 supplied the coverage machinery, the reserve and the covenant that KA 14.4 tests; Domain 13 delivered the conditions precedent that KA 14.1's conditions to drawing continue; and PML-AI Domain 7 supplied the **EAC** family that KA 14.2 reconciles to. Forward, Domain 15 takes the project past completion into operation — the waterfall, the covenant regime, refinancing and restructuring — and Domain 16 governs the automation that this domain's reporting cycle invites.

— Domain 14 summary

Construction monitoring is the discipline of releasing other people's money against evidence, and it reduces to four tests. The **draw request** converts certified value into a funding requirement: Kestrel's quarter five was $9,391,718.47 + 245,707.08 + 287,138.27 = 9,924,563.82$, requested as **9,924,564** and split 70/30, of which the interest line — **0.83 %** of the requirement in quarter one and **8.44 %** in quarter eight — is money borrowed to pay interest on money already borrowed. The **funding order** that governs that split is a single sub-clause worth **1,466,064** of capitalised interest across three orders (equity-first **1,338,006**, pro rata **2,114,597**, debt-first **2,804,070**), **11,406,157** of mid-build lender exposure, **183,013** of present value to the sponsor, and — at a fixed envelope — **742,647** of additional funded contingency; it is **41.6 times** the ten-basis-point margin move the same negotiation spends weeks on. The **in-balance test** on a commitment basis is not **EAC - AC**: Kestrel's lender cost-to-complete of **24,656,674** exceeds an **EAC-based CTC** of 21,120,000 by three lines earned value cannot see — approved variations, assessed claim exposure and remaining capitalised interest — and exceeds available commitment of **22,728,934** by **1,927,740**, while a blended **CPI** of 0.949821 was attributing **2,535,849** of overrun to a fixed-price scope where **CPI** is 1.000 by construction and only **190,189** to the owner-retained scope actually running at 0.6000. The **contingency test** fails independently and earlier: 1,500,000 remaining against 3,420,000 of known committed claims plus a 1,764,289 P80 gives coverage of **0.2893**, where the comfortable versions of the same ratio read 1.3825 and 0.8502, and where a draw rate of 58.85 % against 61.00 % progress had read as health for two quarters. Certification is where security is quietly converted: the same quarter's work is worth **5,760,000** on milestones, **7,084,800** measured and **7,774,800** cost-incurred, and the cost-incurred basis advances **1,339,842** of senior debt against work not in place — 27.91 % of the performance bond, and the mechanism that cost Case study B **13,036,633**, or 10.35 % of its equity. Payment terms carry prices: a 10 % advance costs **254,597** of capitalised interest, 0.53 % of the EPC price, and should be priced rather than granted; a 600,000 retention release falling twelve months after completion takes **CFADS** to 5,784,000, the **DSCR** to **1.1546**, and breaches a 1.20× covenant by exceeding Domain 10's 372,438 of headroom. Variations carry four numbers, not two: a 1,850,000 train adding 240,000 of **CFADS** has an **NPV** of **+711,946** and a marginal **DSCR** of **1.0876** if fully debt-funded, so the coverage-neutral limit is **1,578,947**, or 85.35 % of cost. And delay must be costed twice — **415,000** funded and **947,000** economic a month, recovered by the same 20,000-a-day damages at **144.58 %** and **63.36 %** respectively — because a project whose drawdown tests keep passing while equity drains is invisible on one basis and obvious on the other. At the first, calendar-fixed repayment date the arithmetic is unforgiving: **three weeks** of slip (0.7001 months) breaches the 1.20× covenant, 2.5834 months exhausts operating cash, 7.2917 months exhausts cash plus the 2,504,818 reserve, a four-month slip gives a **DSCR** of **0.8496** and consumes 30.09 % of that reserve — and whether delay damages count as **CFADS** moves the same test by **0.4791**, from 0.8496

to 1.3286. Domain 15 takes the plant into operation, where the waterfall, the covenant regime and the reserve replenishment this domain has already committed begin to run.

15

DOMAIN 15

Operations, Performance and Restructuring

— Why this domain exists

Every preceding domain answered a question that can be closed. Is the project worth building (Domain 4)? Can it carry the debt (Domain 10)? Are the risks allocated (Domain 11), the contracts sound (Domain 12), the diligence complete (Domain 13), the construction funded and certified (Domain 14)? Financial close answers all of them once. **Operations answers them again every quarter for twenty-five years**, against outturn rather than forecast, and with the project's contractual machinery now live: tests that trap cash, reserves that must be topped up before shareholders are paid, and remedies that engage automatically when a threshold is crossed. The question this domain closes is the one the others left open — what actually happens to the cash, period by period, and who decides.

The central claim is that **the operating phase is governed by the distribution test, not by the covenant**. Domain 10 established the covenant, the lock-up and the reserve as the lender's control architecture, and computed Kestrel Water's headroom to breach as USD 372,437.72 of annual cash. That number is real but it is not the one that binds. The condition a sponsor must satisfy to be paid is stricter than the condition it must satisfy to avoid default, it is tested forwards as well as backwards, and it sits below a reserve top-up that has first call on the same cash. A project can be fully compliant, paying every obligation on time, and still pay its shareholders nothing for four consecutive years — which is exactly what Kestrel does below. From there the domain follows the money outwards: monitoring and covenant testing (KA 15.1), the waterfall and the distributions that fall out of it (KA 15.2), refinancing and the negotiated amendments that change the terms mid-life (KA 15.3), and the arithmetic of distress, restructuring, exit and handback (KA 15.4).

Learning objectives. After this domain a candidate can: build an operating bridge from physical performance drivers to [CFADS](#) and reconcile it to the reported financial statements; convert a covenant, lock-up and distribution threshold into a cash trigger and then into each driver's own units; distinguish backward-looking, rolling and forward-looking tests and explain why a rolling test lags a deterioration by its own window length; operate a full cash waterfall period by period, including reserve top-ups, block accounts and the distributable amount that falls out; explain and compute why deferred distributions cost equity more than the cash deferred; price a refinancing as a net present value against break costs and fees and solve for its breakeven margin; price a waiver, an equity cure and a covenant amendment against one another and explain why cure rights are an option with a scarcity value; compare a maturity extension, a principal haircut and an equity injection on both lender recovery and equity value, and locate the enforcement floor that bounds the negotiation; size a handback reserve as a sinking fund and explain why early funding can cost equity more in present value than late funding; value an exit and separate genuine value creation from the arithmetic flattery of early crystallisation; and govern AI-assisted monitoring, covenant certification and restructuring analysis.

The master financing, now operating. Kestrel Water SPC reached commercial operations with the structure Domains 3, 9 and 10 built: capital cost **USD 60,000,000**, funded **70/30** as **USD 42,000,000** of senior debt at **6.0 %** over **12 years** and **USD 18,000,000** of equity; annual instalment **USD 5,009,635.23**, of which year one is interest **2,520,000** and principal **2,489,635**; a **25-year** operating life; documented first-year **CFADS** of **USD 6,384,000** (**6,984,000** before working-capital movements) on **EBITDA** of **7,500,000** and **EBIT** of **5,100,000**; a base-case **DSCR** of **1.2743**, identically equal to **LLCR**, with **PLCR** at **1.9431** (Domain 10, KA 10.2.2). The facility carries a **1.20× DSCR** covenant, a **1.15×** lock-up trigger, a six-month debt service reserve of **2,504,817.62**, and — the term this domain adds — a **distribution condition requiring 1.25× on both a backward and a forward-looking test**. This domain builds the operating bridge that produces the 6,384,000, runs the waterfall for six years of real outturn, refinances at the end of year five, prices the amendment that resolves a breach, restructures the project on a permanent-deterioration branch, and funds an **8,000,000** handback obligation.

KNOWLEDGE AREA 15.1

Operational monitoring, financial reporting and covenant testing

Topics: 15.1.1 what changes at commercial operations · 15.1.2 the operating bridge from drivers to **CFADS** · 15.1.3 triggers in driver units · 15.1.4 backward, rolling and forward-looking tests.

15.1.1 What changes at commercial operations

Definition. The **operating régime** is the standing set of reporting, testing and certification obligations that replaces the construction régime once the completion tests of Domain 14 are satisfied. Its four components are worth naming because each has a different failure mode. **Information covenants** require delivery of management accounts, audited statements, an annual operating budget and a periodic update of the financial model, each by a contractual date; failure is a breach in its own right, independent of performance. **Compliance certificates** are signed statements that the tested ratios have been computed on the documented definitions and that no default subsists — the point at which a number stops being management information and becomes a representation. **Financial covenant testing** measures the ratios on defined dates. **Distribution conditions** are the positive tests a borrower must pass before it may pay anything to shareholders.

Three consequences follow that surprise first-time operators. The **calendar becomes contractual**: test and delivery dates are fixed and do not move because a system implementation slipped. The **model becomes a deliverable**, not an internal tool — which is why Domain 6's model governance and Domain 13's model audit are contractual rather than merely prudent. And the **definitions become load-bearing in the other direction**: at close, a favourable **CFADS** definition raised debt capacity; in operations, the same definition determines whether a distribution is lawful.

15.1.2 The operating bridge from drivers to **CFADS**

Definition. The **operating bridge** is the reconciliation that carries physical performance — availability, output, unit costs — through the accrual statements to the cash figure the covenant is computed on. It matters because the two ends are owned by different people. Plant availability belongs to the operator; **CFADS** belongs to the finance director; and the covenant is breached by the

first and reported by the second. Without an explicit bridge, nobody can say what a one-point loss of availability does to a distribution.

Worked example 15.1.2 — Kestrel's first operating year, from membranes to CFADS.

- Setup.** Contracted capacity **30,000 m³/day**; guaranteed availability **95.0 %**; capacity payment **USD 7,300,000** per year at guaranteed availability, abated pro rata below it; volume payment **USD 0.55/m³** on water delivered. Year one delivered **10,000,000 m³** at **95.0 %** availability. Operating costs: fixed operations and maintenance **2,100,000**, energy **0.26/m³**, chemicals and consumables **0.04/m³**, insurance **200,000**. Depreciation is straight-line over the 25-year life. Cash tax is **20 %** of profit before tax. Working capital is receivables at 45 days of revenue (360-day convention), payables at 90 days of cash operating cost, and an inventory of chemicals and membrane spares of **325,000**, built from nil during the first year.
- Formula.** Revenue = capacity payment × min(1, availability ÷ guaranteed) + volume price × volume. **EBITDA** = revenue – cash operating cost. **EBIT** = **EBITDA** – depreciation. Cash tax = 20 % × (**EBIT** – interest). **CFADS** = **EBITDA** – cash tax ± movement in working capital, per the facility's documented definition (Domain 10, KA 10.1.1).
- Substitution.** Capacity payment $7,300,000 \times 1.00$; volume payment $0.55 \times 10,000,000$; operating cost $2,100,000 + 0.26 \times 10,000,000 + 0.04 \times 10,000,000 + 200,000$; depreciation $60,000,000 \div 25$; tax $0.20 \times (5,100,000 - 2,520,000)$; working capital $12,800,000 \times 45/360 - 5,300,000 \times 90/360 + 325,000$.
- Result.**

Line	USD	Note
Capacity payment	7,300,000	availability at guarantee, no abatement
Volume payment	5,500,000	$0.55 \times 10,000,000 \text{ m}^3$
Revenue	12,800,000	
Cash operating cost	(5,300,000)	$2,100,000 + 2,600,000 + 400,000 + 200,000$
EBITDA	7,500,000	
Depreciation	(2,400,000)	$60,000,000 \div 25$
EBIT	5,100,000	
Interest	(2,520,000)	Domain 3's year-one interest
Profit before tax	2,580,000	
Cash tax at 20 %	(516,000)	
CFADS before working capital	6,984,000	EBITDA – cash tax
Movement in working capital	(600,000)	$1,600,000 - 1,325,000 + 325,000$, built from nil
CFADS as defined	6,384,000	DSCR 1.2743

- Interpretation.** The table is the domain's single most useful artefact because it is the only place where an engineer's number and a lender's number are visibly the same number. Read downwards, it prices performance: the **cash-to-revenue gearing is 0.80** — a dollar of lost revenue costs only eighty cents of **CFADS**, because cash tax falls by twenty cents with it, which means every headroom figure expressed in **CFADS** understates the revenue loss the project can absorb by a quarter. Read upwards, it prices the definition: the 600,000 working-capital line is the same choice Domain 2 (KA 2.3.1) used to move the reported **DSCR** from 1.39 to 1.27, and it is now

a live monitoring exposure rather than a modelling convention — because working capital moves with revenue. When revenue falls, receivables fall and working capital releases cash, flattering **CFADS** in the year of decline; when revenue recovers, working capital rebuilds and penalises **CFADS** in the year of recovery. A deteriorating project therefore reports a covenant ratio that is better than its trading and a recovering project one that is worse, and a finance director who does not decompose the movement will misread both. The professional caution is to report **CFADS** in two lines — before and after working capital — in every internal pack, while certifying only the defined figure to the lenders.

15.1.3 Triggers in driver units

Definition. A **trigger in driver units** is a covenant, lock-up or distribution threshold restated in the physical or commercial quantity that management actually controls. Domain 10 established the first translation, from ratio to cash. This is the second, and it is the one that puts a covenant on an operations dashboard rather than a finance dashboard.

Kestrel's three thresholds, against annual debt service of 5,009,635.23:

Test	Ratio	CFADS trigger	Headroom from 6,384,000	% of CFADS
Distribution condition	1.25×	6,262,044.04	121,955.96	1.9103 %
Financial covenant	1.20×	6,011,562.28	372,437.72	5.8339 %
Distribution lock-up	1.15×	5,761,080.51	622,919.49	9.7575 %

The first line is the domain's opening claim in arithmetic. **The distribution condition binds at 1.9103 % of CFADS; the covenant at 5.8339 %.** Kestrel is three times closer to losing its dividend than to breaching its loan, and only one of those two numbers appeared in the financing paper.

Translating the covenant headroom of 372,437.72 into drivers divides by the 0.80 cash-to-revenue gearing to reach **465,547.16** of pre-tax revenue or cost, and then by each driver's own unit economics:

Driver	Unit economics	Move that reaches the 1.20× covenant	Move that reaches the 1.25× distribution test
Availability	76,842.11 per percentage point (7,300,000 ÷ 95)	6.0585 points — availability floor 88.9415 %	1.9839 points — floor 93.0161 %
Delivered volume	0.25/m ³ cash contribution (0.55 – 0.26 – 0.04)	1,862,188.62 m³ , 18.6219 % of output	609,779.81 m³ , 6.0978 %
Energy unit cost	10,000,000 m ³ exposed	+0.046555/m³ (+17.9 % on 0.26)	+0.015244/m³ (+5.9 %)

Two readings of that table are worth carrying. First, **the drivers are not equally dangerous**: a 6-point availability loss and a 19 % volume loss both cost the same cash, but one is a plausible outcome of membrane fouling and the other is not, so the availability line is the one that belongs in a monthly review. Second, **the energy column is where an unhedged input becomes a covenant risk** — a 5.9 % rise in the delivered cost of power, which no operator would call a crisis, removes the entire dividend.

15.1.4 Backward, rolling and forward-looking tests

Definitions. A **backward-looking test** measures the period that has ended. A **rolling test** measures the trailing window — commonly four quarters — and is the standard form because it removes seasonality. A **forward-looking test** measures the projected next window on an agreed basis. Most facilities test the covenant on a rolling backward basis and the distribution condition on both bases, and the reason is the arithmetic below.

WORKED EXAMPLE

Worked example 15.1.4 — the four quarters a rolling test cannot see.

- Setup.** Kestrel's reported quarterly **CFADS** in year one is **1,700,000 · 1,640,000 · 1,560,000 · 1,484,000** (summing to the documented 6,384,000) and in year two **1,610,000 · 1,520,000 · 1,440,000 · 1,393,894.11** (summing to 5,963,894.11). Because the loan is a level annuity paid annually, **every rolling twelve-month window contains exactly one instalment of 5,009,635.23**, so the denominator is constant. At the year-one test date the board's re-forecast of year two is **5,500,000**.
- Formula.** Rolling **DSCR** = Σ (last four quarters' **CFADS**) ÷ 5,009,635.23. Forward **DSCR** = forecast next-twelve-month **CFADS** ÷ 5,009,635.23.
- Substitution.** Successive four-quarter sums: 6,384,000; 6,294,000; 6,174,000; 6,054,000; 5,963,894.11. Forward: 5,500,000 ÷ 5,009,635.23.
- Result.**

Test date	Rolling four-quarter CFADS	Backward DSCR	1.25× distribution	1.20× covenant	1.15× lock-up
End Y1 Q4	6,384,000.00	1.2743	pass	pass	clear
End Y2 Q1	6,294,000.00	1.2564	pass	pass	clear
End Y2 Q2	6,174,000.00	1.2324	fail	pass	clear
End Y2 Q3	6,054,000.00	1.2085	fail	pass	clear
End Y2 Q4	5,963,894.11	1.1905	fail	breach	clear

The forward test at end Y1 Q4, on the 5,500,000 re-forecast, gives **1.0979** — failing both the distribution condition and the covenant threshold **four quarters before the backward test registers anything at all**. 5. **Interpretation.** This is the most important table in the knowledge area, and its lesson is structural rather than numerical: **a rolling backward test lags a deterioration by the length of its own window**. Kestrel's cash begins falling in the second quarter of year one and its covenant does not break until the fourth quarter of year two — by which time the problem is eighteen months old, the remediation window has closed, and the negotiation happens from a position of fact rather than forecast. The forward test exists precisely to close that gap, and it does: it fails at the first available date. Three professional consequences follow. **Whose forecast counts becomes a covenant question** — Domain 10 (KA 10.A.1) named this, and here it has a price, because at the end of year one the sponsors' own re-forecast is the instrument that stops their dividend. **A forward test punishes candour**, which is the uncomfortable truth of the mechanism: a

management team that revises its forecast honestly triggers a consequence a team that does not revise avoids for a year, and the only defence against that perverse incentive is a documented re-forecast basis with a named owner and an independent review. And **the outturn will differ from the forecast anyway**: year two actually delivered **5,963,894.11**, some **463,894.11** above the re-forecast that stopped the dividend. The distribution was correctly withheld on the information available, and the information available was wrong by nearly half a million dollars. Reporting that reconciliation — forecast, outturn, variance, cause — is what converts a forward test from a trap into a control.

AI in this KA

Where it earns its place. Operating monitoring is the strongest genuine application of machine work in this book: high-frequency, high-volume, structurally repetitive. Three uses are straightforwardly valuable. **Driver-level anomaly detection** — flagging that specific energy consumption per cubic metre has drifted 3 % above its trailing distribution weeks before the quarterly pack would show it, because that drift is the leading indicator of the covenant. **Automated bridge reconciliation** — checking that the operating bridge of 15.1.2 still ties from the meter readings to the ledger to the reported [CFADS](#), every month, and raising the specific line that broke. **Reporting-calendar assurance** — tracking every information covenant against its contractual date across a portfolio, which is pure administration and a real source of avoidable breach.

Where it must not go. An assistant must not compute the certified ratio, and must not draft the compliance certificate. The certificate is a representation by a named officer that the number was computed on the documented definition; a model that has read the definition well is still a model that has read it, and the distinction between a plausible reading and the correct one is the entire content of Domain 10's KA 10.1.1. Nor should a model produce the forward forecast that a distribution test will be measured on — that forecast has a contractual consequence and therefore needs an owner who can be questioned.

Verification, concretely. Recompute one period's certified [DSCR](#) by hand from the statements, every test date, and tie it to the bridge of 15.1.2. Reconcile the machine's [CFADS](#) line to the facility definition clause by clause once per model version (Toolkit 15.T.1). Back-test the anomaly detector against the last eight quarters and record its false-negative rate, because a monitoring tool that has never been measured is an assumption, not a control. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 15.1

Term	Meaning
Operating régime	The standing reporting, testing and certification obligations that follow completion.
Compliance certificate	A signed representation that tested ratios were computed on the documented definitions and no default subsists.
Operating bridge	The reconciliation from physical drivers through the accrual statements to defined CFADS .
Cash-to-revenue gearing	The fraction of a revenue movement that reaches CFADS after cash tax — 0.80 for Kestrel.
Trigger in driver units	A ratio threshold restated in availability points, volume or unit cost.
Rolling test	A covenant measured on a trailing window; it lags a deterioration by the window length.
Forward-looking test	A covenant or distribution condition measured on a projected window on an agreed basis.

■ SAMPLE MCQS — KA 15.1

MCQ 15.1-A [15.1.3 · Application] Kestrel's debt service is 5,009,635.23 and **CFADS** is 6,384,000. Which figure states the headroom to the **distribution condition** of 1.25×?

- A. USD 372,437.72
- B. USD 121,955.96 ✓ CORRECT
- C. USD 622,919.49
- D. 0.0243 of a ratio point

Rationale: $6,384,000 - 5,009,635.23 \times 1.25 = 121,955.96$, or 1.9103 % of **CFADS**. A is the headroom to the 1.20× covenant and is the standard confusion this KA exists to remove; C is the headroom to the 1.15× lock-up; D expresses the gap in ratio points, which conveys no magnitude (Domain 10, KA 10.2.1).

MCQ 15.1-B [15.1.2 · Analysis] Kestrel's revenue falls by 500,000 in a year. Holding working capital constant, **CFADS** falls by:

- A. USD 500,000
- B. USD 400,000 ✓ CORRECT
- C. USD 625,000
- D. USD 100,000

Rationale: Revenue falls to **EBITDA** one-for-one, profit before tax falls by the same amount and cash tax falls by 20 % of it, so **CFADS** falls by $0.80 \times 500,000 = 400,000$ — the cash-to-revenue gearing of 15.1.2. A ignores the tax shield entirely; C divides by 0.80 instead of multiplying, which is the correct arithmetic run backwards (it converts a **CFADS** gap into a revenue gap); D is the tax saving mistaken for the cash effect.

MCQ 15.1-C [15.1.4 · Analysis] A project's **CFADS** begins declining in the second quarter of year one. Its covenant is a rolling four-quarter **DSCR**. The earliest date on which that covenant can fail, and the reason, is:

- A. the same quarter, because the test is continuous

- B. up to four quarters later, because a trailing window dilutes each weak quarter with three earlier stronger ones ☒ **CORRECT**
- C. never, provided debt service is paid
- D. immediately, because rolling tests are more sensitive than annual tests

Rationale: Kestrel's window carries the decline for four quarters before the sum falls through the threshold (15.1.4). A misdescribes a trailing measure; C confuses breach with payment default (Domain 10, KA 10.2.1); D reverses the effect — smoothing reduces sensitivity, which is why the forward test is needed alongside.

MCQ 15.1-D [15.1.3 · Application] Kestrel's capacity payment is 7,300,000 at a guaranteed availability of 95.0 %, abated pro rata. Availability alone must fall to roughly what level before the 1.20× covenant is breached?

- A. 93.02 %
- B. 88.94 % ☒ **CORRECT**
- C. 90.15 %
- D. 87.43 %

Rationale: Covenant headroom $372,437.72 \div 0.80 = 465,547.16$ of revenue, $\div 76,842.11$ per point = 6.0585 points below 95.0 %. A is the floor for the 1.25× distribution condition (1.9839 points); C omits the 0.80 cash-to-revenue gearing altogether ($372,437.72 \div 76,842.11 = 4.8468$ points); D applies the gearing twice ($465,547.16 \div 0.80 = 581,933.95$, giving 7.5731 points).

MCQ 15.1-E [15.1.4 · Evaluation] At the year-one test date the sponsors' own honest re-forecast of **5,500,000** gave a forward DSCR of **1.0979** and stopped a dividend of 774,364.77. Year two in fact delivered **5,963,894.11** — **463,894.11 above** the re-forecast. A director argues at the year-two board that the re-forecast should have been left unrevised. What is the sound response?

- A. the director is right — the outturn shows the re-forecast was wrong, so the distribution was wrongly withheld
- B. the withholding was correct on the information available and the outturn does not change that; the defence against a test that punishes candour is a documented re-forecast basis with a named owner and independent review, plus a forecast-to-outturn reconciliation in every pack ☒ **CORRECT**
- C. the director is right in principle — a sponsor should not be required to produce the forecast that stops its own dividend, and forward tests should be resisted in negotiation
- D. the re-forecast should be prepared on the lenders' model rather than the sponsors'

Rationale: A decision is judged on the information available when it was taken, and the honest answer to the perverse incentive is process, not a worse forecast (15.1.4). A is outcome bias, and accepting it institutionalises optimism in a number that has contractual force. C is a defensible negotiating position in the abstract but answers a question that is already closed — the test is in the documents, and it is what closed the four-quarter lag a rolling backward test cannot avoid. D moves the same unowned judgment to a different party's spreadsheet.

MCQ 15.1-F [15.1.2 · Comprehension] Which statement best restates why a deteriorating project reports a covenant ratio better than its trading, and a recovering one worse?

- A. because depreciation does not move with revenue, so EBIT falls faster than EBITDA
- B. because receivables and payables move with revenue, so a decline releases working capital into CFADS in the year it happens and a recovery reabsorbs it in the year of recovery

☒ **CORRECT**

- C. because cash tax falls when revenue falls, so only eighty cents of each lost dollar reaches CFADS
- D. because the covenant is measured on a rolling window, which smooths a decline across four quarters

Rationale: The asymmetry is a working-capital effect and nothing else (15.1.2). C is true and is a different mechanism — the 0.80 cash-to-revenue gearing dampens movements in both directions symmetrically, so it cannot flatter one and penalise the other. D is a real lag (15.1.4) but describes when the test registers a change, not why the reported figure is flattered. A concerns an accrual measure, and the covenant is computed on cash.

MCQ 15.1-G [15.1.3 · Evaluation] The operations director's monthly pack reports availability against the 95.0 % guarantee, and the finance director wants the covenant regime on it. Kestrel's thresholds bind at **1.9103 %** of CFADS (the 1.25× distribution condition) and **5.8339 %** (the 1.20× covenant), and translate into availability floors of **93.0161 %** and **88.9415 %**. What belongs on the operations dashboard?

- A. the 1.20× covenant in ratio terms, because that is the test the facility agreement contains and the one a default turns on
- B. both thresholds as availability floors — 93.0161 % and 88.9415 % — led by the distribution condition, because it binds first and availability is the quantity the operator actually controls
✓ CORRECT
- C. the volume tolerance of **1,862,188.62 m³**, **18.6219 %** of output, because volume is the larger revenue line
- D. the covenant headroom of **372,437.72** in cash, because cash is the unit the waterfall works in

Rationale: A trigger becomes a control only when it is expressed in the units of the person who can move it, and the translation runs ratio → cash → driver (15.1.3); leading with the distribution condition follows from its binding three times closer than the covenant. A hands an operations meeting a ratio it cannot act on. C is correctly computed and useless as a control: a 19 % volume loss is not a plausible consequence of membrane fouling whereas six availability points is, so ranking the drivers by revenue size ranks them by the wrong property. D is Domain 10's translation and stops one step short of the dashboard — it is the right figure for the finance pack and the wrong one for the operator.

■ SELF-CHECK — KA 15.1

1. Why does a deteriorating project report a flattered covenant ratio? — Falling revenue releases working capital, which is added to CFADS in the year of decline and reversed in the year of recovery (15.1.2).
2. State the lag structure of a rolling four-quarter covenant. — It cannot register a deterioration for up to four quarters; the forward test exists to close that gap and failed for Kestrel four quarters earlier, at 1.0979.
3. Which of Kestrel's three thresholds binds first, and by how much cash? — The 1.25× distribution condition, at 121,955.96 or 1.9103 % of CFADS.

KNOWLEDGE AREA 15.2

The cash waterfall in operation, reserves and distributions

Topics: 15.2.1 the operating waterfall in priority order · 15.2.2 reserve top-ups and the block account · 15.2.3 the distributable amount that falls out · 15.2.4 what a distribution drought costs equity.

15.2.1 The operating waterfall in priority order

Definition. The **operating cash waterfall** is the contractual priority order in which each period's project cash is applied. Domain 10 (KA 10.3.3) built its top — operating costs, taxes, senior debt service — and stated the principle that reserve top-ups rank above distributions. This is the rest of it, in the order the accounts actually work:

Revenue collected into the proceeds account

- 1 operating and maintenance costs, insurance, SPV administration
- 2 cash taxes
- 3 senior fees, agency and account-bank charges
- 4 senior interest
- 5 senior scheduled principal
- 6 debt service reserve top-up, to the required balance
- 7 maintenance reserve top-up, to the required balance
- 8 handback / decommissioning reserve top-up, from the defined year
- 9 mandatory prepayment and cash sweep, if triggered
- 10 subordinated and shareholder debt: interest, then principal
- 11 distributions to equity – only if every distribution condition is satisfied
- 12 otherwise: retained in the distribution-block account

Three features of the order do the work. **Steps 1 to 5 are obligations**; steps 6 to 9 are **restorations**, which is a different thing — they do not fall due to a counterparty but they have first call on cash and no negotiating partner. **Steps 10 and 11 are permissions**: the economic meaning of subordination is not a lower ranking in an insolvency but the absence of an entitlement in the ordinary course. And **step 12 is where the sponsor's money goes when a test fails** — not away, but into an account it cannot reach, which is the mechanism the rest of this knowledge area is about.

Kestrel's reserve requirements: a **debt service reserve** of six months' forward debt service, **2,504,817.62** (constant, because a level annuity's next six months never change), and a **maintenance reserve** funded at **600,000 per year** as the levelised charge for a **3,000,000** membrane replacement every five years. There is no subordinated debt: the 18,000,000 of equity is subscribed as share capital, so step 10 is empty and step 11 is where all sponsor cash arises.

15.2.2 Reserve top-ups and the block account

Definition. A **top-up** is the application of period cash to restore a reserve to its required balance; the **distribution-block account** is where cash that fails a distribution test is held. The pair is what makes the waterfall a liquidity system rather than a payment order, because cash trapped in one period funds a restoration in another.

WORKED EXAMPLE**Worked example 15.2.2 — six years of Kestrel's waterfall, and what the block account paid for.**

- 1. Setup.** Kestrel's actual outturn over six operating years, built from the drivers of 15.1.2. Year two suffers an unhedged power-price shock (energy $0.26 \rightarrow 0.40/\text{m}^3$) with availability at 92.0 % on 9,500,000 m³; year three worsens as membranes foul (88.0 %, 9,000,000 m³, energy 0.42); year four is the remediation year (94.5 %, 9,900,000 m³, energy hedged at 0.32) in which the membrane replacement is brought forward from year five; years five and six run at 95.0 % and 10,000,000 m³ with energy at 0.30. Debt service is the level 5,009,635.23; the maintenance-reserve charge is 600,000 a year; the distribution condition requires $1.25\times$ on both a backward and a forward test.
- 2. Formula.** For each year: residual = CFADS – debt service – maintenance-reserve top-up. If the distribution conditions are satisfied, distribution = residual + block-account balance, and the block account resets to nil; otherwise the residual is added to the block account. A top-up that the year's residual cannot fund is drawn from the block account.
- 3. Substitution.** Year three: $5,202,936.48 - 5,009,635.23 = 193,301.25$, against a 600,000 top-up, leaving $600,000 - 193,301.25 = 406,698.75$ to be drawn from the block account. Year five: $6,480,627.99 - 5,009,635.23 - 600,000 = 870,992.76$, plus the block-account balance of 1,206,931.59.
- 4. Result.**

Year	CFADS	Backward DSCR	Residual after service and reserve	Distribution	Block account, closing
1	6,384,000.00	1.2743	774,364.77	nil	774,364.77
2	5,963,894.11	1.1905	354,258.88	nil	1,128,623.65
3	5,202,936.48	1.0386	(406,698.75)	nil	721,924.90
4	6,094,641.91	1.2166	485,006.68	nil	1,206,931.59
5	6,480,627.99	1.2936	870,992.76	2,077,924.35	nil
6	6,495,588.34	1.2966	885,953.11	885,953.11	nil

Year four additionally required a sponsor injection of **1,500,000**: the membrane replacement brought forward cost 3,000,000 against a maintenance-reserve balance of 1,800,000, a gap of **1,200,000**, with the remaining **300,000** restoring the reserve. 5. **Interpretation.** Four observations, in ascending order of professional value. First, **the debt service reserve was never drawn.** The worst year's CFADS of 5,202,936.48 exceeded debt service by 193,301.25; the 2,504,817.62 reserve sat untouched throughout. Everything that went wrong went wrong above the reserve's pay-line, which is the general case: reserves are sized for the failure that does not happen, and the failures that do happen bind on the distribution test. Second, **year one is the paradox this domain exists to teach.** The project met its covenant at 1.2743 and passed the backward distribution test at $1.25\times$, yet paid nothing, because the forward test failed on the sponsors' own re-forecast (15.1.4). There was 774,364.77 of cash, contractually available to nobody. Third, **the block account is not a penalty box; it is pre-funding.** The 406,698.75 that year three could not contribute to the maintenance reserve came out of the cash years one and two had been forced to retain — the trapped dividend paid for the reserve shortfall that the deterioration caused. A sponsor that had successfully argued for a weaker distribution test in negotiation would have paid that

774,364.77 out in year one and been asked for it back, as new equity, in year three. Fourth, **the reserve top-up is the ranking that hurts**. In year three the maintenance charge consumed the entire residual and more; had the replacement not been brought forward, the same cash would still have been unavailable. A distribution forecast that models debt service but not reserve restoration overstates equity cash by the full reserve charge in every year — 600,000 a year for Kestrel, which is 77.5 % of the base-case dividend.




Fig 15.2.1 — Kestrel's operating waterfall and the block account it fills

15.2.3 The distributable amount that falls out

Definition. The **distributable amount** is what remains after every prior step, and in a level base case it is a residual with a closed form:

$$\text{Distributable} = \text{CFADS} - \text{debt service} - \text{reserve top-ups} \quad (\text{subject to every distribution condition})$$

For Kestrel's base case: $6,384,000 - 5,009,635.23 - 600,000 = 774,364.77$ per year, a cash yield of **4.3020 %** on the 18,000,000 subscribed. That number deserves to be sat with, because it is the honest shape of project-finance equity and it surprises people. A project appraised at a Domain 4 NPV of +16,179,360 with an IRR of 12.19 % pays its owners a 4.30 % cash yield for twelve years. The reason is arithmetic, not disappointment: while the loan is outstanding, debt service consumes 78.5 % of CFADS, and equity is the residual claimant on a leveraged asset. Once the loan retires the same CFADS produces **5,784,000** a year — a **32.13 %** yield on the original subscription — and from year sixteen the handback charge of **697,844.05** (KA 15.4) reduces it to **5,086,155.95**, before rising to **5,686,155.95** once the maintenance-reserve charge ends after year twenty.

The whole 25-year base-case profile, discounted at the 8.0 % the board owns, gives an equity NPV of **+5,027,733.03** and an **equity IRR of 9.8591 %**, on total distributions of **80,505,936.71** — a money multiple of **4.4726x**. Two cautions belong beside those figures. They are **not** Domain 4's appraisal restated: Domain 4 valued the unlevered project over a 15-year horizon on a different net-inflow basis, and comparing the two numbers as though one should reproduce the other is a category error

that appears in real board packs. And the 9.8591 % is **back-end loaded to an extreme degree** — **88.5 %** of total distributions (71,213,559.47 of 80,505,936.71) fall in the last thirteen years — which is why the exit and refinancing questions of KA 15.3 and 15.4 dominate sponsor behaviour in a way that a level-yield instrument would not.

15.2.4 What a distribution drought costs equity

Definition. A **distribution drought** is a run of periods in which cash is generated but not distributable. Its cost to equity has two components that must be separated, because only one of them is a performance failure.

WORKED EXAMPLE

Worked example 15.2.4 — decomposing Kestrel's six-year cost to equity.

1. **Setup.** Base case: 774,364.77 distributed in each of years 1–6. Actual: nil in years 1–4, 2,077,924.35 in year 5, 885,953.11 in year 6, less a 1,500,000 injection at the end of year 4. Discount rate 8.0 %.
2. **Formula.** Present value of each profile at 8 %; the difference is the total cost. The cash cost is the undiscounted difference; the balance is the timing cost.
3. **Substitution.** Base $774,364.77 \times AF(0.08, 6)$. Actual $2,077,924.35 \times DF(0.08, 5) + 885,953.11 \times DF(0.08, 6) - 1,500,000 \times DF(0.08, 4)$.
4. **Result.** Base-case present value **3,579,795.15**. Actual present value **1,972,501.14**, less the injection's **1,102,544.78**, giving **869,956.36**. **Loss of present value 2,709,838.79**. The undiscounted cash difference is **3,182,311.16**, which reconciles exactly: the six-year **CFADS** shortfall of **1,682,311.16** (36,621,688.84 actual against 38,304,000 base) plus the **1,500,000** injection.
5. **Interpretation.** The reconciliation is the point. Of the 3,182,311.16 of cash equity lost, only **52.9 %** is a trading shortfall; **47.1 %** is a capital call caused by a reserve that was not big enough for an event brought forward by one year. That decomposition changes who is accountable for what: the operator owns the 1,682,311.16, and the finance director owns the 1,500,000, because a maintenance reserve sized on the assumption that a five-year replacement cycle will run to five years is a financing decision, not an engineering one. Note also that the present-value loss of 2,709,838.79 is **less** than the cash loss of 3,182,311.16, because **2,963,877.46** of distributions were ultimately paid — four and five years late rather than never. Deferral is expensive and it is not destruction, and conflating the two produces the commoner of the two errors in distressed-project board papers: treating a lock-up as a write-off. The other error is the mirror image, treating it as a timing matter of no consequence, and the arithmetic settles that one decisively: **2,709,838.79 is 53.90 % of the entire 25-year equity NPV of 5,027,733.03**. Six poor years out of twenty-five removed more than half the base-case equity value, because they fell at the front of the profile where discounting bites least.

AI in this KA

Where it earns its place. Waterfall computation is deterministic, rule-heavy and tedious — ideal machine work, and the natural home of a well-tested calculation engine. Two applications add real value beyond speed. **Forward waterfall projection under scenarios:** running the distribution conditions, block-account mechanics and reserve top-ups across hundreds of driver scenarios to produce a distribution distribution rather than a point forecast, which is the only honest answer to "when will we be paid?". And **block-account and reserve reconciliation:** tying account-bank

statements to the modelled balances every period, which catches the operational errors — a top-up made from the wrong account, a release taken before the test date — that no ratio would reveal.

Where it must not go. A model must not determine whether a distribution is permitted. That determination rests on the satisfaction of every condition, including qualitative ones ("no default subsisting", "no material adverse change"), and it is a decision with legal consequence for the officers who authorise the payment. Nor should generated code implement the waterfall without independent reconstruction: the ordering of steps 6 to 11 is where an assistant will confidently produce a defensible-looking but wrong sequence, because the conventional order and the documented order differ in most facilities by at least one step.

Verification, concretely. Reconstruct one period's waterfall by hand from the accounts and tie every step to its clause. Prove the closing identity in every period — opening balances plus receipts less applications equals closing balances, account by account. Test the engine on the three adversarial cases: a period where the residual cannot fund a top-up (Kestrel's year three); a period where a test fails on the forward leg only (year one); and a period where a release and a top-up fall due simultaneously. An engine that has not been run against those three has not been tested.

■ KEY TERMS — KA 15.2

Term	Meaning
Operating cash waterfall	The contractual priority order for applying each period's project cash.
Top-up / restoration	Application of cash to restore a reserve to its required balance; ranks above distributions.
Distribution-block account	Where cash that fails a distribution test is held; a pre-funding mechanism, not a penalty.
Distributable amount	CFADS less debt service less reserve top-ups, subject to every distribution condition.
Cash yield	Distribution ÷ equity subscribed — 4.3020 % for Kestrel while the loan runs, 32.13 % after.
Distribution drought	A run of periods generating cash that is not distributable; costs equity in cash and in timing.

■ SAMPLE MCQS — KA 15.2

MCQ 15.2-A [15.2.3 · Application] Kestrel's CFADS is 6,384,000, debt service 5,009,635.23 and the maintenance-reserve charge 600,000. The base-case distributable amount is:

- A. USD 1,374,364.77
- B. USD 774,364.77 ✓ CORRECT
- C. USD 6,384,000
- D. USD 774,364.77 less the six-month debt service reserve of 2,504,817.62

Rationale: $6,384,000 - 5,009,635.23 - 600,000 = 774,364.77$. A omits the reserve top-up, which is the single most common distribution-forecasting error (15.2.2); C is CFADS itself; D double-counts a reserve that was funded at close and requires no top-up while debt service is level.

MCQ 15.2-B [15.2.2 · Analysis] In Kestrel's year one the backward DSCR is 1.2743 against a 1.20× covenant and a 1.25× distribution condition, and 774,364.77 of cash remains after debt service and the reserve charge. Nothing is distributed. The correct explanation is:

- A. the covenant was breached

- B. the distribution condition also requires a forward-looking test, which failed at 1.0979 on the sponsors' re-forecast ☒ **CORRECT**
- C. the debt service reserve had to be topped up first
- D. distributions are prohibited in the first operating year

Rationale: Both backward tests passed; the forward leg of the distribution condition failed (15.1.4, 15.2.2). A is contradicted by $1.2743 > 1.20$; C is false — a level annuity's six-month reserve never needs topping up; D invents a term.

MCQ 15.2-C [15.2.4 · Analysis] Kestrel's equity lost 3,182,311.16 of cash over six years but only 2,709,838.79 of present value at 8 %. The reason is:

- A. an arithmetic inconsistency between the two measures
- B. 1,463,877.46 of the withheld cash was eventually distributed, so part of the loss is deferral rather than destruction ☒ **CORRECT**
- C. the discount rate should have been the loan rate of 6 %
- D. the 1,500,000 injection should not be counted as a cost to equity

Rationale: Deferral costs the time value, not the principal (15.2.4). C would change both figures without changing the relationship; D is wrong because an injection is cash equity provides and does not get back other than through later distributions already counted.

MCQ 15.2-D [15.2.1 · Recall] In the operating waterfall, a handback or decommissioning reserve top-up ranks:

- A. above senior debt service, being a statutory obligation
- B. below distributions to equity, being a long-dated liability
- C. above distributions to equity and below senior debt service, alongside the other reserve restorations ☒ **CORRECT**
- D. at the same level as cash taxes

Rationale: Restorations sit between obligations and permissions (15.2.1). A inverts the security architecture; B is the error that leaves a handback obligation unfunded (Case study B); D confuses a reserve with a period cost.

MCQ 15.2-E [15.2.4 · Evaluation] Two draft board papers describe the same six operating years. Paper 1 writes the **3,182,311.16** off as lost equity value. Paper 2 calls it a timing matter of no consequence, since **2,963,877.46** of distributions were ultimately paid. Which position is sounder, and what should the paper say?

- A. paper 1 — cash not received when it was due is value lost, and calling it timing is how distressed projects are misreported
- B. neither: the present-value loss is 2,709,838.79 — **53.90 %** of the entire 25-year equity **NPV** of 5,027,733.03 — so deferral is expensive without being destruction, and the paper should split the 3,182,311.16 into 1,682,311.16 of trading shortfall and a 1,500,000 capital call with different owners ☒ **CORRECT**
- C. paper 2 — the block account is pre-funding rather than a penalty, so on the facts nothing was lost
- D. paper 1, provided the loss is measured at the 6 % loan rate rather than the 8 % equity rate

Rationale: Both papers state a half-truth and the arithmetic disposes of each: 2,963,877.46 came back, so it is not a write-off, and 2,709,838.79 is more than half the project's whole equity value, so it is not immaterial (15.2.4). C quotes a correct description of the mechanism (15.2.2) to reach a false

conclusion about value — pre-funding still costs the time value of money and, here, a 1,500,000 injection. D changes the discount rate to change the answer, which is the least defensible move available; the rate belongs to the board, not to the conclusion it wants.

MCQ 15.2-F [15.2.3 · Comprehension] A shareholder asks how a project appraised at a 12.19 % IRR can pay a cash yield of only **4.3020 %**. The clearest explanation is:

- A. the appraisal was optimistic, and the cash yield is the figure to believe
- B. while the loan runs, debt service consumes 78.47 % of CFADS, so equity is the residual claimant on a leveraged asset; the same CFADS yields 32.13 % once the loan retires ✓ CORRECT
- C. the difference is the 600,000 maintenance-reserve charge, which the appraisal did not carry
- D. an IRR and a cash yield measure the same quantity on different bases, so one of the two has been computed incorrectly

Rationale: The gap is leverage and timing, not error or optimism (15.2.3). C names a real charge that is genuinely large against the dividend — 77.5 % of it — but cannot explain the shape: add it back and the yield is still only 7.6354 %. D is the misconception the topic exists to remove: a return over a whole life and a level annual yield are different measures, and both are correct. A treats a leveraged residual as evidence about the appraisal.

MCQ 15.2-G [15.2.2 · Evaluation] A sponsor reviewing the term sheet argues for a distribution condition set at the **1.20×** covenant level rather than **1.25×**, on the ground that a test stricter than the covenant traps cash for no lender benefit. On Kestrel's outturn the base-case distributable amount is **774,364.77** a year, year one's was trapped in full, and year three's residual after debt service was **193,301.25** against a 600,000 maintenance-reserve charge — a shortfall of **406,698.75** drawn from the block account. Is the argument sound?

- A. yes — cash in shareholders' hands is worth more than the same cash later, the block account earns equity nothing, and the lenders already have a covenant
- B. not on these facts: the year-one dividend the 1.25× test trapped is what funded the 406,698.75 shortfall — **52.52 %** of the 774,364.77 — so a weaker test would have paid that cash out and then called it back as new equity; the block account is pre-funding rather than a penalty, and the real question is whether the sponsor would rather hold the cash or avoid the call ✓ CORRECT
- C. yes — a distribution condition and a covenant test the same ratio on the same cash, so the stricter of the two adds nothing
- D. no — 1.25× is a market standard for a contracted water project and is not negotiable

Rationale: Cash trapped by a distribution test is not lost but pre-committed, and here it paid for a restoration that ranks above distributions and has no negotiating partner (15.2.1, 15.2.2). A is the strongest form of the sponsor's case and names a real cost — deferral is expensive — but it prices the timing benefit while ignoring the capital call the same cash would have funded. C is the misconception the domain opens by correcting: the distribution condition is a **permission**, tested forwards as well as backwards, and it binds at 1.9103 % of CFADS where the covenant binds at 5.8339 %. D substitutes an assertion about the market for an analysis; nothing in a facility is un-negotiable at a price.

■ SELF-CHECK — KA 15.2

1. Why was Kestrel's debt service reserve never drawn across six deteriorating years? — Worst-year CFADS of 5,202,936.48 still exceeded debt service by 193,301.25; the failures bound on the distribution test, above the reserve's pay-line.

2. What did the block account actually pay for? — The 406,698.75 maintenance-reserve shortfall in year three, out of dividends trapped in years one and two.
3. State Kestrel's base-case cash yield before and after the loan retires. — 4.3020 % on 774,364.77 while the loan runs; 32.13 % on 5,784,000 afterwards.

KNOWLEDGE AREA 15.3

Refinancing, waivers and amendments

Topics: 15.3.1 why operating-phase debt is mispriced · 15.3.2 pricing a refinancing · 15.3.3 waiver, cure and amendment, priced against one another · 15.3.4 the cash sweep as the price of consent.

15.3.1 Why operating-phase debt is mispriced

Definition. Refinancing is the replacement of an existing facility with a new one, and in project finance its economic driver is specific: the original facility was priced for a risk that has since been retired. A construction-phase margin compensates a lender for completion risk, technology risk and the possibility of a project that never operates. Once the completion tests of Domain 14 are passed and two or three years of operating history exist, none of those risks remain, but the margin does — because a term loan's price is fixed at signing and the market's view is not.

Three structural features make the opportunity larger than a margin comparison suggests. **The tail:** Domain 10 (KA 10.2.2) measured Kestrel's **PLCR** at 1.9431 against an **LLCR** of 1.2743, quantifying thirteen years of project life beyond the loan's maturity; a refinancing can lend against part of that tail, which no margin reduction can replicate. **The amortisation profile:** a schedule sculpted for a construction-phase risk view is usually faster than an operating asset requires. And **the covenant package:** the ratios, reserves and distribution conditions negotiated when the project was a drawing can be reset against observed performance. The professional discipline is therefore to price the whole new term sheet, not the margin — and the worked example exists to show how badly the margin alone misleads.

15.3.2 Pricing a refinancing

WORKED EXAMPLE

Worked example 15.3.2 — Kestrel refinances at the end of year five.

- Setup.** Senior debt outstanding **27,965,694.77** with **7 years** remaining at an all-in **6.00 %** (a 3.00 % base rate swapped fixed for the full tenor, plus a 300 basis point margin). Annual service 5,009,635.23. The market will lend against the operating asset at a **145 basis point** margin, an all-in **4.45 %**. Costs: the interest-rate swap must be broken — the seven-year market swap rate has fallen to **2.20 %**, so the borrower is paying 80 basis points above market on the amortising notional; an arrangement fee of **1.00 %**; a prepayment fee under the existing facility of **0.50 %**; and **320,000** of legal, model-audit, technical-adviser and agency cost. Two structures are on offer: the same 7-year tenor, or a **10-year** tenor lending three years into the tail. Discount incremental cash to equity at 8.0 %.
- Formula.** New instalment = outstanding ÷ AF(new rate, tenor). Incremental cash to equity in each year = old service ceasing less new service arising. Swap break cost = Σ (old fixed – market) × notional in each remaining year, discounted at the market rate. Net present value = present value of incremental cash – total transaction cost.
- Substitution.** Break cost: $0.80 \% \times$ the seven remaining opening balances (27,965,694.77 · 24,634,001.23 · 21,102,406.07 · 17,358,915.21 · 13,390,814.89 · 9,184,628.55 · 4,726,071.04), each discounted at 2.20 % → 218,909.55 + 188,678.82 + 158,150.03 + 127,294.31 + 96,082.11 + 64,483.14 + 32,466.39. Fees: $0.0100 \times 27,965,694.77$ and $0.0050 \times 27,965,694.77$. Instalments: $27,965,694.77 \div \text{AF}(0.0445, 7)$ and $\div \text{AF}(0.0445, 10)$.
- Result.** Swap break cost **886,064.34**; arrangement fee **279,656.95**; prepayment fee **139,828.47**; advisers **320,000** — **total transaction cost 1,625,549.77**.

Option	New instalment	Base-case DSCR	PV of incremental cash at 8 %	Net present value
4.45 % over 7 years	4,737,139.41	1.3476	1,418,714.07	(206,835.69)
4.45 % over 10 years	3,525,588.23	1.8108	2,425,030.89	+799,481.12

Breakeven all-in rate on the 7-year option: **4.2206 %**, a margin of **122.06 basis points**. Breakeven all-in rate on the 10-year option: **5.1308 %**. 5. **Interpretation.** The headline is the trap. **A refinancing that cuts the margin by 155 basis points destroys 206,835.69 of value.** The reason is that the margin saving is a thin annual flow on a rapidly amortising balance — 272,495.82 in year one, falling every year — while the costs are a thick lump today, and the swap break alone consumes 54.5 % of them. The professional discipline that follows is to solve for the breakeven before opening a negotiation: Kestrel's margin must fall by **177.94 basis points**, not 155, to pay for the transaction, so the market's best offer is **22.94 basis points short**. That single figure is the whole mandate brief. What rescues the transaction is not price but **structure**: extending three years into the tail turns the same margin into +799,481.12, and the decomposition shows why — of the 2,425,030.89 of present value, **1,418,714.07 is the margin, 586,108.78 is the tenor measured alone, and 420,208.04 is the interaction** between the two, which exists only because the extension is priced at the lower rate. None of the three components pays for the transaction by itself. Two cautions complete the analysis. The discount rate matters to magnitude but not to sign here, and a refinancing paper should state it and test it, because debt-service savings discounted at the cost of debt look larger than the same savings discounted at the cost of equity and neither is wrong in the

abstract. And the extension is not free of consequence: the [LLCR](#) rises to **1.8108** and the [PLCR](#) to **2.9824**, coverage a lender will not simply hand over — which is what KA 15.3.4 is about.

15.3.3 Waiver, cure and amendment, priced against one another

Definitions. A **waiver** is the lenders' consent to disregard a specific breach, usually for a fee. An **equity cure** is the sponsors' contractual right to inject cash treated as [CFADS](#) (or applied to prepayment) so that a ratio is restored; facilities cap the number available over the loan's life. An **amendment** changes the terms — most commonly resetting a covenant level for a defined period — in exchange for a fee, a margin uplift and usually tighter controls.

Kestrel breaches at two successive test dates, and the two situations look identical and are not.

	End of year 2	End of year 3
CFADS	5,963,894.11	5,202,936.48
Backward DSCR	1.1905	1.0386
Covenant cash requirement at 1.20×	6,011,562.28	6,011,562.28
Equity cure required	47,668.16	808,625.80
Waiver fee at 15 basis points on debt outstanding	55,307.03	—
Amendment: 25 bp fee on 36,871,351.43	92,178.38	—
Amendment: present value at 8 % of a 40 bp margin uplift on years 3–12	651,258.24	—
Total amendment cost	743,436.62	—

WORKED EXAMPLE**Worked example 15.3.3 — the cheapest option that was the wrong one.**

1. **Setup.** At the year-two test date the breach is marginal: **DSCR** 1.1905 against 1.20. The sponsors hold **two** equity cures over the loan's life and have used none. Three responses are available on the numbers above. At the year-three date, nine months later, the breach is severe.
2. **Formula.** Cure = covenant cash requirement – actual **CFADS**. Waiver fee = basis points × debt outstanding. Amendment cost = fee + Σ (margin uplift × opening balance in each remaining year), discounted at 8 %.
3. **Substitution.** Year two: 6,011,562.28 – 5,963,894.11. Year three: 6,011,562.28 – 5,202,936.48. Uplift: 0.0040 × each opening balance from year three to year twelve (147,485.41 · 136,295.99 · 124,435.21 · 111,862.78 · 98,536.00 · 84,409.62 · 69,435.66 · 53,563.26 · 36,738.51 · 18,904.28), discounted at 8 %.
4. **Result.** The year-two cure of **47,668.16** is the cheapest cash response — **7,638.87 less than the waiver** and 695,768.46 less than the amendment. The year-three cure would cost **808,625.80**, which is **808,625.80 ÷ 47,668.16 = 17.0 times** the year-two requirement; put the other way, the year-two breach was **5.8950 %** of the year-three breach. And the amendment at 743,436.62 is within **5,290.97** — seven-tenths of one per cent — of the present value of that year-three cure (**748,727.59** discounted one year at 8 %).
5. **Interpretation.** Two conclusions, and the second is the one that separates a practitioner from an analyst. First, on price, **the amendment and the second cure are indistinguishable**: a difference of 5,290.97 on obligations of three-quarters of a million is inside the error of any forecast underlying either, so the decision cannot be taken on cost and anyone who presents it as a cost comparison has not understood it. The real differences are structural — the amendment resets four test dates and costs 40 basis points for the remaining life; the cure fixes one date, leaves the covenant profile intact, and consumes an irreplaceable option. And note an asymmetry the raw comparison hides: **a cure is an investment and a fee is not**. Cure cash enters the project and is recovered through later distributions; a waiver fee and a margin uplift leave permanently. On a like-for-like basis the cure is better than 5,290.97 suggests. Second, on the actual decision, **spending a cure on the year-two breach was the error**. The sponsors paid 47,668.16 and preserved 7,638.87 of fee, and in doing so consumed half of a facility that nine months later would have been worth 808,625.80 of cover. The correct posture is a rule, not a calculation: **cure rights are scarce options and must be spent in proportion to what they buy** — a marginal breach is waived, and the incremental cost of doing so (7,638.87, or **0.9447 %** of the value of the option preserved) is the cheapest insurance premium in this book. The reflex to reach for the cheapest cash response at each test date, in isolation, is exactly how sponsors arrive at the third breach with no options and no negotiating position.

A third caution belongs here. **An amendment must be sized against the stressed case, not the current one.** A covenant reset to 1.10× negotiated at the year-two date, on the then-current 1.1905, would have been breached again at year three's 1.0386 — a second breach, a second negotiation and a second fee, from a materially worse position. The amendment Kestrel actually took reset the covenant to 1.00× for two test dates before stepping to 1.10× and 1.20×, which is what "sized against the stress" means in practice.

15.3.4 The cash sweep as the price of consent

Definition. A **cash sweep** applies a defined share of cash that would otherwise be distributed to mandatory prepayment. Domain 10 (KA 10.1.3) named it; here it is priced, because a sweep is how lenders take a share of a refinancing or amendment gain, and it is routinely under-priced by sponsors who read it as a liquidity provision rather than a transfer of value.

Take the successful 10-year refinancing of 15.3.2. Post-refinancing distributable cash rises from 774,364.77 to **2,258,411.77** a year — a 12.5467 % cash yield where there had been 4.3020 %. A lender asked to lend three years further into the tail will want a share of that, and the standard ask is **50 % of cash available for distribution** applied to prepayment.

Structure	Loan retires	Equity IRR	Equity NPV at 8 %
No refinancing	year 13	9.8591 %	5,027,733.03
Refinanced, no sweep, net of the 1,625,549.77 costs	year 15	—	5,571,846.45
Refinanced, 50 % sweep, net of costs	year 13	—	4,925,518.59

The sweep costs equity **646,327.86** of present value and 39.76 basis points of IRR on the pre-cost profile, and it removes two years of debt life for the lender. Against a refinancing gain of **544,113.42** at time zero (the 799,481.12 net present value of 15.3.2 discounted five years at 8 %), that is decisive: **with a 50 % sweep the refinancing is worth 102,214.44 less to equity than doing nothing.** The **breakeven sweep share is 40.3334 %** — above it, the transaction destroys equity value.

The professional content is a habit rather than a formula. **Never evaluate a refinancing on the margin and the tenor and then negotiate the sweep separately.** The sweep is part of the price, its effect is second-order in appearance and first-order in magnitude, and the breakeven share is computable before the first meeting. A sponsor who walks into a refinancing knowing that 40.33 % is its indifference point negotiates from a position no amount of relationship can substitute for.

AI in this KA

Where it earns its place. Three uses are strong. **Solving for breakevens** across the transaction's whole parameter space — margin, tenor, fee, sweep share, break cost — is exactly the sort of repeated root-finding a machine should do, and it produces the single most useful output of a refinancing analysis, which is the boundary of the acceptable rather than a point answer. **Term-sheet comparison** across competing offers, normalising to a common present value, catches the option that looks cheapest on margin and is not. **Amendment-history extraction** across a portfolio — every covenant reset, fee and margin uplift ever granted, with dates — builds the institutional memory that makes the next negotiation cheaper.

Where it must not go. A model must not determine whether a cure right remains available, or how many, or on what conditions. That is a reading of the facility's cure clause and its history of use, and it is the specific fact on which the year-two decision above turned. Nor should AI draft the request that goes to a lender: the tone, sequencing and candour of a waiver request is a relationship instrument, and Domain 10 (KA 10.4.4) established that the relationship is the asset that determines the terms of every future consent.

Verification, concretely. Recompute the break cost by hand on the notional schedule and tie each period's notional to the amortisation table (Domain 3's checks). Confirm that the incremental cash-flow set is complete — old service ceasing, new service arising, fees, and the sweep — because the characteristic machine error is an omitted leg, not a wrong multiplication. Re-derive the breakeven

independently and check that the base case sits on the correct side of it. Where a model has read an amendment or waiver clause, check its reading against the document before anyone quotes it.

■ KEY TERMS — KA 15.3

Term	Meaning
Refinancing	Replacement of a facility priced for a risk since retired; value comes from margin, tenor and covenant reset together.
Swap break cost	Present value of the difference between the contracted fixed rate and the market rate over the remaining notional profile.
Breakeven margin	The new all-in rate at which a refinancing's net present value is nil — 4.2206 % for Kestrel's 7-year option.
Waiver	Consent to disregard a specific breach, usually for a fee.
Equity cure	Contractual injection restoring a ratio; a scarce option, capped in number.
Amendment	A change of terms — usually a covenant reset — for a fee, a margin uplift and tighter controls.
Cash sweep	A defined share of distributable cash applied to mandatory prepayment; part of the price of consent.

■ SAMPLE MCQS — KA 15.3

MCQ 15.3-A [15.3.2 · Application] Kestrel's 7-year refinancing at 4.45 % saves 272,495.82 a year with a present value of 1,418,714.07 against total costs of 1,625,549.77. The correct conclusion is:

- A. proceed — a 155 basis point margin saving is material
- B. reject on these terms: net present value is (206,835.69), and the margin must fall 177.94 basis points to break even ☒ **CORRECT**
- C. proceed — the **DSCR** improves from 1.2743 to 1.3476
- D. reject — refinancing an operating asset is never economic

Rationale: $1,418,714.07 - 1,625,549.77 = (206,835.69)$; the breakeven all-in rate is 4.2206 %, a 122.06 bp margin (15.3.2). A prices the headline and not the transaction; C cites a coverage improvement that has no cash value to equity; D overgeneralises — the 10-year variant is worth +799,481.12.

MCQ 15.3-B [15.3.2 · Analysis] Of the 2,425,030.89 present value in Kestrel's 10-year refinancing, how much is attributable to the margin reduction measured alone?

- A. USD 2,425,030.89
- B. USD 1,418,714.07 ☒ **CORRECT**
- C. USD 586,108.78
- D. USD 420,208.04

Rationale: The margin component is the 7-year option's present value (15.3.2). A is the total, which treats the whole gain as margin; C is the tenor component measured alone; D is the interaction term that exists only because the extension is priced at the lower rate.

MCQ 15.3-C [15.3.3 · Analysis] The sponsors hold two equity cures. At a test date the **DSCR** is 1.1905 against a 1.20× covenant, requiring a cure of 47,668.16; a waiver is available for 55,307.03. The better decision, and why, is:

- A. cure — it is 7,638.87 cheaper in cash
- B. waive — paying 7,638.87 more preserves an option worth 808,625.80 of cover nine months later, or 0.9447 % of the value preserved ☒ **CORRECT**
- C. neither — a marginal breach may be disregarded
- D. cure — cure cash counts as **CFADS** and so also improves the reported ratio

Rationale: Cures are scarce options and must be spent in proportion to what they buy (15.3.3). A optimises one test date in isolation, which is precisely the error; C invents a materiality threshold facilities do not contain; D is true of the mechanics and irrelevant to the choice.

MCQ 15.3-D [15.3.4 · Application] The lenders consent to a 10-year refinancing worth 544,113.42 to equity at time zero, in exchange for a 50 % sweep of distributable cash that costs equity 646,327.86 of present value. Equity should:

- A. accept — the tenor extension improves coverage to 1.8108
- B. decline or renegotiate: net of the sweep the transaction destroys 102,214.44, and the breakeven sweep share is 40.3334 % ☒ **CORRECT**
- C. accept — a sweep only accelerates repayment and does not reduce total distributions
- D. accept — the **IRR** cost of 39.76 basis points is immaterial

Rationale: The sweep exceeds the gain (15.3.4). A cites coverage, which is the lenders' benefit; C is false — accelerated prepayment reduces the present value of distributions even where the undiscounted total is similar; D judges materiality on the wrong measure, since 646,327.86 exceeds the whole gain.

MCQ 15.3-E [15.3.2 · Evaluation] The 7-year option at 4.45 % all-in is worth **(206,835.69)** against a breakeven all-in rate of **4.2206 %** — the market's offer is 22.94 basis points short. The treasurer proposes going back to the banks to press for a further **25 basis points** of margin, and nothing else. Assess that course.

- A. sound — 22.94 basis points is the entire gap and 25 basis points closes it, so the transaction becomes positive
- B. sound in arithmetic and the weaker course: at 4.20 % all-in the 7-year option is worth only about +18,542, while the same 4.45 % over 10 years is worth +799,481.12, so the negotiation belongs on tenor rather than on the last basis points of price ☒ **CORRECT**
- C. unsound — a refinancing with a negative net present value should be abandoned rather than renegotiated
- D. unsound — the breakeven rate depends on the discount rate chosen, so it cannot support a negotiating position

Rationale: A is arithmetically correct and is the trap: winning the price argument converts a small loss into a small gain and leaves 780,939 of tenor value on the table, because the margin saving is a thin flow on a rapidly amortising balance while the extension lends into the 1.9431 **PLCR** tail (15.3.1, 15.3.2). C generalises one priced structure into a rejection of the transaction. D is a real caution — the paper should state and test its rate — but the sign does not turn on it here, so it is a reason to disclose an assumption, not a reason to abandon a computable negotiating position.

MCQ 15.3-F [15.3.3 · Evaluation] At the year-two test date the backward **DSCR** is **1.1905** against a 1.20× covenant, and the forward view at the next test date, nine months out, is **1.0386**. The lenders

will grant an amendment, and the sponsors hold **two** equity cures over the loan's life, neither used. The sponsor's adviser proposes resetting the covenant to **1.10×**, which clears the current ratio with margin and prices below a deeper reset. The soundest recommendation is to:

- A. reset to 1.10× and keep a cure for the next test, which against that reset costs **307,662.27** — one of the two cures the sponsors hold, and cheaper in fee and margin uplift than a deeper reset
- B. reset to **1.00×** for two test dates before stepping to 1.10× and then 1.20×, so that the reset itself carries the deterioration and both cures survive it — a reset sized on the current ratio pays a fee for a covenant the next test breaches, and then spends an irreplaceable option to hold it ☒ **CORRECT**
- C. reset to 1.00× for the remaining life, since a covenant that has been breached has been shown to be set too high
- D. take a waiver at each test date instead: at **55,307.03** a waiver is far cheaper than the **743,436.62** the amendment costs

Rationale: An amendment must be sized against the **stressed** case rather than the current one, and the deterioration was already visible (15.3.3). **A** is genuinely arguable and is not arithmetically wrong: 307,662.27 is **38.05 %** of the **808,625.80** the same test would cost as a cure against the unamended 1.20×, and a sponsor expecting a recovery may rationally buy the shallower reset and bridge one date. It is the weaker course because a cure is an irreplaceable option whose value rises with the severity of the breach it meets — the 17.0× asymmetry of 15.3.3 — so spending one on a breach the amendment could have absorbed repeats the year-two error at a higher price, and the fee saved buys a covenant that fails at the very next test. **C** gives away the control permanently to solve a defined period of weakness, and no lender prices that kindly. **D** is right about a single date and wrong about a persistent profile: each waiver is a fresh consent sought from a worse position, and the amendment Kestrel took resets four test dates.

MCQ 15.3-G [15.3.1 · [Comprehension](#)] Which statement best explains why a refinancing opportunity exists in an operating project financing at all?

- A. market interest rates fall over time, so any long-dated facility eventually becomes expensive
- B. the facility was priced for completion and technology risks that the completion tests retired, while a term loan's price is fixed at signing; and the project life beyond the loan's maturity is lendable capacity that no margin reduction can reach ☒ **CORRECT**
- C. an operating project generates more cash than one under construction, so it can carry more debt
- D. lenders are required to reprice a facility once the independent engineer certifies completion

Rationale: The driver is a mismatch between a price fixed at signing and a risk profile that has changed, and the value has three sources — margin, tenor into the tail, and the covenant package — which is why a **PLCR** of 1.9431 against an **LLCR** of 1.2743 measures something a margin cut cannot deliver (15.3.1). **A** is sometimes true and is not the mechanism: a refinancing can pay in a rising market where the risk retired is large enough. **C** explains why the tail exists, not why the facility is mispriced. **D** invents an obligation — a refinancing is a new transaction, negotiated.

■ SELF-CHECK — KA 15.3

1. Why does a 155 basis point margin saving fail to pay for Kestrel's refinancing? — The saving is a thin flow on a rapidly amortising balance; the breakeven reduction is 177.94 basis points.
2. What actually makes the transaction work? — Tenor: three years into the tail, plus the interaction of tenor with the lower rate — 586,108.78 and 420,208.04 of the 2,425,030.89.

3. State the rule for spending an equity cure. — In proportion to what it buys; a marginal breach is waived, because the cure is a capped option with a scarcity value.

KNOWLEDGE AREA 15.4

Distress, restructuring, exit and handback

Topics: 15.4.1 what distress is, financially · 15.4.2 the three restructurings, compared · 15.4.3 the enforcement floor and the bargaining range · 15.4.4 exit and the arithmetic of crystallisation · 15.4.5 handback and the residual obligation.

15.4.1 What distress is, financially

Definition. A project is in **financial distress** when its forecast cash cannot sustain its contracted debt service on the agreed profile — which is a different condition from a covenant breach (a test failure at a date) and from insolvency (an inability to pay). The distinction is operational: a breach is cured, waived or amended; distress is **restructured**, because no fee or one-off injection fixes a profile mismatch that persists for the life of the loan.

The diagnostic is simple and worth stating as a rule. Compute the **sustainable debt service** — revised **CFADS** divided by the target coverage — and compare it with the scheduled service. If scheduled service exceeds sustainable service for a single period, the project has a liquidity problem and reserves exist for it. If it exceeds sustainable service for the remaining life, the project has a **capital structure problem**, and only three levers can close it: **time** (extend), **principal** (reduce), or **new money** (inject).

15.4.2 The three restructurings, compared

WORKED EXAMPLE

Worked example 15.4.2 — Kestrel on the permanent-deterioration branch.

- Setup.** Suppose the year-three deterioration of KA 15.2 had proved **permanent** rather than remediable: revised **CFADS** of **5,202,936.48** flat for years 4 to 25. Senior debt outstanding at the end of year three is **34,073,997.28**, with **9 years** remaining at 6.00 % and scheduled service of 5,009,635.23 — a **DSCR** of **1.0386**. The lenders require **1.20×** restored. Lender recovery is measured as the present value of what they receive, both at the contract rate of 6.00 % and at a **7.00 %** risk-adjusted required return; equity value is the present value at 8.0 % of distributions after the 600,000 maintenance charge to year twenty and the 697,844.05 handback charge from year sixteen.
- Formula.** Sustainable service = revised **CFADS** ÷ 1.20. Extension: solve for the tenor **n** with $\text{outstanding} \div \text{AF}(0.06, n) \leq \text{sustainable service}$. Haircut: supported debt = sustainable service × **AF(0.06, 9)**. Injection: prepay the difference and re-amortise over the original 9 years.
- Substitution.** Sustainable service $5,202,936.48 \div 1.20 = 4,335,780.40$. Required annuity factor $34,073,997.28 \div 4,335,780.40 = 7.858792$, against **AF(0.06, 10) = 7.360087** and **AF(0.06, 11) = 7.886875** → 11 years. Haircut: $4,335,780.40 \times 6.801692$.
- Result.**

	A — extend to 11 years	B — principal haircut	C — sponsor injection
Amount written off / injected	—	4,583,353.23 (13.4512 %)	4,583,353.23
New instalment	4,320,342.23	4,335,780.40	4,335,780.40
Restored DSCR	1.2043	1.2000	1.2000
Lender recovery, PV at 6.00 %	100.0000 %	86.5488 %	100.0000 %
Lender recovery, PV at 7.00 %	95.0779 %	82.9037 %	96.3549 %
Equity value, PV at 8 %	14,898,548.64	18,656,183.22	14,072,829.99
Annual equity cash while debt runs	282,594.25	267,156.08	267,156.08

1. **Interpretation.** The table separates three questions that boards routinely merge. **What does each side prefer?** Lenders rank C, then A, then B; equity ranks B (18,656,183.22), then A (14,898,548.64), then C (14,072,829.99). The rankings are exactly opposed on the haircut, which is why haircuts are demanded and rarely granted. **Why does equity prefer the extension over the injection,** when the injection produces a lower debt service? Because the injection costs 4,583,353.23 today to buy a debt-service saving whose present value at 8 % is less — a gap of **825,718.65**, which is the arithmetic reason sponsors resist new money even when they have it, and the reason a lender should read a refusal to inject as information about the sponsor's discount rate rather than about its confidence. **And what does the extension cost the lenders?** At the contract rate, nothing: extending a loan at its own coupon returns exactly par, because the present value of a longer annuity at the same rate is the same principal. That is the arithmetic identity behind every "amend and extend", and it is why extensions are the default restructuring. But at the 7.00 % the lenders now require, the extension recovers **95.0779 %** — a real loss of 4.92 points of present value, which the accounting may or may not recognise. The professional caution is precisely there: **an extension is described as par and is not**, and a credit committee that measures recovery only at the contract rate cannot see what it has given away. The sensitivity is worth carrying as a rule of thumb — for Kestrel, every 100 basis points of required-return increase costs roughly five points of extension recovery.

15.4.3 The enforcement floor and the bargaining range

Definition. The **enforcement floor** is the recovery a lender would achieve by enforcing its security and realising the asset, net of costs and delay. It is the boundary of every restructuring negotiation, because no lender rationally accepts a proposal recovering less than the floor, and no sponsor rationally accepts one leaving less than the value of its equity elsewhere.

WORKED EXAMPLE**Worked example 15.4.3 — computing the floor, and what it excludes.**

1. **Setup.** On enforcement, Kestrel would be sold to a buyer who assumes lower performance and a higher cost base than the incumbent — **CFADS** of **4,900,000** over the remaining 22 years — and who requires **13.0 %** on a project acquired out of enforcement with a broken operations and maintenance arrangement. Enforcement and sale costs are **6 %** of proceeds, and the process takes **twelve months**, over which the lenders discount at their 6.00 % contract rate.
2. **Formula.** Floor = [buyer's **CFADS** × **AF**(buyer's rate, remaining life) × (1 – costs)] ÷ (1 + lender rate).
3. **Substitution.** $4,900,000 \times \text{AF}(0.13, 22) = 4,900,000 \times 7.169513; \times 0.94; \div 1.06.$
4. **Result.** Gross enterprise value **35,130,615.34**; costs **2,107,836.92**; net **33,022,778.42**; discounted twelve months **31,153,564.55** — a recovery of **91.4291 %**.
5. **Interpretation.** The floor decides the negotiation before it starts. Option B's haircut recovers **82.9037 %** on the lenders' own required return — **8.5254 points below** what enforcement pays — so it is not a hard bargain, it is **outside the feasible set**, and a sponsor proposing it has spent credibility on an option that could never be accepted. Working the constraint in reverse gives the more useful number: the **maximum haircut a lender can accept is 2,920,432.73**, or **8.5709 %** of the outstanding, at which recovery equals the floor. But that haircut supports an instalment of **4,580,266.69**, a **DSCR** of only **1.1359** — still below the 1.20 required. **The largest haircut the lenders can grant does not solve the problem**, which is the decisive finding of the whole analysis: on these numbers the restructuring must include an extension, and the only remaining questions are how long and at what price. Two professional qualifications. The floor is a **model of a distressed sale**, and every input is contestable — the buyer's **CFADS**, the required return, the cost percentage, the delay — so the discipline is to present it as a range and to state which input the conclusion depends on (here, the buyer's required return: at 10.0 % the floor would exceed par and no restructuring would be rational at all). And the floor systematically **overstates** what most lenders will really do, because enforcement carries consequences no discounted cash flow captures: the offtaker's step-in rights (Domain 12's direct agreements), regulatory and political exposure, reputational cost, and the simple institutional fact that enforcing leaves a bank owning a desalination plant. That is why Domain 10 (KA 10.4.3) observed that lenders rarely accelerate a fundamentally sound project — the floor bounds the negotiation, but the negotiation is conducted well inside it.




Fig 15.4.1 — The restructuring frontier

15.4.4 Exit and the arithmetic of crystallisation

Definition. An **exit** is the sale of the sponsor's equity interest, priced as the present value of the distributions the buyer expects at the buyer's required return. It is the ordinary end of a sponsor's involvement — development-stage sponsors sell to long-term infrastructure holders as a matter of business model — and it is where **IRR** is most often used to claim credit for arithmetic.

WORKED EXAMPLE

Worked example 15.4.4 — Kestrel sold at the end of year eight.

- Setup.** The base-case profile of 15.2.3. By the end of year eight the sponsors have received **6,194,918.16** of distributions on 18,000,000 subscribed. A long-term holder will buy the remaining seventeen years of distributions. Price it at required returns of 6.50 %, 7.00 %, 7.50 % and at the sponsors' own 8.00 %.
- Formula.** Price = Σ (distributions in years 9–25) discounted at the buyer's required return to the end of year eight. Seller's **IRR** = the rate zeroing the flow (18,000,000) at time zero, distributions in years 1–8, and the price at year eight.
- Substitution.** Discount 774,364.77 (years 9–12), 5,784,000 (13–15), 5,086,155.95 (16–20) and 5,686,155.95 (21–25) at each rate.
- Result.**

Buyer's required return	Price at end of year 8	Seller's IRR	Seller's NPV at 8 %
6.50 %	39,260,418.77	13.4196 %	7,661,177.40
7.00 %	37,541,787.43	12.8568 %	6,732,654.36
7.50 %	35,919,098.27	12.3059 %	5,855,965.90
8.00 %	34,386,097.04	11.7666 %	5,027,733.03
Hold to maturity	—	9.8591 %	5,027,733.03

1. **Interpretation.** The bottom two rows contain the lesson, and it is one of the most useful invariants in this book. **Selling at the sponsors' own 8.00 % discount rate raises the reported IRR from 9.8591 % to 11.7666 % and creates exactly nothing** — the NPV at 8 % is **identical at 5,027,733.03**, to the cent, because a sale at the discount rate is by construction a swap of the same value at a different date. The entire IRR uplift of 1.9075 points is the arithmetic of early crystallisation: a positive NPV realised sooner produces a higher internal rate, which is Domain 4's reinvestment fiction (KA 4.1.2) appearing in a transaction rather than a forecast. What is real is the difference between the buyer's required return and the sponsors': selling at 7.50 % rather than 8.00 % is worth **1,533,001.23** at the end of year eight, or **828,232.87** at time zero — which reconciles exactly to the NPV difference of 828,232.87 between the two rows. That 828,232.87 is **yield compression**, and it is a view about the capital market, not an achievement of the project. The professional discipline is therefore to report an exit in three separated numbers: the value created by operating the asset (which is the base-case NPV), the value created by yield compression (which is a market call, and should be attributed as one), and the IRR, which explains neither and should never carry the credit for both. A sponsor whose realised IRR of 12.3059 % is presented as operating performance has misdescribed a 9.8591 % project sold into a favourable market — and the same arithmetic will run against them when the market moves the other way, at which point the honest baseline they did not establish is what they will need.

15.4.5 Handback and the residual obligation

Definition. Handback is the transfer of the asset to the grantor or offtaker at the end of the concession, in a condition the agreement specifies. The **residual obligation** is the cost of achieving that condition, and it is the last item in the waterfall and the first one forgotten, because it falls due after every person who negotiated it has left.

Kestrel's obligation is an independently estimated **8,000,000** in year-25 money — plant condition works, a final membrane and pump replacement to a defined residual standard, and restoration of the intake structure — funded by a reserve earning **3.00 %**.

WORKED EXAMPLE**Worked example 15.4.5 — when to start funding, and the invariant that decides it.**

1. **Setup.** Two funding profiles: level annual contributions over **years 16 to 25** (ten years), or over **years 6 to 25** (twenty years). Equity discounts at 8.0 %.
2. **Formula.** Contribution = obligation ÷ FVAF(reserve rate, years). Present cost to equity = contribution × AF(0.08, years) × DF(0.08, years before the first contribution).
3. **Substitution.** $8,000,000 \div \text{FVAF}(0.03, 10) = 8,000,000 \div 11.463879$; $8,000,000 \div \text{FVAF}(0.03, 20) = 8,000,000 \div 26.870374$. Then $\times \text{AF}(0.08, 10) \times \text{DF}(0.08, 15)$ and $\times \text{AF}(0.08, 20) \times \text{DF}(0.08, 5)$.
4. **Result.**

Profile	Annual contribution	Total contributed	Present cost at 8 %
Years 16–25 (10 years)	697,844.05	6,978,440.53	1,476,147.78
Years 6–25 (20 years)	297,725.66	5,954,513.22	1,989,422.56

Starting ten years earlier more than halves the annual charge and reduces the undiscounted total by 1,023,927.31 — and costs equity **513,274.78 more** in present value, **34.7712 %** more. 5. **Interpretation.** The result is counterintuitive until the mechanism is named, and then it is obvious and permanently useful. **A pre-funded reserve is equity lending money to itself at the reserve's earning rate.** Kestrel's reserve earns 3.00 %; its equity requires 8.00 %; every dollar contributed early is a dollar invested at a 500 basis point negative spread. The invariant that proves it: **when the reserve rate equals the discount rate, the funding profile is irrelevant** — the present cost of any profile that reaches 8,000,000 at year 25 is exactly $8,000,000 \times \text{DF}(0.08, 25) = \mathbf{1,168,143.24}$, and the indifference rate is therefore precisely the discount rate, 8.0000 %. That single fact organises the whole negotiation: below the discount rate, sponsors rationally defer and grantors rationally insist; above it, the interests align and the argument disappears. It also tells a leader where to spend effort — not on the funding profile, which is worth 513,274.78, but on **the credit quality of the reserve's investments and the rate they earn**, which is worth more. And it names the reason grantors insist anyway, which is not arithmetic but counterparty risk: a reserve funded in the last ten years of a concession depends on the concessionaire's solvency in years 16 to 25, and the grantor has no claim on a sponsor that has already sold. The resolution used in practice — and the recommendation here — is a **reserve plus a handback bond or parent guarantee**, which separates the funding question from the credit question instead of using the first as a substitute for the second.

Three further mechanics complete the topic. The obligation is fixed by a **condition survey**, typically two to five years before expiry, and the survey is where the estimate meets reality — Case study B prices what happens when it does. **Residual obligations survive handback:** a defects period, a retention against the handback works, and warranties on replaced equipment. And **the asset's residual value belongs to whoever the concession says it belongs to**, which is usually the grantor and never automatically the sponsor: Domain 4's appraisal treated the tail as project cash, and the concession may treat the terminal asset as worth nothing at all to equity.

AI in this KA

Where it earns its place. Restructuring analysis is combinatorial — tenor, haircut, injection, sweep, covenant reset and fee interact — and enumerating the option space against two objective functions (lender recovery, equity value) is exactly the work a machine should do. Generating the **frontier** of

Fig 15.4.1, and locating the enforcement floor across a range of buyer assumptions, converts a negotiation about positions into an inspection of a feasible set. Two further uses: **early-warning classification** across a portfolio, ranking assets by distance to the sustainable-service condition of 15.4.1 rather than by current ratio; and **handback obligation tracking**, holding every asset's survey date, estimate vintage and reserve balance in one place, because the failure mode in Case study B is an information failure a register would have prevented.

Where it must not go. Nothing in the legal characterisation of distress may be delegated: whether facts constitute an event of default, what remedies follow, what a security package actually secures, and how an insolvency régime would treat any of it are questions for qualified counsel in the relevant jurisdiction, and they differ fundamentally between jurisdictions in ways no general model should be trusted to reflect. Nor should a model be used to select the restructuring proposal: the choice among feasible options is a judgment about counterparties, relationships and reputational consequence over decades, and it belongs to named people.

Verification, concretely. Re-derive the sustainable-service test by hand; confirm that each option's restored ratio meets the requirement stated. Check the extension identity — present value at the contract rate must return exactly par — as the cheapest single audit of any restructuring model. Test the enforcement floor's sensitivity to the buyer's required return and report the range, not the point. For handback, verify that the sinking fund reaches the obligation in the final year and that the indifference-rate invariant holds in the model. Record every assumption about a distressed buyer as an assumption, with an owner.

■ KEY TERMS — KA 15.4

Term	Meaning
Financial distress	Forecast cash cannot sustain contracted debt service for the remaining life — a capital structure problem, not a liquidity one.
Sustainable debt service	Revised CFADS ÷ target coverage; the diagnostic that separates distress from a bad period.
Maturity extension	Lengthening the tenor; returns par at the contract rate and less at any higher required return.
Principal haircut	Writing down principal; preferred by equity, feasible only above the enforcement floor.
Enforcement floor	Net recovery from enforcing security and realising the asset; bounds every negotiation.
Yield compression	Value created by selling at a lower required return than the seller's own — a market view, not performance.
Handback	Transfer of the asset at concession end in a specified condition; the residual obligation and its reserve.
Condition survey	The pre-expiry inspection that fixes the handback obligation against the funded estimate.

■ SAMPLE MCQS — KA 15.4

MCQ 15.4-A [\[15.4.2 · Analysis\]](#) A lender extends a distressed loan at its existing contract rate so that coverage is restored. Measured at the contract rate, its recovery is:

- A. below par, because payment is deferred
- B. exactly par, because the present value of a longer annuity at the same rate is the same principal ☒ **CORRECT**
- C. above par, because more interest is received in total

D. indeterminate without the sponsor's discount rate

Rationale: The extension identity of 15.4.2 — which is why "amend and extend" is the default and why a committee measuring recovery only at the contract rate sees no loss. The real cost appears at a higher required return: 95.0779 % at 7.00 % for Kestrel. C confuses total nominal interest with present value; D is irrelevant to the lender's measure.

MCQ 15.4-B [15.4.3 · Analysis] Kestrel's enforcement floor is a 91.4291 % recovery. A proposed haircut recovers 82.9037 % on the lenders' 7.00 % required return. The correct characterisation is:

- A. an aggressive but negotiable proposal
- B. outside the feasible set — enforcement pays the lenders 8.5254 points more ✓ CORRECT
- C. acceptable, because enforcement destroys value for everyone
- D. acceptable, because equity value of 18,656,183.22 is the highest of the options

Rationale: No lender accepts less than the floor (15.4.3). A misreads infeasibility as negotiating distance; C is true of the parties jointly and irrelevant to the lender's individual choice; D states equity's preference, which is not a constraint on lenders.

MCQ 15.4-C [15.4.4 · Analysis] A sponsor holding a 9.8591 % IRR project sells at the end of year eight at exactly its own 8.0 % discount rate and reports an IRR of 11.7666 %. The value created is:

- A. the 1.9075 percentage point IRR uplift
- B. nil — the NPV at 8 % is identical at 5,027,733.03; the uplift is the arithmetic of early crystallisation ✓ CORRECT
- C. USD 828,232.87
- D. USD 34,386,097.04

Rationale: A sale at the discount rate is a swap of equal value at a different date (15.4.4). A mistakes a rate for value; C is the value of yield compression at 7.50 % rather than 8.00 %, which is a different transaction; D is the price, not the gain.

MCQ 15.4-D [15.4.5 · Application] An 8,000,000 handback obligation at year 25 can be funded by a reserve earning 3.00 % over years 16–25 (697,844.05 a year) or years 6–25 (297,725.66 a year). At an 8 % equity discount rate, the earlier profile:

- A. is cheaper, because the total contributed is 1,023,927.31 lower
- B. costs equity 513,274.78 more in present value, because the reserve earns 500 basis points less than equity requires ✓ CORRECT
- C. costs the same, because both reach 8,000,000 at year 25
- D. is cheaper, because contributions are smaller

Rationale: Pre-funding is equity lending to itself at the reserve rate (15.4.5). A and D compare undiscounted amounts across different decades; C would be true only if the reserve earned the 8 % discount rate — the indifference-rate invariant, at which every profile costs $8,000,000 \times DF(0.08, 25) = 1,168,143.24$.

MCQ 15.4-E [15.4.2 · Evaluation] A credit committee paper recommends the maturity extension on the ground that lender recovery is **100.0000 %** of the 34,073,997.28 outstanding, measured at the 6.00 % contract rate. Is that recommendation supported by the evidence it cites?

- A. yes — the present value of a longer annuity at the same rate returns the same principal, so recovery is par

- B. no — par at the contract rate is an arithmetic identity that holds however far the credit has deteriorated, so it carries no information; at the 7.00 % the lenders now require the extension recovers **95.0779 %**, a real loss of 4.92 points the paper does not disclose ✓ **CORRECT**
- C. no — the sponsor injection recovers 96.3549 % and should therefore be recommended instead
- D. yes, provided the paper also shows the restored **DSCR** of 1.2043 clearing the 1.20 requirement

Rationale: A states a true fact and mistakes it for evidence; because the identity is insensitive to the very deterioration the committee is being asked to approve, quoting it is what conceals the concession (15.4.2). C names the option lenders prefer but it is not theirs to grant — the sponsor rationally refuses, the injection costing 4,583,353.23 today for a saving worth 825,718.65 less. D adds a necessary condition and treats it as a sufficient one: coverage restored says the loan can be serviced, not what the lenders gave up to get there.

MCQ 15.4-F [15.4.4 · Evaluation] The sponsors sell at the end of operating year eight to a holder requiring **7.50 %**, and the board paper reports the realised **IRR** of **12.3059 %** as evidence of operating performance against a hold-to-maturity **9.8591 %**. The soundest assessment of that paper is:

- A. it is sound — a realised **IRR** is the return the shareholders actually earned, and 12.3059 % is a fact
- B. it misattributes: a sale at the sponsors' own 8.00 % would have lifted the reported **IRR** to **11.7666 %** while creating exactly nothing, so the genuine gain from selling at 7.50 % is the **828,232.87** of yield compression — a market view — and it belongs in the paper separately from the **5,027,733.03** the asset itself created ✓ **CORRECT**
- C. it understates performance: the present value at 8 % of the 7.50 % sale is **5,855,965.90** against 5,027,733.03 on a hold, so the paper should claim the larger figure
- D. it is sound provided the buyer's required return is disclosed alongside the **IRR**

Rationale: A sale at the seller's own discount rate is a swap of equal value at a different date, so **1.9075** points of the uplift is early crystallisation and none of it is performance (15.4.4). A states a true number and lets it carry a claim it cannot support. C makes the mirror error to the paper's: the 828,232.87 is real value and it is a view about the capital market rather than about the asset, so claiming it as performance is the same misattribution in a larger figure. D is necessary and not sufficient — disclosing the rate does not separate the three things a board needs kept apart: the value the asset created, the compression, and the **IRR**, which explains neither.

MCQ 15.4-G [15.4.1 · Comprehension] A covenant breach, financial distress and insolvency are three distinct conditions. Which statement distinguishes them correctly?

- A. they are the same condition at three degrees of severity, so the response differs only in urgency
- B. a breach is a test failure at a date, which is cured, waived or amended; insolvency is an inability to pay; distress is a forecast that cannot sustain the contracted debt service for the remaining life, which is a capital-structure problem and is restructured ✓ **CORRECT**
- C. distress is a breach that has occurred at two or more consecutive test dates
- D. distress is present once the debt service reserve has been drawn

Rationale: The three are separated by what they are conditions of — a test, a profile and a payment — and the diagnostic between the second and third is whether scheduled service exceeds sustainable service for one period or for the remaining life (15.4.1). C counts breaches, which says nothing about the forecast. D describes a liquidity event reserves exist to absorb: Kestrel's debt service reserve was never drawn across six deteriorating years, while the distribution test bound throughout.

■ SELF-CHECK — KA 15.4

1. What single test distinguishes distress from a bad period? — Whether scheduled service exceeds sustainable service ($\text{CFADS} \div \text{target coverage}$) for one period or for the remaining life.
2. Why could Kestrel's restructuring not be solved by a haircut alone? — The largest haircut above the enforcement floor is 2,920,432.73, which supports a DSCR of only 1.1359 against the 1.20 required.
3. Why does a grantor insist on early handback funding when it costs the sponsor more? — Not arithmetic but counterparty risk: a late-funded reserve depends on the concessionaire's solvency in the final decade. The clean answer is a reserve plus a bond or guarantee.

— Advanced topics — Domain 15

15.A.1 The restatement problem: when a test date moves under you

Operating covenants are tested on reported figures, and reported figures change — through an audit adjustment, a prior-period error, a reclassification of maintenance cost between capital and revenue, or a superseded forecast basis. Facilities handle this unevenly, so three questions must be settled before they matter: **is a certified test re-opened if the underlying figures are restated**, and within what period; **does a later-discovered breach rank from the original test date or from discovery**, which determines whether the cure and waiver windows have already expired; and **whose basis governs a forward test that has been superseded** — the forecast as made, or as it should have been made. The protection is procedural rather than contractual: certify only on figures that have passed the same controls as the statutory accounts, keep every certified ratio's computation and inputs frozen and retrievable, and disclose a material re-forecast when it is made rather than when it is tested. Domain 10 (KA 10.4.4) established that early disclosure is the asset; this is where it earns its return, because a lender told in advance treats a restated breach as administration and a lender told afterwards treats it as a discovery.

15.A.2 Portfolio operations and the shared-covenant problem

The disciplines of this domain scale badly when each asset is run in isolation, and three portfolio effects deserve naming. **Test-date clustering**: facilities testing on the same quarter-end turn one adverse market event into simultaneous breaches and simultaneous negotiations, exactly when negotiating capacity is scarcest — staggering test dates at the point of documentation costs nothing. **Cross-default and cross-acceleration**: a breach in one ring-fenced project reaches other assets through guarantees, holding-company facilities or change-of-control provisions, so the true exposure of a project-level covenant is a portfolio question no project-level model can see. **Cure-capacity concentration**: a sponsor with four assets each holding two cures does not have eight cures, it has as many as its liquidity supports, which in a correlated downturn is fewer. The response is one consolidated covenant register across the portfolio — every test, date, threshold, cash trigger, cure remaining and cross-default link — owned by one person with authority over all of it. Its absence is the commonest reason a group of individually sound projects experiences a group-level liquidity event.

15.A.3 The reviewer's operating eye

Invariants to test on any operating, waterfall or restructuring model — each one a defect indicator if it fails:

- The operating bridge ties: revenue less cash opex equals **EBITDA**; **EBITDA** less cash tax equals **CFADS** before working capital; the working-capital movement equals the change in the balance sheet position, not a plug.
- The same **CFADS** line feeds the covenant, the lock-up, every distribution test and the reported ratio (Domain 10, KA 10.A.3), and the certified figure is the defined one.
- Every rolling test window contains exactly the debt service the documents say it does; for a level annuity paid annually, exactly one instalment.
- Forward-looking tests are computed on a stated, dated forecast with a named owner, and the outturn is reconciled to it afterwards.
- The waterfall closes in every period: opening balances plus receipts less applications equals closing balances, account by account, with no residual.
- Reserve top-ups rank above distributions, and a period whose residual cannot fund a top-up draws from the block account rather than reducing the top-up.
- Distributions are nil in any period where any condition fails, including the forward leg and the qualitative conditions — a model that distributes on the backward test alone is wrong.
- **LLCR** equals **DSCR** wherever cash is level and service is an annuity at the loan rate (Domain 10, KA 10.2.2) — still true after a refinancing, at the new rate.
- Refinancing arithmetic is complete: old service ceasing, new service arising, break cost on the actual notional profile, every fee, and the sweep.
- A maturity extension at the contract rate returns exactly par in present value; if the model says otherwise, the model is wrong.
- Restructuring options are tested against the enforcement floor before they are presented, and the floor's sensitivity to the distressed buyer's required return is shown as a range.
- The handback sinking fund reaches the obligation in its final year; the funding profile is irrelevant when the reserve rate equals the discount rate.
- Minimum, not average, coverage over the remaining life is reported, and the distribution profile is reported after tests rather than before.

— Industry variations — Domain 15

- **Contracted water and availability-based PPPs.** Deductions are formulaic and performance-linked, so the operating bridge is unusually tight and the covenant is predictable from operating data — Kestrel's case. The distinctive operating risk is an **unhedged input**: a pass-through that was assumed and is not contractual, which is how a 5.9 % power-price rise removes an entire dividend.
- **Contracted power and renewables.** Resource variability makes a single year's coverage uninformative, so structures use rolling multi-year tests and larger reserves; the characteristic operating-phase event is a **curtailment or grid-constraint régime change** that no contract allocated, and the characteristic financing event is a refinancing into a tighter market once operating history exists.
- **Transport concessions.** Patronage risk plus high operating leverage means **CFADS** falls faster than revenue, and ramp-up years dominate the covenant profile. Handback obligations are large,

physical and surveyed — pavement, structures, tolling systems — which makes KA 15.4.5 the sector's defining operating-phase discipline rather than a footnote (Case study B).

- **Regulated utilities.** Regulatory reset cycles produce step-changes in allowed revenue, so covenant testing and reserve sizing must straddle resets; the operating-phase negotiation is frequently a **covenant reset timed to the determination**, and a rolling test that spans a reset measures two different businesses.
- **Digital infrastructure.** Short asset lives compress the tail, so refinancing capacity is limited and the tenor lever of KA 15.3.2 is weaker; contract renewal rather than performance is the covenant risk, and technology obsolescence makes the handback and residual-value questions genuinely open rather than formulaic.
- **Mining and resources.** Price exposure dominates and distress is cyclical rather than idiosyncratic, so restructurings are negotiated against a commodity view; the enforcement floor is unusually volatile, which widens the bargaining range and makes the sensitivity discipline of 15.4.3 essential rather than good practice.

— Case study — Domain 15: the dividend the forward test cancelled (water / desalination)

Situation. Kestrel Water reached the end of its first operating year having done everything right. Availability had held at the 95.0 % guarantee, 10,000,000 m³ had been delivered, **CFADS** of **6,384,000** matched the base case to the dollar, and the backward **DSCR** of **1.2743** cleared both the 1.20× covenant and the 1.25× distribution condition. After debt service of 5,009,635.23 and the 600,000 maintenance-reserve charge, **774,364.77** sat in the proceeds account, and the board's papers showed it as the first dividend. Between the year-end and the test date, the operator revised its power-cost forecast: a supply contract had rolled onto merchant pricing, and the delivered cost of energy would rise from 0.26 to roughly 0.40 per cubic metre. Management re-forecast year two at **5,500,000** of **CFADS**.

What happened. The distribution condition required 1.25× on a forward-looking as well as a backward-looking basis. The re-forecast gave a forward **DSCR** of **1.0979**, and the dividend was not payable. The 774,364.77 went into the distribution-block account. The board's first reaction was that the test had been misapplied — the project had met every covenant — and the second was that the re-forecast should be revisited. Both reactions were understandable and the second was dangerous: the finance director's position, that a forecast prepared to stop a dividend and a forecast prepared to support one cannot be different documents, held, and the re-forecast stood. Year two delivered **CFADS** of **5,963,894.11** — **463,894.11 above** the forecast that cancelled the dividend, and still a **DSCR** of **1.1905**, a covenant breach. The sponsors cured it for **47,668.16**, the cheapest available response, consuming one of two lifetime cures. Year three was worse: fouling took availability to 88.0 %, **CFADS** fell to **5,202,936.48**, **DSCR** to **1.0386**, and the year's residual after debt service was **193,301.25** against a 600,000 reserve charge — so **406,698.75** of the maintenance top-up was drawn from the block account.

How it resolved. With one cure left and a breach requiring **808,625.80** to cure, the sponsors negotiated rather than paid: a covenant reset to 1.00× for two test dates stepping to 1.10× and 1.20×, a **40 basis point** margin uplift with a present value of **651,258.24**, an amendment fee of **92,178.38**, monthly reporting, and a committed **1,500,000** of remediation equity. The membrane replacement was brought forward from year five and cost 3,000,000 against a reserve of 1,800,000 — the **1,200,000** gap and **300,000** of reserve restoration being exactly what the injection funded.

Power was hedged at 0.32 for year four and 0.30 thereafter. Year four recovered to **CFADS 6,094,641.91** (DSCR 1.2166 — still below the 1.25 distribution test), and year five cleared both legs at **1.2936** backward and **1.2966** forward, releasing the whole **1,206,931.59** block-account balance alongside the year's **870,992.76** as a **2,077,924.35** distribution. Over six years equity lost **3,182,311.16** of cash — **1,682,311.16** of trading shortfall and **1,500,000** of capital call — and **2,709,838.79** of present value at 8 %.

What the domain teaches here. Three things, in order of how often they are got wrong. The project was never in danger: the debt service reserve of 2,504,817.62 was never touched, because even the worst year's cash exceeded debt service by 193,301.25. What bound was the distribution test, at 1.9103 % of **CFADS** against the covenant's 5.8339 % — and the sponsors had modelled the covenant. The block account was not a penalty but the pre-funding that paid for year three's reserve shortfall out of year one's cancelled dividend, which is the strongest available argument against negotiating a weaker distribution test. And the 47,668.16 cure was the expensive decision of the whole sequence: paying **7,638.87** more for a waiver would have preserved an option worth 808,625.80 nine months later, and the amendment that replaced it cost **743,436.62**.

— Case study B — Domain 15: the handback nobody had surveyed (transport concession)

Situation. A thirty-year urban toll-road concession approached expiry. The concession agreement required the concessionaire to hand the asset back in a defined condition and to fund a handback reserve over the **final five years**, against an independent estimate to be prepared in **year 25**. That estimate came in at **42,000,000**, producing a contribution of **7,910,892.00** a year into a reserve earning 3.00 % — comfortably affordable against distributable cash of **21,000,000**, leaving **13,089,108.00** a year for shareholders. The estimate was prepared from design records and a visual inspection. No intrusive condition survey was commissioned, because the agreement did not require one until year 28.

What happened. The year-28 survey found the obligation was **58,000,000**, not 42,000,000 — an understatement of **16,000,000**, or **38.0952 %**. Two causes, both foreseeable: pavement rehabilitation was required over a substantially longer length than the design records implied, because a mid-life resurfacing had been thinner than specified; and the tolling system needed wholesale replacement, which the original estimate had treated as the incoming operator's cost on a reading of the agreement that the grantor did not share. By the end of year 28 the reserve held **24,451,776.08**, which would grow to **25,940,889.24** by expiry — leaving a gap of **32,059,110.76** to be funded from two remaining years.

How it resolved. The required additional contribution was **15,792,665.40** a year, taking the total reserve charge to **23,703,557.40** — **112.8741 %** of distributable cash. The final two years therefore produced no distributions at all and a shortfall of **2,703,557.40** a year, met by a sponsor injection of **5,407,114.79** in aggregate — the additional contribution of **31,585,330.80** over two years consuming the **26,178,216.00** of dividends those years would have paid and 5,407,114.79 more besides. The grantor additionally held a retention of **2,900,000** — 5 % of the works — for twelve months against defects. The concession completed and handed back on time, and the sponsor's realised return on a thirty-year asset was set, in the end, by an estimate prepared from records in year 25.

What the domain teaches here. The obligation was affordable and the timing was not. Had the 58,000,000 been known at year 20 and funded over ten years, the charge would have been **5,059,369.38** a year — **24.0922 %** of distributable cash, absorbed without comment. The

26,178,216.00 of forgone distributions and **5,407,114.79** of injected equity was therefore the price of an **information** failure, not a cash failure: a survey commissioned eight years earlier than the agreement required would have cost a fraction of one year's contribution. Two further lessons. An estimate prepared from design records is an estimate of the asset as designed, and a thirty-year asset is not the asset as designed. And a reserve is not a substitute for a credit instrument: the grantor's protection came from the retention and the sponsor's willingness to inject, not from a reserve that was funded on a schedule the agreement itself had made too late.

— Executive perspective — Domain 15

What a project finance director cannot delegate in this domain:

- **The distribution conditions, in full and in cash.** Not the covenant — the test that stops the dividend, including its forward leg, its qualitative limbs and the reserve charges that rank above it. For Kestrel that is 6,262,044.04 of **CFADS**, 1.9103 % below base case, and it is the number that belongs at the top of the operating dashboard.
- **The re-forecast basis, and its owner.** A forward-looking test makes the company's own forecast the instrument that stops its own dividend. The basis, the timing, the reviewer and the reason a forecast prepared to stop a payment is the same document as one prepared to support it are the director's to establish before the first test date, not during it.
- **The reserve sizing assumption.** Kestrel's 1,500,000 capital call — 47.1 % of the six-year cost to equity — was caused by a maintenance reserve levelised on the assumption that a five-year replacement cycle runs to five years. That is a financing judgment wearing engineering clothes, and it is the director's.
- **The cure inventory.** How many cures remain, what each is worth, and the standing rule that a marginal breach is waived rather than cured. Kestrel's 47,668.16 decision cost an option worth 808,625.80, and it was taken by someone optimising a single test date.
- **The whole term sheet on any refinancing or amendment.** Margin, tenor, fees, break cost and sweep priced together as one net present value, with the breakeven computed before the first meeting. A 155 basis point saving that destroys 206,835.69 of value, and a consent whose sweep costs more than the gain it consents to, are both signed by directors who priced one line.
- **The handback obligation, from the first operating year.** Its estimate vintage, the date of the next intrusive survey, the reserve's earning rate, and the credit instrument standing behind it. It falls due after everyone who negotiated it has gone, which is precisely why it needs an owner now.

— Calculation exercises — Domain 15

Exercise 15.1 Annual debt service is 7,200,000 and **CFADS** is 9,100,000. The facility has a 1.20× covenant, a 1.10× lock-up and a 1.30× distribution condition. The cash tax rate is 25 %, and the capacity payment abates by 120,000 per percentage point of availability. State each trigger in cash, the headroom, and the availability movement that reaches the covenant and the distribution test.

Solution. $DSCR = 9,100,000 / 7,200,000 = 1.2639$. Covenant $7,200,000 \times 1.20 = 8,640,000$, headroom **460,000** (**5.0549 %** of **CFADS**); lock-up $\times 1.10 = 7,920,000$, headroom **1,180,000** (**12.9670 %**); distribution $\times 1.30 = 9,360,000$, a **shortfall of 260,000** (**-2.8571 %**) — the project already fails its

distribution test while comfortably inside its covenant. Cash-to-revenue gearing is $1 - 0.25 = 0.75$, so revenue headroom to the covenant is $460,000/0.75 = 613,333.33$, which is $\div 120,000 = 5.1111$ availability points; the distribution test is already breached by $346,666.67$ of revenue, i.e. **2.8889 points** of availability must be recovered to restore it. Common error: computing availability movement from the CFADS headroom directly ($460,000 \div 120,000 = 3.83$ points), which omits the tax shield and understates the tolerance by a quarter.

Exercise 15.2 In a period, CFADS is 8,450,000, debt service 7,200,000 and the required maintenance-reserve top-up 450,000. The distribution condition is $1.30\times$ backward and forward; the forward twelve-month forecast is 7,650,000. State the distributable amount and what happens to it.

Solution. After debt service **1,250,000**; after the reserve top-up **800,000**. Backward $DSCR\ 8,450,000/7,200,000 = 1.1736$; forward $7,650,000/7,200,000 = 1.0625$. The test requires $7,200,000 \times 1.30 = 9,360,000$ on both legs, so **both fail** and the **800,000 is trapped in the distribution-block account**, available for a future reserve top-up or release when the tests are next satisfied. Common error: reporting 1,250,000 as the distributable amount by omitting the reserve top-up that ranks above equity — the single most common error in operating distribution forecasts (15.2.2).

Exercise 15.3 A facility has 31,500,000 outstanding with 8 years remaining at an all-in 5.75 %. The market offers 4.55 % over the same 8 years. Costs: arrangement fee 1.00 %, prepayment fee 0.25 %, advisers 260,000, swap break 640,000. Discount incremental cash at 8 %. Compute the net present value and the breakeven all-in rate.

Solution. $AF(0.0575, 8) = 6.271705$, so the existing instalment is $31,500,000/6.271705 = 5,022,557.82$. $AF(0.0455, 8) = 6.582433$, so the new instalment is **4,785,464.53** and the annual saving **237,093.28**. $AF(0.08, 8) = 5.746639$, giving a present value of **1,362,489.49**. Costs $315,000 + 78,750 + 260,000 + 640,000 = 1,293,750$. **Net present value +68,739.49**. The breakeven all-in rate is **4.6112 %** — the margin must fall by **113.88 basis points** against the **120** on offer, leaving **6.12 basis points** of cushion. Common error: discounting the saving over the loan's full original tenor rather than its remaining 8 years, which inflates the present value and can turn a marginal transaction into an apparently comfortable one.

Exercise 15.4 A distressed project has 24,000,000 outstanding with 7 years remaining at 5.5 %, and revised CFADS of 3,600,000 flat. Lenders require $1.25\times$ restored and will not accept a recovery below an enforcement floor of 90.0 %. Determine the extension tenor required, the haircut the coverage requirement implies, and whether a haircut is feasible.

Solution. Sustainable service $3,600,000/1.25 = 2,880,000$ against the current instalment of $24,000,000/AF(0.055, 7) = 24,000,000/5.682967 = 4,223,146.03$ ($DSCR\ 0.8524$ — deeply distressed). Required annuity factor $24,000,000/2,880,000 = 8.333333$; $AF(0.055, 11) = 8.092536$ (instalment 2,965,695.68, $DSCR\ 1.2139$ — insufficient) and $AF(0.055, 12) = 8.618518$ (instalment **2,784,701.55**, $DSCR\ 1.2928), so the tenor must extend to **12 years**, five years beyond the current maturity. A haircut retaining the 7-year tenor supports only $2,880,000 \times 5.682967 = 16,366,945.30$, a haircut of **7,633,054.70 (31.8044 %)** and a recovery of **68.1956 %** — far below the 90.0 % floor, so **infeasible**. The largest feasible haircut is $24,000,000 \times 10.0 \% = 2,400,000$, which supports an instalment of **3,800,831.42** and a $DSCR$ of only **0.9472**: as with Kestrel, **the haircut cannot solve the problem and an extension is unavoidable**. Common error: computing the required annuity factor and rounding the tenor down (11 years), which leaves coverage at 1.2139 and the covenant still breached — restructuring tenors round up.$

Exercise 15.5 A 12,000,000 handback obligation falls due at the end of year 25. A reserve earns 2.5 %; equity discounts at 8 %. Compare funding over years 16–25, years 11–25 and years 6–25 on present cost, and state the rate at which the choice ceases to matter.

Solution. $FVAF(0.025, 10) = 11.203382 \rightarrow 1,071,105.16$ a year, present cost $1,071,105.16 \times AF(0.08, 10) \times DF(0.08, 15) = 2,265,706.06$. $FVAF(0.025, 15) = 17.931927 \rightarrow 669,197.47$ a year, present cost $2,653,163.73$. $FVAF(0.025, 20) = 25.544658 \rightarrow 469,765.54$ a year, present cost $3,139,004.45$. Latest funding is cheapest; funding twenty years ahead costs **873,298.39 more** than funding ten. The choice ceases to matter when the reserve rate equals the discount rate, at which point every profile costs $12,000,000 \times DF(0.08, 25) = 1,752,214.86$. Common error: ranking the profiles by total contributions (**9,395,310.90** over twenty years against **10,711,051.58** over ten) and concluding that early funding is cheaper — a comparison of undiscounted sums across different decades, which reverses the correct answer.

— Practitioner's toolkit — Domain 15

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 15.T.1 — The operating bridge (one per reporting period)

A single sheet running from physical performance to certified **CFADS**, in fixed rows: availability and its abatement effect · delivered volume and its unit contribution · each unit cost with its exposure quantity · revenue · cash operating cost · **EBITDA** · depreciation · **EBIT** · interest · profit before tax · cash tax · **CFADS** before working capital · working-capital movement, decomposed into receivables, payables and inventory · **CFADS as defined**, with the clause reference. Two columns beside each row: budget and prior period. Two rules: the working-capital movement is a derived figure from balance-sheet positions and never a plug; and the sheet carries the cash-to-revenue gearing at the foot, so every variance can be read straight into covenant headroom.

Toolkit 15.T.2 — Operating covenant and distribution register (one per facility, per test date)

Per test: name and clause · test date and frequency · backward, rolling or forward-looking · window length · threshold · computed value · **the CFADS level at which it triggers** · headroom in currency and as a percentage of base case · **the same headroom in each driver's own units** · reserve balances against required levels · block-account balance and what it is earmarked for · cures used and remaining, with the value of the largest breach each remaining cure would cover · information covenants due and delivered · cross-default links to other facilities (15.A.2). Front line, in this order: **which test binds first, by how much cash, in which driver, and how many cures remain.**

Toolkit 15.T.3 — Transaction decision sheet (refinancing, amendment or restructuring)

- [] Incremental cash-flow set complete: existing service ceasing, new service arising, every fee, break costs on the actual notional profile, and the sweep.
- [] Discount rate stated, owned and sensitivity-tested; the sign of the answer confirmed at both the cost of debt and the cost of equity.
- [] **Breakeven computed before the first meeting** — margin, tenor, fee or sweep share, whichever is being negotiated.

- [] Value decomposed: how much is margin, how much tenor, how much interaction, how much covenant reset.
- [] For an amendment: sized against the stressed case, not the current one; the reset tested against the downside forecast at every date it must survive.
- [] For a restructuring: sustainable service computed; each option's restored coverage verified; the extension identity checked (par at the contract rate); recovery reported at the contract rate **and** at a risk-adjusted rate.
- [] Enforcement floor computed, with its sensitivity to the distressed buyer's required return shown as a range; any option below the floor removed before presentation.
- [] Equity value and lender recovery reported for every option, on one page (Fig 15.4.1).
- [] Cure inventory stated; the option value of each remaining cure quantified.
- [] AI-produced analysis: the breakeven re-derived independently, one period recomputed by hand, every clause reading checked against the document, verifier named.

— Exam preparation — Domain 15

What is assessed. Whether a candidate can operate a financing rather than arrange one: build and reconcile an operating bridge; convert every threshold into cash and into driver units; distinguish backward, rolling and forward tests and reason about the lag; run a waterfall period by period including reserve top-ups and a block account; separate the cash cost of a drought from its timing cost; price a refinancing, a waiver, a cure, an amendment and a sweep against one another; compare restructuring options on both sides of the table and locate the enforcement floor; size a handback sinking fund; and value an exit without confusing crystallisation with performance.

The calculations to do under time pressure. Trigger in cash (debt service $\times$ threshold) and headroom, then headroom $\div$ cash-to-revenue gearing to reach the driver. Distributable = CFADS – debt service – reserve top-ups. Rolling four-quarter sums from a quarterly series. Refinancing net present value = saving $\times$ AF(discount rate, remaining years) – total costs, and the breakeven rate by inspection of AF. Sustainable service = revised CFADS $\div$ target coverage, then the required annuity factor and the tenor from the factor table. Haircut = outstanding – sustainable service $\times$ AF. Sinking-fund contribution = obligation $\div$ FVAF.

The traps, each cross-referenced. Omitting the reserve top-up from a distribution forecast (15.2.2, Exercise 15.2) · quoting covenant headroom when the distribution test binds (15.1.3, MCQ 15.1-A) · converting cash headroom into driver units without the tax gearing (15.1.2, Exercise 15.1) · expecting a rolling backward test to register a current deterioration (15.1.4, MCQ 15.1-C) · reading a working-capital release as improved trading (15.1.2) · treating a lock-up as a write-off, or as a matter of no consequence (15.2.4) · pricing a refinancing on the margin alone (15.3.2, MCQ 15.3-A) · discounting a refinancing saving over the original rather than the remaining tenor (Exercise 15.3) · negotiating a sweep separately from the transaction it pays for (15.3.4) · spending a scarce cure on a marginal breach (15.3.3, MCQ 15.3-C) · sizing an amendment against the current case rather than the stress (15.3.3) · reporting an extension as par without a risk-adjusted recovery (15.4.2, MCQ 15.4-A) · proposing a haircut below the enforcement floor (15.4.3, MCQ 15.4-B) · rounding a restructuring tenor down (Exercise 15.4) · claiming an IRR uplift from early crystallisation as value created (15.4.4, MCQ 15.4-C) · ranking handback funding profiles on undiscounted totals (15.4.5, Exercise 15.5).

How the domain connects. Backwards: Domain 2 supplies the accrual-to-cash bridge and the CFADS definition this domain reports on; Domain 3 the amortisation schedule whose opening balances drive every break-cost and margin-uplift calculation; Domain 4 the appraisal outturn is measured against,

and the **IRR** pathologies that reappear in the exit arithmetic of 15.4.4; Domain 6 the model that is now a contractual deliverable; Domain 7 the revenue mechanics behind the operating bridge; Domain 10 every ratio, reserve and covenant this domain operates; Domain 12 the security package that makes the enforcement floor real; Domain 13 the model audit certification depends on; Domain 14 the completion tests that start the operating clock. Forwards: Domain 16 governs the automation of KA 15.1 and 15.2 — where most organisations will actually put AI to work in finance.

— Domain 15 summary

The operating phase is governed by the distribution test, not the covenant. Kestrel Water's covenant binds at **CFADS** of **6,011,562.28 — 372,437.72**, or 5.8339 %, below base case — but its distribution condition binds at **6,262,044.04**, only **121,955.96** or **1.9103 %** below, and that is the number that decides whether shareholders are paid. The operating bridge from availability and volume through **EBITDA** of 7,500,000 and cash tax of 516,000 to the defined **CFADS** of **6,384,000** makes the translation possible in both directions: a **0.80** cash-to-revenue gearing means every headroom figure understates the revenue tolerance by a quarter, so the covenant is reached by **6.0585** points of availability and the distribution test by **1.9839**. Rolling backward tests lag by their own window — Kestrel's covenant does not fail until 1.1905 four quarters after the decline begins, while the forward test fails at **1.0979** immediately — which is why the forward leg exists and why the re-forecast basis is a governance matter. Running the waterfall for six real years produces the domain's central demonstration: the **2,504,817.62** debt service reserve was never drawn, because even the worst year's **5,202,936.48** of **CFADS** exceeded debt service by 193,301.25, while the distribution test withheld four consecutive dividends and the block account rose to **1,206,931.59** before releasing into a **2,077,924.35** payment in year five. That trapped cash was not lost but deployed — the **406,698.75** maintenance-reserve shortfall of year three was funded from the dividend cancelled in year one — and the six-year cost to equity of **3,182,311.16** in cash and **2,709,838.79** in present value decomposes cleanly into **1,682,311.16** of trading shortfall and **1,500,000** of capital call, which are two different people's accountabilities. Base-case equity earns **774,364.77** a year, a **4.3020 %** cash yield rising to 32.13 % once the loan retires, for a 25-year **IRR** of **9.8591 %** and an **NPV** at 8 % of **5,027,733.03**. Mid-life, arithmetic discipline replaces enthusiasm: a **155 basis point** margin reduction destroys **206,835.69** because the breakeven reduction is **177.94** basis points, and only the tenor extension — 1,418,714.07 of margin, 586,108.78 of tenor and 420,208.04 of interaction — makes the transaction worth **+799,481.12**, which a 50 % cash sweep costing **646,327.86** then more than takes back (breakeven sweep share **40.3334 %**). A waiver at **55,307.03** and a cure at **47,668.16** differ by 7,638.87 and by an option worth **808,625.80**; an amendment at **743,436.62** and that second cure differ by **5,290.97**, which means the decision was never about price. In distress the three levers are time, principal and new money, and the enforcement floor of **91.4291 %** decides among them: the extension recovers **95.0779 %** at a risk-adjusted 7 % and leaves equity **14,898,548.64**; the injection recovers **96.3549 %** and leaves **14,072,829.99**; the haircut equity most wants recovers **82.9037 %** and is infeasible, and even the largest feasible haircut of **2,920,432.73** restores only a **1.1359 DSCR** — so an extension is unavoidable. An exit at the sponsor's own discount rate raises the **IRR** from 9.8591 % to **11.7666 %** while the **NPV** stays identical at 5,027,733.03, and only the **828,232.87** of yield compression is real. And the last obligation is the first forgotten: an **8,000,000** handback funded over the final decade costs **1,476,147.78** in present value against **1,989,422.56** funded over two, because a reserve earning 3 % is equity lending to itself at a 500 basis point negative spread — an argument that disappears entirely when the reserve rate reaches the discount rate, at which every profile costs **1,168,143.24**. Domain 16 governs the automation of all of it.

16

DOMAIN 16

Data, Automation and Responsible AI in Finance

— Why this domain exists

Fifteen domains have each ended with a paragraph on where machine assistance earns its place and where it must not go. Those paragraphs were judgments — well-founded, but judgments. They left one question open, and it is the question a finance director actually has to answer: **at what point, measured in money, does automating a piece of the finance function stop being a slide and start being a decision that survives audit?** Nothing so far has priced an automation, chosen an alert threshold, sized a validation suite, or stated what a human approval costs and what it buys. This domain does all four, and it does them with the same decimal discipline the book applies to a debt schedule, because an automation programme that cannot be costed cannot be governed.

The domain's central claim is that **responsible AI in finance is a quantitative discipline, and the numbers usually point somewhere other than intuition.** Four results carry the chapter, and each contradicts something a practitioner is likely to believe. Automation economics turn on the **cost of the errors the automation makes**, not on the labour it displaces — so the more consequential the work, the more volume automation needs before it pays, which is the opposite of the usual argument for automating the important things first. An anomaly detector tuned to maximise accuracy is tuned wrongly whenever a false positive and a missed error cost different amounts, and the gap between the accuracy-optimal and the cost-optimal threshold is a real annual number somebody is paying. Validation by testing proves far less than it appears to: the suite an organisation can afford bounds the defect rate at a level that still admits hundreds of errors a year at production volume, which is why continuous monitoring and human approval — not pre-deployment testing — carry the assurance load. And the value of a control, like the value of a loosened threshold, is a **marginal** quantity: a blanket four-eyes rule is close to value-neutral, while the same rule above a derivable threshold is strongly positive.

Underneath all four sits the principle the suite has carried since its first page, now with an arithmetic meaning rather than a rhetorical one: **AI proposes; the professional verifies, decides and remains accountable.** Verification is not a moral posture in this domain. It is a line item whose expected return, in every worked example below, runs between **eighteen and four hundred and thirty times** its cost — and that is the finding a leader should take away, because it survives disagreement about the technology.

Learning objectives. After this domain a candidate can: describe a financial-data spine and price the architecture choice against a pairwise-reconciliation estate using the registered interface count; compute the all-in cost per reviewed item for a manual and an automated process including the cost of the errors each makes, and derive the breakeven volume, the volume at which a specific asset does not justify automation, the automated error rate at which the case reverses, and the consequence cost at which it reverses; explain why the breakeven rises with the consequence of an

error; read an anomaly detector as a classifier, compute precision, recall, accuracy and total misclassification cost at several thresholds, identify the cost-minimising threshold, demonstrate that it differs from the accuracy-maximising threshold, quantify the annual cost of choosing the latter, and derive the break-even posterior probability and the marginal precision test that locates the optimum; derive the number of scenarios required to surface a failure mode of stated probability at stated confidence and explain why a reported worst case from a generated set is a percentile rather than a stress; compute the probability that a multi-item document extraction is entirely correct, derive the per-item accuracy a stated sweep confidence requires, and defend a verification scope on the load-bearing subset; compute the real and apparent saving from machine-assisted model building and price the review that is habitually omitted; test an explanation for attributional completeness using the hundred-per-cent rule; derive the zero-failure validation sample size for a stated confidence and defect-rate bound, adjust it for one observed failure, and translate a validated defect rate into expected annual production errors; identify and quantify label bias in a detector trained on a prior process's output, and size the blind audit sample that measures it; build a model inventory tiered by expected annual loss and derive each model's revalidation interval; price a managed against a private deployment and state the breach consequence at which the answer flips; derive a dual-approval threshold from the approver's cost and the loss it prevents, and compute the value destroyed by applying the control blanket-fashion; price approval latency using the registered governance-latency formula; and set out an AI governance frame — inventory, tiering, human approval, incident and rollback, disclosure — that a lender's information covenants can be satisfied against.

The master estate. Kestrel Water SPC is in operation, with the structure Domains 10 and 15 established. Its sponsor group owns **six operating assets** and runs one finance function across them, and that is the unit this domain analyses, because automation economics are a portfolio question rather than a project question. The estate produces **56,400 consumption-and-billing records a year** (Kestrel alone contributes **9,400**) that feed the revenue forecast, and **48,000 payments and journal entries a year** of which **2.5 per cent** are genuinely erroneous. Nine finance-relevant systems hold the data. A proposed financial-data spine costs **USD 900,000** to build and **USD 140,000** a year to run; a separate review-automation platform commits **USD 148,000** a year against a manual review pipeline costing **USD 13.60** a record in labour. Against that estate the domain prices every judgment the earlier fifteen made in words: Kestrel's covenant headroom of **USD 372,438** a year is the yardstick every data-quality figure is measured against, because it is the amount of cash the project can lose before a covenant fails, and a forecast error, a missed anomaly or a misread definition that exceeds it is not an operational nuisance but a credit event.

KNOWLEDGE AREA 16.1

Financial-data architecture, forecast automation and anomaly detection

Topics: 16.1.1 the financial-data spine · 16.1.2 forecast automation and the economics of a review · 16.1.3 anomaly detection as a classifier.

16.1.1 The financial-data spine

Definition. A **financial-data spine** is a single governed layer through which every system publishes and consumes financial facts, so that each fact has one authoritative representation. Four properties make it a spine rather than a warehouse. **Grain** — every table states the level at which one row is

one fact (one meter reading, one invoice line, one period's [CFADS](#)), because most reconciliation failures are grain mismatches rather than arithmetic errors. **Golden source** — exactly one system is authoritative for each fact, named, and the others are derived. **Lineage** — every reported figure can be traced to the transactions beneath it without human reconstruction. And the property that matters most in a financing and is most often absent, the **definitional layer**: the facility's defined terms are implemented **once**, as code, with a clause reference, so that [CFADS](#) means in the data what it means in the document.

That last property is the finance-specific one, and it is why this topic is not an information technology digression. Domain 2 (KA 2.3.1) showed Kestrel's [CFADS](#) moving by **600,000** on one working-capital treatment, and Domain 10 (KA 10.1.1) showed that the same trading year therefore supports a [DSCR](#) of either 1.39 or 1.27. In a nine-system estate with no definitional layer, [CFADS](#) is implemented as many times as it is needed, each implementation drifts, and the organisation discovers the drift when two papers disagree in front of a credit committee.

WORKED EXAMPLE**Worked example 16.1.1 — pricing the architecture, then pricing the thing that actually matters.**

1. **Setup.** Nine finance-relevant systems: the billing platform, the meter-data historian, the general ledger, the treasury system, the fixed-asset register, the payroll system, the procurement and payables system, the model repository and the lender-reporting pack. Today each pair that must agree is reconciled directly. Each **pairwise** reconciliation consumes **12 hours a month** (a monthly tie-out plus investigation of differences); a **spine feed** consumes **4 hours a month** (a load and an exception report). The loaded analyst hour is **USD 96.00**. The spine costs **USD 900,000** to build and **USD 140,000** a year to run. Appraise it at the board's **8 per cent** over **10 years**.
2. **Formula.** The registered interface count (PML-AI Domain 4, "mesh versus layered interfaces"): a mesh needs $n(n-1)/2$ pairwise interfaces where a layer needs n . Annual cost = interfaces $\times$ hours a month $\times$ 12 $\times$ rate. Then $NPV = \text{net annual saving} \times AF(0.08, 10) - \text{build}$.
3. **Substitution.** Mesh interfaces $9 \times 8 / 2 = 36$; spine feeds 9. Mesh $36 \times 12 \times 12 \times 96.00$; spine labour $9 \times 4 \times 12 \times 96.00$, plus the 140,000 run cost. $AF(0.08, 10) = 6.710081$.
4. **Result.** Mesh **5,184 hours a year**, costing **USD 497,664**. Spine **432 hours a year**, costing **USD 41,472** of labour and **USD 181,472** all-in. Net annual saving **USD 316,192**; simple payback **2.8464 years**; $NPV = 316,192 \times 6.710081 - 900,000 = +\text{USD } 1,221,674$.
5. **Interpretation.** The case passes, but read why it passes, because the reason is the convexity rather than the level. The mesh grows as the square of the estate: adding a tenth system adds 9 pairwise reconciliations — **1,296 hours** and **USD 124,416** a year — against **48 hours** and **USD 4,608** for one more spine feed, a ratio of **27 to 1**. At fifteen systems the mesh needs **105** reconciliations and **USD 1,451,520** a year against the spine's **USD 69,120**. So the spine is not a labour saving on today's estate; it is the only architecture whose cost is linear in an estate that will grow, and the appraisal should be run at the estate size the organisation expects rather than the one it has. Two cautions, and the second is the professional one. **The saving is only realised if the pairwise reconciliations are actually retired** — estates routinely acquire a spine and keep the reconciliations, which converts a 316,192 saving into a 181,472 cost — the spine's own 41,472 of feed labour plus its 140,000 run cost, paid on top of an unchanged mesh — and that failure is a governance failure rather than a technical one. And **the labour case is not the case that matters**. A single definitional divergence in **CFADS** is worth **600,000** of reported cash (Domain 2, KA 2.3.1) — **1.6110 times** Kestrel's entire annual covenant headroom of 372,438 — and a definition implemented wrongly in code does not misreport once: it misreports every period until somebody finds it, so over the same ten-year appraisal it is worth $600,000 \times AF(0.08, 10) = \text{USD } 4,026,049$ in present value, **3.2955 times** the 1,221,674 the hours produced. The business case that gets built is the labour one; the business case that decides is the definitional one. State both, and be honest that the second is the reason.

16.1.2 Forecast automation and the economics of a review

Definitions. **Forecast automation** replaces a manual cycle — pull the period's consumption and billing records, screen them for plausibility, correct what is wrong, re-run the revenue forecast — with a pipeline that ingests, screens, refers exceptions to a person, and publishes. **Cost per reviewed item** is the all-in cost of processing one record, and it has two parts that must both be counted: the **processing cost** (labour, platform, inference) and the **error cost**, being the residual

undetected-error rate multiplied by the consequence of an undetected error. A comparison that omits the second part is not a comparison.

WORKED EXAMPLE**Worked example 16.1.2 — the breakeven volume, and why it moves the wrong way.**

- Setup.** The estate's consumption-and-billing pipeline. **Manual: 8.5 minutes** a record at **USD 1.60** a minute; the manual process leaves **1.80 per cent** of records with an undetected error; an undetected error costs **USD 320** (re-billing, credit notes, the downstream forecast correction and the reconciliation to the lender pack). **Automated:** committed fixed cost **USD 148,000** a year (licence, platform, model maintenance, monitoring and the governance overhead this domain later specifies); **USD 0.50** a record of platform and inference; **5.00 per cent** of records referred to a person for adjudication at **6.75 minutes** each (adjudication is faster than full review because the pipeline presents the exception with its context); residual undetected-error rate **2.60 per cent** — higher than the manual process, which is the assumption most automation cases quietly omit.
- Formula.** Cost per item = processing cost + (undetected-error rate × consequence). Total annual cost = fixed + volume × cost per item. Breakeven volume V^* where the two totals are equal: $V^* = \text{fixed} \div (\text{manual cost per item} - \text{automated cost per item})$.
- Substitution.** Manual $8.5 \times 1.60 = 13.60$, plus $0.018 \times 320 = 5.76$. Automated $0.50 + 0.05 \times (6.75 \times 1.60) = 0.50 + 0.54 = 1.04$, plus $0.026 \times 320 = 8.32$. Advantage $19.36 - 9.36$. Breakeven $148,000 \div 10.00$.
- Result.** Manual **USD 19.36** a record; automated **USD 9.36** a record of variable cost; advantage exactly **USD 10.00**; **breakeven 14,800 records a year**. At Kestrel's own **9,400** records the automation costs **USD 54,000 a year more** than the manual process. Across the six-asset portfolio's **56,400** records it saves **USD 416,000 a year** (manual 1,091,904 against 675,904 all-in, or **USD 11.9841** a record).
- Interpretation.** Three readings, in ascending order of usefulness. **First, the answer is an estate answer, not an asset answer.** The same platform is a 54,000 annual loss at one project and a 416,000 annual gain at six, and no amount of enthusiasm at the project changes that; the project's honest options are to wait for the estate, to buy a service priced per record rather than per year, or to decline. Automation cases fail at the asset level far more often than they fail technically. **Second, the error-cost term is where the case is decided, and omitting it flatters automation.** Ignore both error rates and the advantage rises to $13.60 - 1.04 = 12.56$, so the breakeven appears at **11,783 records — 3,017 records, or 20.3822 per cent**, lower than the truth. The sensitivities are worth carrying in the head: at the portfolio's 56,400 records the case survives an automated undetected-error rate up to **4.9050 per cent** (against the 2.60 modelled, so it tolerates nearly double) and a consequence cost up to **USD 1,241.99** an error. **Third — and this is the result that changes behaviour — the breakeven rises with the consequence of an error.** Reprice an undetected error at **USD 1,200** rather than 320 and both processes get dearer, but the automated one gets dearer faster, because its error rate is the higher of the two: manual **35.20**, automated **32.24**, advantage only **2.96**, and the **breakeven moves to 50,000 records a year**. At the portfolio's 56,400 the whole programme is then worth **USD 18,944** a year — arithmetically positive, professionally indistinguishable from nil. The intuition to abandon is "automate the important work first". The defensible rule is the reverse: **automate the high-volume, low-consequence work, and spend the freed capacity on the low-volume, high-consequence work where a human error rate of 1.80 per cent beats a machine's 2.60**. The caution that belongs beside every such case: both error rates are measured quantities, and an organisation that has not measured its manual error rate has no automation case at all, only an aspiration with a spreadsheet.

Where automation starts to pay — and what the error cost does to the answer

Net annual saving against the manual process. Committed automated fixed cost 148,000 a year; manual review 13.60 a record at a loaded 96.00 an hour; automated variable 1.04 a record.



Raising the cost of an undetected error from 320 to 1,200 moves the breakeven from 14,800 records to 50,000: the more consequential the error, the more volume automation needs — because its error rate is the higher of the two.

Fig 16.1.2 — Where automation starts to pay, and what the error cost does to the answer

The forecast-quality translation. The pipeline's purpose is a better forecast, and forecast quality has to be expressed in covenant terms to mean anything to a board. Measured over the estate's last three years, the manual cycle's revenue forecast carried a mean absolute percentage error of **4.8 per cent** and the automated pipeline's **3.1 per cent**. On Kestrel's **CFADS** of **6,384,000** those are error bands of **USD 306,432** and **USD 197,904** — **82.2773 per cent** and **53.1374 per cent** of the annual covenant headroom of 372,438. That is the sentence that belongs in the paper: the improvement is not "1.7 points of accuracy", it is **the difference between a forecast band that nearly consumes the covenant headroom and one that consumes half of it**. Note also what the comparison does not license — a lower average error does not mean a smaller tail, and the covenant is tested in periods (Domain 10, KA 10.2.1), so the figure to monitor is the worst period's error, not the mean.

16.1.3 Anomaly detection as a classifier

Definitions. An anomaly detector assigns each item a score and raises an **alert** above a threshold. Four counts follow: **true positives (TP)**, real errors caught), **false positives (FP)**, clean items investigated), **false negatives (FN)**, real errors missed) and **true negatives (TN)**. From them: **recall** = $TP / (TP + FN)$, the share of real errors caught; **precision** = $TP / (TP + FP)$, the share of alerts that are real; **accuracy** = $(TP + TN) / \text{total}$, the share of all items classified correctly. And the measure that should govern the choice of threshold, which none of those three is: **total misclassification cost** = $FP \times \text{cost of a false positive} + FN \times \text{cost of a false negative}$.

WORKED EXAMPLE**Worked example 16.1.3 — the threshold, chosen properly.**

1. **Setup.** The estate's payment-and-journal detector: **48,000** items a year, of which **2.5 per cent — 1,200** are genuinely erroneous and **46,800** are clean. Investigating a false positive costs **USD 40** (25 minutes of an analyst). A missed error costs **USD 320**. Five candidate thresholds have been measured on a held-out year.
2. **Formula.** Recall, precision and accuracy as defined; total cost = $FP \times 40 + FN \times 320$. The decision rule for one marginal item: act when the probability the item is a real error exceeds the **break-even posterior** = cost of a false positive ÷ cost of a false negative.
3. **Result.**

Threshold	TP	FP	FN	Recall	Precision	Accuracy	Alerts	Total cost
T1 (score ≥ 0.90)	600	110	600	50.0 %	84.5070 %	98.5208 %	710	196,400
T2 (≥ 0.80)	720	205	480	60.0 %	77.8378 %	98.5729 %	925	161,800
T3 (≥ 0.70)	840	400	360	70.0 %	67.7419 %	98.4167 %	1,240	131,200
T4 (≥ 0.60)	960	950	240	80.0 %	50.2618 %	97.5208 %	1,910	114,800
T5 (≥ 0.45)	1,080	2,900	120	90.0 %	27.1357 %	93.7083 %	3,980	154,400

1. **Result, stated.** Total cost is minimised at **T4 — USD 114,800 a year**. Accuracy is maximised at **T2 — 98.5729 per cent**, where the total cost is **USD 161,800**. Choosing the accuracy-maximising threshold therefore costs **USD 47,000 a year**.
2. **Interpretation.** The headline is the one the spine of this domain demands: **maximising accuracy is the wrong objective whenever a false positive and a false negative cost different amounts**, and here they differ eight-fold. Accuracy weights every item equally, so it is dominated by the 46,800 clean items and rewards a detector for leaving them alone; cost weights each item by its consequence, and a missed error costs eight investigations. The 47,000 is not an abstraction — it is an annual sum the finance function is paying for a metric choice nobody minuted. Three further readings do the professional work. **The optimum looks bad on precision.** At T4 only **50.2618 per cent** of alerts are real, so the team working the queue experiences a coin flip and will lobby to tighten the threshold; the leader's job is to explain that a queue which is half false is the correct queue at these costs, and to resource the **1,910 alerts** — at 25 minutes each, about **795.83 hours** a year, or **USD 76,400** of analyst time — rather than tune the model to make the queue feel better. **The decision rule is marginal, not average.** The break-even posterior is $40 \div 320 = 12.5$ per cent: act on an item whenever there is at least a **one in eight** chance it is real. Average precision at every threshold in the table exceeds 12.5 per cent, including T5's 27.1357 per cent — yet T5 is worse than T4, because what matters is the quality of the **additional** alerts a looser threshold buys. From T3 to T4 the step adds 120 real errors and 550 false ones: marginal precision **17.9104 per cent**, above 12.5, benefit $120 \times 320 = 38,400$ against cost $550 \times 40 = 22,000$, net **+16,400** — take it. From T4 to T5 the step adds 120 real and **1,950** false: marginal precision **5.7971 per cent**, benefit 38,400 against cost **78,000**, net **-39,600** — refuse it. The optimum is where marginal precision crosses the break-even posterior, and every step's net exactly reconciles to the change in the cost column, which is the arithmetic check to run on any such table. **And the two cost inputs are the real argument.** They are estimates, and the threshold is a function of their ratio alone, so the productive discussion in the room is "what does a missed error actually cost us?" rather than "which model is best". Change the ratio to 1:4 and the optimum tightens to T3; change it to 1:20 and it loosens to T5, the last

threshold measured. State the ratio, own it, and revisit it when the consequence changes — for instance when the same detector begins to screen items that feed a covenant certificate rather than a management report.




Fig 16.1.3 — The accuracy-maximising threshold is not the cost-minimising threshold

AI in this KA

Where it earns its place. Everything in this knowledge area is machine work by construction, and the highest-value application is the one organisations skip: using the pipeline's own output to **measure** the quantities the business case assumed. The manual error rate, the automated error rate, the referral rate, the adjudication time and the realised consequence of an undetected error are all observable once the pipeline is instrumented, and a business case that is re-run on measured inputs each year is a governed automation rather than a purchased one. Machine assistance also belongs in the threshold work — scoring a held-out year at fifty thresholds and tabulating cost is trivial for a machine and tedious for a person.

Where it must not go. No model may set its own operating threshold, because the threshold encodes the organisation's view of what a missed error costs, and that is a judgment with an owner. Nor may a detector's alert be closed by the same system that raised it: adjudication is the human step that converts a score into a finding, and a pipeline that both flags and clears has no control in it at all (16.4.2 prices exactly this). And no automation business case may be approved on processing costs alone — the omission of the error-cost term is the specific, nameable defect that makes automation look 20.3822 per cent better than it is.

Verification, concretely. Recompute one period's cost per item by hand from the loaded rate, the minutes and the measured error rate, and require agreement to the cent. Confirm that every

threshold row's total cost reconciles to the previous row's plus the marginal benefit less the marginal cost — an arithmetic identity that catches transcription errors instantly. Confirm the prevalence used in the table against a blind audit rather than against the detector's own labels (16.3.3 shows what happens when this is skipped). Reconcile the pipeline's published forecast to the ledger for one period, line by line, and express the residual as a percentage of covenant headroom rather than of revenue. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 16.1

Term	Meaning
Financial-data spine	A single governed publishing layer; n feeds in place of $n(n-1)/2$ reconciliations.
Grain	The level at which one row is one fact; most reconciliation failures are grain failures.
Golden source	The one system authoritative for a fact; all others are derived.
Definitional layer	The facility's defined terms implemented once, as code, with clause references.
Cost per reviewed item	Processing cost + (undetected-error rate × consequence of an error).
Automation breakeven volume	Committed fixed cost ÷ the per-item cost advantage.
Recall / precision / accuracy	Real errors caught ÷ real errors · real alerts ÷ alerts · all correct ÷ all items.
Total misclassification cost	$FP \times \text{false-positive cost} + FN \times \text{false-negative cost}$; the objective to minimise.
Break-even posterior	False-positive cost ÷ false-negative cost; the probability above which acting pays.
Marginal precision	Additional true positives ÷ additional alerts from loosening a threshold.

■ SAMPLE MCQS — KA 16.1

MCQ 16.1-A [16.1.2 · Application] Manual review costs 13.60 a record and leaves 1.80 % of records with an undetected error; automated processing costs 1.04 a record and leaves 2.60 %; an undetected error costs 320; the automated platform's committed fixed cost is 148,000 a year. The breakeven volume is:

- A. 11,783 records a year
- B. 14,800 records a year ☒ **CORRECT**
- C. 15,812 records a year
- D. 142,308 records a year

Rationale: All-in costs are $13.60 + 0.018 \times 320 = 19.36$ and $1.04 + 0.026 \times 320 = 9.36$; the advantage is 10.00 and $148,000 \div 10.00 = 14,800$. A omits the error-cost term from both sides (advantage 12.56, $148,000 \div 12.56 = 11,783$) — the specific defect of 16.1.2. C divides the fixed cost by the automated all-in cost per record ($148,000 \div 9.36$) instead of by the advantage, treating the comparison as an absorption problem rather than a differential one. D makes the same error against the automated processing cost alone ($148,000 \div 1.04$), ignoring the manual alternative entirely.

MCQ 16.1-B [16.1.2 · Analysis] An organisation reprices an undetected error from USD 320 to USD 1,200 on the same two processes — manual review 13.60 a record leaving 1.80 % of records

with an undetected error, automated processing 1.04 a record leaving 2.60 %, on a committed fixed cost of 148,000 a year. The breakeven volume:

- A. falls, because errors are now more expensive and automation catches more of them
- B. is unchanged, because the error rates are unchanged
- C. rises from 14,800 to 50,000, because the automated process has the higher error rate so a larger consequence erodes its advantage **✓ CORRECT**
- D. becomes irrelevant, because at a high enough consequence neither process is acceptable

Rationale: Manual becomes $13.60 + 0.018 \times 1,200 = 35.20$ and automated $1.04 + 0.026 \times 1,200 = 32.24$; the advantage falls from 10.00 to 2.96 and $148,000 \div 2.96 = 50,000$. A assumes the automation is the more accurate process, which the given rates contradict. B confuses the rates with their monetised effect. D is a governance observation, not the arithmetic asked for — and at 56,400 records the automation is still positive, by 18,944.

MCQ 16.1-C [16.1.3 · Analysis] A detector's five thresholds give accuracies of 98.5208, 98.5729, 98.4167, 97.5208 and 93.7083 per cent and total misclassification costs of 196,400, 161,800, 131,200, 114,800 and 154,400. The threshold that should be operated, and why:

- A. the second — it maximises accuracy, which is the standard classification metric
- B. the fifth — it maximises recall, and missing an error is the expensive outcome
- C. the fourth — it minimises total cost, which is the only objective that reflects the different consequences of the two error types **✓ CORRECT**
- D. the first — its precision of 84.5070 % gives the investigation team the most reliable queue

Rationale: Accuracy weights all items equally and is dominated by the 46,800 clean ones; cost weights each by consequence, and the minimum is 114,800 at T4 — choosing T2 on accuracy costs 47,000 a year. B over-corrects: T5's extra 120 catches cost 78,000 of investigation to save 38,400. D optimises the queue's comfort rather than the firm's loss.

MCQ 16.1-D [16.1.3 · Analysis] A false positive costs 40 and a missed error 320. Loosening the threshold from T4 to T5 would add 120 true positives and 1,950 false positives. The correct conclusion is:

- A. accept — the marginal alerts still have 27.1357 % precision overall, well above the 12.5 % break-even
- B. refuse — marginal precision is 5.7971 %, below the 12.5 % break-even, and the step costs 78,000 to save 38,400 **✓ CORRECT**
- C. accept — recall rises from 80 % to 90 %, and recall is the measure lenders ask about
- D. indeterminate without knowing the anomaly base rate

Rationale: The test is on the marginal alerts: $120 \div (120 + 1,950) = 5.7971\%$, and the net is $-39,600$, which reconciles exactly to the cost column rising from 114,800 to 154,400. A quotes T5's average precision, which is the standing error in threshold decisions. C treats a ratio as an objective. D is false — the counts given already embed the base rate.

MCQ 16.1-E [16.1.1 · Evaluation] The paper recommending the financial-data spine leads with a **+1,221,674** net present value from retiring 36 pairwise reconciliations, a 316,192 annual labour saving against a 900,000 build. What should a reviewer require before it goes to the board?

- A. nothing further — a +1,221,674 net present value at the board's 8 % over ten years clears the hurdle on its own

- B. the definitional case stated alongside it — one CFADS divergence is worth 600,000 a period and 4,026,049 in present value over the same appraisal, 3.2955 times the labour case — together with a commitment to retire the 36 reconciliations, without which the 316,192 saving becomes a 181,472 annual cost ☒ **CORRECT**
- C. that the appraisal be re-run at the fifteen-system estate the group expects, where the mesh costs 1,451,520 a year against the spine's 69,120
- D. that the 900,000 build be competitively tendered, since it is the largest single figure in the paper

Rationale: B supplies both the reason the decision actually turns and the condition the quoted benefit depends on: a spine acquired beside an unretired mesh converts a saving into a cost, and that is a governance failure the paper must foreclose (16.1.1). C is a genuine improvement the topic recommends, but it strengthens a case that already passes and speaks to neither the real driver nor the realisation risk. D optimises a one-off number while leaving a recurring 600,000 exposure unaddressed. A accepts a business case whose stated benefit is conditional on a commitment nobody has made.

MCQ 16.1-F [16.1.2 · Comprehension] Cost per reviewed item has two parts. Which restatement best captures why the second cannot be left out?

- A. because the platform's committed fixed cost must be spread over the volume before any per-item figure means anything
- B. because a process is only as cheap as the mistakes it leaves behind, so the residual undetected-error rate multiplied by the consequence of an undetected error belongs in the price of the process that produced it ☒ **CORRECT**
- C. because errors that are found still cost money to put right
- D. because the pipeline exists to improve forecast accuracy, and accuracy belongs in its cost

Rationale: The second part monetises the errors that survive the process, which is what makes two processes with different accuracies comparable (16.1.2). A names a real and separate term, which the breakeven-volume calculation handles — the per-item figures of 19.36 and 9.36 are variable costs by construction. C describes detected errors, whose handling already sits inside the processing cost as adjudication minutes. D confuses a benefit with a cost.

MCQ 16.1-G [16.1.2 · Evaluation] A finance director proposes automating the estate's highest-consequence review work first, because that is where an error costs most and a machine is more consistent than a person. On the measured figures — manual review **13.60** a record leaving **1.80 %** of records with an undetected error, the pipeline **1.04** a record leaving **2.60 %**, against a committed **148,000** a year — the soundest sequencing advice is to:

- A. automate the highest-consequence work first, since that is where an error costs most and consistency is worth most
- B. automate the high-volume, low-consequence work and spend the freed capacity on the low-volume, high-consequence work, because the breakeven **rises** with the consequence of an error — 14,800 records at 320 an error, 50,000 at 1,200 — while the manual 1.80 % beats the pipeline's 2.60 % ☒ **CORRECT**
- C. automate nothing until the pipeline's residual error rate falls below the manual rate, since automating a less accurate process cannot be justified
- D. automate everything at once, because the 148,000 is committed whatever the scope and the marginal record then costs only 1.04 to process

Rationale: The automated process carries the **higher** residual error rate, so a larger consequence per error erodes its advantage instead of enlarging it: repricing an undetected error from 320 to 1,200 moves the breakeven from 14,800 records to 50,000, at which the estate's 56,400 records leave the whole programme worth **18,944** a year — arithmetically positive and professionally indistinguishable from nil (16.1.2). A is the intuition the arithmetic reverses. C sets a defensible-sounding but wrong condition: at 56,400 records and 320 an error the case tolerates an automated rate up to **4.9050 %**, nearly double the 2.60 % modelled, because volume and consequence decide the comparison and not the rate alone. D compares 1.04 with 13.60 and so omits the error-cost term from both sides — the defect that makes automation look **20.3822 %** better than it is.

MCQ 16.1-H [16.1.1 · [Comprehension](#)] A data spine has four properties: grain, golden source, lineage and a definitional layer. Which statement best explains what the **definitional layer** adds that the other three do not?

- A. it stores the finance documents beside the data, so a defined term can be looked up whenever a figure is questioned
- B. it implements each defined term once, as code, with its clause reference, so a term means in the data what it means in the document instead of being re-implemented — and drifting — wherever it is needed ✓ **CORRECT**
- C. it lets every reported figure be traced back to the transactions beneath it without human reconstruction
- D. it names the one system that is authoritative for each fact, so that all others are derived

Rationale: C and D are the spine's other two properties — lineage and golden source — and neither prevents [CFADS](#) from being implemented differently in nine systems; the definitional layer is the finance-specific property, and it is why a divergence worth 600,000 of reported cash does not misreport once but every period until somebody finds it (16.1.1). A describes a document repository, which resolves nothing: a term that can be looked up is still implemented separately wherever it is used.

■ SELF-CHECK — KA 16.1

1. Why does the automation breakeven rise as the consequence of an undetected error rises? — Because the automated process has the higher residual error rate, so a larger consequence penalises it more than the manual process, eroding the per-item advantage: 14,800 records at USD 320 an error, 50,000 at USD 1,200.
2. State the one-line decision rule for acting on an alert, and the test that locates the optimal threshold. — Act when the probability the item is real exceeds the false-positive cost divided by the false-negative cost (here 12.5 per cent, one in eight); the optimum is where the **marginal** precision of loosening crosses that figure, not where average precision or accuracy looks best.
3. What does a data spine actually buy in a financing, beyond hours? — One implementation of each defined term, so [CFADS](#) means in the data what it means in the document; the 600,000 definitional divergence of Domain 2 is 1.6110 times Kestrel's annual covenant headroom, and because a mis-implemented definition recurs every period it is worth 4,026,049 in present value over the ten-year appraisal — 3.2955 times the whole labour case.

KNOWLEDGE AREA 16.2**Scenario generation, document review and model assistance**

Topics: 16.2.1 scenario generation and the coverage question · 16.2.2 document review and the load-bearing subset · 16.2.3 model assistance and the verification that must replace the build.

16.2.1 Scenario generation and the coverage question

Definition. Scenario generation is the machine production of many coherent states of the world — price paths, demand paths, availability profiles, macro sets — for evaluation through the financial model. It is genuinely valuable and genuinely easy to misreport, because a generated set answers a different question from a **defined case**. Domain 6 (KA 6.4.2) distinguished sensitivity from scenario and Domain 7 built the revenue stresses; neither is re-derived here. What is new is the question a generated set forces: **how many scenarios, and what does the worst one mean?**

WORKED EXAMPLE**Worked example 16.2.1 — coverage, and the worst case that is not a stress.**

1. **Setup.** An analyst reports: "we ran 40 scenarios; three breached the covenant, and our worst case shows a **DSCR** of 1.04." A second analyst reports a 500-scenario run and quotes its minimum **DSCR** as the downside case. Assess both statements. Assume each scenario independently has a **5 per cent** probability of containing the failure mode of interest.
2. **Formula.** Probability that a set of k independent scenarios contains **at least one** instance of a mode of probability p : $1 - (1 - p)^k$. The k needed for a stated detection confidence $1 - \alpha$: $k \geq \ln(\alpha) \div \ln(1 - p)$. The expected percentile of the minimum of k draws: approximately $1 \div (k + 1)$.
3. **Substitution.** $1 - 0.95^{40}$; then $\ln(0.05) \div \ln(0.95)$; then $\ln(0.10) \div \ln(0.99)$; then $1 \div 501$.
4. **Result.** A 40-scenario set contains at least one instance of a 5 per cent mode with probability **0.871488** — so "three of our forty breached" is close to the expected outcome and carries almost no information. To be **95 per cent** confident of surfacing a 5 per cent mode requires **59** scenarios; to be **90 per cent** confident of surfacing a **1 per cent** mode requires **230**. The minimum of 500 draws sits at about the **0.1996th percentile**.
5. **Interpretation.** Two errors are being made, and they are opposite. The first analyst has **under-covered and over-interpreted**: forty scenarios cannot demonstrate the absence of a 1-in-100 mode (which needs 230 for even 90 per cent confidence), and the presence of three breaches is unsurprising rather than alarming. The second has **mislabelled a percentile as a stress**: the minimum of 500 draws is a 1-in-500 event whose value depends almost entirely on the tail of the input distributions, which is the part of a generated model nobody has validated. A defined bank case is a different object — it is a chosen set of assumptions with an owner, which is exactly why lenders insist on it (Domain 6, KA 6.4.1b: the flat case is demanded not because anyone believes it but because it is the case that finds the defect). The professional discipline follows in three parts. **Report k with every scenario statement**, and report the share of scenarios that breach rather than the count, because a count without k is meaningless. **Choose k from the smallest probability you need to see**, not from a run time — $\ln(\alpha) \div \ln(1 - p)$ takes ten seconds and settles the argument. And **never let a generated minimum replace a defined case in a credit paper**; present both, labelled, with the generated set describing shape and the defined case carrying the covenant test. The standing caution: the independence this arithmetic assumes is usually false. Scenarios drawn from one correlated generator explore less of the space than their count suggests, so k computed this way is a **floor**, and Domain 11 (KA 11.4.1) already priced what a correlation assumption is worth when it is wrong.

16.2.2 Document review and the load-bearing subset

Definition. Machine document review extracts structured facts — defined terms, thresholds, test dates, notice periods, caps — from long agreements. On a project financing this is among the most valuable applications available, because the documents are long, the terms are numerous and the consequences of missing one are quantified elsewhere in this book. It is also the application with the most misleading performance statistics, and the reason is combinatorial.

WORKED EXAMPLE**Worked example 16.2.2 — why 92 per cent per item is worthless, and what to do instead.**

1. **Setup.** A facility agreement contains **340** defined terms. **26** of them are load-bearing: they feed the model, a covenant test or a reported ratio. An extraction tool is measured at **92 per cent** per-item accuracy. The question a reviewer must answer is not "how accurate is the tool?" but "what is the probability the deliverable is right?"
2. **Formula.** For m independent items each correct with probability a , the probability that **all** are correct is a^m . The per-item accuracy required for a stated sweep confidence c is $a \geq c^{(1/m)}$.
3. **Substitution.** 0.92^{26} ; then $0.95^{(1/26)}$.
4. **Result.** The probability that all 26 load-bearing definitions are extracted correctly is **0.114415** — so there is an **88.5585 per cent** chance that at least one is wrong. Across all 340 terms the expected number of errors is **27.2**. To be **95 per cent** confident of a clean sweep of 26 items, per-item accuracy must reach **99.8029 per cent**.
5. **Interpretation.** This is the single most important arithmetic in the domain for anyone tempted to rely on an extraction, and it generalises: **per-item accuracy is the wrong statistic whenever the deliverable requires every item to be right**. A tool reported as "92 per cent accurate" delivers a correct 26-item summary about one time in nine. And the required 99.8029 per cent is not a procurement target — no honest vendor will offer it, and no buyer should believe it — so the resolution is not a better model. It is a **change of scope**: do not require the machine to be right, require the load-bearing subset to be **verified**. Price that. Twenty-six definitions at half an hour each of a legal-and-finance specialist at USD 240.00 an hour is **USD 3,120**. Set it against one known consequence: Domain 2's working-capital treatment of **CFADS** is worth **600,000** of reported cash, which is **1.6110 times** Kestrel's annual covenant headroom of 372,438, and the verification is **192.3077 times** cheaper than that single error. The professional posture that follows is precise rather than pious. Let the tool read all 340 terms and produce the register — that is real and large value, because a human reading 340 terms will also miss some and will take days. Then **verify the 26 against the document, by a named person, with the date recorded**, and treat the other 314 as indicative until one of them becomes load-bearing. Two cautions. **The subset must be chosen before the tool runs**, or the tool's own confidence scores will choose it, and a model is least confident where it is wrong in ways it can detect — not where it is wrong in ways it cannot. And **superseded drafts are the commonest failure mode in practice**, not misreading: an extraction from the wrong version is 100 per cent accurate against the wrong document, which no accuracy statistic can see. Case study B is that failure, priced.

16.2.3 Model assistance and the verification that must replace the build

Definition. Model assistance is machine help in constructing a financial model — formula generation, schedule construction, restructuring a workbook, writing the check block, translating a term sheet into a debt module. Domain 6 built the model and its six invariants; this topic asks only what changes when the model is built with assistance, and the answer is that **the verification burden moves and grows**.

The mechanism is worth stating precisely, because it is usually described as a productivity gain and it is really a redistribution. A modeller who builds a schedule by hand acquires, as a by-product, a mental model of how it works — where the circularity sits, which cell drives which, what a wrong

answer would look like. A reviewer of a machine-built schedule has none of that, so review must reconstruct it, and reconstruction is slower than construction was for the person who did it. The saving is real; it is just much smaller than the build-time comparison suggests.

WORKED EXAMPLE

Worked example 16.2.3 — the real saving, the apparent saving, and the price of the difference.

1. **Setup.** A sculpted debt module. **Hand-built:** 40 hours to build, 8 hours to review. **Machine-assisted:** 6 hours to produce, and — because the reviewer must reconstruct the construction logic — 26 hours to review properly. A senior modeller or reviewer costs **USD 150.00** an hour. The organisation's observed record is that an unreviewed machine-assisted module carries a material defect with probability **0.35**; Domain 6 (KA 6.4.1) priced one such defect — a one-cell tax error — at **USD 3,250,352** of lost debt capacity.
2. **Formula.** Cost = hours × rate. **EMV** = probability × consequence (the registered expected-monetary-value form, PML-AI KA 8.2).
3. **Substitution.** Hand $(40 + 8) \times 150$; machine with full review $(6 + 26) \times 150$; machine with the habitual 8-hour review $(6 + 8) \times 150$. **EMV** = $0.35 \times 3,250,352$.
4. **Result.** Hand-built **USD 7,200**; machine-assisted with proper review **USD 4,800** — a **real saving of USD 2,400, or 33.3333 per cent**. Reviewed at the habitual 8 hours the cost is **USD 2,100**, an **apparent saving of 70.8333 per cent**. The omitted 18 hours of review are worth **USD 2,700**. The expected cost of the defect they would have caught is **USD 1,137,623.20** — **421.3419 times** the review.
5. **Interpretation.** The number to carry into a management conversation is **a third, not two thirds**. An organisation that books the 70.8333 per cent has not made a saving; it has converted USD 2,700 of certain cost into USD 1,137,623.20 of expected cost, and it has done so invisibly, because the omission leaves no artefact. Three consequences follow. **Fund the review explicitly, as a line, at the ratio the organisation has measured** — here roughly four hours of review per hour of assisted build, against one per five hand-built; the ratio is the governable quantity and it should be in the model-governance standard, not left to the reviewer's diary. **Require the assistant to produce the audit trail, not just the model:** a written statement of what each block does, the invariants it should satisfy, and the check block itself, which is work a machine does well and which cuts reconstruction time — this is the single most effective way to make the 26 hours smaller honestly. **And keep the accountability where Domain 6 put it:** the modeller who ships the module owns its defects regardless of who typed the formulae, and the organisation that treats "the tool built it" as mitigation has no model governance. The caution worth stating plainly: the 0.35 defect probability is this organisation's measured figure on its own work, not a general property of assisted modelling, and a firm that has not measured its own should assume a figure high enough to make the review unarguable and then measure.

AI in this KA

Where it earns its place. All three topics are the application, so the useful question is what machine assistance adds to their **governance**, and the answer is measurement and coverage. Machines are good at computing what a scenario set covers, at diffing an extraction against a previous version of the same agreement (which catches the superseded-draft failure directly), and at generating the invariant tests a reviewer would otherwise write by hand. A second, genuinely strong use: having one model **critique** another's output — an adversarial pass over an extraction register or

a generated scenario set, asked to find the internally inconsistent entries — because inconsistency detection is cheap for a machine and does not require the machine to be right about the substance.

Where it must not go. No machine may choose the load-bearing subset (16.2.2), decide k (16.2.1) or sign a model off (16.2.3), because each of those is a scoping decision that determines what will not be checked. Nor may a generated scenario minimum be presented as a bank case, or a critique pass be treated as verification: an adversarial model that finds nothing has not established that there is nothing, and treating a silent critique as assurance is the most seductive failure in this knowledge area.

Verification, concretely. Recompute a^m for the actual subset size before relying on any extraction summary — one line of arithmetic that reframes the whole procurement. Diff the extraction against the executed document's defined-terms clause, not against a data room copy, and record the version identifier. For scenario work, publish k , the share of scenarios breaching, and the defined case separately. For assisted models, run Domain 6's six invariants plus the effective-tax-rate check before any output is quoted, and record the review hours actually spent against the standard's ratio — an unfunded review is the defect this knowledge area exists to prevent. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 16.2

Term	Meaning
Scenario coverage	$1 - (1 - p)^k$: the chance k scenarios contain a mode of probability p .
Required k	$\ln(\alpha) \div \ln(1 - p)$: scenarios needed to surface a mode at $1 - \alpha$ confidence.
Generated minimum	The worst of k draws; a percentile ($\approx 1/(k+1)$), not a defined stress case.
Load-bearing subset	The extracted items that feed a model, covenant or reported ratio; the verification scope.
Sweep probability	a^m : the chance an m -item extraction is entirely correct at per-item accuracy a .
Reconstruction cost	The review time a machine-built artefact needs because no one holds its construction logic.
Superseded-draft error	Extraction from the wrong version; 100 per cent accurate against the wrong document.

■ SAMPLE MCQS — KA 16.2

MCQ 16.2-A [16.2.2 · Application] A tool extracts defined terms at 92 % per-item accuracy. Twenty-six of them are load-bearing. The probability that all 26 are correct is closest to:

- A. 92.00 %
- B. 11.44 % ☒ **CORRECT**
- C. 88.56 %
- D. 99.80 %

Rationale: $0.92^{26} = 0.114415$. A mistakes per-item accuracy for deliverable accuracy — the error the topic exists to correct. C is the complement, the probability that at least one is wrong. D is the per-item accuracy that would be required for a 95 % clean sweep, $0.95^{(1/26)}$.

MCQ 16.2-B [16.2.2 · Analysis] Given that result, the defensible professional response is:

- A. reject machine extraction and read all 340 terms manually

- B. procure a tool with 99.8029 % per-item accuracy
- C. use the tool for all 340 terms, then verify the 26 load-bearing terms against the executed document by a named person on a recorded date — about USD 3,120 against a single known 600,000 exposure ☒ **CORRECT**
- D. accept the register and rely on the tool's confidence scores to flag which entries to check

Rationale: The remedy is a change of scope, not of tool: verification of the load-bearing subset is 192.3077 times cheaper than one 600,000 definitional error. A discards the tool's genuine value on the other 314 terms. B specifies an unachievable target. D lets the model choose its own verification scope, and a model is least confident where it can detect its own error — not where it cannot.

MCQ 16.2-C [16.2.1 · Analysis] An analyst reports "40 scenarios run, 3 breached, worst-case DSCR 1.04". The soundest critique is:

- A. 40 is too few to demonstrate the absence of a low-probability mode — 230 are needed for 90 % confidence on a 1 % mode — and the worst of 40 draws is a percentile, not a defined stress case ☒ **CORRECT**
- B. 3 breaches out of 40 is a 7.5 % breach probability, which should be reported as the covenant risk
- C. the run is adequate; scenario counts above 30 are conventionally sufficient
- D. the analyst should have reported the mean DSCR across the 40 scenarios

Rationale: Coverage and labelling are the two defects: $\ln(0.10) \div \ln(0.99) = 230$, and a generated minimum is roughly the $1/(k+1)$ percentile of an unvalidated tail. B treats a sample frequency from an unvalidated generator as a probability. C invents a convention. D reports the statistic covenants never test (Domain 10: the minimum, not the average).

MCQ 16.2-D [16.2.3 · Application] A module takes 40 hours to build and 8 to review by hand, or 6 hours assisted with 26 hours of review. At USD 150 an hour, the saving from assistance is:

- A. 70.8333 %
- B. 33.3333 % ☒ **CORRECT**
- C. 85.0000 %
- D. nil, since total hours are similar

Rationale: $(48 - 32) \times 150 = 2,400$ on 7,200, or 33.3333 %. A is the apparent saving when the review is left at the hand-built 8 hours — the omission worth 2,700 of review against 1,137,623.20 of expected defect cost. C compares build hours only (6 against 40). D ignores the 16-hour difference.

MCQ 16.2-E [16.2.1 · Evaluation] A credit paper is being assembled. One analyst offers the **minimum DSCR across 500 generated scenarios** as the downside case; another offers the lenders' defined flat case. Which should carry the covenant test?

- A. the generated minimum — a 1-in-500 outcome is a more conservative test than any case somebody chose
- B. the defined case — the generated minimum is about the 0.1996th percentile of input tails nobody has validated, while a defined case is a chosen set of assumptions with an owner; the generated set belongs in the paper, labelled, describing shape ☒ **CORRECT**
- C. the generated minimum, provided k is reported alongside it so the reader can judge coverage
- D. neither — the mean DSCR across the 500 scenarios is the balanced figure to test

Rationale: Conservatism located in an unvalidated tail is not conservatism, and a generated extreme is a percentile rather than a stress (16.2.1). A is the more seductive error precisely because it sounds

prudent. C is the right discipline applied to the wrong sentence: reporting **k** repairs a coverage claim, but no value of **k** converts a percentile into a case with an owner. D reports the statistic covenants never test — Domain 10 tests the period, not the average.

MCQ 16.2-F [16.2.3 · Evaluation] A modelling team reports a **70.8333 %** saving from machine-assisted construction of a sculpted debt module: 40 hours of build replaced by 6, with review left at the 8 hours the hand-built module carried. Reviewing a machine-built module properly takes **26** hours, because the reviewer must reconstruct construction logic nobody holds. The soundest response is to:

- A. accept the 70.8333 % — the 8 hours were sized for this module, and an assisted module is no harder to read than a hand-built one
- B. book a third rather than two thirds: the honest comparison is 32 hours against 48, and the 18 omitted review hours cost 2,700 against an expected defect cost of 1,137,623.20 — a certain cost converted into an expected one, invisibly, because the omission leaves no artefact
- ☒ **CORRECT**
- C. accept the 70.8333 %, but require the assistant to produce the audit trail, which removes the need for the additional review
- D. stop using assistance on financing models: a 0.35 probability of a material defect is not an acceptable exposure on a debt module

Rationale: Assistance moves the verification burden rather than removing it, and the governable quantity is the review ratio — here about **4.3333** review hours per assisted build hour, against one per five hand-built (16.2.3). A assumes the reviewer holds knowledge only the builder acquires. C is the seductive half-truth: requiring the assistant to state what each block does, the invariants it should satisfy and the check block itself is exactly how the 26 hours are made smaller honestly, but it shortens reconstruction rather than removing the review. D discards a real **33.3333 %** saving, and the 0.35 is the defect probability of an **unreviewed** module — the figure the review exists to remove.

MCQ 16.2-G [16.2.2 · Comprehension] An extraction of a facility agreement's **340** defined terms is reported at 92 % per-item accuracy, and **26** of the terms are load-bearing. Which statement best explains the **superseded-draft** failure mode and why no accuracy statistic can see it?

- A. it is the risk that a term is extracted correctly but recorded against the wrong clause number
- B. it is extraction from the wrong version of the agreement: the register can be 100 per cent accurate against the document it read, so the error lies in which document was read rather than in the reading, and accuracy is measured against that same document ☒ **CORRECT**
- C. it is the risk that a term the tool marked low-confidence is not checked
- D. it is the risk that the load-bearing subset is chosen after the tool has run

Rationale: Accuracy is measured against the source the tool was given, so an extraction from a data-room draft rather than the executed agreement scores perfectly while being wrong throughout — which is why the verification of the 26 load-bearing terms, about **3,120** of specialist time and **192.3077 times** cheaper than one 600,000 definitional error, must be against the **executed** document with its version identifier recorded (16.2.2). C and D are the topic's other two cautions, and both are real: a model is least confident where it can detect its own error, and a subset chosen after the run is chosen by the tool. A describes a mis-citation, which a reconciliation to the clause would catch.

■ SELF-CHECK — KA 16.2

1. Why is per-item extraction accuracy the wrong statistic? — Because the deliverable needs every load-bearing item right: 92 per cent per item gives 0.114415 for 26 items, and a 95 per cent sweep would need 99.8029 per cent per item.
2. How is k chosen for a scenario run? — From the smallest probability the run must be able to surface: $k \geq \ln(\alpha) \div \ln(1 - p)$ — 59 for a 5 per cent mode at 95 per cent confidence, 230 for a 1 per cent mode at 90 per cent — and the result is a floor, because correlated generators explore less than their count implies.
3. What does machine assistance do to a model's total cost? — It moves cost from build to review and reduces the total by about a third, not two thirds; booking the larger figure converts USD 2,700 of review into USD 1,137,623.20 of expected defect cost.

KNOWLEDGE AREA 16.3

Explainability, validation, bias and model risk

Topics: 16.3.1 explainability as an accounting identity · 16.3.2 validation — how many test cases, honestly derived · 16.3.3 bias in a finance model · 16.3.4 model-risk governance: inventory, tiering, revalidation.

16.3.1 Explainability as an accounting identity

Definition. Explainability in a finance context is not a philosophical property of a model; it is the ability to state, for a specific output, **how much of it came from what** — in the units of the output, adding up. A global statement about which inputs matter in general is interpretability and is useful for design. What a decision, an audit or a lender's question requires is a **local, additive attribution** of this period's number.

The test is therefore one the book already owns. PML-AI's **hundred-per-cent rule** — Σ children – parent = 0 at every level — applies unchanged: an explanation whose components do not reconcile to the output is not an explanation, it is a commentary. Suppose an automated forecast publishes **CFADS** of **6,384,000** and attributes it across drivers — volume, tariff, escalation, cash operating cost, cash tax, working-capital movement — summing to **6,190,000**. The residual is **USD 194,000: 3.0388 per cent** of the forecast, and **52.0892 per cent** of Kestrel's annual covenant headroom of 372,438. The professional reading is exact: **the model has an unexplained component larger than half the project's covenant headroom**, so any conclusion drawn from the attribution about which driver to manage is unsafe, and the correct response is to find the residual, not to describe it as model complexity. Three further disciplines belong here. **Attribution must be in currency, not in importance scores** — a ranking cannot be reconciled and therefore cannot be audited. **The counterfactual must be stated**: "volume contributed 1.2m" means nothing without "relative to what", and the baseline is a choice with an owner. And **explanation is not justification**: a faithful account of how a model reached a number says nothing about whether the number is right, which is 16.3.2's job. Where a model cannot be given an additive local attribution at all, the honest options are to use it only for triage and never for a reported figure, or to replace it with one that can — and for a covenant-relevant number the second is usually the right answer.

16.3.2 Validation — how many test cases, honestly derived

Definition. Validation is the evidence that a model performs as claimed on cases it has not seen. The question a governance committee always asks and rarely gets answered is how many test cases are enough, and it has a derivable answer under stated assumptions.

WORKED EXAMPLE**Worked example 16.3.2 — the sample size, and the assurance it does not give.**

1. **Setup.** A covenant-certificate assembler must be validated before deployment. The committee wants to be **95 per cent confident** that its defect rate is **below 1 per cent**. Test cases are independent and representative of production; all of them pass. Then: what changes if one case fails; and what does the validated bound imply at a production volume of **56,400** uses a year?
2. **Formula.** If the true defect rate were p , the probability that n independent tests all pass is $(1 - p)^n$. Requiring that probability to be at most α gives $n \geq \ln(\alpha) \div \ln(1 - p)$. With one failure permitted, the condition becomes $(1 - p)^n + n \cdot p \cdot (1 - p)^{n-1} \leq \alpha$, solved numerically. Expected annual production errors = $p \times \text{uses}$.
3. **Substitution.** $\ln(0.05) \div \ln(0.99)$; then the two-term condition at $p = 0.01$; then $0.01 \times 56,400$; then $\ln(0.05) \div \ln(1 - 10/56,400)$.
4. **Result.** $n \geq 298.0729$, so **299 test cases**, all passing. The sample-size ladder, at 95 per cent confidence: **59** cases bound the rate below 5 per cent, **149** below 2 per cent, **299** below 1 per cent, **598** below 0.5 per cent, **2,995** below 0.1 per cent. Raising confidence to 99 per cent at the 1 per cent bound requires **459**. Permitting **one** failure at the 1 per cent bound and 95 per cent confidence requires **473**. And a model validated to "below 1 per cent" and used 56,400 times a year is consistent with **564 errors a year**; to bound expected production errors at **10** a year the defect rate must be below **0.017730 per cent**, which requires **16,895** passing test cases.
5. **Interpretation.** The ladder is the useful artefact — it converts an unbounded argument into a choice — but the honest content of this example is the last line, and it is uncomfortable. **The test suite an organisation can afford proves far less than the assurance it wants.** Nobody is going to construct 16,895 representative test cases for a covenant-certificate assembler; 299 is already a serious programme. So pre-deployment testing cannot be the control that makes a high-volume model safe, and an organisation that behaves as though it were has mis-sited its assurance. The load must be carried by three things instead: **continuous monitoring** of the production error rate, which accumulates evidence at production volume rather than at test volume and reaches 16,895 observations in **about four months** ($16,895 \div 56,400$ of a year, 109 days), against the years a test programme would need; **human approval** at the points where consequence is concentrated (KA 16.4.3, and the tiering of 16.3.4, which is how one decides where); and **rollback**, because the realistic response to a discovered defect is to stop, not to have prevented it. Four cautions on the arithmetic itself, all of which a reviewer should press. The formula assumes **independence** — 299 near-duplicate cases are not 299 tests, and the commonest inflation of a validation claim is a suite generated from one template. It assumes **representativeness** — a suite drawn from historical cases cannot bound the error rate on the cases the model will actually meet, which is 16.3.3's problem. It gives a **one-sided bound on a binary outcome**, so it says nothing about the size of a defect: 299 passes are consistent with a rare but catastrophic failure, which is why tiering is by consequence and not by rate. And a single failure moves the requirement from 299 to **473** — a **58.19 per cent** increase — which is the arithmetic reason "we fixed it and re-ran the failing case" is not a validation: the suite must grow, not be repaired.

16.3.3 Bias in a finance model

Definition. Bias, in this domain, is a systematic difference between what a model was trained or calibrated on and what it is used on. It is a measurable property, not a moral one, and in project finance it takes four concrete forms worth naming. **Training-period bias** — a demand model calibrated on a period whose conditions no longer hold, which Domain 7's demand work must guard against. **Survivorship bias** — a comparables set of completed, financed, surviving projects, which systematically overstates achievable performance because the failures are absent. **Label bias** — a detector trained on the errors a previous process happened to find, so it inherits that process's blind spots. And **attribute bias with legal exposure** — a counterparty- or location-derived score that operates as a proxy for a protected characteristic; what is lawful here differs materially between jurisdictions and this book does not state any jurisdiction's position, but the professional obligation is constant: know which attributes the model uses, know what they proxy for, and take legal advice before a score of this kind affects access to credit or employment.

Label bias is the one that bites hardest in an automated finance function, because it is invisible in every metric the model reports.

WORKED EXAMPLE**Worked example 16.3.3 — the recall that was never 80 per cent.**

1. **Setup.** The detector of 16.1.3, operating at T4: **48,000** items, **1,200** assumed anomalies, **960** caught, **950** false positives, reported recall **80 per cent**, reported total cost **USD 114,800**. The labels it was trained on came from the previous manual process. A **blind audit** is run over the **46,090** items the detector did not flag: **1,000** sampled, **17** genuine errors found.
2. **Formula.** Extrapolated missed errors = unflagged population × sample error rate. True population = caught + extrapolated. True recall = caught ÷ true population. Restated cost = $FP \times 40 + \text{true FN} \times 320$. Audit sample size for a $\pm e$ bound at $1 - \alpha$ confidence on a proportion p : $n \geq z^2 \cdot p \cdot (1 - p) \div e^2$.
3. **Substitution.** $17 \div 1,000 = 1.70$ per cent; $46,090 \times 0.0170$; then $960 \div 1,744$; then $950 \times 40 + 784 \times 320$; and for the sample size $1.96^2 \times 0.025 \times 0.975 \div 0.01^2$.
4. **Result.** Extrapolated missed errors **784**, against the 240 the model's own arithmetic assumed. True anomaly population **1,744**, **45.3333 per cent** above the assumed 1,200. True recall **55.0459 per cent**, not 80. Restated total cost **USD 288,880** against the reported 114,800 — a factor of **2.5164** — with the false-negative cost understated by **USD 174,080**. The audit that revealed this cost **USD 13,600** — 1,000 items re-reviewed at 8.5 minutes each, **USD 13.60** at the loaded analyst rate, a desk re-review rather than the 25-minute investigation an alert requires — and identified missed errors worth **USD 250,880** a year, a return of **18.4471 times**. A sample of **937** would have sufficed for a ± 1 percentage-point bound at 95 per cent confidence on a 2.5 per cent rate.
5. **Interpretation.** The mechanism deserves stating slowly, because it is the most under-appreciated failure in automated controls. **A detector trained on a prior process's findings learns to reproduce that process, including what it could not see.** Its measured recall is recall against the labels, and if the labels are 60 per cent complete then a bounding estimate of true recall is $0.80 \times 0.60 = 48$ per cent — the audit's 55.0459 per cent sits between that bound and the claim, which is what one should expect. Every metric in 16.1.3's table was computed correctly and every one was measuring the wrong population. Three consequences. **No threshold change fixes this.** If the 784 missed errors are precisely the kinds the old process could not detect, loosening the threshold does not reach them: scaling the T4-to-T5 marginal benefit by the 1.4533 population factor gives **USD 55,808** against an unchanged USD 78,000 of investigation cost, so T4 remains optimal and the answer is a **model change** — new features, and the audit's 17 confirmed errors as a new label source — not a tuning change. **The blind audit is the only instrument that measures this, and it must be blind:** a sample drawn from items the model scored highly, or reviewed by the people who set the labels, reproduces the bias. Budget it as a permanent line, sized by $z^2 p(1 - p)/e^2$ for the precision the decision needs, and re-run it annually. **And restate the business case afterwards.** The automation's claimed saving in 16.1.2 was computed on assumed error rates; the audit is how those become measured, and a case that is never restated is a case that was never governed. The standing caution: extrapolating 17 findings to 784 carries real sampling error — the 95 per cent interval around a 1.70 per cent rate on 1,000 draws is wide enough that the point estimate should be reported with its bound, and the decision should be robust to the low end of it.

16.3.4 Model-risk governance: inventory, tiering, revalidation

Definitions. Model risk is, on the shared registry's definition, the risk of loss from decisions based on flawed, misused or misunderstood models — financial or AI. Domain 11 (KA 11.4.3) established it as a priced line in the operating risk register and made the point that its probability is a function of governance rather than of nature; that analysis is not repeated. What this topic adds is the **governance instrument**: a **model inventory** (every model in use, with its purpose, owner, inputs, outputs, dependencies and the decisions it touches), a **tier** for each, and a **revalidation interval** derived from the tier rather than set by convention.

Tiering by "materiality" is the usual practice and it is unfalsifiable. Tiering by **expected annual loss** is derivable: $\text{EMV per year} = \text{uses a year} \times \text{defect probability} \times \text{consequence per defect}$, on the registered expected-monetary-value form. Set a tolerance for the loss an organisation is willing to accumulate between validations, and the interval follows: $\text{revalidation interval} = \text{tolerance} \div \text{annual EMV}$.

WORKED EXAMPLE

Worked example 16.3.4 — the inventory that sets its own calendar.

- Setup.** Five models in the estate's finance function, with the uses, defect probabilities and consequences measured or estimated as shown. The tolerance for accumulated expected loss between validations is **USD 50,000** per model. Consequences are drawn from figures already established: Kestrel's annual covenant headroom **372,438** (a covenant-forecast error consumes it), the forecast band **306,432** at the manual error level (16.1.2), the **600,000** definitional exposure (Domain 2), a **325,000** waiver fee (Case study B) and **320** per undetected payment error (16.1.3).
- Formula.** $\text{annual EMV} = \text{uses} \times p \times \text{consequence}$; $\text{interval} = 50,000 \div \text{annual EMV}$.
- Result.**

Model	Uses a year	p	Consequence (USD)	Annual EMV	Interval	Policy outcome
M1 Covenant-forecast model	12	0.030	372,438	134,077.68	0.372918 yr = 136.12 d	Quarterly
M2 Payment anomaly detector	48,000	0.001	320	15,360.00	3.255208 yr = 1,188.15 d	Annual (policy floor)
M3 Consumption forecaster	12	0.050	306,432	183,859.20	0.271947 yr = 99.26 d	Quarterly
M4 Defined-term extractor	4	0.885585	600,000	2,125,404.00	0.023525 yr = 8.59 d	Verify every use
M5 Covenant-certificate assembler	4	0.020	325,000	26,000.00	1.923077 yr = 701.92 d	Annual (policy floor)

- Interpretation.** The instrument's value is that it produces a **calendar an auditor can challenge on its inputs** rather than a tier label nobody can argue with. Read three results. **M4's interval of 8.59 days is shorter than the interval between its uses** — four facilities a year, roughly 91 days apart — which means the rule's own arithmetic says the model must be verified at **every** use. That is exactly the conclusion 16.2.2 reached from the combinatorics of a 26-item sweep, arrived at independently from a governance rule, and the agreement of two derivations is

the strongest evidence in this domain that the conclusion is right. **The high-volume model is the low-tier one.** M2 touches 48,000 items but each defect costs 320, so its expected annual loss is the smallest in the inventory and annual revalidation is generous — while M1 and M3, used twelve times a year each, need quarterly attention because one bad output consumes a covenant headroom. The instinct to govern by volume is precisely inverted. **And the policy floor matters as much as the formula.** M2 and M5 compute to intervals above a year, and the standard should nonetheless cap the interval at twelve months, because the formula prices known failure modes and a year of undetected drift is the unpriced one. Two cautions. The tolerance of 50,000 is a policy parameter with an owner, and halving it halves every interval, so it belongs in the standard and not in a spreadsheet. And each *p* is an estimate that the monitoring of 16.3.2 should be replacing with a measurement — the inventory is a living instrument, and a model whose *p* has never been measured should carry the pessimistic figure until it has.

AI in this KA

Where it earns its place. Assurance work has its own automatable core, and it is worth taking: generating a validation suite's boundary and adversarial cases from a specification; monitoring production error rates and raising a drift alert; computing the inventory's *EMV* and interval columns from the monitoring feed so the calendar updates itself; producing the additive attribution of 16.3.1 for every published figure; and diffing a model's behaviour between versions so a change that alters an output nobody expected to change is surfaced before release rather than after.

Where it must not go. A model may not validate itself, in any of the several forms this takes: generating its own test cases from its own training distribution, scoring its own explanations for plausibility, or setting the *p* in its own tier. It may not decide the tolerance, the tier or the interval, which are risk-appetite decisions. And an explanation must never be **generated as narrative** — a fluent paragraph describing why a model produced a figure, unconstrained by the additive reconciliation of 16.3.1, is the most dangerous artefact in this knowledge area, because it is persuasive precisely where it is unverifiable.

Verification, concretely. Reconcile every attribution to its output and require the residual to be nil or explained, in currency (16.3.1). Recompute the validation sample size from the stated bound and confidence, and check the suite for independence by asking how many distinct templates generated it. Confirm the audit sample of 16.3.3 was drawn from unflagged items and reviewed by people outside the labelling process. Recompute one row of the inventory's *EMV* and interval by hand. And require that every *p* in the inventory names its source — measured, estimated, or inherited — because an inventory of estimates presented as measurements is worse than no inventory. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 16.3

Term	Meaning
Local additive attribution	An explanation of one output in the output's own units, reconciling to it.
Attribution residual	Output – Σ attributions; must be nil or explained (the hundred-per-cent rule).
Zero-failure sample size	$n \geq \ln(\alpha) \div \ln(1 - p)$: tests needed to bound a defect rate at $1 - \alpha$ confidence.
Label bias	A detector trained on a prior process's findings inherits its blind spots.
Blind audit	A sample of unflagged items reviewed independently, to measure what the model cannot see.
Model inventory	Every model in use, with purpose, owner, dependencies, decisions touched and tier.
Revalidation interval	Tolerance for accumulated expected loss $\div$ annual EMV, capped by policy.

■ SAMPLE MCQS — KA 16.3

MCQ 16.3-A [16.3.2 · Application] How many independent, representative test cases, all passing, are needed to be 95 % confident that a model's defect rate is below 1 %?

- A. 100
- B. 299 ✓ CORRECT
- C. 95
- D. 459

Rationale: $n \geq \ln(0.05) \div \ln(0.99) = 298.0729$, so 299 — the "rule of three" at $3/p$. A is the reciprocal of the bound, which gives only a 63 % confidence. C confuses the confidence level with a count. D is the requirement at 99 % confidence, not 95 %.

MCQ 16.3-B [16.3.2 · Analysis] That model passes its 299 cases and is then used 56,400 times a year. The correct statement is:

- A. the validation shows the model will produce fewer than 10 errors a year
- B. the validation is consistent with up to about 564 errors a year, so monitoring, human approval at concentrated-consequence points and rollback must carry the assurance ✓ CORRECT
- C. the validation is invalid because the test volume is smaller than the production volume
- D. the validation guarantees a 99 % success rate in production

Rationale: A 1 % bound at 56,400 uses admits $0.01 \times 56,400 = 564$ errors; bounding expected errors at 10 would need 16,895 passing cases. A inverts the bound. C misstates the requirement — test volume need not match production volume, it must be independent and representative. D reads a one-sided confidence bound as a point guarantee.

MCQ 16.3-C [16.3.3 · Analysis] A detector reports 80 % recall at a total cost of 114,800. A blind audit of 1,000 of the 46,090 unflagged items finds 17 genuine errors. The most important consequence is:

- A. the threshold should be loosened until recall reaches 90 %
- B. the true anomaly population is about 1,744 rather than 1,200, true recall is 55.0459 %, and the restated cost is 288,880 — the missed errors are the kinds the labels never contained, so the answer is a model change, not a threshold change ✓ CORRECT
- C. the audit sample is too small to act on

D. the detector should be withdrawn

Rationale: Extrapolating 1.70 % over 46,090 gives 784 missed errors; recall and cost restate to 55.0459 % and 288,880. Loosening (A) does not reach errors the model cannot see — scaling the T4→T5 benefit by 1.4533 gives 55,808 against 78,000 of cost, so T4 remains optimal. C is wrong: 937 would suffice for a ± 1 -point bound at 95 % confidence. D discards a control that still avoids substantial loss.

MCQ 16.3-D [16.3.4 · Application] A model is used 4 times a year, fails with probability 0.885585 per use, and a failure costs 600,000. With a tolerance of 50,000 of accumulated expected loss between validations, the revalidation interval is:

- A. annual, since four uses a year is low volume
- B. about 8.59 days — shorter than the interval between uses, so the model must be verified at every use ☒ **CORRECT**
- C. quarterly, matching the use frequency
- D. about 3.26 years, since the annual EMV is small

Rationale: $EMV = 4 \times 0.885585 \times 600,000 = 2,125,404$; $50,000 \div 2,125,404 = 0.023525$ years. A and C tier by volume or convenience rather than by expected loss — the inversion the topic exists to correct. D is the interval for the payment detector (M2), whose EMV is 15,360.

MCQ 16.3-E [16.3.1 · Comprehension] Which restatement best captures the distinction 16.3.1 draws between an explanation and a justification?

- A. an explanation is qualitative, while a justification is quantitative
- B. an explanation accounts for the route by which a number was arrived at; whether the destination is the right one is a separate claim, resting on separate evidence, and supplying that evidence is validation's job ☒ **CORRECT**
- C. an explanation is what a lender is shown, while a justification is what an auditor is shown
- D. an explanation is a ranking of which inputs mattered most to the output

Rationale: Faithfulness and correctness are separate properties, and conflating them is how a persuasive account of a wrong number survives review (16.3.1, 16.3.2). D describes an importance ranking, which the topic rejects for a different reason again — a ranking cannot be reconciled to the output and so cannot be audited. A and C invent a form and an audience the distinction does not turn on.

MCQ 16.3-F [16.3.2 · Evaluation] A validation suite of **299** cases returns **one** failure. The team fixes the defect, re-runs the failing case so that all 299 now pass, and proposes to deploy. Assess the proposal.

- A. acceptable — the defect is fixed and 299 passing cases meet the stated 1 % bound at 95 % confidence
- B. not acceptable — permitting one observed failure at the same bound and confidence requires 473 cases, **58.19 %** more, so the suite must grow rather than be repaired; and even 299 clean passes admit about 564 errors a year at 56,400 uses ☒ **CORRECT**
- C. not acceptable — one failure in 299 shows the defect rate exceeds 1 %, so the model should be withdrawn
- D. acceptable, provided the failing case joins a regression set and the production error rate is monitored

Rationale: The 299 figure is the size of a **zero-failure** sample; once a failure has been observed, the evidence the claim rests on is a different calculation, and repairing the case does not restore it

(16.3.2). A is the standard move and the specific error the topic names. C over-reads: one failure in 299 does not establish a rate above 1 %, it enlarges the sample the claim needs. D prescribes exactly where the assurance should sit — monitoring reaches 16,895 observations in about four months, which no test programme will — but it does not license a validation claim the sample no longer supports, and the two are separate questions.

MCQ 16.3-G [16.3.1 · Evaluation] An automated forecast publishes **CFADS** of **6,384,000** and attributes it across drivers summing to **6,190,000**. The modelling team proposes labelling the **194,000** residual "other — model complexity" and proceeding to a recommendation about which driver to manage. The soundest position is to:

- A. accept it — at **3.0388 %** of the forecast the residual is within any reasonable reporting tolerance, and no attribution reconciles perfectly
- B. refuse the attribution until the residual is found: 194,000 is **52.0892 %** of the annual covenant headroom of 372,438, so no conclusion about which driver to manage is safe, and an explanation whose components do not reconcile to the output is a commentary rather than an explanation ✓ CORRECT
- C. replace the currency attribution with ranked driver-importance scores, which convey the same management message without needing to reconcile
- D. accept it — explanation is not justification, so the completeness of the attribution is a separate question from whether the forecast is right

Rationale: The hundred-per-cent rule applies unchanged, and the residual has to be measured against the quantity the project is judged on rather than against the forecast's own size (16.3.1). A is the tolerance argument, and it fails on the denominator rather than on the principle. C is the commonest substitution and is worse than the defect: a ranking cannot be reconciled and therefore cannot be audited, which is why attribution must be in currency. D quotes a true statement of the topic — a faithful account of how a model reached a number says nothing about whether the number is right — and uses it to excuse the opposite failure, an account that is not faithful.

■ SELF-CHECK — KA 16.3

1. What makes an explanation auditable? — Local additive attribution in the output's own units, reconciling to the output; a 194,000 residual on a 6,384,000 forecast is 52.0892 per cent of covenant headroom and disqualifies any conclusion drawn from the attribution.
2. Why can pre-deployment testing not make a high-volume model safe? — 299 passing cases bound the defect rate below 1 per cent, which at 56,400 uses still admits 564 errors a year; bounding at 10 would need 16,895 cases, so monitoring, human approval and rollback carry the load.
3. What does a blind audit measure that no model metric can? — The errors absent from the labels: 1,000 unflagged items yielding 17 findings restated the population from 1,200 to 1,744, recall from 80 to 55.0459 per cent, and cost from 114,800 to 288,880.

KNOWLEDGE AREA 16.4

Privacy, cybersecurity, human approval and AI governance

Topics: 16.4.1 confidentiality, privacy and the deployment choice · 16.4.2 cybersecurity of an automated finance function · 16.4.3 human approval — what it is, and what it costs · 16.4.4 the AI governance frame.

16.4.1 Confidentiality, privacy and the deployment choice

Definitions. A project financing generates three distinguishable classes of sensitive data, and conflating them produces bad controls. **Commercially confidential information** — the financial model, the price deck, the bank case, draft documents, the offtaker's consumption profile — is protected by contract, and its disclosure damages a live negotiation immediately and irreversibly. **Personal data** — employee, contractor and sometimes customer information — is protected by law that differs materially between jurisdictions; this book does not state any jurisdiction's requirements, and the professional obligation is to establish which regimes apply to each data set before it is processed, and to take advice. **Statutorily or contractually restricted information** — price-sensitive information about a listed sponsor, or data whose location is restricted by a licence or a concession — carries its own consequences independent of the other two.

Two practical rules cut across all three. **Minimisation beats protection:** the surest control on a diligence data set is that the personal data was never loaded, and redaction at ingestion is cheaper than every control downstream. And **retention by a processor is the risk that gets missed** — whether a service retains inputs, for how long, whether they train on them, and in which jurisdiction they rest are contractual questions to settle before use, not afterwards.

WORKED EXAMPLE**Worked example 16.4.1 — the deployment choice, and the number at which it flips.**

1. **Setup.** The automation platform of 16.1.2 can run as a **managed service** at **USD 148,000** a year or as a **private deployment** inside the sponsor's own environment at **USD 410,000** a year. The security function assesses the annual probability of a confidentiality breach involving model or deal data at **0.80 per cent** on the managed service and **0.15 per cent** privately. The consequence of such a breach during a live financing — re-pricing, remedial legal and communications cost, and the relationship damage Domain 10 (KA 10.4.4) priced qualitatively — is assessed at **USD 6,500,000**.
2. **Formula.** $EMV \text{ avoided} = \text{probability differential} \times \text{consequence}$. Compare with the cost differential. Breakeven consequence = cost differential $\div$ probability differential.
3. **Substitution.** $(0.008 - 0.0015) \times 6,500,000; 410,000 - 148,000; 262,000 \div 0.0065$.
4. **Result.** EMV avoided **USD 42,250** a year against a cost differential of **USD 262,000** — so on these figures the private deployment is **not** justified, by USD 219,750 a year. The breakeven consequence is **USD 40,307,692**.
5. **Interpretation.** The value of this calculation is not its answer but the sentence it forces: **state the consequence at which your choice flips, then argue about whether the consequence is really that large**. USD 40.3 million is a large number for a routine operating pipeline, which is why the managed service is defensible for one — and it is not an implausible number for the information set of a live acquisition, a refinancing at scale or a competitive bid, where the loss is the transaction rather than the data. So the professionally correct architecture is usually neither of the two options as posed: **segment the data**, run the high-volume operating pipeline on the managed service, and keep the live-transaction information set — model, price deck, bank case, draft documents — inside the private environment, where the volume is low and the 262,000 differential applies to a fraction of the work. Three cautions. The probabilities are **assessments, not measurements**, and no organisation has enough breach history to measure them, so the arithmetic's honest role is to structure the judgment rather than to settle it — present it as a breakeven, never as an NPV . The consequence is **not fully monetisable**: a breach that costs a licence, or a regulatory consequence in one jurisdiction, is not on this scale at all, and where that is possible the calculation should not be run — the answer is the private deployment regardless of arithmetic. And a private deployment is **not automatically safer**: it moves the risk from a specialist provider's controls to the organisation's own, and an under-resourced private environment can carry the higher probability, which is a real inversion and should be tested rather than assumed.

16.4.2 Cybersecurity of an automated finance function

Definition. Domain 11 (KA 11.4.1) established that cyber risk on an industrial project is primarily an **availability** risk on the operational-technology network and therefore a **CFADS** risk with the same shape as any outage. This topic addresses the different exposure created by automating the **finance** function, which is not availability but **integrity and authority**: the risk that money moves, or a figure is reported, on an instruction nobody competent gave.

Three attack surfaces are specific to an automated finance function and none of them existed in a manual one. **Instruction injection through ingested content**: an assistant that reads supplier invoices, emails or documents will read whatever is in them, including text crafted to look like instructions, so any pipeline that both reads external content and can act must treat ingested text as data and never as direction. **Label and data poisoning**: an adversary who can influence what a

detector learns — by shaping which items get labelled, or by operating just below a known threshold — degrades the control quietly, and 16.3.3's blind audit is the only routine instrument that would notice. **Authority accumulation:** automation tends to concentrate permissions, because it is easier to give a pipeline broad access than to scope it, and the result is a single identity that can read the ledger, initiate a payment and update the record of what it did.

The control that answers the third is separation of duties, and it should be sized rather than declared.

WORKED EXAMPLE

Worked example 16.4.2 — the dual-approval threshold, derived.

1. **Setup.** The estate makes **4,800** payments a year totalling **USD 68,000,000**. A second approver costs **15 minutes** at **USD 1.60** a minute — **USD 24.00** a payment. **0.20 per cent** of payments are erroneous or fraudulent, and a second approval catches **85 per cent** of those, so **0.17 per cent** of payment value is protected per payment reviewed. **1,150** payments, worth **USD 63,400,000**, exceed the threshold derived below; the remaining **3,650**, worth **USD 4,600,000**, fall under it.
2. **Formula.** Expected loss avoided on one payment = caught rate × payment value. The control pays where that exceeds the approver's cost, so the threshold is $V^* = \text{approver cost} \div \text{caught rate}$. Net value of a policy = caught rate × value reviewed − approver cost × payments reviewed.
3. **Substitution.** $24.00 \div 0.0017$; then the two policies on the value and count above and below.
4. **Result. Threshold $V^* = \text{USD } 14,117.65$** , so dual approval pays on any payment above about **USD 14,118**. **Blanket dual approval on all 4,800 payments** costs **USD 115,200** and avoids **USD 115,600** — a net value of **USD 400 a year**. **Thresholded dual approval on the 1,150 payments above 14,118** costs **USD 27,600** and avoids **USD 107,780** — a net value of **USD 80,180**. The 3,650 small payments cost **USD 87,600** to approve and avoid **USD 7,820**, destroying **USD 79,780**, which reconciles exactly to the difference between the two policies.
5. **Interpretation.** The blanket rule — the rule almost every finance function actually has — is **value-neutral to three significant figures**, and it achieves that by combining a strongly positive control on large payments with a strongly negative one on small ones. That is the general lesson of this domain restated in a third setting: **the value of a control, like the value of a looser alert threshold and the value of a verification step, is a marginal quantity, and averaging destroys the information**. Four practical consequences. **Derive the threshold and put it in the policy**, with its two inputs visible — the approver's cost and the caught rate — because both are arguable and neither is usually written down. **Spend the released capacity on the exposure that has no control:** 87,600 a year of approver time bought 7,820 of protection, and the same money spent on the blind audit of 16.3.3 bought a 18.4471-times return. **Do not read this as an argument against controls on small payments** — a sampling control on the sub-threshold population costs a fraction of blanket approval and preserves deterrence, which the arithmetic above does not model and which matters, because a published threshold is an instruction to an adversary to stay below it. That last point is the professional caution, and it is why the threshold should be reviewed against the observed distribution of attempts, not set once. **And the caught rate is the input to defend:** at 85 per cent the control is strong; a second approver who signs without looking has a caught rate near nil, at which point the whole 115,200 is waste and the arithmetic says so.

16.4.3 Human approval — what it is, and what it costs

Definition. Human approval is a named person taking responsibility for an output before it has an effect. It has three levels that must not be confused. **Review** — a person examines the output and can stop it. **Approval** — a person is accountable for it having proceeded. **Certification** — a person makes a representation to a third party, with the consequences that attach; Domain 14's treatment of draw-request certifications stands, and nothing in an automated pipeline may generate a representation.

Approval architecture is usually discussed as though it were free, and it is not. PML-AI's registered governance-latency formula gives the price directly: the expected wait for a committee decision is $E[\text{wait}] = M/2 + L$, for a meeting interval M and a paper lead time L .

WORKED EXAMPLE

Worked example 16.4.3 — what an approval gate costs while it waits.

1. **Setup.** A change to the automation pipeline of 16.1.2 would deliver the **USD 416,000** a year of saving established there. Two approval designs: a **quarterly AI governance committee** ($M = 60$ days of effective interval between usable decision slots, $L = 10$ days of paper lead time) and a **weekly delegated panel** with a defined mandate ($M = 7$ days, $L = 2$ days).
2. **Formula.** $E[\text{wait}] = M/2 + L$. Value forgone = $E[\text{wait}] \times \text{annual benefit} \div 365$.
3. **Substitution.** $60/2 + 10 = 40$ days; $7/2 + 2 = 5.5$ days; $416,000 \div 365 = 1,139.7260$ a day.
4. **Result.** The committee design forgoes **USD 45,589.04** of value per change; the delegated panel forgoes **USD 6,268.49**. The difference — **USD 39,320.55 per change** — is the price of the governance design, paid whether or not the committee changes the decision.
5. **Interpretation.** The point is emphatically **not** that approval should be removed. It is that **approval must be tiered by consequence, because the tier is where the cost sits**, and an organisation that routes every model change to one quarterly committee is paying roughly 39,000 a change for assurance it does not need on most of them while giving inadequate attention to the few that matter. The design this domain endorses has three tiers derived from the instruments already built. Changes to a model in the **top tier** of 16.3.4's inventory — M1 and M3, where one bad output consumes a covenant headroom — go to the committee, and the 45,589 is well spent because the exposure is 372,438 a year of headroom. Changes to **threshold parameters** go to a delegated panel with a written mandate, because 16.1.3 showed the decision is a cost-ratio judgment that a small standing group can take competently and repeatedly. Changes that alter **what is reported to a lender** go nowhere near either: they are an information-covenant matter (Domain 10, KA 10.4.1) and require the finance director's own decision. Two cautions worth holding. **Latency is not the only cost of a gate** — PML-AI's gate-net-value form prices the defect the gate catches against the delay it imposes, and a gate whose catch rate is nil is pure cost — so measure what the committee actually changes. And **the delegated mandate must be written**, naming which parameters may move, within what bounds, and what triggers escalation, because an undocumented delegation is not a tier, it is an absence of control that will be described as one after an incident.

16.4.4 The AI governance frame

Definition. AI governance in a finance function is the set of arrangements that makes the use of models decidable, reversible and attributable. Stripped of framework language, it answers three

questions for every model: **what is it for, who verifies its output before it has an effect, and who is accountable for the decision it informs.** A programme that cannot answer those three for every entry in its inventory does not have governance, whatever documentation it holds.

Six components carry the weight, and each has been derived rather than asserted in this domain. The **inventory and tiering** of 16.3.4, with intervals that follow from expected loss and a policy floor. The **validation and monitoring** regime of 16.3.2, with monitoring sized to carry the assurance that testing cannot. The **human-approval architecture** of 16.4.3, tiered so that its latency cost is spent where consequence is. The **audit trail**: for every published figure, the model version, the input data version, the attribution (16.3.1), and the named verifier with a date — which is what makes an output defensible a year later, when the person has moved on. **Incident response and rollback**, including the number nobody computes: 16.A.2 prices a quarter's suspension of the estate's pipeline at **USD 141,000**, and a rollback plan without that figure has not been tested. And **disclosure**, which is the component most often forgotten in a financing: where a model materially affects a reported figure or a covenant certificate, whether and how that is disclosed to lenders is an information-covenant question, and a sponsor who is asked about it for the first time during a waiver negotiation has lost the initiative Domain 10 (KA 10.4.4) identified as the most valuable asset in a covenant relationship.

On external frameworks, accurately. Several published frameworks are useful reference points and are named here in the book's own words, with no text reproduced. **ISO/IEC 42001** specifies requirements for an artificial-intelligence management system, in the same management-system idiom as ISO/IEC 27001 for information security, and is therefore the natural home for the inventory, tiering and approval arrangements above. **ISO/IEC 23894** offers guidance on managing risk in artificial-intelligence systems. The **NIST AI Risk Management Framework**, published by the United States National Institute of Standards and Technology, is a voluntary, function-based framework widely used as a structuring device. The **European Union's Artificial Intelligence Act** is a risk-tiered regulatory regime whose obligations depend on how a system is classified and on the role a party plays in relation to it, applying in phases; whether and how it reaches a particular project company is a legal question that depends on facts and jurisdiction, and it is not answered in this book. In addition, banking supervisors in several jurisdictions publish model-risk management expectations for regulated lenders. A project company is not usually within their scope — but **its lenders are**, and the expectation therefore propagates to the borrower through diligence questionnaires and information covenants, which is why a sponsor with a defensible model inventory has a commercial advantage and not merely a tidy file. None of these frameworks is endorsed by the Institute, none is reproduced, and none substitutes for advice on the law applicable to a specific project.

AI in this KA

Where it earns its place. Governance work has real automatable substance: maintaining the inventory from the deployment pipeline so that no model is in production without an entry; monitoring for models in use that are not in the inventory, which is the commonest governance failure and is detectable from access logs; assembling the audit trail automatically at publication time, because an audit trail assembled later is an assertion; tracking approvals against mandates and flagging the ones that exceeded them; and drafting the disclosure language a lender pack needs, for a human to settle.

Where it must not go. No model may approve, certify or disclose. No model may set its own tier, tolerance or mandate. And no model may write the governance framework it will be governed by — a recursion that sounds absurd and is nonetheless the most likely way an organisation ends up with a policy that reads well, cites the right frameworks, and imposes no constraint anyone has costed. The

test to apply to any such document is the one this domain has applied throughout: **which number in it would change a decision?** A governance document with no numbers governs nothing.

Verification, concretely. Reconcile the inventory against production access logs and require the difference to be nil. Sample five published figures and attempt to reproduce each from the recorded model version, data version and attribution alone; a figure that cannot be reproduced from its own trail is not auditable. Test the rollback by running it, and record the cost. Confirm that every approval in the last quarter was within a written mandate, and that the exceptions were escalated. And confirm that the disclosure position on model-derived figures has been stated to lenders in a document, not in a conversation. **AI proposes; the professional verifies, decides and remains accountable.**

■ KEY TERMS — KA 16.4

Term	Meaning
Minimisation	Not loading the sensitive data; the cheapest and strongest confidentiality control.
Breakeven consequence	Cost differential ÷ probability differential; the loss at which a deployment choice flips.
Instruction injection	Ingested content crafted to be read as direction; treat all ingested text as data.
Label poisoning	Influencing what a detector learns; detectable only by blind audit.
Authority accumulation	One automated identity able to read, act and record; the separation-of-duties failure.
Dual-approval threshold	Approver cost ÷ caught rate; the value above which a second approval pays.
Review / approval / certification	Can stop it · accountable for it · represents it to a third party.
Governance latency	$E[\text{wait}] = M/2 + L$; the value forgone while a gate waits.

■ SAMPLE MCQS — KA 16.4

MCQ 16.4-A [16.4.2 · Application] A second approver costs USD 24 a payment; 0.20 % of payments are bad and a second approval catches 85 % of those. The payment value above which dual approval pays is closest to:

- A. USD 12,000
- B. USD 14,118 ✓ CORRECT
- C. USD 120,000
- D. USD 80,000

Rationale: Caught rate $0.0020 \times 0.85 = 0.0017$; $24.00 \div 0.0017 = 14,117.65$. A omits the catch rate and divides by 0.0020. C misplaces a decimal in the bad-payment rate, using 0.02 % rather than 0.20 % ($24.00 \div 0.0002$). D uses the **15 %** a second approval misses instead of the 85 % it catches ($24.00 \div 0.0003$) — the sign-of-the-control error.

MCQ 16.4-B [16.4.2 · Analysis] On the same figures, 4,800 payments a year total 68,000,000, of which 1,150 payments worth 63,400,000 exceed the threshold. Comparing blanket dual approval with thresholded dual approval:

- A. blanket is better, because it catches more bad payments in total

- B. they are equivalent, because the same catch rate applies
- C. thresholded is worth 80,180 a year against blanket's 400, because the 3,650 small payments cost 87,600 to approve and protect only 7,820 ✓ CORRECT
- D. neither is worthwhile, since the blanket policy nets only 400

Rationale: Blanket costs 115,200 and avoids 115,600; thresholded costs 27,600 and avoids 107,780. A is true and irrelevant — the extra catches cost more than they save. B ignores that the value protected varies with payment size while the approver's cost does not. D draws the wrong conclusion from the blanket result: the control is strongly positive where it is targeted.

MCQ 16.4-C [16.4.1 · Analysis] A managed service costs 148,000 a year with an assessed 0.80 % annual breach probability; a private deployment costs 410,000 at 0.15 %. The most defensible use of the arithmetic is:

- A. compute the EMV avoided of 42,250, conclude the managed service wins, and close the question
- B. state the breakeven consequence of 40,307,692 and then debate whether the information at risk is worth that — which segments the answer: operating pipeline managed, live-transaction data private ✓ CORRECT
- C. choose the private deployment, because confidentiality cannot be quantified
- D. choose the managed service, because the probability differential is only 0.65 percentage points

Rationale: The arithmetic's role is to locate the argument, not to end it: $262,000 \div 0.0065 = 40,307,692$, a figure implausible for a routine pipeline and entirely plausible for a live transaction. A over-reads an assessment as a measurement. C abandons a usable structure. D confuses a small differential with a small consequence.

MCQ 16.4-D [16.4.3 · Application] A change worth 416,000 a year waits for a committee with a 60-day effective interval and a 10-day paper lead time. The value forgone while it waits is closest to:

- A. USD 6,268
- B. USD 45,589 ✓ CORRECT
- C. USD 68,384
- D. nil — the benefit accrues once approved

Rationale: $E[\text{wait}] = 60/2 + 10 = 40$ days at $416,000 \div 365 = 1,139.7260$ a day. A is the delegated panel's 5.5-day wait. C prices the full 60-day meeting interval in place of $M/2 + L$, dropping both the expected-half rule and the paper lead time. D ignores that a delayed benefit is a forgone benefit.

MCQ 16.4-E [16.4.2 · Evaluation] The finance director accepts the derived **14,118** threshold — worth **80,180** a year against the blanket rule's **400** — and proposes to remove dual approval from the 3,650 sub-threshold payments altogether and publish the threshold in the payments policy. Assess the proposal.

- A. sound as it stands — the arithmetic is unambiguous and it removes 79,780 of destroyed value
- B. sound in its main move but incomplete: a published threshold is an instruction to an adversary to stay below it, so the sub-threshold population needs a sampling control the arithmetic does not model, and the released 87,600 of approver time is better spent on the blind audit that returned 18.4471 times its cost ✓ CORRECT
- C. unsound — the blanket rule nets a positive 400 a year and should be retained
- D. unsound — the 85 % caught rate is an assessment rather than a measurement, so no threshold derived from it can be relied on

Rationale: The calculation is right and is not a complete policy: it prices detection and is silent on deterrence, which is precisely what publishing a threshold changes (16.4.2). A treats a correct figure as a finished decision. C defends a control that is value-neutral to three significant figures by combining a strongly positive rule on large payments with a strongly negative one on small. D raises the input that most deserves defending — a second approver who signs without looking makes the whole 115,200 waste — but at any plausible caught rate the blanket rule remains the weaker policy, so uncertainty in that input is a reason to test it, not to abandon the derivation.

MCQ 16.4-F [16.4.3 · Evaluation] Shown that the quarterly AI governance committee forgoes **45,589.04** of value per change against the delegated panel's **6,268.49** — a difference of **39,320.55** a change — the head of finance proposes abolishing the committee and routing every model change to the weekly panel. The soundest recommendation is to:

- A. abolish the committee: at 39,320.55 a change its latency destroys more value than its scrutiny creates, and the panel can escalate anything it finds
- B. tier the approvals rather than remove them: changes to the models where one bad output consumes the 372,438 of annual covenant headroom keep the committee, threshold parameters go to the panel under a written mandate, and anything that alters what is reported to a lender is the finance director's own decision ✓ CORRECT
- C. keep the committee for every change: latency is not a cost the finance function pays in cash, and a gate that applies to some changes and not others is no gate at all
- D. route everything to the panel for a year and measure the outcome before deciding, since the committee's catch rate has never been measured

Rationale: The latency cost is real and is an argument for putting the gate where the consequence sits, not for removing it — 45,589.04 is **12.24 %** of the headroom a top-tier model can consume in a year, so it is well spent there and wasted on a threshold change, which 16.1.3 showed to be a cost-ratio judgment a standing panel can take competently (16.4.3). A is the plausible cost-driven overcorrection and mistakes an escalation route for a control: a panel not told which changes are top-tier will not escalate them. C denies a cost that is being paid in forgone benefit. D names the right missing measurement — a gate whose catch rate is nil is pure cost, and what the committee actually changes should be measured — but proposes to obtain it by removing the control from precisely the changes whose consequence justifies it, when the measurement can be made with the tiering in place.

■ SELF-CHECK — KA 16.4

1. How is a dual-approval threshold derived, and what does a blanket rule do? — Approver cost ÷ caught rate: USD 24.00 ÷ 0.0017 = USD 14,118. A blanket rule nets USD 400 a year by combining a strongly positive control above the threshold with an USD 79,780 loss below it.
2. What does the deployment breakeven of USD 40,307,692 tell a director? — That the managed service is defensible for a routine operating pipeline and indefensible for a live-transaction information set, so the answer is to segment the data rather than to choose once.
3. What are the three levels of human involvement, and which may never be automated? — Review (can stop it), approval (accountable for it), certification (represents it to a third party). Certification may never be generated by a model; a pipeline produces a draft for a person to verify and sign.

— Advanced topics — Domain 16

16.A.1 Agentic automation and the authorisation boundary

An **agent** differs from an assistant in one respect that changes every calculation in this domain: it can **act**, not merely propose. The temptation is obvious — the 16.4.2 pipeline already identifies which payments are sound, so allowing it to release them removes the approver's cost entirely. Price that. Removing the thresholded human approval saves **USD 27,600** of approver time and adds **USD 107,780** of expected loss, a net destruction of **USD 80,180** a year, which is precisely the value of the control. Removing approval altogether takes expected loss from **USD 20,400** (0.20 per cent of value, 15 per cent of it uncaught) to **USD 136,000**. The inversion is exact and general: **an agent that replaces a control does not inherit the control's effect, it inherits its absence**, and the saving it books is the control's cost while the loss it creates is the control's benefit.

Three design rules follow, each with an arithmetic basis in this domain. **Scope authority by consequence, using the threshold that already exists**: an agent may release below the 14,118 threshold, where human approval was destroying value anyway, and may only prepare above it. **Keep the recording separate from the acting** — an identity that can both move money and amend the record of having moved it defeats reconstruction, and 16.4.4's audit trail is the control being defeated. And **treat every ingested document as data**: an agent with release authority that reads supplier correspondence has an instruction-injection surface directly onto the payment run, which is the single most consequential new exposure in an automated finance function. The honest summary is that agentic automation is defensible exactly where the human control was uneconomic, and nowhere else — which is a narrower claim than the technology's advocates make and a broader one than its sceptics allow.

16.A.2 The automation you cannot switch off

Every automation case in this domain is a comparison with a manual process, and the comparison assumes the manual process still exists. It does not, after about a year. The **fallback capacity** question is therefore part of the case, and it is a staffing lead-time question rather than a cost question. Restoring manual review over the estate's **56,400** records at **8.5 minutes** each requires **7,990 hours** a year — **4.99375 full-time equivalents** at 1,600 productive hours — and that capability cannot be assembled inside a reporting cycle, whatever the budget.

The number that belongs in the rollback plan is the cost of a **suspension**, because the fixed cost is committed while the manual cost returns. Suspending the pipeline for one quarter means paying the quarter's committed fixed cost of **USD 37,000** and reviewing 14,100 records manually at 19.36 all-in — **USD 272,976** — for a total of **USD 309,976**, against the automated quarter's **USD 168,976**: an incremental **USD 141,000** for one quarter's suspension. Two consequences. **Rollback is a funded option, not a right**, and a plan that does not name its cost has not been tested — the 141,000 should sit in the incident procedure beside the technical steps. And **capability decay should be resisted deliberately**: retaining each pipeline's manual procedure as documented, exercised work — a blind sample reviewed manually every period, which the audit discipline of 16.3.3 already requires and prices — keeps the fallback real at almost no marginal cost. That is the rare control that satisfies two purposes at once, and it is the strongest argument for the audit line surviving its first budget round.

16.A.3 The reviewer's automation eye

Invariants to test on any automation, model or governance claim in a finance function:

- Every automation business case carries an **error-cost line for both processes**, and both error rates are measured rather than assumed; omitting them flatters automation by 20.3822 per cent on 16.1.2's figures.
- The **breakeven volume** is stated, and the case is assessed at the volume the entity actually has — 9,400 records is a 54,000 loss where 56,400 is a 416,000 gain.
- The breakeven is **recomputed at the consequence cost the work actually carries**; a case built at 320 an error does not transfer to work worth 1,200 an error.
- Any threshold is justified by **total misclassification cost**, never by accuracy; and the optimum is confirmed by **marginal** precision against the break-even posterior (false-positive cost ÷ false-negative cost).
- Each threshold row's total cost **reconciles** to the adjacent row plus marginal benefit less marginal cost.
- The **prevalence** underlying any precision or recall figure comes from a **blind audit**, not from the model's own labels; recall against incomplete labels overstates itself (80 per cent claimed, 55.0459 per cent measured).
- Scenario statements carry **k** and the **share** breaching, and no generated minimum is presented as a defined case.
- Extraction reliance is assessed on **aⁿ for the load-bearing subset**, and that subset is chosen **before** the tool runs, verified against the **executed** document, with the version identifier recorded.
- Every published figure has a **local additive attribution** that reconciles to it, with a nil or explained residual, in currency.
- Every validation claim states its **confidence and bound**, and the sample size reconciles to $\ln(\alpha) \div \ln(1 - p)$; the suite's **independence** is evidenced; and the claim is translated into **expected annual production errors**.
- Every model in production has an **inventory entry**, a tier derived from $\text{uses} \times p \times \text{consequence}$, a revalidation interval capped by policy, and a named owner — and the inventory reconciles to production access logs.
- Every approval sits within a **written mandate**; certifications are never machine-generated; and the **latency cost** of the gate is known.
- The **rollback cost** is computed and the rollback has been exercised.

— Industry variations — Domain 16

- **Water and regulated utilities.** Telemetry is dense and consumption data is regulated, so the data spine's value is high and the deployment question of 16.4.1 is constrained by licence conditions on data location rather than by the arithmetic. Regulatory reset cycles break the training period, so the training-period bias of 16.3.3 is structural: a consumption model calibrated across a reset is calibrated on two different worlds.
- **Contracted power and availability payments.** Revenue is formulaic, so forecast automation is the easiest win in the estate and the anomaly detector's prevalence is low — which raises the false-positive burden at any recall, because a low base rate means most alerts are false however

good the model. Threshold economics dominate, and the 16.1.3 arithmetic is the whole discussion.

- **Transport concessions.** Patronage data is high-volume, granular and genuinely non-stationary, so 56,400-record-scale automation pays easily while forecast automation is the hardest case in the book: the model that fitted last year's ramp is the model that will mislead through the next disruption, and validation must be on out-of-period data or it proves nothing.
- **Digital infrastructure.** Contract terms are numerous, bespoke and frequently amended, which makes document review the highest-value application and the superseded-draft failure of 16.2.2 the highest-probability one — Case study B is drawn from this sector for that reason. Tenant data is commercially sensitive third-party data, so minimisation is a contractual obligation, not a preference.
- **Mining and resources.** Price-deck scenario generation is central and the sign-change appraisal pathologies of Domain 4 make generated-scenario reporting especially treacherous; a generated minimum across a commodity path distribution is a statement about the tail of an assumed price process, and should be labelled as such.
- **Public-sector and development-finance-supported projects.** Explainability is not optional: a figure that affects a public payment must be reconstructable by an auditor from its own trail, so 16.3.1's additive attribution and 16.4.4's audit trail move from good practice to condition of funding, and models that cannot support them are simply unusable however accurate.

— Case study — Domain 16: the automation that lost at one asset and won at six (water)

Situation. Kestrel Water's sponsor group approved an automation platform for its consumption-and-billing review on a business case built at the Kestrel project, where the finance team had the appetite and the data. The case compared **USD 13.60** a record of manual review with **USD 1.04** a record of automated processing and a committed **USD 148,000** a year, and showed a saving. It carried no error-cost line for either process.

What happened. Three things, in sequence, each worth a number.

The volume error. At Kestrel's **9,400** records a year the platform cost **USD 235,984** against the manual process's **USD 181,984** — **USD 54,000 a year more**, not less. Restated properly, with the manual undetected-error rate measured at **1.80 per cent** and the automated at **2.60 per cent** against a consequence of **USD 320**, the all-in costs are **19.36** and **9.36** a record and the breakeven is **14,800 records a year**. The original case, omitting error costs, had implied a breakeven of **11,783 — 20.3822 per cent** flattering — and even that was above Kestrel's volume. The programme was rescoped to the six-asset estate's **56,400** records, where it saves **USD 416,000 a year**. The rescoping was the right answer arrived at for the wrong reason: nobody had computed a breakeven at all.

The threshold error. The payment-and-journal detector deployed alongside it was tuned, on the vendor's recommendation, to maximise accuracy: **98.5729 per cent** at threshold T2, with **925** alerts a year and a total misclassification cost of **USD 161,800**. Recomputed on the estate's own costs — **USD 40** to investigate a false positive, **USD 320** for a missed error — the cost-minimising threshold is **T4**, at **USD 114,800**, with **1,910** alerts and precision of only **50.2618 per cent**. Moving the threshold saved **USD 47,000 a year** and was resisted for two quarters by the team working the queue, whose objection — that half the alerts were now false — was factually correct and economically irrelevant, since the break-even posterior is $40 \div 320 = 12.5$ per cent.

The label-bias discovery. In the second year the finance director commissioned a **blind audit** of the items the detector had not flagged: **1,000** of **46,090**, reviewed independently of the labelling team at 8.5 minutes an item, a cost of **USD 13,600**. It found **17** genuine errors — a **1.70 per cent** rate, extrapolating to **784** missed errors a year against the **240** the detector's own arithmetic assumed. The true anomaly population was therefore about **1,744**, not 1,200 — **45.3333 per cent** higher — the detector's true recall was **55.0459 per cent**, not 80, and the restated total cost at T4 was **USD 288,880**, a factor of **2.5164** on the reported figure. The false-negative cost had been understated by **USD 174,080** a year.

How it resolved. The estate adopted four changes, each traceable to one of the numbers above. The business case is now restated annually on measured error rates rather than assumed ones. The threshold is a delegated-panel decision within a written mandate, reviewed when either cost input moves, rather than a vendor default. The blind audit became a permanent annual line, sized at **1,000** records (above the **937** a ± 1 -percentage-point bound at 95 per cent confidence requires), which returned **18.4471 times** its cost in its first year; the same discipline was extended as a periodic manual sample across the billing pipeline, which is how the fallback capacity of 16.A.2 is kept exercised. And the detector was **retrained** rather than retuned, using the audit's confirmed findings as a new label source, because scaling the T4-to-T5 marginal benefit by the 1.4533 population factor gives **USD 55,808** against an unchanged **USD 78,000** of investigation cost — no threshold reaches errors the labels never contained.

What the domain teaches here. Three failures, one cause. The volume error, the threshold error and the label bias were all failures to compute something computable, and each was defended with a qualitative argument — the platform is strategic, accuracy is the standard metric, the model reports 80 per cent recall. **Every one of those arguments dissolved on contact with arithmetic that took under an hour.** The programme's total annual improvement from arithmetic alone, before any technology changed, was **USD 470,000** of rescoping and **USD 47,000** of retuning, against a restated loss estimate that was **USD 174,080** worse than believed — and the honesty of the third number is what made the first two credible to the board.

— Case study B — Domain 16: the definition read from the wrong draft (digital infrastructure)

Situation. A hyperscale data-centre financing carried **USD 130,000,000** of senior debt with annual debt service of **USD 17,000,000**, a **1.25×** DSCR covenant and a **1.20×** distribution lock-up. The borrower's finance team used a document-extraction tool to build its covenant register from the facility agreement's **340** defined terms, and reported the first annual compliance certificate on that register.

What happened. The register's **CFADS** definition had been extracted from a **late negotiation draft** rather than the executed agreement. In the executed version, **capitalised maintenance** was struck **above CFADS**; in the draft it sat below. The reported **CFADS** was **USD 22,780,000** and the reported **DSCR 1.3400** — comfortably inside covenant. On the executed definition, **CFADS** was **USD 20,230,000**, a difference of **USD 2,550,000**, and the **DSCR** was **1.1900**.

The consequences followed mechanically. The **1.25×** covenant required **CFADS** of **USD 21,250,000**, so the project was short by **USD 1,020,000** and in breach from the first test date. The **1.20×** lock-up trigger of **USD 20,400,000** was also crossed, by **USD 170,000**, so distributions were trapped — and the sponsor had already declared a dividend against the 1.3400 figure. The tool's per-item accuracy was never the issue: the extraction was faithful to the document it was given, which is the failure mode no accuracy statistic can detect, and the combinatorial arithmetic of 16.2.2 had already

said what to expect — at 92 per cent per-item accuracy the probability that all **26** load-bearing definitions were right was **0.114415**.

How it resolved. The sponsors injected an equity cure of **USD 1,020,000** to restore the covenant, and paid a waiver fee of **25 basis points** on the outstanding **USD 130,000,000 — USD 325,000** — for the historic breach and the mis-stated certificate. Total direct cost **USD 1,345,000**, before the declared dividend was reversed and before the lenders moved the facility to monthly reporting for a year. The verification that would have prevented it — **26** load-bearing definitions at half an hour each of a legal-and-finance specialist at **USD 240.00** an hour — costs **USD 3,120**. The direct cost was **431.0897 times** the verification.

What the domain teaches here. The extraction was accurate, the arithmetic was correct, and the certificate was false. **The only control that would have caught it operates on the executed document and records the version identifier**, and it is the control 16.3.4's tiering rule independently demands: with four uses a year, an 88.5585 per cent chance of at least one wrong load-bearing term and a 600,000 consequence, the model's annual **EMV** is **USD 2,125,404** and its revalidation interval is **8.59 days** — shorter than the interval between its uses, which is the formula's way of saying verify every time. Two derivations, from combinatorics and from expected loss, converge on the same instruction, and the borrower had implemented neither.

— Executive perspective — Domain 16

What a project finance director cannot delegate in this domain:

- **The error-cost line in every automation case.** Not the labour saving — the two error rates and the consequence per error. Their omission flattered Case study A's breakeven by 20.3822 per cent and hid a 54,000 annual loss at the asset that sponsored the programme.
- **The threshold, because it encodes what a missed error costs us.** The number is a cost-ratio judgment with an owner, not a model setting: 12.5 per cent break-even posterior, T4 not T2, 47,000 a year.
- **The blind audit, and its permanence.** It is the only instrument that measures what the model cannot see, and it is the first line cut in a budget round. It restated a claimed 114,800 loss to 288,880 and returned 18.4471 times its cost.
- **The verification scope on load-bearing items.** Twenty-six definitions, named verifier, recorded date, executed document, version identifier — USD 3,120 against the 431.0897 multiple Case study B paid.
- **The approval architecture and its price.** 45,589 a change through a quarterly committee against 6,268 through a mandated panel: tier it by consequence, write the mandate, and keep certification and lender disclosure to the director's own hand.
- **The rollback, funded and exercised.** USD 141,000 for a quarter's suspension and 4.99375 full-time equivalents to restore manual capacity — figures that must exist before an incident, not after.

— Calculation exercises — Domain 16

Exercise 16.1 Manual review takes 7 minutes a record at a loaded USD 96.00 an hour and leaves 2.20 per cent of records with an undetected error. An automated pipeline costs USD 0.95 a record in processing and leaves 3.50 per cent undetected, on a committed fixed cost of USD 96,000 a

year. An undetected error costs USD 500. Find the breakeven volume. Solution. Manual $7 \times 1.60 = 11.20$ plus $0.022 \times 500 = 11.00$, total **USD 22.20**. Automated 0.95 plus $0.035 \times 500 = 17.50$, total **USD 18.45**. Advantage **USD 3.75**; breakeven $96,000 \div 3.75 = 25,600$ records a year. Common error: omitting the error-cost terms, which gives an advantage of $11.20 - 0.95 = 10.25$ and an apparent breakeven of 9,366 records — 63.4 per cent too low, and the specific defect of 16.1.2.

Exercise 16.2 A detector screens 30,000 items a year of which 900 are genuinely erroneous. A false positive costs USD 60 to investigate; a missed error costs USD 900. Three thresholds give: A — 450 true positives, 90 false; B — 675 true positives, 300 false; C — 855 true positives, 1,500 false. Compute accuracy and total cost at each, choose the threshold, and confirm the choice marginally. Solution. Accuracy: A $(450 + 29,010)/30,000 = 98.2000\%$; B $(675 + 28,800)/30,000 = 98.2500\%$; C $(855 + 27,600)/30,000 = 94.8500\%$. Total cost: A $90 \times 60 + 450 \times 900 = 410,400$; B $300 \times 60 + 225 \times 900 = 220,500$; C $1,500 \times 60 + 45 \times 900 = 130,500$. **Choose C** — accuracy is maximised at B, and choosing B would cost **USD 90,000 a year**. Marginal confirmation: B to C adds 180 true and 1,200 false positives, marginal precision $180/1,380 = 13.0435\%$, above the break-even posterior $60 \div 900 = 6.6667\%$ (one in 15); benefit $180 \times 900 = 162,000$ against cost $1,200 \times 60 = 72,000$, net **+90,000**, which reconciles exactly to the fall in total cost. Common error: selecting B on accuracy — the 90,000 mistake this domain exists to prevent.

Exercise 16.3 How many independent, representative test cases, all passing, are needed to be 95 per cent confident that a model's defect rate is below 2 per cent? And at 99 per cent confidence? Solution. $n \geq \ln(\alpha) \div \ln(1 - p)$. At 95 per cent: $\ln(0.05) \div \ln(0.98) = 148.2837$, so **149** cases. At 99 per cent: $\ln(0.01) \div \ln(0.98) = 227.9482$, so **228**. Common error: using $1/p = 50$ or $100/p$ -style reasoning; a defect rate bound of 2 per cent needs roughly $3/p$ cases at 95 per cent confidence, not $1/p$, and the difference between 50 and 149 is the difference between a claim and evidence.

Exercise 16.4 An extraction tool is 95 per cent accurate per item. Eighteen extracted terms are load-bearing. What is the probability the deliverable is entirely correct, and what per-item accuracy would a 99 per cent clean sweep require? Solution. $0.95^{18} = 0.397214$, so a **39.7214 per cent** chance all eighteen are right and a **60.2786 per cent** chance at least one is wrong. For a 99 per cent sweep, $a \geq 0.99^{(1/18)} = 99.9442$ per cent per item. Common error: reporting the tool's 95 per cent as the reliability of the register — the mistake that produced Case study B's false certificate.

Exercise 16.5 An estate makes 3,600 payments a year totalling USD 52,000,000. A second approver costs 12.5 minutes at USD 96.00 an hour. 0.25 per cent of payments are bad and a second approval catches 80 per cent of them. Derive the dual-approval threshold, then value blanket against thresholded approval given that 820 payments worth USD 48,900,000 exceed the threshold. Solution. Approver cost $12.5 \times 1.60 = \text{USD } 20.00$; caught rate $0.0025 \times 0.80 = 0.0020$; threshold $20.00 \div 0.0020 = \text{USD } 10,000$. Blanket: cost $3,600 \times 20 = 72,000$, avoided $0.0020 \times 52,000,000 = 104,000$, net **+32,000**. Thresholded: cost $820 \times 20 = 16,400$, avoided $0.0020 \times 48,900,000 = 97,800$, net **+81,400**. The 2,780 sub-threshold payments cost **55,600** and avoid **6,200**, destroying **49,400** — exactly the difference between the two policies. Common error: concluding from the blanket policy's positive 32,000 that the policy is sound; the control is strongly positive above the threshold and strongly negative below it, and only the marginal view shows it.

— Practitioner's toolkit — Domain 16

Adoption-ready artefacts; adapt headings to your organisation, then keep them stable.

Toolkit 16.T.1 — The automation business case, on one page

Mandatory lines, in this order, with no line permitted to be blank: the task and the **volume** the deciding entity actually has (asset, estate, group); **manual cost per item** = minutes × loaded rate, with the rate stated; **measured manual undetected-error rate** and its source; **consequence per undetected error** and its derivation; **manual all-in cost per item**; **automated committed fixed cost** a year; **automated processing cost per item**, including the referral rate and adjudication time; **measured or assumed automated undetected-error rate**, flagged as which; **automated all-in cost per item**; **advantage per item**; **breakeven volume**; **net annual value at the actual volume**; the **automated error rate** and the **consequence cost** at which the case reverses; the **rollback cost** for one period's suspension; and the **fallback capacity** in full-time equivalents and lead time. Rule: a case with no error-cost line is returned unread.

Toolkit 16.T.2 — Threshold and alert-queue sheet (per detector, per review)

Per candidate threshold: score cut · **TP** · **FP** · **FN** · **TN** · recall · precision · accuracy · alert count · adjudication hours · **total misclassification cost**. Above the table: the false-positive cost and the false-negative cost, each with its owner and derivation, and the derived **break-even posterior**. Below it: the **marginal** true positives, false positives, precision, benefit, cost and net for each step, with the arithmetic check that each row's net reconciles to the change in total cost. Footer lines: the operating threshold and who approved it; the date of the last **blind audit** of unflagged items, its sample size, findings, extrapolated missed errors and restated cost; and the prevalence in use, marked labelled or audited.

Toolkit 16.T.3 — Model inventory, tier and approval record

One row per model in production, reconciled quarterly to production access logs — an unreconciled inventory is the governance failure this artefact exists to prevent. Columns: model and version · purpose · owner · inputs and their golden sources · outputs and the decisions they touch · whether any output reaches a lender or a certificate · **uses a year** · **defect probability** p , marked measured / estimated / inherited · **consequence per defect** and its derivation · **annual EMV** · **revalidation interval** = tolerance ÷ **EMV**, with the policy cap applied · date last validated, sample size, confidence and bound · monitoring in place and the drift trigger · **approval tier and written mandate reference** · attribution method and the last reconciliation residual · rollback procedure, its cost, and the date it was last exercised · named verifier for the current period. Header: the tolerance parameter and its owner.

— Exam preparation — Domain 16

What is assessed. All-in cost per reviewed item for a manual and an automated process, and the breakeven volume; the effect on the breakeven of the consequence per error and of each process's error rate; the volume, error-rate and consequence breakevens as sensitivities; a classifier's recall, precision, accuracy and total misclassification cost across thresholds, the cost-minimising threshold, the annual cost of choosing the accuracy-maximising one, the break-even posterior, and the marginal-precision test; scenario coverage $1 - (1 - p)^k$ and the required k for a stated confidence; the sweep probability a^m and the per-item accuracy a stated sweep confidence demands; the real against the

apparent saving from machine-assisted model building, and the expected cost of an omitted review; attributional completeness and the residual as a share of covenant headroom; zero-failure validation sample size, the one-failure adjustment, and the translation of a validated bound into expected annual production errors; label bias, the extrapolation from a blind audit, the restated recall and cost, and the audit sample size for a stated bound; model tiering by annual EMV and the derived revalidation interval; the deployment breakeven consequence; the dual-approval threshold and the value of blanket against thresholded application; and governance latency $E[\text{wait}] = M/2 + L$ priced against a daily benefit.

The calculations to do under time pressure. $\text{minutes} \times \text{rate} + \text{rate of error} \times \text{consequence}$ for each process, then $\text{fixed} \div \text{advantage}$. The consequence and error-rate breakevens by rearranging the same equation. $FP \times \text{cost} + FN \times \text{cost}$ down a threshold column, then the marginal step: $\Delta TP \times FN \text{ cost} - \Delta FP \times FP \text{ cost}$, and $FP \text{ cost} \div FN \text{ cost}$ for the posterior. $\ln(\alpha) \div \ln(1 - p)$ for both scenario coverage and validation sample size — the same formula twice, which is worth noticing. a^m and $c^{(1/m)}$. $\text{uses} \times p \times \text{consequence}$, then $\text{tolerance} \div \text{EMV}$. $\text{approver cost} \div \text{caught rate}$, then cost and avoided loss on each population. $M/2 + L$, times $\text{annual benefit} \div 365$.

The traps. Omitting the error-cost term from an automation case (Exercise 16.1, MCQ 16.1-A, Case study A) · assuming the automated error rate equals or beats the manual one when the case depends on it (16.1.2) · appraising an automation at the estate's volume when the deciding entity is one asset, or the reverse (16.1.2, Case study A) · assuming a higher consequence per error strengthens the automation case when it weakens it (MCQ 16.1-B) · selecting a threshold on accuracy (Exercise 16.2, MCQ 16.1-C, Case study A) · testing a threshold step on average rather than marginal precision (MCQ 16.1-D) · quoting recall or precision computed against incomplete labels (16.3.3, MCQ 16.3-C, Case study A) · attempting to fix label bias by moving the threshold (16.3.3) · drawing an audit sample from flagged items or having it reviewed by the labelling team (16.3.3) · reporting a scenario count without k , or a generated minimum as a bank case (16.2.1, MCQ 16.2-C) · reading per-item extraction accuracy as deliverable accuracy (Exercise 16.4, MCQ 16.2-A, Case study B) · extracting from a data-room draft rather than the executed document (16.2.2, Case study B) · letting the tool's confidence scores choose the verification scope (MCQ 16.2-B) · booking the apparent saving from assisted model building while leaving the review at its hand-built hours (16.2.3, MCQ 16.2-D) · treating a validation bound as a production guarantee (MCQ 16.3-B) · repairing a failing test case instead of enlarging the suite from 299 to 473 (16.3.2) · tiering models by transaction volume rather than by expected loss (MCQ 16.3-D, 16.3.4) · omitting the policy cap on a computed revalidation interval (16.3.4) · presenting a deployment EMV as a decision rather than its breakeven consequence as a question (MCQ 16.4-C) · deriving a dual-approval threshold without the catch rate (MCQ 16.4-A) · concluding that a blanket control is sound because its net is positive (Exercise 16.5, MCQ 16.4-B) · pricing an approval gate at zero (MCQ 16.4-D) · and assuming an agent inherits the effect of the control it replaces rather than its absence (16.A.1).

How the domain connects. Domain 2 supplied the definitional exposure — 600,000 of CFADS on one working-capital treatment — that makes the definitional layer of 16.1.1 and the verification scope of 16.2.2 worth their cost. Domain 6 built the model, its six invariants and the effective-rate check that 16.2.3's review must run, and supplied the 3,250,352 defect consequence that prices it. Domain 10 supplied CFADS, the debt service, the $1.20\times$ covenant and the 372,438 of annual headroom that every data-quality figure in this domain is measured against, and the information covenants that make model disclosure a contractual matter. Domain 11 established model risk as a priced register line whose probability is a function of governance, which is the claim 16.3.4 turns into a calendar. Domain 13's model audit is the external counterpart of 16.3.2's validation, and Domain 14 established that no pipeline may generate a representation. PML-AI supplied three registered forms used unchanged: the mesh-versus-layer interface count, EMV, and governance latency. Backwards, this domain gives every earlier AI in this KA section its arithmetic; forwards, it is the last domain, and

what it hands on is not another technique but a standard of proof — that a claim about automation, like a claim about coverage, is worth exactly what its arithmetic can carry.

— Domain 16 summary

Responsible AI in finance is a quantitative discipline, and its four central results all contradict a common belief. **Automation is decided by error costs, not labour.** Manual review of the estate's consumption-and-billing records costs **USD 13.60** a record plus **1.80 per cent** of undetected errors at **USD 320 — USD 19.36** all-in — against the pipeline's **USD 1.04** plus **2.60 per cent**, or **USD 9.36**, so on a committed **USD 148,000** the breakeven is **14,800 records a year**: a **USD 54,000** annual loss at Kestrel's 9,400 and a **USD 416,000** annual gain across the estate's 56,400. Omitting the error terms moves the apparent breakeven to **11,783** and flatters automation by **20.3822 per cent**; repricing an undetected error at **USD 1,200** moves the real breakeven to **50,000** and leaves the whole programme worth **USD 18,944** — so the more consequential the work, the more volume automation needs, and the rule is to automate high-volume, low-consequence work rather than important work. **Accuracy is the wrong objective for a detector.** Over 48,000 payments and journals at a 2.5 per cent anomaly rate, with a false positive costing **USD 40** and a missed error **USD 320**, cost is minimised at **USD 114,800** (threshold T4, 80 per cent recall, precision only **50.2618 per cent**) while accuracy peaks at **98.5729 per cent** two thresholds away, where cost is **USD 161,800** — a **USD 47,000** annual price for a metric choice. The rule is a **12.5 per cent** break-even posterior, one in eight, tested on marginal precision: **17.9104 per cent** from T3 to T4 earns 16,400 and **5.7971 per cent** from T4 to T5 loses 39,600. **Validation proves less than it appears.** 299 passing independent cases bound a defect rate below 1 per cent at 95 per cent confidence — and at 56,400 uses a year that still admits **564** errors; bounding expected errors at ten would need **16,895** cases, and one observed failure raises the 299 to **473** — which is why monitoring, tiered human approval and a funded rollback carry the assurance, not testing. **And controls, thresholds and verification are marginal quantities.** Blanket dual approval nets **USD 400** a year; the same control above a derived **USD 14,118** threshold nets **USD 80,180**, because 3,650 small payments cost 87,600 to approve and protect 7,820. Around those four results sit the domain's other derivations: a data spine costing **USD 900,000** returns an NPV of **+USD 1,221,674** on hours while its real value is the single implementation of **CFADS** whose divergence is worth **1.6110** times Kestrel's annual covenant headroom of **372,438**; a 92 per cent-accurate extractor gets all **26** load-bearing definitions right **11.4415 per cent** of the time, so a 95 per cent sweep would demand **99.8029 per cent** per item and the answer is **USD 3,120** of human verification instead — the control Case study B omitted at a cost of **USD 1,345,000**, or **431.0897** times; machine-assisted model building saves a real **33.3333 per cent**, not the apparent 70.8333, and the omitted 18 hours of review are **USD 2,700** against **USD 1,137,623.20** of expected defect cost; a blind audit of **1,000** unflagged items restated the detector's recall from 80 to **55.0459 per cent** and its cost from 114,800 to **USD 288,880**, returning **18.4471** times its cost; a model inventory tiered on **uses × p × consequence** gives the defined-term extractor an annual **EMV** of **USD 2,125,404** and an **8.59-day** interval that independently reproduces "verify every use"; a deployment choice turns on a breakeven consequence of **USD 40,307,692** rather than on an **EMV**; and an approval gate costs **USD 45,589.04** a change through a quarterly committee against **USD 6,268.49** through a mandated panel. Every one of those verification steps returns between eighteen and four hundred and thirty times its cost, which is the domain's real finding and the one that survives every disagreement about the technology: **AI proposes; the professional verifies, decides and remains accountable — and the verification is the cheapest line in the budget.**

— Appendix A — Formula and symbol sheet

30 symbols, of which **30 carry a verified worked example** in this volume or its companion. A symbol marked pending is registered and used but does not yet have a golden-answer check behind a printed result — treat its appearances with the same care you would any unchecked number. Units are stated because a unit error is the commonest arithmetic failure in practice and the hardest to see in a finished sentence.

SYMBOL	MEANING	UNIT	FIRST HOME	VERIFIED
PV (BCWS)	Planned Value (EVM context)	currency	inherited (PCL-AI master table)	yes
EV (BCWP)	Earned Value	currency	inherited (PCL-AI master table)	yes
AC (ACWP)	Actual Cost	currency	inherited (PCL-AI master table)	yes
BAC / EAC / ETC / VAC	Budget / Estimate at Completion, Estimate to Complete, Variance at Completion	currency	inherited (PCL-AI master table)	yes
$CV = EV - AC$ $SV = EV - PV$	Cost / Schedule Variance	currency	inherited (PCL-AI master table)	yes
$CPI = EV/AC$ $SPI = EV/PV$	Performance indices	ratio	inherited (PCL-AI master table)	yes
TCPI	To-Complete Performance Index	ratio	inherited (PCL-AI master table)	yes
PoC	Percentage of completion	%	inherited (PCL-AI master table)	yes
r, n	Discount rate per period; number of periods	ratio; count	inherited (PCL-AI master table)	yes
PV(x)	Present value of amount x	currency	inherited (PCL-AI master table)	yes
FV(x)	Future value of amount x	currency	PFL-AI D3	yes
NPV	Net present value = $\sum CF_t/(1+r)^t - I_0$	currency	PFL-AI D4	yes
IRR / MIRR	Internal / modified internal rate of return	%/period	PFL-AI D4	yes
PI	Profitability index = $PV(\text{future CF})/I_0$	ratio	PFL-AI D4	yes
EAV	Equivalent annual value	currency/ period	PFL-AI D4	yes
WACC	Weighted average cost of capital = $g \cdot k_d(1-T) + (1-g) \cdot k_e$ — derived in PFL-AI D9, which discharges D4's use of 8 % as a given; note it is linear in gearing only while k_e is held fixed	%/period	PFL-AI D4/D9	yes
CFADS	Cash flow available for debt service (a defined term — see PFL-AI D2 KA 2.3.1: whether it is struck before or after working-capital movements changes every ratio built on it)	currency/ period	PFL-AI D2/ D10	yes
DSCR	Debt service coverage ratio = $CFADS/(\text{interest} + \text{scheduled principal})$ per period	ratio	PFL-AI D10	yes
LLCR	Loan life coverage ratio = $PV(\text{CFADS over loan life, at loan rate})/\text{outstanding debt}$	ratio	PFL-AI D10	yes

SYMBOL	MEANING	UNIT	FIRST HOME	VERIFIED
PLCR	Project life coverage ratio = $PV(CFADS \text{ over project life}) / \text{outstanding debt}$	ratio	PFL-AI D10	yes
ICR	Interest coverage ratio = $EBIT \text{ (or EBITDA)} / \text{interest}$ — accounting-based; ignores principal	ratio	PFL-AI D2/ D10	yes
Max debt service	$CFADS \div \text{target } DSCR \text{ per period}$	currency/ period	PFL-AI D10	yes
Max debt capacity	$\text{max debt service} \times AF(r, n)$ at the loan rate and tenor	currency	PFL-AI D10	yes
Sculpted debt service	$CFADS(t) \div \text{target } DSCR$ — coverage constant by construction	currency/ period	PFL-AI D10	yes
Covenant / lock-up trigger in cash	$\text{debt service} \times \text{threshold ratio}$ (the number that belongs on a dashboard)	currency/ period	PFL-AI D10	yes
DSRA	$\text{debt service} \times \text{months}/12$ (funded reserve; expressed as the shortfall it survives)	currency	PFL-AI D10	yes
D/E	Gearing (debt : equity)	ratio	PFL-AI D9/ D10	yes
i_{nom}, i_{real}, π	Nominal rate, real rate, inflation (Fisher: $1+i_{nom} = (1+i_{real})(1+\pi)$)	%/period	PFL-AI D3	yes
$DF(t)$	Discount factor at period $t = 1/(1+r)^t$	ratio	PFL-AI D3	yes
A	Annuity payment (context-flagged; PCL-AI uses A = Assets in accounting chapters — write "annuity payment A" at first use)	currency/ period	PFL-AI D3	yes

Conventions that apply to every formula above. Financial arithmetic is decimal, never binary floating point. Intermediate values carry full precision; rounding happens only at display, which is why a printed figure may not reproduce if you round as you go. Rates and periods must agree — an annual rate against monthly periods is the error the golden suite catches most often. Datetimes are YYYY-MM-DD HH:MM:SS in UTC and are compared as instants, never lexically.

— Appendix B — Notation, terminology and conventions

Terms fixed at programme level, which the chapters use without redefining:

TERM	AS USED IN BOTH VOLUMES
PML-AI	PCI Project Management Leader – AI: the certification; its BoK is this programme's Book One
PFL-AI	PCI AI Project Finance Leader: the certification; its BoK is Book Two
Responsible AI principle	"AI proposes; the professional verifies, decides and remains accountable" — the suite-wide principle; it supersedes the retired formulation "AI proposes, the professional disposes" used in the first PCL-AI printing under its former PCP-AI designation
Domain / Knowledge Area / Topic	The three-level content hierarchy D.K.T , identical to PCL-AI
Sponsor	The accountable executive owner of the business case (PML-AI); in PFL-AI project-finance contexts, an equity investor promoting the project — the books flag the context at each use
Special-purpose vehicle (SPV)	The ring-fenced legal entity created to own, finance and operate a project
Bankability	The degree to which a project's contracts, risks and cash flows support limited-recourse financing on acceptable terms
CFADS	Cash flow available for debt service, as defined in the formula registry
Cash waterfall	The contractually agreed priority order in which project cash is applied each period
Benefits realisation	The identification, planning, measurement and sustainment of the outcomes a programme exists to deliver
Decision rights	The explicit allocation of which role may take which decision at which threshold
Psychological safety	A shared belief that the team is safe for interpersonal risk-taking — candour without penalty
Hybrid delivery	A deliberate combination of predictive and adaptive methods under one governance frame
Model risk	The risk of loss from decisions based on flawed, misused or misunderstood models (financial or AI)

Conventions

The hierarchy. Content is addressed as [D.K.T](#) — Domain, Knowledge Area, Topic. A cross-reference of the form KA 7.3 or 10.2.2 is precise and is the authority; a page number is not used, because the corpus is regenerated.

Context flags. Where one word carries two genuinely different concepts, the later use states the collision explicitly rather than relying on the reader to infer it — tailoring of method against tailoring of a message, [PV](#) as present value against [PV](#) as planned value, [A](#) as annuity payment against [A](#) as assets. A flag is a signal that both meanings are live in the corpus, not a warning that one is wrong.

Citation over restatement. A result established in one domain is cited from the others rather than re-derived. If two domains appear to derive the same thing, that is a defect and worth reporting.

Currency and units. USD throughout, with SAR shown where it aids a Gulf reader at an indicative [USD 1 ≈ SAR 3.75](#). That rate is illustrative and is not a forecast or a quotation. Every worked example states its units, its currency, its rounding and its date basis; where one is missing, treat it as a drafting defect.

Fictitious entities. Every organisation, project, person and case in this volume is invented. Any resemblance to a real entity is coincidental, and no real project's data is used.

The responsible-AI principle, which governs every AI in this KA section: AI proposes; the professional verifies, decides and remains accountable.

— Appendix C — Verification record

7,935 golden-answer checks stand behind this volume. Every number printed as a result — in worked examples, in-text calculations, multiple-choice options (all of them, not only the correct one), exercise solutions, case studies and figure specifications — is recomputed independently with decimal arithmetic at 28-digit precision and compared to the printed value. Each domain's module also pins the invariants the domain claims: an identity, a breakeven, a bound, an inequality, so that a claim cannot silently stop being true.

DOMAIN		CHECKS
0	Cross-domain check modules (span several domains)	905
1	Foundations of Project Finance Leadership	306
2	Accounting and Financial-Statement Foundations	538
3	Time Value of Money and Financial Mathematics	526
4	Investment Appraisal and Capital Budgeting	475
5	Project Development and Bankability	428
6	Financial Modelling and Model Governance	490
7	Revenue, Demand and Commercial Models	378
8	Cost, Schedule and Contingency Integration	520
9	Funding Structure and Sources of Capital	397
10	Debt Sizing, Covenants and Credit Metrics	449
11	Risk Identification and Allocation	460
12	Contracts and Transaction Structure	294
13	Due Diligence and Financial Close	274
14	Construction Monitoring and Drawdown	356
15	Operations, Performance and Restructuring	379
16	Data, Automation and Responsible AI in Finance	554
17	Appendix G — integrated capstones	206
Total		7,935

The Institute's verification suite recomputes this record in full on demand, and can recompute a single domain of it as readily as the whole volume. The suite is fail-closed: a check that cannot be evaluated is recorded as a failure, never passed over as a skip.

What this record does and does not establish. It establishes that the arithmetic is right — that each number is the one its stated method produces from its stated inputs. It does **not** establish that the method chosen was the right method for the situation, that the professional judgements are ones an experienced practitioner would endorse, that the emphasis across topics is well calibrated, or that nothing important is missing. Those are questions for editorial and technical review, and a reader should not read a large number in this appendix as an answer to them.

— Appendix D — Figure index

45 figures, all of them drawn as PCI-original artwork generated from source specifications maintained by the Institute. Each is also specified in words in the chapter, stating every plotted value, so that a figure can be read — and redrawn — without the artwork, and so that a reader using assistive technology loses nothing. No figure in either volume reproduces a diagram from another publisher, and every annotated value in a drawn figure is a literal verified by the golden-answer suite.

FIGURE	SUBJECT	ARTWORK
1.1.1	The recourse spectrum	drawn
1.1.2	The SPV at the centre of its contracts	drawn
1.1.3	The recourse decision against facility size	drawn
1.2.1	The bankability triangle	drawn
1.2.2	Where leverage helps, and where the cliff is	drawn
2.2.1	Kestrel's accrual-to-cash bridge	drawn
2.3.1	The covenant as a collection period	drawn
2.4.1	Kestrel's return ladder, year one	drawn
3.1.1	Simple versus compound growth of USD 100,000 at 8 %	drawn
3.1.2	Discount-factor curves at 6 %, 10 % and 14 %	drawn
3.2.1	Anatomy of an annuity loan: Kestrel's USD 42,000,000, 12 years at 6 %	drawn
3.2.2	Three shapes, one loan: annual debt service under annuity, level-principal and bullet	drawn
3.2.3	Outstanding principal, not debt service: Kestrel's USD 42,000,000 under four shapes	drawn
3.3.1	What 3 % inflation does to USD 1,000,000 of purchasing power	drawn
3.3.2	Compound versus simple escalation of a USD 10,000,000 cost at 4 %	drawn
3.3.3	One stream, four treatments: what mixing nominal and real costs	drawn
4.1.1	Kestrel's NPV profile	drawn
4.2.1	Two paybacks: cumulative cash versus cumulative present value	drawn
4.3.1	Two NPV profiles and the crossover	drawn
4.4.1	What flexibility is worth: the same mean, two spreads	drawn
5.1.1	The development funnel as an option premium	drawn
5.3.1	Bankability as a conjunction	drawn
6.2.1	Construction funding and interest during construction	drawn
6.4.1	The minimum coverage a level line hides	drawn
7.1.1	Identical expected cash, different bankability	drawn
7.3.1	Margin drift over the concession	drawn
8.3.1	Six answers to one question: how much contingency?	drawn
8.4.1	The cost of a month of slip rises through the build	drawn
9.1.4	The leverage ladder: what gearing buys and what it costs	drawn
9.2.3	Four capital structures, priced	drawn
10.1.1	Debt capacity as a function of coverage and tenor	drawn
10.1.2	Three ways to size the same project at 1.30×	drawn
10.2.2	Which covenant binds first	drawn
11.1.1	The allocation price test	drawn
11.3.1	Coverage against the reference rate, at three hedge ratios	drawn
12.1.1	The cap stack against the loss it was drafted for	drawn
12.2.1	The contracted volume floor a covenant requires	drawn

FIGURE	SUBJECT	ARTWORK
13.1.1	The breakeven detection rate of each diligence stream, in parallel and in series	drawn
13.3.1	Kestrel's conditions-precedent conjunction	drawn
14.1.1	Funding order: who is exposed, and what the interest costs	drawn
14.4.1	Coverage at a calendar-fixed first repayment date	drawn
15.2.1	Kestrel's operating waterfall and the block account it fills	drawn
15.4.1	The restructuring frontier	drawn
16.1.2	Where automation starts to pay, and what the error cost does to the answer	drawn
16.1.3	The accuracy-maximising threshold is not the cost-minimising threshold	drawn

— Appendix E — Practitioner's toolkit library

52 adoption-ready artefacts, indexed here and defined in the Knowledge Areas they belong to. They are indexed rather than reprinted deliberately: a template that exists twice is a template that will disagree with itself, and the version in the chapter is the one the surrounding text explains. Adapt the headings to your organisation, then keep them stable — a checklist whose wording changes every quarter records nothing over time.

TOOLKIT	ARTEFACT	WHAT IT IS FOR
1.T.1	Stakeholder map (one page per project)	Per party: name and role · what they optimise · contract binding them (Domain 12 reference) ·
1.T.2	Financing-route decision record	Options considered (corporate / limited recourse / non-recourse / hybrid) · recourse sentence
1.T.3	Conflicts and AI-use register	Conflicts: relationship · parties affected · disclosure date · handling (barriers/consent/
1.T.4	Recourse-cost worksheet (one per financing route considered)	The arithmetic of WE 1.1.2, in the order a decision paper needs it, so that the incremental cost of
2.T.1	Defined-terms sheet (one per financing)	For each term used in a covenant or report — CFADS, EBITDA, net debt, distributable cash,
2.T.2	Accrual-to-cash bridge (standing monthly schedule)	Net income · + depreciation and amortisation · + other non-cash charges (provisions) ·
2.T.3	Statement-integrity checklist	
3.T.1	TVM assumption register (one row per modelled stream)	
3.T.2	Schedule QA checklist	frequency; the two frequencies confirmed separately against the facility agreement.
3.T.3	Escalation register	For each escalating line: base amount and base date · index (publisher, series, definition) ·
3.T.4	Rate comparison worksheet (one column per offer)	Never compare quoted rates. Build one column per competing facility and require every row to be
4.T.1	The appraisal one-pager (per decision)	Decision question (accept/reject · exclusive choice · rationing) · cash-flow source and world
4.T.2	IRR pathology checklist	
4.T.3	Rationing worksheet	Columns: project · I_0 · NPV · PI · strategic notes/dependencies. Steps: rank by PI →
4.T.4	Hurdle-rate reconciliation sheet	One page, completed before the appraisal is circulated rather than after it is challenged.
5.T.1	The bankability condition register	One row per condition, decomposed to the level at which something must independently be true (Case study
5.T.2	Sponsor commitment and support schedule	One row per sponsor. Columns: equity share · base equity commitment · each support commitment separately
5.T.3	COD-slip and readiness pack	Two parts, maintained from twelve months before COD. The slip calculator: drawn debt × rate ÷
6.T.1	The model conventions sheet (one page, in the inputs block)	One line per convention, each with the value chosen, the alternative rejected, and the reason:
6.T.2	The check block (built before the first answer)	
6.T.3	Model governance register (per model, per version)	Columns: version number (appearing on every printed page) · date · author · reviewer · reason for
7.T.1	Revenue mechanism specification	One row per component of the payment mechanism, populated from the agreement and signed off

TOOLKIT	ARTEFACT	WHAT IT IS FOR
7.T.2	Indexation mismatch map	Domain 3's escalation register (Toolkit 3.T.3) catalogues each line's index mechanics. This
7.T.3	Revenue stress and counterparty pack	Section A, counterparty: each payer's share of revenue · rating or internal grade with source
8.T.1	Contingency basis note (one page, per sanction and per recalculation)	One page that must exist before any contingency figure is quoted. Base estimate: amount, base
8.T.2	Construction cost model check (before any envelope is fixed)	
8.T.3	Monthly construction pack, financing annexe	One annexe to the existing controls report — never a second set of numbers. Rows: certified progress
9.T.1	Cost-of-capital derivation record (one per project, per structure)	One page, signed. Rows: r_f — instrument, tenor, currency, quotation date, source · ERP —
9.T.2	Tranche comparison sheet (all-in, like-for-like)	One column per candidate tranche. Rows: amount · currency · base rate and margin, or profit rate ·
9.T.3	Capital-structure decision record	For each candidate structure, one row: tranche amounts and costs · re-levered k_e · WACC ·
10.T.1	CFADS definition reconciliation	Column 1: each line of the facility's CFADS definition, with its clause reference. Column 2: the
10.T.2	Covenant dashboard (per facility, per test date)	Per covenant: test name and clause · test date and frequency · historic or forward-looking ·
10.T.3	Coverage model check (before any ratio is quoted)	
10.T.4	Sizing-basis statement (one page, agreed before any capacity number circulates)	Nine lines, each with a named owner and a document reference. 1 — CFADS definition and its
11.T.1	Risk allocation price sheet (one row per register line)	Columns: ID · risk statement · phase · our p and impact, with the evidence reference ·
11.T.2	The breakeven page (one side of paper, per facility)	Every material exposure, expressed in the covenant's own units. Rows: covenant and lock-up cash
11.T.3	Register aggregation and re-cut worksheet	Three panels. Sponsor case: items with p, impact, evidence reference, EMV, σ ; mean = Σ EMV
12.T.1	The contract limits and calibration sheet (one per contract)	One page, filled before the contract is signed and re-filled at every amendment. Rows: contract
12.T.2	Security package sufficiency register (one per transaction)	One row per instrument: instrument type · obligor, and which entity in the group is actually bound
12.T.3	Claim assessment and settlement-zone worksheet (one per claim)	Header: claim reference, event, notice served and whether within the contractual time bar (fact,
13.T.1	Diligence stream economics and interface sheet (one per transaction)	inside the envelope or on the critical path (and if the latter, the justification and its weekly
13.T.2	Model-audit finding register (one per model version)	Per finding: number · date raised · raised by (auditor / sponsor review / machine scan) · scope
13.T.3	Close register: conditions, costs and funds flow (one per transaction)	third-party / adviser / financial) · chain and predecessor · duration estimate · owner · evidence
14.T.1	Draw request pack and certification control sheet	period, split into value of milestones achieved, value of assessed percentage completion, and value

TOOLKIT	ARTEFACT	WHAT IT IS FOR
14.T.2	Restated sources and uses, the in-balance test, and the EAC bridge	total — against sources in the same three columns, with available commitment stated as undrawn debt
14.T.3	Contingency coverage and change-control register	draw retires; remaining unallocated. Denominator, itemised: approved variations not yet
15.T.1	The operating bridge (one per reporting period)	A single sheet running from physical performance to certified CFADS, in fixed rows: availability
15.T.2	Operating covenant and distribution register (one per facility, per test date)	Per test: name and clause · test date and frequency · backward, rolling or forward-looking · window
15.T.3	Transaction decision sheet (refinancing, amendment or restructuring)	break costs on the actual notional profile, and the sweep.
16.T.1	The automation business case, on one page	Mandatory lines, in this order, with no line permitted to be blank: the task and the volume the
16.T.2	Threshold and alert-queue sheet (per detector, per review)	Per candidate threshold: score cut · TP · FP · FN · TN · recall · precision · accuracy ·
16.T.3	Model inventory, tier and approval record	One row per model in production, reconciled quarterly to production access logs — an unreconciled

On the one appendix the volume plan lists and this volume does not carry. The plan for this family also names a consolidated self-check answers appendix. It is not printed, and the reason is worth stating rather than leaving as an apparent omission: each self-check in this volume already carries its own answer beside the question, so a consolidated set would be a verbatim second copy — precisely the duplication this programme's editorial rules forbid. The questions are indexed by their Knowledge Area instead.

The standards and frameworks referenced register the plan calls for **is** published, as Appendix F. It states no edition years, deliberately and for a stated reason, and that single outstanding verification is recorded in the Institute's corpus gate report rather than glossed over.

The consolidated question bank the plan calls for is published separately as [QUESTION_BANK.md](#), and the global glossary as [GLOSSARY.md](#); both are generated from the chapters by the same principle as these appendices.

— Appendix F — Standards and frameworks referenced

This volume references **10 documents, standards or frameworks**. Every one is named and characterised — never reproduced. No protected text, table, figure, clause, checklist or question from any of them appears in this volume; each is described at the level of its stated scope, in this programme's own words, and the treatment of the underlying subject is this programme's own. Where a chapter needs a number, it derives one rather than citing one.

Nothing here implies endorsement. No standards body, institute, professional association or financial institution has reviewed, approved or endorsed this volume, the designation it supports, or this programme. A reference means only that the document exists and is relevant to the topic under discussion.

Editions are deliberately not stated. No entry below carries an edition year or revision date. Standards are revised, withdrawn and superseded on their own schedules, and a citation to a superseded edition is worse than no citation, because it reads as authoritative while being wrong. Confirming the current edition of each document against the publisher's catalogue at the date of publication is a review task, and it is recorded as outstanding in [CORPUS_GATE_REPORT.md](#). **A reader consulting any document below should obtain the current edition from its publisher.** Standards are copyright works and are not reproduced or redistributed by this programme.

Artificial intelligence, information security and privacy

REFERENCE	DESCRIBED IN THIS VOLUME AS ADDRESSING	DISCUSSED IN
ISO/IEC 42001	artificial-intelligence management systems	D16
ISO/IEC 23894	guidance on risk management for artificial intelligence	D16
ISO/IEC 27001	information-security management systems	D16
NIST	the United States National Institute of Standards and Technology, referenced for its AI Risk Management Framework — a voluntary, function-based framework, not a standard and not a regulation	D16

Financial reporting

REFERENCE	DESCRIBED IN THIS VOLUME AS ADDRESSING	DISCUSSED IN
IFRS 15	revenue from contracts with customers	D2
IFRS 16	leases	D2
IAS 37	provisions, contingent liabilities and contingent assets	D2

Project finance, environmental and social frameworks

REFERENCE	DESCRIBED IN THIS VOLUME AS ADDRESSING	DISCUSSED IN
Equator Principles	a voluntary risk-management framework adopted by participating financial institutions for environmental and social risk in project finance	D5, D9
IFC Performance Standards	the International Finance Corporation's environmental and social performance standards, widely adopted as a reference benchmark in project finance	D5
OECD	the Organisation for Economic Co-operation and Development, referenced for its arrangement on officially supported export credits	D9

What this register does not contain

No bibliography of textbooks or certification-body publications. This volume is written from first principles and its worked examples are original, so there is no borrowed material to cite. Where a body of practice is discussed — cost-estimate classification, iterative delivery, portfolio governance — the discussion is of the practice, described in this programme's own words, and the reader is pointed to the owning body rather than given a paraphrase of its text.

No legal, tax or accounting authority. The financial-reporting standards above are named where a chapter explains why a treatment matters, never to state what the treatment is in any jurisdiction. Every such passage carries the volume's standing caution: treatments are jurisdiction-specific, and the applicable position requires written advice for the specific entity and structure. The same applies to every legal question raised in the text.

— Appendix G — Integrated capstones

A capstone is not a longer case study. Each domain's cases test whether a candidate can apply one domain's machinery; a capstone tests something the chapters structurally cannot — whether the **answers agree with each other**, and whether the reader can see which of them is actually binding at each point in a project's life. A financing is not a sequence of sixteen correct calculations. It is one asset whose appraisal, structure, contracts, diligence, drawdown and covenants must all be true at the same time, and the interesting failures are the ones that live in the joints.

Four capstones, and why the first is different. Three of the four are new projects, each chosen for a revenue basis the others do not share: **Aurora Ridge** (G.2), a toll-road concession where demand is unhedged and nothing guarantees the revenue; **Helios Flats** (G.3), a solar-plus-storage independent power project where the price is contracted for the asset's whole life and the resource is not; and **Harbourgate Point** (G.4), a hyperscale data centre whose contract is investment-grade and **expires five years before the debt does**. Each is worked from its own arithmetic, and none reuses another's figures. A closing section sets the four side by side, because the argument they make together — that no two of them bind in the same place — is not visible from any one of them. Every project, company and person in this appendix is fictitious.

The first capstone is the **Kestrel Water desalination PPP** — the master thread this volume has carried since Domain 3. It is not reworked here, because reworking it would be the duplication this programme's editorial rules forbid. What it has never had is an **assembly**: the thread is distributed across sixteen chapters and has never been laid out in one place, so no reader has yet seen the whole ledger, the sequence in which its decisions were actually taken, the three places its own numbers had to be reconciled against one another, or — the finding that matters most — how the **binding constraint moves** as the project ages. That assembly is new content, and it is the single strongest test available of whether this volume is internally consistent.

— Capstone One — Kestrel Water: the master thread, assembled

The asset. A single-purpose company holds a 25-year concession to build and operate a seawater desalination plant, sized at 60,000,000 of capital expenditure against a 48,000,000 fixed-price, date-certain EPC wrap, funded 70/30 senior debt to sponsor equity, with a 12-year senior facility at 6.0 % and an availability-based offtake. Every figure below is a result printed in this volume and independently recomputed by the golden-answer suite; the cross-references are the authority.

G.1.1 The ledger — which chapter produced which number

#	DOMAIN	THE RESULT THAT LEAVES THE CHAPTER	WHERE IT IS USED AGAIN
1	Foundations	limited-recourse premium 5,202,128 PV; enforcement exposure removed 10,073,997 ; breakeven failure probability 51.6392 %	frames every later structural choice
2	Accounting	EBITDA 7,500,000 → net income 2,064,000 → operating cash flow 3,864,000 ; working capital absorbs 600,000	D10's CFADS definition; D15's operating bridge
3	Time value	senior instalment 5,009,635.23 on $AF(0.06, 12) = 8.383844$	D9, D10, D15 — every coverage ratio
4	Appraisal	NPV +16,179,360 at 8 %; IRR 12.1921 % ; MIRR 9.7327 % ; discounted payback 10.07 years	D6 reconciles it; D9 supplies the rate
5	Bankability	six conditions averaging 90.5 % multiply to 54.72 % probability of close; honest origination cost 7,400,000	G.1.4 — the finding that changes the case
6	Modelling	five defensible NPVs spanning 29,545,516 ; capitalised interest 2,114,597 quarterly against 1,247,352 annually; sources and uses close at 60,000,000 on contingency 3,645,403	D8's provision; D14's drawdown
7	Revenue	availability and volume offers with identical expected CFADS 6,384,000 and DSCR 1.2743 , differing by 10,679,727 of debt capacity	D10's sizing; D15's covenant
8	Cost and contingency	contingency 3,645,403 (7.59 %); lifecycle programme 6,881,021 PV, 644,606 a year	G.1.3 — the constraint nobody funds
9	Funding structure	k_e 15.42 % , after-tax k_d 4.80 % , WACC 7.9860 % ; $WACC(g) = 8.70 \% - 1.02 \% \times g$	D4's hurdle, reconciled in KA 4.A.3
10	Debt sizing	capacity 41,171,123 at 1.30×, against a 42,000,000 request; covenant headroom 372,438	G.1.2 — the first reconciliation
11	Risk allocation	three risks transferred for 2,128,000 of premium against 4,420,000 retained; five declined	D8's retained register; D12's caps
12	Contracts	exposure 12,255,674 against risk-adjusted cover 8,160,000 — residue 4,095,674	G.1.5 — what equity actually carries
13	Diligence	seven streams worth +4,066,700 in parallel and −1,146,900 in series	the 5,213,600 that is scheduling alone
14	Drawdown	quarter-five draw 9,924,564 ; the funding-order sub-clause worth 1,466,064 of capitalised interest	D6's interest convention
15	Operations	covenant binds at CFADS 6,011,562.28 ; the distribution test binds at 6,262,044.04	G.1.3 — the real constraint
16	Data and AI	manual review 19.36 a record against 9.36 automated; breakeven 14,800 records a year	why the estate automates and the project does not

G.1.2 The first reconciliation — the 828,877 that was never in the plan

Domain 9 proposes 70/30 gearing: 42,000,000 of senior debt against 18,000,000 of equity. Domain 10 sizes the debt from cash flow outwards and finds that level **CFADS** of 6,384,000 at a 1.30× target supports **41,171,123**. The gap is **828,877**, and it does not close by negotiation — every route to closing it runs through redefining **CFADS**, which fails at the first competent credit review.

It closes with equity. The consequence is small in percentage terms and large in what it reveals:

	AS PROPOSED	AS FINANCEABLE
Senior debt	42,000,000	41,171,123
Sponsor equity	18,000,000	18,828,877
Equity share of capex	30.00 %	31.38 %

Two lessons sit in that table. First, **the sizing target, not the gearing target, decides the structure** — a sponsor who negotiates gearing without computing coverage is negotiating a number the lender will not honour. Second, the equity cheque in every subsequent calculation should be 18,828,877, not the 18,000,000 in the term sheet, and a return computed on the term-sheet figure overstates the sponsor's outcome. Domain 9's own ladder makes the same point structurally: the 1.30× requirement binds at **68.6185 %** gearing, so 70 % was never available.

G.1.3 The binding constraint moves — and this is the capstone's central finding

Ask, at four points in this project's life, what would stop it? The answer is a different quantity each time, and the gap between the answers is where projects are actually lost.

LIFE STAGE	THE BINDING TEST	ITS VALUE	HEADROOM
Appraisal	NPV positive at the owned rate	+16,179,360	21.24 % of revenue (KA 4.3.3)
Financial close	joint probability of all conditions	54.72 %	no headroom — it is a probability
Sizing	DSCR ≥ 1.30 at the target	1.2743 achieved	372,438 of annual cash
Operation	the distribution condition	binds at CFADS 6,262,044.04	121,956 , or 1.9103 %

The operating row is the one that should change behaviour. The covenant everyone watches has **372,438** of annual headroom — 5.8339 % of base-case cash. The distribution condition, which decides whether the sponsors are paid at all, has **121,956**, only **32.75 %** of the covenant's headroom and **1.9103 %** of base cash. A dashboard built around the covenant is therefore monitoring the lender's risk while the shareholders' risk fails almost three times earlier, and the sponsor discovers the difference the first quarter a distribution is blocked.

Set the lifecycle programme beside that number and the picture sharpens into something close to alarming. Domain 8 prices Kestrel's membrane and pump replacement at 6,881,021 in present value — **644,606** as a level annual charge, **10.0972 %** of CFADS. That annual charge is **5.2856 times** the distribution headroom and **1.7308 times** the covenant headroom. Fund it out of operating cash and CFADS falls to 5,739,394, taking DSCR from **1.2743 to 1.1457** — below the 1.20 covenant. So the lifecycle reserve **cannot** be funded from the cash the covenant is measured on; it has to come from the capital envelope, a dedicated reserve built at close, or a tariff term that recognises it. Domain 8's year-seven DSCR of **0.4561** on an unreserved programme is the same finding at its sharpest: a payment default, on an otherwise healthy asset, caused by a maintenance schedule everyone knew about from the first day.

This is what a capstone is for. No chapter is wrong. Domain 10 correctly reports 1.2743, Domain 8 correctly prices 644,606, and Domain 15 correctly identifies the distribution test. Only the assembly shows that the three are in tension, and only the assembly forces the question of which balance sheet absorbs it.

G.1.4 The project is excellent and the business barely pays

Domain 4 reports +16,179,360 of value. Domain 5 reports that the six conditions precedent multiply to a **54.72 %** probability of ever reaching it, and that the honest origination cost — the programme spend across forty screened opportunities divided by the two that closed — is **7,400,000**, not the 2,400,000 on this project's own charge code.

Put the two together, which no chapter does:

LINE	USD
Expected value at the decision to develop — $16,179,360 \times 0.5472$	8,853,346
Honest origination cost	7,400,000
Net	1,453,346

The origination cost is **83.58 %** of the probability-weighted value. A project that looks like a sixteen-million-dollar success is, at the moment the development decision is actually taken, a one-and-a-half-million-dollar business — and that is before the recourse premium of 5,202,128 that Domain 1 prices for the structure that makes it financeable at all. Three professional consequences follow, and none of them is "reject the project".

The development portfolio is the unit of account, not the project. A 54.72 % close probability is not a defect to be argued away; it is the ordinary state of a development pipeline, and it means the economics only work across a portfolio with a close rate above the **2.29 %** breakeven Domain 5 computes. A sponsor that charges origination to individual projects will always conclude that development is cheap and will always be wrong.

Conditions precedent are the highest-return work available. Domain 5's own sensitivity says lifting the weakest condition from 0.85 to 0.95 adds **6.4375 points** of close probability while lifting the strongest adds **1.7280** — a 3.7255× difference. At an 8,853,346 expected value, 6.4375 points is worth more than a million dollars of expected value for what is usually a few weeks of legal and commercial work. Nothing else in this ledger has that return.

Elapsed time is priced, not free. Domain 13's diligence programme is worth **+4,066,700** run inside a twelve-week parallel envelope and **−1,146,900** run in series — a **5,213,600** swing that is entirely scheduling. The same seven streams, the same 1,500,000 of fees, the same findings, and a five-million-dollar difference in value depending only on whether someone drew a critical path.

G.1.5 What the equity cheque actually carries

Domain 12 prices the contractual protection: against a 300-day delay and a 5 % output shortfall, the exposure is **12,255,674** and the risk-adjusted cover is **8,160,000**, leaving a credit-adjusted residue of **4,095,674**. Against the equity actually required from G.1.2 — 18,828,877 — that residue is **21.7521 %** of the cheque, and against Domain 4's NPV it is **25.3142 %**. Net of it, the project's value to the sponsor is **12,083,686**.

The temptation is to buy more protection. Domain 11 prices that too: the full EPC wrap on all eight risk items raises capex to **64,620,000** and pushes year-one DSCR to **1.1832** — below the 1.20 covenant. **The protection is unaffordable not because of its price but because of its effect on coverage**, which is a sentence worth committing to memory, because it is invisible to anyone comparing premium against expected loss. Domain 11's own allocation test explains why the eight items divide as they do: the three the contractor genuinely controls transfer at **2.0771** dollars of expected-cost reduction per

dollar of premium, while the five it cannot control destroy **460,000** of value even at a zero margin, because the bidder's own expected cost (3,300,000) exceeds the owner's (2,840,000). Risk transfer is not insurance; it is a bet on who is the cheaper bearer, and it is negative-value whenever the answer is the person already holding it.

G.1.6 Which of the five NPVs the board saw

Domain 6's most uncomfortable result is that this one project supports **five arithmetically correct net present values spanning 29,545,516** — from −9,670,265 to +19,875,251 — differing only in basis, horizon and case. Domain 4's headline +16,179,360 is the pre-tax, fifteen-year member of that family, and it sits at the **87.49th percentile** of the span.

That is not an accusation; the pre-tax fifteen-year basis is a defensible screening convention and Domain 6 reconciles it to **CFADS** to within 661 of present value on an implied escalation of 2.967 %. But a director who has seen only that number has seen the second-best of five defensible answers without being told that four others exist. The deliverable Domain 6 insists on — **the bridge, not the number** — is therefore not modelling hygiene. It is the difference between a board that has been informed and a board that has been persuaded.

G.1.7 The five questions this capstone equips a candidate to ask

1. **Is the debt sized or negotiated?** If the gearing came before the coverage arithmetic, the equity cheque in the term sheet is understated (here by 828,877, taking equity from 30.00 % to 31.38 % of capex).
 2. **Which test is actually binding, today?** Appraisal, close probability, coverage and the distribution condition bind at different times, and the distribution test — 1.9103 % of headroom — is invisible on a covenant dashboard.
 3. **Where is the lifecycle programme funded from?** If the answer is operating cash, compute the resulting **DSCR** before agreeing (1.2743 → 1.1457 here, through the covenant).
 4. **What is the expected value at the development decision, and what did origination really cost?** 8,853,346 against 7,400,000 is a different business from 16,179,360 against 2,400,000.
 5. **How many defensible NPVs does this model support, and which one am I looking at?** If the answer is "one", the model has not been interrogated yet.
-

— Capstone Two — Aurora Ridge: the road that cannot be geared

Kestrel's revenue is an availability payment: a counterparty pays for a plant that is ready, and volume risk sits with the offtaker. Every ratio in Capstone One rests on that. **Aurora Ridge is the same discipline applied to a revenue nobody guarantees**, and the arithmetic does not merely shift — it changes what the project can be.

The asset. A 30-year concession to build and operate an inter-urban toll road. Capital expenditure **USD 240,000,000**. Design traffic **18,000 vehicles a day** at a **2.40** toll, so mature annual revenue is $18,000 \times 365 \times 2.40 = 15,768,000$. Operations and routine maintenance **4,200,000** a year, largely fixed; a pavement and structures reserve of **1,368,000** a year, so mature **CFADS = 10,200,000**. Senior debt is offered at **7.0 %** over a **20-year** tenor. There is no offtaker, no availability payment, no minimum revenue guarantee, and no hedge for traffic — which is the whole point of the case. (Fictitious project. Cash taxes are assumed nil in the ramp years under capital allowances and are excluded from **CFADS** here; the treatment is jurisdiction-specific and would need written advice, per Domain 4's cross-sector caution.)

G.2.1 The demand-risk premium, in coverage and then in money

Lenders price unhedged demand risk in the **required ratio**, not in the margin. Where Kestrel's availability structure was sized at **1.30x**, a merchant toll road is sized at **1.40x** or higher. That is a small-looking change:

REQUIRED DSCR	ANNUAL SERVICE	DEBT CAPACITY ON AF (0.07, 20) = 10.594014	GEARING
1.30x	7,846,153.85	83,122,265.62	34.63 %
1.40x	7,285,714.29	77,184,960.93	32.16 %
1.45x	7,034,482.76	74,523,410.55	31.05 %

Ten basis points of coverage costs **5,937,304.69** of debt capacity — **7.1429 %** of it, which is exactly $1 - 1.30/1.40$, because capacity is inversely proportional to the required ratio and nothing else in the calculation moved. That identity is worth carrying: **a coverage requirement is a proportional tax on debt capacity**, so a negotiation over "just a tenth of a turn" is a negotiation over seven per cent of the senior facility, and it should be conducted in money.

Note the gearing column, though, because it is the finding. Even at the lower 1.30x requirement this road supports only **34.63 %** senior debt against Kestrel's 68.6185 %. Nothing is wrong with the road; the ratio is simply being asked to cover a cash flow that no one has promised.

G.2.2 The ramp is the project, and level sizing cannot see it

Toll roads do not open at design traffic. Assume a conventional three-year ramp — **60 %, 80 %, 100 %** of design traffic — with operating cost and the pavement reserve unchanged, because they are functions of the road and not of the traffic on it. That last clause is where the damage comes from: **revenue ramps and cost does not**.

YEAR	TRAFFIC	REVENUE	CFADS	DSCR ON LEVEL-SIZED SERVICE OF 7,285,714.29
1	10,800	9,460,800	3,892,800	0.5343
2	14,400	12,614,400	7,046,400	0.9672
3	18,000	15,768,000	10,200,000	1.4000

Year one does not breach a covenant; it **fails to pay**, at barely half of debt service, and year two still cannot. The cash shortfall across the two years is **3,632,228.57** and the shortfall against the 1.40× covenant across the ramp is **9,460,800**. A facility sized on mature **CFADS** was never financeable; it was arithmetically correct and commercially fictional.

The instinctive correction is to size on year one instead. That produces a capacity of **29,457,413.32** — **47,727,547.61** less than level sizing, a 62 % reduction — and a gearing of 12.27 %, which is not a project financing at all.

G.2.3 What actually works, and what it costs

Neither extreme is the answer; the structure has to be **shaped to the ramp**. Take interest only for three years and amortise over the remaining seventeen, and two constraints now compete:

CONSTRAINT, BOTH AT 1.40×	TEST	DEBT CAPACITY
Year-one interest cover	$0.07 \times D \leq 3,892,800 / 1.40$	$D \leq$ 39,722,448.98
Steady-state amortisation	$D / AF(0.07, 17) \leq 10,200,000 / 1.40$, with $AF(0.07, 17) = 9.763223$	$D \leq$ 71,132,053.24

The binding constraint is year-one interest cover, and it binds at **39,722,448.98** — 55.8 % of what the amortisation test would allow. Sculpting recovers **10,265,035.66** over sizing on year one and still gives up **37,462,511.95** against level sizing. The resulting structure is comfortable everywhere except the place it was built for: year-two cover on interest only is **2.5342×**, and steady-state cover after amortisation begins is **2.5070×** on a service of **4,068,579.51**. Three years of interest-only costs **8,341,714.29** of interest with no principal retired.

Gearing lands at **16.55 %** of capital expenditure. Set that beside Capstone One:

	KESTREL WATER	AURORA RIDGE
Revenue basis	availability payment	unhedged demand
Required DSCR	1.30×	1.40×
Senior gearing achieved	68.6185 %	16.55 %
Equity or support required	31.38 %	83.45 %

The same discipline, applied to a different revenue risk, produces a four-fold difference in gearing — 4.1459× on these figures. This is the single most important thing a second capstone can teach, and it cannot be learned from Kestrel at any depth, because Kestrel's offtaker absorbed the risk that Aurora Ridge's structure has to absorb with capital.

Which is why real demand-risk roads are not financed the way this one has been. Read the last row as a requirement rather than a result: to bring the equity cheque down to Kestrel's 30 %, the project

needs **128,277,551.02** of support — **53.45 %** of capital expenditure — as a construction grant, availability element, minimum revenue guarantee, or subordinated public debt. That is not a subsidy smuggled in to rescue a weak project; it is the price of the risk transfer the market declines to make, computed rather than asserted. A leader who cannot produce that number is not in a position to argue for it, and a public authority that has not been shown it is being asked to approve a structure whose economics it has not seen.

G.2.4 The lever that looks free and is not

Faced with the ramp, sponsors reach for the toll. With a constant-elasticity demand curve at $e = -0.40$ — inelastic, as inter-urban traffic with no competing route usually is — a toll rise does raise revenue, and this is where judgement is needed rather than arithmetic:

TOLL CHANGE	TOLL	TRAFFIC	REVENUE	CHANGE
-10 %	2.16	18,775	14,802,058.52	-6.1260 %
base	2.40	18,000	15,768,000.00	—
+10 %	2.64	17,327	16,695,991.78	+5.8853 %
+20 %	2.88	16,734	17,590,790.60	+11.5601 %

Because $|e| < 1$, **revenue rises with every toll increase**, without limit inside the model. The revenue-maximising toll would require $e = -1$, and the model never reaches it. That is precisely the trap. **The binding limit on the toll is contractual and political, not economic**, so a model that optimises the toll will always recommend raising it, and will be right about the revenue and silent about the concession's cap, the escalation formula, the shadow-toll politics of a road whose users vote, and the diversion onto unpriced local roads that a 3.7 % traffic loss represents in someone else's network. An elasticity of -0.40 is also an estimate from a mature network applied to a road with no operating history — Domain 7's demand-forecast discipline applies in full, and the estimate should carry a range rather than a point.

The professional handling is to price the toll lever, disclose that the model has no interior optimum, and put the ceiling where it belongs: in the concession agreement, negotiated once, rather than in an annual revenue decision the sponsor will always want to resolve one way.

G.2.5 The four questions Aurora Ridge adds to Capstone One

1. **Who has promised this revenue?** If the answer is nobody, expect the required ratio to rise and read the consequence in money — 7.1429 % of capacity per tenth of a turn here.
2. **What does year one look like, not the mature year?** Level sizing on this project produced a facility that fails to pay debt service in its first year at $0.5343\times$ while every mature-case ratio was healthy.
3. **Which constraint binds after sculpting?** Here it is year-one interest cover at 39,722,448.98, binding at 55.8 % of what the amortisation test allows — so effort spent negotiating tenor or steady-state cover buys nothing.
4. **If the structure needs support, how much, and stated as what?** 128,277,551.02, or 53.45 % of capex, to reach a conventional equity cheque. A number of that size is a policy decision and must be presented as one.

— Capstone Three — Helios Flats: the ratio that is not what it says

Aurora Ridge's revenue risk was **demand**, and the lender priced it in the required ratio: 1.40× instead of 1.30×. Helios Flats has a **contracted price** — so on the face of it the credit is far better, and the market sizes it at **1.20×**. A leader who reads those two numbers side by side and concludes that a solar project is the more bankable proposition has made the most expensive mistake available in this volume, and this capstone exists to show why.

The asset. A 25-year fixed-price power purchase agreement at **42.00 per MWh** for energy delivered from a 200 MW solar plant with a co-located 50 MW / 200 MWh battery. Capital expenditure **USD 180,000,000**, of which **140,000,000** is the solar plant and **40,000,000** the battery. P50 first-year generation **460,000 MWh**, so P50 revenue is **19,320,000**. Operations and maintenance **4,320,000** a year and a reserve contribution of **1,000,000**, both essentially fixed, so P50 first-year **CFADS = 14,000,000**. Senior debt at **6.5 %** over an **18-year** tenor. Interannual resource variability $\sigma = 7.0 \%$; module and system degradation **0.5 % a year**. (Fictitious project. Cash taxes excluded as in Capstone Two; the treatment is jurisdiction-specific.)

G.3.1 The risk is priced in the quantity, not the ratio

Nobody guarantees the weather. A lender therefore does not size on the P50 energy estimate — the central case — but on a **one-year exceedance probability**, conventionally P90: the level the resource beats nine years in ten. For a normally distributed annual yield that is $P50 \times (1 - z_{90}\sigma)$ with $z_{90} = 1.2816$:

QUANTITY	CALCULATION	RESULT
P90 factor	$1 - 1.2816 \times 0.070$	0.910288
P90 energy	$460,000 \times 0.910288$	418,732.5 MWh
P90 revenue	$418,732.5 \times 42.00$	17,586,764.16

The energy falls **8.9712 %**. **CFADS** falls **12.3803 %**, to **12,266,764.16**, because the 4,320,000 of operations and the 1,000,000 reserve do not fall at all. That ratio — **1.3800× of cash sensitivity per unit of resource sensitivity** — is the project's operating leverage, and it is the first thing to compute on any asset whose revenue is a quantity times a fixed price. It is also why a "P90 sensitivity" run on revenue alone understates the coverage effect by nearly four points.

G.3.2 The binding year is the last one, and that is the mirror image of Aurora Ridge

Solar output declines. At 0.5 % a year the cumulative factor by the final year of an 18-year facility is $0.995^{17} = 0.918316$, so P90 energy in year 18 is 384,528.9 MWh and P90 **CFADS** is **10,830,215.15** — **11.7109 %** below the first year.

YEAR	P90 ENERGY (MWH)	P90 CFADS
1	418,732.5	12,266,764.16
5	410,420.4	11,917,658.11
10	400,262.0	11,491,004.58
18	384,528.9	10,830,215.15

Size at 1.20× on **year one** and the facility is **106,643,837.27**, on a service of 10,222,303.47. Carry that service to year 18 and coverage is **1.0595×** — a covenant breach, and one that arrives not from any adverse event but from the degradation curve that was in the technical report at financial close. Sizing on the **binding year** instead gives **94,154,879.59**, at a cost of **12,488,957.68** of capacity.

Set that beside Capstone Two and the pair becomes a single lesson. **Aurora Ridge's binding year is its first** — revenue ramps up while cost does not. **Helios Flats' binding year is its last** — revenue degrades while cost does not. Neither project's binding year is the one a mature-case or first-year model looks at, and the two fail in opposite directions from the same omission: cost does not move with revenue. The general rule the two cases establish together is that **the year to size on is the year of minimum coverage, and it must be found rather than assumed.**

G.3.3 What 1.20× actually means, restated

Now the comparison that gives this capstone its title. Restate the sizing requirement onto a common basis — first-year P50 CFADS, which is the figure a sponsor's own model reports:

The restatement has to be done on **cash**, not on energy, and the distinction is not pedantry — it is G. 3.1's operating leverage doing its work a second time. Scaling the ratio by the two energy factors ($1.20 / 0.910288 / 0.918316 = 1.4355\times$) is the intuitive move and it is **wrong**, because it assumes CFADS falls in proportion to generation. It does not: $C_{50} \times 0.910288 \times 0.918316 = 11,703,054$ against an actual year-18 P90 CFADS of **10,830,215**, the **872,839** difference being the operations and reserve that never fall. The correct equivalent ratio is the one that reproduces the same facility from first-year P50 cash — $1.20 \times C_{50} / C_{18}$:

	AURORA RIDGE	HELIOS FLATS
Quoted required DSCR	1.40×	1.20×
Cash-flow basis it applies to	level, P50-equivalent	P90, in the final year
Restated onto first-year P50 cash — resource only	1.40×	$1.20 \times 14,000,000 / 12,266,764 =$ 1.3696×
Restated onto first-year P50 cash — resource and degradation	1.40×	$1.20 \times 14,000,000 / 10,830,215 =$ 1.5512×

The 1.20× is a 1.5512×. Twenty basis points of apparent advantage is in fact **fifteen and a tenth points of genuine disadvantage**, and the whole difference is in two words nobody reads: which cash flow the ratio multiplies. A term sheet quoting a ratio without its basis has quoted nothing, and a sponsor comparing offers across two projects on the ratio alone is comparing the conventions of two credit committees.

Note carefully what the energy-scaled shortcut does and does not cost you, because it is not a disaster and that is what makes it dangerous. At 1.4355× it still lands **above** Aurora Ridge's 1.40×, so it reaches

the right conclusion: this project is the more demanding credit. What it loses is the size of the finding. It reports a margin of **0.0355** of a turn against a true **0.1512 — 23.49 %** of it — which turns a substantial difference into a rounding argument, and a rounding argument is one a committee will overrule. Getting the direction right and the magnitude wrong by three-quarters is how correct analysis loses to confident analysis.

This is the single most transferable finding in the appendix. **A coverage ratio is a fraction, and both parts of it are negotiable.** Aurora Ridge's lenders took their protection in the numerator's multiplier; Helios Flats' lenders took the same protection in the denominator's definition, and took slightly more of it. Neither is wrong; only the comparison is.

G.3.4 The forty million that earns no contracted revenue

The PPA pays for **energy delivered from the solar plant**. The battery does not generate energy — it shifts it — so under this contract it earns nothing contracted at all. Its economics are arbitrage, capacity payments or ancillary services: merchant revenue, on which no lender will advance senior debt sized at 1.20x.

The consequence is arithmetic, not opinion. The **94,154,879.59** of capacity is supported by the solar plant's contracted cash and stands at **67.25 %** of the solar plant's 140,000,000 — a healthy contracted-asset gearing. Against the **180,000,000** actually being spent, it is **52.31 %**, and **85,845,120.41 — 47.69 %** — has to come from equity or from a separate merchant financing on different terms. The battery therefore dilutes blended gearing by nearly fifteen points, and it does so **without any change to the solar project's credit**.

Three professional consequences, in the order they get missed:

The hybrid asset must be financed as two assets. A single facility sized against blended capex either over-advances against the battery or under-advances against the solar. The disciplined structure is two tranches with two bases, and the merchant tranche priced for what it is.

The battery's business case is a separate paper. Whether 40,000,000 of storage earns its keep is a merchant-revenue question — dispatch spreads, cycle life, degradation of the cells on a different curve from the modules — and it cannot be answered inside a contracted-project model. Presenting it inside one is how storage gets approved on the solar plant's credit.

The PPA's definition of the delivered product is a financing term. If the offtake had been written for dispatchable energy at the point of interconnection rather than for energy from the plant, some of the battery's value would have become contracted, and some of that 47.69 % would have become bankable. That clause is negotiated by commercial teams, years before anyone computes a gearing, and it is worth tens of millions here.

G.3.5 The three questions Helios Flats adds

1. **What basis does this ratio apply to?** P50 or P90, first year or minimum year, before or after degradation. Until that is answered the ratio is a number without units.
2. **Where is the year of minimum coverage?** Not the first, not the mature one — found. It is year one on Aurora Ridge and year eighteen here, and both projects would have breached if sized on the other's binding year.
3. **Which part of the asset earns the contracted revenue?** Whatever does not is not collateral for senior debt at the contracted ratio, however physically integrated it is.

— Capstone Four — Harbournate Point: lending past the lease

Kestrel's revenue was contracted for the concession's whole life. Aurora Ridge had no contract at all. Helios Flats had one for twenty-five years against an uncertain resource. **Harbournate Point has an investment-grade counterparty on a contract that expires five years before the debt does**, and that single fact relocates the entire credit question: it is no longer the coverage in any modelled year, because every modelled year is fine. It is the probability and price of a lease nobody has signed.

The asset. A 60 MW hyperscale data centre. Capital expenditure **USD 720,000,000** — 12,000,000 a MW. A **seven-year** anchor lease with an investment-grade tenant over 40 MW at **120 per kW-month**, and the remaining 20 MW let at **130** — annual revenue $40,000 \times 120 \times 12 + 20,000 \times 130 \times 12 =$ **88,800,000**. Operating and property costs **22,800,000**, so net operating income is **66,000,000**. Senior debt at **6.0 %**; the market will offer a **12-year** tenor. Required **DSCR 1.35x**. (Fictitious project; tax excluded as in Capstones Two and Three.)

G.4.1 Sizing on contracted cash produces a facility with zero tolerance

Take the 1.35x at face value against the 66,000,000 and the arithmetic is unremarkable: service of **48,888,889** against $AF(0.06, 12) = 8.383844$ supports **409,876,814.86**, or **56.93 %** of cost. Every year from one to twelve covers at exactly 1.35x, and a covenant-compliance table would be green in all twelve rows.

Now ask the only question that matters. Years eight to twelve are paid by a lease that does not exist, and the outstanding balance entering year eight is $48,888,889 \times AF(0.06, 5) =$ **205,937,785.07** — **50.24 %** of the original facility, resting entirely on a re-letting. So: how far can the market fall before the covenant breaks?

By construction, not at all. The facility was sized so that today's net operating income yields exactly 1.35x, which means the breakeven re-let is **100.0000 %** of today's revenue and the tolerance is **zero points**. That is not a coincidence to be worked around; it is what sizing a twelve-year facility on seven years of contracted cash means. The structure requires a market in year eight identical to the market today, and it requires it as a condition of not defaulting.

Price a modest softening and the consequence is immediate. Operating leverage is $88,800,000 / 66,000,000 =$ **1.3455x**, so a 15 % rent decline is a **20.1818 %** decline in net operating income:

RE-LETTING OUTCOME	NET OPERATING INCOME	DSCR ON THE CONTRACTED-CASH FACILITY
flat	66,000,000	1.3500
−5 % rent, 95 % occupancy	57,342,000	1.1729
−10 % rent, 92 % occupancy	50,726,400	1.0376
−15 % rent, 90 % occupancy	45,132,000	0.9232

The last row is a **payment default**, not a covenant breach — the third time in this appendix that a project reaches one, after Aurora Ridge's ramp and Helios Flats' degradation, and again from a condition documented before financial close.

G.4.2 The extra tenor buys 2.70 %, not 50 %

Set the naive twelve-year facility beside the two structures a competent credit committee would actually consider, and the comparison inverts:

STRUCTURE	FACILITY	LOAN TO COST	RE-LET TOLERANCE
1 — tenor matched to the lease (7 years)	272,916,425.94	37.91 %	not exposed
2 — 12 years on contracted cash	409,876,814.86	56.93 %	0.0000 %
3 — 12 years, sized on a stressed re-let	280,281,218.31	38.93 %	23.5000 points

Structure 3 sizes the whole tenor on the –15 %/90 % case: service of **33,431,111.11** against a stressed net operating income of 45,132,000, which covers **1.9742x** on today's cash and holds 1.35x down to **76.5000 %** of today's revenue.

And structure 3 lands within 2.70 % of structure 1. The twelve-year tenor, honestly stressed, buys **7,364,792.37** of additional facility — not the **136,960,388.93** that structure 2 appears to offer. That apparent 136.96 million is the entire content of the re-letting assumption, and it is an assumption with no tolerance at all.

This is the finding to carry out of the appendix. **A tenor extension beyond the contracted period is not a financing improvement; it is a position on a market, taken by a lender and paid for by a sponsor.** The two structures that price it honestly converge, which is what one expects when the underlying cash is the same and only the pretence differs. A committee choosing structure 2 over structure 3 has not obtained cheaper capital — it has bought 129.6 million of debt against a re-letting forecast, and would be better served by saying so and pricing it.

G.4.3 What the re-letting question actually requires

Three obligations follow, none of them a modelling exercise:

A refinancing plan, priced. With 205,937,785.07 outstanding at year seven, the sponsor's real exposure is the loan-to-value at the refinancing date — and the value at that date is a function of the same re-let. The two move together, which is the definition of the wrong kind of correlation: the asset is worth least exactly when the balance must be refinanced. A tail sized on today's value has priced neither.

A leasing pipeline treated as a condition precedent to the tail, not to drawdown. Kestrel's conditions precedent were tested once, before close (Capstone One, G.1.4). Harbournate Point's decisive condition falls due in year seven and nobody tests it, because financial-close discipline does not reach that far. The instrument that does is a covenant requiring a stated share of capacity re-let by a stated date, with cash sweeps ahead of it — which converts an untested assumption into a monitored one.

Honesty about what the counterparty's rating covers. An investment-grade tenant makes the contracted seven years very safe, and does nothing whatever for years eight to twelve. A credit paper leading on the tenant's rating has described the half of the exposure that is not at risk. The technology risk sits in the same place: 12,000,000 a MW buys a specification with a useful commercial life that may be shorter than the debt, and re-letting at today's rate assumes a facility that is still competitive when a hyperscale tenant next chooses.

G.4.4 The three questions Harbourgate Point adds

1. **Does the contract outlive the debt?** If not, identify what share of the facility is paid by an unsigned agreement — 50.24 % here — and treat that share as merchant, whatever the tenant's rating.
 2. **What is the re-let tolerance, in points of revenue?** A facility sized on contracted cash has zero, by construction. If nobody has computed the number, the answer is zero and nobody knows it.
 3. **What does the longer tenor buy once the tail is honestly stressed?** Here, 2.70 % — and the arithmetic that shows it takes one afternoon, against a 129.6 million position that would otherwise be taken by default.
-

— The eight capstones, and what they establish together

Four programmes in each volume, and in this one four financings whose only common feature is the discipline applied to them. Read in sequence they make one argument that no single capstone makes:

CAPSTONE	REVENUE BASIS	WHERE THE BINDING CONSTRAINT TURNED OUT TO BE
One — Kestrel Water	availability payment	the distribution test, at 1.9103 % of headroom, not the covenant at 5.8339 %
Two — Aurora Ridge	unhedged demand	year one , at a DSCR of 0.5343
Three — Helios Flats	contracted price, uncertain resource	year eighteen , at 1.0595× if sized on year one
Four — Harbournate Point	contracted, but shorter than the debt	year eight , outside every modelled year

Not one of the four binds where a competent analyst would first look, and no two bind in the same place. That is the argument. **The ratio is never the finding; locating the year and the test that govern is the finding**, and it has to be done project by project because the answer moves with the revenue basis. Every one of these projects would have passed a compliance table built around its headline covenant, and three of the four reach a payment default rather than a breach — which is the distinction between a conversation with a lender and a default notice.

PCI Professional Laws

Mandatory professional rules established by PCI Global for work within a PCI certification scope. They are not legislation and do not displace applicable law, contract or authoritative standards, and each law is cited by its stable identifier — never by page. The foundational set binds every PCI credential; the certification set that follows it binds this one.

PCI Foundational Laws

Status: Foundational law set of the PCI Professional Law System. These laws apply to **all three PCI credentials** — PCL-AI (AI Project Controls Leader), PFL-AI (AI Project Finance Leader) and PML-AI (Project Management Leader – AI) — and to every candidate and credential holder within the scope of their PCI-certified work. Drafted under the binding specification in [LAW_SYSTEM.md](#); IDs are stable (**PCI-LAW-F-NN**) and are cited by ID, never by page.

⚠ CAUTION

PCI Professional Laws are professional certification rules and standards of conduct established by PCI Global. They are not legislation, regulatory requirements or substitutes for applicable law, contractual obligations or authoritative professional standards. Where any applicable law, regulation, contract or authoritative professional standard imposes a stricter requirement, that requirement governs.

How to read these laws

+ PCI PRACTICE GUIDANCE

Every law below follows the mandatory drafting format of [LAW_SYSTEM.md](#) §4, with no field omitted. The normative language of §3 applies throughout: **must** / **must not** / **shall** / **shall not** mark mandatory professional rules; **should** marks recommended practice; **may** marks discretion. Each law is a **Mandatory PCI Law**; material labelled as guidance, external requirement, jurisdictional requirement or illustrative example is identified as such in text and is never itself a law. The whole set is governed by the suite principle, stated once and used identically everywhere:

⚠ CAUTION

AI proposes; the professional verifies, decides and remains accountable.

External instruments are named and characterised in PCI's own words per [LAW_SYSTEM.md](#) §5 and the shared source registry ([./registries/SOURCES.md](#)); their official publications govern; no external text is reproduced. Certification-specific laws (**PCL-LAW-DD-NN**, **PFL-LAW-DD-NN**, **PML-LAW-DD-NN**) are subordinate elaborations of this foundational set and must not conflict with it.

No endorsement, affiliation or accreditation is claimed or implied. Naming an external instrument means only that the instrument exists and is relevant to the topic under discussion. No standards body, professional institute, government, supervisory authority or financial institution has reviewed, approved, endorsed or accredited these laws, the credentials they support or PCI Global, and nothing in this set is a claim of conformity with, certification to, or accreditation under any instrument named. Editions, clause numbers and effective dates are not asserted; where an instrument's status is known to be changing, that is noted at the point of use and the reader must confirm the current position with the publisher.

Part I — Accountability and the governed use of AI

§ PCI LAW

PCI-LAW-F-01**Professional Accountability and the Suite Principle**

Rule. A PCI credential holder or candidate is personally and non-delegably accountable for every professional work product, judgement and decision within the scope of their PCI-certified work, whether or not artificial intelligence assisted in its production, and shall apply the suite principle — AI proposes; the professional verifies, decides and remains accountable — to all such work.

Purpose. To establish that certification attaches accountability to a person, not to a tool, a model, a vendor or a team, and to make the suite principle the single governing formulation for AI use across all three credentials.

Scope. All candidates and credential holders of PCL-AI, PFL-AI and PML-AI, in all professional work performed within a PCI certification scope, with or without AI assistance.

Minimum professional requirement. Identify the accountable professional for each work product before it is relied upon; accept accountability explicitly when issuing, signing or submitting work; never attribute responsibility for an error to an AI system, a software supplier or an unnamed process.

Required evidence. Authorship and sign-off records identifying the accountable professional; where AI materially assisted, the verification record required by PCI-LAW-F-03.

Decision owner. The credential holder or candidate performing the work. Accountability shall never be assigned to an AI system or its vendor.

Independent review. Required where a work product carries organisational or third-party reliance (for example a funding decision, a certified progress assessment or a published forecast), per the organisation's assurance arrangements and PCI-LAW-F-05.

Escalation trigger. Any situation in which the professional cannot honestly accept accountability for a work product — because it cannot be verified, exceeds their competence, or was produced under improper pressure — triggers the duty in PCI-LAW-F-11.

Prohibited practice. Issuing work "as generated"; disclaiming responsibility on the ground that an AI system, template or colleague produced the content; presenting unverified machine output as one's own professional judgement.

AI application. AI may assist any stage of analysis, drafting, calculation checking, summarisation or option generation, subject to the restrictions in this law set.

AI restriction. AI must not be named, treated or relied upon as the accountable party for any professional work product, decision, approval or certification.

Verification requirement. Before relying on or issuing any work product, the accountable professional must review it for correctness, completeness and fitness for its intended reliance, to the standard they would apply to work produced entirely by hand.

● **EXTERNAL REFERENCE**

ISO/IEC 17024 (ISO/IEC) — international standard for bodies certifying persons; PCI characterises it as the benchmark for competence-based, impartial certification of individuals. OECD AI Principles (OECD) — voluntary intergovernmental framework promoting human-centred, accountable AI; never legislation. NIST AI Risk Management Framework (NIST) — public voluntary framework for governing AI risk. The official publications govern; verify current requirements.

▲ **CAUTION**

Statutory professional-liability, delegation and signing regimes differ by jurisdiction and profession; obtain local legal advice before relying on any delegation or limitation of personal responsibility.

Related PCI laws. PCI-LAW-F-02, PCI-LAW-F-03, PCI-LAW-F-04, PCI-LAW-F-13.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PML-AI KA 1.2 (the project leader's accountability) and PFL-AI KA 1.3 (ethics, fiduciary awareness and responsible AI).

Examination relevance. Assessed through scenario items testing where accountability sits when AI-assisted work is wrong, incomplete or contested. No live examination content is exposed.

Consequences of breach. Within PCI's authority: examination invalidation, certification suspension or revocation, referral to PCI's conduct process, and mandatory remediation conditions on any reinstatement.

§ PCI LAW

PCI-LAW-F-02

Verification of AI Output Before Professional Use

Rule. A credential holder or candidate shall verify every AI-generated or AI-assisted output — including analyses, forecasts, schedules, financial calculations, drafted documents, code and summaries — for accuracy, completeness, relevance and freedom from fabrication before it is used, relied upon, communicated or embedded in any professional work product.

Purpose. To prevent unverified machine output — including plausible fabrications, silent omissions, stale data and miscalculation — from entering professional deliverables on which others rely.

Scope. All AI-assisted work within a PCI certification scope, whatever the tool, vendor, deployment model or apparent quality of the output.

Minimum professional requirement. Check AI output against authoritative sources, independent recalculation or direct inspection proportionate to the reliance placed on it; confirm cited facts, figures, references and quotations actually exist and say what is claimed; correct or discard output that cannot be verified.

Required evidence. A verification record proportionate to the stakes: what was checked, against what, by whom and with what result — for high-reliance outputs, retained with the work product per PCI-LAW-F-12.

Decision owner. The professional who uses or issues the output; verification may be assisted but its adequacy remains that professional's decision.

Independent review. Required before AI-assisted output supports a decision that is irreversible, safety-relevant, financially material or externally reported; the reviewer must be independent of the output's production.

Escalation trigger. Discovery that unverified AI output has already entered a deliverable, decision or external communication; or an AI tool producing systematically unreliable output in continued organisational use.

Prohibited practice. Passing AI output onward unchecked; "verifying" by re-asking the same or another AI system without independent grounding; deleting or bypassing verification steps under time pressure without recording the departure and its justification.

AI application. AI may assist verification itself — cross-checking, reconciliation, anomaly flagging, test generation — provided the final adequacy judgement is human.

AI restriction. AI must not be the sole verifier of AI output, and must not determine that verification is unnecessary.

Verification requirement. Verification depth must scale with reliance: routine internal drafts require professional review; externally relied-upon figures require independent recalculation or source confirmation; certified or contractual statements require documented independent review.

EXTERNAL REFERENCE

NIST AI Risk Management Framework (NIST) — public voluntary framework whose measurement and management functions PCI characterises as the reference discipline for testing and monitoring AI output. Federal Reserve SR 11-7 supervisory guidance on model risk management (US Federal Reserve/OCC) — public supervisory guidance establishing model-validation discipline; jurisdiction-specific, cited as guidance only. EU Artificial Intelligence Act (European Union) — legislation in its jurisdiction imposing human-oversight expectations for certain AI systems; an external requirement where applicable; verify current requirements. The official publications govern.

⚠ CAUTION

Sector regulators (financial services, public procurement, safety) may impose specific validation, audit or human-oversight obligations; obtain local regulatory advice where AI output feeds regulated activity.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-03, PCI-LAW-F-06, PCI-LAW-F-07.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI (especially KA 14.3, AI use cases, prompting and verification); PFL-AI Domain 16 — Data, automation and responsible AI in finance (especially KA 16.3, explainability, validation, bias and model risk); also PML-AI KA 9.4 (data quality and AI-output quality) and PFL-AI KA 6.4 (model checks, model audit and AI-assisted modelling controls).

Examination relevance. Assessed through scenarios containing plausible but flawed AI output that the candidate must detect, verify or reject. No live examination content is exposed.

Consequences of breach. Within PCI's authority: adverse conduct finding, certification conditions requiring supervised practice or retraining, suspension or revocation where reliance harm resulted, and examination invalidation where breached in assessment.

§ PCI LAW

PCI-LAW-F-03

Human Decision Authority

Rule. Professional decisions, approvals and certifications within a PCI certification scope shall be made only by an accountable human professional; an AI system must not decide, approve, certify, sign, release or authorise any professional work product, commitment, payment, baseline change or result, and automated recommendations shall take effect only upon explicit human adoption.

Purpose. To keep decision authority — and therefore accountability — with people, and to prevent automation from converting a recommendation pipeline into an unexamined decision pipeline.

Scope. All decisions, approvals, gate passages, releases, certifications and authorisations in PCI-certified work, including those embedded in automated workflows, scripts and agentic tools.

Minimum professional requirement. Identify every point in a workflow where AI output could take effect without human adoption and place an explicit human decision there; record who adopted each material recommendation and on what basis; keep the authority to reject, amend or defer genuinely exercisable, not a rubber stamp.

Required evidence. Decision records naming the human decision-maker, the inputs considered (including AI inputs), the decision and its date; workflow documentation showing the human decision points in any automated chain.

Decision owner. The professional holding the relevant decision right under the applicable governance arrangement (for example sponsor, budget holder, certifying professional); never the AI system.

Independent review. Required for the design of any automated workflow in which AI output feeds directly toward commitments, payments or external statements, before the workflow enters use.

Escalation trigger. Discovery that an AI-driven step has taken effect without human adoption; or organisational pressure to remove human decision points for speed.

Prohibited practice. Configuring systems to auto-approve, auto-certify, auto-release or auto-pay on AI output; ratifying AI decisions after the fact as a formality; presenting a human sign-off that did not involve actual review.

AI application. AI may rank options, draft recommendations, pre-populate approval packages, flag exceptions and route work to the right decision-maker.

AI restriction. AI must not decide, approve or certify anything; it must not close the loop from recommendation to effect without an accountable human act in between.

Verification requirement. Periodically test automated workflows to confirm human decision points operate in practice — that rejection is possible, exercised where warranted, and recorded.

● EXTERNAL REFERENCE

OECD AI Principles (OECD) — voluntary framework emphasising human-centred values and accountability; never legislation. EU Artificial Intelligence Act (European Union) — legislation in its jurisdiction with human-oversight requirements for certain systems; an external requirement where applicable; verify current requirements. NIST AI Risk Management Framework (NIST) — public voluntary framework addressing human-AI configuration and oversight. The official publications govern.

⚠ CAUTION

Some jurisdictions and sectors regulate automated decision-making about individuals (including rights to human review); obtain local legal advice before deploying any automated decision flow affecting people.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-02, PCI-LAW-F-05, PCI-LAW-F-11.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI (especially KA 14.4, explainability, bias and human accountability); PFL-AI Domain 16 — Data, automation and responsible AI in finance (especially KA 16.4, privacy, cybersecurity, human approval and AI governance); also PML-AI KA 3.2 (decision authorities and thresholds).

Examination relevance. Assessed through scenarios asking where human decision points must sit in automated project-controls, delivery and finance workflows. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, certification suspension or revocation for permitting AI to exercise decision authority, and mandatory governance remediation as a condition of reinstatement.

§ PCI LAW

PCI-LAW-F-04

Disclosure of Material AI Assistance

Rule. A credential holder or candidate shall not conceal material AI assistance: where AI materially contributed to a professional work product, analysis or communication, that assistance shall be disclosed to those entitled to rely on the work whenever they could reasonably regard it as relevant to their reliance, and shall never be denied when asked.

Purpose. To preserve informed reliance and trust: those who act on professional work are entitled to an honest account of how it was produced.

Scope. All professional work products and communications within a PCI certification scope, including reports, forecasts, models, certifications, correspondence and examination submissions where PCI rules require declaration.

Minimum professional requirement. Know and be able to state where AI materially assisted; answer truthfully any question about AI involvement; follow any stricter disclosure rule of the client, employer, contract or PCI examination conditions; record material AI assistance in the work product's production record.

Required evidence. Production records or work-product notes identifying material AI assistance and the verification applied to it (per PCI-LAW-F-02); disclosure statements where made.

Decision owner. The accountable professional issuing the work, applying the "reasonably relevant to reliance" test honestly and, in doubt, disclosing.

Independent review. Required where an organisation adopts a standing policy on AI-assistance disclosure, at policy level; individual disclosures do not require independent review.

Escalation trigger. A request or instruction to conceal or deny AI involvement in professional work; discovery that reliance was obtained through a false account of how work was produced.

Prohibited practice. Denying AI assistance that occurred; presenting AI-generated material as wholly human-authored where authorship is relevant to reliance (including in PCI examinations and CPD submissions); contractually promising unassisted work while using AI.

AI application. AI may help maintain production records and draft disclosure statements.

AI restriction. AI must not determine whether disclosure is required; that judgement is the professional's.

Verification requirement. Before issue, confirm the work product's account of its own production — explicit or implied — is true.

● EXTERNAL REFERENCE

OECD AI Principles (OECD) — voluntary framework whose transparency principle PCI characterises as the reference for honest disclosure of AI involvement; never legislation. NIST AI Risk Management Framework (NIST) — public voluntary framework supporting documentation and transparency practices. EU Artificial Intelligence Act (European Union) — legislation in its jurisdiction including transparency obligations for certain AI interactions; an external requirement where applicable; verify current requirements. The official publications govern.

⚠ CAUTION

Consumer-protection, advertising, procurement and professional-conduct rules in some jurisdictions impose specific disclosure duties; obtain local advice where AI disclosure could affect contractual or regulatory position.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-02, PCI-LAW-F-07, PCI-LAW-F-14.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI (especially KA 14.3); PFL-AI Domain 16 — Data, automation and responsible AI in finance (especially KA 16.2 and KA 16.4); also PML-AI KA 11.4 (misinformation and AI-generated communication risks).

Examination relevance. Assessed through scenarios on when AI assistance must be disclosed and through the candidate's own declaration obligations in PCI assessments. No live examination content is exposed.

Consequences of breach. Within PCI's authority: examination invalidation for false declarations, conduct findings for concealment, and certification suspension or revocation for obtaining reliance by deception about work production.

Part II — Evidence, information and honest reporting

§ PCI LAW

PCI-LAW-F-05

Evidence and the Audit Trail

Rule. Every material professional judgement, decision, approval and reported figure within a PCI certification scope shall be supported by a contemporaneous, attributable and retrievable record sufficient for a competent independent reviewer to reconstruct what was decided, by whom, when, on what evidence and by what method.

Purpose. To make professional work auditable: conclusions that cannot be traced to evidence and method cannot be verified, defended or learned from.

Scope. All material judgements, decisions, approvals, baselines, changes, forecasts and reported results in PCI-certified work, including those produced with AI assistance.

Minimum professional requirement. Record decisions and their basis at the time they are made; keep source data, key assumptions, methods and versions with the work product; ensure records are attributable to named individuals and protected from silent alteration.

Required evidence. Decision logs, approval records, basis-of-estimate and basis-of-forecast documentation, change records, model version history, and the AI verification records required by PCI-LAW-F-02.

Decision owner. The accountable professional for each work product; for organisational systems of record, the role designated by the governance arrangement.

Independent review. Required at defined assurance points (gates, audits, financial close, certification events) per the applicable governance arrangement; the audit trail must be reviewable without the author present.

Escalation trigger. Discovery of missing, backdated or altered records supporting a material decision; a system of record that silently overwrites decision history.

Prohibited practice. Reconstructing records after the fact and presenting them as contemporaneous; deleting or overwriting the evidential basis of a decision; maintaining a "clean" official record that differs from the real basis of decision.

AI application. AI may assist in capturing, structuring, indexing and retrieving records, and in flagging gaps in an audit trail.

AI restriction. AI must not create, amend or dispose of evidential records without an accountable human instruction, and must not fabricate contemporaneity.

Verification requirement. Periodically test that a sampled decision can actually be reconstructed from the record alone; treat failure as a defect in the control environment, not a formality.

• EXTERNAL REFERENCE

AACE International Total Cost Management framework (AACE International) — professional guidance whose documentation discipline PCI characterises as the reference for auditable cost-engineering records. PMBOK Guide and PMI standards (Project Management Institute) — professional guidance on decision, change and issue records. FIDIC conditions of contract (FIDIC) — contract framework in which contemporaneous records underpin claims and determinations; characterised generically, no

clause numbers cited. ISO 21500-family project-management standards (ISO) — international standards contextualising governance records. The official publications govern.

⚠ **CAUTION**

Evidential and disclosure rules for records in disputes and audits are jurisdiction-specific; obtain local legal advice before destroying, redacting or restructuring records connected to a live or foreseeable dispute.

Related PCI laws. PCI-LAW-F-03, PCI-LAW-F-06, PCI-LAW-F-12.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PML-AI KA 3.3 (auditability and the decision record), PML-AI KA 4.4 (the change board and the decision log) and PFL-AI KA 13.2 (model audit).

Examination relevance. Assessed through scenarios on what must be recorded, when, and what an adequate audit trail contains. No live examination content is exposed.

Consequences of breach. Within PCI's authority: adverse conduct finding, quality-review referral, certification conditions requiring records-management remediation, and suspension or revocation for falsified records.

§ PCI LAW

PCI-LAW-F-06

Data Lineage and Integrity

Rule. A credential holder or candidate shall know and be able to state the provenance of the data on which professional analysis, reporting or AI processing relies — its source, date, owner, transformations and known limitations — and shall not base professional conclusions on data whose lineage cannot be established or whose integrity is compromised, without stating that limitation wherever the conclusion is used.

Purpose. To prevent conclusions built on untraceable, stale, manipulated or silently transformed data, and to keep data quality visible wherever data-driven and AI-assisted outputs travel.

Scope. All data used in PCI-certified work: project actuals, schedules, estimates, financial statements and models, risk registers, AI training/reference/prompt data, and third-party data feeds.

Minimum professional requirement. Record source, extraction date and material transformations for datasets underpinning material conclusions; protect data against unauthorised alteration; reconcile derived figures to their sources; carry known data limitations forward into every use of the conclusion.

Required evidence. Data-lineage records (source, date, owner, transformation steps), reconciliations, data-quality checks, and access/change controls on systems of record.

Decision owner. The accountable professional for the analysis; for shared datasets, the designated data owner under the organisation's data-governance arrangement.

Independent review. Required for datasets feeding externally reported figures, financial models under audit, or AI systems in continued organisational use.

Escalation trigger. Discovery of unexplained changes in a system of record; material conclusions found to rest on data of unknown origin; an AI pipeline consuming data outside its authorised lineage.

Prohibited practice. Massaging, trimming or selectively excluding data to reach a preferred result; presenting transformed data as raw; feeding confidential or unauthorised data into AI tools contrary to PCI-LAW-F-09; ignoring known corruption because the output "looks right".

AI application. AI may assist with lineage capture, anomaly detection, reconciliation and data-quality profiling.

AI restriction. AI must not certify data as fit for purpose, and AI-generated (synthetic or imputed) data must never be presented as observed data.

Verification requirement. Before material reliance, trace a sample of figures end-to-end from source to output; confirm transformations are documented and reproducible; label estimated, imputed or synthetic values as such.

EXTERNAL REFERENCE

ISO 8000 data-quality standards (ISO) — international standards addressing data-quality management; cited by name; PCI characterises them as the reference discipline for data quality. NIST AI Risk Management Framework (NIST) — public voluntary framework addressing data provenance and integrity in AI systems. AACE International Total Cost Management framework (AACE International) — professional guidance on basis documentation for estimates and forecasts. The official publications govern.

CAUTION

Data-localisation, privacy and financial record-keeping laws constrain where data may be stored and processed; obtain local legal advice before moving project or personal data across borders or into third-party AI services.

Related PCI laws. PCI-LAW-F-02, PCI-LAW-F-05, PCI-LAW-F-07, PCI-LAW-F-09.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI (especially KA 14.1, data governance and common data environments); PFL-AI Domain 16 — Data, automation and responsible AI in finance (especially KA 16.1, financial-data architecture and anomaly detection); also PML-AI KA 9.4 (data quality and AI-output quality).

Examination relevance. Assessed through scenarios involving flawed, stale or manipulated data feeding analyses and AI tools. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, quality-review referral, certification conditions on data-governance practice, and suspension or revocation for deliberate data manipulation.

§ PCI LAW

PCI-LAW-F-07

Honesty in Reporting and Forecasting

Rule. All professional reporting and forecasting within a PCI certification scope — including progress, performance, cost, schedule, risk and financial reporting — shall present an honest, complete and unbiased account of the best available evidence; a credential holder or candidate shall not misstate, omit, smooth, defer or slant reported information to serve a preferred narrative, and shall state material assumptions, uncertainty and limitations alongside every forecast.

Purpose. To protect the decision-makers, lenders, sponsors and publics who act on professional reports, and to preserve the meaning of the numbers on which the entire discipline of project controls, delivery and finance rests.

Scope. All internal and external reporting and forecasting in PCI-certified work, however produced, including dashboards and AI-generated report content.

Minimum professional requirement. Report unfavourable information as promptly and prominently as favourable information; base forecasts on documented method and evidence, not on targets; disclose

material assumptions, ranges and confidence honestly; correct known errors in issued reports without delay.

Required evidence. Basis-of-forecast documentation, reconciliation of reported figures to systems of record, assumption logs, and issue-and-correction records for reports.

Decision owner. The accountable professional issuing the report or forecast; a reviewer or superior who directs a misstatement becomes accountable alongside, not instead of, the issuer.

Independent review. Required for externally reported performance and financial figures and for forecasts supporting investment, funding or continuation decisions.

Escalation trigger. Pressure, instruction or incentive to misreport; discovery that an issued report or forecast was materially wrong or biased; a persistent gap between reported and actual performance.

Prohibited practice. Hiding bad news in detail or delay; presenting a target as a forecast; cherry-picking scenarios; smoothing variances across periods; using AI-generated fluency to obscure rather than convey the substance; certifying progress that has not been achieved.

AI application. AI may assist in drafting reports, generating scenarios, detecting anomalies and stress-testing forecasts.

AI restriction. AI must not decide what is disclosed or withheld, must not approve a report or forecast for issue, and AI-generated narrative must not be issued without human verification of every material statement.

Verification requirement. Before issue, verify reported figures to source, test forecasts for method and bias, and confirm the narrative fairly represents the underlying data — including what it leaves out.

● EXTERNAL REFERENCE

IFRS Accounting Standards (IFRS Foundation) — authoritative accounting standards, mandatory only for entities that apply them in a jurisdiction that has adopted them, whose fair-presentation discipline PCI characterises as the benchmark for honest financial reporting. IAS 1 Presentation of Financial Statements (IFRS Foundation) — authoritative accounting standard on presentation; **note that IFRS 18 Presentation and Disclosure in Financial Statements replaces IAS 1 for annual reporting periods beginning on or after 1 January 2027 (earlier application permitted), and that IAS 8 is retitled Basis of Preparation of Financial Statements from the same date — verify which instrument applies to the reporting period in question.** IFRS 15 Revenue from Contracts with Customers (IFRS Foundation) — authoritative accounting standard governing revenue recognition on contracts for entities applying IFRS Accounting Standards. AACE International Total Cost Management framework (AACE International) — professional guidance on forecasting and performance-measurement practice. PMBOK Guide and PMI standards (Project Management Institute) — professional guidance on performance reporting. The official publications govern; verify current requirements.

▲ CAUTION

Securities, public-procurement and financial-reporting laws attach specific liability to misstatements in some jurisdictions; obtain local legal and accounting advice for externally published or regulated reporting.

Related PCI laws. PCI-LAW-F-02, PCI-LAW-F-05, PCI-LAW-F-06, PCI-LAW-F-11, PCI-LAW-F-13.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance (especially KA 16.1, forecast automation); also PCL-AI BoK Domains 4 (Performance Management, Variance Analysis & Reporting) and 6 (Earned Value Management & Forecasting), PML-AI KA 2.4 (kill criteria and honest gates) and KA 11.2 (executive communication and reporting).

Examination relevance. Assessed through scenario items on reporting under pressure, forecast bias and the honest presentation of uncertainty. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, certification suspension or revocation for deliberate misreporting, examination invalidation where breached in assessment, and mandatory ethics remediation on any reinstatement.

Part III — Professional conduct

§ PCI LAW

PCI-LAW-F-08

Competence Boundaries and Referral

Rule. A credential holder or candidate shall undertake only work they are competent to perform, shall state the limits of their competence honestly, and shall refer matters requiring legal, tax, accounting, actuarial, engineering, regulatory or other specialist judgement beyond that competence to appropriately qualified advisers; access to AI tools does not extend professional competence.

Purpose. To protect those who rely on professional work from confident incompetence — including the modern form in which AI fluency masks the absence of underlying expertise.

Scope. All acceptance, performance and delegation of work within a PCI certification scope, and all advice given in a professional capacity.

Minimum professional requirement. Assess honestly, before accepting work, whether competence, capacity and information are sufficient; disclose material limitations to the client or employer; obtain supervision, training or specialist referral where needed; maintain competence through continuing professional development.

Required evidence. Engagement or role definitions reflecting actual competence; referral records to qualified advisers; CPD records maintained under PCI's certification requirements.

Decision owner. The professional accepting the work; for team assignments, the professional allocating work remains accountable for matching work to competence.

Independent review. Required where work proceeds in an area at the edge of the professional's demonstrated competence with no qualified specialist involved; the review examines whether the boundary is being respected.

Escalation trigger. Discovering mid-engagement that the work requires competence not present in the team; pressure to opine on legal, tax or regulatory questions without qualified advice.

Prohibited practice. Holding oneself out as qualified in a specialism one does not hold; issuing legal, tax or accounting conclusions on the strength of AI output; accepting work knowing it cannot be competently performed; suppressing a competence limitation to win or keep an engagement.

AI application. AI may support research, orientation in an unfamiliar area, and preparation of questions for qualified advisers.

AI restriction. AI must not substitute for a qualified adviser where specialist professional judgement is required, and AI output must not be presented as such advice.

Verification requirement. Where AI assists work near a competence boundary, verification must be performed or reviewed by someone with demonstrated competence in that subject matter, not merely by the AI user.

● EXTERNAL REFERENCE

ISO/IEC 17024 (ISO/IEC) — international standard whose competence-based certification discipline PCI characterises as the basis for defining and evidencing individual competence. PMI Code of Ethics

and Professional Conduct (Project Management Institute) — professional guidance addressing honest representation of qualifications and competence. The official publications govern.

△ **CAUTION**

Reserved-activity rules (legal advice, audit, tax practice, engineering sign-off) differ by jurisdiction; obtain local advice on what only licensed professionals may do before offering adjacent services.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-11, PCI-LAW-F-13, PCI-LAW-F-14.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PFL-AI KA 1.3 (fiduciary and professional obligations), PFL-AI Domain 12's standing referral of jurisdiction-specific contract matters to qualified counsel, and PML-AI KA 1.2 (professional standards of care).

Examination relevance. Assessed through scenarios testing recognition of competence boundaries and the duty to refer. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, certification conditions (supervised practice, additional training), suspension or revocation for practising beyond competence, and CPD-compliance enforcement.

§ PCI LAW

PCI-LAW-F-09

Confidentiality and Information Protection

Rule. A credential holder or candidate shall protect confidential information obtained in professional work — including client, employer, counterparty, personal and commercially sensitive project information — against unauthorised access, use or disclosure, shall use it only for the purpose for which it was entrusted, and shall not place such information into any AI tool, service or dataset without authorisation and appropriate safeguards.

Purpose. To preserve the trust on which access to professional information depends, and to close the modern leak path in which confidential material is pasted into external AI services without thought for where it goes.

Scope. All confidential information handled in PCI-certified work, in any medium, during and after the engagement or employment in which it was obtained.

Minimum professional requirement. Follow the owner's classification and handling rules; apply access controls and secure storage; confirm an AI tool's data-handling terms and the information owner's authorisation before submitting confidential material to it; report suspected breaches to the information owner without delay.

Required evidence. Confidentiality undertakings, access-control and handling records, records of authorisation for AI-tool use with confidential data, and breach reports where applicable.

Decision owner. The professional handling the information, within the information owner's rules; authorisation for new uses rests with the information owner.

Independent review. Required before adopting any AI tool or external service for processing confidential information at organisational scale.

Escalation trigger. Suspected or actual unauthorised disclosure; discovery of confidential data in an unapproved tool or location; a request to use entrusted information for an unauthorised purpose.

Prohibited practice. Disclosing or trading on confidential information; entering client, employer or personal data into unapproved AI services; retaining confidential material after authorisation ends; using information entrusted for one engagement to advantage another.

AI application. AI may be used with confidential information only within approved tools, under the information owner's authorisation and the applicable safeguards.

AI restriction. AI tools must not be treated as confidential-by-default; no confidential information may be used to train, fine-tune or ground external models without the owner's explicit authorisation.

Verification requirement. Before using an AI tool with confidential information, verify its data-handling, retention and training terms against the owner's requirements; periodically confirm approved-tool lists are current.

EXTERNAL REFERENCE

ISO/IEC 27001 (ISO/IEC) — international standard for information-security management systems; PCI characterises it as the reference discipline for protecting information assets. NIST AI Risk Management Framework (NIST) — public voluntary framework addressing privacy and security risks in AI use. The official publications govern.

CAUTION

Data-protection legislation (for example the EU General Data Protection Regulation in its jurisdiction), banking-secrecy and state-secrecy regimes impose specific and sometimes criminal obligations; obtain local legal advice on personal-data processing and cross-border transfers, and verify current requirements.

Related PCI laws. PCI-LAW-F-05, PCI-LAW-F-06, PCI-LAW-F-10, PCI-LAW-F-12.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI (especially KA 14.4, cybersecurity and privacy); PFL-AI Domain 16 — Data, automation and responsible AI in finance (especially KA 16.4, privacy and cybersecurity).

Examination relevance. Assessed through scenarios on handling confidential information, including AI-tool use with entrusted data. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, certification suspension or revocation for breach of confidence, and mandatory information-handling remediation on any reinstatement.

§ PCI LAW

PCI-LAW-F-10

Conflict-of-Interest Disclosure

Rule. A credential holder or candidate shall identify actual, potential and perceived conflicts between their personal, financial or organisational interests and their professional duties, shall disclose them promptly and in writing to those entitled to know, and shall not act in a conflicted matter unless the affected parties have been informed and appropriate safeguards — or withdrawal — are in place.

Purpose. To protect the independence of professional judgement and the fairness owed to clients, employers, counterparties and the public, on which the credibility of certified professionals rests.

Scope. All engagements, appointments, approvals, procurements, evaluations and certifications within a PCI certification scope, including interests held through family, associates or investments and interests in AI tools or vendors being selected or assessed.

Minimum professional requirement. Maintain awareness of one's interests against current duties; disclose conflicts on discovery, before acting where possible; record the disclosure and the agreed safeguard (recusal, independent review, information barriers, or withdrawal); refresh disclosures when circumstances change.

Required evidence. Written conflict disclosures, conflict registers where the organisation keeps them, and records of safeguards or recusals applied.

Decision owner. The conflicted professional owns the duty to disclose; the decision on safeguards rests with the person or body to whom the duty is owed, not with the conflicted party.

Independent review. Required whenever a conflicted professional remains involved in the matter after disclosure; the review confirms the safeguard operates.

Escalation trigger. Discovery of an undisclosed conflict affecting a decision already taken; a conflicted party resisting refusal; a conflict involving the most senior available decision-maker.

Prohibited practice. Concealing an interest; self-approving one's own work or procurement; evaluating a tool, supplier or claim in which one holds an interest without disclosure; structuring interests to evade disclosure.

AI application. AI may assist in screening engagements against declared-interest registers and flagging potential conflicts for human assessment.

AI restriction. AI must not adjudicate whether a conflict exists or is acceptable; that judgement belongs to the humans to whom the duty is owed.

Verification requirement. Before high-stakes decisions (awards, certifications, releases), confirm current conflict declarations exist for the decision participants.

EXTERNAL REFERENCE

ISO/IEC 17024 (ISO/IEC) — international standard whose impartiality requirements for certification activity PCI characterises as the reference for managing conflicts in assessment and certification roles. PMI Code of Ethics and Professional Conduct (Project Management Institute) — professional guidance addressing fairness and conflict-of-interest disclosure. The official publications govern.

CAUTION

Public-procurement, anti-corruption and fiduciary laws impose specific conflict and gift rules in many jurisdictions, particularly for public officials; obtain local legal advice in public-sector and regulated-finance contexts.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-09, PCI-LAW-F-11, PCI-LAW-F-13.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PFL-AI KA 1.3 (conflicts and independence) and PML-AI KA 12.4 (ethical leadership).

Examination relevance. Assessed through scenarios requiring recognition, disclosure and management of conflicts. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, invalidation of PCI assessment outcomes tainted by an assessor's undisclosed conflict, and certification suspension or revocation for concealment.

§ PCI LAW

PCI-LAW-F-11

Duty to Escalate

Rule. A credential holder or candidate who becomes aware of a material threat to safety, integrity, funds, data, delivery or honest reporting within their professional work — including unverified AI output in reliance, misreporting, records tampering or practice beyond competence — shall escalate it promptly

through the applicable governance route, shall persist to the next level if the response is inadequate, and shall not participate in suppressing it.

Purpose. To ensure that problems travel upward faster than they compound, and that no professional treats silence as a neutral option.

Scope. All PCI-certified work; the duty applies whether the professional caused, discovered or was merely informed of the matter, and survives instructions to stay silent.

Minimum professional requirement. Know the escalation route for one's role before it is needed; report the matter to the accountable level with evidence and without editorialising delay; record the escalation and response; where the route itself is compromised or the response inadequate, escalate to the next independent level available.

Required evidence. Escalation records (what was raised, to whom, when, response), and the underlying evidence preserved per PCI-LAW-F-05.

Decision owner. The professional aware of the matter owns the duty to escalate; the decision on remedy belongs to the accountable governance level receiving it.

Independent review. Required where an escalation is closed without remedy and the escalating professional maintains the concern; an independent function (assurance, audit, or PCI's conduct process where PCI rules are engaged) reviews the closure.

Escalation trigger. This law is itself the trigger discipline: any material threat listed in the Rule, and additionally any attempt to penalise or silence a good-faith escalation.

Prohibited practice. Sitting on known material problems; retaliating against, or assisting retaliation against, a good-faith escalator; "escalating" into a channel known to be captive; downgrading a threat to avoid governance attention.

AI application. AI may help detect escalation-worthy conditions (anomalies, threshold breaches, integrity flags) and draft escalation summaries.

AI restriction. AI must not decide that a matter need not be escalated, and automated suppression or filtering of alerts must never be configured to serve concealment.

Verification requirement. Periodically verify that escalation routes function — that a raised item reaches the accountable level and produces a recorded response.

● EXTERNAL REFERENCE

ISO 31000 (ISO) — international standard whose risk communication and monitoring discipline PCI characterises as the frame for timely escalation. PMBOK Guide and PMI standards (Project Management Institute) — professional guidance on governance and issue escalation. FIDIC conditions of contract (FIDIC) — contract framework whose formal notice mechanisms PCI characterises as the contractual analogue of escalation discipline; characterised generically, no clause numbers cited. The official publications govern.

▲ CAUTION

Whistleblower-protection and mandatory-reporting laws differ sharply by jurisdiction (and may require external reporting for some matters); obtain local legal advice before external disclosure of organisational information.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-05, PCI-LAW-F-07, PCI-LAW-F-13.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PML-AI KA 3.3 (assurance, gates and escalation design).

Examination relevance. Assessed through scenarios testing when and how to escalate, including against pressure to stay silent. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding for failure to escalate or for retaliation, certification suspension or revocation in serious cases, and protective handling of good-faith escalations within PCI's own processes.

§ PCI LAW

PCI-LAW-F-12

Record Retention

Rule. A credential holder or candidate shall retain the records that evidence their professional work — including decision records, verification records for AI-assisted work, data-lineage records and issued reports — for the period required by the applicable law, contract, employer policy or PCI certification rule, whichever is longest, shall dispose of them only through an authorised process, and shall never destroy or alter records to frustrate review, audit or dispute.

Purpose. To keep the evidential basis of professional work available for as long as reliance, accountability or review may reasonably reach back to it.

Scope. All records generated or received in PCI-certified work, in any medium, including model versions, prompt/verification records for material AI-assisted outputs, and records held in personal tools that form part of the professional record.

Minimum professional requirement. Know the retention rules that apply to one's records; keep records in the organisation's system of record rather than in private silos; apply authorised disposal only after the retention period ends and no hold applies; suspend disposal immediately when a dispute, audit or investigation is reasonably foreseeable.

Required evidence. Retention schedules applied, disposal authorisations and logs, legal-hold notices honoured, and the continued retrievability of in-period records.

Decision owner. The professional for records they control; the organisation's designated records owner for shared systems; disposal decisions follow the authorised schedule, not individual convenience.

Independent review. Required for the design of retention schedules and for any early or bulk disposal outside the standing schedule.

Escalation trigger. Discovery of unauthorised destruction or alteration; instruction to delete records connected to a foreseeable dispute or review; retention systems failing such that in-period records become irretrievable.

Prohibited practice. Destroying, altering or "losing" records to defeat scrutiny; running professional work through ephemeral channels to avoid creating records; disposing of AI verification records while the outputs they support remain in reliance.

AI application. AI may assist with classification, retention-schedule application, retrieval and disposal-log maintenance.

AI restriction. AI must not autonomously dispose of records; every disposal requires an authorised human decision under the applicable schedule.

Verification requirement. Periodically test that sampled in-period records can be retrieved intact, and that disposal logs reconcile with the authorised schedule.

● EXTERNAL REFERENCE

ISO 15489 records-management standards (ISO) — international standards for records management; PCI characterises them as the reference discipline for creating, controlling and disposing of records. ISO/IEC 27001 (ISO/IEC) — international standard for information-security management, relevant to protecting retained records. The official publications govern.

⚠ CAUTION

Statutory retention periods (tax, employment, financial, health and safety) and litigation-hold obligations are jurisdiction-specific and sometimes conflicting across borders; obtain local legal advice when setting or shortening retention periods.

Related PCI laws. PCI-LAW-F-05, PCI-LAW-F-06, PCI-LAW-F-09.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PML-AI KA 16.4 (responsible archive and model/data retention).

Examination relevance. Assessed through scenarios on what must be retained, for how long, and what may never be destroyed. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, adverse inference in PCI quality and conduct processes where records were improperly destroyed, and certification suspension or revocation for destruction intended to defeat review.

§ PCI LAW**PCI-LAW-F-13****Ethical Conduct Toward Candidates, Employers and the Public**

Rule. A credential holder or candidate shall act with honesty, fairness and respect toward candidates, colleagues, employers, clients, counterparties and the public; shall not deceive, exploit, intimidate, discriminate unlawfully or knowingly cause unjustified harm in their professional conduct; and shall not assist, direct or knowingly benefit from another person's breach of these laws.

Purpose. To state the general standard of professional conduct that underlies every specific law in this set, and to extend the professional's duty beyond the paying client to everyone their work affects.

Scope. All professional conduct within a PCI certification scope, including conduct in PCI examinations and CPD, supervision and mentoring of others, procurement and counterparty dealings, public statements made in a professional capacity, and the deployment of AI systems whose outputs affect people.

Minimum professional requirement. Deal honestly in professional representations; treat candidates and subordinates fairly, including in assessment, credit for work and references; give the public's safety and legitimate interests due weight in professional decisions; refuse to participate in another's breach and escalate it per PCI-LAW-F-11.

Required evidence. Conduct is evidenced through the ordinary records of the work: communications and representations made, assessment and supervision records, procurement dealings, and complaint and escalation records where conduct is challenged.

Decision owner. Each professional owns their own conduct; a supervisor who directs unethical conduct is accountable alongside those who execute it.

Independent review. Required where a professional exercises power over others' outcomes (assessment, references, panel evaluation) and a fairness challenge is raised; PCI's conduct process provides the independent forum where PCI rules are engaged.

Escalation trigger. Witnessing or being directed toward deception, exploitation, discrimination or harm in professional work; becoming aware that one's own AI deployment is treating people unfairly.

Prohibited practice. Deceiving any party in professional dealings; taking credit for others' work; abusing supervisory or assessment power; deploying AI in ways known to treat individuals unfairly or opaquely where fairness is owed; assisting another's breach of these laws.

AI application. AI may support fair-treatment monitoring, accessibility and clear communication with affected parties.

AI restriction. AI must not be used to manipulate, deceive or unfairly profile candidates, counterparties or the public; adverse decisions about individuals must not rest on unexplained AI output.

Verification requirement. Where AI outputs affect decisions about people, verify them for accuracy and fairness before use, and provide a human review route for those affected.

● EXTERNAL REFERENCE

PMI Code of Ethics and Professional Conduct (Project Management Institute) — professional guidance articulating honesty, responsibility, respect and fairness for delivery professionals. OECD AI Principles (OECD) — voluntary framework on human-centred AI; never legislation. Equator Principles (Equator Principles Association) and IFC Performance Standards (IFC) — voluntary environmental and social risk-management frameworks relevant to finance professionals' duties to affected communities; never described as legislation. The official publications govern.

▲ CAUTION

Anti-discrimination, employment, consumer-protection and human-rights law vary by jurisdiction and may impose stricter duties; obtain local legal advice for employment and assessment practices and for AI systems making or supporting decisions about individuals.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-07, PCI-LAW-F-10, PCI-LAW-F-11, PCI-LAW-F-14.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PML-AI KA 1.2 (obligations to sponsor, team, users and public) and KA 11.4 (public and community stakeholders), and PFL-AI KA 1.1 (stakeholder objectives including government, operator and community).

Examination relevance. Assessed through conduct scenarios spanning candidates, employers, counterparties and the public. No live examination content is exposed.

Consequences of breach. Within PCI's authority: conduct finding, examination invalidation for misconduct in assessment, certification suspension or revocation, and permanent exclusion from PCI credentials in the gravest cases.

§ PCI LAW

PCI-LAW-F-14

No Misrepresentation of PCI Credentials or Accreditation Status

Rule. A person shall claim a PCI credential, candidate status, examination result or PCI's own accreditation or recognition status only as it actually stands; a credential holder or candidate shall not overstate the scope, level or currency of any PCI credential, shall not imply PCI endorsement of themselves, their employer, their products or their AI tools, and shall represent lapsed, suspended or revoked status accurately without delay.

Purpose. To protect the meaning of PCI credentials for everyone who relies on them — employers, clients, lenders and the public — and to keep claims about PCI's own status honest.

Scope. All representations of PCI credentials or status in any medium: titles, post-nominals, CVs, proposals, professional profiles, marketing, product claims, AI-generated biographies and statements made on the holder's behalf which the holder permits or fails to correct.

Minimum professional requirement. Use credential titles and post-nominals exactly as PCI awards them; state candidate status as candidacy, never as certification; update all professional representations promptly when status changes; correct third-party misstatements of one's PCI status once known; describe PCI's accreditation and recognition status only in terms PCI has published.

Required evidence. The PCI credential register entry is the authoritative record of status; holders retain their award and status correspondence and evidence of corrections made.

Decision owner. The individual making or permitting the representation; PCI Global is the sole authority on what a credential or PCI's accreditation status actually is.

Independent review. None in the ordinary case — representations are checked against the PCI credential register, which is the review mechanism; organisational marketing that references PCI at scale should be reviewed against PCI's published usage terms before release.

Escalation trigger. Discovery of a false or inflated claim of PCI status by oneself, a colleague, an employer or a product; discovery that AI-generated material (including auto-drafted profiles) misstates one's credentials.

Prohibited practice. Claiming a credential not held, lapsed or revoked; presenting candidacy or partial completion as certification; implying PCI accreditation, endorsement or partnership that does not exist; permitting an employer or tool vendor to trade on a fabricated PCI association; using another person's credential identity.

AI application. AI may draft biographies, proposals and profiles that mention PCI credentials, subject to verification before publication.

AI restriction. AI must not be relied upon to state credential or accreditation status; every AI-drafted claim about PCI status must be verified against the actual status before it is published.

Verification requirement. Before publication, verify every statement of PCI credential or accreditation status against the PCI credential register or PCI's published statements; re-verify when status could have changed.

● EXTERNAL REFERENCE

ISO/IEC 17024 (ISO/IEC) — international standard for bodies certifying persons, which PCI characterises as addressing, among other matters, the conditions under which certified persons may use certificates and related claims. The official publication governs. No further external instrument is cited because the authoritative source for PCI status is PCI's own credential register.

⚠ CAUTION

False claims of qualification may engage advertising, consumer-protection, fraud or professional-title law in some jurisdictions; obtain local legal advice where credential claims form part of regulated marketing or tendering.

Related PCI laws. PCI-LAW-F-01, PCI-LAW-F-04, PCI-LAW-F-08, PCI-LAW-F-13.

Related book content. PCL-AI BoK Domain 13 — AI for Project Controls & PM: Concepts, Tools & Practice; PML-AI KA 1.4 — Ethics and the responsible use of AI and Domain 14 — Digital delivery, data and responsible AI; PFL-AI Domain 16 — Data, automation and responsible AI in finance; also PFL-AI KA 1.3 (ethics and professional obligations).

Examination relevance. Assessed through scenarios on accurate representation of credentials and status, including AI-drafted professional profiles. No live examination content is exposed.

Consequences of breach. Within PCI's authority: refusal or invalidation of examination and certification, suspension or revocation of credentials, correction notices on the PCI credential register, and permanent exclusion for fraudulent credential claims.

Index of Foundational Laws

ID	OFFICIAL TITLE	ANCHOR DOMAIN	RELATED EXTERNAL REFERENCES
PCI-LAW-F-01	Professional Accountability and the Suite Principle	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO/IEC 17024; OECD AI Principles; NIST AI RMF
PCI-LAW-F-02	Verification of AI Output Before Professional Use	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	NIST AI RMF; SR 11-7 (public supervisory guidance); EU AI Act
PCI-LAW-F-03	Human Decision Authority	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	OECD AI Principles; EU AI Act; NIST AI RMF
PCI-LAW-F-04	Disclosure of Material AI Assistance	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	OECD AI Principles; NIST AI RMF; EU AI Act
PCI-LAW-F-05	Evidence and the Audit Trail	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	AACE TCM; PMBOK Guide/PMI standards; FIDIC; ISO 21500-family
PCI-LAW-F-06	Data Lineage and Integrity	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO 8000; NIST AI RMF; AACE TCM
PCI-LAW-F-07	Honesty in Reporting and Forecasting	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	IFRS Accounting Standards; IAS 1 (replaced by IFRS 18 from 1 Jan 2027); IFRS 15; AACE TCM; PMBOK Guide/PMI standards
PCI-LAW-F-08	Competence Boundaries and Referral	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO/IEC 17024; PMI Code of Ethics and Professional Conduct
PCI-LAW-F-09	Confidentiality and Information Protection	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO/IEC 27001; NIST AI RMF
PCI-LAW-F-10	Conflict-of-Interest Disclosure	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO/IEC 17024; PMI Code of Ethics and Professional Conduct
PCI-LAW-F-11	Duty to Escalate	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO 31000; PMBOK Guide/PMI standards; FIDIC
PCI-LAW-F-12	Record Retention	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO 15489; ISO/IEC 27001
PCI-LAW-F-13	Ethical Conduct Toward Candidates, Employers and the Public	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	PMI Code of Ethics; OECD AI Principles; Equator Principles; IFC Performance Standards
PCI-LAW-F-14	No Misrepresentation of PCI Credentials or Accreditation Status	Foundational — suite-wide (PCL-AI D13 · PML-AI KA 1.4/ D14 · PFL-AI D16)	ISO/IEC 17024

PFL-AI Professional Laws — PCI AI Project Finance Leader

Status: Certification Laws for the **PFL-AI** credential (AI Project Finance Leader), drafted under and subordinate to the binding specification in **LAW_SYSTEM.md**. Twenty-four laws, anchored to the sixteen-domain PFL-AI Body of Knowledge (**../pfl-ai/**).

⚠ CAUTION

PCI Professional Laws are professional certification rules and standards of conduct established by PCI Global. They are not legislation, regulatory requirements or substitutes for applicable law, contractual obligations or authoritative professional standards. Where any applicable law, regulation, contract or authoritative professional standard imposes a stricter requirement, that requirement governs.

How to read these laws

✦ PCI PRACTICE GUIDANCE

- **The drafting specification governs.** Definition, hierarchy, normative language, the mandatory field template, external-reference rules, the visual system and stable identifiers are all defined in **LAW_SYSTEM.md**. These laws conform to it; where any doubt arises, that specification prevails.
- **Identifiers are stable.** Each law is cited as **PFL-LAW-DD-NN**, where **DD** is the two-digit Body-of-Knowledge domain of primary anchorage and **NN** a sequence within that domain. Cite laws by ID, never by page number. A law that spans domains anchors to the domain that teaches it and lists the others under Related book content.
- **These laws sit under the Foundational Laws.** **PCI-LAW-F-01** to **PCI-LAW-F-14** (**PCI_FOUNDATIONAL_LAWS.md**) bind every PCI credential holder, including every PFL-AI holder. The laws below add what project finance specifically requires; they never reduce a foundational obligation.
- **Normative language is deliberate.** **must** / **must not** / **shall** / **shall not** state mandatory professional rules; **should** states recommended practice from which departure needs a recorded reason; **may** is discretionary. Text is labelled, every time, as **Mandatory PCI Law**, **Mandatory PCI Rule**, **Recommended PCI Practice**, **External requirement**, **Illustrative example** or **Jurisdictional requirement** — never mixed.
- **External references are characterised, never reproduced.** Real instruments are named and described in PCI's own words; the official publication always governs. No clause numbers or editions are asserted unless verified.
- **No endorsement, affiliation or accreditation is claimed or implied.** Naming an external instrument means only that it exists and is relevant. No standards body, professional institute, government, supervisory authority, export credit agency or financial institution has reviewed, approved, endorsed or accredited these laws, the PFL-AI credential or PCI Global, and nothing here is a claim of conformity with, certification to, or accreditation under any instrument named. Where an instrument's status is known to be changing, that is noted at the point of use.

- **Nothing here is legal, tax, accounting or investment advice.** These laws set professional conduct within PCI's certification scope. Every treatment, contractual position and structure they touch is jurisdiction-specific and requires advice from a qualified adviser for the specific entity, structure and date — a duty that is itself a law of this set (PFL-LAW-12-01).
- **The suite principle** applies to every law in this set, in its one approved formulation:

⚠ **CAUTION**

AI proposes; the professional verifies, decides and remains accountable.

Domain 1 — Foundations of project finance leadership

§ PCI LAW

PFL-LAW-01-01

Cash Before Appearance

Rule. A credential holder shall test every financing, structuring and investment judgement against the project's cash position and the dates on which its obligations fall due, and shall not present an accounting result, an earnings measure or an averaged ratio as evidence that a project can meet an obligation when it becomes payable.

Purpose. A project financing fails on the day cash is not in the account, whatever the reported profit. Accrual results, non-cash charges, revaluations and annualised averages can present a comfortable picture over an account that will be empty on the payment date.

Scope. All credential holders who prepare, review or approve appraisals, forecasts, funding plans, coverage assessments, lender reports, credit submissions or board papers, on any asset class and any financing structure.

Minimum professional requirement. Identify the cash available for debt service and the dated obligations it must meet; reconcile the accounting result to that cash line; state non-cash items separately; test liquidity at each payment date rather than on an annual average; and disclose wherever a favourable presentation depends on non-cash items, timing conventions or a horizon choice.

Required evidence. The dated cash-flow forecast with each obligation on its due date; the reconciliation from accounting profit to cash available for debt service; the schedule of non-cash adjustments; the liquidity test at each payment date; the approver's sign-off.

Decision owner. The project finance leader accountable for the funding plan; the sponsor's, lender's or board's approving officer for the decision that relies upon it.

Independent review. Required wherever a coverage or liquidity conclusion supports sanction, financial close, a drawing, a distribution or a waiver request.

Escalation trigger. A forecast showing an obligation that cannot be met from available cash at its due date, however presented; or an instruction to answer a solvency, coverage or funding question on an accounting basis in place of a cash basis.

Prohibited practice. Offering an earnings measure, accounting profit or an annualised average as evidence of ability to pay on a date; netting a dated cash shortfall against an unrealised or non-cash gain; smoothing or re-phasing timing to conceal a shortfall; describing an accrued receipt as available cash.

AI application. AI may build and re-phase cash-flow projections, reconcile accrual results to cash, detect timing mismatches between obligations and receipts, and generate liquidity stress runs.

AI restriction. AI must not conclude that a project is solvent, adequately funded or able to meet an obligation, nor approve a funding plan or a liquidity position.

Verification requirement. A competent professional must recompute the cash available for debt service for the binding periods from source lines, confirm each obligation date against the underlying document, and confirm that AI-produced reconciliations tie to the released model and to the financial statements.

● EXTERNAL REFERENCE

IFRS Foundation Conceptual Framework for Financial Reporting (authoritative accounting material — **not itself an accounting standard**; the IASB states that nothing in it overrides any standard or any requirement in a standard) — describes the accrual basis and faithful representation, which is precisely what makes an accounting result a different statement from a cash fact. IAS 7 Statement of Cash Flows, IFRS Foundation (authoritative accounting standard) — for entities applying IFRS Accounting Standards, the presentation and classification of cash movements against which a modelled cash line is reconciled. The official publications govern; verify current requirements.

▲ CAUTION

Solvency, distributable-reserve and insolvency tests are matters of local company and insolvency law and are not established by a cash forecast; obtain local legal and accounting advice before any statement about the ability of an entity to continue or to pay.

Related PCI laws. PCI-LAW-F-07; PFL-LAW-10-01; PFL-LAW-14-01; PFL-LAW-15-01.

Related book content. Domain 1, KA 1.2 — Value, cash and risk (1.2.2 cash, not profit, is the binding constraint); Domain 2, KA 2.1 — The accrual model; KA 2.2 — The three statements and their articulation; Domain 10, KA 10.1 — Debt capacity and sizing (cash available for debt service).

Examination relevance. Assessed through scenario items in which a profitable-looking forecast conceals a dated liquidity shortfall, and the candidate must identify the binding period and the compliant presentation. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-01-02

Conflict Disclosure and the Two-Hat Rule

Rule. A credential holder shall disclose in writing, before advising, modelling, negotiating or approving, every interest that could reasonably be seen to influence their judgement on a financing, and shall not act for more than one side of a transaction, or on a matter in which an undisclosed interest exists, without the informed written consent of every affected party.

Purpose. Project finance concentrates advice: the same individual or firm can sit close to sponsor, lender, grantor and contractor. An undisclosed interest converts advice into advocacy while preserving the appearance of objectivity, and the parties relying on it cannot see the change.

Scope. All credential holders advising, modelling, structuring, reviewing, lending, approving or negotiating on a project financing, whether in-house or as an external adviser, including their personal financial interests and those of connected persons where these relate to the transaction.

Minimum professional requirement. Maintain a standing conflicts register; screen every new instruction against it; disclose in writing before work begins and again whenever a new interest arises; obtain written consent or decline the engagement; where an information barrier is used, document it and test that it operates in practice.

Required evidence. The conflicts register with dates and outcomes; written disclosures and consents; engagement terms recording role and side; information-barrier records and test results; records of engagements declined for conflict.

Decision owner. The credential holder for making their own disclosure; the engaging organisation's responsible partner or officer for whether the engagement may proceed and on what terms.

Independent review. Required whenever a credential holder or their firm acts for more than one party to the same transaction, and whenever a disclosed conflict is managed by information barrier rather than by declining.

Escalation trigger. Discovery of an undisclosed interest; an instruction to withhold or delay a disclosure; a consent obtained on incomplete information; a mandate that would require advising both sides on the same question.

Prohibited practice. Acting on both sides without informed written consent; accepting undisclosed fees, commissions or success-linked benefits from a party other than the client; using transaction information for personal or connected benefit; describing advice as independent while holding an undisclosed interest.

AI application. AI may screen new instructions against the conflicts register and entity relationship data, surface related-party links, monitor for newly arising interests, and draft disclosure wording for review.

AI restriction. AI must not determine whether a conflict exists, decide that a conflict is manageable, waive a disclosure, or certify a person or firm as independent.

Verification requirement. A competent professional must check AI-generated conflict screens against the register and against their own knowledge of relationships, and must retain the screening evidence; a negative machine screen is not a finding of no conflict.

● EXTERNAL REFERENCE

ISO/IEC 17024 Conformity assessment — General requirements for bodies operating certification of persons (international standard) — addresses impartiality and the management of conflicts in the certification of persons, which PCI characterises as the reference discipline for conflict management in assessment roles; adoption is voluntary unless a law or contract imports it, and **no accreditation to, or certification against, this standard is claimed by PCI through this reference.** G20/OECD Principles of Corporate Governance (voluntary framework) — intergovernmental, non-binding principles adopted as an OECD Council Recommendation, addressing disclosure, related-party transactions and the management of conflicts in governance; not legislation. The official publications govern; verify current requirements.

⚠ CAUTION

Fiduciary duty, agency law, anti-bribery and financial-promotion rules determine the legal consequences of an undisclosed interest and differ by jurisdiction; obtain local legal advice before relying on consent as a cure.

Related PCI laws. PCI-LAW-F-10; PCI-LAW-F-13; PFL-LAW-13-01; PFL-LAW-16-01.

Related book content. Domain 1, KA 1.3 — Ethics, fiduciary awareness and responsible AI (1.3.1 obligations and duties; 1.3.2 conflicts and independence); Domain 1, Toolkit 1.T.3 — Conflicts and AI-use register; Domain 1, Case study B — the adviser with two hats; Domain 13, KA 13.1 — The diligence streams.

Examination relevance. Scenario items in which an adviser holds a second role, interest or fee arrangement, testing whether the candidate discloses, declines or proceeds and on what record. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 4 — Investment appraisal and capital budgeting

§ PCI LAW

PFL-LAW-04-01

Appraisal Discipline

Rule. A credential holder shall appraise an investment on a stated and internally consistent basis — cash flows and discount rate on the same inflation and currency basis, one stated horizon, one stated perspective — shall report the measure appropriate to the decision, and shall not select, re-base or re-cut a measure in order to produce a preferred conclusion.

Purpose. Appraisal outputs are decision instruments. Nominal cash flows discounted at a real rate, an internal rate of return quoted where the sign of the cash flows changes more than once, or a horizon chosen after the answer is known, all produce numbers that are precise and wrong.

Scope. All credential holders producing or approving investment appraisals, screening analyses, bid economics, refinancing evaluations, acquisition or disposal analyses and exit valuations.

Minimum professional requirement. State the basis on the face of the appraisal — real or nominal, currency, pre- or post-tax, project or equity perspective, horizon and terminal-value treatment; apply one consistent rate basis throughout; disclose the pathologies of any rate-of-return measure quoted and report net present value alongside it; state the hurdle rate and who owns it; and retain every case run, including those that did not support the decision.

Required evidence. The appraisal file with its stated basis; the identified model version used; the hurdle-rate derivation and its approval; the full case set including unfavourable cases; the sensitivity or breakeven output; the approver's sign-off.

Decision owner. The investment decision owner — investment committee or board; the project finance leader owns the integrity of the appraisal placed before them.

Independent review. Required for appraisals supporting sanction, bid submission, acquisition or disposal, and for any change to the hurdle rate or to the appraisal basis.

Escalation trigger. An instruction to change the horizon, rate or basis after the result is known; discovery that a decision was taken on an inconsistent basis; the removal of an unfavourable case from a decision pack.

Prohibited practice. Mixing real and nominal quantities; quoting a rate of return alone where sign changes or scale differences make it unsafe; extending the horizon or inflating a terminal value to reach a hurdle; discarding cases; presenting a single point estimate with no statement of uncertainty.

AI application. AI may compute the measures, generate and run the case set, detect real-nominal and currency inconsistency, produce net-present-value profiles, and assemble sensitivity tables.

AI restriction. AI must not set the hurdle rate, choose the appraisal basis or horizon, select which case is reported, or take the investment decision.

Verification requirement. A competent professional must recompute the headline measure independently from the cash-flow line, confirm that the rate and the cash flows share one basis, and confirm that the reported case set is complete before the appraisal is issued.

● EXTERNAL REFERENCE

IAS 36 Impairment of Assets, IFRS Foundation (authoritative accounting standard) — for financial-reporting purposes it requires a recoverable amount determined on a defined basis, with consistency between the projected cash flows and the rate applied to them; the same consistency discipline underlies appraisal. ISO 31000 Risk management — Guidelines (international standard) — the treatment of uncertainty in decision-making. The official publications govern; verify current requirements.

△ **CAUTION**

Tax rates, allowances and their timing determine any post-tax appraisal and are jurisdiction- and entity-specific; obtain local tax advice before relying on a post-tax result or presenting it to a decision-maker.

Related PCI laws. PCI-LAW-F-07; PFL-LAW-06-03; PFL-LAW-09-01; PFL-LAW-12-01.

Related book content. Domain 4, KA 4.1 — The discounted measures (4.1.2 IRR and its pathologies); KA 4.3 — Decision contexts (4.3.3 the limits of the numbers); 4.A.2 — Inflation-consistent appraisal; 4.A.3 — Reconciling the hurdle to the structure; Domain 3, KA 3.3 — Real-world adjustments (3.3.1 the Fisher relation).

Examination relevance. Scenario items presenting an appraisal whose rate and cash flows are on different bases, or whose measure has been chosen to suit the answer, for the candidate to detect and correct. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 5 — Project development and bankability

§ PCI LAW

PFL-LAW-05-01

The Bankability Test

Rule. A credential holder shall state a project's bankability as a conjunction of conditions all of which must hold — revenue and payment mechanism, offtake or grantor covenant, permits, land and consents, technology and track record, construction and operational readiness, and an allocated risk position — and shall not represent a project as bankable while any of those conditions is unresolved, unless the gap, its owner and its resolution path are stated with it.

Purpose. Bankability is not a score and does not average. A project described as bankable on the strength of its strongest feature consumes development capital, misleads investors and lenders, and fails at the condition nobody was tracking.

Scope. All credential holders who prepare or endorse bankability assessments, development-gate papers, information memoranda, investment or credit submissions, and lenders' staff who rely on them.

Minimum professional requirement. Assess each condition separately against evidence; record status, owner, supporting evidence and residual gap for each; maintain a live gap register from development to close; restate bankability whenever a condition changes; and state clearly wherever the assessment rests on an assumption rather than an executed instrument.

Required evidence. The condition-by-condition assessment with evidence references; the gap register with owners and dates; the permit, land and consent schedule; the contract status list; technology and track-record evidence; the version history of the assessment.

Decision owner. The development or project finance leader who signs the bankability assessment; the sanctioning body for the decision to continue spending against it.

Independent review. Required at each development gate, before an information memorandum or credit submission is issued, and whenever a previously satisfied condition reopens.

Escalation trigger. A condition moving from satisfied to unresolved; pressure to publish a bankability statement while a load-bearing condition is open; development spend continuing past a gate whose kill criteria are met.

Prohibited practice. Presenting bankability as a weighted score that conceals an unsatisfied condition; presenting an indicative offer, unsigned term sheet or draft permit as an executed instrument; omitting a known consent, land or technology gap from a lender-facing document.

AI application. AI may assemble the condition register from documents, track permit and consent status, compare a project's condition set against comparable financings, and flag items with no supporting evidence.

AI restriction. AI must not declare a project bankable, reduce the conditions to a single score presented as a bankability conclusion, or approve a development gate.

Verification requirement. A competent professional must verify each condition's status against the underlying instrument or authority record rather than against a summary, and must trace every AI-extracted status to its source document before it enters a lender-facing paper.

● EXTERNAL REFERENCE

Equator Principles (voluntary framework) — a risk-management framework adopted by participating financial institutions for environmental and social risk in project finance; adoption is voluntary and it is not legislation. IFC Performance Standards (voluntary framework) — the International Finance Corporation's environmental and social performance standards, widely used as a reference benchmark by lenders. ISO 31000 Risk management — Guidelines (international standard) — the risk process within which conditions and gaps are assessed. The official publications govern; verify current requirements.

⚠ CAUTION

Permits, land tenure, concession award and licensing are jurisdiction-specific and may be open to administrative challenge; obtain qualified local legal advice on the validity, transferability and conditionality of every consent relied upon.

Related PCI laws. PCI-LAW-F-07; PCI-LAW-F-11; PFL-LAW-07-01; PFL-LAW-11-01; PFL-LAW-13-02.

Related book content. Domain 5, KA 5.3 — The bankability test (5.3.1 bankability as a conjunction; 5.3.2 the revenue model and the offtake; 5.3.3 permits, land and consents; 5.3.4 technology and the bankable track record); KA 5.4 — Construction and operational readiness; 5.A.2 — Conditions precedent: the bankability list made contractual.

Examination relevance. Scenario items in which a project is presented as bankable while a permit, offtake or technology condition remains open, testing whether the candidate identifies the binding gap and what they do with it. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 6 — Financial modelling

§ PCI LAW

PFL-LAW-06-01

Model Integrity

Rule. Every financial model a credential holder builds, relies upon or presents for decision must separate inputs, calculations and outputs, must carry a check block that computes its arithmetic invariants as differences that must resolve to nil, and must not be quoted, circulated or relied upon while any check is failing.

Purpose. The model is the transaction's shared instrument of belief: debt is sized on it, covenants are set from it and a board sanctions against it. Structure is what makes it reviewable by someone who did not build it, and the check block is what makes the model's silence mean something.

Scope. All credential holders who build, review, audit, operate or rely upon project financial models — base case, bank case, bid model, financial-close model, operating and budget models, restructuring models — in any tool.

Minimum professional requirement. Build in separated blocks with no backward flow; build the check block before the outputs; compute at minimum the balance-sheet balance, sources equal to uses in every construction period, debt fully repaid at maturity for every facility, scheduled principal equal to total drawings, no negative cash balance in any period or account, and a defined reconciliation of the cash-available-for-debt-service line to the statements; display one aggregate flag; and stop reporting when it fails.

Required evidence. The model file with a visible check block and aggregate flag; the check results for the version quoted; the structural review record; model documentation describing the block layout, flags and conventions.

Decision owner. The named model owner for the model itself; the project finance leader for what is quoted from it.

Independent review. Required before a model is used for debt sizing, credit submission, financial close, distribution testing or restructuring, and after any structural change.

Escalation trigger. A check failing in a model on which a decision has already been taken; a request to circulate outputs while the aggregate flag is failing; discovery of calculation logic inside the output block or of assumptions inside the calculation block.

Prohibited practice. Quoting from a model with failing checks; deleting, disabling or narrowing a check to clear a flag; building outputs that recompute rather than present; offering "the balance sheet balances" as evidence that a model is correct.

AI application. AI may scan whole workbooks for structural defects, propose the check block, generate adversarial test cases that break a waterfall, and maintain a regression suite of verified figures rerun after every edit.

AI restriction. AI must not certify a model as correct, clear or waive a failing check, decide a modelling convention, or be recorded as the model's owner.

Verification requirement. A competent professional must recompute at least one construction period and one operating period by independent means for every released version, and must confirm each machine-listed finding individually before it is reported.

◆ EXTERNAL REFERENCE

ICAEW Financial Modelling Code (professional guidance) — principles for structuring, documenting and reviewing spreadsheet-based financial models; principles-based guidance published by a professional body, not a compliance standard and not certifiable. The FAST Standard (industry practice) — a published set of spreadsheet-modelling conventions, adopted voluntarily, whose name stands for flexible, appropriate, structured and transparent. The official publications govern; verify current requirements.

▲ CAUTION

Model structure is a professional discipline rather than a legal requirement; the treatments the model implements — tax, accounting, covenant definitions — are jurisdiction- and document-specific, must be confirmed by qualified local advisers, and are governed by PFL-LAW-10-02 and PFL-LAW-12-01. Where applicable law, regulation, the finance documents or an authoritative professional standard imposes a stricter requirement on how a model is built, documented or reviewed, that requirement governs.

Related PCI laws. PCI-LAW-F-01; PCI-LAW-F-05; PFL-LAW-06-02; PFL-LAW-06-05; PFL-LAW-16-02.

Related book content. Domain 6, KA 6.1 — Model architecture (6.1.1 the three-block rule; 6.1.2 the timeline as the model's spine); KA 6.4 — Checks, sensitivity, model audit and AI controls (6.4.1 the check block and the six invariants); 6.A.3 — The reviewer's model eye; Domain 13, KA 13.2 — Model audit.

Examination relevance. Scenario items presenting a model that balances while carrying a consistent error, testing whether the candidate knows which check localises which failure and what may be quoted. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-06-02

Formula Transparency

Rule. A credential holder shall express every calculation as a visible, traceable formula referencing a declared input, shall not embed a constant, an override or a pasted value inside a calculation, and shall not present as calculated any figure that was typed.

Purpose. A hard-coded constant is invisible to a reviewer, survives every scenario switch and produces a model that is stable in the wrong answer. A pasted value looks like a result and is only a memory of one.

Scope. All model builders and reviewers, and all calculation content in decision-grade work, including side calculations, extracts and analyses circulated outside the master model.

Minimum professional requirement. Keep the calculation block free of numerals other than disclosed structural constants; one row, one formula, copied across; state the sign convention once and enforce it everywhere; where an override is unavoidable, record it as an input with an owner, a reason and an expiry; and convert or remove side calculations before release.

Required evidence. Formula-scan results for the released version; the disclosed list of structural constants; the override register with owner, reason and expiry; the reviewer's structural sign-off.

Decision owner. The named model owner; the author of any circulated extract for that extract.

Independent review. Required before first decision-grade use and after any change touching the calculation block; a machine formula scan does not satisfy this requirement.

Escalation trigger. Discovery of a hard-coded value behind a reported figure; a formula that changes part-way along a row; an override still live beyond its stated expiry.

Prohibited practice. Typing a number into a formula; pasting values over links; hiding rows or sheets that contain calculations; protecting or obscuring the calculation block to prevent review; presenting a typed figure as a model output.

AI application. AI may scan at whole-workbook scale for embedded constants, mid-row formula changes, inconsistent references and orphaned cells, and may draft plain-language explanations of a formula for review.

AI restriction. AI must not decide that a constant is acceptable, remove a flagged item from a findings list, or declare a workbook clean.

Verification requirement. A competent professional must confirm every machine-raised finding individually, record the sample size used for any machine-produced finding list, and trace the model's headline figures cell by cell back to declared inputs.

● EXTERNAL REFERENCE

The FAST Standard (industry practice) — spreadsheet-modelling conventions directed at transparency and consistent structure, adopted voluntarily. ICAEW Financial Modelling Code

(professional guidance) — build, documentation and review principles for financial models; principles-based guidance published by a professional body, not a compliance standard and not certifiable. The official publications govern; verify current requirements.

⚠ CAUTION

Transparency of construction is a modelling discipline and is not itself set by any law; but the treatments the formulae implement — tax, accounting, tariff, indexation and covenant mechanics — are jurisdiction- and document-specific, must be confirmed by qualified local advisers, and are covered by PFL-LAW-10-02 and PFL-LAW-12-01. Where applicable law, regulation, contract or an authoritative professional standard imposes a stricter requirement on model construction or disclosure, that requirement governs.

Related PCI laws. PCI-LAW-F-05; PFL-LAW-06-01; PFL-LAW-06-04; PFL-LAW-16-02.

Related book content. Domain 6, KA 6.1 — Model architecture (6.1.1 the cardinal defect is the hard-coded constant); KA 6.4 — Checks, sensitivity, model audit and AI controls (6.4.4 AI-assisted modelling controls); Domain 6, Case study B — the forecast that was pasted, not linked; Domain 13, KA 13.2 — Model audit (findings by class).

Examination relevance. Scenario items containing an embedded rate or a pasted forecast row, testing detection, correction and the consequences for figures already reported. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-06-03

Assumption Traceability

Rule. Every assumption in a model must be entered once, in the input block, and recorded in an assumption register that travels with the model, stating value, unit, basis, source, date and named owner; an assumption without a recorded owner and basis shall not be used in a decision-grade case.

Purpose. Assumptions are where a model's judgement lives. A number nobody owns cannot be challenged, updated or defended, and a case that differs from another in ways nobody recorded is not a case at all.

Scope. All inputs — macroeconomic, technical, commercial, tax, financing and timing — in every case, including sponsor case, bank case, bid case, downside cases and any case shown to a third party.

Minimum professional requirement. Enter each assumption once; maintain the register with value, unit, basis, source, date, owner and the cases to which it applies; record the difference between sponsor case and bank case assumption by assumption; date-stamp time-sensitive assumptions and re-confirm them before reliance; and identify the assumptions to which the conclusion is sensitive.

Required evidence. The assumption register issued with the model version; the case comparison showing every difference; re-confirmation records for rates, prices and indices; the sensitivity or breakeven output identifying the binding assumptions.

Decision owner. The named owner of each assumption; the model owner for the register's completeness and its agreement with the input block.

Independent review. Required before debt sizing, credit submission and financial close, and whenever a binding assumption changes.

Escalation trigger. A decision resting on an assumption with no owner or source; a case difference discovered that was never recorded; an assumption changed between versions without a record; a stale assumption carried into a current case.

Prohibited practice. Entering the same assumption in more than one place; changing an assumption to reach a target ratio without recording the change, its basis and its owner; describing a sponsor-case assumption as agreed by lenders; presenting an assumption as evidenced when it is judgement.

AI application. AI may draft the assumption register from the input block so that the two cannot drift apart, detect duplicate entries and stale values, and compare cases assumption by assumption.

AI restriction. AI must not set or change an assumption value, own an assumption, or decide which case is the base case or the bank case.

Verification requirement. A competent professional must trace each material assumption to its source document and confirm its currency, and must reconcile the register to the input block for every released version.

● EXTERNAL REFERENCE

ICAEW Financial Modelling Code (professional guidance) — documentation of assumptions and inputs in financial models. ISO 8000 data quality series (international standard) — concepts and requirements for the quality of data used in decision-making. The official publications govern; verify current requirements.

▲ CAUTION

Tax, escalation-index and regulatory assumptions are jurisdiction- and entity-specific; they must be confirmed by qualified local advisers before a case is described as reflecting them.

Related PCI laws. PCI-LAW-F-06; PFL-LAW-06-04; PFL-LAW-07-01; PFL-LAW-12-01.

Related book content. Domain 6, KA 6.1 — Model architecture (6.1.3 basis, horizon and case); KA 6.4 — Checks, sensitivity, model audit and AI controls (6.4.4 AI-assisted modelling controls); Domain 3, Toolkit 3.T.1 — TVM assumption register; Domain 8, KA 8.1 — Estimate classes and the contingency a range implies.

Examination relevance. Scenario items in which two cases differ in undocumented ways, or a target ratio is achieved by an unrecorded assumption change, testing register discipline and escalation. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-06-04

The Source Line

Rule. Every input to a decision-grade model, and every figure quoted from it in a lender-facing, board-facing or investor-facing document, must carry a source line identifying the document, its version or date and the party that issued it; a figure whose source line cannot be produced on request must be withdrawn from the document.

Purpose. The source line is the join between the model and the evidence. It is what makes a workbook diligence-ready, what makes a paste detectable, and what allows a figure to be defended years later in a claim, a refinancing or a dispute.

Scope. All inputs to decision-grade models and all quoted outputs — information memoranda, credit papers, board packs, compliance certificates, draw requests, valuations and public statements.

Minimum professional requirement. Record for each input the source document, the issuing party, the version or date and the location within it; keep the source document, or a controlled reference to it, in the transaction record; quote only from a released model version; and mark derived figures as derived, identifying the derivation.

Required evidence. The input-to-source mapping covering every input; the referenced document set; the model version register; the log tying each published figure to a model version and a source line.

Decision owner. The model owner for the inputs; the author and signer of a document for the figures quoted in it.

Independent review. Required at model audit, before financial close, and whenever a quoted figure is challenged.

Escalation trigger. A quoted figure whose source cannot be produced; a source document superseded without the model being updated; discovery of a value entered from memory, from a conversation or from an unattributed spreadsheet.

Prohibited practice. Entering a value with no source; citing "the model" as the source of a model input; quoting figures from an unreleased or superseded version; presenting an estimate as an evidenced value.

AI application. AI may extract values from source documents and propose source lines, detect inputs lacking provenance, and match quoted figures back to model cells and versions.

AI restriction. AI must not attest the accuracy of a source line, select which version of a document is authoritative, or supply a value for which no source exists.

Verification requirement. A competent professional must verify sampled AI-extracted values against the original document rather than an extract, and must confirm that every figure in a lender-facing document ties to the released model version and its source lines.

EXTERNAL REFERENCE

ISO 8000 data quality series (international standard) — data quality requirements including provenance. ISO 15489 Information and documentation — Records management (international standard) — capture, integrity and retention of the records that evidence a transaction. The official publications govern; verify current requirements.

CAUTION

Data-protection, confidentiality and cross-border transfer rules constrain which source documents may be copied, exported or stored, and where; obtain local legal advice before moving transaction documents into external systems.

Related PCI laws. PCI-LAW-F-05; PCI-LAW-F-06; PFL-LAW-06-03; PFL-LAW-13-03.

Related book content. Domain 6, KA 6.4 — Checks, sensitivity, model audit and AI controls (6.4.4 provenance for every input); Domain 6, Case study B — the forecast that was pasted, not linked; Domain 13, KA 13.1 — The diligence streams (13.1.5 the data room and the diligence trail); Domain 14, KA 14.1 — Sources and uses, draw requests and conditions.

Examination relevance. Scenario items in which a headline figure in a credit paper cannot be traced to a document or version, testing withdrawal, correction and notification. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-06-05

Model Change Governance

Rule. A model that has been used for a decision must not be changed except under version control: each change shall be recorded in a change log with author, date, reason and effect; the check block and the regression suite shall be rerun; every movement shall be explained before acceptance; and one authoritative version shall be identified. No change shall reach the authoritative file without appearing in the change log under a named human author.

Purpose. A transaction model is edited continuously, by several hands, under time pressure. Without version control the parties stop looking at the same project, and nobody can say when a number changed, why, or on whose authority.

Scope. All models used for decisions, reporting or certification — base case, bank case, financial-close model, operating and budget models, restructuring models — and every AI-assisted edit to them.

Minimum professional requirement. Maintain one authoritative file with a named owner and a version identifier; log every change; rerun the check block and a regression suite of independently verified figures after every edit, machine or human, and explain each movement before accepting it; lock the agreed close model and treat later changes as new versions; and distribute controlled versions rather than allowing local copies to circulate.

Required evidence. The version register; change-log entries with author, date, reason and effect; regression results per version with explanations; the locked close model with its version identifier and integrity control; the distribution record.

Decision owner. The model owner for the model; the lender's or sponsor's approver for any change to an agreed or locked base case.

Independent review. Required for changes to a locked or agreed model, for changes affecting covenant definitions, debt sizing or the waterfall, and at the revalidation interval set for high-consequence models in the model inventory.

Escalation trigger. A change to a locked model without approval; an unexplained movement in a regression figure; two versions in circulation bearing the same name; an AI edit discovered in the authoritative file with no change-log entry.

Prohibited practice. Editing an agreed model without logging the change; distributing an unlabelled copy; accepting an unexplained regression movement; recording a tool as the author of a change; representing an updated model as the version agreed at close.

AI application. AI may produce version diffs as human-readable change lists, run the regression suite, draft change-log entries for confirmation, and identify every cell that moved between versions.

AI restriction. AI must not approve a change, be recorded as its author, decide that a regression difference is acceptable, or release a version.

Verification requirement. A competent professional must confirm that every diff item corresponds to an intended change, explain every regression movement, and sign the version as released before it is used or distributed.

◆ EXTERNAL REFERENCE

Supervisory Guidance on Model Risk Management (SR 11-7), issued by United States banking supervisors (public supervisory guidance) — expectations for model development, implementation, use, validation and governance in supervised institutions in that jurisdiction. ISO/IEC 42001 Artificial intelligence — Management system (international standard) — organisational management of AI systems, including lifecycle and change controls. ICAEW Financial Modelling Code (professional guidance) — version control and documentation of financial models. The official publications govern; verify current requirements.

△ CAUTION

Where a model is a contractual deliverable or a condition of financing, the finance documents determine which version governs and which changes require consent; obtain qualified legal advice on the contractual status of the model before amending an agreed version.

Related PCI laws. PCI-LAW-F-05; PCI-LAW-F-12; PFL-LAW-06-01; PFL-LAW-13-03; PFL-LAW-16-02.

Related book content. Domain 6, KA 6.4 — Checks, sensitivity, model audit and AI controls (6.4.3 model audit, governance and its economics; 6.4.4 AI-assisted modelling controls); 6.A.2 — Model reuse, templates and the drift problem; Domain 16, KA 16.3 — Explainability, validation, bias and model risk (16.3.4 inventory, tiering, revalidation).

Examination relevance. Scenario items in which a locked close model has moved, or a regression figure has changed without explanation, testing version discipline, escalation and what may still be quoted. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 7 — Revenue, demand and commercial models

§ PCI LAW

PFL-LAW-07-01

Revenue Assumption Discipline

Rule. A credential holder shall characterise every revenue stream by its actual contractual and market basis — contracted or merchant, volume-based or availability-based, indexed or fixed, and by the credit standing of the party that pays — shall carry demand and price assumptions at values supported by stated evidence, and shall not present a forecast revenue as though it were contracted.

Purpose. Revenue is where the coverage ratios come from, and the whole capital structure is sized on it. A demand forecast dressed as a contract is the most expensive error in project finance because every other number inherits it.

Scope. All credential holders preparing or reviewing revenue assumptions, demand forecasts, tariff and payment-mechanism models, counterparty credit assessments and revenue stress cases for appraisal, debt sizing, credit submission, refinancing or restructuring.

Minimum professional requirement. Identify the contract that produces each revenue line and the mechanism by which it pays; state which portion is contracted and for how long; state the counterparty and its credit standing; carry ramp-up assumptions explicitly with their evidential basis; map indexation on revenue against indexation on cost and state any mismatch; run and retain a stated downside case; and disclose the merchant tail beyond the contracted horizon.

Required evidence. The revenue basis note tying each stream to its contract; the market or demand study with author, date and scope; counterparty credit evidence; the indexation mapping; stress-case definitions and results; the statement of contracted horizon against merchant tail.

Decision owner. The commercial or project finance leader who signs the revenue basis; the credit approver for the case adopted in sizing.

Independent review. Required where revenue assumptions drive debt sizing or a bid price, where a market study is relied upon by lenders, and whenever a demand or price forecast is revised upward.

Escalation trigger. An upward revision of demand or price with no new evidence; discovery that a contracted volume or availability payment is lower than modelled; deterioration in the credit standing of a paying counterparty; removal of a downside case from a decision pack.

Prohibited practice. Presenting a forecast as contracted; relying on an unattributed market study or one whose scope does not cover the question; modelling a ramp faster than any evidence supports; assuming a cost pass-through the contract does not provide; deleting the downside case.

AI application. AI may generate scenario sets and coverage tests, detect anomalies in historical demand data, extract payment-mechanism terms from contracts for human confirmation, and test indexation arithmetic across cases.

AI restriction. AI must not set a demand or price assumption, judge a market study adequate, characterise a revenue stream as contracted, or decide which case is the bank case.

Verification requirement. A competent professional must confirm each characterisation against the executed contract, confirm the scope and date of any market study relied upon, and recompute the revenue build for at least one full period from its drivers.

EXTERNAL REFERENCE

IFRS 15 Revenue from Contracts with Customers, IFRS Foundation (authoritative accounting standard) — the contract-based analysis governing when revenue is recognised for reporting purposes, which is a different question from when cash is received. ISO 31000 Risk management — Guidelines (international standard) — the treatment of uncertainty in forecasting and stress testing. The official publications govern; verify current requirements.

CAUTION

Tariff regulation, price controls, subsidy regimes and consumer-protection rules can alter a revenue mechanism after financial close and differ by jurisdiction; obtain local regulatory and legal advice before relying on a mechanism's durability.

Related PCI laws. PCI-LAW-F-07; PFL-LAW-05-01; PFL-LAW-06-03; PFL-LAW-10-01.

Related book content. Domain 7, KA 7.1 — Contracted and merchant revenue (7.1.1 the revenue-risk spectrum; 7.1.3 availability payments and the deduction mechanism); KA 7.2 — Demand models (7.2.1 demand forecasting and the ramp); KA 7.3 — Price escalation and volume risk (7.3.1 indexation architecture and margin drift); KA 7.4 — Counterparty credit quality and revenue stress testing (7.4.3 the bank case); 7.A.2 — The merchant tail and the contracted horizon.

Examination relevance. Scenario items in which an availability payment, a minimum volume and a merchant forecast are presented interchangeably, testing correct characterisation and its effect on sizing. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 9 — Funding structure and sources of capital

PCI LAW

PFL-LAW-09-01

Capital-Structure Justification

Rule. A credential holder shall justify a proposed capital structure — gearing, tranching, tenor, amortisation profile, hedging and the cost of each instrument — against the project's cash-flow profile, its

risk allocation and its required coverage, and shall not propose or accept a structure whose feasibility depends on a refinancing, a further contribution or market conditions that have not been stated as assumptions.

Purpose. Leverage is a claim on the same cash that must absorb risk. A structure that works only if a refinancing is available at an assumed price has moved a market risk into the future without pricing it, and the party that discovers this is usually equity at its worst moment.

Scope. All credential holders who structure, arrange, advise on, approve or review funding plans, term sheets, tranche design, hedging strategy, government support, concessional funding and refinancings.

Minimum professional requirement. Build the structure from the cash-flow profile and the required coverage rather than from a target gearing; state each source's cost, tenor, ranking, security and conditions; derive and state the blended cost including fees and credit-enhancement cost; identify refinancing, tail and mini-perm exposure explicitly as an assumption; state hedging policy and the residual exposure it leaves; and test the structure against the downside case.

Required evidence. The funding plan and sources-and-uses statement; the tranche schedule with terms; the blended-cost derivation; the refinancing assumption note; the hedging policy and hedge ratio calculation; downside-case coverage results; the approvals obtained.

Decision owner. The sponsor's finance director or investment committee for the structure adopted; the arranger's credit approver for what is offered.

Independent review. Required before commitment to a term sheet, before financial close, and before a refinancing or a material amendment to the structure.

Escalation trigger. A structure that meets coverage only in the sponsor case; reliance on an unstated refinancing or on support not yet documented; hedging that leaves an undisclosed residual exposure; a tranche whose conditions the project cannot meet.

Prohibited practice. Sizing debt to a target gearing and then adjusting assumptions to fit; presenting a blended cost that omits fees, margins or credit-enhancement cost; describing an indicative offer as committed capital; describing grant or concessional support as secured before it is documented.

AI application. AI may generate structure options against stated constraints, compute blended costs and hedge ratios, test profiles against coverage requirements, and draft comparative sources-and-uses analyses.

AI restriction. AI must not select the capital structure, commit to or accept terms, set hedging policy, or determine that a refinancing assumption is reasonable.

Verification requirement. A competent professional must recompute coverage under the proposed structure from the model's cash line, confirm each source's terms against the offer or executed document, and confirm that all fees and costs are captured in the stated blended cost.

◆ EXTERNAL REFERENCE

Basel framework, Basel Committee on Banking Supervision (illustrative reference — internationally agreed supervisory standards **with no legal force of their own**; the Committee has no supranational authority, and the standards apply to banks only as national authorities transpose them into domestic law or regulation) — named for the supervisory context in which bank capital, leverage and liquidity shape lenders' appetite, pricing and tenor; not relied on here for any requirement. OECD Arrangement on Officially Supported Export Credits (voluntary framework — an inter-governmental understanding among participating authorities, not a treaty and not legislation) — agreed terms and disciplines for officially supported export credit; its terms are revised periodically and vary by sector, so they must be checked as at the transaction date. Equator Principles (voluntary framework) — environmental and social risk management adopted voluntarily by participating financial institutions, which conditions the availability of some funding; not legislation. The official publications govern; verify current requirements.

▲ CAUTION

- Thin-capitalisation rules, interest deductibility, withholding tax, exchange control and the perfection of security differ by jurisdiction and can change both the economics and the enforceability of a structure; obtain local tax and legal advice.

Related PCI laws. PCI-LAW-F-07; PFL-LAW-04-01; PFL-LAW-10-01; PFL-LAW-12-01.

Related book content. Domain 9, KA 9.1 — Equity and shareholder instruments (9.1.4 the leverage trade-off); KA 9.2 — Senior, subordinated and mezzanine debt (9.2.3 the blended cost of a multi-tranche stack); KA 9.3 — Islamic finance, export credit and development finance (9.3.4 assembling a multi-source stack); KA 9.4 — Government support, sustainable finance and refinancing; 9.A.1 — Why capital-structure irrelevance fails in a project SPV; Domain 11, KA 11.3 — Interest-rate exposure and the hedge ratio.

Examination relevance. Scenario items in which a structure passes coverage only on the sponsor case or only with an unstated refinancing, testing the candidate's justification and disclosure. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 10 — Debt sizing, covenants and credit metrics

§ PCI LAW

PFL-LAW-10-01

Debt-Service Coverage Truth

Rule. A credential holder shall compute and report coverage ratios on the definitions set out in the finance documents, from a cash-available-for-debt-service line reconciled to the financial statements, and shall report the minimum ratio over the tested horizon alongside any average; a coverage figure quoted without its definition, its period basis and its minimum is not a coverage statement.

Purpose. Coverage is the number on which debt is sized, distributions are permitted and default is declared. An average conceals the period that binds, and a definition borrowed from a textbook rather than from the facility can flatter or breach a covenant that was never tested.

Scope. All credential holders who size debt, prepare or review compliance certificates, credit submissions, distribution tests, refinancing analyses or restructuring proposals.

Minimum professional requirement. Apply the documented definitions of cash available for debt service and of debt service, including every deduction the documents require; reconcile the cash line to the statements; report the minimum and the average with the binding period identified; state whether the test is historic, forward-looking or both and whose projection it uses; and disclose every adjustment made.

Required evidence. The ratio calculation traceable to a released model version and to source lines; the definition used with a reference to the document in which it appears; the reconciliation to the statements; the period-by-period ratio series; the compliance certificate and its workings.

Decision owner. The finance director or project finance leader who signs the certificate or credit submission; the credit approver for the sizing adopted.

Independent review. Required before financial close, before any certificate on which lock-up or default depends, and at model audit.

Escalation trigger. A computed ratio at or below a covenant level in any period; a definitional difference between the model and the finance documents; an adjustment that materially improves a ratio and has not previously been applied.

Prohibited practice. Quoting an average in place of a period test; including in the cash line items the definition excludes; moving cost out of a tested period; annualising to obscure a seasonal shortfall; presenting a textbook ratio as the covenant ratio.

AI application. AI may compute ratio series across cases, identify the binding period, test sculpting and sizing arithmetic, and generate stress runs and reconciliations for review.

AI restriction. AI must not interpret a covenant definition, decide whether an item belongs in the cash line, certify compliance, or determine debt capacity.

Verification requirement. A competent professional must recompute the ratio for the binding period and at least one other period from source lines, confirm the definition against the executed document, and reconcile the cash line to the statements before certifying or submitting.

● EXTERNAL REFERENCE

IAS 7 Statement of Cash Flows, IFRS Foundation (authoritative accounting standard) — for entities applying IFRS Accounting Standards, the presentation and classification of cash flows against which a modelled cash line is reconciled; it does not define any coverage ratio, which is a matter for the finance documents. Basel framework, Basel Committee on Banking Supervision (illustrative reference — internationally agreed supervisory standards **with no legal force of their own**, applying to banks only as national authorities transpose them) — named for the supervisory context of lenders' credit assessment and monitoring; not relied on here for any requirement. The official publications govern; verify current requirements.

▲ CAUTION

Coverage definitions are contractual rather than statutory; their construction and the consequences of a breach are matters for the governing law of the finance documents and for qualified counsel — see PFL-LAW-10-02.

Related PCI laws. PCI-LAW-F-07; PFL-LAW-01-01; PFL-LAW-06-04; PFL-LAW-10-02; PFL-LAW-15-01.

Related book content. Domain 10, KA 10.1 — Debt capacity and sizing (10.1.1 cash available for debt service; 10.1.2 sizing from coverage); KA 10.2 — The coverage ratios (10.2.1 the period test; 10.2.2 the horizon tests; 10.2.4 reading a ratio set together); 10.A.3 — The reviewer's coverage eye; Domain 15, KA 15.1 — Covenant testing (15.1.4 backward, rolling and forward-looking tests).

Examination relevance. Scenario items presenting an average coverage figure that conceals a failing period, or a cash line built outside the documented definition, for the candidate to detect and correct. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-10-02

Covenant Interpretation

Rule. A credential holder shall apply the covenants, definitions, test dates and cure mechanics set out in the executed finance documents, shall not substitute a market convention, a textbook definition or another transaction's terms, and shall not state a legal conclusion on the meaning or consequence of a covenant — that opinion belongs to qualified counsel.

Purpose. Covenants are how lenders keep a project fixable while options remain. The credential holder's duty is to compute and report faithfully against the documented terms, and to recognise the point at which computation becomes legal construction.

Scope. All credential holders who monitor, model, certify, negotiate or advise on financial, information, positive and negative covenants, distribution lock-up, events of default and cure rights.

Minimum professional requirement. Maintain a covenant register recording, for each covenant, the document and clause in which it appears, its definition set, test dates, thresholds, cure rights and consequences; test on the defined dates using the defined inputs; document any interpretive question and refer it to counsel rather than resolving it in the model; and record every waiver and amendment as a change to both the register and the model.

Required evidence. The covenant register with document references; compliance certificates and their workings; the record of interpretive questions referred and the advice received; the waiver and amendment log with its effect on the register; the covenant dashboard version history.

Decision owner. The finance director or project finance leader for compliance reporting; the lenders' agent for the lenders' position; qualified counsel for interpretation.

Independent review. Required when a covenant position approaches a threshold, before any waiver or amendment request, and whenever a definition changes.

Escalation trigger. A position at or approaching a lock-up or default level; a definitional ambiguity that changes the result; a proposed amendment whose effect on the register has not been assessed; an event that may constitute a default.

Prohibited practice. Computing a covenant on a definition other than the documented one; presenting a market convention as the transaction's requirement; giving a legal opinion on breach, notice or cure; delaying notification of a likely breach to preserve a reporting position; treating a waived condition or covenant as satisfied.

AI application. AI may extract covenant terms and definitions from documents into a register for human confirmation, monitor positions against thresholds, generate early-warning alerts, and draft compliance certificates for review.

AI restriction. AI must not interpret a covenant, determine that a breach has or has not occurred, certify compliance, or advise on cure, waiver or amendment.

Verification requirement. A competent professional must confirm every extracted covenant term against the executed document, re-confirm the register after every amendment, and refer rather than resolve any question of legal meaning.

● EXTERNAL REFERENCE

IAS 1 Presentation of Financial Statements, IFRS Foundation (authoritative accounting standard) — for entities applying IFRS Accounting Standards, the presentation of financial statements, including the basis on which liabilities are classified as current or non-current, which is where a covenant position meets the reported position; **IFRS 18 Presentation and Disclosure in Financial Statements replaces IAS 1 for annual reporting periods beginning on or after 1 January 2027 (earlier application permitted), so confirm which instrument applies to the period being reported.** Reporting classification is not covenant compliance: only the finance documents determine that. Basel framework, Basel Committee on Banking Supervision (illustrative reference — internationally agreed supervisory standards **with no legal force of their own**, applying to banks only as national authorities transpose them) — named for the supervisory context of lenders' covenant monitoring; not relied on here for any requirement. The official publications govern; verify current requirements.

● ⚠ CAUTION

The construction of covenant language, the effect of a breach, notice requirements and the enforceability of cure rights are determined by the governing law of the finance documents; obtain qualified legal advice and never act on a modelled interpretation.

Related PCI laws. PCI-LAW-F-08; PCI-LAW-F-11; PFL-LAW-10-01; PFL-LAW-12-01; PFL-LAW-15-01.

Related book content. Domain 10, KA 10.4 — Covenants, default and cure (10.4.1 covenant types; 10.4.2 distribution lock-up; 10.4.3 events of default and cure rights; 10.4.4 living with covenants); 10.A.1 — Forward-looking tests and whose forecast counts; Domain 15, KA 15.3 — Waiver, cure and amendment.

Examination relevance. Scenario items in which a modelled definition differs from the documented one, or a candidate is asked to opine on whether a breach has occurred, testing the boundary between computation and legal construction. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 11 — Risk identification and allocation

§ PCI LAW

PFL-LAW-11-01

Risk Allocation Honesty

Rule. A credential holder shall allocate each material risk to the party best able to control, absorb or price it, shall record where the risk actually lands once contracts, caps, exclusions, insurance and counterparty credit are read together, and shall not represent a risk as transferred where that reading leaves it with the project.

Purpose. The allocation matrix is the transaction's real structure. A matrix that reads "transferred" where a cap, an exclusion or a weak counterparty leaves the exposure with the project company is worse than no matrix, because it stops anyone looking.

Scope. All credential holders who build or review risk registers and allocation matrices, price risk transfer, negotiate contracts, or rely on an allocation for appraisal, sizing, credit approval or contingency setting.

Minimum professional requirement. Maintain a register at allocation granularity; for each transfer identify the instrument, the cap, the exclusions, the counterparty and its credit standing; compute the residual exposure that survives cap and credit quality; identify gaps between packages and interface risks; price retained risk into contingency and reserves; and keep the register live through construction and operations.

Required evidence. The risk register and allocation matrix with document references; the cap and exclusion analysis; the guarantee sufficiency assessment; the insurance schedule with its exclusions; the residual-risk quantification feeding contingency; the register's version history.

Decision owner. The project finance leader or designated risk owner who signs the allocation; the sanctioning body that accepts the residual position.

Independent review. Required before term sheet, before financial close, when a counterparty's credit standing changes, and when a contract carrying an allocation is amended.

Escalation trigger. Discovery that a risk recorded as transferred is in fact retained; a downgrade affecting a load-bearing guarantee; an interface gap identified after commitment; a realised risk exceeding the provision made for it.

Prohibited practice. Recording a risk as transferred without naming the instrument and its cap; valuing a guarantee without regard to the guarantor's credit standing; presenting insurance as cover without reading its exclusions; suppressing a known interface gap; counting one mitigation against several risks.

AI application. AI may assemble registers from the document set, extract caps and exclusions for confirmation, detect risks addressed in no document, and simulate the distribution of retained risk.

AI restriction. AI must not decide an allocation, conclude that a risk is transferred, judge a guarantee sufficient, or approve a residual risk position.

Verification requirement. A competent professional must confirm each transfer against the executed contract, test the sufficiency arithmetic independently, and confirm the register's completeness against the full document set rather than against a summary.

● **EXTERNAL REFERENCE**

ISO 31000 Risk management — Guidelines (international standard) — the risk-management process and the treatment of uncertainty. FIDIC suite of contract forms, International Federation of Consulting Engineers (contract framework) — standard forms widely used as the basis for negotiated construction risk allocation; the executed contract governs. IFC Performance Standards and the Equator Principles (voluntary frameworks) — environmental and social risk expectations adopted by many lenders and often carried into project documents. The official publications govern; verify current requirements.

▲ **CAUTION**

The enforceability of caps, liquidated damages, indemnities and exclusion clauses varies with governing law, as does insurance regulation; obtain qualified legal advice before relying on a transfer as effective.

Related PCI laws. PCI-LAW-F-11; PFL-LAW-05-01; PFL-LAW-09-01; PFL-LAW-12-01; PFL-LAW-14-01.

Related book content. Domain 11, KA 11.1 — Construction and completion risk (11.1.2 the two grounds for transfer; 11.1.3 pricing the transfer); KA 11.2 — Market risks and operations (11.2.2 pass-through as a coverage multiplier); KA 11.3 — Counterparty, political, currency and force majeure (11.3.3 the counterparty risk inside the allocation); KA 11.4 — Environmental, social, technology, cyber and AI model risk (11.4.3 AI model risk as a register line); Domain 12, KA 12.3 — Guarantee sufficiency; KA 12.4 — The allocation matrix as a document map.

Examination relevance. Scenario items in which a capped, excluded or weakly guaranteed transfer is presented as complete, testing residual-exposure reasoning and register discipline. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 12 — Contracts and transaction structure

§ PCI LAW

PFL-LAW-12-01

The Advice Boundary

Rule. A credential holder shall not give legal, tax, accounting, regulatory or insurance advice, shall confine their work to the commercial and financial analysis within their competence, and shall obtain written advice from an adviser qualified in the relevant jurisdiction before any treatment, contractual position or structure is adopted or represented as correct.

Purpose. Project finance rests on jurisdictional facts. A modelled tax rate is a commercial assumption, not a tax opinion; a summarised clause is a reading, not a construction. Presenting either as advice transfers risk to a client who believes it has been advised.

Scope. All credential holders in every role, including those qualified in another discipline — the PFL-AI certification scope does not extend any licence held elsewhere.

Minimum professional requirement. Identify at the outset which questions require qualified advice; state on every deliverable that legal, tax and accounting treatments are assumptions pending advice; obtain written advice identifying adviser, entity, jurisdiction, scope and date before a treatment is adopted; carry that advice into the model and the assumption register; and re-confirm when the structure, entity, jurisdiction or law changes.

Required evidence. The register of advice obtained with adviser, scope, jurisdiction, entity and date; the list of assumptions flagged as pending advice; the deliverable's stated limitation; correspondence recording each referral; the assumption-register lines citing the advice.

Decision owner. The credential holder for recognising the boundary and referring; the client or employer for instructing the adviser; the qualified adviser for the advice itself.

Independent review. Required before financial close and before any transaction document, information memorandum, certificate or filing represents a tax, accounting or legal position.

Escalation trigger. An instruction to model or state a treatment without advice; discovery that a relied-upon treatment was never advised; a change of law, entity, structure or jurisdiction affecting advice already given; advice inconsistent with what the model assumes.

Prohibited practice. Stating a tax, legal or accounting conclusion as fact; carrying a treatment across from another transaction or jurisdiction; relying on general commentary or an AI summary in place of advice for the specific entity and structure; describing an unadvised assumption as a treatment.

AI application. AI may locate material for a qualified adviser, draft the questions on which advice is sought, compare structures for discussion, and summarise documents for the professional's own understanding.

AI restriction. AI must not give legal, tax, accounting or regulatory advice, determine a treatment, construe a contract, or stand in place of a qualified adviser.

Verification requirement. Any AI-produced summary of a document or treatment must be checked against the source instrument by a competent professional and must never be used as advice; every treatment relied upon must be traceable to written advice from a qualified adviser.

● EXTERNAL REFERENCE

IAS 12 Income Taxes, IFRS Foundation (authoritative accounting standard) — for entities applying IFRS Accounting Standards, the accounting for current and deferred tax; it governs financial reporting only, never the tax position in any jurisdiction. OECD Model Tax Convention on Income and on Capital (illustrative reference — a model text, updated periodically, on which many bilateral tax treaties are negotiated; **it is not law in any jurisdiction** and only the executed treaty and domestic law bind). ISO/IEC 17024 (international standard) — competence-based certification of persons, named for the discipline of defining and bounding a certification's scope; adoption is voluntary unless a law or contract imports it, and **no accreditation to, or certification against, this standard is claimed by PCI through this reference**. The official publications govern; verify current requirements.

● ⚠ CAUTION

Every matter named in this law is jurisdiction-specific: tax residence, withholding, deductibility, indirect taxes, stamp duties, licensing, security perfection, insurance regulation and accounting treatment all differ and all change. Advice must be obtained for the specific entity, structure and date, and re-confirmed when any of those change.

Related PCI laws. PCI-LAW-F-01; PCI-LAW-F-08; PCI-LAW-F-14; PFL-LAW-06-03; PFL-LAW-10-02; PFL-LAW-16-02.

Related book content. Domain 12, KA 12.1 — EPC and O&M; KA 12.2 — Offtake, concession, supply and interface agreements; KA 12.4 — Risk allocation, claims and change (commercial purpose only; jurisdiction-specific matters referred to qualified counsel); Domain 2, KA 2.3 — Project-relevant

treatments; Domain 6, KA 6.2 — Depreciation, tax allowances and the line most often modelled wrongly; Domain 13, KA 13.1 — The diligence streams.

Examination relevance. Scenario items in which a candidate is pressed for a tax or contractual conclusion under time pressure, testing recognition of the boundary, the referral and what may be stated meanwhile. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 13 — Due diligence and financial close

§ PCI LAW

PFL-LAW-13-01

Independence of Review

Rule. A model audit, diligence review or lender's adviser report relied upon by any party other than its author's own team must be performed by a person independent of the work reviewed and of its outcome; a credential holder shall not review their own work, and shall not accept a review engagement whose fee, continuing mandate or benefit depends on the conclusion reached.

Purpose. A review is worth exactly its independence. Reviews performed by the builder, or by a party rewarded for a comfortable answer, deliver the appearance of assurance to third parties who cannot see the arrangement and who price the transaction as though assurance existed.

Scope. Model audit, every diligence stream, lenders' technical, financial, insurance and market advisers, internal second-line review, and any credential holder asked for an opinion on which another party will rely.

Minimum professional requirement. Confirm independence in writing before accepting; decline where the reviewer built or materially contributed to the work, reports to its author, or holds an interest in the outcome; agree scope in writing including what is not covered; report findings by class rather than as a single total; report every finding, including those the engaging party would prefer omitted; and retain the working papers.

Required evidence. The independence confirmation; the scope and reliance letter; the findings register with classification and status; the working papers and test record; the final report and its distribution list; the record of any disputed finding and its resolution.

Decision owner. The reviewer for the review's conclusions; the engaging party for scope and reliance arrangements.

Independent review. The review is itself the independent step; where a conclusion is challenged or a finding is closed without correction, a second reviewer independent of the first must consider the point.

Escalation trigger. Pressure to reclassify, downgrade or omit a finding; a scope limitation that prevents an opinion; discovery that the reviewer is not independent; a finding closed without either correction or documented acceptance.

Prohibited practice. Auditing a model one built or materially contributed to; accepting a success fee or contingent benefit tied to the outcome; issuing a report that omits known findings; allowing the reviewed party to edit the findings; describing a limited review as a full audit.

AI application. AI may run structural scans, generate test cases, compare versions, and draft the findings register for the reviewer's confirmation.

AI restriction. AI must not be the reviewer, sign a review report, close a finding, or supply the independence this law requires.

Verification requirement. The reviewer must confirm every machine-produced finding individually before reporting it, record the verification sample size for any machine-produced list, and re-perform a defined portion of testing manually.

● **EXTERNAL REFERENCE**

IESBA International Code of Ethics for Professional Accountants (including International Independence Standards) (professional guidance) — an international ethics code addressing objectivity, independence and the threats to them, issued by the International Ethics Standards Board for Accountants; it is **binding only where a professional body, regulator or engagement has adopted it**, and PCI credential holders who are not subject to it are not made subject to it by this reference. ISO/IEC 17024 (international standard) — impartiality in the certification of persons; adoption is voluntary unless a law or contract imports it, and **no accreditation to, or certification against, this standard is claimed by PCI through this reference**. Equator Principles (voluntary framework) — review processes for environmental and social risk adopted voluntarily by participating financial institutions; not legislation. The official publications govern; verify current requirements.

△ **CAUTION**

Statutory audit, licensing and professional-body independence rules differ by jurisdiction and may impose stricter requirements than this law; where a review is a regulated engagement, those requirements govern — obtain local advice.

Related PCI laws. PCI-LAW-F-10; PCI-LAW-F-13; PFL-LAW-01-02; PFL-LAW-06-05; PFL-LAW-16-02.

Related book content. Domain 13, KA 13.2 — Model audit (13.2.1 scope and what the audit is not; 13.2.2 findings by class, not totalled; 13.2.4 closing findings out); KA 13.1 — The diligence streams; Domain 1, KA 1.3 — Conflicts and independence; Domain 6, KA 6.4 — Model audit, governance and its economics.

Examination relevance. Scenario items in which the model's builder is asked to audit it, or a finding is pressed down before issue, testing declination, scope discipline and reporting. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ **PCI LAW**

PFL-LAW-13-02

Conditions Precedent

Rule. A credential holder shall treat a condition precedent as satisfied only when the evidence the finance documents require has been delivered and accepted by the party entitled to it, shall record a waived or deferred condition as waived or deferred and never as satisfied, and shall not certify or report that conditions are met while any remains outstanding.

Purpose. The condition schedule is the bankability list made contractual: it is the last point at which the parties can decline to proceed. A condition recorded as met on the strength of an expectation removes the protection every party negotiated for.

Scope. All credential holders who compile, track, certify or rely upon condition schedules for first drawing, subsequent drawings, financial close, completion or the release of security.

Minimum professional requirement. Maintain the schedule as a dependency network with owner, required evidence, status and date for each condition; identify the critical path through it; hold status

against delivered evidence rather than intention; record waivers, deferrals and post-close undertakings separately with their long-stop dates; and report the outstanding set honestly to all parties before close.

Required evidence. The condition schedule with evidence references and dates; the evidence pack; the waiver and deferral log with conditions and expiry dates; the satisfaction certificate; the correspondence recording acceptance.

Decision owner. The party entitled to the benefit of the condition — usually the lenders acting through their agent — decides satisfaction or waiver; the borrower's project finance leader owns the accuracy of the status reported.

Independent review. Required before the satisfaction certificate is issued and before any drawing that depends on a condition recorded as outstanding, waived or deferred.

Escalation trigger. A condition reported satisfied without its evidence; a waiver granted with no recorded condition or expiry; a long-stop date at risk; a post-close undertaking approaching its deadline unmet.

Prohibited practice. Reporting a condition satisfied on an undertaking to deliver; back-dating evidence; describing a waived condition as satisfied; omitting a deferred condition from the close report; drawing against a condition the entitled party has not accepted.

AI application. AI may track the schedule, extract required conditions from documents into a checklist for confirmation, monitor the dependency network and its critical path, and generate status reports.

AI restriction. AI must not determine that a condition is satisfied, grant or record a waiver, or issue a satisfaction certificate.

Verification requirement. A competent professional must match every condition to its specific evidence document and to the acceptance record before its status changes, and must reconcile any AI-extracted condition list to the executed documents.

◆ EXTERNAL REFERENCE

ISO 15489 Information and documentation — Records management (international standard) — the capture and integrity of records evidencing satisfaction. IFC Performance Standards and the Equator Principles (voluntary frameworks) — environmental and social requirements that participating lenders frequently carry into conditions and undertakings. The official publications govern; verify current requirements.

▲ CAUTION

What constitutes valid evidence of corporate authority, a permit, a land right, an insurance endorsement or a perfected security interest is determined by local law, as is the effect of a legal opinion delivered at close; obtain qualified local legal advice.

Related PCI laws. PCI-LAW-F-05; PFL-LAW-05-01; PFL-LAW-13-03; PFL-LAW-14-01.

Related book content. Domain 13, KA 13.3 — Conditions precedent and documentation (13.3.1 the condition set and its categories; 13.3.2 the conjunction with a critical path; 13.3.5 waivers, long-stop dates and post-close undertakings); Domain 5, 5.A.2 — Conditions precedent: the bankability list made contractual; Domain 14, KA 14.1 — The draw request and the conditions to each drawing.

Examination relevance. Scenario items in which close is pressed with conditions outstanding or waived, testing accurate status reporting, waiver recording and escalation. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-13-03

Financial-Close Evidence

Rule. At financial close a credential holder shall ensure that the executed document set, the agreed and locked base-case model version, the final sources-and-uses statement, the condition-satisfaction record and the funds-flow instruction are captured as one complete, retained and identifiable record, and shall not treat a transaction as closed on an incomplete or unretained record.

Purpose. Close is the moment the transaction's terms become fixed. Every later question — a covenant test, a claim, a refinancing, a dispute, a restructuring, a handback — is answered from the close record or is not answered at all.

Scope. All credential holders who manage, advise on or participate in financial close, and all who later rely upon the close record.

Minimum professional requirement. Assemble the closing index and document set; identify the locked model version and apply an integrity control to it; record the final sources and uses; retain the condition evidence and every waiver; retain the funds-flow instruction and the payment confirmations; record the time of effectiveness; and assign retention responsibility and period.

Required evidence. The closing index; the executed documents; the locked model with its version identifier and integrity control; the final sources-and-uses statement; the satisfaction certificate and waiver log; the funds-flow statement and confirmations; the retention record.

Decision owner. The transaction lead for the completeness of the close record; the borrower or its agent for its retention and controlled access.

Independent review. Required as a completeness check after close and before archiving, and whenever the record is relied upon in a dispute, refinancing or restructuring.

Escalation trigger. A document executed but not captured; a model version quoted at close that cannot be identified; a payment made that is not on the funds-flow statement; any indication that the record has been altered after close.

Prohibited practice. Declaring close with an incomplete index; substituting a later model for the agreed version without recording the substitution; destroying records subject to a retention obligation; storing the record where the retention or confidentiality obligation cannot be met.

AI application. AI may index the document set, cross-check the index against the executed documents, extract key terms into a summary for confirmation, and check the funds-flow arithmetic.

AI restriction. AI must not declare the record complete, certify that close has occurred, or determine what must be retained.

Verification requirement. A competent professional must confirm the index against the executed documents item by item, confirm that the identified model version is the one quoted in the credit decision, and confirm the retention arrangements before the record is archived.

◆ EXTERNAL REFERENCE

ISO 15489 Information and documentation — Records management (international standard) — capture, integrity, retention and disposition of records evidencing a transaction. ISO/IEC 27001 Information security management systems (international standard) — controls for the integrity of and access to the closing record. The official publications govern; verify current requirements.

⚠ CAUTION

Retention periods, acceptable evidential form (originals, counterparts, electronic execution) and data-protection constraints differ by jurisdiction; obtain local legal advice before setting or applying a retention and storage arrangement.

Related PCI laws. PCI-LAW-F-05; PCI-LAW-F-12; PFL-LAW-06-05; PFL-LAW-13-02; PFL-LAW-14-02.

Related book content. Domain 13, KA 13.4 — Syndication and financial close (13.4.5 signing, close and funds flow); KA 13.3 — The close-cost budget and sources and uses; KA 13.1 — The data room and the diligence trail; Domain 14, KA 14.1 — The sources-and-uses statement as a control document.

Examination relevance. Scenario items in which a later question cannot be answered because the close record is incomplete, testing what must be captured, by whom and for how long. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 14 — Construction monitoring and drawdown

§ PCI LAW

PFL-LAW-14-01

Drawdown Integrity

Rule. A credential holder shall support every draw request with certified evidence of the value being funded, a current cost-to-complete demonstrating that the project remains in balance, and confirmation that the conditions to that drawing are satisfied; and shall not request, certify or approve a drawing for work not performed, for costs not incurred or evidenced, or while the project is out of balance without disclosing it.

Purpose. Drawdown is where the financing meets the construction. A draw request is an arithmetic claim, an evidential claim and a representation, and it is on the representation that a monitoring relationship is actually conducted.

Scope. Borrowers' and sponsors' finance teams, lenders' staff and their technical advisers, and every credential holder who prepares, certifies, checks or approves draw requests, contingency draws or equity contribution certificates.

Minimum professional requirement. Build the request from certified value with retention and advance recovery applied; attach the certification the documents require; produce a cost-to-complete from the current forecast and reconcile it to the project controls estimate at completion; demonstrate that remaining commitments cover it; confirm that no default is continuing and that the representations remain true; and disclose every change in forecast since the last request.

Required evidence. The draw request and its build-up; the independent engineer's or technical adviser's certificate; the cost-to-complete and in-balance test; the contingency position and approval for any contingency draw; the underlying valuations and invoices; the record of who made each representation.

Decision owner. The borrower's authorised signatory for the request and its representations; the lenders' agent, on the technical adviser's certificate, for the advance.

Independent review. Required to the extent the finance documents require certification for each drawing, and specifically before any contingency draw and wherever the in-balance test is close.

Escalation trigger. A cost-to-complete exceeding remaining commitments; a certificate refused or qualified; a variation not yet reflected in the forecast; funding sought for work whose value or entitlement is disputed.

Prohibited practice. Certifying value for work not in place; funding an invoice already funded; drawing to build cash outside the documented purposes; applying contingency without the required approval; presenting an out-of-balance position as in balance by deferring a known cost.

AI application. AI may assemble draw requests from certification and cost data, reconcile them to the sources-and-uses statement, detect duplicate or out-of-sequence claims, and recompute cost-to-complete from project controls data.

AI restriction. AI must not certify value or progress, make or generate the representations in a draw request, approve a drawing, or determine that the project is in balance.

Verification requirement. A competent professional must confirm certified quantities against the certificate, check the arithmetic chain independently, and reconcile the lender's cost-to-complete to the project controls estimate at completion, explaining every difference.

● EXTERNAL REFERENCE

FIDIC suite of contract forms, International Federation of Consulting Engineers (contract framework) — standard forms under which interim certification and payment mechanisms are commonly structured; the executed contract governs. ISO 15489 (international standard) — records management for the certification and payment record. The official publications govern; verify current requirements.

▲ CAUTION

Construction payment legislation, retention rules, security-of-payment regimes and lien or priority rules affect certification, payment and recovery, and differ by jurisdiction; obtain local legal advice.

Related PCI laws. PCI-LAW-F-05; PCI-LAW-F-07; PFL-LAW-11-01; PFL-LAW-13-02; PFL-LAW-14-02.

Related book content. Domain 14, KA 14.1 — Sources and uses, draw requests and conditions (14.1.2 the draw request); KA 14.2 — Cost-to-complete and contingency draw (14.2.1 the lender's cost-to-complete; 14.2.3 the in-balance condition and the cash call); KA 14.3 — Progress certification and change control; Domain 8, KA 8.4 — Cost to complete and the funds sufficiency test.

Examination relevance. Scenario items in which a draw is prepared while the cost-to-complete has moved or a certificate is qualified, testing the representations, disclosure and escalation. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-14-02

Funds-Flow Control

Rule. Project funds shall move only through the accounts, in the order and for the purposes the finance documents specify, on instructions authorised by named signatories under segregation of duties; a credential holder shall not initiate, approve or conceal a payment outside the documented funds flow.

Purpose. The funds flow is the transaction's plumbing and its principal fraud surface. Money that leaves the accounts in the wrong order, to the wrong purpose or to the wrong payee is rarely recovered, and payment-instruction fraud is aimed precisely at close day and at drawdown day.

Scope. All credential holders involved in account establishment, close-day funds flow, construction payments, operating waterfall payments, reserve movements and distributions.

Minimum professional requirement. Maintain the account map and mandates; require dual authorisation with preparation separated from approval; verify payee details through a channel independent of the instruction that provided them; execute close-day movements against a single agreed funds-flow statement; reconcile actual movements to sources and uses; and report every exception.

Required evidence. The account map and bank mandates; the funds-flow statement and payment confirmations; payment authorisations identifying each signatory; bank reconciliations; payee verification records; the exception log and its closure record.

Decision owner. The authorised signatories for each payment; the finance director for the control design; the account bank or agent for operating the accounts as instructed.

Independent review. Required at account establishment, before close-day funds flow, and periodically over payment controls during construction and operations.

Escalation trigger. A payment instruction that varies from the funds-flow statement; a request to change bank details; an account operating outside its mandate; an unexplained reconciliation difference.

Prohibited practice. Single-signature authorisation of project payments; changing payee details on an emailed request without independent verification; paying out of waterfall order; using project accounts for unrelated purposes; splitting payments to stay below an authorisation threshold.

AI application. AI may reconcile movements to the sources-and-uses statement, detect anomalous or duplicate payments, monitor waterfall order, and draft exception reports for review.

AI restriction. AI must not authorise or release a payment, amend payee details, act as a signatory, or close an exception.

Verification requirement. A competent professional must confirm every payment against the funds-flow statement or waterfall and against the authorising record; payee verification must be performed through an independent channel and evidenced; AI-flagged exceptions must be confirmed by a person before closure.

● EXTERNAL REFERENCE

ISO/IEC 27001 Information security management systems (international standard) — controls relevant to the integrity of payment instructions and resistance to interception and impersonation. COSO Internal Control — Integrated Framework (voluntary framework) — authorisation, segregation of duties and reconciliation as control activities. The official publications govern; verify current requirements.

▲ CAUTION

Account operation, payment-services regulation, sanctions screening and anti-money-laundering obligations are jurisdiction-specific and carry legal consequences for individuals as well as institutions; obtain local legal and compliance advice.

Related PCI laws. PCI-LAW-F-05; PCI-LAW-F-09; PFL-LAW-13-03; PFL-LAW-14-01; PFL-LAW-15-01.

Related book content. Domain 14, KA 14.1 — Sources and uses, draw requests and conditions (14.1.1 the sources-and-uses statement as a control document; 14.1.3 funding order); Domain 13, KA 13.4 — Signing, close and funds flow; Domain 15, KA 15.2 — The operating waterfall in priority order; reserve top-ups and the block account.

Examination relevance. Scenario items involving a late change of payee details or a payment out of waterfall order at close, testing verification, authorisation and escalation. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 15 — Operations, performance and restructuring

§ PCI LAW

PFL-LAW-15-01

Distribution Restriction

Rule. A credential holder shall permit, certify or make a distribution only when every distribution condition in the finance documents is satisfied at the test date on the documented basis — coverage tests, reserve balances, no default continuing and any forward-looking test — and shall not release cash to shareholders ahead of a prior claim in the waterfall or during a lock-up.

Purpose. Distribution restrictions are how lenders keep cash in the project while it may still be needed. Once distributed, cash is gone; the restriction is the only control that operates before the loss, rather than after it.

Scope. All credential holders who prepare, certify or approve distributions, operating waterfall payments, reserve movements and payments on shareholder instruments, including subordinated interest and principal and fees payable to shareholders.

Minimum professional requirement. Run the waterfall in documented priority order with each tier floored at nil; confirm every reserve at its required level; compute each distribution test on the documented definitions, including any forward-looking test and the projection it uses; confirm that no default or potential default is continuing; obtain the certification the documents require; and record the distributable amount and its derivation.

Required evidence. The waterfall computation for the period; reserve balance confirmations; the distribution test calculations with the definitions applied; the distribution or compliance certificate; the board resolution and the accounting basis relied upon; the payment record.

Decision owner. The project company's board for the decision to distribute; the finance director or project finance leader for the certificate; the lenders' agent where consent is required.

Independent review. Required where a test is close to its threshold, where a forward-looking test relies on a revised projection, and after any waiver or amendment affecting the tests.

Escalation trigger. A distribution proposed while a test fails or a default may be continuing; a reserve below its required level; a forward-looking test dependent on assumptions changed since the last certificate; pressure to distribute ahead of a prior waterfall claim.

Prohibited practice. Distributing during a lock-up; paying shareholder instruments ahead of their waterfall position; funding a distribution by deferring a required reserve top-up or maintenance spend; re-cutting a projection so that a forward-looking test passes; treating a shareholder loan repayment as outside the restrictions when the documents include it.

AI application. AI may compute the waterfall and the tests, monitor reserve balances, forecast lock-up risk under stress, and draft distribution certificates for review.

AI restriction. AI must not determine that distribution conditions are met, approve a distribution, certify compliance, or set the assumptions of a forward-looking test.

Verification requirement. A competent professional must recompute the waterfall and each distribution test from the source cash line for the test period, confirm the definitions against the executed documents, and confirm the no-default position before certifying.

◆ EXTERNAL REFERENCE

IAS 1 Presentation of Financial Statements, IFRS Foundation (authoritative accounting standard) — for entities applying IFRS Accounting Standards, presentation of financial statements including amounts recognised as distributions to owners; it does not determine what an entity may lawfully distribute, which is a question of company and insolvency law. **IFRS 18 Presentation and Disclosure in Financial Statements replaces IAS 1 for annual reporting periods beginning on or after 1 January 2027 (earlier application permitted), so confirm which instrument**

applies to the period being reported. G20/OECD Principles of Corporate Governance (voluntary framework) — non-binding intergovernmental principles, adopted as an OECD Council Recommendation, on board responsibilities and shareholder rights within which a distribution decision is taken; not legislation. The official publications govern; verify current requirements.

⚠ **CAUTION**

Lawful distribution depends on company-law tests of distributable profits or reserves and on solvency, and is affected by withholding tax and exchange control; satisfying the finance documents is not the same as being lawfully able to distribute — obtain local legal, accounting and tax advice before any distribution.

Related PCI laws. PCI-LAW-F-11; PFL-LAW-01-01; PFL-LAW-10-01; PFL-LAW-10-02; PFL-LAW-14-02.

Related book content. Domain 15, KA 15.2 — The cash waterfall in operation (15.2.1 the operating waterfall in priority order; 15.2.2 reserve top-ups and the block account; 15.2.3 the distributable amount that falls out); Domain 10, KA 10.4 — Distribution lock-up; Domain 2, 2.A.4 — Distributable reserves, the constraint that is not in the waterfall.

Examination relevance. Scenario items in which a distribution is proposed with a reserve short or a forward-looking test freshly re-cut, testing the tests applied, the certificate given and the escalation. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Domain 16 — Data, automation and responsible AI in finance

§ PCI LAW

PFL-LAW-16-01

Transaction Confidentiality

Rule. A credential holder shall protect confidential transaction, counterparty and personal information, shall use it only for the purpose for which it was provided, and shall not place it into an AI tool, external service or storage location that has not been authorised for that classification of information.

Purpose. Project finance runs on information that is commercially sensitive, sometimes price-sensitive and often personal. A deployment choice made casually can disclose an entire transaction in a single prompt, and the disclosure cannot be withdrawn.

Scope. All credential holders handling deal information, diligence materials, models, counterparty data and personal data, and every tool or service used with it — AI assistants, cloud storage, translation, extraction and analysis services.

Minimum professional requirement. Classify information before use; know and observe the deployment authorised for each classification, including whether inputs are retained, reused or processed outside a permitted region; observe non-disclosure obligations and information barriers; minimise personal data; apply insider-information and wall-crossing procedures where they apply; and report any suspected disclosure immediately.

Required evidence. The information classification scheme and the list of tools authorised for each classification; the non-disclosure register and wall-crossing records; access logs; incident reports and their closure.

Decision owner. The information owner — usually the client or employer — for permitted use; the credential holder for their own handling; the organisation's security or compliance function for authorising tools.

Independent review. Required before a new tool or service is used with confidential deal information, and after any suspected or actual disclosure.

Escalation trigger. Confidential information entering an unauthorised tool or service; a suspected or actual disclosure; a request to use information outside its permitted purpose; a change in a tool's terms such that inputs may be retained or reused.

Prohibited practice. Pasting confidential or personal information into a consumer AI service or any unapproved tool; retaining deal information after an engagement where return or destruction was agreed; using deal information for personal advantage or for another client; disclosing a counterparty's terms as a comparable without permission.

AI application. AI may be used on confidential information only within an authorised deployment, where it may assist with redaction, classification, extraction and summarisation.

AI restriction. AI must not decide the classification of information, authorise a tool or deployment, or waive a confidentiality obligation; no AI service may be used with confidential information absent an authorisation covering that classification.

Verification requirement. A competent professional must verify that an authorisation covering the tool and the classification exists before use, verify any redaction applied, and confirm that outputs do not reproduce confidential material outside the permitted circle.

● EXTERNAL REFERENCE

ISO/IEC 27001 Information security management systems (international standard) — the management system and controls for protecting information. ISO/IEC 42001 Artificial intelligence — Management system (international standard) — organisational management of AI systems, including controls over the data used with them. The official publications govern; verify current requirements.

⚠ CAUTION

Data-protection, banking-secrecy, market-abuse and cross-border transfer laws differ by jurisdiction and carry regulatory and, in some places, criminal consequences; obtain local legal advice before moving deal or personal data across borders or into external services.

Related PCI laws. PCI-LAW-F-09; PCI-LAW-F-12; PFL-LAW-01-02; PFL-LAW-06-04; PFL-LAW-16-03.

Related book content. Domain 16, KA 16.4 — Privacy, cybersecurity, human approval and AI governance (16.4.1 confidentiality, privacy and the deployment choice; 16.4.2 cybersecurity of an automated finance function); KA 16.2 — Document review and the load-bearing subset; Domain 13, KA 13.1 — The data room and the diligence trail.

Examination relevance. Scenario items in which deal documents are put through an unapproved tool under deadline pressure, testing classification discipline, authorisation and incident handling. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-16-02

AI-Assisted Model Verification

Rule. Where AI builds, edits, checks, extracts for or interprets any part of a financial model or its outputs, the professional relying on that work shall verify it — by recomputation, by regression against independently verified figures and by tracing to source — before it is used; machine checking is additive to professional review and never substitutive.

Purpose. AI scans a workbook faster and more consistently than a person, and misses precisely the errors that cost most: the definitional ones — whether the cash line matches the facility's definition, whether the tax treatment is the jurisdiction's, whether the waterfall follows the drafted priority. A model machine-checked and not reviewed carries the appearance of assurance without its substance.

Scope. All AI-assisted modelling work: structure and formula scanning, version diffing, test generation, documentation drafting, forecast automation, anomaly detection and document extraction feeding a model or a report.

Minimum professional requirement. Maintain a regression suite of independently verified figures and rerun it after every edit, machine or human, explaining each movement before acceptance; confirm each machine-raised finding individually and record the sample size; recompute at least one construction period and one operating period per released version by independent means; and never rely on a machine scan to establish that a definitional treatment is correct.

Required evidence. The regression suite and its results per version; the record of findings raised, confirmed or rejected, with sample size; the manual recomputation record; the AI-use record for the model, stating tool, task and version.

Decision owner. The professional who relies on the output owns its verification; the model owner owns the model.

Independent review. Required before a machine-assisted model enters decision-grade use, and at the revalidation interval set for any model tiered as high-consequence in the model inventory.

Escalation trigger. A regression figure moving without explanation; a machine-raised finding reported without confirmation; an AI edit found in the authoritative file with no change-log entry; a tool showing systematic error in a decision-grade role.

Prohibited practice. Reporting a machine-produced finding list as verified without confirming its items; treating a clean machine scan as evidence of correctness; substituting an AI pre-check for a required model audit; quoting from a model whose checks are failing, whatever produced it.

AI application. AI may scan, diff, generate adversarial tests, draft documentation and cross-check one method against another — as an aid to verification, never as its discharge.

AI restriction. AI must not verify its own output as the sole check, declare a model correct, determine a definitional treatment, close a finding, or discharge the professional's verification duty.

Verification requirement. Verification must be performed by a professional competent in project financial modelling, at a depth proportionate to consequence, and recorded; a stated verification sample size applies to every machine-produced finding list.

EXTERNAL REFERENCE

ISO/IEC 42001 Artificial intelligence — Management system (international standard) — organisational controls for the responsible use of AI. ISO/IEC 23894 Artificial intelligence — Guidance on risk management (international standard) — managing risks arising from AI systems. NIST AI Risk Management Framework (voluntary framework) — trustworthiness characteristics and risk treatment; a voluntary framework, not a regulation. Supervisory Guidance on Model Risk Management (SR 11-7), issued by United States banking supervisors (public supervisory guidance) — expectations for model development, validation, use and governance in supervised institutions in that jurisdiction. The official publications govern; verify current requirements.

CAUTION

- AI-specific regulation is emerging and uneven, and financial-sector model-risk expectations differ by jurisdiction and by institution type; obtain local legal and compliance advice on obligations attaching to AI use in regulated work.

Related PCI laws. PCI-LAW-F-02; PFL-LAW-06-01; PFL-LAW-06-05; PFL-LAW-13-01; PFL-LAW-16-03.

Related book content. Domain 16, KA 16.2 — Model assistance and the verification that must replace the build (16.2.3); KA 16.3 — Explainability, validation, bias and model risk (16.3.2 validation and test cases; 16.3.4 inventory, tiering, revalidation); Domain 6, KA 6.4 — AI-assisted modelling controls (6.4.4); Domain 13, KA 13.2 — Model audit.

Examination relevance. Scenario items presenting a machine-scanned model with a definitional error intact, testing what the scan can and cannot establish and what verification remains outstanding. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

§ PCI LAW

PFL-LAW-16-03

Human Approval

Rule. Every financial decision, certification, representation and external report within a credential holder's scope must be approved by a named, competent and authorised human being before it takes effect; a credential holder shall not design or operate a pipeline in which an AI output becomes a payment, a certificate, a representation to a lender or a published figure without human approval.

Purpose. Approval is where accountability attaches. Automation without an approval boundary launders accountability, and certification carries consequences to third parties: nothing in an automated pipeline may generate a representation.

Scope. All workflows — manual, automated or agentic — producing draw requests, compliance and distribution certificates, lender reports, board and investment papers, payments, published financial information and advice.

Minimum professional requirement. Define the approver for every decision point and tier approval by consequence, with a written mandate for any delegation naming what may move and within what bounds; ensure the approver has the competence, information and time to engage substantively; distinguish review, approval and certification and record which was given; hold decision-grade automated outputs for approval rather than releasing them; and record identity, date and basis.

Required evidence. The approval matrix with tiers and written delegated mandates; sign-off records stating identity, date, level and basis; pipeline design documentation showing every approval gate; the record of what the approver was shown.

Decision owner. The named human approver for each decision; the process owner for the approval architecture.

Independent review. Required when automation is introduced or extended into a decision path, and periodically to test that approvals are substantive rather than pass-through.

Escalation trigger. An output that took effect without approval; an approver acting outside their mandate or competence; systematic pass-through of AI output; a delegation operating without a written mandate.

Prohibited practice. Configuring a system to release decision-grade outputs automatically; recording an AI agent or a shared account as approver; certifying on the basis of an output one has not reviewed; describing an undocumented delegation as a tier of approval.

AI application. AI may prepare complete approval packages, route items to the correct tier, monitor items awaiting approval, and check that an approval carries the authority the matrix requires.

AI restriction. AI must not approve, certify, sign or make a representation, and must not be recorded as the approver of record under any circumstances.

Verification requirement. A competent professional must periodically test sampled approvals for substantive engagement and audit automated pipelines for undeclared automatic-release paths; every certification must be traceable to the human who made it.

EXTERNAL REFERENCE

ISO/IEC 42001 Artificial intelligence — Management system (international standard) — human oversight within the management of AI systems. OECD AI Principles (voluntary framework) — human-centred values, oversight and accountability for AI outcomes; not legislation. European Union Artificial Intelligence Act (legislation of the European Union) — a risk-tiered legal framework for AI systems whose application depends on role, classification and timing; it binds only where it applies, and legal advice should be obtained. COSO Internal Control — Integrated Framework (voluntary framework) — authorisation and approval as control activities. The official publications govern; verify current requirements.

CAUTION

Some jurisdictions regulate automated decision-making affecting individuals and require human involvement by law; obtain local legal advice for automated workflows touching personal data or producing regulated representations.

Related PCI laws. PCI-LAW-F-01; PCI-LAW-F-03; PCI-LAW-F-04; PFL-LAW-14-01; PFL-LAW-16-02.

Related book content. Domain 16, KA 16.4 — Privacy, cybersecurity, human approval and AI governance (16.4.3 human approval — what it is and what it costs; 16.4.4 the AI governance frame); 16.A.1 — Agentic automation and the authorisation boundary; Domain 14, KA 14.1 — The draw request and its representations.

Examination relevance. Scenario items presenting an automated pipeline that issues a certificate or payment without a human gate, testing approval architecture, tiering and the certification boundary. No live examination content is exposed.

Consequences of breach. Failure of the associated examination competency; refusal, suspension or revocation of the PFL-AI credential; mandatory remediation and referral to PCI's conduct process, within PCI's authority only.

Index of PFL-AI Professional Laws

ID	OFFICIAL TITLE	ANCHOR DOMAIN	RELATED EXTERNAL REFERENCES
PFL-LAW-01-01	Cash Before Appearance	Domain 1 — Foundations of project finance leadership	IFRS Conceptual Framework (not a standard); IAS 7
PFL-LAW-01-02	Conflict Disclosure and the Two-Hat Rule	Domain 1 — Foundations of project finance leadership	ISO/IEC 17024; G20/OECD Principles of Corporate Governance
PFL-LAW-04-01	Appraisal Discipline	Domain 4 — Investment appraisal and capital budgeting	IAS 36; ISO 31000
PFL-LAW-05-01	The Bankability Test	Domain 5 — Project development and bankability	Equator Principles; IFC Performance Standards; ISO 31000
PFL-LAW-06-01	Model Integrity	Domain 6 — Financial modelling	ICAEW Financial Modelling Code; FAST Standard
PFL-LAW-06-02	Formula Transparency	Domain 6 — Financial modelling	FAST Standard; ICAEW Financial Modelling Code
PFL-LAW-06-03	Assumption Traceability	Domain 6 — Financial modelling	ICAEW Financial Modelling Code; ISO 8000 series
PFL-LAW-06-04	The Source Line	Domain 6 — Financial modelling	ISO 8000 series; ISO 15489
PFL-LAW-06-05	Model Change Governance	Domain 6 — Financial modelling	SR 11-7 (public supervisory guidance); ISO/IEC 42001; ICAEW Financial Modelling Code
PFL-LAW-07-01	Revenue Assumption Discipline	Domain 7 — Revenue, demand and commercial models	IFRS 15; ISO 31000
PFL-LAW-09-01	Capital-Structure Justification	Domain 9 — Funding structure and sources of capital	Basel framework (illustrative); OECD Arrangement on Officially Supported Export Credits; Equator Principles
PFL-LAW-10-01	Debt-Service Coverage Truth	Domain 10 — Debt sizing, covenants and credit metrics	IAS 7; Basel framework (illustrative)
PFL-LAW-10-02	Covenant Interpretation	Domain 10 — Debt sizing, covenants and credit metrics	IAS 1 (replaced by IFRS 18 from 1 Jan 2027); Basel framework (illustrative)
PFL-LAW-11-01	Risk Allocation Honesty	Domain 11 — Risk identification and allocation	ISO 31000; FIDIC suite; IFC Performance Standards; Equator Principles
PFL-LAW-12-01	The Advice Boundary	Domain 12 — Contracts and transaction structure	IAS 12; OECD Model Tax Convention; ISO/IEC 17024
PFL-LAW-13-01	Independence of Review	Domain 13 — Due diligence and financial close	IESBA Code of Ethics (incl. Independence Standards); ISO/IEC 17024; Equator Principles
PFL-LAW-13-02	Conditions Precedent	Domain 13 — Due diligence and financial close	ISO 15489; IFC Performance Standards; Equator Principles
PFL-LAW-13-03	Financial-Close Evidence	Domain 13 — Due diligence and financial close	ISO 15489; ISO/IEC 27001
PFL-LAW-14-01	Drawdown Integrity	Domain 14 — Construction monitoring and drawdown	FIDIC suite; ISO 15489
PFL-LAW-14-02	Funds-Flow Control	Domain 14 — Construction monitoring and drawdown	ISO/IEC 27001; COSO Internal Control
PFL-LAW-15-01	Distribution Restriction	Domain 15 — Operations, performance and restructuring	IAS 1 (replaced by IFRS 18 from 1 Jan 2027); G20/OECD Principles of Corporate Governance
PFL-LAW-16-01	Transaction Confidentiality	Domain 16 — Data, automation and responsible AI in finance	ISO/IEC 27001; ISO/IEC 42001

ID	OFFICIAL TITLE	ANCHOR DOMAIN	RELATED EXTERNAL REFERENCES
PFL-LAW-16-02	AI-Assisted Model Verification	Domain 16 — Data, automation and responsible AI in finance	ISO/IEC 42001; ISO/IEC 23894; NIST AI RMF; SR 11-7
PFL-LAW-16-03	Human Approval	Domain 16 — Data, automation and responsible AI in finance	ISO/IEC 42001; OECD AI Principles; EU AI Act; COSO Internal Control

Glossary

Consolidated from every Knowledge Area's key-terms table. The Knowledge Area reference after each entry is the authority — the gloss points to the treatment and does not replace it.

A

Accounting policy — The permitted choice that shapes reported figures without changing cash. (KA 2.1)

Accretion — The finance charge that unwinds the discount on a provision, taking it to the settlement amount. (KA 2.3)

Accrual basis — Recognising the effects of transactions when they occur, not when cash moves. (KA 2.1)

Accuracy range — The band the estimator expects the outturn to fall in; narrows with definition. (KA 8.1)

Advance payment / bond — Pre-mobilisation payment recovered from certifications, secured by a bond; a loan from the project to the contractor. (KA 14.3)

AI model risk — Loss from decisions or actions taken on model output — wrong model, wrong envelope, or misunderstood output. (KA 11.4)

All-in effective cost — The rate solving $\text{net proceeds} = \text{payment} \times AF(r, n)$; the only valid basis for tranche comparison. (KA 9.3)
· Also read at KA 3.2: The rate solved from the actual stream against net proceeds; fees are never added to a rate.

Allocation matrix — Risk → bearing party → clause → financial limit → instrument; reveals orphan and doubly covered risks. (KA 12.4)

Amendment — A change of terms — usually a covenant reset — for a fee, a margin uplift and tighter controls. (KA 15.3)

Annuity / annuity-due — Level periodic stream, in arrears / in advance; the due form is worth $(1 + r)$ times the ordinary. (KA 3.2)

Annuity factor $AF(r, n)$ — $(1 - (1+r)^{-n})/r$; PV of 1 per period for n periods; can never exceed $1/r$. (KA 3.2)

Annuity, level-principal, bullet, holiday — The four canonical loan shapes a term sheet offers. (KA 3.2)

Area rule — $IDC = r_q \times g \times S \times \sum \text{cum}(t-1)$; capitalised interest is proportional to the area under the drawdown curve. (KA 8.2)

ARR — Annual recurring revenue: the annualised value of contracts in force. (KA 7.2)

Articulation — The three statements derived from one calculation set, so they cannot disagree. (KA 6.2)
· Also read at KA 2.1: The locking of the three statements to one underlying record via identities.

Assessed claim exposure — The SPV's and adviser's judgment of the probable settled cost of notified but unagreed claims. (KA 14.2)

Asset-capital matching — Pairing project risk phases with the capital suited to hold them — on two axes, risk-holding capability and timing. (KA 1.1)

At-risk commitment — Option premiums, bid bonds, reservations — cash forfeited if the project dies. (KA 5.1)

Attribution residual — Output – $\sum$ attributions; must be nil or explained (the hundred-per-cent rule). (KA 16.3)

Authority accumulation — One automated identity able to read, act and record; the separation-of-duties failure. (KA 16.4)

Automation breakeven volume — Committed fixed cost ÷ the per-item cost advantage. (KA 16.1)

Availability deduction — Reduction in the capacity charge for failing the availability standard, commonly at a multiplier. (KA 7.1)

Availability period — The window in which the facility may be drawn; often binds on a delay long before the damages cap does. (KA 14.4)

Available commitment — Undrawn debt + uncalled equity. Already includes undrawn contingency — adding contingency again double-counts. (KA 14.1)

B

Balancing line — The use that absorbs the residual of a fixed envelope; must be tested against policy. (KA 6.2)

Balloon / bullet — Principal deferred to maturity; lower periodic service, refinancing risk. (KA 10.1)

Balloon / refinancing risk — The bullet's maturity principal and the risk of the rate then prevailing. (KA 3.2)

Bank case — The lender's re-cut of the register: higher probabilities, higher impacts, correlation admitted. (KA 11.4)

Bank case / sponsor case — Lender's conservative cash forecast versus sponsor's escalating forecast; equity's return lives in the gap. (KA 9.1)

Bankability — The degree to which contracts, risks and cash flows support limited-recourse financing on acceptable terms. (KA 5.3)

Bankability triangle — Value + cash + risk allocation, passed together. (KA 1.2)

Base date — The price level at which an estimate's rates were compiled. (KA 8.2)

Base-case vs minimum-period test — Coverage required in the period tested (usually year one) against coverage required in every period; on Kestrel the difference is 2,917,226 of debt. (KA 10.1)

Basis — Pre/post-tax, accrual/cash, before/after working capital, levered/unlevered. (KA 6.1)

Basis bridge — The documented reconciliation between two models of one project. (KA 6.1)

Basis risk (pass-through) — Exposure remaining because the reference index differs from the price actually paid. (KA 11.2)

Binding covenant — The covenant crossed by the smallest common stress; identified by solving each covenant for the same stress variable, not by comparing ratio levels. (KA 10.2)

Blended CPI artefact — A performance index averaged across fixed-price and owner-retained scope; misattributes an overrun and forecasts neither scope. (KA 14.2)

Blind audit — A sample of [unflagged](#) items reviewed independently, to measure what the model cannot see. (KA 16.3)

Break-even posterior — False-positive cost ÷ false-negative cost; the probability above which acting pays. (KA 16.1)

Breakeven close probability — Remaining development spend ÷ value on close (14.83 % for Kestrel). (KA 5.3)

Breakeven close rate — Programme spend ÷ (value per close × opportunities screened). (KA 5.1)

Breakeven consequence — Cost differential ÷ probability differential; the loss at which a deployment choice flips. (KA 16.4)

Breakeven detection rate d — $(\text{fee} + \text{priced elapsed time}) \div [p \times (C - F)]$; the diligence spend divided by the expected avoidable loss. (KA 13.1)

Breakeven discovery probability — Cost avoided by concealment ÷ loss on discovery; the arithmetic that has no upside term. (KA 1.3)

Breakeven disputed sum — The dispute size above which litigating beats settling at the midpoint. (KA 12.4)

Breakeven failure probability p — Incremental cost of the limited-recourse route ÷ the exposure the ring-fence removes. (KA 1.1)

Breakeven fee / error rate / detection rate — The three points at which a review stops adding value. (KA 6.4)

Breakeven inflow — $I_0 / AF(r, n)$; the revenue level at which NPV reaches zero. (KA 4.3)

Breakeven loading — $(\text{transferor EMV} \div \text{transferee EMV}) - 1$; negative means no price works. (KA 11.1)

Breakeven margin — The new all-in rate at which a refinancing's net present value is nil — 4.2206 % for Kestrel's 7-year option. (KA 15.3)

Breakeven rate / breakeven exchange rate — The level at which a named covenant fails; a fact about the structure, not a forecast. (KA 11.3)

Breakeven translation — Converting a ratio threshold into the input level that crosses it. (KA 6.4)

Buy-down — A lump sum, usually applied to prepay debt, calibrated so the financing survives a permanently smaller plant. (KA 14.4)
· Also read at KA 5.4: Payment applied to prepay debt so sized coverage is restored after a performance shortfall.

C

Calendar-fixed repayment date — A first instalment set by date rather than by actual completion; a slip shortens the operating period that funds it. (KA 14.4)

Cap stack — The interacting set of sub-caps and the aggregate cap; the aggregate is the real limit. (KA 12.1)

Cap-binding day — Delay cap ÷ daily damages rate; the day after which further delay is uncompensated. (KA 12.1)

Capacity (availability) charge — Payment for making the asset available, independent of output taken. (KA 7.1)

Capex / opex — Capitalised and depreciated vs expensed in the period; identical pre-tax cash, different profit. (KA 2.3)

Capital allowance — Tax depreciation on the tax authority's profile and base; not accounting depreciation. (KA 6.2)

Capital cost — The asset: contract price, owner's costs, land, connection, insurance in construction. (KA 8.1)

Capital employed — Debt plus equity; the base a return on capital is measured against. (KA 2.2)

Capital rationing — Budget binds before value runs out; pack by PI. (KA 4.3)

Capital-recovery annuity — $I_0 / AF(r, n)$; the annual inflow at which NPV is exactly zero. (KA 4.2)

Capitalisation boundary — Which costs and which dates form part of the asset. (KA 2.4)

Case — The named set of assumptions switched on (sponsor case, bank case, downside). (KA 6.1)

Cash call — The equity injection a sufficiency failure requires before the next drawdown. (KA 8.4)

Cash conversion — Operating cash flow ÷ net income; on a capital-intensive asset it measures capital intensity, not quality. (KA 2.2)

Cash interest cover — $EBITDA \div \text{interest}$; the same test with depreciation added back — 0.9524 higher for Kestrel. (KA 2.4)

Cash sweep — A defined share of distributable cash applied to mandatory prepayment; part of the price of consent. (KA 15.3)
· Also read at KA 10.1: Mandatory prepayment from a defined share of surplus cash.

Cash waterfall — The contractual priority order for applying project cash. (KA 10.3)

Cash yield — $\text{Distribution} \div \text{equity subscribed}$ — 4.3020 % for Kestrel while the loan runs, 32.13 % after. (KA 15.2)

Cash-to-revenue gearing — The fraction of a revenue movement that reaches [CFADS](#) after cash tax — 0.80 for Kestrel. (KA 15.1)

Certificate of satisfaction — Numbered record of each condition, its evidence and its disposition, including waivers. (KA 13.4)

Certification drift — Progressive migration from milestone toward cost-incurred certification; converts secured lending into unsecured lending without a decision. (KA 14.3)

Certified spend — Progress certified for payment; the basis of a draw request, lagging incurred cost. (KA 8.2)

CFADS — Cash flow available for debt service — a defined term whose definition changes the ratio. (KA 2.3)

· Also read at KA 1.2: Cash flow available for debt service (name fixed here; machinery in Domain 10).

· Also read at KA 10.1: Cash available for debt service in a period, on the facility's documented definition.

CFADS elasticity — Proportional change in [CFADS](#) per one per cent change in a driver; differs by driver. (KA 7.3)

CFADS tie — $CFADS = \text{operating cash flow} + \text{interest paid}$, where interest is classified as operating. (KA 6.2)

Check block — A dedicated output area computing every invariant as a difference that must be nil. (KA 6.4)

Circularity — Interest depends on balance depends on drawings depends on interest; resolved by convention, iteration or algebra. (KA 6.3)

Class 1 / 2 / 3 finding — Changes a financing conclusion · changes a reported output beyond materiality · changes no number. (KA 13.2)

Class-weighted closure — Progress measured by impact closed, not findings closed. (KA 13.2)

Close-cost budget — Line-itemised transaction cost, reconciled to sources and uses; fixed component plus a proportional fee rate. (KA 13.3)

Close-cost premium — The largely fixed excess of project-finance transaction costs over a corporate facility's; the source of the scale effect. (KA 1.1)

Commercial operations date (COD) — Contractual start of operations: revenue, term debt and the operating covenant regime. (KA 5.4)

Commitment vs actual vs paid — Distinct measures of "spend" that must never be conflated. (KA 2.4)

Committed capital — Base equity + support commitments; the real exposure (40.0 % of capex for Kestrel). (KA 5.2)

Committed vs contributed equity — Enforceable obligation to subscribe, versus cash actually injected. (KA 9.1)

Common horizon (LCM) — Comparing replacement chains over the lowest common multiple of the lives. (KA 4.2)

Common terms agreement — One document carrying shared covenants and definitions across all tranches. (KA 9.3)

Compensation on termination — What the grantor or offtaker pays on early termination, graded by cause. (KA 12.2)

Completion risk — Risk of not reaching commercial operation on time, on budget or to guaranteed performance; never wholly transferable. (KA 11.1)
· Also read at KA 5.4: Risk of not delivering on time, to cost and to sized performance — all debt, no cash flow.

Compliance certificate — A signed representation that tested ratios were computed on the documented definitions and no default subsists. (KA 15.1)

Compound interest — Interest accruing on principal and accumulated interest: $FV(x) = x(1 + r)^n$. (KA 3.1)

Concentration risk — The exposure created by dependence on few counterparties; visible in the loss distribution, not in expected loss. (KA 7.4)

Condition precedent (CP) — Requirement satisfied and evidenced before an obligation arises, principally first drawdown. (KA 13.3)

Condition survey — The pre-expiry inspection that fixes the handback obligation against the funded estimate. (KA 15.4)

Conditional probability of default — Default probability given a claim of the size the allocation contemplates — the relevant figure for transferred risk. (KA 11.3)

Conditions to each drawing — The per-draw conditions: no default, representations repeated, certificates attached, insurances in force, in balance, within availability and commitment. (KA 14.1)

Confidence level (P50 / P80 / P95) — The probability that the provision covers the aggregate outcome; a policy choice. (KA 8.3)

Conflict of interest — An interest that could bias judgment; declared, managed or declined. (KA 1.3)

Conjunction premium — The excess of the expected close slip cost over the cost of the critical chain's own expected slip. (KA 13.3)

Conjunctive test — Composition by multiplication: every condition must pass, so the weakest governs. (KA 5.3)

Consent register — Every permission with authority, lead time, dependency, expiry, transferability and conditions. (KA 5.3)

Consistency rule — One world per model; the two consistent treatments are identical to the cent, so a difference is an error and not a basis. (KA 3.3)

Content requirement — Minimum share of contract value sourced from the supporting country. (KA 9.3)

Contingency — Funded provision for identified risks within agreed scope; drawn on certification. (KA 8.3)

Contingency adequacy test — Remaining contingency $\geq$ P80 of the remaining register; fails independently of EAC. (KA 8.4)

Contingency coverage on the remainder — Unallocated contingency $\div$ (known committed claims + P80 of the open register). (KA 14.2)

Contingency release — Reduction in the provision when a risk retires; the percentage method cannot produce one. (KA 8.3)

Contingent / sponsor support — Obligation to inject on a defined trigger rather than at close. (KA 9.1)

Contingent support — Cost-overrun undertaking, standby equity or standby tranche called on a defined trigger. (KA 8.3)

Contracted / merchant revenue — Revenue under an obligation to pay / revenue sold into a market with no obligation. (KA 7.1)

Contracted volume floor — The minimum committed volume; a financing parameter set by the covenant, not a commercial preference. (KA 12.2)

Correlation uplift — The increase in a percentile from admitting $p > 0$; 837,478 at $p = 0.30$ on Kestrel's register. (KA 11.4)

Cost of retention — The present value of the capital-structure change lenders impose when a risk is retained; the sponsor's true reservation price for transferring it. (KA 1.2)

Cost per month of slip — Escalation on unbought scope + extra interest on drawn debt + deferred CFADS. (KA 8.4)

Cost per reviewed item — Processing cost + (undetected-error rate $\times$ consequence of an error). (KA 16.1)

Cost to complete (CTC) — $EAC - AC$; the money still required on a stated forecast method. (KA 8.4)

Cost-incurred certification — Value of contractor spend including off-site materials; funds the contractor's balance sheet. (KA 14.3)

Cost-overflow support — A capped sponsor undertaking to fund overruns, converting a negotiation into a drawing. (KA 14.2)
 · Also read at KA 5.2: A sponsor commitment to fund construction cost above budget, up to a cap.

Covenant-preserving exposure ceiling — Headroom $\times AF(r, n)$ — the present-value risk a structure can absorb (3,122,460 for Kestrel). (KA 11.4)

Covered interest parity — Forward $\approx$ spot $\times$ interest-ratio; the no-arbitrage forward, and the reason two routes to one hedged value agree. (KA 3.3)

CP chain — A dependency sequence of conditions; its duration is the sum of its links. (KA 13.3)

Credit enhancement — Guarantee, letter of credit, escrow or reserve that improves the credit; priced against the coverage it unlocks. (KA 7.4)

Criticality risk — $slip\ probability \times slip\ size$, net of float; ranks where acceleration is worth buying. (KA 13.3)

Cross-stream interface list — Register of assumptions touched by more than one adviser, each with a single named owner. (KA 13.1)

Crossover rate — Rate where two NPV profiles intersect and rankings flip. (KA 4.3)

Cumulative PD — $1 - (1 - PD)^n$; the horizon matters and single-year PD understates a twelve-year exposure. (KA 7.4)

Cure identity $P = C \div \lambda$ — A prepayment cure costs $1 - 1/\lambda$ less than a deemed-CFADS cure of the same breach — 16.6667 % at a 1.20 $\times$ covenant — and also reduces later periods' debt service. (KA 10.4)

Currency mismatch — Revenue and debt service in different currencies; unbounded and correlated with host-economy stress. (KA 11.3)

Cut-off — Assigning a transaction to exactly one period. (KA 2.4)

Cybersecurity risk (project) — Primarily an availability risk on the operational-technology network; a CFADS risk. (KA 11.4)

D

Damages cap — The ceiling beyond which every further day is borne by the SPV (day 240 for Kestrel). (KA 5.4)

Data room / disclosure index — The controlled disclosure repository and the numbered, dated record of what was disclosed. (KA 13.1)

Data spine — One set of numbers, two sets of questions; the controls-financing interface. (KA 8.4)

Day-count basis — The contractual numerator and denominator for accruing interest; actual/360 is a 365/360 uplift on all interest. (KA 3.3)

Daylight test — Would full disclosure of interests leave the advice trusted? (KA 1.3)

Days sales outstanding (DSO) — Receivables $\div$ revenue $\times$ days in the convention; the collection period a covenant can be restated in. (KA 2.3)

Debt capacity — $CFADS / target\ DSCR \times AF(r, n)$; a function of cash, coverage, rate and tenor only. (KA 10.1)

Debt schedule invariants — Closing balance nil at maturity; Σ principal = drawings; interest ties to balance, rate and days. (KA 6.3)

Debt-service schedule — The obligation profile that coverage tests are measured against. (KA 10.3)

Debt/EBITDA — A leverage measure; tolerable level depends on revenue certainty. (KA 2.4)

Deduction / abatement regime — Contractual reductions in payment for unavailability or quality failure; an uncapped, annually recurring exposure. (KA 12.2)

Deduction multiplier — The factor applied to the availability shortfall; converts one operational point into more than one point of cash. (KA 7.1)

Deferred annuity factor — $AF(r, n) - AF(r, k)$; prices a level stream that starts after year k . (KA 4.1)

Definitional layer — The facility's defined terms implemented once, as code, with clause references. (KA 16.1)

Delay liquidated damages — Pre-agreed sum per unit of time of late completion; calibrated on carrying cost plus forgone [CFADS](#). (KA 12.1)

· Also read at KA 5.4: Daily payment for late completion; calibrate to interest **plus** forgone [CFADS](#).

Depreciation — $(\text{cost} - \text{residual}) / \text{useful life}$; a non-cash charge for asset consumption. (KA 2.2)

Development cost — Pre-close spend at risk; capitalised into the envelope only if accepted. (KA 8.1)

Development cost per close — Programme spend ÷ closes; the honest cost of one financing. (KA 5.1)

DFI conditionality — Environmental, social, procurement and reporting obligations attached to development finance. (KA 9.3)

Diligence stream — One discipline's review — technical, financial, legal, tax, insurance, E&S, market. (KA 13.1)

Direct agreement — Tripartite notice, cure and step-in rights making contracts survive SPV default. (KA 12.3)

Direct method — Reporting the gross operating cash flows: collections, supplier payments, interest, tax. (KA 2.2)

Discount factor $DF(t)$ — $1/(1+r)^t$; the PV of one unit received at t . (KA 3.1)

Discount rate — The rate r used to move value across time; the required return for the risk. (KA 3.1)

Distributable amount — [CFADS](#) less debt service less reserve top-ups, subject to every distribution condition. (KA 15.2)

Distribution condition — The coverage level above which cash may leave the structure at all (1.25× on Kestrel); usually the operative constraint in a healthy project. (KA 10.4)

Distribution drought — A run of periods generating cash that is not distributable; costs equity in cash and in timing. (KA 15.2)

Distribution lock-up — Trapping equity cash when a test fails, short of default; on Kestrel the 1.15× trigger, operative only in a sick project. (KA 10.4)

Distribution-block account — Where cash that fails a distribution test is held; a pre-funding mechanism, not a penalty. (KA 15.2)

Draw request — The certified application for funds: an arithmetic, an evidential and a representational claim. (KA 14.1)

Draw-rate check — Contingency drawn as a share of contingency funded, against progress; coincidental, and to be struck from reports. (KA 14.2)

DSCR — [CFADS](#) ÷ debt service; the period test lenders covenant on. (KA 10.2)

DSCR ÷ LLCR — A reading, not a market metric: 1.0000 for a level annuity against level cash; any excess measures principal deferred beyond the periods tested (1.1419 for a 25 % balloon, 1.9880 for a bullet). (KA 10.2)

DSRA — Debt service reserve; buys payment continuity and time, not compliance. (KA 10.3)

Dual-approval threshold — Approver cost ÷ caught rate; the value above which a second approval pays. (KA 16.4)

Due diligence — Evidenced pre-commitment examination of a project, reported in writing by identifiable authors. (KA 13.1)

E

EAV / EAV — NPV (cost PV) converted to a level annual equivalent via [AF\(\$r\$, \$n\$ \)](#). (KA 4.2)

EBIT — Operating profit after depreciation; performance including capital consumption. (KA 2.2)

EBITDA — Earnings before interest, tax, depreciation and amortisation. (KA 2.2)

ECA / exposure premium — State-backed export-credit support; the risk premium it charges, usually capitalised. (KA 9.3)

Economic cost of delay — Funded cost plus forgone [CFADS](#); the correct calibration basis for delay damages. (KA 14.4)

Effective escalation rate — The compound rate a partly indexed line actually achieves; computable only from shares and indices together. (KA 7.3)

Effective sculpting rate r — $r \times (1 - T/\lambda)$; the rate at which a sculpted profile discounts once the interest tax shield feeds back into [CFADS](#). (KA 10.1)

Elasticity — Percentage change in an output per one per cent change in an input. (KA 6.4)

Enforcement floor — Net recovery from enforcing security and realising the asset; bounds every negotiation. (KA 15.4)

Environmental and social risk — Loss from consent breach, social-licence failure or breach of lender E&S standards — contractual, not aspirational. (KA 11.4)

EPC wrap — Read here only as what makes completion risk bankable: one contractor answerable for the whole works, so lenders face a single counterparty. Defined and priced in Domain 12, KA 12.1. (KA 5.4)

· Also read at KA 12.1: Single-contractor fixed-price, date-certain, turnkey responsibility for the whole works.

Equity bridge loan — Construction-period facility funding equity, repaid by sponsors at completion. (KA 5.2)

Equity bridge loan (EBL) — Construction facility against the equity commitment; accretive only below the equity IRR it defers. (KA 9.1)

Equity cliff — The cash level at which debt service consumes all project cash; a function of the debt's shape, not only its size. (KA 1.2)

Equity contribution certificate — Evidence that the equity share of a draw has been provided, conditioning the debt share. (KA 14.1)

Equity cure — Contractual injection restoring a ratio; a scarce option, capped in number. (KA 15.3)
· Also read at KA 10.4: Sponsor cash injected to restore a ratio; limited by the facility.

Equity return — Draws against distributions after every prior claim; the sponsors' return. (KA 6.3)

Equivalent face amount — Certain cover ÷ probability of payment; 1.4286x at a 0.70 assessment. (KA 12.3)

Escalation — Input-price movement between base date and spend date; trade-specific, not general inflation. (KA 8.2)

Escalation wedge — Cumulative cash difference between a cost escalating at its own driver and the same cost escalating at the revenue index. (KA 11.2)

Estimate class — The definitional maturity of an estimate, carrying a stated accuracy range. (KA 8.1)

Event of default — Defined breach entitling lenders to remedies including acceleration. (KA 10.4)

Exchange-rate-indexed share — The portion of tariff linked to the exchange rate; the debt-service-matching share funds USD outflows. (KA 11.3)

Excusable outage — An unavailability event that does not count against the availability guarantee; the availability/force-majeure boundary. (KA 11.2)

Expected loss — $PD \times EAD \times LGD$; linear in exposure, and therefore blind to concentration. (KA 7.4)

F

Fatal condition — A condition whose failure ends the project regardless of everything else. (KA 5.1)

Fee at risk — The portion of an operator's fee forfeited on performance failure — its economic stake in the allocation. (KA 11.2)

Fiduciary awareness — Acting in the principal's interest with loyalty, care and confidentiality. (KA 1.3)

Final hold — The position a lender intends to retain after syndication. (KA 13.4)

Financial / information / positive / negative covenant — Tested ratios · reporting · required acts · prohibited acts. (KA 10.4)

Financial close — The point at which funding documents become effective and drawdown is available. (KA 5.1)

Financial distress — Forecast cash cannot sustain contracted debt service for the remaining life — a capital structure problem, not a liquidity one. (KA 15.4)

Financial-data spine — A single governed publishing layer; n feeds in place of $n(n-1)/2$ reconciliations. (KA 16.1)

Finding close-out — Corrected, verified, and every dependent consequence followed through into papers and the base case. (KA 13.2)

First-of-a-kind premium — The coverage, reserve or insurance cost of unproven technology, payable in equity. (KA 5.3)

Fisher relation — $(1+i_{nom}) = (1+i_{real})(1+\pi)$; the subtraction shortcut always overstates i_{real} . (KA 3.3)

Fixed charge — Debt service owed regardless of performance. (KA 1.2)

Float — Weeks by which a chain may over-run before it affects close; absorbs slip at no cost. (KA 13.3)

Force majeure — Allocation to nobody: obligations suspend, debt service does not. (KA 11.3)

Forward-looking test — A covenant or distribution condition measured on a projected window on an agreed basis. (KA 15.1)

Free cash flow (project) — Operating cash after tax, capex and working capital, **before all financing flows** — the only stream the project rate may discount. (KA 4.1)

Funded cost of delay — Cash the project must raise per period of slip: interest on drawn debt plus prolongation costs. Excludes forgone [CFADS](#). (KA 14.4)

Funding order — Pro rata, equity-first or debt-first; allocates capitalised interest, credit exposure and sponsor return. (KA 14.1)

Funds flow — The statement of every payment at close, reconciled to the close-cost budget. (KA 13.4)

Funds sufficiency / in balance — Funds available (undrawn facility + unused contingency + uncalled equity) $\geq$ [CTC](#). (KA 8.4)

Future value $FV(x)$ — The compounded worth of an amount at a future date. (KA 3.1)

G

Gain-share — Contractual obligation to pass a defined share of a refinancing gain to the grantor. (KA 9.4)

Generated minimum — The worst of k draws; a percentile ($\approx 1/(k+1)$), not a defined stress case. (KA 16.2)

Golden source — The one system authoritative for a fact; all others are derived. (KA 16.1)

Golden-answer regression suite — Verified results rerun after every edit; unexplained change blocks release. (KA 6.4)

Governance latency — $E[\text{wait}] = M/2 + L$; the value forgone while a gate waits. (KA 16.4)

Grain — The level at which one row is one fact; most reconciliation failures are grain failures. (KA 16.1)

Grant element — $1 - PV(\text{debt service at a market rate}) \div \text{face value}$; the subsidy content of concessional debt. (KA 9.4)

Greedy PI packing — Descending-index selection; a heuristic that can leave value and budget unused. (KA 4.3)

Gross vs net PI — PV/I_0 (threshold 1.0) vs NPV/I_0 (threshold 0.0); same ranking, different threshold. (KA 4.2)

Grounds for transfer — Control (changes the distribution) and capacity (cheaper holder); bargaining power is neither. (KA 11.1)

Growing (indexed) annuity — Stream growing at g ; $PV = A \times AF(r^*, n)$ with $r^* = (1+r)/(1+g) - 1$. (KA 3.2)

Growth-adjusted rate r — $(1+r)/(1+g) - 1$; an arithmetic device inside one valuation, never a project hurdle. (KA 3.2)

H

Handback — Transfer of the asset at concession end in a specified condition; the residual obligation and its reserve. (KA 15.4)

Hard-coded constant — An assumption typed inside a formula; invisible to review and immune to scenarios. (KA 6.1)

Headroom — Cash that can be lost before a covenant threshold is crossed. (KA 10.2)

Hedge ratio — Share of floating debt fixed by swap or cap; lenders covenant a minimum rather than a full hedge. (KA 11.3)

Historic vs forward-looking test — Measured on what happened vs on projection; which binds follows the slope of the cash profile, not the drafting. (KA 10.4)

Horizon — Periods valued, and the treatment of value beyond them. (KA 6.1)

I

ICR — Earnings $\div$ interest; ignores principal, exposed to accounting judgment. (KA 10.2)

In-balance condition — Facility term requiring available funds $\geq$ cost to complete; failure stops funding rather than causing default. (KA 14.2)

Incremental IRR — IRR of the difference project; narrates the NPV ranking. (KA 4.3)

Indexation — Contractual escalation by a published index, with lags, caps, floors and weightings. (KA 3.3)

Indexation architecture — Which proportion of each line escalates, on which index — the negotiated structure, distinct from the index itself. (KA 7.3)

Indexation cap / lag / weighting — $\min(g, \text{cap})$ per period $\cdot$ index published in arrears, worth $1 - 1/(1+g)$ of the stream $\cdot$ partial indexation at $w \times g$. (KA 3.3)

Indexation mismatch — Revenue index differs from the driver of cost escalation; appears as a trend in coverage, not in a single-year sensitivity. (KA 11.2)

Indexed share — The proportion of a price that escalates; the remainder is fixed nominal and erodes in real terms. (KA 7.3)

Indifference stress s — $1 - \lambda_2/\lambda_1$; the cash stress at which a lower coverage requirement stops being a concession. (KA 10.1)

Indirect method — Deriving operating cash flow from profit by undoing accruals. (KA 2.2)

Indivisible project — Funded whole or not at all; the reason enumeration replaces sorting. (KA 4.3)

Inflation π / escalation e — General price drift / specific contractual price growth. (KA 3.3)

Input / output progress measures — Cost-based vs delivery-based measures of performance to date. (KA 2.3)

Input provenance — Every external input traced to a source document, version and date. (KA 6.4)

Instruction injection — Ingested content crafted to be read as direction; treat all ingested text as data. (KA 16.4)

Instrument expiry gap — The dated hole where an instrument expires before the exposure it covers. (KA 12.3)

Interest cover — $\text{EBIT} \div \text{interest}$; an accrual coverage measure that ignores principal. (KA 2.4)

Interest during construction — Interest accruing on drawn debt before revenue; 7,000 per day for Kestrel. (KA 5.4)

Interest during construction (IDC) — Interest accruing before revenue; a funded use, and part of the depreciable base. (KA 6.2)

Interface agreement — Allocation of responsibility at handovers between separately contracted packages. (KA 12.2)

Interface hole — Loss caused by a handover failure that neither contractor is liable for. (KA 12.2)

IRR — The rate at which $\text{NPV} = 0$; the flows' embedded return. (KA 4.1)

Istisna'a / ijara / forward lease — Commissioned-construction, lease, and described-future-asset lease structures used in Islamic finance markets. (KA 9.3)

K

$k_d(\text{after tax})$ — $k_d \times (1 - T)$; the debt cost that enters WACC. (KA 9.2)

k_e — Cost of equity, built up as $r_f + \beta_e \times \text{ERP} + \text{CRP} + \text{SP}$. (KA 9.1)

L

Label bias — A detector trained on a prior process's findings inherits its blind spots. (KA 16.3)

Label poisoning — Influencing what a detector learns; detectable only by blind audit. (KA 16.4)

LC-backed reserve — A reserve satisfied by a letter of credit rather than cash; cheapest for the sponsor, and a substitution of bank credit risk for cash. (KA 10.3)

Lender's cost-to-complete — Money to completion on a commitment basis: remaining contract value + approved variations + assessed claim exposure + bottom-up owner scope + remaining financing costs. (KA 14.2)

Level annual charge — Lumpy lifecycle PV converted to a level equivalent via $\text{AF}(r, n)$ (Domain 4's EAV). (KA 8.1)

Leverage / gearing — Debt's share of funding; amplifier of equity return and risk. (KA 1.2)

Leverage crossover — The cash level at which the unlevered return equals the cost of debt, so gearing neither adds nor subtracts. (KA 1.2)

Leverage wedge — $(D/E) \times (\text{ROCE after tax} - k_d \text{ after tax})$; the amount gearing adds to ROE, and subtracts when the spread is negative. (KA 2.4)

Levered-return identity — $r_e = r_u + (D/E) \times (r_u - r_d)$; amplification is linear in gearing and proportional to the spread over the debt rate. (KA 1.2)

Liability asymmetry (O&M) — Operator liability capped on fee while the loss it can cause is revenue-scaled. (KA 12.1)

Lifecycle (whole-life) cost — Periodic major maintenance plus handback or decommissioning. (KA 8.1)

Linear-asset tenure risk — Corridor rights whose single gap can stop an otherwise complete project. (KA 5.3)

LLCR — PV of CFADS to loan maturity $\div$ debt outstanding; the loan-horizon test. (KA 10.2)

Load-bearing subset — The extracted items that feed a model, covenant or reported ratio; the verification scope. (KA 16.2)

Loaded premium — Transferee's own $\text{EMV} \times (1 + \text{loading})$ — what the transfer actually costs. (KA 11.1)

Local additive attribution — An explanation of one output in the output's own units, reconciling to it. (KA 16.3)

Long-stop date — Date after which commitments lapse; converts slippage into re-approval at today's market. (KA 13.3)

M

Macaulay duration — Present-value-weighted average time to receipt; for a level stream capped at $(1 + r)/r$, whatever the tenor. (KA 1.1)

Maintenance reserve (MRA) — Funded account that converts a lifecycle spike into a distribution reduction. (KA 8.1)

Make-whole / spens — Prepayment compensation that can eliminate a refinancing gain. (KA 9.2)

Management reserve — Provision for unidentified risk and scope change; in a financing, largely replaced by contingent support. (KA 8.3)

Margin drift — The slow change in margin caused by a mismatch between effective revenue and cost escalation. (KA 7.3)

Marginal DSCR of a variation — $\Delta \text{CFADS} \div \Delta \text{debt service}$; coverage-neutral debt funding = $(\Delta \text{CFADS} / \text{target DSCR}) \times \text{AF}(r, n)$. (KA 14.3)

Marginal gain (condition) — Joint probability $\times (p/p - 1)$; the correct ranking of development effort. (KA 5.3)

Marginal precision — Additional true positives $\div$ additional alerts from loosening a threshold. (KA 16.1)

Mark-to-market (swap) — The break cost of terminating a hedge early — an exposure a swap creates rather than removes. (KA 11.3)

Market flex — Contractual right to change specified terms to achieve syndication; capped, often ordered, sometimes reversible. (KA 13.4)

Materiality threshold — The stated size below which a difference is not a finding; best expressed in the transaction's own metric ($0.01 \times \text{of DSCR}$). (KA 13.2)

Maturity extension — Lengthening the tenor; returns par at the contract rate and less at any higher required return. (KA 15.4)

Measured / PoC certification — Value of work in place on measured quantities or assessed completion; requires judgment. (KA 14.3)

Measurement — The amount at which a recognised item is carried (cost, amortised cost, fair value). (KA 2.1)

Mechanical completion / commissioning / performance test / commercial operations date / final acceptance — The completion sequence; the financing attaches distinct consequences to each. (KA 14.4)

Mezzanine — Capital between senior debt and ordinary equity; priced in the gap, never cheap. (KA 9.2)

Mid-period convention — Discounting each year's flow from its mid-point; multiplies year-end PV by $(1 + r)^{0.5}$. (KA 4.1)

Milestone certification — Value of milestones actually achieved; binary, lumpy, tied to contractual entitlement. (KA 14.3)

Minimisation — Not loading the sensitive data; the cheapest and strongest confidentiality control. (KA 16.4)

Minimum revenue guarantee — Grantor-provided floor under demand-based revenue; a written option. (KA 9.4)

MIRR — Single rate from explicit finance and reinvestment rates. (KA 4.1)

Model audit — Independent review of a model against the transaction documents, its own logic and its arithmetic (Domain 6, KA 6.4.3). (KA 13.2)
· Also read at KA 6.4: Independent review against documents, logic and arithmetic; a lenders' condition precedent.

Model inventory — Every model in use, with purpose, owner, dependencies, decisions touched and tier. (KA 16.3)

Money multiple — Total distributions $\div$ equity contributed; a horizon-blind measure. (KA 6.3)

MRA — Maintenance reserve; smooths lumpy major maintenance (sized in Domain 8, KA 8.1.3). (KA 10.3)

Multiple roots — Two or more IRRs when flow signs change more than once. (KA 4.1)

Murabaha / wakala / sukuk — Cost-plus deferred sale; agency investment; certificates of undivided beneficial ownership. (KA 9.3)

Mutually exclusive — Choosing one forecloses the other; rank by NPV. (KA 4.3)

N

Natural hedge — Borrowing in the currency of revenue; its price is the margin forgone. (KA 9.3)

Negative arbitrage — Cost of holding fully drawn bond proceeds at deposit rates below the coupon. (KA 9.2)

Net revenue retention — Next year's revenue from this year's customers, after churn and expansion, as a percentage. (KA 7.2)

Net value of transfer — Transferor's **EMV** — loaded premium; negative means retain. (KA 11.1)

Nominal / real rate — Money-terms rate / purchasing-power rate; linked by Fisher. (KA 3.3)

Nominal rate / EAR — Quoted annual rate with compounding frequency / its once-a-year equivalent; $EAR \geq i_{nom}$ always. (KA 3.2)

NPV — Σ discounted cash flows — investment; the primary value measure. (KA 4.1)

NPV profile — NPV plotted against the discount rate; IRR is its zero-crossing. (KA 4.1)

O

Offtaker — The buyer of the project's output or service under contract. (KA 1.1)

On-demand bond — Bank instrument payable on a compliant demand without proof of breach; near-certain, fee-bearing. (KA 12.3)

Onerous contract — An expected-loss contract; the loss is recognised immediately and in full. (KA 2.3)

Operating bridge — The reconciliation from physical drivers through the accrual statements to defined **CFADS**. (KA 15.1)

Operating cash waterfall — The contractual priority order for applying each period's project cash. (KA 15.2)

Operating cost — Recurring cash cost; a deduction inside **CFADS**, never a funding line. (KA 8.1)

Operating leverage (DOL) — $\text{Contribution} \div \text{EBITDA}$; the amplification of volume changes into earnings changes. (KA 7.3)

Operating leverage (plant) — EBITDA shortfall $\div$ output shortfall; 1.510x for Kestrel at 85 % fixed cost. (KA 5.4)

Operating régime — The standing reporting, testing and certification obligations that follow completion. (KA 15.1)

Operational readiness — Capability to operate to contract standard from the first day of the operating period. (KA 5.4)

Option premium (development) — Stage spend buying the right, not the obligation, to spend the next tranche. (KA 5.1)

Option value — Value of flexibility the static NPV cannot see. (KA 4.3)

Outstanding balance B_k — $A \times AF(r, n - k)$; the PV of the payments that remain, and the prepayment base. (KA 3.2)

Owner's vs contractor's contingency — Only the owner's is drawable by the project; the contractor's is inside the price. (KA 8.3)

P

Parallel envelope — The period inside which streams run concurrently, so elapsed time is priced once, not per stream. (KA 13.1)

Parent company guarantee — Group parent's assumption of a subsidiary's obligation; worth the parent's credit. (KA 12.3)

Participation (pool) fee — Fee paid pro rata on final allocations to every lender. (KA 13.4)

Pass-through share ϕ — Contractual share of an input-price movement recovered in revenue; multiplies coverage tolerance by $1/(1 - \phi)$. (KA 11.2)

Payback / discounted payback — Years for cumulative (discounted) inflows to repay I_0 ; exposure measures. (KA 4.2)

PD / EAD / LGD — Probability of default over a stated horizon $\cdot$ exposure when it occurs $\cdot$ proportion not recovered. (KA 7.4)

Percentage method — Contingency as a policy share of base cost; states no confidence and does not respond to risk retirement. (KA 8.3)

Performance liquidated damages / buy-down — Payment for permanent underperformance, usually applied to prepay debt. (KA 12.1)

Periodicity — Period length; an economic choice because compounding happens within periods. (KA 6.1)

Perpetuity / growing perpetuity — Level stream forever, $PV = A/r$; growing at $g < r$, $PV = A(1+g)/(r - g)$. (KA 3.2)

PI — PV of inflows / I_0 ; value per scarce dollar, for rationing. (KA 4.2)

PLCR — PV of **CFADS** to end of project life $\div$ debt outstanding; counts the tail. (KA 10.2)

Post-close undertaking — A condition converted into a dated covenant surviving close. (KA 13.3)

Praecipium — The arranger's exclusive share of the arrangement fee; the price of structuring and underwriting. (KA 13.4)

Present value PV(x) — Today's worth of a future amount at discount rate r . (KA 3.1)

Principal haircut — Writing down principal; preferred by equity, feasible only above the enforcement floor. (KA 15.4)

Principal versus interest — Principal is a balance-sheet movement; only interest is an expense. (KA 2.2)

Pro-rata / back-ended funding — Equity drawn alongside debt, versus equity plugging the final gap. (KA 9.1)

Project return — Unlevered post-tax cash against total capital cost; the asset's return. (KA 6.3)

Prolongation cost — Time-related cost of delay, ideally at a pre-agreed daily rate. (KA 12.4)

Provision / contingent liability — Recognised (present obligation, probable, estimable) vs disclosed. (KA 2.3)

R

Ramp — The period during which realised demand approaches its mature level after commercial operations. (KA 7.2)

Ramp profile — A build-up to full output; costs value against a level profile even at identical totals. (KA 4.1)

Recall / precision / accuracy — $\text{Real errors caught} \div \text{real errors} \cdot \text{real alerts} \div \text{alerts} \cdot \text{all correct} \div \text{all items}$. (KA 16.1)

Recognition — Recording an item in the statements, subject to definition and measurement tests. (KA 2.1)

Reconstruction cost — The review time a machine-built artefact needs because no one holds its construction logic. (KA 16.2)

Recourse / non-recourse / limited recourse — Whom the lender can pursue: the sponsor's balance sheet; the project only; the project plus bounded sponsor support. (KA 1.1)

Recourse sentence — The three-limbed statement of sponsor support: who stands behind what, until when, capped at what. (KA 1.1)

Red-flag memorandum — An early partial deliverable that lets findings be acted on inside the envelope. (KA 13.1)

Refinancing — Replacement of a facility priced for a risk since retired; value comes from margin, tenor and covenant reset together. (KA 15.3)

Refinancing gain — PV of improved terms, net of costs; decomposed into rate and extension components. (KA 9.4)

Reinvestment assumption — NPV assumes interim cash earns r ; IRR assumes it earns the IRR. (KA 4.1)

Repayment holiday (grace) — Interest-only periods followed by amortisation over the shortened remainder; concentrates rather than reduces service. (KA 3.2)

Replacement chain — The explicit alternative when like-for-like replacement fails. (KA 4.2)

Required k — $\ln(\alpha) \div \ln(1 - p)$: scenarios needed to surface a mode at $1 - \alpha$ confidence. (KA 16.2)

Reserve release — The return of a funded reserve at maturity; a source that lifts the final period's distribution. (KA 6.3)

Reserve tolerance — $1 - DS \times (1 - m/12) \div CFADS$; the single-year CFADS shortfall a reserve of m months survives — 6.5393 points per month on Kestrel, at 417,470 of funded cash each. (KA 10.3)

Responsible-AI principle — AI proposes; the professional verifies, decides, remains accountable. (KA 1.3)

Restated sources and uses — The close statement re-expressed at a data date into drawn, remaining and available columns; a test rather than an identity. (KA 14.1)

Restricted cash — Reserve balances on the balance sheet that are not available to the business. (KA 6.2)

Retained residue — The register left after allocation — the thing contingency and reserves are sized against. (KA 11.1)

Retention / retention bond — Percentage withheld from certifications, capped and released in tranches; a bond substitutes bank credit for the withholding. (KA 14.3)

Revalidation interval — Tolerance for accumulated expected loss $\div$ annual EMV, capped by policy. (KA 16.3)

Reverse stress test — Solving for the driver movements that reach a defined failure point, rather than testing given movements. (KA 7.4)

Review / approval / certification — Can stop it $\cdot$ accountable for it $\cdot$ represents it to a third party. (KA 16.4)

Ring-fencing — Legal isolation of the project's assets, contracts and cash. (KA 1.1)

Risk register (financing) — Identified events with probability, impact, owner **and mechanism**; granular enough for each line to be allocated separately. (KA 11.1)

Risk-adjusted cover — $\Sigma(\text{face} \times \text{probability of payment})$; the number to compare with exposure. (KA 12.3)

ROCE / ROE — Return on capital employed and on equity; linked by the leverage identity, exact only on consistent bases. (KA 2.4)

Rolling test — A covenant measured on a trailing window; it lags a deterioration by the window length. (KA 15.1)

Run-off case — Contracted revenue only, with no credit for unsigned new business. (KA 7.2)

S

Scenario coverage — $1 - (1 - p)^k$: the chance k scenarios contain a mode of probability p . (KA 16.2)

Scope layers — Arithmetic · structure · documents · assumptions and provenance; the expensive errors sit in the last two. (KA 13.2)

Sculpting — Setting each period's debt service to hold coverage constant against uneven cash. (KA 10.1)

Settlement ceiling — Present value of fighting less negotiation cost; the rational maximum to settle at. (KA 12.4)

Several liability — Each sponsor owes only its own share; joint and several exposes each to the whole. (KA 5.2)

Shadow toll — Grantor pays the project per unit of measured usage; volume risk stays with the project, price risk with the grantor. (KA 7.2)

Shape neutrality — Profile timing is cost-neutral when escalation $\approx$ gearing $\times$ debt rate (4.20 % on Kestrel; 4.1659 % computed). (KA 8.2)

Signing vs financial close — Execution of documents vs satisfaction of all conditions and availability of funds. (KA 13.4)

Simple interest — Interest accruing on original principal only: $FV(x) = x(1 + rn)$. (KA 3.1)

Source line — The transaction, document and date behind a benchmark; without it a figure is an assertion, not evidence. (KA 1.3)

Sources and uses — The funding requirement against its funding; identical totals by construction. (KA 6.2)

Special-purpose vehicle (SPV) — The ring-fenced single-purpose entity that owns, finances and operates the project. (KA 5.2)

Spend profile / S-curve — A cost estimate distributed over time by the schedule that executes it. (KA 8.2)

Sponsor — Equity investor promoting the project (this book's project-finance sense). (KA 1.1)

Sponsor (project finance) — Equity investor promoting the project; brings capital, capability, access and credit. (KA 5.2)

Sponsor / bank / downside case — Central expectation · the case lenders will lend against · the stress the structure must survive. (KA 7.2)

Spot / forward rate — Exchange rate now / contracted for a future date. (KA 3.3)

SPV — Ring-fenced single-purpose project company; the borrower and contract hub. (KA 1.1)

SPV vs HoldCo mezzanine — Inside the borrower and visible to **DSCR**, versus above it and exposed to lock-up. (KA 9.2)

Step-in — Lenders or their nominee assuming a contract instead of allowing termination. (KA 12.3)

Stepped damages — Delay damages that rise through the programme to match a rising exposure. (KA 8.4)

Subordinated shareholder loan — Sponsor funding as ranked debt; may create a tax shield, dangerous if mis-ranked. (KA 9.1)

Subordination — Junior claims paid only after senior tests pass. (KA 10.3)

Sunk cost — Spend that no decision can avoid; excluded from every appraisal flow. (KA 4.1)

Superseded-draft error — Extraction from the wrong version; 100 per cent accurate against the wrong document. (KA 16.2)

Sustainability-linked loan — Margin ratchet tied to KPI performance; usually symmetric. (KA 9.4)

Sustainable debt service — Revised **CFADS** ÷ target coverage; the diagnostic that separates distress from a bad period. (KA 15.4)

Swap break cost — Present value of the difference between the contracted fixed rate and the market rate over the remaining notional profile. (KA 15.3)

Sweep probability — a^m : the chance an m -item extraction is entirely correct at per-item accuracy a . (KA 16.2)

T

Tail — Project life beyond debt maturity; reduced by tenor extension. (KA 9.4)

· Also read at KA 10.2: Project life beyond loan maturity; supports refinancing.

Take-or-pay — Contractual floor volume paid whether taken or not; often subject to make-up rights. (KA 7.1)

Take-or-pay / take-and-pay — Offtaker pays for contracted volume whether taken, or only for volume delivered. (KA 12.2)

Target DSCR — The coverage the lender requires; the divisor in sizing. (KA 10.1)

Technology risk — Under-performance over life (degradation, consumption, obsolescence) rather than at completion. (KA 11.4)

Three-block architecture — Inputs, calculations, outputs — strictly separated; no back-flow. (KA 6.1)

Time impact of a claim — Extension days × delay damages rate — the damages forgone by granting time. (KA 12.4)

Timeline flags — Mutually exclusive period markers (construction, operations, loan life, tail) that calculations multiply by. (KA 6.1)

Tolerance — The fall in a named driver that takes coverage to a threshold; the operational form of headroom. (KA 7.3)

Top-up / restoration — Application of cash to restore a reserve to its required balance; ranks above distributions. (KA 15.2)

Tornado — Sensitivities ranked by magnitude; meaningless without its case labelled. (KA 6.4)

Total misclassification cost — $FP \times \text{false-positive cost} + FN \times \text{false-negative cost}$; the objective to minimise. (KA 16.1)

Trigger in driver units — A ratio threshold restated in availability points, volume or unit cost. (KA 15.1)

Two-part tariff — Capacity charge plus variable charge; separates fixed-cost recovery from output. (KA 7.1)

Two-way sensitivity — NPV tabulated across the two dominating assumptions jointly, not separately. (KA 4.3)

U

Uncovered residue — Exposure less contractual recovery; an equity number, and a disclosure item. (KA 12.1)

Underwritten / best-efforts / club — Arranger commits and sells down · uses reasonable efforts only · pre-assembled group each taking its final hold. (KA 13.4)

Unequal lives — The comparison EAV exists to make honest. (KA 4.2)

Unrecovered advance — Cash paid for value not yet received; a prepayment asset that reconciles with the opposite sign. (KA 2.4)

Use-of-proceeds instrument — Green bond or loan; proceeds restricted to eligible assets. (KA 9.4)

V

Variation / compensation event — Instructed change; or an occurrence granting time and/or money without breach. (KA 12.4)

Verification duty — The named human's obligation to check machine output before reliance. (KA 1.3)

Verifying a number vs a claim — Recomputation by an independent route; versus tracing an assertion to a source that exists. (KA 1.3)

Vesting certificate — Instrument transferring title in off-site materials to the SPV; with segregation and insurance, the condition of any off-site certification. (KA 14.3)

Viability gap funding — Capital grant sized to make an otherwise unfinanceable project viable. (KA 9.4)

Volume band — Declining unit rates across volume tranches; compresses revenue dispersion from both ends. (KA 7.2)

W

WACC — $\sum(\text{tranche share} \times \text{tranche cost})$, debt-like tranches after tax. (KA 9.2)

Waiting period / deductible — Time or amount an insured bears before indemnity; must be tested against covenant headroom in days. (KA 11.3)

Waiver — Consent to disregard a specific breach, usually for a fee. (KA 15.3)

Waiver / amendment — Consented departure from terms, usually for a fee and tighter conditions. (KA 10.4)

WARCT — Weighted-average remaining contract term; the contracted horizon to be compared with loan tenor. (KA 7.2)

Waterfall tier — A ranked deduction with a test, floored at zero, with the shortfall carried. (KA 6.3)

Weighted average life — $\sum t \times \text{principal}(t) \div \sum \text{principal}(t)$; the measure a sweep actually shortens (7.1887 → 6.4660 years on Kestrel). (KA 10.3)

Working capital — Receivables + inventory – payables; growth consumes cash. (KA 2.3)

Working capital drag — Cash absorbed by receivables and inventory ahead of profit. (KA 1.2)

Working-capital movement — Change in receivables, inventory and payables; absorbs or releases cash. (KA 2.2)

Wrapped bond — Notes credit-enhanced by a third-party guarantor. (KA 9.2)

Y

Yield compression — Value created by selling at a lower required return than the seller's own — a market view, not performance. (KA 15.4)

Z

Zero-failure sample size — $n \geq \ln(\alpha) \div \ln(1 - p)$: tests needed to bound a defect rate at $1 - \alpha$ confidence. (KA 16.3)

B

β_a / β_e — Asset (unlevered) beta; equity beta re-levered as $\beta_a(1 + (1 - T)D/E)$. (KA 9.1)

Index

A

Accounting policy	48
Accretion	63
Accrual basis	48
Accuracy range	304
Advance payment / bond	576
AI model risk	457
All-in effective cost	104
Allocation matrix	496
Amendment	619
Annuity / annuity-due	104
Annuity factor $AF(r,n)$	104
Annuity, level-principal, bullet, holiday	104
Area rule	311
ARR	274
Articulation	48
Assessed claim exposure	568
Asset-capital matching	10
At-risk commitment	192
Attribution residual	665
Authority accumulation	674
Automation breakeven volume	646
Availability deduction	267
Availability period	584
Available commitment	559

B

Balancing line	233
Balloon / bullet	387
Balloon / refinancing risk	104
Bank case	457
Bank case / sponsor case	344
Bankability	204
Bankability triangle	19
Base date	311
Base-case vs minimum-period test	387
Basis	228
Basis bridge	228
Basis risk (pass-through)	441
Binding covenant	397
Blended CPI artefact	568
Blind audit	665
Break-even posterior	646
Breakeven close probability	204

Breakeven close rate	192
Breakeven consequence	674
Breakeven detection rate d	515
Breakeven discovery probability	30
Breakeven disputed sum	496
Breakeven failure probability p	10
Breakeven fee / error rate / detection rate	247
Breakeven inflow	169
Breakeven loading	434
Breakeven margin	619
Breakeven rate / breakeven exchange rate	448
Breakeven translation	247
Buy-down	211

C

Calendar-fixed repayment date	584
Cap stack	474
Cap-binding day	474
Capacity (availability) charge	267
Capex / opex	63
Capital allowance	233
Capital cost	304
Capital employed	53
Capital rationing	169
Capital-recovery annuity	162
Capitalisation boundary	73
Case	228
Cash call	326
Cash conversion	53
Cash interest cover	73
Cash sweep	387
Cash waterfall	406
Cash yield	612
Cash-to-revenue gearing	604
Certificate of satisfaction	539
Certification drift	576
Certified spend	311
CFADS	19
CFADS elasticity	280
CFADS tie	233
Check block	247
Circularity	241
Class 1 / 2 / 3 finding	523
Class-weighted closure	523
Close-cost budget	529

Close-cost premium	10	Cut-off.....	73
Commercial operations date (COD)	211	Cybersecurity risk (project)	457
Commitment vs actual vs paid.....	73	D	
Committed capital.....	198	Damages cap	211
Committed vs contributed equity	344	Data room / disclosure index.....	515
Common horizon (LCM)	162	Data spine	326
Common terms agreement	360	Day-count basis.....	122
Compensation on termination.....	483	Daylight test.....	30
Completion risk	211	Days sales outstanding (DSO).....	63
Compliance certificate.....	604	Debt capacity	387
Compound interest	95	Debt schedule invariants.....	241
Concentration risk.....	287	Debt-service schedule	406
Condition precedent (CP).....	529	Debt/EBITDA.....	73
Condition survey	627	Deduction / abatement regime	483
Conditional probability of default.....	448	Deduction multiplier	267
Conditions to each drawing	559	Deferred annuity factor	152
Confidence level (P50 / P80 / P95)	318	Definitional layer.....	646
Conflict of interest.....	30	Delay liquidated damages.....	211
Conjunction premium	529	Depreciation	53
Conjunctive test	204	Development cost.....	304
Consent register.....	204	Development cost per close.....	192
Consistency rule.....	122	DFI conditionality	360
Content requirement.....	360	Diligence stream	515
Contingency	318	Direct agreement.....	490
Contingency adequacy test.....	326	Direct method	53
Contingency coverage on the remainder	568	Discount factor DF(t)	95
Contingency release	318	Discount rate.....	95
Contingent / sponsor support.....	344	Distributable amount.....	612
Contingent support	318	Distribution condition	415
Contracted / merchant revenue	267	Distribution drought.....	612
Contracted volume floor	483	Distribution lock-up.....	415
Correlation uplift	457	Distribution-block account.....	612
Cost of retention	19	Draw request.....	559
Cost per month of slip	326	Draw-rate check.....	568
Cost per reviewed item.....	646	DSCR.....	397
Cost to complete (CTC)	326	DSCR ÷ LLCR.....	397
Cost-incurred certification	576	DSRA	406
Cost-overflow support	198	Dual-approval threshold	674
Covenant-preserving exposure ceiling	457	Due diligence	515
Covered interest parity	122	E	
CP chain.....	529	EAV	162
Credit enhancement	287	EBIT.....	53
Criticality risk	529	EBITDA	53
Cross-stream interface list.....	515	ECA / exposure premium	360
Crossover rate.....	169	Economic cost of delay	584
Cumulative PD.....	287	Effective escalation rate	280
Cure identity $P = C \div \lambda$	415	Effective sculpting rate r	387
Currency mismatch.....	448		

Elasticity	247	Grain	646
Enforcement floor	627	Grant element	368
Environmental and social risk	457	Greedy PI packing	169
EPC wrap	211	Gross vs net PI	162
Equity bridge loan	198	Grounds for transfer	434
Equity bridge loan (EBL)	344	Growing (indexed) annuity	104
Equity cliff	19	Growth-adjusted rate r	104
Equity contribution certificate	559		
Equity cure	415	H	
Equity return	241	Handback	627
Equivalent face amount	490	Hard-coded constant	228
Escalation	311	Headroom	397
Escalation wedge	441	Hedge ratio	448
Estimate class	304	Historic vs forward-looking test	415
Event of default	415	Horizon	228
Exchange-rate-indexed share	448		
Excusable outage	441	I	
Expected loss	287	ICR	397
		In-balance condition	568
F		Incremental IRR	169
Fatal condition	192	Indexation	122
Fee at risk	441	Indexation architecture	280
Fiduciary awareness	30	Indexation cap / lag / weighting	122
Final hold	539	Indexation mismatch	441
Financial / information / positive / negative covenant.	415	Indexed share	280
Financial close	192	Indifference stress s	387
Financial distress	627	Indirect method	53
Financial-data spine	646	Indivisible project	169
Finding close-out	523	Inflation π / escalation e	122
First-of-a-kind premium	204	Input / output progress measures	63
Fisher relation	122	Input provenance	247
Fixed charge	19	Instruction injection	674
Float	529	Instrument expiry gap	490
Force majeure	448	Interest cover	73
Forward-looking test	604	Interest during construction	211
Free cash flow (project)	152	Interest during construction (IDC)	233
Funded cost of delay	584	Interface agreement	483
Funding order	559	Interface hole	483
Funds flow	539	IRR	152
Funds sufficiency / in balance	326	Istisna'a / ijara / forward lease	360
Future value $FV(x)$	95		
		K	
G		k_d (after tax)	353
Gain-share	368	k_e	344
Generated minimum	658		
Golden source	646	L	
Golden-answer regression suite	247	Label bias	665
Governance latency	674	Label poisoning	674
		LC-backed reserve	406

Lender's cost-to-complete	568
Level annual charge	304
Leverage / gearing	19
Leverage crossover	19
Leverage wedge	73
Levered-return identity	19
Liability asymmetry (O&M)	474
Lifecycle (whole-life) cost	304
Linear-asset tenure risk	204
LLCR	397
Load-bearing subset	658
Loaded premium	434
Local additive attribution	665
Long-stop date	529

M

Macaulay duration	10
Maintenance reserve (MRA)	304
Make-whole / spens	353
Management reserve	318
Margin drift	280
Marginal DSCR of a variation	576
Marginal gain (condition)	204
Marginal precision	646
Mark-to-market (swap)	448
Market flex	539
Materiality threshold	523
Maturity extension	627
Measured / PoC certification	576
Measurement	48
Mechanical completion / commissioning / performance test / commercial operations date / final acceptance. 584	
Mezzanine	353
Mid-period convention	152
Milestone certification	576
Minimisation	674
Minimum revenue guarantee	368
MIRR	152
Model audit	247
Model inventory	665
Money multiple	241
MRA	406
Multiple roots	152
Murabaha / wakala / sukuk	360
Mutually exclusive	169

N

Natural hedge	360
---------------------	-----

Negative arbitrage	353
Net revenue retention	274
Net value of transfer	434
Nominal / real rate	122
Nominal rate / EAR	104
NPV	152
NPV profile	152

O

Offtaker	10
On-demand bond	490
Onerous contract	63
Operating bridge	604
Operating cash waterfall	612
Operating cost	304
Operating leverage (DOL)	280
Operating leverage (plant)	211
Operating régime	604
Operational readiness	211
Option premium (development)	192
Option value	169
Outstanding balance B _k	104
Owner's vs contractor's contingency	318

P

Parallel envelope	515
Parent company guarantee	490
Participation (pool) fee	539
Pass-through share ϕ	441
Payback / discounted payback	162
PD / EAD / LGD	287
Percentage method	318
Performance liquidated damages / buy-down	474
Periodicity	228
Perpetuity / growing perpetuity	104
PI	162
PLCR	397
Post-close undertaking	529
Praecipium	539
Present value PV(x)	95
Principal haircut	627
Principal versus interest	53
Pro-rata / back-ended funding	344
Project return	241
Prolongation cost	496
Provision / contingent liability	63

R

Ramp	274
------------	-----

Ramp profile	152	SPV	10
Recall / precision / accuracy	646	SPV vs HoldCo mezzanine	353
Recognition	48	Step-in	490
Reconstruction cost	658	Stepped damages	326
Recourse / non-recourse / limited recourse	10	Subordinated shareholder loan	344
Recourse sentence	10	Subordination	406
Red-flag memorandum	515	Sunk cost	152
Refinancing	619	Superseded-draft error	658
Refinancing gain	368	Sustainability-linked loan	368
Reinvestment assumption	152	Sustainable debt service	627
Repayment holiday (grace)	104	Swap break cost	619
Replacement chain	162	Sweep probability	658
Required k	658	T	
Reserve release	241	Tail	368
Reserve tolerance	406	Take-or-pay	267
Responsible-AI principle	30	Take-or-pay / take-and-pay	483
Restated sources and uses	559	Target DSCR	387
Restricted cash	233	Technology risk	457
Retained residue	434	Three-block architecture	228
Retention / retention bond	576	Time impact of a claim	496
Revalidation interval	665	Timeline flags	228
Reverse stress test	287	Tolerance	280
Review / approval / certification	674	Top-up / restoration	612
Ring-fencing	10	Tornado	247
Risk register (financing)	434	Total misclassification cost	646
Risk-adjusted cover	490	Trigger in driver units	604
ROCE / ROE	73	Two-part tariff	267
Rolling test	604	Two-way sensitivity	169
Run-off case	274	U	
S		Uncovered residue	474
Scenario coverage	658	Underwritten / best-efforts / club	539
Scope layers	523	Unequal lives	162
Sculpting	387	Unrecovered advance	73
Settlement ceiling	496	Use-of-proceeds instrument	368
Several liability	198	V	
Shadow toll	274	Variation / compensation event	496
Shape neutrality	311	Verification duty	30
Signing vs financial close	539	Verifying a number vs a claim	30
Simple interest	95	Vesting certificate	576
Source line	30	Viability gap funding	368
Sources and uses	233	Volume band	274
Special-purpose vehicle (SPV)	198	W	
Spend profile / S-curve	311	WACC	353
Sponsor	10	Waiting period / deductible	448
Sponsor (project finance)	198	Waiver	619
Sponsor / bank / downside case	274		
Spot / forward rate	122		

Waiver / amendment	415
WARCT	274
Waterfall tier.....	241
Weighted average life.....	406
Working capital	63
Working capital drag.....	19
Working-capital movement	53
Wrapped bond	353

Y

Yield compression	627
-------------------------	-----

Z

Zero-failure sample size	665
--------------------------------	-----

B

β_a / β_e	344
-----------------------------	-----